Stefan Zawadzki

# **Garments of the Gods**

Vol. 2: Texts

Academic Press Fribourg Vandenhoeck & Ruprecht Göttingen Stefan Zawadzki

## Garments of the Gods

Vol. 2: Texts

Ihre Beziehungen im Spiegel der Archäologie und der Literatur des Alten Testaments und seiner Umwelt

Academic Press Fribourg Vandenhoeck & Ruprecht Göttingen



Publication subsidized by the University of Poznań and the Swiss Academy of Humanities and Social Sciences

Internet general catalogue: Academic Press Fribourg: www.paulusedition.ch Vandenhoeck & Ruprecht, Göttingen: www.v-r.de

Camera-ready text prepared by Marcia Bodenmann, Institute of Religious Studies, University of Zurich.

© 2013 by Academic Press Fribourg, Fribourg Switzerland Vandenhoeck & Ruprecht Göttingen

ISBN: 978-3-7278-1742-7 (Academic Press Fribourg) ISBN: 978-3-525-54386-3 (Vandenhoeck & Ruprecht)

ISSN: 1015-1850 (Orb. biblicus orient.)

In Memoriam of my sister Helena (1936–2010)

### **Table of Contents**

Prefac	e	IX
	Remarks to the edition of the texts	IX
	Abbreviations and conventions	XII
	Bibliography	XIV
I.	The early dullu peşû texts	1
II.	The classical dullu peṣû texts	31
	GARMENTS FOR CYCLE A	31
	1. Garments for the Nisannu <i>lubuštu</i> ceremony	31
	2. Garments for the Ayaru <i>lubuštu</i> ceremony	45
	3. Garments for the Araḥsamna <i>lubuštu</i> ceremony	59
	4. Garments for the <i>lubuštu</i> ceremony in cycle A (Nisannu, Ayaru or Arahsamna)	70
	GARMENTS FOR CYCLE B	88
	5. Garments for the Ulūlu <i>lubuštu</i> ceremony	88
	6. Garments for the Tašrītu <i>lubuštu</i> ceremony	100
	7. Garments for the Addaru <i>lubuštu</i> ceremony	110
	8. Garments for the <i>lubuštu</i> ceremony in cycle B (Ulūlu, Tašrītu or	110
	Addaru)	120
	9. Garments for not recognized <i>lubuštu</i> ceremonies (cycle A or B)	129
III.	The ēpeš nikkassi accounts	143
	•	
IV.	The dullu peşû and tabarru texts	149
V.	The dullu tabarru and takiltu texts	154
VI.	BM 91002 (BBST 36): Nabû-apal-iddina's regulation concerning garments for Šamaš: No. 175	162
VII.	The early <i>miḥṣu tenû</i> texts	164
VIII.	The classical miḥṣu tenû texts	173
	GARMENTS FOR CYCLE A	173
	1. Garments for the Nisannu <i>lubuštu</i> ceremony	173
	2. Garments for the Ayaru <i>lubuštu</i> ceremony	177
	3. Garments for the Arahsamna <i>lubuštu</i> ceremony	181
	4. Garments for the <i>lubuštu</i> ceremony in cycle A (Nisannu, Ayaru or	
	Araḥsamna)	190
	GARMENTS FOR CYCLE B	210
	5. Garments for the Ulūlu <i>lubuštu</i> ceremony	210
	6. Garments for the Tašrītu <i>lubuštu</i> ceremony	215
	7 Garmants for the Addary lubustu caramony	221

## VIII TABLE OF CONTENTS

	8. Garments for the <i>lubuštu</i> ceremony in cycle B (Ulūlu, Tašrītu or	
	Addaru)	227
	9. Garments for not recognized <i>lubuštu</i> ceremony	236
IX.	The mixed classical <i>dullu peṣû</i> and <i>miḫṣu tenû</i> texts	277
X.	The texts of Nabû-bēl-šumāti	290
XI.	The tabû lists	315
XII.	The kitû ša Šamaš u ilāni Sippar	343
XIII.	The iškāru texts	347
XIV.	Diverse texts concerning manufacture of garments	355
XV.	Issue of (white) wool for the manufacture of the garments for the gods	376
XVI.	Issue of the coloured wool for manufacture of the garments for the gods	418
XVII.	Texts concerning dying and dying materials	455
XVIII.	Texts concerning kitinnû	475
XIX.	Silver paid for materials or as payment for the prebendaries	491
XX.	Miscellanea	519
Additio	ons and corrections to Garments of the Gods, Volume I	538
Indexe	·s	540
	Personal names	540
	Divine names	544
	Terms of garments and fabrics	549
	Terms written ideographically	564
	Other terms	564
	Text concordance	567
Plates.		575

### **Preface**

### Remarks to the edition of texts

In general the edition of texts follows the description of garments given in *Garments of the Gods*, Vol. I, Chapter II, with some small changes. The number of texts concerning the manufacture or distribution of garments for the gods is so great that the edition of all of them is impossible. However, all the texts belonging to the category of *dullu peṣû* and *mihṣû tenû* (Nos 1–292), and texts concerning *kitinnû* (XVII) are published; from the texts belonging to the groups X–XIII, and XVIII only texts preserved extremely badly or in small fragments are omitted. The more important selection is made in groups XIV–XVII and XIX–XX. In these groups I usually resigned from edition of texts of which copies are already published (mainly in CT 55 and CT 57); only if the newly published text is parallel to extant texts, the previously known text follows or precedes the new one. Here also I resigned from the edition of texts which are badly preserved, and I could not be certain if my translation would be accurate.

If the newly published text is broken or damaged I have reconstructed the missing part on the basis of existing parallels. The reconstructions were relatively easy in respect to the *dullu peṣû* or mihṣu tenû texts, where the problem was not how to reconstruct the content but how to reconstruct the particular writing of the word, i.e. syllabically or ideographically, with or without determinative. The following rule was used: the reconstructed world is written in the same way as is known from the preserved part of the text. If the broken part has no parallel in the preserved part, and where both forms of writing (because of space) are possible I have filled the gap with a transliteration, i.e. one can find [LUGAL Bābilî]. Instead of [LUGAL E<sup>ki</sup>] or [LUGAL TIN.TIR<sup>ki</sup>].

Sometimes the reconstruction is hindered because the number and colour of garments delivered to the particular god differs from text to text. For example, for Aya five *nahlaptu*-cloaks were delivered, but sometimes they were all made of red (*tabarru*) wool, while sometimes only three were made of red wool, one from blue-purple (*takiltu*) and one from multicoloured wool (*birmu*). If other lines are better preserved, their length is helpful, as separate writing needs much more space. Sometimes, when it is difficult to say whether the colour of wool was given or not, this uncertainty is expressed by writing (red): this means that it is impossible to decide if the colour was or wasn't expressed.

Because not all texts are copied, in order to give the reader a chance to estimate the state of preservation of a particular ideogram, in transliterations the actual signs are given, even if the proper reading is different, i.e. instead of TÚG.GÚ.È.A there is TÚG.GÚ.UD.DU.A.

The amount of 20 shekels was written as 20 GÍN or as 1/3 *ma-na* and the amount of 50 shekels as 50 GÍN or 5/6 *ma-na*, but in translation both are transformed into 20 or 50 shekels.

X PREFACE

The reader may be surprised that in translation the original name of a garment is preserved. Such a decision is justified by the fact that many items seems to have similar functions, for example <code>hullānu</code> and <code>nahlaptu</code>, dressed probably over the <code>salhu-tunic</code>, translated as "cloak" (although the translation "wrap" or "shirt" might also be acceptable) had the similar function, with the difference that the first one was the part of the gods' clothing while the second one of the goddesses. Similarly, the <code>nēbehu</code> and <code>patinnu</code>, both are translated as "belt" and the <code>lubār kulūlu</code>, <code>lubār mētu</code> and <code>lubār erru</code>, all three as "headbands". Thanks to the preservation of the original name the reader can avoid having to compare it with the translation to know precisely what type of item is meant. However, if the translation is in no way misleading, the original name of the item is omitted. Accordingly, the following translation is used:

```
salhu – tunic, placed on the "naked" statue of the gods or goddess. kus\overline{t}u – robe (which might be translated also as "gown" or similar): an outer garment of the goddess husannu – sash² guhassu – scarf adil\overline{a}nu – tassel².
```

Usually the measurements of the previously unpublished text are given. Note that the italic writing of the second numeral (e.g. 5.6 cm) denotes that the tablet is broken, but that most probably it was no longer or wider than 6.0 cm; if both numerals are written in italics in my opinion the tablet was longer or wider than 6.0 cm.

### Copies and index

The preparation of the copies of all tablets would have needed many more months of work. I copied all texts which include new data in comparison with previously known texts: new readings of a word or new data concerning the weight or quality of the garments, or the position of the gods in the pantheon of Sippar, etc. The arrangement of the copies and the technical improvement of some of them I owe to Piotr Namiota of the Photography and Graphics Workshop of the Institute of History at Adam-Mickiewicz University. I am deeply indebted to Joachim Marzahn for collating three tablets from the Vorderasiatisches Museum (VS 6, 26, 28, 208).

In the first volume of this work I announced the publication of a detailed index which was to contain a variety of ways of recording individual graphic forms and other terms. It turned out that, should such an index actually be prepared, it would be close to a hundred pages long, so it became necessary to make choices. In essence I gave up the idea of presenting terms in an ideographic form, albeit the form preferred by the writers, despite the fact that such a writing took up more space on the tablet. The index thus contains all the syllabic forms of words, as this can constitute a basis for arriving at conclusions concerning the changes taking place in the pronunciation of individual terms. In the case of the term *patinnu* = TÚG.MURUB<sub>4</sub>.ÍB.LÁ alone, the index contains all the forms enabling the reader

<sup>&</sup>lt;sup>1</sup> Cf. Tawil 2009, p. 108.

For biblical parallel, see Tawil 2009, p. 117.

PREFACE XI

to check the recommended identification. Because in Volume I the Index of the personal names was published, there is no sense in repeating them here. Only the new and reconstructed names, which were seldom included in Volume I of the index are added here.

The Index includes data from the texts edited in this volume, but sometimes an exception is made. If the word is rare and appears in already published or unpublished text(s) – or because its general subject is different or because it is too heavily damaged to be published – I have added such data to the index, but the signature of the text is not followed with the number of the text in this volume. Individual text groups were separated on the basis of certain material criteria which emerged from the titles of particular groups. Only the last group ("Miscellaneous") includes texts which didn't fit into any of the specific groups, or which were identified after the editorial work on the entire list; placing them in the appropriate place would have required enormous effort and increased the costs.

Once again I wish to express my gratitude to all those persons mentioned in the first volume of this study for their support in different ways during the many years of my studies on this subject. I feel compelled, though, to express my enormous debt of gratitude to Aleksandra and Zygmunt Podhorodecki (London), whose welcoming home became something of a small centre for many Polish Assyriologists who maintained contact with the Department of Ancient Eastern History at Adam Mickiewicz University, Poznań. The general atmosphere of industry and heartfelt kindness there has been extremely helpful. I also wish to mention Jacek Serwański, Ph.D. who many times corrected my English before the manuscript was delivered to John MacGinnis, who read it again and whose many remarks greatly improved this edition. Dr Małgorzata Sandowicz (Warsaw University) was also kind enough to read the entire work and contribute numerous remarks, which helped avoid a number of errors, greater or smaller. It goes without saying, though, that the responsibility for all possible mistakes, misreading and misinterpretations is exclusively mine. The Index and Concordance was prepared with the great help of my daughter Barbara.

Finally, I wish to express my gratitude to Christoph Uehlinger, senior editor of the OBO series, who kindly accepted this volume for publication, his supervision of the editorial process and valuable advice. Special thanks are addressed to Mrs Marcia Bodenmann who adapted the manuscript to OBO standard and with patience and kindness introduced subsequent additions and changes.

XII PREFACE

### Abbreviations and conventions

### Notes to the editions

[....] break difficult to estimate  $[x \ x \ (x \ x)]$  break with space for two or possibly four signs, etc.

rx x signs damaged

< x x> sign(s) omitted by scribes {x x} supefluous sign(s) reading of sign uncertain reading of sign emended

reading highly uncertain mostly because of malformed sign

new reading of sign in result of collation

l.e. lower edgel.h.e left hand edgeobv. obverserev. reverse

determinative preceding female personal name determinative preceding male personal name

fd or md determinative preceding female/male personal name with theo-

phoric element

[DN] unidentified divine name
[PN] unidentified personal name
[KN] unidentified name of the king
/ between first and second name son

/ between first and second name son of // between second and third name descendant of

### Babylonian months:

Nisannu March/April
 Ayyaru April/May
 Simānu May/June
 Du'uzu June/Jule
 Abu Jule/August
 Ulūlu August/September

6. intercalary Ulūlu

7. Tašrītu September/October
8. Araḥsamna October/November
9. Kislīmu November/December
10. Ṭebētu December/January
11. Šabāṭu January/February
12. Addaru February/March

12b. intercalary Addaru

PREFACE XIII

### Abbreviation of the kings' names:

Sši Sîn-šar-iškun (627–612 BC) Nbp Nabopolassar (626–605 BC) Nbk II Nebuchadnezzar (605-562 BC) Amēl-Marduk (562–560 BC) AmM Nbn Nabonidus (556-539 BC) Cyr Cyrus (539–530 BC) Camb Cambyses (530-522 BC) Nbk III Nebuchadnezzar III (522 BC) Nbk IV Nebuchadnezzar IV (521 BC) Darius I (521-486 BC) Dar

The dates of the Neo-Babylonian texts consist the day, the month, the king's name and year, i.e.  $9.2.Nbk\ 36$  is  $9^{th}$  day of Ayaru,  $36^{th}$  year of Nebuchadnezzar II.

### Metrology

```
1 KÙR (kurru) = 5 PI (p\bar{a}n) = 180 q\hat{u} (litres)

1 PI (p\bar{a}n) = 6 BÁN (s\bar{u}tu) = 36 q\hat{u} (litres)

1 BÁN (s\bar{u}tu) = 6 q\hat{u} (litres)
```

### Weight

1 GÚ.UN	=60 ma-na	= ca. $30  kg$
1 ma-na	= 60 GÍN ( <i>šiqlu</i> )	= ca. 0, 5 kg
1 GÍN ( <i>šiqlu</i> )		= ca. 8.3 g

XIV PREFACE

### Bibliography<sup>3</sup>

- J. Alvarez-Mon, "The Introduction of Cotton in the Near East: A View from Elam" (www.achemenet.com/ressources).
- JURSA 2006 = M. Jursa, "Agricultural Management, Tax Farming and Banking: Aspects of Entrepreneurial Activity in Babylonia in the Late Achaemenid and Hellenistic Periods," in: P. Briant, et F. Joannès (eds), 'La transition entre l'empire achéménide et les royaumes hellenistiques (vers 350–300 av. J.-C.), Paris, 137–222.
- JURSA 2010 = M. Jursa (with Contributions by J. Hackl, B. Janković, K. Kleber, E.E. Payne, C. Waerzeggers and M. Weszeli), Aspects of the Economic History of Babylonia in the First Millennium BC. Economic Geography, Economic Mentalities, Agriculture, the Use of Money and the Problem of Economic Growth (Veröffentlichungen zur Wirtschaftsgeschichte Babyloniens im 1. Jahrtausend v. Chr., Bd 4), Münster.
- KLEBER 2008 = K. Kleber, Tempel und Palast. Die Beziehungen dem König und dem Eanna-Tempel im spätbabylonischen Uruk (Veröffentlichungen zur Wirtschaftsgeschichte Babyloniens im 1. Jahrtausend v. Chr., Bd 3), Münster.
- LORENZ 2008 = J. Lorenz, Nebukadnezar III/IV. Die politischen Wirren nach dem Tod des Kambyses im Spiegel der Keilschrifttexte, Dresden.
- ÓLAFSSON and PEDERSÉN 2001 = S. Ólafsson and O. Pedersén, "Cuneiform Texts from Neo-Babylonian Sippar in the Gothenburg City Museum," Orientalia Suecana 50, 75–130.
- PAYNE 2008 = E.E. Payne, "The "Rough Draft" of Neo-Babylonian Accounting Document," in: M. Ross (ed.), From the Banks of the Euphrates: Studies in Honor of Alice Louise Slotsky, Winona Lake, 181–192.
- POSTGATE 1973 = J.N. Postgate, *The Governor's Palace Archives* (Cuneiform Texts from Nimrud, 2), London.
- TAWIL 2009 = H. Tawil, An Akkadian Lexical Companion for Biblical Hebrew. Etymological-Semantic and Idiomatic Equivalents with Supplement on Biblical Aramaic, Jersey City, NJ.
- WAERZEGGERS 2006 = C. Waerzeggers, "Neo-Babylonian Laundry," RA 100, 83-96.
- WOODS 2004 = Ch.E. Woods, "The Sun-God Tablet of Nabû-apla-iddina Revisited," JCS 23, 23–103.
- ZAWADZKI 2010 = S. Zawadzki, "Garments in Non-Cultic Contexts (Neo-Babylonian Period)", in: C. Michel and M.-L. Nosch (eds.), *Textile Terminologies in the Ancient Near East and Mediterranean from the Third to the First Millennia BC*, Oxford, 409–429.

<sup>&</sup>lt;sup>3</sup> Only entries not cited in Volume I are quoted here.

### I. The early dullu peşû texts

### **1. BM 50272** (82-3-23, 1263)

PLATE 1

 $5.8 \times 3.3$  cm

### $1^{1}+[x].8.Nbp 9$

- 1. 30 5/6 ma-na dul-lu gam-ru
- 2. KI.LAL TÚG.HI.A *u* TÚG.MÁŠ *šá* <sup>d</sup>UTU
- 3. lu-bar ziq- $\langle qu \rangle$  3  $t^{tig}su$ -ni-e
- 4. TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU u <sup>d</sup>A-a
- 5. dGAŠAN Sip-par<sup>ki</sup> TÚG.HI.A u TÚG.MÁŠ 6. [šá] dBu-ne-ne mB[a²-la-tu²]

7. lúUŠ.BAR it-[ta-din] L.e.

8. ITI.APIN U<sub>4</sub>. 「111.KAM MU.9.KAM Rev.

9. mdAG-A-PAP LUGAL TIN.TIRki

30 minas 50 shekels, the completed work, the weight of the lubāru and şibtugarments of Šamaš, the lubār ziqqu-garment, 3 sūnu-belts, sashes for Šamaš and Aya (and) the Queen of Sippar; the lubāru and the sibtu-garments for Bunene, (which) B[alātu²], the weaver has de[livered]. Month of Araḥsamna, 11+[x]<sup>th</sup> day, 9<sup>th</sup> year of Nabopolassar, king of Babylon.

- L. 1. Concerning the meaning of dullu gamru, cf. Bongenaar, Ebabbar, p. 359.
- L. 3. for lubar ziqqu, cf. CAD Z, 129a 2' ("an ornament imitating battlements or the like") and Woods 2004, p. 102 ("garments (or jewellery) with a crenellated hem or design"). Cf. similar texts BM 49416 (= 19) and 49268 (= 3).

### 2. BM 49902 (82-3-23, 893)

 $5.4 \times 3.3$  cm

### $[x.x].Nbp^{?}10$

- 1. [30+] 4 ma-na 1/3 GÍN dul-lu gam-ru
- 2. KI.LAL TÚG.HI.A TÚG.MÁŠ TÚG.HI.A ziq-tu<sub>4</sub>
- 3. TÚG. TÚR MEŠ TÚG. NJÍG. ÍB. LÁ. MEŠ
- 4. 「šá<sup>†</sup> dU[TU dA-a ù d]GAŠAN Sip-par<sup>ki</sup>
- 5. [.... ME]Š<sup>?</sup>

Edge lost

Rev.

- 1'. U<sub>4</sub>.[x.KAM] MU.10.[KAM]
- $2.\ ^{md}AG\text{-}[DUMU.U]\mathring{S}\text{-}PAP\ LUGAL\ K\acute{A}.DINGIR.RA}^{ki}$
- L. 2. TÚG.HI.A ziq-tu<sub>4</sub>, a by-form for ziq-qu.

Rev. 2'. The reading Nabopolassar is suggested because the space between AG and PAP is too large to place there only [NÍG.D]U (the second wedge is broken and both readings [U]Š and [D]U are possible). Also the writing  $K\dot{A}$ .DINGIR.RA $^{ki}$  was more frequent in the time of Nabopolassar than in the time of Nebuchadnezzar.

[3]4 minas, 20 shekels, the completed work, the weight of *lubāru*-garment, the *ṣibtu*-garment, the *lubār ziqtu*-garment(s), *sūnu*-belts, sashes for Šamaš, [Aya and] the Queen of Sippar [....].

[Month of x, n<sup>th</sup> day], 10<sup>th</sup> year of Nabo[polas]sar, king of Babylon.

### 3. BM 49268 (82-3-23, 259)

PLATE 1

 $3.9 \times 3.15$  cm

### 3.1.Nbp 17

- 1. 35 ma-na dul-lu <gam>-ru
- 2. KI.LAL TÚG.ḤI.A <sup>túg</sup>sib-tu<sub>4</sub>
- 3. TÚG.HI.A SIG<sub>5</sub> TÚG.ÚR.MEŠ
- 4. TÚG.NÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>UTU
- 5. TÚG.ḤI.A túgṣib-tu4

Edge

6. šá <sup>d</sup>Bu-ne-ne

Rev.

- 7. [10] TÚG.NÍG.ÍB.LÁ.MEŠ šá d{É} A-a
- 8. <sup>m</sup>Du-muq ma-hir
- 9. ITI.BÁR U<sub>4</sub>.3.KAM
- 10. 「MU¹.17.KAM <sup>d</sup>PA-A-PAP

Cf. BM 49416 (= 19) and BM 50272 (= 1).

35 minas, the completed work, the weight of the *lubāru* (and) *ṣibtu*-garments, fine cloths, *sūnu*-belts and sashes for Šamaš; the *lubāru* (and) the *ṣibtu*-garments for Bunene (and) 10 sashes for Aya received from Dummuqu. Month of Nisannu, 3<sup>rd</sup> day, 17<sup>th</sup> year of Nabopolassar.

### 4. VS 6, 208; cf. NUVI 3, No. 208

### 13.12. <Nbp> 15

- 1. 34 ma-na dul-la gam-ru KI.LAL
- 2. TÚG.ḤI.A <TÚĞ >.MÁŠ <šá>  $^{\rm d}$ UTU <TÚG>.ÚR.MEŠ TÚG.<NÍG.ÍB>.LÁ.「MEŠ  $^{\rm l}$
- 3. šá $^{\rm d}$ UTU u $^{\rm d}A$ -aTÚG. ḤI.A <TÚG>.MÁŠ
- 4. šá <sup>d</sup>Bu-ne-ne a-di si-ti
- 5. 1 ma-na <10 GÍN> KI.LAL <TÚG>.ÚR ù <TÚG>.NÍG.ÍB.LÁ.MEŠ
- 6. šá <sup>d</sup>IM <sup>md</sup>AG-EN-MU.MEŠ
- 7. it-ta-din
- L.e. 8. ITI.ŠE U<sub>4</sub>.13.KAM
- Rev. 9. 「MU1.15.KAM

L. 4–5. Cf. the different translation in CAD Š III 139: "including the remaining  $s\bar{u}nu$  and  $n\bar{e}behu$  garments weighting 1 mina". First, the text mentions husannus (<TÚG>. NÍG.ÍB.LÁ.MEŠ) not  $n\bar{e}behu$  (TÚG.ÍB.LÁ). It seems to me that lines 5–6 refer to the separate items for Adad, but because the total weight of (one) sūnu and 10 sashes for Adad (and) Šala is 1 mina 10 shekels, the text was amended in such a way. For si-ti, see CAD Š, s. v. šittu.

34 minas, the completed work, the weight of the *lubāru* (and) *sibtu* garments (for) Šamaš, the sūnu-belts, the sashes for Šamaš and Aya; the lubāru (and) sibtugarments for Bunene including the remaining 1 mina <10 shekels>, the weight of the *sūnu*-belt and the sashes for Adad, Nabû-bēl-šumāti has delivered. Month Addaru, 13th day, 15th year.

### **5. VS 6, 15**; cf. NUVI 3, No. 237

### 1.6.Nbp 18

- 1. [½] GÚ.UN 7 ½ ma-na 「dul¬-lu TIL
- 2. [KI.LAL TÚG].ḤI.A TÚG.MÁŠ TÚG.ḤI.A ziq-qu
- 3. 「TÚG¹.ÚR.MEŠ TÚG.<NÍG>.ÍB.LÁ.MEŠ šá  $^{d}$ UTU 4.  $^{d}$ A-a  $^{d}$ GAŠAN Sip-pa $^{ki}$  TÚG.HI.A

- 5. u TÚG.MÁŠ šá <sup>d</sup>Bu-ne-ne 6. <sup>md</sup>U+GUR-ú-še-zib A-šú šá <sup>md</sup>AG-NUMUN-DÙ
- 7. A <sup>m</sup>Ha-am-ma-a-a <sup>r</sup>ma-hir<sup>1</sup>
- 8. ITI.KIN U<sub>4</sub>.[1.KAM]

Rev.

- 9. 2 ma-na KI.LAL <sup>túg!</sup>mu-ut-ta-<sup>r</sup>ti<sup>1</sup> 10. [šá] <sup>d</sup>UTU <sup>md</sup>AG-EN-MU.MEŠ A-šú šá <sup>m</sup>Du-muq
- 11. ma-hir ITI.KIN U<sub>4</sub>.1.KAM
- 12. MU.18.KAM <sup>md</sup>AG-A-ÙRU
- 13. [LUGAL] TIN.TIR<sup>ki</sup>

[½] talent 7½ minas of wool, the completed work, [the weight of] the *lubāru* (and) sibtu-garments, the lubār ziqqu-garment, the sūnu-belts, the sashes for Šamaš, Aya and the Queen of Sippar; the lubāru (and) şibtu garments for Bunene, received from Nabû-zēr-ibni, son/descendant<sup>?</sup> of Hammaya.

Month Ulūlu, [1st day].

2 minas (of wool), the weight of the muttatu-headdress [for] Šamaš received from Nabû-bēl-šumāti, son of Dummuqu.

Month Ulūlu, 1<sup>st</sup> day, 18<sup>th</sup> year of Nabopolassar, [king] of Babylon.

### **6. BM 51498** (82-3-23, 2532)

PLATE 2

 $3.7 \times 4.9$  cm

12.12.Nbp 18

- 1. mi-iḥ-[ṣu-ú] šá <sup>d</sup>UTU
- 2.  ${}^{d}A$ -a  ${}^{\dagger}\hat{u}$   ${}^{d}{}^{\dagger}Bu$ -ne-ne

- 3. ITI.ŠE U<sub>4</sub>.12.KAM MU.18.KAM
- 4. mdAG-A-PAP LUGAL TIN.TIRki

- 5. 35 ½ ma-na KI.LAL
- 6. TÚG. ḤI.A <br/> túg ṣib-tu $_4$  TÚG SIG $_5$
- 7. 4 TÚG.ÚR.MEŠ 16 TÚG.NÍG.ÍB.LÁ.MEŠ
- 8. šá <sup>d</sup>UTU u <sup>d</sup>A-a
- 9. TÚG.HI.A ù túg șib-tu4
- 10. šá <sup>d</sup>Bu-[n]e-ne

Rest lost

Wo[ven] garments for Šamaš, Aya and Bunene. Month of Addaru, the  $12^{th}$  day,  $18^{th}$  year of Nabopolassar, king of Babylon.

35 ½ minas, the weight of the *lubāru* (and) *şibtu*-garments, the fine? cloths, 4 *sūnu*belts, 16 sashes for Šamaš and Aya; the *lubāru* (and) *şibtu* garments for Bunene [....].

### 7. VS 6, 17; cf. NUVI 3, No. 239

[x.x].Nbp 20

- 1. mi-ih-si šá [<sup>d</sup>UTU <sup>d</sup>A-a]
- 2. *u* <sup>d</sup>*Bu-ne-ne* ITI.[x U<sub>4</sub>.x.KAM]
- 3. MU.20.KAM <sup>md</sup>AG-A-<sup>[</sup>PAP] [LUGAL TIN.TIR<sup>ki</sup>]
- 4. šá ina ŠU<sup>ii lú</sup>UŠ.BAR ma-[hir]

- 5. 36 ma-na dul-lu <sup>r</sup>gam-ru<sup>1</sup>
- 6. KI.LAL TÚG.HI.A TÚG.MÁŠ 6 hu-ṣa-an-na
- 7. TÚG.ḤI.A SIG5 šá  $^{\rm d}$ UTU 10  $\rlap/ \mu u$ -ṣa-ni-e
- 8. *šá* <sup>d</sup>*A-a* TÚG.ḤI.A TÚG.MÁŠ 9. *šá* <sup>d</sup>*Bu-ne-ne* 4 <TÚG>.ÚR.MEŠ
- 10. <sup>md</sup>AG-EN-MU.MEŠ *ma-hir*

- 11. GADA gú-<sup>r</sup>ḥal<sup>?</sup>¹-ṣa <sup>túg</sup>ḥu-ṣa-ni-e</sup>
- 12. *šá* <sup>d</sup>UTU 13. *šá* <sup>d</sup>*Bu-ne-ne*
- 14. ina IGI-šú

Woven garments for [Šamaš, Aya] and Bunene on the month [x, n<sup>th</sup> day] 20<sup>th</sup> year of Nabopolassar, [king of Babylon] were received from the weaver.

36 minas, the completed work, the weight of the lubāru (and) sibtu-garments, 6 sashes, the fine cloths for Šamaš, 10 sashes for Aya, the lubāru (and) sibtugarments for Bunene, 4 sūnu-belts was received from Nabû-bēl-šumāti.

Linen scarf, sashes for Šamaš (and) for Bunene are at his disposal.

### **8. CT 55, 830** = BM 55803

### 11.12.Nbp 19

- 1. ½ GU.UN 5 ½ ma-na
- 2. \( \frac{1}{2} dul-lu \ gam-ru \( \) (erased)
- 3. KI.LAL TÚG.ḤI.A [*u*<sup>?</sup> TÚ]G.MÁŠ
- 4. 6 TÚG.NÍG.ÍB.LÁ<sup>!</sup>.[MEŠ *šá* <sup>d</sup>]UTU
- 5. 10 TÚG.NÍG. TÍB¹. LÁ! MEŠ! šá <sup>d</sup>A-a
- 6. TÚG.HI.<sup>r</sup>A<sup>1</sup> [TÚG].MÁŠ<sup>!</sup> (T: dir)

Edge Rev.

7. <sup>r</sup>šá <sup>d</sup>¹*Bu-ne-ne* 8. 4 TÚG.ÚR.MEŠ

- 9. šá <sup>md</sup>AG-EN-MU.MEŠ { <sup>m</sup>TIN-su}
- 10. it-ta-din ITI.ŠE U<sub>4</sub>.11.KAM
- 11. MU.19.KAM <sup>d</sup>AG-A-ÙRU
- 12. LUGAL TIN.TIR<sup>ki</sup>

Bongenaar, Ebabbar, p. 320, recognised in Balassu the deliverer of garment manufactured by Nabû-bēl-šumāti. Although such an interpretation is possible, there is no argument to identify him as a member of išpar kitê group. Another possibility, which accords with the wording of other texts, is that <sup>m</sup>TIN-su was inserted by mistake.

L. 4. The proper place for l. 8 is between line 4 and 5.

35 ½ minas, the completed work, the weight of the *lubāru* [and?] *şibtu*-garments, 6 sashes for Šamaš, 10 sashes for Aya; the *lubāru* (and) *sibtu*-garments for Bunene (and) 4 sūnu-belts, which Nabû-bēl-šumāti has delivered.

Month of Addaru, 11<sup>th</sup> day, 19<sup>th</sup> year of Nabopolassar, king of Babylon.

### 9. BM 52361 (82-3-23, 3395)

PLATE 2

 $3.1 \times 3.7 \text{ cm}$ 

### 12.8.Nbp [x]

- 1. 35 *ma-na* [*dul-lu*]
- 2. gam-ru KI.LAL T[ÚG.HI.A TÚG.MÁŠ]
- 3. TÚG.HI.A ziq TÚG.ÚR.[MEŠ TÚG.NÍG.ÍB.LÁ.MEŠ]
- 4. šá <sup>d</sup>UTU <sup>d</sup>A-a
- 5. TÚG.HI.A TÚG. MÁŠ šá [dBu-ne-ne]
- 6. <sup>md</sup>AG-EN-MU.M[EŠ <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>]
- 7. ITI.APIN U<sub>4</sub>.12.[KAM MU.x.KAM]

8. mdAG-A-PAP LU[GAL TIN.TIR<sup>ki</sup>] Rev.

35 minas, [the completed] work, the weight of the [lubāru (and) şibtu-garments], the  $lub\bar{a}r ziq < qu>$ , the  $s\bar{u}nu$ -belts, [the sashes] for Šamaš (and) Aya; the lubāru (and) sibtu-garments [for Bunene] Nabû-bēl-šum[āti, the weaver has

Month of Arahsamna, 12<sup>th</sup> [day, n<sup>th</sup> year of] Nabopolassar, ki[ng of Babylon].

```
10. BM 50426 (82-3-23, 1417); cf. Lorenz 2008, No. 40 5.2 × 3.1 cm
```

PLATE 3

### [x.x].Nbk 1

- 1.  $38 \frac{1}{2}$  ma-na dul-lu gam-r[u]
- 2. KI.LAL TÚG.ḤI.A MÁŠ TÚG.ḤI.A [me-e SAG.DU]
- 3. 4 TÚG. TÚR I. [MEŠ TÚG. NÍG. ÍB. LÁ. MEŠ]
- 4. [....]
- ---[....]
- 5. <sup>[</sup>x<sup>1</sup>[....]

Rest lost

Rev.

- 1.  $i[t^2-ta-di]n^2$  [ITI].[x U<sub>4</sub>.x.KAM]
- 2. MU.1.KAM <sup>d</sup>AG-NÍG.[DU-ÙRU]
- 3. LUGAL TIN.TIR<sup>ki</sup>
- L. 2. Instead of TÚG.ḤI.A [me-e SAG.DU] one can reconstruct TÚG.ḤI.A [SIG<sub>5</sub>] or TÚG.ḤI.A [ziq]
- L. 6. Maybe small fragment of ruling line.
- 38 ½ minas, the completed work, the weight of  $lub\bar{a}ru$  (and) sibtu-garments, the  $lub\bar{a}r$  [ $m\bar{e}$  qaqqadi]-headdress,  $4s\bar{u}nu$ -belts, [the sashes ....]

---[------

Thas given<sup>1</sup>? Month [x, n<sup>th</sup> day], 1<sup>st</sup> year of Nebuchad[nezzar], king of Babylon.

### **11. BM 82578** (93-10-14, 30)

PLATE 3

 $3.7 \times 5.4$  cm

### 5.7.Nbk 2

- 1. [3]<sup>[9]</sup> ½ ma-na KI.[LAL]
- 2. [TÚG].HI.A MÁŠ
- 3. 4 TÚG.ÚR.MEŠ
- 4. TÚG.HI.A SIG<sub>5</sub>
- 5. 16 TÚG.NÍG.ÍB.LÁ.MEŠ
- 6. šá <sup>d</sup>UTU <sup>d</sup>A-a
- 7. 「ù dGAŠAN Sip-parki
- 8. 1 *ma-*<sup>r</sup>*na*<sup>1</sup> 10 G[ÍN]
- 9. KI.LAL <sup>1</sup>1 TÚG<sup>1</sup>.Ú[R]
- 10. *u* TÚG.NÍG.ÍB.LÁ.[MEŠ]
- 11. šá <sup>d</sup>IM
- L.e.  $12. u^{d} \check{S}a l[a]$ 
  - 13. PAP 40 ½ ma-na
  - 14. 5 GÍN
- Rev. 16. dul-la gam-ru
  - 17. md AG-EN-MU.MEŠ

18. lúUŠ.BAR ma-hir!

19. ITI.DU<sub>6</sub> U<sub>4</sub>.5.KAM

20. MU.2.KAM <sup>md</sup>AG-NÍG. DU-ÙRU

 $LUGAL \: E^{ki}$ 

ma in 1. 13 and hir in 1. 18 are written over erasure.

Note that the sum of 39 ½ (1. 1) and 1 mina 10 shekels (1. 8) gives 40 minas 40 shekels, and not 40 minas 35 shekels as in lines 13-14.

L. 5. The typical amount of sashes was 6 for Šamaš and 10 for each of the two mentioned goddesses, however, the number is clearly 16, not 26 as it is expected. Note also that by adding the fixed weight of the lubāru+şibtu+4 sūnu+26¹ huşannus one arrives at only 34 minas 20 shekels, which leaves 5 minas 10 shekels for lubār SIG5, much more than the weight of this item known from other texts.

L. 10. Instead of u one can read 10, but the first possibility is more probable in light of BM 49416 (= 19): 8–9 (1 ma-na 10 GÍN <KI.LAL> TÚG.ÚR ù <sup>9</sup>TÚG.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>IM).

[3]9 ½ minas, the weight of the *lubāru* (and) the *şibtu*-garments, 4 *sūnu*-belts, the fine? cloths, 2<sup>1</sup>6 sashes for Šamaš, Aya and the Queen of Sippar;

1 mina 10 shekels, the weight of 1 sūnu-belt (and) sashes for Adad and Šala; total 40 minas 35 shekels, the completed work was received from Nabû-bēl-šumāte, the

Month of Tašrītu, 5<sup>th</sup> day, 2<sup>nd</sup> year of Nebuchadnezzar, king of Babylon.

### **12. BM 52110+52541** (82-3-23, 3144+3575)

PLATE 4

 $5.8 \times 4.3$  cm

### 2.6.Nbk 5

- 1. 2 ma-[na x GÍN dul-la ga]m-ru
- 2.  $\lceil KI \rceil$ . [LAL x x x mu-ut-t]a-ti

\_\_\_\_\_

- 3.  $[x \times x \times x \times x]^{T} \times 1.LA.M[EŠ]$
- 4. [x x x x]. LÁ¹.MEŠ 1 TÚG.ÚR
- 5. [šá <sup>d</sup>IM u] <sup>d</sup>Ša-la 6. [<sup>md</sup>AG-EN-M]U.MEŠ *ma-ḫir*

7. [ITI.KIN U]D.2.KAM MU.5.KAM Edge

- 8. [mdAG-NÍG].DU-ÙRU
- [LUGAL] Eki

10.  $[x \times x \times m]a$ -na dul-la Rev.

- 11. [gam-ru KI.LA]L 2 TÚG.HI.A
- 12.  $[x \times x \times]$ -lu <sup>d</sup>Bu-ne-ne
- 13. [x x x] <sup>r</sup>x¹ GÍN *ta-kil-ti*
- 14. [2<sup>?</sup>] <sup>túg</sup>ṣi-ba-ta šá <sup>d</sup>UTU 15. 「ù<sup>? d</sup>Bu¹-ne-ne
- 16. [x TÚG.NÍG]. ÍB¹.LÁ.MEŠ

17. [x x x TÚG]. 「ÚR¹. MEŠ

18.  $[1^e]^n$  TÚG.ḤI.A me-e SIG $_5^{q\acute{a}}$ /.GA

One line erased

19. [<sup>md</sup>U+GUR]-ú-še-zib ù

20.  $[^{\text{m}}\check{S}u^?-l]a^?-a^{\text{l}\acute{u}}U\check{S}.BAR.ME\check{S}$ 

21. [ma-hi]r ITI.KIN U<sub>4</sub>.2.KAM

22. MU. <sup>5</sup>1.KAM <sup>md</sup>AG-NÍG.DU-ÙRU

23.  $[LUGAL] \Gamma E^{ki_1}$ 

Note that last two lines of reverse are written on the very top of obverse.

2 minas [x shekels], the completed [work], the weight of the [... mutta]tu-headdress [....], 1 sūnu-belt [for Adad and] Šala was received from [Nabû-bēl]-šumāti. [Month of Ulūlu], 2<sup>nd</sup> [day], 5<sup>th</sup> year of [Nebu]chadnezzar, [king] of Babylon. [x mi]nas, [the completed] work, [the weight] of 2 lubāru-garments, [.......] (for) Bunene, [..., x shekels] of blue-purple wool, (for) [2] sibtu-garments of Šamaš and Bunene, [x] sashes [and x] sūnu-belts, 1 fine lubār mesiqqa-headdress received from [GN]-ušēzib and [Šu]lā<sup>?</sup>, the weavers.

### **13. BM 49580** (82-3-23, 571)

PLATE 5

 $5.05 \times 3.5$  cm

### 20.8.Nbk 5

- 1. 「3<sup>1</sup>1 5/6 ma-na KI.LAL
- 2. túgtu-un-šú šá UGU GIŠ.NÁ
- 3. šá <sup>d</sup>UTU ina ITI.APIN
- 4. <sup>md</sup>AG-EN-MU.MEŠ ma-hir
- 5. ina lìb-bi 5 ma-na < síg > ḥaš-ḥu-ru
- 6. <SÍG>.ÌR.Ú.MA.MI.「IŠT
- 7. ù ki-tu-ú
- 8. ri-e-<sup>[</sup>hi<sup>1</sup> 26 5/6 ma-na
- 9. <sup>síg!</sup>*h*[*a-áš*]-*hu-ri*
- 10. <sup>síg</sup>[*ta*]-*kil-ti*

Rev.

- 11. md AG-EN-MU.MEŠ
- 12. ma-hir ITI.APIN
- 13. U<sub>4</sub>.20.KAM MU.5.KAM
- 14. md AG-NÍG.DU-ÙRU
- 15. LUGAL Eki
- L. 5. Concerning the <code>hašhūru</code> colour, see now Payne 2008, p. 189 ("more likely ... that the <code>hašhūru</code>-wool was a reddish hue rather than the yellow-green generally suggested"). L. 9. The síg sign is written over erasure.
- <sup>7</sup>3<sup>1</sup>1 minas 50 shekels, the weight of *tunšu*-garment for covering of the bed of Šamaš in the month of Araḥsamna was received from Nabū-bēl-šumāti, including

5 minas of the apple-coloured (and)  $iR.\acute{U}.MA.MI.I\r{S}$ -wool and linen; the rest -26 minas 50 shekels of the apple-coloured and blue-purple wool was received from Nabû-bēl-šumāti.

Month of Arahsamna, 20<sup>th</sup> day, 5<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

### **14. BM 78914** (88-5-12, 100)

PLATE 5

 $3.8 \times 3.6$  cm

### 20.8.Nbk 5

- 1. 31 ma-na 1/3 GÍN
- 2. KI.LAL tug-un-šú
- 3. *šá* UGU GIŠ.NÁ *šá* <sup>d</sup>UTU
- 4. ina lìb-bi 5 x (er.) ma-na
- 5. síghašhur u SÍG.ìr.ú.ma.mi.iš

Edge 6. 1 ma-na ki-tu-ú

Rev. 7. md AG-EN-MU.MEŠ

8. it-ta-din

9. ITI.APIN U<sub>4</sub>.20.KAM

10. MU.5.KAM <sup>d</sup>AG-NÍG.DU-ÙRU

L.e. 11. LUGAL TIN.TIR<sup>ki</sup>

31 minas 20 shekels, the weight of the *tunšu*-garment for covering of the bed of Šamaš including 5 minas of apple-coloured wool and SÍG.ÌR.Ú.MA.MI.IŠ-wool (and) 1 mina of linen has been delivered by Nabû-bēl-šumāte.

Month of Arahsamna, 20<sup>th</sup> day, 5<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

The text is evidently connected contextually with BM 49580 (the same date) and with VS 6, 16 (dated 23.2.Nbp 20), i.e. the last one was written about six years earlier. In all of them it appears Nabû-bēl-šumāti and all mention apple-green coloured wool (ħašħūru), and another type of wool, not known from other texts to my knowledge. In VS 6, 16 this wool is written SÍG.ÌR.Ú.MA.IŠ while in BM 49580 and BM 78914 SÍG.ÌR.Ú.MA.MI.IŠ. The designation for cloth or a cover tunšu, is slightly different: ša muḥḥi kilzappu "for (laying) on the pedestal" (VS 6, 16: 5), and ša muḥḥi ešru ša Šamaš "for (covering) the bed for Šamaš" (new texts). All three texts concern the completion of similar sets of garments, most probably of almost identical weight, although the interpretation of the texts is not free of doubt due to ambiguities in the wording.

We begin the interpretation with the comparison of BM 49580 to BM 78914, written on the same day and evidently concerning the same matter, i.e. materials for manufacturing a *tunšu* for the bed of Šamaš, although in the first one the initial amount is 31 minas 50 shekels and in the second one only 31 minas 20 shekels, i.e. ½ mina less. According to BM 78914 for manufacturing the *tunšu* 5 minas of the apple-green coloured wool and SÍG.ÌR.Ú.MA.IŠ have been used in addition to 1 mina of linen. If we remove both quantities from the initial amount we are left with 25 minas 20 shekels. However, according to BM 49580 the *tunšu* weighed 31 minas 50 shekels, but it is stated also that this included 5 minas of *hašhūru*, SÍG.IR.Ú.MA.MI.IŠ (and) linen and the remaining 26 minas 50 shekels is accounted for by the red and blue-purple wool. It is clear from this text that the scribe who wrote it, or the accountant who dictated the data to the scribe, thought that 5 minas consisted

not only of \$\hash\bar{u}ash\bar{v}u\$ and SÍG.IR.Ú.MA.MI.IŠ but also of linen, which — in the light of BM 78914 — is evidently wrong; the "rest" in BM 49580 must be corrected to 25 minas 50 shekels. Although both texts concern the same case, they can't be treated as simple duplicates, because there are some differences between them. The exact interpretation of BM 49580 (i.e. that for manufacturing of the tunšu 5 minas of \$\hashas\bar{u}\sin\bar{u}u\$ and SÍG.IR.Ú.MA.MI.IŠ and 1 mina of linen was used) is possible only by comparison with BM 78914. If BM 78914 were written in order to correct the unclear content of BM 49580, also the initial total amount was corrected (in BM 78914 it is ½ a mina smaller).

Also VS 6, 16, although it concerns the manufacturing of garments a few years later, is contextually close to both texts under discussion. Lines 1–10 concern 36 minas 33 shekels described as *dullu gamru*, and next  $ha\bar{s}h\bar{u}ru$  and SÍG.ÌR.Ú.MA.<MI>.IŠ wool are mentioned, used for a *tunšu* of the finest quality for the pedestal (*kilzappu*) and for 4 *paršīgus ša muṣê*. The total weight of  $54 \frac{2}{3}!$  minas comprise the weight of these items plus the 36 mina 33 shekels mentioned earlier. It means that for the cover (*tunšu*) for the pedestal and for 4 *paršīgu ša muṣê* 18 minas 15 ½ shekels of *hašhūru* and SÍG.IR.Ú.MA.<MI>.IŠ wool was used. It means also that the text does not give the intended use of 36 minas 33 shekels of red and blue-purple wool, described as *dullu gamru*, "completed work".

It should be noted that according to 1. 7 the total of 54 minas 48 ½ shekels also comprises the prebendary income (*pappasu*). If we deduct the initial sum of 36 minas 33 shekels from the total from 1. 7, we received 18 minas 15 ½ shekels, i.e. almost exactly 1/3 of the total and half the amount in 1. 1. As recognized in Vol. I, the weaver's prebendary income was 1/3 of the total (*maššartu*). If this observation is correct it means that the items produced from apple-green coloured and SÍG.ÌR.Ú.MA.<MI>.ĬŠ wool were destined this time not for the god (as in BM 49580 and BM 78914) but for the weaver as his prebendary income. Because the quality of apple-green coloured and SÍG.ÌR.Ú.MA.<MI>.IŠ wool was lower, the quality of the *pappasu* would be less than 1/3 of the total (*maššartu*).

### 15. VS 6, 16; cf. NRV 735; NUVI 3, No. 328

### 23.2.Nbp 20

- 1. 36 ½ ma-na 3 GÍN SÍG.HÉ.ME.DA
- 2. ù SÍG.ZA.GÌN.KUR.RA dul-lu gam-ru
- 3. e-lat! síg haš-hu-ru SÍG.ÌR.Ú.MA.<MI>.IŠ
- 4. KI.LAL 1<sup>en</sup> tu-un-šu lu-bu-uš-tu<sub>4</sub> SAG
- 5. šá UGU GIŠ.GÌR.GUB ù 4 SÍG.BAR.SI.MEŠ
- 6.  $\delta a < IGI > mu-se-e PAP 54^{2/3} ma-na 8 \frac{1}{2} GÍN$
- 7. SÍG.HÉ.ME.DA u SÍG.ZA.GÌN.KUR.RA a-di pap-pa-su
- 8. [x]  $\lceil x \ x \rceil$  šá  $1^{en}$  tu-un-šú lu-bu-uš-tu<sub>4</sub> SAG
- 9. [šá muḥ-ḥi] GIŠ.GÌR.GUB u 4 SÍG.BAR.SI.MEŠ

Edge

- 10. [ $\check{s}\acute{a}$  <IGI> mu-s]e-e ki-i pi-i 5- $(x^?)a_4$
- Rev. 11. [10] *ma-na* 5[7] GÍN 3-*ta* 4-*ta* l<sup>meš</sup> KÙ.BABBAR
  - 12. šá SÍG.ḤÉ.ME.ʿDA¹ [ù SÍG.ZA.GÌN].KUR.RA
  - -----
  - 13. 11 ½ ma-na  $^{\text{síg}}$ [ $\hat{y}_a$ š¹-[ $\hat{y}_u$ -ru] u SÍG.ÌR.Ú.MA.<MI>.IŠ
  - 14. šá 「a¹-ḫi ḫal-ṣu<sup>meš</sup> a-di pap-pa-su
  - 15. 11 ½ GÍN KÙ.BABBAR [ki-i] pi-i 1 [ma]-na-a<sub>4</sub>

## 16. PAP.PAP 11 <sup>r</sup>ma<sup>1</sup>-[na 9 GÍN] 4-tú KÙ.BABBAR

- 17. 12 ma-na SÍG.[x x x] $^{r}$ x $^{1}$  KI.LAL  $^{t\acute{u}g}$ lu-bar ku-lu-lu
- 18.  $^{\text{túg}}$ lu-bar me-tu 「šá  $^{\text{d}}$ x [x  $^{\text{túg}}$ ku]-si-ti TÚG.GÚ.UD.DU
- 19. <sup>túg</sup>lu-bar ku-lu-lu 2 TÚG.BAR.SI.MEŠ šá <sup>d</sup>GAŠAN<sup>!</sup> Sip-par<sup>ki</sup>
- 20. PAP 18½ ma-na a-di pap-pa-su 3½ ma-na 2 GÍN KÙ.BABBAR-šú
- 21. PAP.PAP 14 ma-na 51 GÍN 4-tú KÙ.BABBAR {1}
- 22. šá <sup>md</sup>AG-EN-MU.MEŠ ina É DINGIR ina lìb-bi
- 23. šá 2 ma-na KÙ.BABBAR SÍG.ḤI.A ma-ḥir šá ina ITI.AB
- 24. MU.19.KAM *iš-šu-ú*

L.h.e. 25. ITI.GU<sub>4</sub> U<sub>4</sub>.23.KAM

- 26. MU.20.KAM <sup>md</sup>AG-A-ÙRU
- 27. LUGAL TIN.TIR<sup>ki</sup> NÍG.KA<sub>8</sub> [ép]-šú

For previous interpretation, see the comment to the previous text.

- L. 3. I suggest emending *e-zib* (1. 3) to *e-lat* which makes possible the translation suggested already in NRV 735 (p. 632) and Salonen, NUVI 3, No. 238. The other possibility is suggested by CAD H 141b (s. v. *hašhūru* 2 c): *e-ṣip* SÍG *haš-hu-ru* "a (twisted) cord of apple-coloured wool".
- L. 5. paršīgu, being the element of the pan muṣê, cannot be translated here as "headdress"; I adopt the translation suggested in CAD M II 246.
- L. 6. 54 minas 48 ½ shekels, the total in l. 6, differs from the initial sum (36 minas 33 shekels), which means that the apple-coloured and SÍG.ÌR.Ú.MA.<MI>.IŠ is not included in the initial sum
- L. 14. The translation of *aḥi šá ḥal-ṣu*<sup>meš</sup> is far from clear. NRVI 735 left it without translation; the translation given here comes from Salonen NUVI 3, No.238. "Armel(<sup>??</sup>) aus ausgekämmer Wolle") is doubtful because the texts from the Ebabbar temple concerning garments for the gods never refer to parts of an item, but always the whole item. The alternative translation might have been "half of which (is of) combed wool".
- 36 minas 33 shekels of red and blue-purple wool, the completed work, except for the apple-coloured and SÍG.ÌR.Ú.MA.<MI>.IŠ wool, the weight of 1 cover, the choice garment for the pedestal, and 4  $parš\overline{i}gu$ -streamers? for the < pan> muṣê, total 54 minas 48 ½ shekels of red and blue-purple wool, including the prebendary income, [... the weight] of 1 cover, the choice garment for the pedestal and 4  $parš\overline{i}gu$ -streamers? for the < pan> muṣê, accordingly for each (shekel of silver) 5 (shekels of wool), (what gives) 10 minas 57 ¾ shekels of silver (for) red and blue-purple wool.
- 11 ½ minas of the apple-coloured and SÍG.ÌR.Ú.MA.<MI>.IŠ wool, for the sleeves? of combed wool, including the prebendary income (for) 11 ½ shekels of silver, accordingly for each (shekel of silver) 1 (mina of wool).

Grand total 11 minas 9 1/4 shekels of silver.

12 minas of .... -wool, the weight of *lubār kulūlu* (and) *lubār mēṭu*-headbands [of GN, 1 ro]be, the *naḥlaptu*-cloak, the *lubār kulūlu*-headband, 2 *paršīgu*-headdresses for the Queen of Sippar, total 18 ½ minas (of wool) including the prebendary income – 3 minas 42 shekels is its (value) in silver; grand total 14 minas 51 ¼

shekels of silver, (received) by Nabû-bēl-šumāti from the house of the god (= Šamaš), including wool for 2 minas of silver (which) he has withdrawn in the month of Tebētu.

Month of Ayaru, 23<sup>rd</sup> day, 20<sup>th</sup> year of Nabopolassar, king of Babylon the accounting has been made.

### 16. VS 6, 28; cf. NUVI 3, No. 243

### 5.1.Nbk 8

- 1. 35 ma-na dul-la gam-ru
- 2. KI.LAL TÚG.HI.A TÚG.MÁŠ 7 TÚG.NÍG.ÍB.[LÁ.MEŠ]
- 3. 4 túgsu-ni-e TÚG.HI.A me-e 「SAG1\*
- 4.  $\dot{s}\dot{a}^{\rm d}$ UTU 10 TÚG.NÍG.ÍB.LÁ.MEŠ
- 5. šá <sup>d</sup>A-a TÚG.HI.A TÚG.MÁŠ
- 6. šá <sup>d</sup>Bu-ne-ne 1 ma-na 10 GÍN
- 7. KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ
- 8. 1<sup>en</sup> TÚG.ÚR šá <sup>d</sup>IM u <sup>d</sup>Ša-la 9. <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>UŠ.BAR
- 10. ma-hir ITI.BÁR U<sub>4</sub>.5.KAM
- 11. MU.8.KAM <sup>md</sup>AG-NÍG.DU-ÙRU
- 12. LUGAL E<sup>ki</sup>

Rev. 13. SÍG.ZA.<GÍN>.KUR.RA ina lìb-bi

- 14. na-si-ih
- 15. 1<sup>en</sup> TÚG.ÚR TÚG.NÍG.ÍB.LÁ.MEŠ
- 16. šá <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra*
- 17. *u* <sup>d</sup>*Bu-ne-ne* [*šá*] <sup>⌈</sup>*la*<sup>¹</sup>\*
- 18. ha-a-tu i-nam-din

Already Ungnad had trouble identifying obverse and reverse, but comparison with other texts makes it certain that the order presented here is correct.

L. 13. In the similar texts the quantity of wool which was removed was precisely quoted, i.e. 6 shekels from the *lubāru*-garment of Bunene and 30 shekels from the *lubāru*-garment of Šamaš, see BM 51099 (= 293), rev. col. II 1'-2': BM 51447, (= 294) obv. col. I 6'-7'; BM 50066 (= 295): 3'-4'; BM 50745 (= 297), obv. col. I 1'-2'; rev. col. II 1'-2'; BM 50179 (= 299): 10'-11'; BM 84509 (= 304): 1-2; BM 67542 (= 307): 9'-10'.

35 minas, the completed work, the weight of the *lubāru* (and) *sibtu*-garments, 7 sashes, 4 *sūnu*-belts, the *lubār mē qaqqadi*-headdress for Šamaš.

10 sashes for Aya; the *lubāru* (and) the *şibtu*-garments for Bunene.

1 mina 10 shekels, the weight of 10 sashes (and) 1 sūnu-belt for Adad and Šala was received from Nabû-bēl-šumāti, the weaver.

Month Nisannu, 5<sup>th</sup> day, 8<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

Blue-purple wool was removed from (them).

1 sūnu-belt (and) sashes for the Daughters of the Ebabbar and for Bunene, which are given [without] (earlier) supply.

### 17. BM 49567 (82-3-23, 558)

PLATE 6

 $4.4 \times 3.5 \text{ cm}$ 

### 5.[x].Nbk [x]

- 1. [x] <sup>r</sup>ma-na<sup>1</sup> KI.LAL 1<sup>en</sup> TÚG.ḤI.A
- 2. [2 TÚG.MÁŠ] 7 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá  $^{\rm d}$ UTU
- 3. [10 TÚG.NÍG.ÍB]. LÁ¹.MEŠ šá dA-a
- 4. [TÚG.HI.A TÚG].MÁŠ šá <sup>d</sup>Bu-ne-ne
- 5. [4 TÚG.ÚR].MEŠ šá <sup>d</sup>UTU
- 6. [*u* <sup>d</sup>*A-a* 10] TÚG.<NÍG>. 「ÍB.LÁ¹.<MEŠ> 1<sup>en</sup> TÚG.ÚR

Edge 7. [ $\check{s}\check{a}^{d}$ IM  $u^{d}\check{S}a$ -la PN ma-hi-ir]

Rev. 8. [ITI.x] U<sub>4</sub>.5.KAM

9. [MU.x.K]AM <sup>md</sup>AG-NÍG.DU-ÙRU

10. [LUGA]L E<sup>ki</sup>

The reconstruction of  $T\dot{U}G.\dot{U}R$  in 1. 5 is based on the fact that the  $s\bar{u}nu$  is present in the typical catalogue of the garments for Šamaš.

L. 7. The name of Nabû-bēl-šumāti is expected here.

[x] minas, the weight of 1 *lubāru*-garment, [2 *şibtu*-garments], 7 sashes for Šamaš, [10 sash]es for Aya, [the *lubāru*] (and) *şibtu*-garments for Bunene; 4 *sūnu*-belts for Šamaš [and Aya; 10] sashes, 1 *sūnu*-belt [for Adad and Šala received from PN]. [Month of x], 5<sup>th</sup> day [n<sup>th</sup> year] of Nebuchadnezzar, king of Babylon.

### 18. BM 49471 (82-3-23,462)

PLATE 6

 $4.7 \times 3.3$  cm

### 5.6<sup>?</sup>.Nbk 9

- 1. 35 ½ ma-na dul-la
- 2. gam-ru KI.LAL TÚG.ḤI.A
- 3. TÚG.MÁŠ {TÚG.<NÍG>.ÍB.LÁ.MEŠ}
- 4. TÚG.HI.A SIG<sub>5</sub> ÚR.MEŠ
- 5. TÚG.<NÍG>.ÍB.LÁ.MEŠ šá  $^{\mathrm{d}!}$ UTU u  $^{\mathrm{d}}$ A-a
- 6. TÚG.HI.A TÚG.MÁŠ šá <sup>d</sup>Bu-<sup>r</sup>ne-ne<sup>1</sup>
- 7. 1 ma-na 10 GÍN KI.LAL

Edge 8. TÚG.ÚR u TÚG.<NÍG>.ÍB.LÁ.<MEŠ>

Rev.

9. *šá* <sup>d</sup>IM *u* <sup>d</sup>*Ša*-[*la*]

- 10. mdAG-EN-MU.MEŠ lú[UŠ.BAR]
- 11. ma-hir ITI. K[IN]
- 12. U<sub>4</sub>.5.KAM MU.9.KAM
- 13. md AG-NÍG.DU-ÙRU LUGAL E<sup>ki</sup>

Cf. the similar text BM 49268 (= 3) and BM 50272 (= 1).

L. 3. The TÚG.<NÍG>.ÍB.LÁ.MEŠ is most probably repeated here mistakenly because the *huṣannu*-sashes for Šamaš and Aya are mentioned in l. 5.

L. 5. Before UTU there is a bar, repeated 3 times. I emended TÚG.ÍB.LÁ.MEŠ to TÚG.<NÍG>.ÍB.LÁ. MEŠ because in many texts the  $s\bar{u}nu$  is mentioned together with the  $hu\bar{s}annu$ -sashes and never with the  $n\bar{e}behu$ -belt(s).

35 ½ minas, the completed work, the weight of the  $lub\bar{a}ru$  (and) sibtu-garments, {the sashes!}, fine? cloths, the  $s\bar{u}nu$ -belts, the sashes! for Šamaš and Aya the  $lub\bar{a}ru$  (and) sibtu-garments for Bunene.

1 mina 10<sup>!</sup> shekels, the weight of *sūnu*-belt and the sashes<sup>!</sup> for Adad and Šala, were received from Nabû-bēl-šumāti, the [weaver].

Month of U[lūlu], 5<sup>th</sup> day, 9<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

### **19. BM 49416** (82-3-23, 407)

PLATE 7

 $5.3 \times 3.5$  cm

### 1.6.Nbk 10

- 1. 37 ma-na dul-la gam-ru
- 2. KI.LAL TÚG. THI.A TÚGI.MÁŠ šá dUTU
- 3. TÚG.ḤI.A 「SIG<sub>5</sub> TÚG¹.ÚR.MEŠ
- 4. ù TÚG.<NÍG>. ÍB.LÁ¹.MEŠ
- 5. TÚG.HI.A TÚG.MÁŠ šá <sup>d</sup>Bu-ne-ne

Edge

- 6. <sup>md</sup>*I-šum-*MU
- 7. it-ta-din ITI.KIN
- 8. 1 ma-na 10 GÍN <KI.LAL> TÚG.ÚR ù
- 9. TÚG.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>IM
- 10. md AG-EN-MU.MEŠ <SUM> ITI.KIN
- 11. U<sub>4</sub>.1.KAM MU.10.KAM <sup>md</sup>AG-NÍG.DU-ÙRU
- 12. LUGAL E<sup>ki</sup>

Cf. BM 49471 (= 18), BM 49268 (= 3) and BM 50272 (= 1).

For the argument for emendation TÚG.ÍB.LÁ to TÚG.<NÍG>.ÍB.LÁ, cf. above.

37 minas, the completed work, the weight of the *lubāru* (and) *ṣibtu*-garments for Šamaš, fine cloths<sup>7</sup>, the *sūnu*-belts and the sashes<sup>!</sup>; the *lubāru* (and) *ṣibtu*-garments for Bunene, Išum-iddin has delivered. Month of Ulūlu.

1 mina 10 shekels, <the weight> of the *sūnu*-belt and the sashes for Adad, Nabû-bēl-šumāti (has delivered).

Month of Ulūlu, 1<sup>st</sup> day, 10<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

### **20. BM 52285** (82-3-23, 3319)

 $2.7 \times 3.0 \text{ cm}$ 

### 10+[x<sup>?</sup>].3.Nbk 13

- 1. [x] ma-na 1/3 6 G[ÍN dul-lu]
- 2. gam-ru KI.LAL 10 [TÚG.NĬG.ÍB.LÁ.MEŠ]
- 3. 1<sup>en</sup> TÚG.ÚR [....]

- 4.  $1^{en}$  TÚG.BAR.SI [(x x x)] 5.  $^{md}$ AG-EN-MU.[MEŠ (x x x)]
- 6. it-ta-din

Edge

- 7. ITI.SIG<sub>4</sub> U<sub>4</sub>.10[+x<sup>?</sup>].KAM
- 8. [MU].13.KAM
- 9. [md][AG]-NÍG.D[U-ÙRU]

[x] minas 26 shek[els, the completed] work, the weight of 10 [husannu]-sashes, 1 *sūnu*-belt, [....], 1 *paršīgu*-headdress [(x x x)], Nabû-bēl-šumāti [....] has delivered. Month of Simanu, day 10+, [year] 13<sup>th</sup> of Nebuchad[nezzar].

### **21. BM 50342** (82-3-23, 1333)

PLATE 8

 $4.0 \times 5.7$  cm

### 7.2.Nb[k x]

- 1. 4<sup>6</sup>1 ½ ma-na {x x- er.} KI.LAL
- 2. TÚG.HI.A 2 TÚG.MÁŠ.MEŠ
- 3. TÚG.HI.A SIG5 4 TÚG.ÚR.MEŠ
- 4. 17 TÚG.NÍG.ÍB.LÁ.MEŠ
- šá <sup>d</sup>UTU u <sup>d</sup>A-a
- 6. <sup>md</sup>AG-EN-MU.MEŠ it-ta-din

one line free

- 7. ITI.GU<sub>4</sub> U<sub>4</sub>.7.KAM
- 8. [MU.x.K]AM <sup>md</sup>AG-[NÍG.DU-ÙRU]

Rest lost

Rev.

- 1'. [x x x] <sup>[</sup>x¹ TÚG.<sup>[</sup>x¹ [....]
- 2'. [x x x] *šá* <sup>d</sup>[DN]
- 3'. fully lost
- 4'.  $[x \times x \times pa]r$ -sig- $g[a^{?}]$
- 5'.  $\lceil \check{s} \acute{a}^{d} A a^{\dagger} \check{s} \acute{a} [x x x] \lceil x^{\dagger}]$
- 6'.  $t^{ig}[lu-bar][ku]-lu-[lu][t]^{ig}[u]-bar me-tu$
- 7'. TÚG.[x x x x] šá <sup>d</sup>Bu-ne-<sup>r</sup>ne<sup>1</sup>
- 8'. 1 ma-na 1/3 GÍN KI.LAL
- 9'. ni-bi-ḥu šá <sup>d</sup>[Bu-ne-ne]
- 10'. 2 ku-sa-a-tú 2 「TÚG.MEй
- 11'. šá <sup>d</sup>DUMU.MÍ.MEŠ É-b[abbar-ra]
- 12'. 1 ma-na 55 GÍN KI.LAL  $^{\text{túg}}$   $sib^1$ - $t[u_4]$ L.h.e.
  - 13'. šá <sup>d</sup>Bu-ne-ne <sup>md</sup>AG-EN-MU.MEŠ it-t[a-din]
- L. 1 between ma-na and KI.LAL there is an erased space for ca. 2 signs.

46 1/2 minas, the weight of the *lubāru*-garment, 2 *sibtu*-garments, fine? cloths, 4 *sūnu*-belts, 17 sashes for Šamaš (and) Aya Nabû-bēl-šumāti has delivered. Month of Ayaru, 7<sup>th</sup> day, [n<sup>th</sup> year] of Nebu[chadnezzar, king of Babylon].

[....] paršīgu-headdress for Aya [....], the lubār kulūlu (and) lubār mēṭu-headbands, the [....] for Bunene.

1 mina 20 shekels, the weight of *nēbeḥu*-wrap? for Bunene.

2 robes, 2 garments for the Daughters of E[babbara].

1 mina 55 shekels, the weight of the sib[tu]-garment for Bunene, Nabû-bēl-šumāti has deli[vered].

### **22. BM 51293** (82-3-23, 2327)

PLATE 9

 $4.7 \times 3.3 \text{ cm}$ 

### 12.8.Nbk [x]

- 1. 35 ½ ma-na 5 GÍN [dul-lu gam-ru]
- 2. KI.LAL TÚG. $\{UD^{?}\}$ .HI.A TÚG.MÁ[Š] 3. 4 TÚG.ÚR.MEŠ 7 TÚĞ.[NÍG.ÍB.LÁ.MEŠ]
- 4. šá <sup>d</sup>UTU 10 TÚG.<NÍG>.ÍB.LÁ.[MEŠ šá <sup>d</sup>A-a]
- 5. [10 TÚ]G.<NÍG>ÍB.LA.MEŠ <sup>d</sup>[GAŠAN Sip-par<sup>ki</sup>]
- 6. [TÚG].HI.A TÚG.MÁŠ *šá* <sup>d</sup>[*Bu-ne-ne*]
- 7. [mdAG]-EN-MU.MEŠ [it-ta-din]

8. [ITI. AP]IN U<sub>4</sub>.12.K[AM MU.x.KAM] Edge 9. [mdA]G-NÍG.DU-[ÙRU LUGAL E.KI] Rev.

10. <sup>[5]</sup> GÍN *mi*<sup>?</sup>-[....]

L. 10. mi is written over an erasure.

35 minas 35 shekels [the completed work], the weight of the lubāru (and) şibtugarments, 4 sūnu-belts, 7 hu[sannu]-sashes for Šamaš, 10 sashes [for Aya], [10] sashes [for the Queen of Sippar];

[the lubā]ru (and) sibtu-garments for [Bunene Nabû]-bēl-šumāti [has delivered]. [Month of Arah]samna, 12<sup>th</sup> day, [n<sup>th</sup> year] of Nebuchadne[zzar, king of Babylon]. 5 shekels [....]

### 23. BM 79386 (89-4-26, 683)

PLATE 9

 $3.65 \times 2.9 \text{ cm}$ 

### $2+x^{?}$ .[x.Nb]p or [Nb]k 12

- 1. 32 ma-na 1/3 GÍN <dul>-la gam-ru KI.LAL
- 2. TÚG.HI.A TÚG.MÁŠ TÚG.HI.A SIG5 4 TÚG.ÚR.MEŠ
- 3. 20 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU <sup>d</sup>A-a
- 4. u dGAŠAN Sip-par<sup>ki</sup>
- 5.[1]+ <sup>[1]</sup> ma-na KI.LAL TÚG.ḤI.A TÚG.MÁŠ
- 6.  $[\check{s}\check{a}]^{\lceil d\rceil}[Bu]$ -ne-ne
- 7. [x *ma-na*] 1/3 GÍN KI.LAL

8. [x x x]  $\lceil x \rceil$  TÚG.<NÍG>.ÍB.[LÁ (x)  $^{t}$ ]  $^{\acute{u}g}$  par-ši-ir Edge

Rev. 9. [x x x x] *ma-hir* 

- 10. [ITI.x.U<sub>4</sub>.x+<sup>?</sup>]2.KAM MU.12.KAM
- 11. [dAG-NÍG.DU]-ÙRU LUGAL E.KI
- L. 3. 26 or 27 huşannu-sashes are expected here, but 20 is clear.
- L. 5. Only [1] is preserved, however, it seems that before, almost on the left edge, one vertical stroke has been written. Note that the numeral 20 in l. 3 is also written partly on the left edge.
- L. 8. The *ir*, placed almost exactly over *ši*, was probably a mistake for *gu*.
- L. 11. Or [dAG-DUMU.UŠ]-ÙRŪ
- 32 minas 20 shekels, the completed work, the weight of the *lubāru*-garment (and) *ṣibtu*-garments, fine? cloth, 4 *sūnu*-belts, 20 sashes for Šamaš, Aya and the Queen of Sippar.
- <sup>[2]</sup> minas, the weight of *lubāru* (and) the *şibtu*-garments for Bunene;
- [x] mina(s) 20 shekels, the weight of ..... sashes (and) paršīgu -headdress was received from [PN].

[Month of x, x+] 2 day, 12<sup>th</sup> year of Nabû-[apal/kudurri]-uşur, king of Babylon.

### **24. BM 50198** (82-3-23, 1189)

PLATE 10

 $5.2 \times 3.9$  cm

### 2.6.Nbk [x]

- 1.  $36 \text{ ma-}^{\text{r}} \text{na}^{\text{l}} [dul\text{-}lu \text{ gam-}ru]$
- 2. KI.LAL TÚG.ḤI.A [TÚ]G].「MÁй
- 3. [6] TÚG.NÍG.ÍB¹.LÁ.MEŠ [šá <sup>d</sup>UTU]
- 4. [10 TÚG]. [NÍG]. [ÍB.L]Á.MEŠ *š*[á <sup>d</sup>*A-a*]
- 5.  $[x \times x \times]$ .MEŠ  $[x \times x \times]$
- 6. [x x x] 10 TÚG.NÍG.ÍB1.LÁ.[MEŠ]
- 7. [[šá <sup>d</sup>GAŠAN Sip]-<sup>r</sup>par<sup>ki</sup>¹ TÚG.ḤI.A
- 8. [TÚG.MÁŠ] *šá* <sup>d</sup>Bu-ne-ne
- 9.  $[^{m}NUMUN]^{-\Gamma}\dot{u}^{1}-tu^{1\dot{u}}U\check{S}.BAR$
- Edge 10. [x x SU]M ITI.KIN U<sub>4</sub>.2.KAM
  - 11. [MU.x].KAM <sup>d</sup>AG-NÍG.DU-ÙRU

Rev. 12. LUGAL E<sup>ki</sup>

- 13. [5 TÚG].NÍG.ÍB.LÁ.MEŠ 1<sup>en</sup> TÚG.ÚR
- 14. <sup>r</sup>šá<sup>†</sup> Bu-ne-ne
- 15. [10] 'TÚG'.NÍG.ÍB.LÁ.MEŠ
- 16. 「šá<sup>†</sup> dDUMU.MÍ.MEŠ É-babbar-[ra]
- 17. *šá la ḥa-a-ṭu* <sup>r</sup>*a*¹-[*na* É DINGIR]
- 18. *i-nam-[din]*

L. 13. The numeral is reconstructed by comparison with BM 51099 (= 293) rev. col. II 4'; BM 51447 (= 294) obv. col. I 9'; BM 50066 (= 295) col. I 6'; BM 50745 (= 297) obv. col. I 4; rev. col. II 4'; BM 52475 (= 298) obv. obv. 9'; BM 50179 (= 299): 5'; CT 55, 844 (= 301): 13; BM 84509 (= 304): 4; CT 55, 837 (= 306): 15. Note that in all other texts mentioned here

(except this one and CT 55, 844 (= 301)) in the list of the garments for Bunene a  $par \check{s} \bar{t} g u$  is also mentioned.

L. 15. The numeral is reconstructed by comparison with BM 51099 (= 293) rev. col. I 1', rev. col. II 6'; BM 51447 (= 294) obv. col. I 10'; BM 50066 (= 295) col. I 7'; BM 50745 (= 297) obv. col. I 5; rev. col. II 5; BM 52475 (= 298) obv $^2$  10'; BM 50179 (= 299): 7'; CT 55, 844(= 301): 15; BM 53364 (= 302): 3'; CT 55, 837 (= 306): 16. Note that *huṣannu*-sashes as a part of garments for Bunene are known only from the texts dated to the early years of Nebuchadnezzar's reign.

36 minas, [the completed work], the weight of the lubāru (and) sibtu-garments,

[6] sashes [for Šamaš], [10] sashes [for Aya ....], 10 sashes [for ....];

the  $lub\bar{a}ru$  [(and) sibtu]-garments for Bunene, [Zērū]tu, the weaver [has deli]vered. Month of Ulūlu ,  $2^{nd}$  day, [ $n^{th}$  year] of Nebuchadnezzar, king of Babylon.

[5] sashes, 1 sūnu-belt for Bunene;

[8] sashes for the Daughter of the Ebabbar, without of an (earlier) supply he delivers [to the temple].

### 25. BM 52731 (82-3-23, 3765)

 $5.5 \times 2.1$  cm

### 13.8.Nbk [x]

Edge

1.32+[x] ma-na dul-la gam-r[u]

Obv.

2. r<sup>md</sup>AG¹-EN-MU.MEŠ lúUŠ.[BAR]

3. [*ma-hir*] ITI.APIN U<sub>4</sub>.13.[KAM]

4. [MU.x.K]AM <sup>md</sup>AG-NÍG.DU-ÙRU [LUGAL TIN.TIR<sup>ki</sup>]

-----

5. [3]+4 'TÚG'.[NÍG].ÍB.LÁ.MEŠ *šá* <sup>d</sup>'UTU' [....]

### Rest lost

Rev.

1'. TÚG.HI.A TÚG.[MÁŠ šá] <sup>d</sup>[Bu]-ne-ne

2'. 1 ma-na 10 GÍN dul-la gam-ru K[I].LAL

3'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ 1 $^{en}$  TÚG.ÚR

4'. šá <sup>d</sup>I[M] u <sup>d</sup>Ša-la

The text has a somewhat atypical structure. Because other texts of this category give first the total weight of all items, and next enumerate the items of a particular god, first Šamaš, next Aya, etc., I decided that it began at the edge. Note that the *ḫuṣannu*-sashes for Šamaš are always (but not here) preceded by his *lubāru*-garment and *ṣibtu*-garment (probably they were mentioned in the missing part of the obverse).

32+x minas, the completed work, [received from] Nabû-bēl-šumāti, the weaver. Month of Araḥsamna, 13<sup>th</sup> day, [n<sup>th</sup> year] of Nebuchadnezzar, king of Babylon. <sup>1</sup>7¹ sashes of Šamaš, [....]

the *lubāru* (and) [*sibtu*-garmen]ts for Bunene

1 mina 10 shekels, the completed work, the weight of 10 sashes (and) 1 *sūnu*-belt for Ad[ad] and Šala.

### **26. BM 52102** (82-3-23, 3136)

PLATE 10

 $3.9 \times 3.4 \text{ cm}$ 

### x+2.x.Nbk[x]

 $1.40 \, ma$ -na dul-la gam-r[u]

TÚG.ḤI.A TÚG.M[ÁŠ]

2. TÚG.HI.A SIG<sub>5</sub> 7 < TÚG.NÍG>.ÍB.L[Á.MEŠ]

3. 4 TÚG.ÚR.MEŠ [šá <sup>d</sup>UTU]

4. 10 TÚG. <NÍG>.ÍB.LÁ.MEŠ [<sup>d</sup>A-a]

5. 10 TÚG. <NÍG>.ÍB.LÁ.MEŠ [dGAŠAN Sip-parki]

6. 10 TÚG. <NÍG>.ÍB.LÁ.MEŠ [*ù*<sup>?</sup>] Edge

7.  $1^{en}$  TÚG.  $\Gamma$ ÚR $^{\dagger}$  [ $\check{s}\acute{a}$   $^{d}$ IM u  $^{d}\check{S}a$ -la]

8. md AG-EN-[MU.MEŠ] Rev.

9. lúUŠ.BAR [*ma-hir*]

10. I[TI.x U<sub>4</sub>.x.KAM]

11. [MU.x.KAM <sup>m</sup>]<sup>d</sup>AG-NÍG.D[U-ÙRU]

12. [LUGAL] E.K[I]

Ll. 6–7. That "10 sashes [and<sup>?</sup>] 1 sūnu-belt [for Adad and Šala]" means sūnu-belt and 5 sashes for Adad and 5 sashes for Šala, see Zawadzki, Garments of the Gods, Vol. I,

40 minas, the completed work, the *lubāru* (and) [sibtu-garments], fine? cloth, 7 sashes, 4 sūnu-belts [for Šamaš],

10 sashes [for Aya],

10 sashes [for the Queen of Sippar],

10 sashes [and<sup>?</sup>] 1 sūnu-belt [for Adad and Šala] has been received from Nabû-bēl-[šumāti], the weaver.

Month [of x, n<sup>th</sup> day, n<sup>th</sup> year] of Nebucha[dnezzar, king of] Babylon.

### **27. BM 50255** (82-3-23, 1246)

PLATE 11

 $2.3 \times 3.2 \text{ cm}$ 

### 13.12.Nbk [x]

1. [x ma-na dul-l]u gam-ru KI.LAL

2. [TÚG.HI.A TÚG.MÁŠ TÚG].HI.A SIG<sub>5</sub>

3. [TÚG.ÚR.MEŠ] ù TÚG.<NÍG>.ÍB.LÁ.<MEŠ>

4. [šá <sup>d</sup>UTU u <sup>d</sup>A]-a TÚG.HI.A TÚG.MÁŠ

5. [šá <sup>d</sup>Bu-ne-n]e 1 ma-na 17 ½ GÍN

6. [KI.LAL 1 $^{en}$  TÚG]. 「ÚR 1 10 TÚG. < NÍG>. ÍB.LÁ.MEŠ 7. [šá  $^{d}$ IM u  $^{d}$ Ša-la  $^{md}$ A]G-EN-MU.MEŠ

8. [lúUŠ.BAR ma-hir I]TI.ŠE U<sub>4</sub>.13.KAM Edge

9. [MU.x.KAM AG]-NÍG.DU-ÙRU

10. LUGAL TIN.TI]Rki Rev.

[x minas], the completed [wor]k, the weight of [the lubāru (and) sibtu-garments, fine? [clo]ths, [the *sūnu*-belts] and sashes [for Šamaš and A]ya;

the *lubāru* (and) *şibtu*-garments [for Bunen]e

1 mina 17 ½ shekels (of wool), [the weight of the  $s\bar{u}$ ]nu-belts (and) 10 sashes [for Adad and Šala was received from Nabû]-bēl-šumāti, [the weaver].

Month of Addaru, 13<sup>th</sup> day, [n<sup>th</sup> year of Nebu]chadnezzar, king of Babylon. [....].

### 28. BM 50439 (82-3-23, 1430)

PLATE 11

 $3.8 \times 5.6$  cm

$$[x].1^{?}[x]$$

- 1. 36 ma-na <dul-lu> gam-ru
- 2. KI.LAL TÚG.ḤI.A TÚG.MÁŠ šá  $[^d]$ UTU
- 3. TÚG.ḤI.A SIG<sub>5</sub><sup>qa</sup> šá <sup>d</sup>UTU <sup>r</sup>x x¹ (erased²)
- 4. TÚG.HI.A TÚG.MÁŠ *šá* <sup>d</sup>Bu-ne-ne

- 5. 1<sup>en</sup> ÚR TÚG.<NÍG>.ÍB.LÁ.MEŠ 6. šá <sup>d</sup>UTU u <sup>[d]</sup> A¹-[a] 7. <sup>md</sup>AG-EN-「MU¹.[MEŠ <sup>lú</sup>UŠ.BAR]
- 8. *it-ta-*[*din*]
- 9. ITI.BÁ[R ....]

Rest lost

Rev. uninscribed

- L. 3. After UTU there are two badly preserved signs written over right edge, probably erased, maybe a badly written  $\dot{u}$ .
- L. 5. Note that only 1 sūnu is mentioned here, instead of the typical 4 sūnus, i. e. 2 for Šamaš and 2 for Aya.

36 minas, the completed <work>, the weight of the *lubāru* (and) *şibtu*-garments [for] Šamaš (and) fine? cloths for Šamaš;

the *lubāru* (and) *sibtu*-garments for Bunene;

1 sūnu-belt (and) sashes for Šamaš and Ay[a], Nabû-bēl-šumāti, [the weaver], has delive[red].

Month of Ni[sannu<sup>?</sup>, ....].

### **29. BM 51568** (82-3-23, 2602)

PLATE 12

 $3.7 \times 3.1 \text{ cm}$ 

- 1. 34 ½ ma-na KI.LAL TÚ[G.ḤI.A]
- 2. TÚG MÁŠ 7 TÚG.NÍG.ÍB.LÁ.M[EŠ]
- 3. 4 TÚG.ÚR.MEŠ TÚG.HI.A [SIG<sub>5</sub>]
- 4. *šá* <sup>d</sup>UTU 10 TÚG.NÍG.ÍB.L[Á.MEŠ *šá* <sup>d</sup>A-a]

5. [10 T]ÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{\rm rd}$ 1[GAŠAN  $\it Sip-par^{\rm ki}$ ] 6.  $[x \times x \times x \times x]^{T} \times x^{T} [....]$ 

Rest lost

Rev.

- 1'.  $[x x x x x]^{\lceil x \rceil} [....]$
- 2'. [É] DINGIR x x <sup>r</sup>x<sup>1</sup> [....] 3'. *šá la ḫa-a-tu* <sup>m</sup>r<sup>d</sup>¹[AG-EN-MU.MEŠ]
- 4'. lúUŠ.BAR [i-nam-din]

### L. 3. $[SIG_5]$ or [SAG.DU].

Rev. 2'. The two signs following DINGIR are written superficially and I cannot identify them.

34  $\frac{1}{2}$  minas, the weight of the  $lu[b\bar{a}ru]$  (and) sibtu-garments, 7 sashes, 4 sūnu-belts, the fine? cloths for Šamaš; 10 sashes [for Aya]; [10 s]ashes for [the Queen of Sippar

[.... to] the temple x x x [whom] no (additional) supply (is given) [Nabû-bēlšumāti], the weaver [delivers].

### **30. BM 49370** (82-3-23, 361)

PLATE 12

 $4.8 \times 3.8$  cm

- 1. 42 ma-na KI.LAL lu-ba-ri u şib-<sup>r</sup>ti<sup>7</sup>
- 2. su-ni-e lu-ba-ri-e zíq-qu
- 3. hu-şa-an-ni-e šá  $^{d}$ UTU x x (x) (er.)
- 4. lu-ba-ri u sib-ti šá <sup>d</sup>Bu-ne-ne
- 5. 21 ma-<sup>r</sup>na<sup>1</sup> [KI.LAL l]u-ba-ri șib-ti
- 6. [.... su]-ú-nu

Rest lost

- L. 2. Or siq-qu, cf. CAD 128 b: ziqqu "an ornament in the shape of crescent or battlements", and p. 129 where it is suggested that ziqqu may be related to sissiktu, i.e. the decorated hem of a garment.
- L. 3. At the end of the line there are traces of two or three erased signs.
- 42 minas, the weight of the *lubāru* and *şibtu*-garments, the *sūnu*-belts, the *lubār* ziqqu-garment (and) the sashes for Šamaš,

the *lubāru* and) the *şibtu*-garments for Bunene.

21 minas, the weight of the *lubāru* (and) *şibtu*-garments, [....  $s\bar{u}$ ]nu-belt [....].

### 31. BM 52314 (82-3-23, 3348)

PLATE 12

 $4.8 \times 2.7$  cm

- 1. 36 ½ ma-na dul-lu gam-ru
- 2. KI.LAL TÚG.ḤI.A TÚG.MÁŠ ÚR.[MEŠ
- 3. [x TÚG.NÍG.ÍB.LÁ].MEŠ

Rest lost

1'. LUGAL TI[N.TIR]<sup>ki</sup> Rev.

36 ½ minas, the completed work, the weight of the  $lub\bar{a}ru$  (and) sibtu-garments, the  $s\bar{u}nu$ -belts, [x] sashes, [....] [...., king of Ba[bylo]n.

### 32. BM 53219 (82-3-23, 4253)

 $3.3 \times 3.2 \text{ cm}$ 

- 1. 31 2/3 ma-n[a dul-lu]
- 2. gam-ru KI.LAL T[ÚG.HI.A]
- 3. [TÚ]G.MÁŠ TÚG.ḤI.A 「x¹ [ÚR.(MEŠ)]
- 4. 6 TÚG.<NÍG>.ÍB.LÁ.ME[Š šá <sup>d</sup>UTU]
- 5. 10 TÚG.<NÍG>.ÍB.LÁ.ME[Š šá <sup>d</sup>A-a]

Edge 6. [....]

Rev. 1'.  $\lceil x \ x \rceil \ [\dots]$ 

- 2'.  $[x \ x] \lceil x \rceil . A \ \hat{u} \lceil x \rceil [....]$
- 3'. <sup>lú</sup>UŠ.BAR.MEŠ [....]
- 4'. [SÍG.ḤÉ.M]E.DA *lu-b*[*u-uš-tu*<sub>4</sub><sup>?</sup>]

Edge 5'. [x x x] <sup>r</sup>x¹ U<sub>4</sub>. <sup>r</sup>2¹. [KAM ....]

6'. [x x x]  $it^{-1}ta^{-1}$ -[din ....]

7'. [x x x] U<sub>4</sub>.1.K[AM ....]

31 minas 40 shekels, the completed [work], the weight of the  $lu[b\bar{a}ru]$  (and) sibtugarments, [x  $s\bar{u}nu$ -belt(s)], 6 sashes [for Šamaš], 10 sashes [for Aya ....]. [....] and [....] the weavers [....] of red (for)  $lub[u\bar{s}tu]$  ceremony? [....]  $\lceil 2^{nd} \rceil$  [day] [PN] has del[vered]? [....]  $1^{st}$  day [...].

### 33. BM 52272 (82-3-23, 3306)

Small fragment of the right side of the tablet

### [x.x.Nb]k 3

- 1. [x] ma-na dul-lu
- 2. [gam-ru] KI.LAL TÚG.HI.A
- 3. [TÚG.MÁŠ x TÚ]G.ÚR.MEŠ
- 4. [x x x] ITI.DU<sub>6</sub> SUM
- 5. [....] x [....]

Rev. 1'. [....] 'x' TÚG/ku 'x' [....]

- 2'. [ITI.x U<sub>4</sub>.x].KAM MU.3.KAM
- 3'. [<sup>md</sup>AG-NÍG.D]U-ÙRU
- 4'. [LUGAL] E<sup>ki</sup>

[x] minas, [the completed] work, the weight of the  $lub\bar{a}ru$  (and) [sibtu-garments, x]  $s\bar{u}nu$ -belts [....] of the month Tašrītu was delivered.

[....]-garment [.... Month of x, n<sup>th</sup> day], 3<sup>rd</sup> year [of Nebuchad]nezzar, [king] of Babylon.

### 34. BM 49992 (82-3-23, 983)

PLATE 13

 $6.6 \times 4.5$  cm

### 4.1.<Nbk> 7

- 1.  $[^t]^{\acute{u}g}lu$ -ba-ri šá  $^dU[TU\ \grave{u}]$  şib-tu<sub>4</sub> 2.  $[^{t\acute{u}}]^glu$ -ba-ri me-si-qu
- 3.  $\int_{0}^{10g_1} hu$ -sa-an-ni-e [4] TÚG.ÚR.MEŠ < šá  $^{\rm d}$ UTU>
- 4.  $^{\text{túg}}$ hu-ṣa-an-ni-e 「šá $^{\text{1}}$ d $^{\text{d}}$ A-a
- 5. [ $^{\text{túg}}$ lu-b]a-ri ù ṣib-tu<sub>4</sub> šá  $^{\text{d}}$ Bu-n[e-n]e ½ GÚ.UN
- 5a. 6 ma-na 10 GÍN KI.LAL-<sup>[</sup>šú-nu]
- 6. [10] <sup>túg</sup>hu-ṣa-an-ni-e ù
- 7. [1 TÚ]G.ÚR *šá* <sup>d</sup>IM
- 8. [1 m]a-na 10 GÍN PA-su-nu
- 9. [ITI].BÁR U<sub>4</sub>.4.KAM MU.<sup>[7]</sup>.KAM

10. [md] AG¹-EN-MU.MEŠ ma-「hir¹ Edge

The atypical shape of the text should be noted. The obverse is convex and the reverse flat. The tablet is rounded and it is not excluded that it is an exercise text of a young apprentice.

- L. 1 The scribe probably wrote dUTU after túglu-ba-ri instead of after the sib-tu<sub>4</sub>.
- L. 2. Concerning me-si-qu, cf. Vol. I, p. 95 ff.
- L. 5a is written on the reverse, however it continues line 5 of the obverse. 36 minas 10 shekels has to be the total weight of all previously counted items.
- L. 8. In parallel passages instead of PA-su-nu there is KI.LAL(-šu-nu), cf. BM 49416 (= 19): 8–9; BM 49471 (= 18): 7–9; BM 61920 (= 305): 6–7; VS 6, 28 (= 16): 12–14 and many others. Maybe PA stays here for SÍG = mihşu (based on the reading TÚG.SÍG = mihşu, cf. Postgate 1973, p. 28). The possible translation is: "[10] huṣannus, [1] sūnu for Adad, (the weight) of their woven cloths." The text in this place is preserved very well and the reading PA is out of doubt.

The *lubāru*-garment for Šamaš [and<sup>?</sup>] the *sibtu*-garment, the *lubār mēsiqu*-garment, the sashes, [4] sūnu-belts <for Šamaš>; the sashes for Aya; the lubāru and sibtugarments for Bunene – their weight is 36 minas 10 shekels;

[10] sashes and [1] sūnu-belt for Adad – their weight is [1] mina 10 shekels. Month of Nisannu, 4<sup>th</sup> day, 7<sup>th</sup> year; received from Nabû-bēl-šumāti.

### 35. BM 69250 (82-9-18, 9248)

 $5.3 \times 4.8$  cm

- 1'. [ $^{t\acute{u}g}$ lu-ba-ri ù sib-tu<sub>4</sub> šá]  $^{d}$ UTU 2'. [ $^{t\acute{u}g}$ lu-ba-ri me]-si-qu šá  $^{d}$ UTU
- 3'. [4 TÚG.ÚR].MEŠ šá <sup>d</sup>[UTU]
- 4'. [túghu-ṣa]-nu<sup>meš</sup> šá <sup>d</sup>UTU

```
5'. [^{\text{túg}}hu-\$a]-\lceil nu\rceil^{\text{meš}} šá ^{\text{d}}A-a 6'. [^{\text{túg}}lu-ba-ri] \$ib-tu \lceil \$á ^{\text{d}} [\text{\ref{HAR}}]
```

7'. [.... šá] <sup>d</sup>ḤAR [....].

The text is reconstructed on the basis of BM 49992 (see above).

[The lubāru and the sibtu-garments] for Šamaš; [the lubār me]siqu-garment for Šamaš, [4] sūnu-belts for Šamaš, [x sas]hes for Šamaš

\_\_\_\_\_

[x sash]es for Aya; [the lubāru] (and) sibtu-garments for [Bunene]; [.... for] Bunene [....].

#### 36. BM 52330 (82-3-23, 3364)

PLATE 13

 $4.7 \times 3.4$  cm

- 1. [x ma-na] dul-la gam-ri
- 2. [KI.LAL túg]mu-ut-ta-ti
- 3. [1 *ma-n*]*a* 17 GÍN KI.LAL
- 4. [1 TÚG.ÚR] 10 < TÚG>. NÍG.ÍB.LÁ.MEŠ
- 5.  $[\check{s}\acute{a}^{\rm d}]$ IM  $u^{\rm d}\check{\check{S}}a$ -la
- 6. [<sup>md</sup>A]G-EN-MU.MEŠ
- 7. [<sup>lú</sup>UŠ.BAR *ma*]-*hir*
- 8. fully lost
- 9. [M]U.<sup>72<sup>?</sup>1.[KAM KN]</sup>

10. LUGAL 「Eiki Rev.

The left part of text is completely damaged. L. 3. Cf. BM 50255 (= 27): 5.

[x mina(s), the completed work, [the weight of] the muttatu-headdress; [1 mina] 17 shekels, the weight of [1 sūnu-belts (and)] 10 sashes [for] Adad and Šala, was [recei]ved from [Na]bû-bēl-šumāti, [the weaver].

[Month x, n<sup>th</sup> day], <sup>[2nd?]</sup> ye]ar [of KN], king of Babylon.

#### 37. BM 51732 (82-3-23, 2766)

PLATE 13

 $5.2 \times 1.7 \text{ cm}$ 

- 1. [túg]lu-bar šá dUTU 2 túglu-bar ziq
- 2.  $[\check{s}\check{a}]^{\mathsf{r}^{\mathsf{d}}}Bu^{\mathsf{l}}$ -ne-ne 1 1/3 ma-na  $^{\mathsf{t}\check{\mathsf{u}}\mathsf{g}}[\mathsf{x}^{\mathsf{l}}]$ ....]
- 3. [....] [lu-bar x x x ] [....]

Rest lost

1'. [x x x]  $^{r}ta^{1}$ -kil-tú šá É  $^{d}$   $^{r}Bu^{1}$ -n[e-ne] 2'.  $^{r}$ x 5'  $^{r}$  ma-na $^{1}$  [x x x]  $^{d}$  UTU Rev.

3'. šá lu-bar [me-ṭu ù] lu-bar ku-lu-lu

4'. [x x] 「šá¬ sígta-kil-tú šá  ${}^{d}GA$ ŠAN Sip-par  ${}^{<\!ki>}$ L.e.

The lubāru-garment for Šamaš, the lubār ziq<qu> for Bunene, 40 shekels, <the weight of> [....]-garment [....] lubār [....]

[....] blue-purple wool for the temple of Bun[ene]; 5 minas [x x x] for Šamaš of the lubār [mēṭu and] lubār kulūlu-headbands [....] of blue-purple wool for the Queen of Sippar.

#### 38. BM 52699 (82-3-23, 3733)

PLATE 14

 $5.5 \times 2.7$  cm

- 1'. [KI.LAL TÚG]. HI.A TÚG. MÁй
- 2'. [TÚG].HI.A me-e SIG<sub>5</sub> 4 TÚG. [ÚR]. [MEŠ]
- 3'. [x x x]  $^{\mathrm{rd}_{\mathrm{I}}}$ UTU 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{\mathrm{d}}$ A-a
- 4'. [10 TÚG.NÍG].ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

Rev.

- 1'. [....] 10 TÚG.[x].[....]
- 2'. [....] *šá* <sup>d</sup>[....]

[....], the weight of the lub]āru (and) sibtu-garments, the fine? lubār mē damqigarment, 4 sūnu-belt[s ....] for Šamaš;

10 sashes for Aya; [10 sash]es for the Queen of Sippar [....] 10 [....] of the god[dess x].

#### 39. BM 49570 (82-3-23, 561)

 $4.4 \times 3.1$  cm

#### 10.3.Nbk 6

- 1. 2 ma-na <sup>5</sup> GÍN dul-lu
- 2. gam-[ru KI.LAL]
- 3. 10 [TÚG.NÍG.ÍB.LÁ.MEŠ]
- 4. 1<sup>en</sup> [ÚR x <sup>túg</sup>par-ši-gu<sup>meš</sup>] 5. 1<sup>en</sup> [lu-bar ku-lu-lu šá <sup>d</sup>]GAŠAN Sip-par<sup>ki</sup> 6. <sup>md</sup>AG-EN-[MU].MEŠ
- 7. <sup>lú</sup>UŠ.BAR 「GADA SUM<sup>na</sup> ]
- 8. ITI.SIG<sub>4</sub> U<sub>4</sub>.10.KAM

Rev.

- 9. MU.6.KAM <sup>md</sup>AG-NÍG.DU-ÙRU
- 10. LUGAL E<sup>ki</sup>

The tablet is heavily eroded.

Lines 3-5, cf. below BM 82586 (= 40): 1-6.

2 minas 5? shekels, the comple[ted] work, [the weight] of 10 [sashes], 1 sūnu-belt [(and) x paršīgu-headdresses], 1 [lubār kulūlu-headband for] the Queen of Sippar, Nabû-bēl-šumāti, the linen weaver?! has delivered. Month of Simanu, 10<sup>th</sup> day, 6<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

#### **40. BM 82586** (93-10-14, 38)

PLATE 14

 $3.8 \times 2.5$  cm

#### 26.11.Nbk 6

- 1. 59 GÍN SÍG.<ZA.GÍN>.KUR.RA
- 2. KI.LAL  $1^{en}$  lu-bar kul-lu-lu
- 3. 3  $^{\text{túg}}pa$ -<ar>- $\check{s}i$ - $\lceil gu \rceil$  $^{<\text{meš}>}$
- 4. 1 ma-na 1/3 GÍN KI.LAL
- 5.  $1^{en}$  ÚR u

Rev.

- 6. 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ
- 7. *šá* <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>
- 8. mdAG-EN-MU.MEŠ
- 9. it-ta-din ITI.ZÍZ
- 10. U<sub>4</sub>.26.KAM MU.6.KAM
- 11. md AG-NÍG.DU-ÙRU (without title)

59 shekels of blue-purple wool, the weight of 1 lubār kulūlu-headband (and) 3 *paršīgu*-headdresses;

1 mina 20 shekels, the weight of 1 sūnu-belt and 10 sashes for the Queen of Sippar Nabû-bēl-šumāti has delivered.

Month of Šabatu, 26<sup>th</sup> day, 6<sup>th</sup> year of Nebuchadnezzar.

#### **41. BM 79326** (89-4-26, 623)

PLATE 15

 $4.6 \times 3.2$  cm

#### 2.11.Nbk 10

- 1. 55 (sic ) dul-la gam-ru 2. KI.LAL 4 <sup>túg</sup>par-si-gu<sup>meš</sup>
- 3. 2 TÚG.SÍG.HÉ.ME.DA
- 4. 2 TÚG.SÍG.ZA.GÌN.<KUR>.RA
- 5. 3 mu-și-e šá ITI.ZÍZ
- 6. <sup>md</sup>AG-EN-MU.MEŠ
- 7. lúUŠ.BAR ma-hir L.e.
  - 8. ITI.ZÍZ U<sub>4</sub>.2.KAM
- 9. 「MU.10<sup>1</sup>.KAM Rev.
  - 10. dAG-NÍG.DU-ÙRU
  - 11. LUGAL TIN.TIR<sup>ki</sup>

The reading of the year is uncertain. One u is clear, what was recognised as a sign by Leichty; two additional slantwise written wedges might be only a crack.

55 (shekels?), the completed work, the weight of 4 paršīgu-headdresses, 2 cloths made of red wool, 2 cloths made of blue-purple wool, 3 <pān>-mūṣê-covers for the month of Šabaţu was received from Nabû-bēl-šumāti, the weaver. Month of Šabatu, 2<sup>nd</sup> day, 10<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

#### **42. BM 49333** (82-3-23, 324)

PLATE 15

 $4.3 \times 2.8$  cm

#### 26.11.Nbk [x+]10

- 1. 50 GÍN ta-kil-ti
- 2. KI.LAL TÚG.HI.A kul-lu-lu
- 3. 「3<sup>1</sup> TÚG.BAR.SI.MEŠ ina lìb-bi
- 4. 1<sup>en</sup> šá a-a-ri pa-ni
- 5. 1 ma-na 55 GÍN KI.LAL
- 6. {「KI.LAL<sup>1</sup>} 1<sup>en</sup> ÚR
- 7.  $\lceil 1^{en_1} \rceil$  [TÚG.HI.A me]  $\lceil SAG^1.DU$

Rev.

- 8. 10 TÚG.¹NÍG.ÍB¹.[LÁ.MEŠ] 9. šá <sup>d</sup>GAŠAN *Sip-par*<sup>[ki]</sup>
- 10. md AG-EN-MU.M[EŠ ma]-hir
- 11. ITI.ZÍZ U<sub>4</sub>.26.KAM [MU.x+]10.KAM
- 12. dAG-NÍG.DU-ÙRU LUGAL [TIN].TIR<sup>ki</sup>

For reconstruction of l. 7, cf. below l. 4.

50 shekels of blue-purple wool, the weight of the *lubār kulūlu*-headband (and) 3 paršīgu-headdresses, among them 1 with the front rosette;

1 mina 55 shekels, the weight of 1 sūnu-belt, 1 [lubāri mē] qaqqadi-headdress (and) 10 sashes for the Queen of Sippar, was [recei]ved from Nabû-bēl-šum[āti]. Month of Šabāṭu, 26<sup>th</sup> day, [x+]10<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

#### **43. BM 49621** (82-3-23, 612)

PLATE 16

 $5.1 \times 3.6$  cm

### 22[(+x)].11<sup>?</sup>.Nbk 12

- 1. 50 GÍN KI.LAL TÚG.HI.A ku-lu-lu
- 2. 3 TÚG.BAR.SI.MEŠ TÚG.SÍG.ZA.GÌN.<KUR>.RA
- 3. 2 ma-na KI.LAL 1 TÚG.ÚR
- 4. T[ÚG.HI.A me]-<sup>r</sup>e<sup>1</sup> SAG.DU
- 5. [10 TÚG.NÍG.ÍB].LÁ.MEŠ
- 6. *šá* <sup>d</sup>GAŠAN *Sip-par*<sup>ki</sup> 7. <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>UŠ.「BAR<sup>1</sup>
- 8. ma-hir ITI. ZÍZ U4.22+x. [KAM]
- 9. MU.12.KAM <sup>d</sup>AG-NÍG.D[U-ÙRU]
- 10. LUGAL TIN.TIR. [KI]

Rev. uninscribed

Lines 3–5 gives us the possibility to establish the weight of *lubar mē qaqqadi* for the Queen of Sippar: 2 minas minus 20 shekels (the weight of one  $s\bar{u}nu$ ) minus 70 shekels (the weight of 10 husannus for the Queen of Sippar) = 30 shekels. Probably only blue-purple wool is meant here.

50 shekels, the weight of the *lubār kulūlu*-headband (and) 3 *paršīgu*-headdresses of blue-purple wool;

2 minas, the weight of 1 *sūnu*-belt, the *lubār mē qaqqadi*-headdress (and) [10 sash]es for the Queen of Sippar, was received from Nabû-bēl-šumāti, the weaver.

Month of Šabatu<sup>?</sup>, 22<sup>nd</sup> +x day, 12<sup>th</sup> year of Nebuchad[nezzar], king of Babylon.

#### **44. BM 50786** (82-3-23, 1778)

 $4.2 \times 2.8 \text{ cm}$ 

- 1. [1/2] GÚ.UN 6 ma-na [SÍG.ḤI.A]
- 2. dul-lu <gam-ru> TÚG.SÍG.ḤI.A ù M[ÁŠ šá dUTU]
- 3. [TÚ]G.SÍG.ḤI.A ù¹ MÁŠ [dḤAR]
- 4. su-ni- $\lceil e \rceil$
- 5. <sup>[</sup>x<sup>1</sup> [....]

Rest lost

Rev. uninscribed

Although only a small fragment of tablet is preserved, a clear parallelism with other early  $dullu\ pe \hat{su}$  texts is striking. TÚG.SÍG.ḤI.A stand for TÚG.ḤI.A =  $lub\bar{a}ru$ .

[3]6 minas of [wool], the <completed> work of the *lubāru* and *s*[*ibtu*-garments for Šamaš], the *lubāru* and *sibtu*-garments for [Bunene], the *sūnu*-belts [of ....].

#### **45. BM 49304** (82-3-23, 295)

PLATE 16

 $4.1 \times 2.3$  cm

3.1.13 (Nbp)

- 1. 50 GÍN TÚG.BABBAR.BABBAR(sic!) dul-lu
- 2. gam-ru ina muh-hi
- 3. *lu-bu-uš-tu*<sub>4</sub>
- 4. šá ITI.BÁR

Edge 5. <sup>m</sup>Du-muq i-te-iq-<sup>[</sup>qu<sup>]</sup>

Rev. 6. ITI.BÁR U<sub>4</sub>.3.KAM

7. MU.13.KAM

The verb  $et\bar{e}qu$  appears in a few texts (see Index), where usually it describes a small part of a much greater amount mentioned before. The exact meaning in such a context can be established on the basis of BM 58641 (= 148) where after the *şibtu* of Gula we read 7 GÍN *a-tar*, while the description of an item for Adad is followed with the note 10 GÍN LAL-*ți* (*māţi*). It is obvious that in the first situation the scribe wished to note that the weight of the item is 7 shekels over the norm, while in the second it is below the norm. Because the verb  $et\bar{e}qu$ 

appear in a few texts in the same context as māţu, it has to have the same sense. In the discussed text and BM 49451 (see below) etēqu might describe the amount not delivered on time (according to the meaning suggested by CDA 84: "be late in payment"), or that the person mentioned in the text delivered less wool than expected to the *lubuštu* ceremony.

50 shekels of white *lubāru*-garment, the completed work for the *lubuštu* ceremony of the month of Nisannu, Dumuq has delayed?. Month of Nisannu, 3<sup>rd</sup> day, 13<sup>th</sup> year.

#### **46. BM 49541** (82-3-23, 532)

PLATE 16

 $4.7 \times 2.3$  cm

#### 13.12.11+[x]

- 1. 2 ma-na 5 GÍN SÍ[G.HI.A]
- 2. *dul-lu gam-ru* <sup>r</sup>x<sup>1</sup> (er.)
- 3. *šá* <sup>md</sup>AG-NUMUN-*ib-ni*
- 4. ina UGU lu-bu-uš-tú

Rev. 5. šá ITI.ŠE

6. *i-te-iq* 

- 7. ITI.ŠE U<sub>4</sub>.13.KAM
- 8. MU.11[+x<sup>?</sup>KAM]

2 minas 5 shekels of w[ool], the completed work, which Nabû-zēr-ibni has delayed? for the *lubuštu* ceremony of the month of Addaru. Month of Addaru, 13<sup>th</sup> day, [x+]11<sup>th</sup> year.

#### **47. BM 51262** (82-3-23, 2296)

PLATE 17

 $5.0 \times 3.0$  cm

#### 13.8.Nbk [x]

- 1. 1/3 ma-na 7 GÍN KI.LAL TÚG.HI.A
- 2. 3 <sup>túg</sup>par-si-gu<sup>meš</sup> SÍG.ZA.GÌN.<KUR>.RA
- 3. 1 ma-na 1/3 GÍN KI.LAL 1 $^{en}$  TÚG.ÚR 4. 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{\rm d}$ GAŠAN Sip-par  $^{\rm rki}$   $^{\rm l}$
- 5. [*l*]*u-bul-ti* ITI.APIN <sup>md</sup>AG-EN-MU.[MEŠ]
- 6. lúUŠ.BAR *it-ta-din* ITI.APIN U<sub>4</sub>.13.KAM
- 7. mdAG-NÍG.DU-ÙRU LUGAL Eki
- 8. [x m]a-na SÍG.ZA.GÌN.<br/>KUR>.RA šá [x] [....]
- 9.  $[x \ x] [x \ x \ x] [....]$

Rev.

- 1'. 4 TÚG [....]
- 2'. šá  $[x x x x x x]^{\lceil x \rceil}$
- 3'. [x x (x x) KI].LAL [....] 4'.  $\delta \dot{a}$  [x x]  $\lceil a \rceil$ -na [x x].L $\dot{A}$ ? [....]
- 5'.  $\Gamma T U G^{?}$  .HI [x x x  $^{d}B$ ]u-ne-ne
- 6'. 18 ma-na 10 GÍN KI].LAL TÚG.ḤI.'A'

7'. 「1<sup>en</sup> TÚG¹.ÚR [5] TÚG.NÍG.ÍB.LÁ.MEŠ [šá <sup>d</sup>IM] 8'. 「5¹ TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>Ša‐「la¹

L.h.e.

9'. [sá la ha]-[a]-[tu ina lìb-bi] [....]

10'.  $[(x)]^{\lceil 2/3^{?_1}}[x \ x]^{\lceil x^1}[...]$ 

11'. [x x x in]a Š $\hat{A}$ ? [....]

Rev. l. 6'. Instead of the total 18 minas 10 shekels we expect here 16 minas 10 shekels: 15 minas (the  $lub\bar{a}ru$  for Adad) + 20 shekels (1  $s\bar{u}nu$ -belt) + 50 shekels (10 husannu-sashes for Adad and Šala).

L. h. e. 10'.  $\lceil 2/3 \rceil$  or  $\lceil ru \rceil$ . The last partly preserved sign is similar to IM.

L. h. e. 11'. Or ah/ih.

27 shekels, the weight of the *lubāru*-garment, 3 *paršīgu*-headdresses of blue-purple wool;

1 mina 20 shekels, the weight of 1 *sūnu*-belt, 10 sashes for the Queen of Sippar (for) the *lubuštu* ceremony of the month Araḥsamna Nabû-bēl-šumāti, the weaver, has delivered. Month of Araḥsamna, 13<sup>th</sup> day, [n<sup>th</sup> year] of Nebuchadnezzar, king of Babylon.

[x] mina of blue-purple wool for [....]

4 [....]-garments [.... for] Bunene

18 minas 10 shekels, [the wei]ght of the *lubāru*-garment, 1 *sūnu*-belt, [5] sashes [for Adad] (and) 5 sashes for Šala which without (additional) sup[ply ....].

#### 47a. BM 58917 (82-7-14, 3326)

PLATE 17

 $4.2 \times 3.0 \text{ cm}$ 

1'. [....] <sup>[</sup>x<sup>1</sup> [....]

2'. [....] [x-qu]

3'. [x]<sup>r</sup>x x<sup>1</sup>10 *hu-ṣa-ni-e* 

4'. [šá] <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>

5'. [(TÚG).Ú]R<sup>?</sup> 5 hu-ṣa-ni-<sup>[</sup>e<sup>]</sup>

Edge

6'. [šá] <sup>d</sup>Gu-la

7'. [PN lú]UŠ.BAR it-ta-din

8'. [ITI].ŠU U<sub>4</sub>.5.KAM MU.1[+x.KAM]

9'. [x x x] 'LUGAL E'.KI

#### L. 2. Maybe $zi | q^{-1}qu^{-1}$

There is problem with qualification of the text to the particular group and its dating. The mention of Gula suggests that the text was written not earlier than 8<sup>th</sup> year of Nebuchadnezzar; however, the text is similar to early text, especially if in 1. 2' the reading *ziqqu* would be certain (but it is not certain). Note that the name of the weaver must have been written with one sign, like Balāṭu (TIN). Also the king's name must be short, or written with "short" sign, what not exclude even the name of Nabopolassar if written PA-A-PAP.

[....] 10 shases for Queen of Sippar,  $s\bar{u}nu^2$ -belt (and) 5 shases for Gula, [PN], the weaver has delivered.

[Month] of Du'ūzu, 5<sup>th</sup> day, year1+[x] of [KN], king of Babylon.

# II. The classical $dullu\ peṣ\hat{u}$ texts

#### GARMENTS FOR CYCLE A

#### 1. Garments for the Nisannu lubuštu ceremony

<b>48. CT 55, 810</b> = BM 56075		
	4.1.Nbn 2	
Rest lost Rev.	1. <i>mi-iḫ-ṣu šá</i> <sup>m</sup> <i>Ba-la-ṭu</i> [A <i>-šú šá</i> ] 2. <sup>md</sup> AG-EN-MU.MEŠ <i>a-na É-babbar-ra</i> 「SUM <sup>in?</sup> 」 3. ITI.BÁR U <sub>4</sub> .4.KAM MU.2.KAM <sup>d</sup> AG-I [LUGAL TIN.TIN <sup>ki</sup> ]	
	4. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup> UTU ina ŚÀ {「x¹ ½ 「x¹-ni si} 1 ma-na LAL	
	5. $\lceil 1 \rceil$ ma-na 13 GÍN KI.LAL 7 <sup>túg</sup> hu <sup>!</sup> - $\lceil sa$ -ni $\rceil$ -[e] šá <sup>d</sup> UTU	
	6. [1] $\lceil 1/3 \text{ ma-na KI} \rceil$ .LAL 4 TÚG.ÚR.MEŠ šá [ $^{\text{d}}$ UTU $u$ ] $^{\text{d}}A$ - $a$	
	7. $[x \times x^{j} x \times x \times x^{j}]$	
	1'. [20 $ma$ - $na$ KI.LAL 2] $^{t\acute{u}g}$ $sib$ - $tu_4$ $^m$ [ $^{e\acute{s}}$ $s\acute{a}$ $^d$ UTU] 2'. [1 $1/3$ $ma$ - $na$ KI.LA]L $^{t\acute{u}g}$ $lu$ - $ba$ - $ru$	
	3'. [2/3 ma-na KI.LAL <sup>túg</sup> ṣib]-tu <sub>4</sub> šá <sup>d</sup> Bu-ne-ne	
	4'. [1/3] <sup>r</sup> ma-na 5 <sup>!</sup> GÍN KI.LAL	
	5'. [5] TÚG.NÍG.ÍB.LA. <meš> šá <sup>d</sup>IM</meš>	
	6'. PAP 20 GÚ.UN 6 ½ ma-na 7'. dul-lu <gam-ru> it-tan-nu</gam-ru>	

L. 5. Note the atypical weight of 7 huṣannus (1 mina 13 shekels instead of 1 mina 10 shekels, i.e. 7 x 10 shekels).

L. 7. Usually the sūnus for Šamaš (and Aya) are followed by huṣannu for Aya, however, it is difficult to identify the preserved traces of signs with ideographic or syllabic writing of huşannu.

Note that the scribe omitted by mistake the sibtu for Šamaš (mentioned regularly in second position) and added it later in rev. 1'. The  $lub\bar{a}ru$  and the sibtu for Bunene are presented here separately, just as in a few other texts.

Note that the dividing line between rev. 4' and 5' is redundant. The reading in Rev. 4' is justified by the fact that 5 *huṣannus*, each weighing 5 shekels, belonged to Adad's vestment. Numeral looks like 4 but it is slightly damaged and it is possible that the scribe wrote in fact 5, as expected.

Rev. 3'. Note the lack of the *lubāru*-garment for Bunene here. The weight of the *şibtu* might be reconstructed as 40 shekels, see Zawadzki, *Garments of the Gods*, Vol. I, p. 92 and n. 215

Rev. 6'. The total of 20 talents is obviously wrong.

Woven garments which Balāṭu, son of Nabû-bēl-šumāti <sup>r</sup>has delivered<sup>1</sup> to the Ebabbar temple. Month of Nisannu, 4<sup>th</sup> day, 2<sup>nd</sup> year of Nabonidus, [king of Babylon].

20 minas, the weight of the *lubāru*-garment for Šamaš, (but) 1 mina is missing

-----

1 mina 13 shekels, the weight of 7 sashes for Šamaš

[1] mina 20 shekels, the weight of 4 sūnu-belts for [Šamaš and] Aya

------

.....

[20 minas, the weight of 2] sibtu-garmen[ts for Šamaš]

[1 mina 20 shekels, the weigh]t of the *lubāru*-garment <for Bunene>

-----

[40 shekels, the weight of the sib]tu-garment for Bunene

-----

[2]5 shekels, the weight of the [5] sash[es] for Adad

Total 20 talents 6 ½ minas, the <completed> work, which was delivered.

#### **49. CT 55. 853** = BM 57242

#### 4.1.Nbn 7

- 1'. [20 ma-n]a KI.LAL TÚG.ḤI.A šá<sup>! d</sup>UTU ina lìb-bi [½] 「ma<sup>?</sup>¹-[na SÍG.ZA.GÌN.KUR.RA]
- 2'. [20 *ma-n*]*a* KI.LAL <sup>[2]</sup> <sup>[</sup>TÚG<sup>1</sup>.[MÁ]Š *šá* <sup>d</sup>UTU 1 *ma-na* 1 <sup>[6]</sup> GÍN
- 3'. [LAL 2 ma]-na 「KI.LAL TÚG.ḤI.A¹ me-re?¹ [SAG].DU
- 4'. [1 *ma-n*]*a* 10 [GÍN KI.LAL] 7 TÚG.<NÍG>.ÍB.LÁ.MEŠ *šá* [<sup>d</sup>UTU]
- 5'. [1] <sup>[1/3]</sup> ma-na KI.LAL 4\* TÚG.Ú[R.MEŠ x x x].MEŠ
- 6'. [1] ma-na KI.LAL 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá dA-a
- 7'. 50 GÍN KI.LAL 10 「TÚG.<NÍG>.ÍB.LÁ.MEŠ šá  ${}^{\rm d}$ IM u  ${}^{\rm d}$ Ša-la
- 8'. 2/3 ma-<sup>r</sup>na<sup>1</sup> [KI.LAL] <sup>r</sup>2 TÚG.ÚR.MEŠ šá <sup>d</sup>Bu-ne-ne<sup>1</sup>

Edge 9'. [2] ma-[na KI.LAL] TÚG.HI.A u MÁŠ

šá <sup>d</sup>Bu-ne-ne

11'. ITI.BÁR U<sub>4</sub>.4.KAM MU.7.KAM Rev.

12'. md AG-I LUGAL Eki

The signs are preserved very badly.

[20 mina]s, the weight of the *lubāru*-garment for Šamaš with addition of ½ mina of blue-purple wool

[20 mina]s, the weight of 2! sibtu-garments for Šamaš of which 1 mina 16 shekels [is missing]

[2 min]as, the weight of the *lubār mē* [qaqq]adi-headdress

[1 mi]na 10 [shekels, the weight of] 7 sashes for [Šamaš]

[1] mina 20 shekels, the weight of 4  $s\bar{u}[nu]$ -belts, [...]

1 mina, the weight of 10 sashes for Aya

50 shekels, the weight of 10 sashes for Adad and Šala

40 shekels, [the weight of] 2 sūnu-belts for Bunene

[2] minas [the weight of] the *lubāru*-garment and the *şibtu*-garments for Bunene.

Month of Nisannu, 4<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

#### **50.** Nbn **320** = BM 92776; cf. BA 1, p. 519; NUVI 3, No. 41; Collated

#### 5.1.Nbn 9

- 1. dul-lu <BABBAR<sup>ú</sup>> šá ITI.BÁR šá ina ŠU<sup>ii lú</sup>UŠ.BAR.HI.A  $[SUM^{nu}]$
- 2. ITI.BÁR U<sub>4</sub>.5.KAM MU.9.KAM  $^{\mathrm{md}}$ AG-I LUGAL T[IN.TIR $^{\mathrm{ki}}$ ] \_\_\_\_\_
- 3. 20 ma-na KI.LAL TÚG.HI.A šá  $^{\rm d}$ [UTU]
- 4. 20 ma-na KI.LAL 2 <sup>túg</sup>ṣib-ba-tu<sub>4</sub> šá <sup>d</sup>[UTU]
- 5. 2 ma-na KI.LAL TÚG me SAG šá <sup>d</sup>[UTU]
- 6. 1 ma-na <10 GÍN> KI.LAL 7  $^{túg}hu$ -sa-ni-e sa  $^d$ [UTU] 7. 1 ma-na KI.LAL 10  $^{túg}hu$ -sa-ni-e sa  $^dA[-a]$
- 8. 2 ma-na KI.LAL TÚG.ḤI.A ù <sup>túg</sup>ṣib-tu₄ šá <sup>d</sup>ḤAR
- 9. 1 1/3<sup>!</sup> (T: 5/6) ma-na KI.LAL 4<sup>!</sup> (T:8) <sup>túg</sup>su-un-ni-e šá  $^{\rm d}$ UTU u  $^{\rm d}$ A-a
- 10. [50] GÍN KI.LAL 10 <sup>túg</sup>hu-sa-ni-e šá <sup>d</sup>IM! (T:UTU) u <sup>d</sup>Ša-<la>
- 11. [1/3] GÍN KI.LAL <sup>túg</sup>su-ú-nu šá <sup>d</sup>IM

12. ITI.BÁR U<sub>4</sub>.5.KAM MU.9.KAM Rev.

- 13. md AG-I LUGAL TIN.TIR ki
- 14. 2 *ma-na* 10 GÍN <sup>r</sup>*mi*<sup>?</sup>- *ih*<sup>?</sup><sup>1</sup>-*tu*<sub>4</sub>
- L. 6. The SAG here and in many other texts is an abbreviation for SAG.DU
- L. 9. Written in a reverse order: 8 KI.LAL.

<White> work for the month of Nisannu, which [was delivered by the hands] of the weavers. Month of Nisannu, 5<sup>th</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon. 20 minas, the weight of the *lubāru*-garment for [Šamaš] 20 minas, the weight of the *sibtu*-garments for [Šamaš] 2 minas, the weight the *lubār mē qaqqadi*-headdress for [Šamaš] 1 mina <10 shekels>, the weight of 7 sashes for [Šamaš] 1 mina, the weight of 10 sashes for A[ya] 2 minas, the weight of the *lubāru* and *sibtu*-garments for Bunene 1 mina 20' shekels, the weight of 4' sūnu-belts for Šamaš and Aya [50] shekels, the weight of 10 sashes for Adad and Ša<la> [20] shekels, the weight of the *sūnu*-belt for Adad. Month of Nisannu, 5<sup>th</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon. 2 minas 10 shekels [....]. **51. CT 55, 804** = BM 57806 [x].1.[Nbn] 11 1. dul-lu BABBAR[<sup>ú</sup> šá <sup>m</sup>]Ba-k[u-ú-a <sup>lú</sup>qal-la šá AG-ÙRU-A  $SUM^{na?}$ 2. ITI.BÁR [U<sub>4</sub>.x.KA]M MU.11.KAM [<sup>md</sup>AG-I LUGAL TIN.TIR<sup>ki</sup>] 3. 20 ma-na [KI.LAL TÚ]G. HI¹. A šá rd¹ [UTU ina lìb-bi] 4. ½ [ma-na SÍG.ZA.GÌN.KUR.RA] 5. 20 *ma-na* KI.LAL 2 *sib\*-tu*<sub>4</sub> [šá <sup>d</sup>UTU] \_\_\_\_\_ 6. 1 ma-na 10 GÍN KI.LAL 7 [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU] \_\_\_\_\_ 7. 2 ma-na KI.LAL TÚG.ḤI.A [me SAG.DU šá <sup>d</sup>UTU] 8. 1 ma-na 1/3 GÍN KI.LAL [4 TÚG.ÚR.MEŠ šá <sup>d</sup>UTU] ca. 4 lines are completely damaged. Rev. 5'. [x] [....] 6'. [5/6] [....]

White work, [which] Bak[ûa, the slave of Nabû-nāṣir-apli has delivered]. Month of Nisannu,  $[n^{th} da]y$ ,  $11^{th}$  year [of Nabonidus, king of Babylon].

20 minas, [the weight of the  $lu]b\bar{a}ru$ -garment for [Šamaš with addition] of ½ [mina of blue-purple wool]

-----

20 minas, the weight of 2 *şibtu*-garments for [Šamaš] ------1 mina 10 shekels, the weight of 7 [sashes for Šamaš] ------2 minas the weight of the *lubār* [*mē qaqqadi*-headdress for Šamaš] -----1 mina 20 shekels, the weight of [4 sūnu-belts for Šamaš]. Rest lost Rev. 6' ma present in the copy of Pinches does not exist more. **52.** Nbn **826** = BM 60184; cf. NUVI 3, No.79  $8.0 \times 5.6$  cm 4.1.Nbn 15 1. dul-lu BABBAR $^{\acute{u}}$  šá  $^{\mathrm{md}}$ AG-na-sir-A  $^{\mathrm{l\acute{u}}}$ UŠ.BAR 2. id-din-nu ITI. $B\acute{A}R$  U $_4$ .4.KAM MU.15.KAM  $^d$ AG-I LUGAL  $E^{ki}$ \_\_\_\_\_ 3. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA \_\_\_\_\_ 4. 20 <sup>r</sup>ma-na<sup>1</sup> [KI.LAL 2] MÁŠ.MEŠ šá <sup>d</sup>UTU \_\_\_\_\_ 5. 2 ma-na KI.LAL TÚG.HI.A me-e SAG to šá dUTU ------6. 1 1/3 ma-na KI.LAL 4 <TÚG>.ÚR.MEŠ šá <sup>d</sup>UTU u <sup>d</sup>A-a \_\_\_\_\_ 7. [1 ma-na 10 GÍ]N KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU \_\_\_\_\_\_ 8. [1 ma-na KI.LAL 10] TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a \_\_\_\_\_ 9. [2 ma-na KI.LAL TÚG.HI.A] ù şib-tu<sub>4</sub> šá <sup>d</sup>HAR 10. [ina lìb-bi] <sup>[6]</sup> GÍN SÍG.ZA.GÌN.KUR.RA \_\_\_\_\_ 11. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> 12. <sup>[2/3]</sup> GÍN KI.LÁL 2 su-ú-nu šá <sup>d</sup>IM u <sup>d</sup>Ša-la 13. [x+]1 ma-na 10 GÍN ana dul-lu ina IGI <sup>m</sup>Ba-ku-ú-a

White work, which Nabû-nāṣir-apli, the weaver has delivered. Month of Nisannu,  $4^{th}$  day,  $15^{th}$  year of Nabonidus, king of Babylon.

<sup>20</sup> minas, the weight of the  $lub\bar{a}ru$ -garment for Šamaš with addition of ½ mina of blue-purple wool

\_\_\_\_\_

20 minas, [the weight of 2] *şibtu*-garments for Šamaš

2 minas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš

1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš and Aya

[1 mina 10 shek]els, the weight of 7 sashes for Šamaš

-----

[1 mina, the weight of 10] sashes for Aya

\_\_\_\_\_

[2 minas, the weight of *lubāru*] and *ṣibtu*-garments for Bunene [with addition of] 6 shekels of blue-purple wool

1 mina, the weight of 10 sashes for the Queen of Sippar] 40 shekels, the weight of 2 *sūnu*-belts for Adad and Šala

[x] + 1 mina 10 shekels for the work at disposal of Bakûa.

#### **53. BM 68163** (82-9-18, 8151)

 $4.8 \times 4.7 \text{ cm}$ 

#### 5.1.Nbn [x]

- 1. dul-lu BABBAR<sup>ú</sup> [šá lu-bu-uš-tu<sub>4</sub> šá PN]
- 2. lúUŠ.BAR *a-n*[*a É-babbar-ra a-na*]
- 3. U<sub>4</sub>.7.KAM ITI.BÁR [SUM<sup>in</sup>]
- 4. ITI.BÁR U<sub>4</sub>.5.KAM M[U.x.KAM]
- 5. md AG-I LUGAL E.[KI]

\_\_\_\_\_

- 6. [20] *ma-na* KI.LAL TÚ[G.ḤI.A *šá* <sup>d</sup>UTU]
- 7. [ina lìb]-bi ½ ma-[na SÍG.ZA.GÌN.<KUR>.RA]
- 8. [20 ma]-na KI.[LAL 2  $^{\text{túg}}$   $\circ$ ib-tu<sub>4</sub>  $\circ$ á  $^{\text{d}}$ UTU]
- 9. [2 ma]-na [KI.LAL TÚG.ḤI.A u <sup>túg</sup>ṣib-tu₄ šá <sup>d</sup>ḤAR]

Rev. Beginning lost

1'. [....]  $^{\Gamma}UD^{?}\check{s}\check{a}^{?}x^{1}$  [....]

Rest of Rev. uninscribed

White work [for the *lubuštu* ceremony, which PN, the weaver has delivered to Ebabbar for] the 7<sup>th</sup> day of the month Nisannu. Month of Nisannu, 5<sup>th</sup> day [n<sup>th</sup> ye]ar of Nabonidus, king of Babylon.

.....

<sup>[20]</sup> minas, the weight of  $lu[b\bar{a}ru$ -garment for Šamaš with addition of] ½ mi[na of blue-purple wool]

<sup>[20</sup> mi]nas, the we[ight of 2 sibtu-garments for Šamaš]

<sup>[2</sup> mi]nas, [the weight of lubāru and sibtu-garments for Bunene, ....].

#### **54. BM 61498** (82-9-18, 1472)

PLATE 18

 $8.6 \times 6.3$  cm

#### 5.1.Cam 1 (538 B.C.)

- 1. dul-lu BABBAR $^{\acute{u}}$  šá lu-bu-uš-tu4 šá U4.7.K[AM]
- 2. šá ITI.BÁR MU.1.KAM <sup>m</sup>Kam-bu-zi-ja LUGAL E[<sup>ki</sup> šá]
- 3. <sup>md</sup>UTU-MU-MU *id-din-nu* ITI.BÁR U<sub>4</sub>.5.KAM
- 4. 20 ma-na KI.LAL TÚG.UD.ḤI.A šá <sup>d</sup>UTU
- 5. 20 ma-na KI.LAL 2 <sup>túg</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>UTU
- 6. 2 [ma]-na KI.LAL TÚG.UD. [HI.A] [me-e] [šá] SIG5
- 7. [1 1/3] *ma-na* KI.LAL 4 「TÚG.ÚR」.MEŠ
- 8. [1 ma] -na 10 GÍN KI.LAL [7 TÚG.NÍG].ÍB.LÁ.[MEŠ]

Edge

\_

Rev.

- 10. 2 ma-na KI.LAL TÚG.UD.ḤI.A u rtúg sib-tu41
- 11. šá <sup>d</sup>Bu-<sup>r</sup>ne-ne<sup>¬</sup>
- 12. 1/3 GÍN KI.LAL TÚG.ÚR šá <sup>d</sup>ḤAR

šá <sup>d</sup>UTU

- 13. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ .<MEŠ> šá <sup>d</sup>IM
- 14. u <sup>d</sup>Ša-la
- 15. 1/3 GÍN KI.LAL TÚG.ÚR šá  $^{\mathsf{r}^{\mathsf{d}^{\mathsf{l}}}}[\mathsf{G}\textit{u-la}]$
- 16. 1 ma-na dul-lu  $\lceil x \rceil$  [....].

White work for the *lubuštu* ceremony for the 7<sup>th</sup> day of the month Nisannu, 1<sup>st</sup> year of Cambyses, king of Babylon, which Šamaš-šum-iddin has delivered. Month of Nisannu, 5<sup>th</sup> day.

-----

20 minas, the weight of the *lubāru*-garment for Šamaš

20 minas, the weight of 2 sibtu-garments for Šamaš

2 minas, the weight of the *lubār mē damqi*-headdress

- [1] mina [20 shekels, the weight of 4 sūnu-belts
- [1] mina 10 shekels, the weight of [7 s]ashes for Šamaš
- 2 minas, the weight of the *lubāru* and *sibtu*-garments for Bunene
- 20 shekels, the weight of (one) sūnu-belt for Bunene
- 50 shekels, the weight of 10 sashes for Adad and Šala
- 20 shekels, the weight of the *sūnu*-belt for G[ula]
- 1 mina, the work [....].

#### **55. CT 55, 802** = BM 57972

#### 3.1.Cyr 3

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-t[u<sub>4</sub>]
- 2. *šá* ITI.BÁR <sup>md</sup>AG-PAP-A <sup>lú</sup>UŠ.BAR
- 3. id-din-nu ITI.BÁR U<sub>4</sub>.3.KAM
- 4. MU.3.KAM <sup>m</sup>Ku-raš LUGAL E<sup>ki</sup> LUGAL KUR.KUR

-----

- 5. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU
- 6. ina lìb-bi 1/2 ma-na SÍG.ZA.GÌN.KUR.RA
- 7. [20 *m*]*a-na* KI.LAL 2 <sup>túg</sup>ṣ*ib-t*[*u*<sub>4</sub>]
- 8. *šá* <sup>d</sup>UTU
- 9. [2 m]a-na KI.[LAL TÚG.HI.A me SAG.DU šá <sup>d</sup>UTU]
- 10. [1 1/3 *ma*]-*na* K[I<sup>?</sup>.LAL 4 TÚG.ÚR.MEŠ *šá* <sup>d</sup>UTU]
- 11. [1 ma-na 10] G[ÍN KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]

#### Rev. uninscribed

L. 2. The reading UŠ.BAR was established already by Bongenaar, *Ebabbar*, p. 337.

Ll. 10–11. The reconstruction of these lines is based on the order known from many parallels.

White work for the *lubuštu* ceremony for the month of Nisannu, which Nabû-nāṣirapli, the weaver has delivered. Month of Nisannu, 3<sup>rd</sup> day, 3<sup>rd</sup> year of Cyrus, king of Babylon, king of Lands.

-----

20 minas, the weight of the  $lub\bar{a}ru$ -garment for Šamaš with addition of ½ mina of blue-purple wool

[20 mi]nas, the weight of 2 *sibtu*-garments for Šamaš

[2 mi]nas, the wei[ght of the *lubār mē qaqqadi*-headdress for Šamaš]

[1 mi]na [20 shekels], the we[ight of 4 sūnu-belts for Šamaš]

[1 mina 10 shek]els, [the weight of 7 sashes for Šamaš].

# **56. Cyr 186** = BM 75808; cf. KB 4, 272; NUVI 3, No. 115; Giovinazzo 1981, No. 7 Collated

4.1.Cyr 5

- 1. dul'-lu' BABBAR $^{\acute{u}}$  šá lu-bu-uš-tu4 šá U4.7.KAM šá ITI.BÁR
- 2. MU.5.KAM <sup>m</sup>Ku- $ra\check{s}$  LUGAL E<sup> $k\dot{i}$ </sup> LUGAL KUR.KUR <sup>m</sup>Ba-ku- $\acute{u}$ -a
- 3.  $^{\text{l\'u}}qal$ -la  $\check{s}\acute{a}$   $^{\text{md}}$ AG-PAP-A  $^{\text{l\'u}}$ UŠ.BAR i-din-nu ITI.BÁR U $_4$ .4.KAM

4. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA

- 5. 20\* ma-na KI.LAL 2 TÚG.MÁŠ\*.MEŠ šá <sup>d</sup>UTU
- 6. 2 ma-na KI.LAL TÚG.HI.A SAG.DU šá <sup>d</sup>UTU
- 7. 1 ma-na 10 GÍN KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
- 8. 1\* ma-na 1/3\* GÍN KI.LAL 4 TÚG.ÚR.MEŠ šá <sup>d</sup>UTU
- 9. [1 *ma-na* KI.LAL 10] TÚG\*.NÍG\*.ÍB\*.LÁ.MEŠ šá <sup>d</sup>A-a
- 10. [50 GÍN KI.LAL 10] TÚG\*.NÍG\*.ÍB.LÁ.MEŠ šá <sup>d</sup>IM u <sup>d</sup>Ša-la
- 11. [1/3 *ma-na* KI.LAL TÚG.ÚR *šá*] <sup>d</sup>IM\* *u* <sup>d</sup>*Ša*\*-[*la*]

L. 11. The reconstruction 1/3 ma-na is supported by comparison with other texts, cf. for example Cyr 201: 16.

White work for the *lubuštu* ceremony for the 7<sup>th</sup> day of Nisannu, 5<sup>th</sup> year of Cyrus, king of Babylon, king of Lands, (which) Bakûa, the slave of Nabû-nāṣir-apli, the weaver has delivered. Month of Nisannu, 4<sup>th</sup> day.

\_\_\_\_\_

20 minas, the weight of the *lubāru*-garment for Šamaš with addition of ½ mina of blue-purple wool

20 minas, the weight of 2 *şibtu* garments for Šamaš

2 minas, the weight of the *lubār* <*mē*> *qaqqadi*-headdress for Šamaš

1 mina 10 shekels, the weight of 7 sashes for Šamaš

1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš

[1 mina, the weight of 10] sashes for Aya

[50 shekels, the weight of 10] sashes for Adad and Šala

[20 shekels, the weight of (one) sūnu-belt for] Adad and Šala.

#### **57. BM 54818+BM 59729** (82-5-22, 1147 82-7-14, 4139)

 $6.3 \times 4.9$  cm

#### [x].1.Cyr 6

- 1. mi-ih-tu<sub>4</sub> lu-<sup>r</sup>bu<sup>1</sup>-uš-tu<sub>4</sub> šá ITI.BÁR U<sub>4</sub>.7.KAM
- 2. MU.6.KAM <sup>m</sup>Ku-ra-áš LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
- 3. <sup>1</sup>20<sup>1</sup> ma-na KI.LAL TÚG.UD.A šá <sup>d</sup>UTU
- 4. [10+] 10 ma-na KI.LAL 2 si-ba-tu<sub>4</sub>  $\check{s}\check{a}^{d}$ UTU
- 5. [2 m]a-na KI.[LAL T]ÚG.UD.A me SAG šá <sup>d</sup>UTU
- 6. [1 ma-na 10 GÍ]N 「KI".[LAL<sup>1</sup> 7 hu-ṣa-an-ni šá <sup>d</sup>UTU
- 7. [1 1/3 ma-na KI].LAL 4 TÚG.ÚŘ.MEŠ šá <sup>d</sup>UTU
- 8. [1 ma-na KI].LAL 10 hu-sa-an-ni šá <sup>d</sup>A-a
- 9. [x ma-na KI.LA]L 2 [.... šá] <sup>d</sup>A-a
- Rev. 10. [2 ma-na] KI.LAL TÚG.[ḤI.A u <sup>túg</sup>sib-tu4 sá] <sup>d</sup>ḤAR
  - 11. [1/3 ma-na] KI.LAL [TÚG.ÚR šá] <sup>d</sup>IM

Rev. uninscribed

L. 1. *mihtu* is obviously a mistake for *mihşu*.

There is a quite substantial distance between the name of garment and the name of god or goddess.

L. 9. I cannot suggest the reconstruction of the lines because it has no parallels in other texts.

Woven garments for the *lubuštu* ceremony for the 7<sup>th</sup> day of Nisannu, 6<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

20 minas, the weight of the *lubāru*-garment for Šamaš

[20] minas, the weight of 2 *şibtu*-garments for Šamaš

[2 mi]nas, the weig[ht of the *l*]ubār mē qaqqadi-headdress

[1 mina 10 shek]els, the weight of 7 sashes for Šamaš

[1 mina 20 shekels], the weight of 4 sūnu-belts for Šamaš

1 [mina, the weight of 10] sashes for Aya [x mina(s), the weig]ht of 2 [...] for Aya [2 minas], the weight of the  $lub\bar{a}[ru]$  and the sibtu-garments] for Bunene [20 shekels], the weight of [(one) sūnu-belt for] Adad.

**58.** Cyr **289** = BM 60342; cf. Salonen, NUVI 3, No. 127; Giovinazzo 1981, No. 16. Collated  $7.5 \times 5.8$  cm

#### 4.1.Cyr 8

- 1. [du]l-lu BABBAR $^{\acute{u}}$  šá lu-bu-uš-tu4 šá ITI.BÁR

2. ITI.BÁR U <sub>4</sub> . <sup>1</sup> 4 <sup>1</sup> .KAM MU.8.KAM <sup>m</sup> <i>Ku-raš</i> LUGAL NUN LUGAL KUR.KUR
3. 20 ma-na KI.LAL 「TÚG*1.ḤI.A šá <sup>d</sup> UTU
4. 20 ma-na KI.LAL [2] $^{\text{túg}}$ $\hat{\text{sib-tu}}_4^1$ $\hat{\text{sá}}^{\text{d}}$ UTU
5. 2 ma-na KI.LAL [TÚG].ḤI.A me SAG šá <sup>d</sup> UTU
6. 1 ma-na 1/3* 「GÍN*1 [KI.L]AL* 4* TÚG.ÚR.MEŠ šá <sup>d</sup> UTU
7. 1 ma-na <sup>†</sup> 10 <sup>†</sup> * G[ÍN KI.LA]L* 7 TÚG. <níg>.ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup>UTU</níg>
8. [1] <i>ma-na</i> [KI.LAL] 10 TÚG <sup>!</sup> (T: GÍN).NÍG <sup>!</sup> (T: TÚG).ÍB.LÁ.MEŠ šá <sup>d</sup> A-a
9. [1 1/3 ma-na KI.LAL TÚG].ḤI.A šá <sup>d</sup> Bu-ne-ne
10. [2/3 ma-na K]I.LAL [túg]şib-tu4 šá dḤAR
11. [50] 'GÍN' KI.LAL 10 TÚG <sup>'</sup> (T: GÍN).NÍG <sup>'</sup> (T: TÚG).ÍB.LÁ.MEŠ

Edge

12. [1/3 GÍN KI.LA]L<sup>!</sup> TÚG.ÚR\* šá <sup>d</sup>IM u <sup>d</sup>Ša-la Rev.

White work for the lubuštu ceremony for the month of Nisannu. Month Nisannu,  $4^{\text{th}}\,\text{day},\,8^{\text{th}}\,\text{year}$  of Cyrus, king of Babylon, king of Lands.

-----20 minas, the weight of the *lubāru*-garment for Šamaš \_\_\_\_\_

20 minas, the weight of [2] *ṣibtu*-garments for Šamaš

2 minas	s, the weight of the [lu]bār mē qaqqadi-headdress for Šamaš	
1 mina	20 shekels, [the wei]ght of 4 <i>sūnu</i> -belts for Šamaš	
1 mina	<sup>7</sup> 10 <sup>1</sup> shek[els, the weig]ht of 7 sashes for Šamaš	
[1] min	a, [the weight] of 10 sashes for Aya	
[1 mina	20 shekels the weight of the $lub]\bar{a}ru$ for Bunene	
[40 she]	kels, the wei]ght of the <i>şibtu</i> -garment for Bunene	
[50] she	ekels, the weight of 10 sashes	
[20 shel	kels, the wei]ght of (one) <i>sūnu</i> -belt for Adad and Šala.	
<b>59. BM</b> 4.6 × 5.	6 <b>68413</b> (82-9-18, 8411) 0 cm	PLATE 18
	<x>.1.Cam 6</x>	
	1. [dul-lu BABBAR] <sup>ú</sup> šá lu-bu-uš-tu <sub>4</sub> 2. [šá U <sub>4</sub> .7.KA]M šá ITI.BÁR MU.6. <kam> 3. [<sup>m</sup>Kam-bu-z]i-ja LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR</kam>	
	4. [20 ma-na] KI.LAL TÚG.ḤI.A šá <sup>d</sup> UTU 5. [20 ma-na K]I.LAL 2 ṣib-ba-tu <sub>4</sub> šá <sup>d</sup> UTU	
	6. [2 ma-na KI.L]AL TÚG.UD.A me SIG $_5$ šá $^{ m d}$ UTU	
Rev.	7. [1 <i>ma-na</i> 10 GÍN KI.LAL <sup>[7]</sup> TÚG.NÍG <sup>!</sup> .(T:MURUB <sub>4</sub> ).ÍB.LÁ.[MEŠ] 8. [šá] <sup>d</sup> UTU 9. [1 <i>ma-na</i> 1/3 GÍN KI.LAL] 4 TÚG.ÚR.[MEŠ] 10. [šá <sup>d</sup> ]UTU	
	11. [1 <i>ma-na</i> KI.LAL] 10 TÚG.NÍG.ÍB.LÁ.[MEŠ] 12. <i>šá</i> <sup>d</sup> A-a	
	13. [2 <i>ma-na</i> KI.LAL] TÚG.UD.A ù <sup>túg</sup> ṣib-tu <sub>4</sub> 14. <i>šá</i> <sup>d</sup> ḤAR	
L. e.	15. [1 <i>ma-na</i> KI.LA]L 3 TÚG.ÚR.MEŠ 16. [šá <sup>d</sup> GAŠAN <i>Sip-par</i> <sup>ki</sup> ] <sup>d</sup> ḤAR ù <sup>d</sup> IM 17. [50 GÍN] KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 18. [šá <sup>d</sup> I]M u <sup>d</sup> Ša-la	

Ll. 15–16 Cf. BM 66247 (= 144): 11 and BM 59405 (= 146): 9'-10'.

[White work] for the *lubuštu* ceremony [for the 7<sup>th</sup> day] of Nisannu, 6<sup>th</sup> year of [Camby]ses, king of Babylon, king of Lands.

[20 minas], the weight of the *lubāru*-garment for Šamaš

[20 minas, the welight of 2 sibtu-garments for Šamaš \_\_\_\_\_

[2 minas, the weigh]t of the *lubār mē damqi*-headdress for Šamaš

-----

[1 mina 10 shekel, the weight] of 7 sashes for Šamaš [1 mina 20 shekels, the weight] of <sup>7</sup>4<sup>7</sup> sūnu-belts for Šamaš

\_\_\_\_\_

[1 mina, the weight] of 10 sashes [for] Aya

\_\_\_\_\_

[2 minas the weight] of the *lubāru* and *şibtu*-garments for Bunene

[1 mina, the weigh]t of 3 sūnu-belts [for Queen of Sippar], Bunene and Adad [50 shekels], the weight of 10 sashes for Adad and Šala.

#### **60. BM 62244** (82-9-18, 2213)

Small fragment, signs are particularly beautiful

30.12.[KN]

- 1. [dul-lu] BABBAR<sup>ú</sup> šá <sup>md</sup>AG-na-ş[ir-A šá ITI.BÁR U<sub>4</sub>.7.KAM]
- 2. [SU]M<sup>nu</sup> ITI.ŠE U<sub>4</sub>.30.KAM 「MU¹.[x.KAM KN]

\_\_\_\_\_

- 3.  $[20 \, ma\text{-}n]a \, \text{KI.LAL}^{\text{túg}} lu\text{-}bar\text{-}ri \, [\check{s}\acute{a}^{\text{d}} \text{UTU}]$
- 4. [20 *ma-n*]*a* KI.LAL 2 *și-ba-*[*tu*<sub>4</sub> *šá* <sup>d</sup>UTU]
- 5. [1 ma-na 10] GÍN KI.LAL 7 TÚG.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
- 6. [2 ma-na] x (er.) KI.LAL TÚG.HI.A [me SAG.(DU) šá <sup>d</sup>UTU]
- 7.  $[1 \ 1/3 \ ma-n]a \ KI.LAL \ 4 < TÚG > \Gamma UR^1. [MEŠ Šá <math>^d$ UTU  $u^d$ A-a]

Rest lost

Rev. completely eroded

The day date (30 Addaru) and the number of sibtus make certain that it is a list of garments for the month of Nisannu.

White [work], which Nabû-n[āṣir-apli has delive]red [for the 7<sup>th</sup> day of Nisannu]. Month of Addaru, 30<sup>th</sup> day, n<sup>th</sup> year [....]

[20 mina]s, the weight of the *lubāru*-garment [for Šamaš]

[20 mina[s, the weight of 2 sibt[u-garments for Šamaš]

[1 mina 10] shekels, the weight of 7 s[ashes for Šamaš]

[2 minas], the weight of the *lubār* [mē qaqqadi-headdress for Šamaš]

[1 mina 20 shekels], the weight of 4 sūnu-belts [for Šamaš and Aya].

#### **61. BM 79745** (89-10-14, 294)

PLATE 19

 $4.8 \times 7.1$  cm

#### 7.1.Dar 10

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub>
- 2. šá  $^{\rm d}$ UTU u DINGIR.MEŠ UD.KIB.NUN $^{\rm ki}$
- 3. šá ITI.BÁR U<sub>4</sub>.7.KAM MU.10.K[AM]
- 4. <sup>m</sup>Da-a-ru-eš-šú šá <sup>md</sup>[UTU]-[MU-MU]
- 5. lúUŠ.BAR id-rdin-nu

\_\_\_\_\_

6. 20 ma-na KI.LAL TÚG.UD.A šá <sup>d</sup>UTU

\_\_\_\_\_

7. 2 ma-na KI.LAL TÚG.UD. A me SIG šá $^{\rm d}$ UTU \_\_\_\_\_

8. <sup>1</sup>1 ma-na 1/3 GÍN KI.LAL <4> TÚG.ÚR.MEŠ šá <sup>d</sup>UTU

\_\_\_\_\_\_

9. 2 ma-na KI.LAL TÚG.UD.A < u TÚG.MÁŠ> šá  $^{\rm d}Bu$ -ne-ne

10. 12 GÍN dul-lu LAL Rev.

L. 9. 2 minas is the weight of the *lubāru* and *ṣibtu* for Bunene, but the *ṣibtu* is missing here. Note that the text does not include the *sibtus* for Šamaš and Bunene and garments for other gods and goddesses.

The line of the reverse is written a little below the center of the tablet.

White work for the *lubuštu* ceremony for Šamaš and the gods of Sippar for the 7<sup>th</sup> day of Nisannu, 10<sup>th</sup> year of Darius, which Šamaš-[šum-iddin], the weaver has delivered.

20 minas, the weight of the *lubāru*-garment for Šamaš

2 minas, the weight of the *lubār mē damqi*-headdress for Šamaš

1 mina 20 shekels, the weight of <4> sūnu-belts for Šamaš

2 minas, the weight of the *lubāru* <and *sibtu*-garments> for Bunene 12 shekels of work is missing.

#### **62. BM 72584** (82-9-18, 12590)

 $4.5 \times 5.2$  cm

#### 3.1.[KN] 7

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-[tu<sub>4</sub> šá ITI.BÁR  $U_4.7.KAM [SUM^{na}]$
- 2. ITI.BÁR U<sub>4</sub>.3.KAM MU.7.[KAM KN LUGAL *Bābili* (LUGAL KUR.KUR)]

- 3. 20 ma-na KI.LAL TÚG.[HI.A šá <sup>d</sup>UTU]
- 4. 2 ma-na KI. LAL TÚG.HI<sup>1</sup>. [A me SAG.(DU) šá <sup>d</sup>UTU]
- 5. 1 ma-na 10 GÍN 「KI.LAL<sup>1</sup> [7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU] \_\_\_\_\_
- 6. [1] <sup>1</sup>/3<sup>1</sup> ma-<sup>1</sup>na KI.LAL 4 TÚG<sup>1</sup>. [ÚR šá <sup>d</sup>UTU u <sup>d</sup>A-a]

\_\_\_\_\_

- 7. 1 ma-<sup>r</sup>na KI.LAL<sup>1</sup> [10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]
- 8. <sup>[2]</sup> ma-<sup>[</sup>na KI.LAL [TÚG.HI.A TÚG.MÁŠ šá <sup>d</sup>HAR]
- 9. [5/6 *m*]*a-na* 「KI<sup>!</sup>].[LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ]

10.  $\check{s}\acute{a}^{\rm d}$ IM  $< u^{\rm d}\check{S}\acute{a}$ -la>Edge

11. 1/3 GÍN KI.LAL [TÚG.ÚR šá <sup>d</sup>IM]

Rev. uninscribed

12. 20 ma-na KI.LAL L.h.e.

13. 2 <sup>túg</sup>sib-tu<sub>4</sub> šá <sup>d</sup>UTU

The surface of the tablet is eroded, but the signs are still readable. The scribe evidently forget about *sibtus* for Šamaš, which should be placed after 1. 3, and added it on the left hand edge.

White work for the  $lubu\check{s}t[u]$  ceremony for the  $7^{th}$  day [was delivered]. Month of Nisannu, 3<sup>rd</sup> day, 7<sup>th</sup> year [of KN, king of Babylon (king of Lands)].

20 minas, the weight of the *lub*[āru-garment for Šamaš]

2 minas, the weight of the *lubār* [*mē qaqqadi*-headdress for Šamaš]

1 mina 10 shekels, the weight of [7 sashes for Šamaš]

-----

[1] [1/3] mina, the weight of 4 [sūnu-belts for Šamaš and Aya]

1 mina, the weight of [10 sashes for Aya]

2 minas, the weight of the [lubāru and sibtu-garments for Bunene]

[50 she]kels, the wei[ght of 10 sashes for Adad <and Šala>

20 shekels, the weight of [(one) sūnu-belt for Adad]

20 minas, the weight of 2 sibtu-garments for Šamaš.

#### 2. Garments for the Ayaru *lubuštu* ceremony

#### **63. BM 62543** (82-9-18, 2512) PLATE 19 $5.5 \times 5.4$ cm 8.2.Nbk 22 1. mi-ih-su1 lu-bu- $u\check{s}$ -tu4 $<<math>\check{s}\acute{a}$ > $^{d}UTU$ 2. šá {ina} ITI. $^{\Gamma}$ GU<sub>4</sub> $^{\Gamma}$ U<sub>4</sub>. 10.KAM MU.22.KAM 3. $^{\text{md}}$ AG-NÍG.DU-ÙRU šá $^{\text{md}}$ AG-EN-MU.MEŠ 4. a-na É-babbar-ra id-din-nu \_\_\_\_\_ 5. 20 ma-na KI.LAL TÚG.HI.A šá <sup>d</sup>UTU 6. 20 ma-na KI.LAL 2 TÚG.MÁŠ.MEŠ 7. 3 ½ ma-na KI.LAL 4 TÚG.ÚR.MEŠ 8. 1<br/>en TÚG.ḤI.A SIG5 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá $^{\rm d}$ UTU \_\_\_\_\_ 9. 3 ma-na SÍG.HÉ.ME.[DA KI].LAL ni-b[i-hu] 10. <sup>1</sup>/<sub>2</sub> ma-na KI.LAL¹ TÚG.ḤI.[A me]-<sup>1</sup>ti¹ TÚG.Ḥ[I.A ku-lu-lu] [šá] <sup>d</sup>UTU Rest lost Beginning of Rev. lost 1'. 「1<sup>?</sup>」2-「ta<sup>?</sup> a-na<sup>? d</sup>IM<sup>?</sup>」 2'. 1/3 7 GÍN KI.「LAL」 <sup>túg</sup>pa-ši-ir TÚG.ḤI.A ku-lu-[lu] šá <sup>d</sup>rŠa-la<sup>1</sup> 3'. 4'. PAP 17 *ma-na* <sup>[9]</sup> [GÍN x x] -----5'. 20 ma-na KI.LAL TÚG.ḤI.A TÚG.「MÁй 6'. 10 TÚG. 「NÍG¹¹.ÍB.LÁ.MEŠ 17 GÍN TÚG.ḤI.A ku-lu-「lu¹

Despite the use of the word  $mih\bar{s}u$  and the presence of  $n\bar{e}beh\bar{u}$  (1. 9), which belongs to the garments listed in the  $mih\bar{s}u$  texts, all other apparels appears in the dullu  $pes\hat{u}$  texts.

L. 7 The numeral 3 ½ is clearly written, however, 4 ½ minas would be expected here because the total weight of 4 *sūnus*, 1 *lubūr* SIG<sub>5</sub> (equivalent to *lubūr mē qaqqadi*) and 7 *huṣannus* for Šamaš gives 4 minas 30 shekels, i.e. 4 x 20 shekels + 2 minas + 7 x 10 shekels.

Rev. 2'. For pašīru, see No. 82: 22 No. 179): 8.

šá <sup>d</sup>IM u <sup>d</sup>Ša-la

9'. U<sub>4</sub>.8.KAM MU.22.KAM

Rev. 5'-7' The total weight of *lubāru*, *şibtu* and 10 *ḫuṣannu*s for Adad and Šala is 21 minas. Probably the scribe omitted by mistake the weight of their *ḫuṣannu*s.

Rev. 8'. For  $^{1\acute{u}}$ TÚG.BABBAR =  $a\check{s}l\bar{a}ku$ , see Waerzeggers 2006, p. 93f.

8'. a-na lúTÚG.BABBAR na-din ITI.GU<sub>4</sub>

Woven garments for the *lubuštu* ceremony of Šamaš for the 10<sup>th</sup> day of the month Ayaru, the 22<sup>nd</sup> year of Nebuchadnezzar, which Nabû-bēl-šumāte has delivered to the Ebabbar.

20 minas, the weight of the *lubāru*-garment for Šamaš 20 minas, the weight of 2 *şibtu*-garments 3 minas 30 shekels, the weight of 4 sūnu-belts, 1 lubār damqi-headdress and 7 sashes for Šamaš 3 minas of red wool, the weight of *nēbehu*-belt. 30 shekels, the weight of the *lubār* [*mē*]*tu* and the *lubār* [*kulūlu*]-headbands for Šamaš. [.... for Adad?; 27 shekels, the weight of the paširu (of) the kulūlu-headband for Šala; total 17 minas <sup>[9]</sup> [shekels ....] 20 minas, the weight of the *lubāru* (and) *şibtu*-garments (and) 10 sashes; 17 shekels (the weight of) the lubār kulūlu-headband for Adad and Šala, which was given the ašlāku. Month of Ayaru, 8th day, 22<sup>nd</sup> year. **64. BM 65732** (82-9-18, 5722) PLATE 20  $6.1 \times 7.0$  cm 6.2.Nbk [x] 1. [10]+10 ½ ma-na dul-<sup>[</sup>lu BA[BBAR<sup>ú</sup> šá TÚG.ḤI.A] 2. šá <sup>d</sup>UTU ina lìb-bi ½ 「ma¹-na SÍG.「ZA¹.[GÌN.KUR.RA] -----3. 20 ma-na KI.LAL 2 <sup>túg</sup>ṣib-ba-tu<sub>4</sub> [šá <sup>d</sup>UTU] 4. [x+] 1 ma-na KI.LAL 4 TÚG.ÚR.MEŠ 1<sup>en</sup> T[ÚG me-(e) SAG.(DU)] 5. [7 TÚ]G.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU ù 10 [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a] \_\_\_\_\_ 6. [1 ma-na] 15 GÍN KI.LAL TÚG.ḤI.A šá r<sup>d</sup>¹[ḤAR] ------7. [x *ma-na*] <sup>[4]</sup>8 GÍN KI.LAL 10 TÚG.NÍG.[ÍB.LÁ.MEŠ] 8. [x x].SI u [11][ $e^{n}$ ?] TÚG.Ú[R $^{?}$  x] [šá  $^{d}$ 1[DN] 9. [x *m*]*a-na* KI.LAL TÚG.ḤI.A 10 TÚG.「NÍG<sup>?</sup>¹.[x x x<sup>¹</sup> 10. [x x x x.L]Á.MEŠ  $1^{et}$  TÚG. [BAR]. SI  $1^{en}$  [....] 11. [5 TÚG.NÍG.ÍB.L]Á.MEŠ šá <sup>d</sup>Ša-la ina lìb-[bi ....] 12. [x x] <sup>r</sup>x x<sup>1</sup> SÍG.ZA.GÌN.<KUR>.RA [(....)] \_\_\_\_\_\_ 13.  $[x(x)] 5 \lceil ma \rceil - [na] \lceil KI \rceil . LAL^{túg} sib - t[u_4]$ 14. [5 TÚG.NÍG].ÍB.LÁ.MEŠ 1<sup>en</sup> TÚG.Ú[R<sup>?</sup>] Rev.

15. [šá <sup>d</sup>Gu-l]a šá É-ul-lu
Free space for two lines
One line erased
16. [x x x x] 5 TÚG.NÍG.ÍB.LÁ.MEŠ SÍ[G² ....]
17. [šá <sup>d</sup>Bu-n]e-ne <sup>md</sup>AG-EN-M[U.MEŠ]
18. [x x (x) <sup>r</sup>šá la ha-a-tu i-n[am-din]
Free space for 1–2 lines
19. ITI.GU<sub>4</sub> U<sub>4</sub>.8.KAM MU.[x.KAM]
20. <sup>d</sup>AG-NÍG.DU-ÙRU LUGAL TI[N.TIR<sup>ki</sup>]

- L1. 4–5. If the reconstruction of ll. 4–5 is correct, the numeral at the very beginning of l. 4 must be [4]  $\frac{1}{2}$  because this is the total amount of 4  $s\bar{u}nus$  (1 mina 20 shekels) + 1 lubar  $m\bar{e}$  qaqqadi (2 minas) +7 husannus for Samaš (1 minas 10 shekels) + 10 husannus for Aya (1 mina) but the preserved wedge is clearly 1.
- L. 6. I fill the gap at the end of line with the name Bunene, because according to the sequence in other texts his garments are expected here. Note, however, that in the preserved text his *şibtu* is not mentioned, and I cannot suggest any place when we could expect it.
- L. 7. The position of preserved decimal in l. 7 make possible to reconstruct the numeral as 48 or even 58, but not 38. 10 *huṣannus* mentioned in l. 10 makes sure that in ll. 7–8 the garments of goddess are enumerated there. Because in the following lines the text concern garments for Šala and Gula, here one can expect the garments for the Queen of Sippar or Anunītu.
- L. 9. The numeral 10 is written over one vertical wedge. The partly preserved sign (ÍB or ÚR) is followed by traces of three signs written on right edge.
- L. 13. The numeral 5 is to high because 1 *şibtu*+ 5 *ḫuṣannus* + 1 *sūnu* gives only 2 minas 35 shekels (2 minas + 15 shekels + 20 shekels).
- L. 16ff. It is possible to fill the gap at the end of the line 16 with S[ÍG.HÉ.ME.DA], however, till now such colour of *huṣannu*-sashes for Bunene is not known. For similar context, see below, texts of Nabû-bēl-šumāti.
- L. 18. They are different possibilities of filling the gap at the beginning of the line:  $[^{16}U\check{S}.BAR]$ , or:  $[a-na\ \acute{E}\ DINGIR]$ .
- 20  $\frac{1}{2}$  minas of white work for the [the  $lub\bar{a}ru$ -garment] for Šamaš, including  $\frac{1}{2}$  mina of blue-purple wool.

20 minas, the weight of 2 *şibtu*-garments for [Šamaš]

[x] + 1 mina, the weight of 4 *sūnu*-belts, 1 *lubār* [*mē qaqqaadi*-headdress], [7] sashes for Šamaš and 10 [sashes for Aya]

[1 mina] 15 shekels, the weight of the *lubāru*-garment [for Bunene]

[x mina(s) 48 shekels, the weight of 10 sash[es], [1² paršī]gu-headdress² and 1 *sūnu*-belt for [DN]

[x mi]nas, the weight of the *lubāru*-garment, 10 sa[shes², [....], 1 paršīgu-headdress, 1 [...., 5 sash]es for Šala, with addition of [x shekels

of blue-pu]rple wool.

[x] + 5 minas, the weight of the *şibtu*-garment, [5 sash]es, 1  $s\bar{u}[nu\text{-belt}]$ for Gula] of the Eulla temple.

[....], 5 sashes [.... for Bun]ene, [...] will be deliv[ered] by Nabû-bēl-šum[āti] without (earlier) supply. Month of Ayaru, 6<sup>th</sup> day, [n<sup>th</sup>] year of Nebuchadnezzar, king of Ba[bylon].

#### **65. CT 55, 807** = BM 58069

#### [x].2.Nbn [x]

- 1. dul-lu BABBAR<sup>ú</sup> šá <sup>md</sup>U+GUR-[MU <sup>lú</sup>....]
- 2. *id-din-nu* ITI.GU<sub>4</sub> U<sub>4</sub>.[x.KAM MU.x.KAM]
- 3. md AG-IM.TUKU LUGAL T[IN.TIRki

4. 20 ma-na KI.LAL! TÚG.ḤI.[A šá <sup>d</sup>UTU] \_\_\_\_\_

5. at present nothing is preserved.

Rest lost

White work, which Nergal-[iddin, the ....] has delivered. Month of Ayaru, [nth day, n<sup>th</sup> year] of Nabonidus, king of Ba[bylon].

\_\_\_\_\_

20 minas, the weight of the *lubār*[*u*-garment for Šamaš].

#### **66. BM 62108** (82-9-18, 2077)

PLATE 20

 $5.2 \times 5.7$  cm

#### 1.[x].Cyr 2

- 1. [dul-lu pi-su-ú] šá lu-bul-tu<sub>4</sub> SUM<sup>na</sup>
- 2. [ITI.x U] 4.1.KAM MU.2.KAM <sup>m</sup>Kur-ra-áš LUGAL [KUR.KUR]

3. [20 ma-na KI.LAL TÚG.ḤI]. 「A¹ šá <sup>d</sup>UTU

- 4. [20 ma-na KI.LAL 2 tú]<sup>g</sup>ṣib-ba-tu<sub>4</sub> šá dUTU 1 ½ ma-na e-te-<sup>r</sup>iq<sup>1</sup>
- 5. [2 ma-na KI.LAL TÚG].HI.A me SAG  $š\acute{a}$   $^d$ UTU
- 6. [1 1/3 ma-na K]I.LAL 4 TÚG.ÚR.MEŠ ½ ma-[na] [e]-te-iq
- 7. [1 ma-na 10 GÍN K]I.LAL 7 TÚG.<NÍG>.ÍB. LÁ.MEŠ šá¹ <sup>d</sup>UTU 4 GÍN *e-te-iq*

- 8. [1 ma-na KI.LAL 10 T]ÚG.<NÍG>ÍB.LÁ.MEŠ šá <sup>d</sup>A-a
- 9. [2 ma-na KI.LAL TÚG.Ḥ]I.A <sup>túg</sup>ṣib-tu₄ šá <sup>d</sup>Bu-<sup>r</sup>ne-ne<sup>1</sup>

[x] GÍN e-te-<sup>r</sup>iq<sup>1</sup>

11. [....] <sup>r</sup>x<sup>1</sup> ma-<sup>r</sup>na<sup>?</sup> KI<sup>!</sup>.LAL<sup>!</sup> 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ Rev. *šá* <sup>d</sup>GAŠAN *S[ip-par*<sup>ki</sup>]

- 12.  $[x G]ÍN e-te^{-r}iq^{-r}$
- 13. [15 GÍN KI.LA]L<sup>!</sup> [T: *zib*] 5 TÚG.<NÍG>.ÍB.LÁ.MEŠ [x] (er.)
- 14. [šá <sup>d</sup>Gu]-la 10 GÍN *e-te-iq*

-----

- 15. [x *ma-na* KI.LAL] TÚG.MÁŠ *šá* <sup>d</sup>IM
- 16. [ina ŠÀ<sup>?</sup> x] <sup>r</sup>ma<sup>¬</sup>-na ina IGI <sup>md</sup>ḤAR-DÙ
- 17. [1/3 ma-na KI.LAL TÚG.Ú]R šá <sup>d</sup>IM
- 18. [50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ].MEŠ šá <sup>d</sup>IM u <sup>d</sup>[Ša-la]
- 19. [1/3 ma-na KI.LAL TÚG.ÚR šá] <sup>d</sup>ḤAR
- L. 11. The scribe made serious mistakes which he only partly corrected.
- L. 13. The MEŠ is followed by one vertical and three horizontal strokes. Very similar is the fragmentary preserved sign before numeral 5 in l. 14, emended here to LAL!
- L. 16. Bunene-ibni, presumably the  $p\bar{u}$ , see also below BM 61192: 2 (= 628 b) and Additions and Corrections.

[White work], which was given for the *lubuštu* ceremony. [N<sup>th</sup> month],  $2^{nd}$  day,  $2^{nd}$  year of Cyrus, king of <sup>T</sup>Lands<sup>T</sup>.

\_\_\_\_\_\_

[20 minas, the weight of the *lubāru*]-garment for Šamaš

[20 minas, the weight of 2] *sibtu*-garments for Šamaš; 1 ½ minas is missing

[2 minas, the weight of the *l*]ubār mē qaqqadi-headdress for Šamaš

[1 mina 20 shekels, the wei]ght of 4 sūnu-belts (for) Šamaš; ½ mina is missing

[1 mina 10 shekels, the weight of 7 sashes for Šamaš; <sup>7</sup>4 shekels are missing

[1 mina, the weight of 10] sashes for Aya

- [2 minas, the weight of the  $lub\bar{a}$ ] ru (and) sibtu-garments for Bunene; [x] shekels are missing.
- [1] mina, the weight of 10 sashes for the Queen of [Sippar]; [x sh]ekels are missing. [15 shekels, the weight of 5 sashes [for Gu]la]; 10 shekels are missing.

-----


- [x minas, the weight] of the *şibtu*-garment for Adad; [out of it? x mina(s) are at disposal of Bunene-ibni
- [20 shekels, the weight of the  $s\bar{u}$ ]nu-belt for Adad
- [50 shekels, the weight of 10 sash]es for Adad and [Šala]
- [20 shekels, the weight of the *sūnu*-belt] for Bunene.


#### **67. CT 44,** 73 = BM 78227, cf. NUVI 3, No. 249 Collated

7.2.Cam 1

- 1. dul-luBABBAR $^{\acute{u}}$  šá $lu\text{-}bu\text{-}u\check{s}\text{-}tu_4$  šá ITI.GU $_4$  šá  $^{\text{md}}$ AG-PAP-A šá  $^{\text{md}}$ UTU-MU-MU
- 2. e-piš-šá-nu id-din-nu ITI.GU $_4$  U $_4$ .7.KAM MU.1.KAM  $^m$ Kam-bu-zi-ja LUGAL E<sup>ki</sup> LUGAL KUR.KUR

- *J* 





15 shekels<sup>1</sup>, the weight of 5 sashes for Gula 20 shekels, the weight of the *sūnu*-belt for Gula

50 shekels, the weight of 10 sashes for Adad 20 shekels, the weight of the sūnu-belt for Adad 50 shekels, the weight of the paršīgu-headdress for Adad ½ mina, the weight of the *lubār mētu* and the *lubār kulūlu*-headbands for Šamaš; 2 shekels of the work are missing 4 minas, the weight of the patinnu-belts for Šamaš and Bunene 11 minas, the weight of the robe for Aya 1 mina 35 shekels, the weight of the 2 paršīgu-headdresses, the lubār kulūluheadbands, the (lubār) erru-headbands for Aya · ----10 shekels of blue-purple *timītu*-yarn for weaving? of the robe for Aya \_\_\_\_\_ 1 mina, the weight of 2 blue-purple paršīgu-headdresses, the lubār kulūlu (and) (lubār) erru-headbands for the Queen of Sippar; 6 shekels are missing ½ mina, the weight of blue-purple *lubār mēṭu* and *lubār kulūlu*-headbands for Anunītu; 1 shekels is missing 20 shekels, the weight of blue-purple *lubār mēţu* and (*lubār*) *kulūlu*-headbands for Adad 10 shekels, the weight of a red sash; 5 shekels of red wool for the lubār qabliloincloth for Anunītu 52 shekels, the weight of red (*lubār*) erru-headband, the paršīgu-headdress and (lubār) kulūlu-headband for Šala! 22 shekels, the weight of red (lubār) erru-headdress, (lubār) kulūlu-headband (and) *paršīgu*-headdress for Gula

15 minas, the weight of the *lubāru*-garment for Adad \_\_\_\_\_\_

(Except for) 1 mina, 9 shekels, the missing work, (all other) Šamaš-šum-iddin has delivered.

**68. BM 67160** (82-9-18, 7156)

PLATE 21

 $6.9 \times 4.4 \text{ cm}$ 

8.2.Cam 5

- 1.  $dul^{-1}lu^{-1} < BABBAR^{u} > r \check{s} \acute{a} lu^{-1} bu u\check{s} tu_{4} \check{s} \acute{a}$
- 2. ITI.GU $_4$  U $_4$ .10.KAM šá  $^{\rm md}$ UTU-MU-MU
- 3. id-[din]-nu 'ITI.GU<sub>4</sub>'U<sub>4</sub>.8.KAM MU.5.<KAM>

```
4. <sup>m</sup>[Kam]-<sup>r</sup>bu-zi<sup>1</sup>-iá LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
              5. 10 ma-[na] SÍG.HÉ.ME.DA KI.LAL ku-si-tu<sub>4</sub>
                                             [\check{s}\check{a}]^{\mathrm{d}}A-[a] [x GÍN SÍG].HÉ.ME.DA
              7. ri-hi-<sup>[</sup>ti<sup>]</sup> [....]
              8. 10 G[ÍN ....]
Rev.
              1'. [2] m[a-na ....]
              2'. 1 ma-<sup>r</sup>na<sup>1</sup> [KI.LAL] <sup>r</sup>10<sup>1</sup> TÚG.<sup>r</sup>NÍG.ÍB.LÁ.MEŠ<sup>1</sup>
              4'. 15 ma-na <sup>túg</sup>lu-ba-ru šá <sup>d</sup>IM
              5'. ina lìb-bi 1 ma-na ina IGI <sup>md</sup>UTU-MU-MU
              6'. ½ ma-na 7 GÍN SÍ[G.HÉ].ME.DA KI.LAL
              7'. e-ri lu-ba-[ri ù TÚ]G.BAR.SI šá
                                     dŠa-[la]
              9'. 17 GÍN SÍG.HÉ.ME.DA KI.LAL e-ri
             10'. <sup>túg</sup>lu-ba-<ri> u TÚG.BAR.SI šá
L. e.
                        <sup>d</sup>Gu-la
             11'.
             12'. u 5 TÚG.NÍG.ÍB.LÁ.MEŠ
L. h.e.
             13'. šá <sup>d</sup>ME.ME
```

Rev. 1. The line might be reconstructed: 2 *ma-na* [KI.LAL *lubār mē qaqqadi*] L. h. e. 12'. Either *u* 5 or 15. I decided to read *u* 5 TÚG.NÍG.ÍB.LÁ.MEŠ because exactly 5 *huṣannus* belonged to the vestment of Gula. The alternative, less probable reading is: 15 <GÍN KI.LAL 5> TÚG.NÍG.ÍB.LÁ.MEŠ.

<White> work for the *lubuštu* ceremony for the 10<sup>th</sup> Ayaru, which Šamaš-šumiddin has delivered. Month of Ayaru, 8<sup>th</sup> day, 5<sup>th</sup> year of [Cam]byses, king of Babylon, king of Lands.

-----

10 minas of red wool, the weight of the robe for Aya; [x she]kels of red wool, the remaining [....] 10 shekels [....] 2 mi[nas ....], 1 mina, [the weight of] 10 sashes for Aya

-----

- 15 minas, <the weight of> the  $lub\bar{a}ru$ -garment for Adad, including 1 minas, which is at disposal of Šamaš-šum-iddin.
- 37 shekels of red wool, the  $< lub\bar{a}r > erru$ -headband, the  $lub\bar{a}[ru$ -garment and  $pa]r\check{s}\bar{s}gu$ -headdress for Šala
- 17 shekels of red wool, the weight of the  $lub\bar{a} < ru >$ -garment,  $< lub\bar{a}r >$  erruheadband and  $par \check{s} \bar{t} g u$ -headdress for Gula and 5 sashes for Gula.

#### **69. Cam 413** = BM 60546; cf. NUVI 3, No.164 Collated

10.2.Cam [x]

- 1. [dul-lu BABB]AR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub> šá U<sub>4</sub>.10.KAM šá ITI.GU<sub>4</sub>
- 2. [MU.x.KAM  $^{\rm m}$ ] Kam-bu-zi-ja LUGAL TIN.TIR $^{\rm ki}$  LUGAL KUR.KUR

	3. [ <i>šá</i> <sup>m</sup> ] <sup>d</sup> UTU-MU-MU <sup>lú</sup> TÚG*.BABBAR* SUM <sup>na</sup> ITI.GU <sub>4</sub> U <sub>4</sub> .[x.KAM]
	4. [20 ma]-na KI.LAL <túg>.UD.ḤI.A šá <sup>d</sup>UTU 5. [20 ma-na] KI.LAL 2 ṣib*-ba*-tu<sub>4</sub> šá <sup>d</sup>UTU 1 ma-na 6. [10 GÍN KI.LAL 7 TÚG].NÍG.ÍB.LÁ.MEŠ 2 ma-na KI.LAL <túg>UD.ḤI.[A me SAG.(DU) šá <sup>d</sup>UTU] 7. [1 ma-na 1/3 GÍN] KI.LAL 4 TÚG.ÚR.MEŠ šá <sup>d</sup>UTU</túg></túg>
	8. [1 <i>ma-n</i> ] <i>a</i> <sup>!</sup> KI.LAL 10 TÚG.NÍG <sup>!</sup> .ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup> <i>A-a</i>
	9. [2 <i>ma</i> ]- <sup>r</sup> <i>na</i> <sup>1*</sup> KI.LAL <túg>.UD.ḤI.A ù ṣib-tu<sub>4</sub> šá <sup>d</sup>ḤA[R]</túg>
Edge	10. [1] <i>ma-na</i> KI.LAL 10 TÚG.NÍG <sup>!</sup> .ÍB.LÁ.MEŠ <i>šá</i> 11. <sup>d</sup> GAŠAN <i>Sip-par</i> <sup>ki</sup>
Rev.	12. <sup>[1/3]*</sup> ma-na KI.LAL BAR.SI šá <sup>d</sup> GAŠAN Sip-par <sup>ki</sup>
	13. 1 ma-na KI.LAL 10 TÚG.NÍG*.ÍB.LÁ.MEŠ šá <sup>d</sup> A-nu-ni-tu <sub>4</sub> 14. <sup>[</sup> 1*]6 ma-na KI.LAL şib-tu <sub>4</sub> šá <sup>d</sup> A-nu-ni-tu <sub>4</sub>
	15. 「50」 GÍN KI.LAL 10 TÚG.NÍG*.ÍB.LÁ.MEŠ šá <sup>d</sup> IM <sup>d</sup> 「Ša¬-l[a] 16. [1/3] <i>ma-na</i> KI.LAL TÚG.BAR.SI šá <sup>d</sup> IM
	17. [1] ma-na KI.LAL 3 TÚG.ÚR.MEŠ šá <sup>d</sup> GAŠAN Sip-par <sup>ki</sup> 18.
	19. [5 <i>m</i> ] <i>a-na</i> KI.LAL <i>șib-tu</i> <sub>4</sub> <i>šá</i> <sup>d</sup> IM

- The text is in fact better preserved than Strassmaier's copy suggests.

  L. 3. The reading TUG.BABBAR was already established by Bongenaar, *Ebabbar*, p. 347.
- L. 8 and 10. There is TÚG.LÁ.ÍB.LÁ.MEŠ (as in Strassmaier's copy), however in l. 13 and 15 the writing is correct.
- L. 12. At the beginning only one vertical wedge is preserved.
- L. 14. The numeral 10 is still visible.
- L. 15. Now preserved much worse than in the time of Strassmaier (only the numeral 20 is

There is a ruling line between 1. 16 and 17 (missing in Strassmaier's copy).

White work for the *lubuštu* ceremony for the 10<sup>th</sup> Ayaru, [n<sup>th</sup> year] of Cambyses, king of Babylon, king of Lands, which Šamaš-šum-iddin, the *ašlāku* has delivered. Month of Ayaru, [nth day].

[20 min]as, the weight of the *lubāru* for Šamaš

[20 minas], the weight of 2 *şibtu*-garments for Šamaš 1 mina [10 shekels, the weight of 7] sashes 2 minas, the weight of the *lubā*[r mē qaqqadi-headdress for Šamaš] [1 mina 20 shekels], the weight of 4 sūnu-belts for Šamaš [1 min]a, the weight of 10 sashes for Aya [2 min]as, the weight of the *lubāru* and *şibtu*-garments for Bune[ne] \_\_\_\_\_ [1] mina, the weight of 10 sashes for the Queen of Sippar \_\_\_\_\_ 20 shekels, the weight of (one) paršīgu-headdress for the Queen of Sippar 1 mina, the weight of 10 sashes for Anunītu 16 minas, the weight of the *şibtu*-garment for Anunītu 50 shekels, the weight of 10 sashes for Adad and Šala [20] shekels, the weight of (one) paršīgu-headdress for Adad -----[1] mina, the weight of 3 sūnu-belts for the Queen of Sippar, Adad and Gula \_\_\_\_\_

[5 mi]nas, the weight of the sibtu-garment for Adad.

#### **70. BM 73276** (82-9-18, 13287)

 $5.9 \times 3.3$  cm

#### 8.2.Dar 8

- 1. [mi-ih-s]u šá-hu-ú šá lu-bu-uš-tu4
- 2. [a-na IT]I.GU<sub>4</sub> MU.8.KAM <sup>m</sup>Da-ri-e-[muš]
- 3. [LUGAL E<sup>ki</sup>] LUGAL KUR.KUR

-----

4. [20 ma-na KI.LAL] TÚG.UD.A šá [<sup>d</sup>UTU]

#### Rest lost

Bottom of Rev. uninscribed

[Wov]en  $\delta ah\hat{u}$ -garments for the  $lubu\delta tu$  ceremony [for the month of Ayaru,  $8^{th}$  year of Dar[ius, king of Babylon], king of Lands.

[20 minas, the weight of] the *lubāru*-garment for [Šamaš].

#### **71. CT 55, 801** = BM 57449 Collated

#### 11.2.(Dar) 15

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub> šá <sup>rd</sup>¹UTU
- 2.  $\dot{u}$  DINGIR.MEŠ UD.KIB.NUN<sup>ki</sup> šá ITI.GU<sub>4</sub> U<sub>4</sub>.11.KAM

- 3. MU.15.KAM <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR *id-din*
- 4. 20 ½ ma-na KI.LAL TÚG.UD.A 「šá dUTU」 5. 2 ma-na KI.LAL TÚG.UD.A me [SAG.DU] šá <sup>d</sup>UTU
- 6. 1 ma-na 1/3 GÍN KI.LAL 4 TÚG.[ÚR.MEŠ] šá <sup>d</sup>UTU
- 7. 1 ma-na 10 GÍN KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
- \_\_\_\_\_\_
- 8. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a \_\_\_\_\_\_
- 9. [2] ma-na KI.LAL TÚG.UD.A ù şib-tu4 šá <sup>d</sup>B[u\*-ne-n]e\*

10. 20 ma-na KI.LAL 2 sib- $tu_4$   $saaa^d$ UTU Rev.

- 11. md AMAR.UTU-ri-man<sup>an</sup>-ni it-ta-din ½ ma-na LAL
- 12. ½ ma-na 1 GÍN 4-tú SÍG!.ZA.GÌN.KUR.RA KI.LAL TÚG.UD.A me-tu
- 13. ù TÚG.UD.A ku-lu-lu šá <sup>d</sup>UTU 1 GÍN 4-tú it-qu
- 14. 1 ma-na KI.LAL TÚG.BAR.SI šá <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>
- 15. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.<MEŠ> šá <sup>d</sup>GAŠAN  $UD.KIB.NUN^{ki}\\$
- 16. 1/3 GÍN KI.LAL TÚG.ÚR *šá* <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>

Two arguments speak for the dating of the text to the 15th year of Darius: (a) Šamaš-šumiddin does not appear with the title of išparu before the time of Cambyses; (b) the text mentions Marduk-rēmanni, who can be identified as a member of the Ṣāḥit-ginê family, see now C. Waerzeggers, Marduk-rēmanni, p. 225.

L. 2. Day date is probably a mistake for 10<sup>th</sup> of Ayaru, the day of the *lubuštu*-ceremony.

L. 14. The amount of 1 mina for the paršīgu of the Queen of Sippar appears also in BM 67093+ (= 86), in BM 75552 (= 91): 10 and maybe in BM 62059 (= 84): 11. Because the weight of the paršīgu is 20 shekels, 1 mina was probably destined for 3 paršīguheaddresses. The lack of plural in these texts is not important, because such a situation is noted in the list of other garments, e.g. 2 sibtu-garments is regularly written without plural. That one paršīgu for the Queen of Sippar weighed less than one mina is clear from the 76590+ (=163), rev. I 12'-13' and rev. II 21'-22' where one mina is the total weight of one lubār kulūlu, 2 paršīgus and one lubār erru. Cf. also Cyr 191 (= 172): 9-10 (1 mina is the weight of 2 paršīgus and 1 lubār kulūlu); the same probably in BM 65979 (= 179): 18'-19'. Cf. also CT 55, 808 (= 181): 11'-12' (one lubār kulūlu and  $\langle 2^2 \rangle$  paršīgus. Two paršīgus for the Queen of Sippar appear in BM 73134 (= 203): 13' and in BM 65484+ (= 210): 18.

White work for the *lubuštu* ceremony for Šamaš and the gods of Sippar, which on the 10<sup>!th</sup>Ayaru, 15<sup>th</sup> year, Šamaš-šum-iddin has delivered.

20 ½ minas, the weight of the *lubāru*-garment for Šamaš

2 minas, the weight of the *lubār* [*mē qaqqadi*-headdress] for Šamaš

1 mina 20 shekels, the weight of 4 *sūnu*-belts for Šamaš

1 mina 10 shekels, the weight of 7 sashes for Šamaš

\_\_\_\_\_ 1 mina, the weight of 10 sashes for Aya

[2] minas, the weight of the *lubāru*-garment and *ṣibtu*-garments for B[une]ne -----20 minas, the weight of 2 sibtu-garments for Šamaš, (which) Marduk-rēmanni has delivered, (but) ½ mina is missing 31 ¼ shekels of the blue-purple wool, the weight of the *lubār mēţu* and lubār kulūlu-headbands for Šamaš (but) 1 ¼ shekels (of wool) is missing 1 mina, the weight of the *paršīgu*-headdress for the Queen of Sippar 1 mina, the weight of 10 sashes for the Queen of Sippar 20 shekels, the weight of the *sūnu*-belt the Queen of Sippar. **72. BM 73018** (82-9-18, 13027) PLATE 22  $6.2 \times 7.0 \text{ cm}$ 2.2.[Dar<sup>?</sup>] 4 1. dul-lu BABBAR<sup>ú</sup> 「šá lu-bu¬-uš-tu<sub>4</sub> šá [PN] 2. id-din-nu ITI.GU $_4$  U $_4$ .2.KAM MU.4.KAM  $^m$  $_\Gamma Da$  $^1$ -[ri-mu- $\check{s}\check{u}$ LUGAL E<sup>ki</sup> LUGAL KUR.KUR] \_\_\_\_\_\_ 3. 20 ma-na KI.LAL TÚG.HI.A [šá <sup>d</sup>UTU] \_\_\_\_\_\_ 4. 20 ma-na KI.LAL 2 <sup>túg</sup>ṣi-ba-tu<sub>4</sub> [šá <sup>d</sup>UTU] 5. 2 ma-na KI.LAL TÚG.ḤI.A me SAG. [x] (er.) [šá dUTU] -----6. [1 m]a-na 1/3 GÍN KI.LAL 4 TÚG.ÚR.MEŠ [šá <sup>d</sup>UTU] \_\_\_\_\_ 7. [1 *m*]*a-na* <10 GÍN> KI.LAL <sup>[7]</sup> [TÚG.NÍ]G<sup>!</sup>ÍB.LÁ.MEŠ [šá <sup>d</sup>UTU] 8. [1 m]a-na KI.LAL 10 TÚG.NÍG.ÍB<sup>!</sup>.LÁ.MEŠ [šá <sup>d</sup>A-a] Rest of obv. and rev. uninscribed There was a long distance between the names of the garments and the broken name of Šamaš and Aya. White work for the *lubuštu* ceremony, which [PN] has delivered. Month of Ayaru, 2<sup>nd</sup> day, 4<sup>th</sup> year of D[arius, king of Babylon, king of Lands]. 20 minas, the weight of the *lubāru*-garment [for Šamaš] 20 minas, the weight of 2 *sibtu*-garments [for Šamaš] 2 minas, the weight of the *lubār mē qaqqadi*-headdress [for Šamaš]

```
[1 mi]na 20 shekels, the weight of 4 sūnu-belts [for Šamaš]
      ·-----
[1 mi]na <10 shekels>, the weight of 7 [sa]shes [for Šamaš]
[1 mi]na, the weight of 10 sashes [for Aya].
73. BM 83987 (83-1-21, 1150)
4.2 \times 4.2 \text{ cm}
                      [x].2.[x]
           1. dul-lu BABBAR\Gamma^{\iota i}\gamma [....]
           2. u <sup>d</sup>Gu-[la ....]
           3. ITI.GU<sub>4</sub> U[<sub>4</sub>.x. KAM MU.x.KAM ....]
           4. LUGAL E[<sup>ki</sup> ....]
           5. 15 ma-na [KI.LAL TÚG.HI.A šá <sup>d</sup>IM]
Rest lost
Rev.
           1'. [x ma]-na TÚG.<sup>r</sup>x x<sup>1</sup> [....]
           2'. 15 < GÍN> KI.LAL 5<sup>!</sup>(T:10) TÚG.NÍG.ÍB.[LÁ.MEŠ šá <sup>d</sup>IM<sup>?</sup>]
           3'. 1/3 GÍN KI.LAL ku-lu-[lu ....]
           4'. 5/6 ma-na KI.LAL [x] [....]
           5'. 1/3 GÍN KI.LAL [x] [....]
           6'. 5/6 ma-na KI.L[AL ....]
           7'. šá <sup>d</sup>[DN]
             _____
Rev. 4–5. At the end of line one vertical stroke is preserved.
White work [....] and Gu[la ....]. Month of Ayaru [nth d]ay, [nth year ...], king of
Babylon [....]
15 minas, [the weight of the lubāru-garment for Adad]
[x mi]na(s) ....]
15 < shekels>, the weight of 5! sash[es for Adad?]
20 shekels, the weight of the < lubār > kulū[lu-headdress....]
50 shekels, the weight of [....]
20 shekels, the weight [....]
50 shekels, the wei[ght of ....] for [DN].
```

#### 3. Garments for the Arahsamna *lubuštu* ceremony

## 74. VS 6, 71; cf. NRV 761; NUVI 3, No. 244 9.8.Nbn 6 1. dul-luBABBAR $^{\acute{u}}\check{s}\check{a}^{\text{ md}}\text{AG-}na\text{-}sir\text{-}<\text{A>}\ ^{\text{l\'u}}\text{U}\check{\textbf{S}}.\text{BAR}$ 2. a-na É-babbar-ra id-din-nu ITI.APIN U<sub>4</sub>.9.KAM 3. MU.6.KAM $^{\rm md}$ AG-I LUGAL TIN.TIR $^{\rm ki}$ \_\_\_\_\_ 4. 20 ma-na KI.LAL TÚG.HI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA 5. 20 ma-na KI.LAL 2 <sup>r</sup>si<sup>1</sup>-ba-tu<sub>4</sub> šá <sup>d</sup>UTU ½ ma LAL 6. 1 ma-na 10 GÍN KI.LAL 7 TÚG.NÍG<sup>!</sup>.ÍB<sup>!</sup>.LÁ. <sup>!</sup>MEŠ<sup>!</sup> šá <sup>d</sup>UTU 7. [2] ma-na KI.LAL TÚG.HI.A me SAG.DU šá <sup>d</sup>UTU \_\_\_\_\_ 8. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a \_\_\_\_\_ 9. [2/3 *ma-na*] 「KI¹.LAL 2 TÚG.ÚR.MEŠ *šá* <sup>d</sup>UTU 10 GÍN <sup>[</sup>x x<sup>]</sup> [....] Rest lost L. 5. It seems that the scribe wrote the last three signs mistakenly and next tried to erase L. 7. TÚG.ÚR.MEŠ is evidently a scribe's error instead of 7 huṣannu-sashes. White work which Nabû-nāṣir-<apli>, the weaver has delivered to the Ebabbar temple. Month of Arahsamna, 9<sup>th</sup> day, 6<sup>th</sup> year of Nabonidus, king of Babylon. 20 minas, the weight of the *lubāru*-garment for Šamaš with addition of ½ mina of blue-purple wool 20 minas, the weight of 2 sibtu-garments for Šamaš; half mina is missing 1 mina 10 shekels, the weight of 7 sashes! for Šamaš -----[2] minas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš

1 mina, the weight of 10 sashes for Aya

[40 shekels], the weight of 2 sūnu-belts for Šamaš; 10 shekels [....].

#### **75. BM 62065** (82-9-18, 2034)

 $6.0 \times 4.1 \text{ cm}$ 

#### x+1.8.[Nbn x]

- 1. [dul-lu BABBAR $^{\acute{u}}$   $\check{s}\acute{a}$   $^{\mathrm{md}}$ ] $^{\mathrm{f}}$ AG $^{\mathrm{l}}$ -PAP $^{\mathrm{m}}$ Ba-ku- $\acute{u}$ -a
- 2. [ $u^{\mathrm{md}}$ AG-up-ni-ja it-ta]-din ITI.APIN [ $U_4$ .x+]1.KAM
- 3. [MU.x.KAM <sup>md</sup>AG-I] 「LUGAL TIN.TIR<sup>1ki</sup>
- 4. [20] ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi [½ ma-na SÍG.ZA.GÌN.KUR.RA]
- 5. [20] ma-na KI.LAL 2 și-ba-tu<sub>4</sub> šá [<sup>d</sup>UTU]
- 6. [2 m]a-na KI.LAL  $1^{et}$  < TÚG> me SAG.DU  $\lceil \check{s}\check{a} \rceil$   $\lceil \overset{d}{U}TU \rceil$
- 7. [1 ma-n]a 10 GÍN KI.LAL 7 「TÚG¹.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
- 8. [1 ma-na 1/3] GÍN KI.LAL [4] [TÚG.ÚR.MEŠ šá <sup>d</sup>UTU]

Rest lost

Rev.

- 1'. [.... KI.LA]L sib- $t[u_4 ....]$
- 2'. [.... KI<sup>'</sup>]. 「LAL<sup>1</sup> *șib-tu*<sub>4</sub> *šá* [....]
- L. 2. Expected *it-tan*]-*nu*! In Bi Or 56 (1999) 293 this is described wrongly as a *mihşû tenû* text.

[White work, which] Nabû-nāṣir, Bakûa [and Nabû-upnīya have de]livered. Month of Araḫsamna, [x+] 1 day,  $n^{th}$  year of Nabonidus], king of Babylon.

[20] minas, the weight of the *lubāru*-garment for Šamaš with addition of [½ mina of blue-purple wool]

[20] minas, the weight of 2 *şibtu*-garments for [Šamaš]

[2 mi]nas, the weight of 1 < lubār > mē qaqqadi-headdress for [Šamaš]

[1 min]a 10 shekels, the weight 7 s[ashes for Šamaš]

[1 mina 20] shekels, the weight of 4 [sūnu-belts for Šamaš]


- [.... the wei]ght of the *şibt*[*u*-garment ....]
- [.... the wei]ght of the *şibtu*-garment for [....].

### **76. BM 58028** [CT 55, 851]+**BM 59834** (82-7-14, 2437+4244)

 $7.3 \times 4.8$  cm

#### 10.8.Nbn 1

- 1. dul-lu BABBARú šá <sup>m</sup>Ba-ku-ú-a ù <sup>md</sup>[AG-PAP]
- 2. lúla-'-ta-nu šá <sup>md</sup>AG-EN-MU.MEŠ lú[UŠ.BAR a-na]
- 3. É-babbar-ra id-di-nu ITI.APIN <U\_4>.10.KAM MU.1.[KAM]  $^{\rm md}$ AG-I LUGAL  $E^{\rm ki}$ ]
- 4. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-n[a SÍG.ZA.GÌN.KUR.RA]
- 5. 20 ma-na KI.LAL 2 TÚG.MÁŠ. MEй [šá dUTU]



1 mina 13? shekels, the weight of 4 sūnu-belts for Bunene, the Queen of Sippar, Gula and Adad ½ mina of blue-purple wool, the weight of the lubār mē[tu] and lubār kulūluheadbands for Šamaš 50 shekels, the weight of 1 paršīgu-headdress for the Queen of Si[ppar] 20 shekels, the weight of 1 paršīgu-headdress for Adad Total 1 talent 13 minas 55 shekels of [wool, the completed work]. **77.** Nbn **726** = BM 60371; cf. BA 1, p. 529; NUVI 3, No. 67 Collated 11.8.Nbn 13 1. 「dul」-lu BABBAR  $^{\acute{u}}$  šá $^{\mathrm{md}}$ U+GUR-MU  $^{1\acute{u}}$ UŠ.BAR id-din2. ITI.APIN U $_4$ .11.KAM MU.13.KAM  $^d$ AG-I LUGAL E $^{ki}$ \_\_\_\_\_ 3. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na 「SÍG.ZA.GÌN.KUR.RA」 -----4. 20 ma-na KI.LAL 2 MÁŠ šá <sup>d</sup>UTU \_\_\_\_\_ 5. 2 ma-na KI.LAL TÚG.HI.A me SAG.DU šá <sup>d</sup>UTU \_\_\_\_\_ 6. 1 ma-na 1/3 GÍN KI.LAL 4 ÚR.MEŠ šá <sup>d</sup>UTU u <sup>d</sup>A-a \_\_\_\_\_ 7. 「1\*1 ma-na 10 GÍN <KI.LAL> 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU 8. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>[A-a] \_\_\_\_\_\_ 9. <sup>[2]</sup> ma-na KI.LAL TÚG. <sup>[HI.A]</sup> ù\*<sup>1</sup> sib-tu<sub>4</sub> [šá <sup>d</sup>HAR] \_\_\_\_\_ 10. 1/3 GÍN KI.LAL < TÚG > . ÚR\* [šá <sup>d</sup>IM] 11. 1 ma-<sup>r</sup>na<sup>1</sup> KI.LAL 10 TÚG.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Edge Sip-par<sup>ki</sup>] 12. 1  $\lceil ma \rceil - \lceil na \rceil$   $\lceil KI^* . LAL^* par^{?*} - \check{s}i^{?*} \rceil - \lceil ... \rceil$ 13. fully lost Rev. 14. fully lost 15. 1/3 [GÍN KI.LAL ....] 16. 5 [....] 17. 20 [....]

18. 50 GÍN [KI.LAL 10 TÚG.NÍG.Í]B\*.LÁ\*.MEŠ\*

- 19.  $\lceil \check{s} \acute{a}^* \stackrel{d_1}{\text{IM}} u \rceil \stackrel{d_1}{\text{I}} [\check{s} a la \times G \check{\text{I}}] N^* \text{ KI.LAL}$
- 20. [x x] <sup>r</sup>x<sup>1</sup> 1/3 GÍN KI.LAL *par-ši-gu*
- 21. šá <sup>md</sup>AG-na-sir-<A> ½ ma-na SÍG.ZA.GÌN.KUR\*.RA!
- 22. [ana TÚG.ḤI.A] me-țu TÚG.ḤI.A <<br/>ku>-lu\*-lu šá $^{\rm d}$ UTU 23. [x x x šá ina] ŠU $^{\rm ii}$ <br/>mdAG-na-șir-A
- L. 9. The numeral at the beginning of line looks like 1, but the sign is slightly damaged. Because in parallel places the weight of the *lubāru* and the *sibtu* for Bunene is always 2 minas, I decided to make here the appropriate emendation.
- L. 20. Before the numeral a fragment of sign similar to  $d\hat{u}$  is preserved.

White work, which Nergal-iddin, the weaver, has delivered. Month of Araḫsamna,  $11^{th}$  day,  $13^{th}$  year of Nabonidus, king of Babylon.

20 minas, the weight of the *lubāru*-garment for Šamaš with addition of ½ mina of blue-purple wool 20 minas, the weight of 2 sibtu-garments for Šamaš

\_\_\_\_\_

2 minas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš

1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš and Aya

1 mina 10 shekels, <the weight> 7 sashes for Šamaš

1 mina, the weight 10 sashes for [Aya]

2 minas, the weight the *lubāru* and *şibtu*-garments for [Bunene]

20 shekels, the weight of (one) *sūnu*-belt [for Adad] 1 mina, the weight of 10 sashes for the Queen of Sippar] 1 mi[na], the weight of (one) parš[īgu-headdress<sup>2</sup>.....

20 [shekels, the weight of ....]

5 [....]

20 [....]

50 shekels, [the weight of 10 sashes for [Adad and Šala; x sheke]ls, the weight of [....]; 20 shekels, the weight of (one) paršīgu-headdress for Nabû-nāṣir-apli; ½ mina of blue-purple wool [for the lubār mēţu (and) lubār kulūlu-headbands for Šamaš [.... from] the hands of Nabû-nāṣir-apli.

## 78. BM 83973 (83-1-21, 1136)

PLATE 22

 $4.5 \times 2.5$  cm

([x].8.Cyr[x])

- 1. mi-iḥ-ṣu dul-lu BABB[AR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub>]
- 2. *šá* <U<sub>4</sub>>.15.KAM *šá* ITI.APIN *šá* <sup>m</sup>[PN]
- 3. <sup>lú</sup>qal-la šá <sup>md</sup>AG-n[a-ṣir-IBILA]

	4. $^{\text{lú}}$ TÚG.BABBAR $id\text{-}din\text{-}nu$ [ITI. x U <sub>4</sub> .x.KAM MU.x.KAM] 5. $^{\text{m}}$ Ku- $^{\text{r}}$ raš LUGAL KUR $^{\text{l}}$ .[KUR]				
Rest lost Rev.	1'. 「5 ma-na <sup>?</sup> ¬ []				
	2'. 20 ma-na KI.LAL TÚG.UD.A 'ù' [TÚG.MÁŠ šá <sup>d</sup> IM] 3'. 2/3 ma-na KI.LAL TÚG.'ÚR'.[MEŠ] 4'. 50 GÍN KI.LAL 10 [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> IM u <sup>d</sup> Ša-la] 5'. 2 ma-na KI.LAL TÚG.U[D.A šá <sup>d</sup> Gu-la]				
The revers	e seems to be written by a different person or with a different stylus.				
which [Pl	whi[te] work [for the <i>lubuštu</i> ceremony] for the 15 <sup>th</sup> day of Araḥsamna N], the slave of Nabû-nāṣir-[apli], the <i>ašlāku</i> has delivered. [Month of x h year] of Cyrus, kin[g of Lands].				
5 「minas	[]				
40 shekel 50 shekel 2 minas, t	the weight the <i>lubāru</i> and [ <i>ṣibtu</i> -garments for Adad] s, the weight of <i>sūnu</i> -belts [] s 10 [sashes for Adad <and šala="">] the weight the <i>lubā</i>[<i>ru</i>-garment for Gula].  4657 (82-9-18, 4637)  PLATE 23</and>				
$7.5 \times 6.3$					
	13.8.Cam 6				
	1. dul-lu BABBAR <sup>ú</sup> šá-ḫu-ú šá [lu-bu-uš-tu <sub>4</sub> ] 2. šá ITI.APIN šá <sup>md</sup> UTU-MU-「MU <sup>†</sup> [] 3. 「ITI <sup>†</sup> .APIN U <sub>4</sub> .13.KAM MU.6. <kam> <sup>m</sup>Kam-[bu-zi-ja] 4. LUGAL TIN.TIR<sup>ki</sup> LUGAL KU[R.KUR]</kam>				
	5. 20 ma-na KI.LAL TÚG.UD.A šá r <sup>d</sup> ¹[UTU] 6. 20 ma-na KI.LAL 2¹ (T: KU) túg şib-ba-tu4 šá r <sup>d</sup> ¹[UTU] 7. 1 ma-na <10 GÍN> KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá r <sup>d</sup> ¹[UTU] 8. [2] ma-na KI.LAL TÚG.UD.A me 「SAG¹ šá r <sup>d</sup> ¹[UTU] 9. 1 ma-na 1/3 GÍN KI.LAL 4 TÚG.ÚR.<				
Rev.	10. [1 1/3 ma]-na KI.LAL [TÚG.ḤI.A šá <sup>d</sup> ḤAR] 11. [2/3 ma-na KI.LAL] <sup>túg</sup> ṣib-tu₄ [šá <sup>d</sup> ḤAR] 12. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup> A-a]				

```
13. [1 m]a-na KI.LAL [10] TÚG.NÍG.[ÍB.LÁ.MEŠ] šá <sup>d</sup>[GAŠAN Sip-par<sup>ki</sup>]
```

14. [1/3 m]a-na KI.LAL TÚG.ÚR šá <sup>d</sup>[IM]

Free space of one line

15.  $\lceil 1/3 \rceil$  ma-na KI.LAL TÚG.[ÚR šá  ${}^{\rm d}Gu\text{-}la$ ]

16. 15 GÍN KI.LAL 5 [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>Gu-la]

17. <sup>[1/3]</sup> GÍN KI.L[AL ....]

Free space for about 2 lines

18. 2 ma-na 7 GÍN [dul-lu ....]

19.  $ina \text{ IGI }^{m_{\Gamma}d_{\gamma}}[\text{UTU-MU-MU}....]$ 

- L. 1. Concerning mihşû peşû šahû, see Zawadzki, Garments of the Gods, Vol. I, p. 11.
- L. 17. We can expect here the *sūnu* for Bunene, or *paršīgu* for Gula.

White *šaḥû* work for [the *lubuštu* ceremony] for the month Araḥsamna, which Šamaš-šum-iddin [has delivered]. Month of Araḥsamna, 13<sup>th</sup> day, 6<sup>th</sup> year of Cam[byses], king of Babylon, king of La[nds].

-----

20 minas, the weight of the *lubāru*-garment for [Šamaš]

20 minas, the weight of 2' sibtu-garments for [Šamaš]

1 mina <10 shekels>, the weight 7 sashes for [Šamaš]

[2] minas, the weight of the *lubār mē qaqqadi*-headdress for [Šamaš]

1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš

[1 mi]na [20] shekels, the weight of [the *lubāru*-garment for Bunene]

[40 shekels, the weight of] the *şibtu*-garment for [Bunene]

1 mina, the weight 10 sashes [for Aya]

1 mina, the weight [10] sash[es for the Queen of Sippar]

[20] shekels, the weight of the *sūnu*-belt [for Adad]

[20] shekels, the weight of the  $s\bar{u}[nu\text{-belt for Gula}]$ 

15 shekels, the weight of 5 [sashes for Gula]

20 shekels, the wei[ght ....]

2 minas 7 shekels, the [completed work<sup>2</sup> ....] at disposal of [Šamaš-šum-iddin ....].

## **80. BM 73528** (82-9-18, 13539)

 $5.0 \times 4.7 \text{ cm}$ 

[x].8.Dar 3

- 1. [dul-lu] BABBAR<sup>ú</sup> šá lu-bu-u[š-tu<sub>4</sub>
- 2.  $[x \ x]^{\lceil x \rceil}$  šá ITI.APIN U<sub>4</sub>.[15.KAM]
- 3.  $[x \times x M]U.3.KAM^{m} Da-[rijamuš]$

-----

<sup>4. 5</sup> ma-na KI.LAL [....]

<sup>5. 50</sup> GÍN KI.LAL [....]

<sup>6. 2/3</sup> ma-na KI.LAL [....]

<sup>7. [</sup>*ù*] 1<sup>en</sup> T[ÚG ....]

The beginning of reverse is completely eroded (there could be 2 lines); the rest is uninscribed.

In 1. 3 the first partially preserved sign resembles end of bu.

L. 4. The possible reconstruction of the line 4 is :[TÚG.ḤI.A  $\delta a$   $^{d}$ IM] and line 5: [10 TÚG.NÍG.ÍB.LÁ.MEŠ  $\delta a$   $^{d}$ IM], cf. for example BM 61114 (= 81): 14-15.

White [work] for the *lubu*[ $\check{s}tu$  ceremony ....] for the month Arahsamna, [15<sup>th</sup>] day [...], the 3<sup>rd</sup> year of Da[rius ....]

\_\_\_\_\_

5 minas, the weight of [....]

50 shekels, the weight of [....]

40 shekels, the weight of [....]

[and] 1 [....]-garment [....].

## **81. BM 61114** (82-9-18, 1090)

PLATE 24

 $7.2 \times 6.3$  cm

Badly preserved tablet written with sloppy signs

#### 15.8.Dar 18

- 1.[dul-lu] pi-si-i  $sá <math>lu^{?}$ 1-[bu-us-t] $u_4$
- 2. [šá <sup>md</sup>]UTU-MU-MU <sup>lú</sup>UŠ.B[AR a-na lu-bu-uš]-tu<sub>4</sub>
- 3.  $[\check{s}\acute{a}]$   $^{\Gamma}$ U<sub>4</sub>.15 $^{1}$ .KAM  $\check{s}\acute{a}$  ITI.APIN MU.18.KAM
- 4. <sup>m</sup>Da-ri-iá-a-muš LUGAL E<sup>ki</sup> u KUR.K[UR]
- 5. id-din-nu

\_\_\_\_\_

6.  $20^!$  (T: 30) ma-na 1/3 (or:  $S\acute{I}G$ )  $^{\Gamma}X$  X  $X^{\Gamma}$  [TÚG.ḤI].  $^{\Gamma}A^{\Gamma}$   $S\acute{a}$   $^{d}$ UTU 6a. ina lib-bi  $^{1}/2$  ma-[na LA]L

.... .... ... , - ..... [.... -- -]\_

- 7. 2 ma-na KI.LAL TÚG.UD.A me SIG<sub>5</sub>
- 8. ina lìb-bi 18 GÍN LAL

\_\_\_\_\_

Rev.

- 9. mi-ih-su dul-lu [a]-na lu-bu- $u\check{s}$ -tu4  $\check{s}\check{a}$ { $\ulcorner \acute{E}$  $\urcorner$ }
- 10.  $^{\rm d}$ IM šá U<sub>4</sub>.15.KAM šá ITI.APIN šá  $^{\rm md}$ UTU-MU
- 11. A <sup>md</sup>AG-ŠEŠ.MEŠ-GI *id-din-*[nu] (tu<sub>4</sub> erased)

.....

- 12. 15 ma-na KI.LAL TÚG.UD.A šá <sup>d</sup>IM
- 13. 1/3 *ma-na* LAL
- 14. 5 ma-na KI.LAL <sup>túg</sup>ṣib-<sup>r</sup>tu<sub>4</sub>¹ šá <sup>d</sup>IM
- 15. 50 GÍN KI.LAL TÚG.NÍG.ÍB.LÁ.MEŠ

L. 6 is badly preserved; additionally l. 6a, added probably later, was written partly over the previous line. In such a situation the reading of the line is difficult. By comparison with other texts we expect here  $20 \, ma\text{-}na \, \text{KI.LALTÚG.HI.A} \, \check{sa}^{\,\,d} \, \text{UTU}$ .

L. 9 There is *mihṣû dullu* instead of usual *mihṣû tenû*.

White [work] for the *lu*[*buštu* ceremony which] Šamaš-šum-iddin, the wea[ver] has delivered [for the lubuš]tu ceremony for the 15th day of the month Arahsamna, 18th year of Darius, king of Babylon, king of Lands.

20! minas, [the weight of the *lubāru*-garment] for Šamaš; out of it ½ mi[na is missling

2 minas, the weight of the *lubār mē damqi*-headdress; out of it 18 shekels is missing

-----

Woven work for the *lubuštu* ceremony for Adad for the 15<sup>th</sup> day of the month Araḥsamna, which Šamaš-iddin, son of Nabû-aḥhē-šullim has delivered

\_\_\_\_\_

15 minas, the weight of the *lubāru*-garment for {the temple of} Adad; out of it 20 shekels is missing

5 minas, the weight of the sibtu-garment for Adad 50 shekels, the weight of <10> sashes.

#### **82. BM 66924+BM 73731** (82-9-18, 6918+13742)

 $5.5 \times 7.4$  cm

## <->.8.Dar 30

- 1. dul-lu pi-ṣu-ú šá lu-[bu-uš-tu<sub>4</sub>]
- 2. *šá* <sup>d</sup>UTU *u* DINGIR.MEŠ UD.KIB.N[UN<sup>ki</sup>]
- 3. *šá* ITI.APIN U<sub>4</sub>.15.KAM MU.30.K[AM]
- 4. <sup>m</sup>Da-ri-ja-muš LUGAL KUR.KUR

\_\_\_\_\_

- 5. 20 ½ ma-na KI.LAL TÚG.UD.A šá <sup>d</sup>UTU
- 6. 1 ½ ma-na 「71 GÍN LAL
- 7. 2 ma-na KI.LAL TÚG. TUD. A me-e¹ šá SIG²
- 8. 1 ma-na <sup>1</sup>10 GÍN <sup>1</sup>KI LAL 7 [TÚG.NÍG. ÍB.LÁ.MEŠ
- 9. 1 ma-na KI.LAL 10 TÚG.<NÍG>ÍB.[LÁ.MEŠ šá <sup>d</sup>A-a]
- 10. 1 1/3 ma-na KI.LAL 4 T[ÚG.ÚR.MEŠ šá <sup>d</sup>UTU]
- 11. ½ ma-na SÍG.ZA.GÌN.<KUR>.RA [KI.LAL TÚG.HI.A]
- 12. ku-lu-<sup>[</sup>lu<sup>]</sup> ù TÚG.[HI.A me-tu]

13. 20 ma-na KI.LAL [túgṣib-tu4] Edge

14. šá <sup>d</sup>UTU

15. 15 *m*[*a-n*]*a* K[I.LAL TÚG.ḤI.A] Rev.

- 16.  $\check{s}\acute{a}^{\rm d}$  IM 50¹ GÍN [....] 17. 5 ma-na 「KI¹.LAL  $^{\rm t}$ [ $^{\acute{\rm u}g}$ sib- $tu_4$  $\check{s}\acute{a}^{\rm d}$ IM]
- 18. ½ m[a-na K]I.LAL [....]
- 19. 「50 GÍN KI¹.LAL 10 [TÚG.<NÍG>].Í[B.LÁ.MEŠ šá]
- 20.  $^{\rm rd_1}[{\rm IM}] \ 1/3 \ [ma] ^{\rm r}na^{\rm r} \ [{\rm K}]{\rm I}^2.{\rm LAL}^2$

## 21. 「TÚG.ÚR $^{?}$ 」 [šá $^{d}$ I]M 1/3 ma-na KI.LAL 22. $^{túg}$ [pa $^{1}$ -ši-r[i šá] $^{d}$ IM

Rev. is extremely badly preserved.

Note that the scribe omitted by mistake the line concerning the *şibtu* for Šamaš and added it later (II. 13–14).

L. 16. Before GÍN only the numeral 30 is preserved, i.e. 20 in the upper and 10 in the lower row. I have no idea how to fill the gap in this line.

L. 20. The first badly preserved sign looks like  $\frac{1}{2}$  which makes possible the suggested reconstruction  $r^{d_1}$ [IM]. Obviously 10 *huṣannus* are destined both for Adad and Šala.

L. 22. Concerning the *paširu*, cf. also CT 55, 808 (= 181), rev. 2<sup>?</sup> and BM 65979 (= 179): 8<sup>?</sup>.

White work for the lu[buštu ceremony] for Šamaš and the gods of Sipp[ar] for the  $15^{th}$  day of Araḥsamna,  $30^{th}$  year of Darius, king of Babylon.

20 ½ minas, the weight of the *lubāru*-garment for Šamaš; out of 1 mina 37 shekels is missing

2 minas, the weight of the *lubār mē damqi*-headdress

1 mina 10 shekels, the weight of 7 [sashes for Šamaš]

1 mina, the weight of 10 sash[es for Aya]

1 mina 20 shekels, the weight of 4 s[ūnu-belts for Šamaš]

 $\frac{1}{2}$  mina of blue-purple wool, [the weight of the  $lub\bar{a}r$ ]  $kul\bar{u}lu$  and the  $lub\bar{a}r$  [ $m\bar{e}tu$ ]-headbands

20 minas, the weight of the] sibtu-garments] for Šamaš

15 mi[nas, the we[ight of the lubāru-garment] for Adad

50 shekels [....]

5 minas, the weight of the [sibtu-garment for Adad]

½ m[in]a, [the we]ight of [....]

50 shekels, the weight of 10 [sash]es [for Adad]

20 shekels, 'the weight of the *sūnu*-belt for Adad'

20 shekels, the weight of the *pašīr*[*u* for Adad].

## 83. BM 59713 (82-7-14, 4123)

 $5.6 \times 4.8$  cm

## 13.8.4

- 1. [dul-lu] BABBAR<sup>i</sup>  $\lceil \check{s}\acute{a} \rceil$  a-na lu-bu- $u[\check{s}$ -tu<sub>4</sub>  $\check{s}\acute{a}]$
- 2. [U<sub>4</sub>.15.K]AM šá ITI.APIN a-na <sup>r</sup>ɹ-[babbar-ra SUM]
- 3. [ITI.A]PIN U<sub>4</sub>.13.KAM MU.4.KAM <sup>m</sup>[....]

4. [1 $^{?}$ ] ma-na 50 GÍN KI.LAL TÚG.ḤI.A me- $^{\Gamma}e^{\uparrow}$  [SAG.DU šá  $^{d}$ UTU]

- 5. 1 ma-na 12<sup>!</sup> GÍN 7 TÚG.NÍG.ÍB.[LÁ.MEŠ šá <sup>d</sup>UTU]
- 6. 2 ½ ma-na KI.LAL 4 TÚG.ÚR.MEŠ 「x¹ [....]
- 7. šá <sup>d</sup>UTU ù <sup>d</sup>A-a
- 8. 2 ma-na KI.LAL TÚG.BAR.SI 1 TÚG.「ÚR」 [....]

# 9. 「10」 TÚG.[NÍG].「ÍB」.[LÁ.MEŠ šá] 「 $^{d}$ 」 GAŠAN UD.KIB.[NUN $^{ki}$ ]

Rev. 10. [1/3 GÍN] KI.LAL 1 TÚG.ÚR

11. [šá <sup>d</sup>I]M u <sup>d</sup>Ša-la

12. [x] ma-na KI.LAL TÚG.ḤI.A 「x¹ [....]

13.  $[\check{s}\acute{a}]^{\mathsf{r}^\mathsf{d}}\mathrm{IM}^{\mathsf{l}}\,u^{\mathsf{d}}\check{S}a\text{-}la$ 

14. [1/3] GÍN KI.LAL 1 TÚG.ÚR

15.  $[\check{s}\check{a}]^{\mathrm{d}_{\Gamma}}Gu^{\mathrm{l}}$ -la

- L. 4. The weight of the  $lub\bar{a}r\ m\bar{e}\ (qaqqadi)$  is here atypical (usually 2 minas).
- L. 5. Note the atypical weight of 7 huṣannus for Šamaš (expected weight of 7 huṣannus is 1 mina 10 shekels).

L. 6 and 12. The broken signs resemble Neo-Babylonian ši. Maybe at least in l. 6 we should read 10 T[ÚG.NÍG.ÍB.LÁ.MEŠ], however, the weight of 4 sūnus (1 mina 20 shekels) and 10 huṣannus for Aya (1 mina) gives only 2 minas 20 shekels. Note that the mention of a lubūru in l. 12 is atypical.

White [work] for the *lubu*[ $\check{s}tu$  ceremony for the 15<sup>th</sup>] day of Araḥsamna to Ebabbar was delivered. [Month of Araḥ]samna, 13<sup>th</sup> day, 4<sup>th</sup> year of [....]

[1<sup>2</sup>] mina 50 shekels, the weight of the *lubār mē* [*qaqqadi*-headdress for Šamaš]

1 mina 12 shekels, the weight of 7 sash[es for Šamaš]

2 ½ minas, the weight of 4 sūnu-belts [and ....] for Šamaš and Aya

2 minas, the weight of the *paršīgu*-headdress, 1 *sūnu*-belt., [....]

10 [sashes] for the Queen of Sipp[ar]

[20] shekels, the weight of 1 sūnu-belt [for Ad][ad and Šala

[x] mina, the weight of the *lubāru*-garment, [....] for Adad and Šala

[20] shekels, the weight of 1 sūnu-belt for Gula.

## 4. Garments for the *lubuštu* ceremony in cycle A (Nisannu, Ayaru or Arahsamna)

## 84. BM 62059 (82-9-18, 2028)

 $4.8 \times 5.55$  cm

## [x.x].Nbn 9

- 1. dul-lu BABBAR<sup>ú</sup> šá <sup>md</sup>[PN]
- 2. a-na É-babbar-ra id-din-[nu ITI.x U<sub>4</sub>.x.KAM]
- 3. MU.9.KAM <sup>md</sup>AG-I [LUGAL TIN.TIR<sup>ki</sup>]

- 4. 20 ma-na KI.LAL TÚG.H[I.A šá <sup>d</sup>UTU]
- \_\_\_\_\_ 5. 20 ma-na KI.LAL [2 TÚG.MÁŠ.MEŠ šá <sup>d</sup>UTU]
- 6. 2 ma-na KI.[LAL TÚG.HI.A me-e SAG.(DU) šá <sup>d</sup>UTU]
- 7. 1 ma-na 1/3 GÍ[N KI.LAL 4 TÚG.ÚR.MEŠ šá  $^{\rm d}$ UTU u  $^{\rm d}$ A-a]
- 8. 1 ma-na 10 GÍ[N KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
- 9. 1 ma-na KI.LA[L 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]

10. 1 ma-na KI.LAL [10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Edge Sip-par<sup>ki</sup>]

Rev.

- 11. 1 ma-na KI.LAL < TÚG>.Ú[R ....]
- 12. 2 ma-na KI.LAL TÚG.HI.A [TÚG.MÁŠ šá <sup>d</sup>HAR]
- 13. 2 ma-na KI.LAL <sup>túg</sup>ṣib-t[u<sub>4</sub> šá <sup>d</sup>Gu-la]

- 14. 1/3 GÍN KI.LAL TÚG.ÚR [šá <sup>d</sup>Gu-la]
- 15. 15 「GÍN」 KI.LAL 5 TÚ[G.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>Gu-la]
- 16. <sup>[15]</sup> (T: <sup>[20]</sup>) ma-na KI.LAL TÚG.Ḥ[I.A šá <sup>d</sup>IM]

- 17. <sup>15</sup> ma-na KI.LAL <sup>tú</sup>[<sup>g</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>IM]
  18. 1/3 GÍN KI.LAL TÚ[G.ÚR šá <sup>d</sup>IM]
  19. <sup>1</sup>1/3<sup>2</sup> ma-na KI.LAL par-ši-[gu(<sup>meš</sup>?) šá <sup>d</sup>Ša-la]

L. 11. The reading  $^{\dagger}$ ÚR $^{\dagger}$  is certain, cf., however BM 67093+ (= 86): 10 and BM 75552 (= 91): 10. The rest of the reverse is uninscribed. The first sign in 1. 19 is preserved only partially, so the reading [2/3] is also possible. We expect here the garment for Šala, and the goddess usually received 2 paršīgus, each weighing 20 shekels.

White work, which [PN] has delivered to the Ebabbar temple. [Month of x, n<sup>th</sup> day], 9<sup>th</sup> year of Nabonidus, [king of Babylon].

20 minas, the weight of the *lubā*[ru-garment for Šamaš]

20 minas, the weight of [2 sibtu-garments for Šamaš] 2 minas, the wei[ght of the *lubār mē qaqqadi*-headdress for Šamaš] 1 mina 20 shek[els, the weight of 4 sūnu-belts for Šamaš and Aya] 1 mina 10 shek[els, the weight of 7 sashes for Šamaš] ..... 1 mina, the wei[ght of 10 sashes for Aya] 1 mina, the weight of [10 sashes for the Queen of Sippar] 1 mina, the weight of the [sūnu] -belt [....] 2 mina, the weight of the *lubāru* [(and) *ṣibtu*-garments for Bunene] 2 mina, the weight of the *şibtu*-garment [for Gula] 20 shekels, the weight of the *sūnu*-belt [for Gula] 15 shekels, the weight of 5 s[ashes for Gula]  $\lceil 15^{!} \rceil$  (T:  $\lceil 20^{!} \rceil$ ) minas, the weight of the *lubā*[ru-garment for Adad] 5 minas, the weight of the [sibtu-garment for Adad] 20 shekels, the weight of the  $s[\bar{u}nu$ -belt for Adad]  $\lceil 20^{?} \rceil$  shekels, the weight of the *paršī*[gu-headdress for Šala]. **85. BM 59723** (82-7-14, 4133) PLATE 25  $7.2 \times 6.6$  cm 11.[x].Nbn 11 1. 20 ma-na KI.LAL TÚG. ḤI '.A šá dUTU 2. 20 ma-na KI.LAL 2 si-ba-tu<sub>4</sub> šá <sup>d</sup>[UTU] \_\_\_\_\_ 3. 2 ma-na KI.LAL TÚG.ḤI.「A¹ SAG.DU 「šá¹ [dUTU] 4. 1 1/3 <sup>r</sup>ma<sup>1</sup>-na KI.LAL 4 su-ni-e šá <sup>d</sup>UT[U] 5. 1 <sup>r</sup>ma-na<sup>1</sup> [10 G]ÍN KI.LAL 7 TÚG.NÍG.ÍB.LÁ.MEŠ [šá <sup>d</sup>UTU] -----6. 1 ma-na KI.LAL 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ [šá <sup>d</sup>A-a] 7. 1 1/3 ma-na KI.[LAL] TÚG.HI.A šá <sup>d</sup>Bu-ne-ne <sup>r</sup>ina<sup>1</sup> [lìb-bi 6 GÍN SÍG.ZA.GÌN.<KUR>.RA] 8. <sup>[2/3]</sup> ma-na KI.LAL <sup>túg</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>B[u-ne-ne] 9. [1 ma-n]a KI.LAL 10 TÚG.<NÍG>.ÍB.LÁ.「MEй [šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>]

10. [2/3 ma-na] KI.LAL  $^{\text{túg}}$ su-ú-n[ $u^{\text{meš}}$  šá  $^{\text{d}}$ GAŠAN  $Sip\text{-par}^{\text{ki}}$ ] 11. [2/3 ma-na KI.L]AL <2> túg par-ši-gu[meš šá dGAŠAN Rev. Sip-par<sup>ki</sup>] 12. [15 ma-na] 「KI¹.LAL TÚG.ḤI.A šá dIM 「x¹ (erased²) 13. [5 ma]-na KI.LAL <sup>túg</sup>ṣib-tu₄ šá <sup>d</sup>[IM<sup>?</sup>] 14. 50 GÍN KI.LAL 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá  ${}^{
m d}$ IM <u  ${}^{
m d}$ Ša-la> 15. 1/3 ma-na KI.LAL TÚG.BAR.SI šá <sup>d</sup>[IM] -----16. 1/3 ma-na KI.LAL $^{\mathrm{t\acute{u}g}}su\text{-}\acute{u}\text{-}ni$ šá $^{\mathrm{d}}[\mathrm{IM}]$ \_\_\_\_\_ 17. 2 ma-na KI.LAL <sup>túg</sup>sib-tu<sub>4</sub> šá <sup>d</sup>G[u-la] \_\_\_\_\_ 18. 15 GÍN KI.LAL 5 hu-sa-an-ni-e <sup>[sá]</sup> [dGu-la] \_\_\_\_\_ 19. <sup>[1/3]</sup> ma-na KI.LAL su-ú-ni šá <sup>d</sup>Gu-la 20. PAP 1 GÚ.UN 1<sup>r</sup>3<sup>1</sup> ma-na 55 GÍN dul-la g[am-ru] 21. a-na lu-bul-tu4  $š\acute{a}$  U4.14.KAM U4.15.KAM  $š\acute{a}$  ITI.[x] 22.  $š\acute{a}$   $^d$ UTU  $^d$ A-a  $^d$ Bu-ne-ne u  $^d$ GAŠAN UD.KIB.[NUN<sup>ki</sup>  $š\acute{a}$ ] 23.  $^{md}$ U+GUR-MU it-ta-din 1 ma-na 4 GÍN SÍ[G $^!$ .HI.A] <sup>lú</sup>UŠ.BAR ina IGI-šú ri-h[i<sup>?</sup>] 25. [ITI.x] U<sub>4</sub>.11.KAM MU.11.KAM L. h.e. 26. [md]AG-I LUGAL Eki

- Ll. 10 and 11. Only the suggested reconstruction of numerals in these lines gives the total in
- L. 13. The numeral [5] is reconstructed by comparison with BM 61114 (= 81): 14.
- L. 21. Although the month is not preserved, the comparison with BM 58028+, which concerns garments for the month of Arahsamna, makes it clear that here the garments for the same month or at least for the same cycle (cycle A) are enumerated. In both texts the same quantity of wool, i.e. 1 talent 13 minas 55 shekels were used for the manufacturing of the garments for the gods.
- L. 22. It is interesting to note that Adad and Gula, whose garments are enumerated in the text, are not mentioned here.
- L. 24. The title was added under the name of weaver, only when l. 23 was written. In this way the scribe avoided making an erasure and writing the whole line again.

Note that *lubuštu* ceremony lasted two days. It is the first data, which do not accord with the data known from Nabû-apal-iddina's instruction and from all other texts known so far.

20 minas, the weight of the *lubāru*-garment for Šamaš 20 minas, the weight of 2 *şibtu*-garments for [Šamaš]

2 minas, the wei[ght of the  $lub\bar{a}r < m\bar{e} > qaqqadi$ -headdress for [Šamaš] 1 mina 20 shekels, the weight of 4 sūnu-belts for Šam[aš] 1 mina [10 she]kels, the weight of 7 sashes [for Šamaš] 1 mina, the weight of 10 sashes [for Aya] 1 mina 20 shekels, the wei[ght of] the lubāru-garment for Bunene with ad[dition of 6 shekels of blue-purple wool] 40 shekels, the weight of the *şibtu*-garment for B[unene] [1 min]a, the weight of 10 sashes [for the Queen of Sippar] [40 shekels], the weight of the *sūn*[*us* for the Queen of Sippar] [40 shekels, the wei]ght of <2> paršīgu-headdress[es for the Queen of Sippar] [15 minas], the weight of *lubāru*-garment for Adad [5 mi]nas the weight of the *sibtu*-garment for [Adad] 50 shekels, the weight of 10 sashes for Adad <and Šala> 20 shekels, the weight of the *paršīgu*-headdress [for Adad] 20 shekels, the weight of the *sūnu*-belt for [Adad] 2 minas, the weight of the *şibtu*-garment for G[ula] 15 shekels, the weight of 5 sashes for [Gula]

Total 1 talent 13 minas 55 shekels, t[he completed] work for the *lubuštu* ceremony of the 14<sup>th</sup> and 15<sup>th</sup> day of the month [x] for Šamaš, Aya, Bunene and the Queen of Sip[par which] Nergal-iddin, the weaver has delivered. 1 mina 4 shekels of w[ool] is in his disposal; the remain[ing<sup>2</sup>...

Month of [x], 11 day, 11 year of Nabonidus, king of Babylon.

**86.** BM **67093+BM 68298** (82-9-18, 7088+ 8296)

20 shekels, the weight of the *sūnu*-belt for Gula

PLATE 26

 $7.7 \times 5.8$  cm

[x.x].Dar 23

- 1. [dul-lu BABBAR $^{\hat{u}}$   $\check{s}\check{a}$ ]  $\lceil lu \rceil$ -bu- $u\check{s}$ - $t[u_4$
- 2. [ITI.x U<sub>4</sub>.x.KAM] MU.23.KAM  $^{\rm m}Da$ - $^{\rm r}ri$ -'a¹-[muš LUGAL KUR.KUR]

	3. [20 <i>ma-n</i> ] <i>a</i> KI.LAL TÚG.UD.A <i>šá</i> <sup>d</sup> UTU					
	4. 2 ma-na KI.LAL ˈTÚG¹.UD.A [me qaq]-「qa <sup>¹</sup> !-di šá <sup>rd</sup> ¹UTU					
	5. 1 1/3 ma-na KI.LAL 4 <sup>túg</sup> [s]u-ni-e šá <sup>d</sup> UTU					
	6. 1 ma-na 10 GÍN KI.LAL <sup>r</sup> 7¹ TÚG.NÍG.UB.BAL.MEŠ šá <sup>d</sup> UTU					
	7. 1 ma-na KI.LAL 10 TÚG.NÍG.UB.BAL.MEŠ šá <sup>d</sup> A <sup>!</sup> -a <sup>!</sup> (T: UTU)					
	8. 1/3 ma-na 1 <sup>túg</sup> su-ú-nu šá <sup>d</sup> GAŠAN Sip- <sup>г</sup> par <sup>ki</sup> <sup>1</sup>					
	9. 1 <i>ma-na</i> KI.LA[L 10] TÚG.NÍG.UB.BAL. <meš> šá <sup>d</sup>GAŠAN Sip-<sup>r</sup>par<sup>ki</sup>l</meš>					
Edge	10. 1 ma-na KI.LAL <sup>r</sup> x <sup>túg</sup> ¹BAR.SI <i>šá</i> <sup>d</sup> GAŠAN <i>Sip-par</i> <sup>ki</sup>					
Rev.	11. 2 ma-na [KI.LAL <sup>tú</sup> ] <sup>g</sup> ṣib-tu <sub>4</sub> šá <sup>d</sup> Gu-la					
	12. $1/3$ ma-na $^{\Gamma}$ KI $^{1}$ .[LAL] $^{\text{túg}}$ su $^{1}$ -ú- $^{\Gamma}$ nu $^{1}$ šá $^{d}$ Gu-la					
	13. 15 GÍN KI.LAL 5 TÚG.NÍG.UB.BAL.MEŠ <i>šá</i> <sup>d</sup> <i>Gu-la</i>					
	14. [x] ma-na [x] GÍN dul-lu e-et-iq					
	15. [15 <i>m</i> ] <i>a-na</i> KI.LAL TÚG.UD.A <i>šá</i> <sup>d</sup> IM					

Note the lack of one line concerning the  $\dot{s}ibtu$ -garment for Šamaš and the  $lub\bar{a}ru$ -garment and the  $\dot{s}ibtu$ -garment for Bunene.

L. 4. We expect in this position *lubār mē qaqqadi*, however, the sign following the gap looks like *ud*, and the next one is almost exactly like *di*, although instead of two it has three horizontal strokes. The only possibility I could suggest is: TÚG.HI.A [*me-e qaq*]-<sup>[</sup>*qa*]-<sup>[</sup>*-di*. L. 6–7, 9, 13. Note the writing TÚG.NÍG.UB.BAL.MEŠ instead of expected TÚG. NÍG.ÍB.LA.MEŠ.

[White work, which] for the *lubuš[tu* ceremony of the n<sup>th</sup> day n<sup>th</sup> year ....]. Month of x, n<sup>th</sup> year] 23<sup>rd</sup> year of Dar[ius], king of [Lands].

[20 min]as, the weight of the  $lub\bar{a}ru$ -garment for Šamaš

2 minas, the weight of the *lubār* [mē qaqq]adi-headdress for Šamaš

1 mina 20 shekels, the weight of 4 [s]ūnu-belts for Šamaš

1 mina 10 shek]els, the weight of 7 sashes for Šamaš

1 mina, the weight of 10 sashes for Aya!

20 shekels, the weight of 1 sūnu-belt for the Queen of Sippar 1 mina, the weig[ht of 10] sashes for the Queen of Sippar 1 mina, the weight of [x] paršīgu-headdress for the Queen of Sippar 2 minas, [the weight of] the *şibtu* for Gula 20 shekels, the wei[ght of the s] $\bar{u}nu$ -belt for Gula 15 shekels, the weight of 5 sashes for [Gula] [x] mina [x] shekels, the missing work [15 mi]nas, the weight of the *lubāru*-garment for Adad. **87. BM 65162** (82-9-18, 5143)  $7.2 \times 7.0 \text{ cm}$ [x.x].Dar[x]1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub> <sup>r</sup>šá<sup>†</sup> [ITI.x] 2. šá <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR *id-din-nu* ITI.[x MU.x.KAM] 3. <sup>m</sup>Da-ri-<sup>r</sup>mu-uš-šú<sup>1</sup> LUGAL TIN.TIR[<sup>ki</sup> LUGAL KUR.KUR] 4. 20 ma-na KI.LAL TÚG.[HI.A šá <sup>d</sup>UTU] 5. 20 ma-na KI.LAL 2 [TÚG.MÁŠ šá <sup>d</sup>UTU] 6.  $^{\text{72}}$  ma-na KI.LAL  $^{\text{T}}\text{LÚG}^{?_{\text{1}}}$  [me]- $^{\text{1}}$  SAG  $^{\text{7}}$ šá $^{\text{1}}$  [ $^{\text{d}}$ UTU] 7. 1 ma-na 10 GÍN 'KI.LAL' 7 'TÚG.NÍG'.ÍB.LÁ.[MEŠ šá<sup>d</sup>UTU] 8. 1 ma-na 1/3 G[ÍN KI.LAL] 4 [TÚG.ÚR.MEŠ šá <sup>d</sup>UTU] 9. ½ ma-na SÍG. ¡ZA].GÌN.<KUR>.RA KI.LAL TÚG.ḤI.A šá dU[TU] 10. 1 ma-na KI.LAL 10 GÍN TÚG.NÍG.ÍB. LÁ [MEŠ šá dA-a] 11. 8 ma-na 10 GÍN SÍG.HÉ.ME.DA KI.LAL t[úg?ku-si-tu4] 12. 1 ma-na KI.LAL TÚG.BAR.SI BABBAR<sup>ú</sup> r<sup>d</sup> [HAR] Rev. 13. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá dIGAŠAN Sip-14. 1 ma-na SÍG. [ZA].GÌN. KUR>.RA KI.LAL> TÚG. [HI.A]  $ku^{1}$ -lu- lu u TÚG.HI.A  $m[e^{!}$ -tu]15. 53 GÍN SÍG.ZA.GÌN.KUR.RA KI.LAL *e-r*[*i* x x x x] 16.  $\check{sa}^{\rm d}$ GAŠAN  $Sip\text{-}par^{\rm ki}$  [ $\check{sa}^{\rm md}$ ] [UTU-MU-MU] [it]- $^{\rm r}ta$ ]-din 7 GÍN [LAL]

17. 15 *ma-na* KI.LAL TÚG.ḤI.A *šá* <sup>d</sup>IM free space for two-three lines 18. 「SÍG.ZA.GÌN」.KUR.RA 「 $ri^2$ 」-[ $hi^2$  ....] 19. [(x x)] 「*šá* <sup>d</sup>GAŠAN」 *Sip-par* <sup>[ki]</sup>

- L. 6. The line is heavily damaged. There is not enough place to read 'TÚG'.[HI.A me]-[e].
- L. 12. The white *parśīgu* is known exclusively as a piece of Bunene's vestment: BM 50066 (= 295): 6'; BM 50745 (= 297) I 4' rev. I 4; BM 51099 (= 293) rev. I 5'; BM 51447 (= 294) I 9'.
- L. 11. If the proposed reconstruction is right, it would be additional data concerning the weight of the robe of Aya, see Zawadzki, *Garments of the Gods*, Vol. I, p. 118.
- L. 14. The numeral at the beginning of the line is out of question, however, according to other texts it is too high.

Only ½ mina of takiltu wool was used for manufacturing both items.

L. 19. It is possible that nothing is missing at the beginning of the line.

White work for the *lubuštu*-ceremony of the month [x, n<sup>th</sup> day which Šamaš-šumukin, the weaver has delivered. Month of [x, n<sup>th</sup> day, n<sup>th</sup> year] of Darius, king of Babylon, [king of Lands].

20 minas, the weight of the *lub*[āru-garment for Šamaš]

20 minas, the weight of 2 [sibtu-garments for Šamaš]

2 minas, the weight of the *lubār* [m]ē qaqqadi-headdress [for Šamaš]

1 mina 10 shekels, the weight of 7 sashes [for Šamaš]

1 mina 20 sh[ekels, the weight of] 4 [sūnu-belts for Šamaš]

½ mina of blue-purple wool, the weight of the *lubāru*-garment for Ša[maš]

-----

1 mina, the weight of 10 sashes [for Aya]

8 minas 10 shekels of blue-purple wool, the weight of [robe? (for Aya)]

-----

1 mina, the weight of the white *paršīgu*-headdress [(for Bunene]

1 mina, the weight of 10 sashes for [the Queen of Sippar]

1 mina of blue-purple wool, <the weight of> the  $lub\bar{a}r\ kul\bar{u}lu$  (and)  $lub\bar{a}r\ m[\bar{e}tu]$ -headbands

\_\_\_\_\_

53 shekels of blue-purple wool, the weight of the *lubār err*[*u*-headband(s) ...... for the Queen of Sippar, [which] Šamaš-šum-iddin has delivered; 7 shekels [are missing]

-----

15 minas the weight of the *lubāru*-garment for Adad blue-purple wool, re[st .....] for the Queen of Sippar.

**88. BM 71730** (82-9-18, 11733)

PLATE 26

 $4.3 \times 4.3 \text{ cm}$ 

3.[x].Ach 7

- 1.  $[dul-lu \ BABBAR^{\acute{u}}\ \check{s}]\acute{a}\ lu-bu-u\check{s}-t[u_4\ \check{s}\acute{a}\ ITI.x]$
- 2.  $[U_4.x.KA]M \check{s}\acute{a}^{md}{}^{\Gamma}AG^{1}-PAP-{}^{\Gamma}A^{1}$
- 3. [SUM<sup>na</sup> ITI.x] U<sub>4</sub>.3.KAM MU.7.KAM

	4. [KN LUG]AL TIN.TIR <sup>ki</sup> LUGAL KUR.KUR
Edge Rev. un	5. [20 ma-na K]I.LAL TÚG.UD.A šá <sup>d</sup> UTU 6. [20 ma-na] KI.LAL 2 MÁŠ šá <sup>d</sup> UTU 7. [2 ma-na K]I.LAL TÚG.ḤI.A me SAG 8. [1 ma-na KI.L]AL <sup>r</sup> 6 <sup>l</sup> ḫu-ṣa-an-ni šá <sup>d</sup> UTU 9. [1 ma-na KI.LAL] 10 ḫu-ṣa-an-ni šá <sup>d</sup> A-a 10. [1 ma-na KI.LAL 10 ḫ]u-ṣa-an-ni šá <sup>d</sup> GAŠAN UD.KIB.NUN <sup>ki</sup> inscribed
[White apli [ha Lands.	work fo]r the <i>lubuštu</i> ceremony of the month [x, n <sup>th</sup> day] which Nabû-nāṣir-s delivered. Month x], 3 <sup>rd</sup> day, 7 <sup>th</sup> year [of KN, ki]ng of Babylon, king of
[20 min [2 mina [1 mina [1 mina	as, the we]ight of the <i>lubāru</i> -garment for Šamaš as, the weight of 2 <i>şibtu</i> -garments for Šamaš s, the we]ight of the <i>lubār mē qaqqadi</i> -headdress, the we]ight of 6 sashes for Šamaš, the weight] of 10 sashes for Aya, the weight of 10 s]ashes for the Queen of Sippar.
<b>89. BM</b> 3.6 × 4.	<b>73909</b> (82-9-18, 13920) 6 cm
	1'. [20 ma]-na KI. <sup>-</sup> LAL¹ [TÚG.ḤI.A <i>šá</i> <sup>d</sup> UTU] 2'. [20] <i>ma-na</i> KI.LAL 2 [TÚG.MÁŠ <i>šá</i> <sup>d</sup> UTU]
	3'. <sup>[1]</sup> ma-na 10 GÍN KI.LAL <sup>[7]</sup> [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> UTU]
	4'. 1 <i>ma-na</i> 1/3 GÍN KI.L[AL 4 TÚG.ÚR.MEŠ <i>šá</i> <sup>d</sup> UTU]
	5'. 2 ma-na [KI.LAL] TÚG.[ḤI.A me-e SAG.(DU) šá <sup>d</sup> UTU] 6'. 1 ma-na KI.LAL 10 TÚG.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> A-a]
	7'. [2 ma]-na KI.LAL TÚG.ḤI.A [u TÚG.MÁŠ šá <sup>d</sup> ḤAR]
Edge	8'. 1 <i>ma-na</i> KI.LAL 10 TÚG.NÍG.ÍB.[LÁ.MEŠ <i>šá</i> <sup>d</sup> GAŠAN <i>Sip</i> - <sup>r</sup> par <sup>l[ki]</sup>
	9'. 1 <i>ma-na</i> [x G]ÍN KI.LAL [] 10'. <i>šá</i> <sup>! d</sup> GAŠAN <i>Sip-</i> <sup>r</sup> <i>par</i> <sup>1[ki]</sup>
	11'. 2/3 ma-na KI.LA[L]

```
12'. <sup>[1/3]</sup> ma-na KI.LAL TÚG.ḤI.[A ....]
          13'. 「2^{?}¬ ma-na KI.LAL [....]
           14'. [x ma]-na K[I.LAL ....]
L. 10'. dGAŠAN is preceded with two erased signs, one of which I emended here to šá.
L. 13'. Only upper part of the numeral is preserved, and the reading \lceil 1/3 \rceil cannot be exclud-
ed. They are two possibilities of the filling the gap:
<sup>7</sup>2<sup>?</sup>1 ma-na KI.LAL [TÚG.ḤI.A šá <sup>d</sup>Gu-la], or <sup>1</sup>/3<sup>?</sup>1 ma-na KI.LAL [TÚG.ḤI.A šá <sup>d</sup>Gu-la]. If we accept the first reading, in the line 14' it
would be [1/3 ma]-na K[I.LAL TÚG.ÚR šá <sup>d</sup>Gu-la].
[20 min]as, the weight of the [lubāru-garment for Šamaš]
[20] minas, the weight of 2 [sibtu-garments for Šamaš]
1 mina 10 shekels, the weight of 7 [sashes for Šamaš]
_____
1 mina 20 shekels the wei[ght of 4 sūnu-belts for Šamaš]
2 minas, [the weight] of the lubār [mē qaqqadi-headdress for Šamaš]
1 mina, the weight] of 10 hu[sannu-sashes for Aya]
[2 mi]nas, the weight of the lubāru [and sibtu-garments for Bunene]
1 mina, the weight of 10 sash[es for the Queen of Sippar]
-----
1 mina, [x she]kels, the weight of [....] for the Queen of Sippar
40 shekels, the weig[ht of ....]
20 shekels, the weight of the lubār [....]
2<sup>?</sup> minas, the weight of [....]
[x min]a(s), the we[ight of ....].
90. BM 73489 (82-9-18, 13500)
5.2 \times 4.0 \text{ cm}
            1'. [....].11. [KAM x][....]
            2'. [20 ma-na KI.LA]
L<br/> TÚG.ḤI.A šá^{\rm d}UTU in
[a lìb-bi] ½ ma-[na
                   SÍG.ZA.GÌN.KUR.RA]
            3'. [20 ma-na K]I.LAL 2 şib-tu<sub>4</sub> šá <sup>d</sup>UTU
            4'. [1 ma-na KI.LA]L 7<sup>!</sup> (T:6) TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
```

-----

5'. [2 ma-na KI.LAL] TÚG.ḤI.A me SAG.DU šá <sup>d</sup>ſUTU¹

6'. [1 1/3 ma-na KI.LA]L 4 TÚG.ÚR.[MEŠ  $š\acute{a}$  <sup>d</sup>UTU (u <sup>d</sup>A-a)] 7'. [....]  $\lceil x \rceil \lceil .... \rceil$ 

Rest lost

Rev.

1'. [1/3 ma-na KI.LAL TÚG.ÚR šá] <sup>d</sup>IM

2'. [50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ]. MEй šá dIM u drŠa-la¹

Rest of rev. is uninscribed

In l. 4'. It should be 7 huşannus because 2 şibtus clearly indicate that the text enumerates the garments for the first cycle, see Zawadzki, Garments of the Gods, Vol. I, p. 93. Because in this cycle 7 huşannus belonged to the vestment of Šamaš, the numeral 6 should be treated as scribe's mistake.

L. 7'. One horizontal stroke followed by the head of vertical is only preserved. Because 10 TÚG.NÍG.ÍB.LÁ.MEŠ  $\check{s}\check{a}^{d}A$ -a are expected, the preserved remnants can be recognized as a small fragment of TÚG or ÍB and the head of the LÁ.

[....] 11<sup>th</sup> [....]

[20 minas, the weig]ht of the  $lub\bar{a}ru$ -garment for Šamaš wi[th addition of] ½ mina of blue-purple wool

[20 minas, the wei]ght of 2 sibtu-garments for Šamaš

[1 mina, the weig]ht of 7! sashes for Šamaš

[2 minas, the weight] of the *lubār mē qaqqadi*-headdress for Šamaš

[1 mina 20 shekels, the weig]ht of 4 sūnu-belts [for Šamaš (and Aya]

[20 shekels, the weight of (one) sūnu-belt for] Adad

[50 shekels, the weight of 10 sashes] for Adad and Šala.

## **91. BM 75552** (83-1-18, 901) = Str II 152/4

 $9.5 \times 6.7$  cm

- 1. [du]l-lu  $^{\mathsf{T}}\mathsf{BABBAR}^{\acute{u}}$   $\check{s}\acute{a}$  lu-bu  $^{\mathsf{T}}-[u\check{s}-tu_4]$
- 2. [eroded].12. [KAM]
- 3. fully eroded
- 4. 20  ${}^{r}ma$ -na KI.LAL TÚG. ${}^{r}$ HI.A ${}^{r}$  šá  ${}^{d}$ UTU 10[+10] ma-na 2  ${}^{t\acute{u}g}[sib$ - $tu_4]$
- 5. 2 <sup>r</sup>ma-na KI.LAL TÚG.ḤI.A<sup>1</sup> me SAG 1 ma-na 10 GÍN <sup>r</sup>KI<sup>1</sup>.[LAL]
- 6. <sup>1</sup>7 TÚG.NÍG.ÍB.LÁ.MEŠ <sup>1</sup> 1 *ma-na* 1/3 GÍN KI.LAL TÚG.ÚR.[MEŠ]

\_\_\_\_\_

- 7. ½ ma-na KI.LAL lu-ba-ri me-tu ù lu-ba-ri ku-lu-lu SÍG.ZA.GÌN.KUR.RA
- 8. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a
- 9. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN UD.KIB.NUNki
- 10. 1 ma-na KI.LAL <3> <sup>túg</sup>par-ši-gu šá <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>

11. 2 ma-na KI.LAL TÚG.UD.A šá <sup>d</sup>Bu-ne-ne

12. ù <sup>túg</sup>ṣib-tu<sub>4</sub>

- 13. 20 ma-na KI.LAL TÚG.UD.A ù túg sib-tu4 šá dIM
- 14. 2/3 ma-na KI.LAL <2> túg par-ši-gu
- 15. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>IM ù <sup>d</sup>rŠa¹-la

16. 2 ma-na KI.LAL TÚG.MÁŠ šá <sup>d</sup>Gu-la

17. 15 GÍN KI.LAL 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>rd</sup>Gu-la<sup>1</sup>

18. 50 GÍN *i-ti-iq* 

L. 10. Concerning this line, cf. above CT 55, 801 (= 71): 14.

L. 14. Placed between the *lubāru* and the *şibtu* for Adad (l. 13) and the *huṣannus* for Adad and Šala (l. 15) the paršīgu from l. 13 must belong to the vestment of Adad, too. Note, however, that 40 shekels is the weight of 2 paršīgus, while Adad received regularly only

[Wh]ite work for the *lubu*[*štu*] ceremony [....] 12<sup>th</sup> [....]

20 minas, the weight of the *lubāru*-garment for Šamaš;

[20] minas, the weight of 2 [sibtu]-garments;

2 minas, the weight of the *lubār mē qaqqadi*-headdress;

1 mina 10 shekels, the weight of 7 sashes;

1 mina 20 shekels, the weight of  $<4 > s\bar{u}nu$ -belts

½ mina, the weight of the blue-purple lubār mēţu and lubār kulūlu-headbands

1 mina, the weight of 10 sashes for Aya

1 mina, the weight of 10 sashes for the Queen of Sippar

1 mina, the weight of <3> paršīgu-headdresses for the Queen of Sippar

2 minas, the weight of the *lubāru* and *sibtu*-garments for Bunene

20 minas, the weight of the *lubāru* and *şibtu*-garments for Adad

40 shekels, the weight of <2> paršīgu-headdresses

50 shekels, the weight of 10 sashes for Adad and Šala

2 minas, the weight of the *şibtu*-garment for Gula 15 shekels, the weight of 5 sashes for Gula

50 shekels are missing.

## **92. BM 67857** (82-9-18, 7855)

 $6.5 \times 4.2 \text{ cm}$ 

- 1'. [x x x] KI.L[AL ....]
- 2'. [1 ma-na] 10 GÍN KI.L[AL 7 TÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{\rm d}$ UTU]
- 3'. [1 m]a-na 1/3 GÍN KI.LAL 4 TÚG. TÚR [.MEŠ šá <sup>d</sup>UTU]
- 4'. [2 ma]-na KI.LAL TÚG.ḤI.A <me> SAG.ʿDU¹ [šá dUTU]
- 5'. [1 ma-n]a KI.LAL 10 TÚG.<NÍG>.ÍB.LÁ.M[EŠ]
- 6'. [....] <sup>[</sup>x<sup>]</sup> *šá* <sup>d</sup>[DN]
- 7'. [....] x [....]

Rev. 1'. [x]-\(^ta\) BAR.\(^SI\).MEŠ SÍG.ZA.\(<GÌN\).KUR.RA \(š\alpha\) [....]

- 2'. [x x]  $\lceil 1/3 \rceil$  ma-na KI.LAL TÚG.BAR.SI šá  $^{d}$  $\lceil DN \rceil$
- 3'. <sup>[1]</sup> ma-na 15 GÍN KI.LAL TÚG.GÚ.UD.DU šá <sup>d</sup><sup>[DN]</sup>
- 4'. 1 2/3 ma-na KI.LAL ni-bi-ih? šá 「DN
- 5'. 'x GÍN' [x] 'x x x' [....]

Beginning of rev. is uninscribed (place for ca. 2 lines)

L. 6. Before šá there is a fragment of upper part of sign, similar to ki or di. In l. 7 only one vertical stroke is preserved.

Rev. 3'. The text on the reverse is atypical for such a list.

[....], the weig[ht of ....]

[1 mina]10 shekels, the wei[ght of 7 sashes for Šamaš]

[1 m]ina 20 shekels, the weight of 4 sūnu-belts [for Šamaš]

[2 mi]nas, the weight of the *lubār* <*mē*> *qaqqadi*-headdress [for Šamaš]

[1 min]a, the weight of the 10 sashes [....] for [DN]

[x] blue-purple *paršīgu*-headdresses for [....]

[...] 20 shekels, the weight of the *paršīgu*-headdress for [DN]

1 mina 15 shekels, the weight of the *nahlaptu*-cloak for [DN]

1 mina 40 shekels, the weight of the *nēbeḥu*-belt [DN]

[x] shekels [....].

## **93. BM 60883** (82-9-18, 859)

PLATE 27

 $7.9 \times 4.8$  cm

## 

\_\_\_\_\_\_

- 2'. 「 $20^{?}$ ½¹ ma-na KI.LAL TÚG.UD.A šá  $^{\rm d}$ UTU
- 3'. 2 ma-na KI.LAL TÚG.UD.A me SIG šá <sup>rd</sup>¹[UTU]
- 4'. 1 1/3 ma-na KI.LAL 4 「TÚG.ÚR¹.[MEŠ šá dUTU]
- 5'. 1 ma-na 10 GÍN KI.LAL [7] [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
- 6'. 1 ma-na 10 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup>A-a]

Rev. Beginning uninscribed (free space for 3 lines)

- 7'. 2 1/3 ma-na 8 GÍN 「KI<sup>?</sup>.LAL<sup>?</sup>」[....]
- 8'.  $[x \ x] [x \ x \ KAM^? \ x^] [....]$

L. 1'. Only the bottom part of this line and upper part of line 8' is preserved. L. 2'. The first sign is written over an erasure and because the vertical stroke is still recognizable, it looks like  $l\acute{u}$ . Between this sign and  $\frac{1}{2}$  there is a small hole. Probably the weight of this *lubāru* amounted to 20 minas of white wool and ½ mina of blue-purple wool. 20 ½ minas, the weight of the *lubāru*-garment for Šamaš 2 minas, the weight of the *lubār mē* siq(qu)-headdress [for Šamaš] 1 mina 20 shekels, the weight of 4 sūnu-belts [for Šamaš] 1 mina 10 shekels, the weight of 7 [sashes for Šamaš] 1 mina, the weight of 10 sash[es for Aya] 2 minas 28 shekels, the weight? [....]. 94. BM 66469 (82-9-18, 6462)  $5.8 \times 5.3$  cm Obv. 1'. [....] 4.KAM [....] 2'. [20 ma-na] KI.LAL TÚ[G.ḤI.A šá <sup>d</sup>UTU] 3'. <sup>[20]</sup> ma-na KI.LAL TÚ[G.MÁŠ šá <sup>d</sup>UTU] \_\_\_\_\_ 4'. <sup>[2]</sup> ma-na KI.LAL TÚG.[HI.A me SAG.(DU) šá <sup>d</sup>UTU] -----5'. [1 1/3 ma-na] 「KI.LAL」 4 [TÚG.ÚR šá <sup>d</sup>UTU (u <sup>d</sup>A-a)] 6'. [1 ma-na 10 GÍN] KI.LAL 7 [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU] \_\_\_\_\_ 7'. [1 ma-na] 「KI.LAL」 10 [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a] Rest lost Rev. 1'. [....] 10 [....] 2'. Completely eroded 3'. Completely eroded 4'. Completely eroded 5'. [....] 10 TÚG.[NÍG.ÍB].LÁ.<MEŠ> TÚG.[....] 6'. [x m]a-na KI.LAL [ 7'. [....]  $[x \ x]$  [....] Rest lost [....] 4<sup>th</sup> [....] [20 minas], the weight of the *lu*[*bāru*-garment for Šamaš] 20 minas, the weight of the [sibtu-garments for Šamaš] 2 minas, the weight of the *lu*[*bār mē qaqqadi*-headdress for Šamaš] [1 mina 20 shekels], the weight of 4 [sūnu-belts for Šamaš (and Aya)] [1 mina 10 shekels], the weight of 7 [sashes for Šamaš]

[1 mina], the weight of 10 [sashes for Aya] [....]10 [....] [....] 10 \(^{\text{sashes}}\) [....] [x m]ina, the weight of [....]. 95. BM 67814 (82-9-18, 7812)  $4.5 \times 4.6$  cm [x.x].Nbn[x]1. [dul-lu BABBAR  $^i$  šá lu]-bu-[uš-tu4 šá ITI.x U4.x.KAM šá] 2. a-na É-babbar-ra [SUM ITI.x U<sub>4</sub>.x.KAM MU.x.KAM] 3. md AG-IM.TUKU L[UGAL TIN.TIRki] \_\_\_\_\_ 4 . 20 ma-na KI.LAL TÚG.ḤI.[A šá <sup>d</sup>UTU] \_\_\_\_\_\_ 5 . <sup>[20]</sup> ma-na KI.LAL <2> şib-tu<sub>4</sub> [šá <sup>d</sup>UTU] \_\_\_\_\_ 6. [2 m]a-na KI.LAL TÚG.HI.A me [SAG.DU šá <sup>d</sup>UTU] 7. [1 1/3 ma]-<sup>r</sup>na<sup>1</sup> [KI]. <sup>r</sup>LAL 4<sup>1</sup> TÚG. Ú[R.MEŠ šá <sup>d</sup>UTU  $(u^{d}A-a)$ Rest lost On the reverse traces of three lines are preserved, but only in l. 1' can one read 10 TÚG.[....] [White work for the lu]bu[štu ceremony of the month x, n<sup>th</sup> day] which [was delivered] to the Ebabbar temple. [Month x, n<sup>th</sup> day, n<sup>th</sup> year] of Nabonidus, ki[ng of Babylon]. 20 minas, the weight of the *lubā*[ru-garment for Šamaš] \_\_\_\_\_ 20 minas, the weight of <2> sibtu-garments [for Šamaš] [2 mi]nas, the weight of the *lubār mē* [qaqqadi-headdress for Šamaš] [1 mi]na [20 shekels, the we]ight of  $4 s\bar{u}[nu$ -belts for Šamaš (and Aya)]. **96. BM 59264** (82-7-14, 3673) PLATE 27  $4.0 \times 4.8$  cm 1'.  $[x x x]^{\lceil} x^{\rceil} id - d[i ....]$ \_\_\_\_\_ 2'. [20] ma-na KI.LAL TÚG.ḤI.A šá [dUTU] 3'. [20 *m*]*a-na* KI.LAL 2 *și-b*[*a-tu*<sub>4</sub> *šá* <sup>d</sup>UTU] 4'. [1 ma-n]a 10 GÍN KI.LAL 7 TÚG.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]

5'. [2 ma-na] KI.LAL TÚG.ḤI.A me-re<sup>1</sup> [SAG.(DU)  $š\acute{a}$   $^d$ UTU]

```
6'. [x x x x x x x x x]^{7} 3 x^{7} [....]
Rest lost
Rev. in preserved part uninscribed
L. 6 '. The numeral 3 is followed by either t[\acute{u}g, or m[a].
[.... has deli[vered ....]
[20] minas, the weight of the lubāru-garment for [Šamaš]
[20 mi]nas, the weight of 2 sib[tu-garments for Šamaš]
[1 min]a 10 shekels, the weight of 7 sa[shes for Šamaš]
[2 minas], the weight of the lubār mē [qaqqadi-headdress for Šamaš]
[....] 3 [....].
97. BM 71237 (82-9-18, 11239)
                                                                                          PLATE 28
5.3 \times 3.9 cm
              1'. [x TÚG]. [HI]. A me SIG šá [d] [UTU 20 ma-na KI.LAL]
              2'. 2 <sup>túg</sup> șib-ba-a-ta šá <sup>rd</sup> [UTU 1 1/3 ma-na]
              3'. [KI].LAL 4 TÚG.ÚR.<MEŠ> šá <sup>d</sup>[UTU 1 ma-na 10 GÍN]
              4'. [KI].LAL 7 「TÚG¹.[NÍG.Í]B.LÁ.<MEŠ> šá [dUTU x x x]
              5'. [KI.LAL x TÚG.U]D<sup>?</sup>.A ù ku-lu-<sup>r</sup>lu šá<sup>?</sup> I dUTU<sup>?</sup> 1 ma-na
                      KI.LAL]
              6'. [10 Τ]ÚG.NÍG.ÍB.LÁ.<ΜΕŠ> šá Γ<sup>d</sup>1[A-a]
              7'. [x TÚG.HI].A 10 TÚ[G.NÍG.ÍB]. LÁ¹. MEŠ> šá rd¹[
L.e.
              8'. [....] bar [x x x] 10 \, ^{r}x^{1} [....]
              9'. [....] {}^{\Gamma}T\dot{U}G^{1}'.[x x x]-{}^{\Gamma}x^{1} < \check{s}\acute{a} > {}^{d}[DN]
Rev.
            10'. [....] KI [x x x l]u^{l} šá <sup>d</sup>[DN]
            11'. [....] hi^{\lceil x \rceil} [x \times x] \check{s} \acute{a}^{d} IM u [DN]
            12'. [....] [x] [x x x]^{d} IM u [DN]
            13'. [....] 「RA<sup>?</sup> [x x x<sup>] d</sup>IM [....]
            14'. [....] šá {}^{d}{}^{\Gamma}Gu^{\Gamma}-la
            15'. [....] \lceil \check{s} \acute{a} \, {}^{\mathsf{d}} \mathsf{G}[u^? - la]
L. 8. \lceil x \rceil – two Winkelhaken, like the beginning of bu.
Ll. 14'-15', cf. BM 75552 (= 91): 16-17.
[....], the lubār mesiq(qu^2)-headdress [for Šamaš]
[20 minas, the weight] of 2 sibtu-garments for [Šamaš]
[1 mina 20 shekels], the weight of 4 sūnu-belts for [Šamaš]
[1 mina 10 shekels, the we]ight of 7 sashes for [Šamaš]
[....], the weight of the lub\bar{a}|r < m\bar{e}tu^2 > and < lub\bar{a}r > kul\bar{u}lu-headbands for [Šamaš]
[1 mina, the weight of 10] sashes for [Aya]
```

[ <i>lubā</i> ] <i>r</i> 10 sashes	for []					
[ for] A	dad dad and [Šala]					
[] for G	ıla					
<b>98. BM 68</b> 5.5 × 4.8 c	<b>109</b> (82-9-18, 8107)					
	1'. [x ma-na KI.LAL] <sup>r</sup> şib-tu <sub>4</sub> <sup>1</sup>		[šá <sup>d</sup> UTU]			
	2'. [2 ma-na KI.LA]L TÚG.ḤI.A me SA	AG	[šá <sup>d</sup> UTU]			
	3'. [1 <i>ma-na</i> 20] GÍN KI.LAL 4 TÚG.ÚR.MEŠ [šá <sup>d</sup> UTU]					
	4'. [1 <i>ma-na</i> 10] GÍN KI.LAL 7 TÚG.ÍB:NÍG.LÁ.MEŠ š[á <sup>d</sup> UTU]					
	5'. [1 <i>ma-na</i> K]I.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ <i>š</i> [á <sup>d</sup> A-a]					
	6'. [2 ma-na] KI.LAL TÚG.ḤI.A ù <sup>túg</sup> ṣib-tu <sub>4</sub> 1/3 GÍN KI.LAL [TÚG.ÚR šá <sup>d</sup> ḤAR]					
	7'. [] KI.LAL TÚG.N					
Rest lost Rev. Only	8'. [] KI.LAL []					
	1–2 signs at the end of 4 lines are preser 1'. [] $\delta a^{rd_1}$ [ 2'. [] $^r x^1 - ba^2$ 3'. [] $^r x^1 - e$ 4'. [] $^r x^1 - e$ 5'. [] $^r x^1$	rved.				
It was a quite long free space between the name of the garments and the name of the gods written probably at the very end of each line.  L. 6'. For the filling the gap, compare BM 72875 (= 118): 10–11.						
[x mina, the weight of] the <i>şibtu</i> -garment [for Šamaš]						
[2 minas, the weight of] the <i>lubār mē qaqqadi</i> -headdress [for Šamaš]						

```
[1 mina 20 shekels], the weight of 4 sūnu-belts [for Šamaš]
-----
[1 mina 10] shekels, the weight of 7 sashes f[or Šamaš]
[1 mina, the we]ight 10 sashes fo[r Aya]
[2 minas,] the weight of the lubāru and sibtu-garments (and)
20 shekels, the weight of the [sūnu-belt for Bunene]
_____
[....], the weigth of [....]
                       -----
[....], the weigth of [....].
99. BM 67970 (82-9-18, 7968)
5.2 \times 4.2 (thick 3.0) cm
            1'. [x x x x]^{\lceil x \rceil} [....]
            2'. 「20<sup>!</sup>」 ½ ma-na KI.LAL TÚG.ḤA.A 「šá¹ [dUTU]
            3'. [2] ma-na KI.LAL TÚG.HA.A me-<sup>r</sup>e<sup>1</sup> [SAG.DU šá <sup>d</sup>UTU]
            4'. [1 1/3 m]a-na KI.LAL 4 <sup>túg</sup>su-[ni-e šá <sup>d</sup>UTU]
            5'. [1 ma-na] 10 GÍN KI.LAL [7] [TÚG.NÍG.ÍB.LÁ.MEŠ
                  šá <sup>d</sup>UTU]
            6'. [x \times x \times x] [KI^{?}] [....]
Rest lost
            1'. [x x x x] ^{\mathsf{T}} x x^{\mathsf{T}} 6 [....]
Rev.
            Free space for about 3-4 lines
            2'. [x x x x^{1} f x x x^{1} [...]
Rev. 2'. Only very upper parts of three signs are preserved.
[20<sup>!</sup>] ½ mina, the weight of the lubāru-garment for [Šamaš]
[2] minas, the weight of] the lubār mē [qaqqadi-headdress for Šamaš]
[1 mi]na [20 shekels], the weight of 4 s\bar{u}[nu\text{-belts for Šamaš}]
[1 mina] 10 shekels, the weight of 7 [sashes for Šamaš].
. . . . . . . . . . . . . .
100. CT 55, 855 = BM 58491
            1'. [....] <sup>[</sup>x<sup>]</sup>
            2'. [2 ma-na KI.LAL TÚG].HI.A SA[G.DU šá <sup>d</sup>UTU]
            3'. [1 ma-na 10 GÍN KI.LAL] 7 TÚG.NÍG.Í[B.LÁ.MEŠ]
                               šá <sup>d</sup>UTU
            5'. [1 ma-na 1/3 GÍN KI].LAL 4 TÚG.ÚR.[MEŠ šá <sup>d</sup>UTU]
            6'. [1 ma-na KI.LAL 10 T]ÚG.NÍG.ÍB.LÁ.MEŠ
```

```
Rev. 8'. [1 ma-na 10 GÍN KI.LA]L^{!} 1^{en} TÚG.ÚR 9'. [10 TÚG.NÍG.ÍB.LÁ.MEŠ \check{s}\acute{a}] ^{d}IM u ^{d}\check{S}\acute{a}-la 10'. [2 ma-na KI.LAL TÚG.ḤI].A ^{t\acute{u}g}\check{s}ib-tu_4 11'. [\check{s}\acute{a}] ^{f^d}1Bu-ne-ne 12'. [....] ^{f^e}1-lat 20 G[ÍN^{?} 13'. [....] 6 ^{f}x^{1} [....] 14'. [....] ^{f}te^{?}1 [x x] Rest lost [2 minas, the weight of the lub]\bar{a}r <m\bar{e}> qa[qqadi-headdress for Šamaš [1 mina 10 shekels, the weight of] 7 sash[es] for Šamaš [1 mina, the weight of 10] sashes for Aya [1 mina 10 shekels, the weight of 1 s\bar{u}nu-belt, [10 sashes] for Adad and Šala [2 minas, the weight of the lub\bar{a}]ru (and) sibtu-garments [for] Bunene [....] except for 20 shek[els ....] 6 [....].
```

#### GARMENTS FOR CYCLE B

## 5. Garments for the Ulūlu *lubuštu* ceremony

```
101. CT 55, 845 = BM 57776
2.6.Nbk [x]
```

- 1. [x+] 1 *ma-na* KI.LAL TÚG.<sup>[x]</sup>[....]
- 2. [x *ma*]-*na* 10 GÍN KI.LAL 1<sup>en</sup> [....]
- 3. [x *ma*]-*na* 5 GÍN KI.LAL [1<sup>en</sup>][....][
- 4. [x ma-na KI.LAL TÚG me] SAG.DU 4 TÚG.ÚR.M[EŠ  $\check{s}\check{a}^{\mathrm{d}}$ UTU]
- 5. [1 ma-na KI.LAL 6 TÚG.NÍG. Í]B.LÁ.MEŠ šá <sup>d</sup>UTU
- 6. [1 ma-na KI.LAL 10 TÚG.NÍG. Í]B.LÁ.MEŠ šá  ${}^{\rm d}A$ -[a]
- 7. [1 ma-na KI.LAL 10 TÚG.NÍG.ÍB].LÁ.MEŠ  $\check{s}\check{a}^{\rm d}$ GAŠAN Sip- $[par^{\rm k}]^{\rm i}$
- 8. [....] <sup>r</sup>x x<sup>1</sup>

Rest lost

Rev.

- 1'. [....] a-na] [É-babbar-ra]
- 2'. [....] *id-di*]*n-nu*

\_\_\_\_\_

- 3'. [x ma-na x GÍ]N KI.LAL [mut]-ta-t[i]
- 4'. [1 ma-na 10] GÍN KI.LAL {KI.LAL}  $1^{en}$  TÚ[G.ÚR]
- 5'. [10 TÚG.NÍG].ÍB.LÁ.MEŠ šá <sup>d</sup>IM u <sup>d</sup>[Ša-la]
- 6'. [mdAG]-EN-MU.MEŠ lúUŠ.BAR
- 7'. [a-na É DINGIR it-t]a-din [IT]I.KIN U<sub>4</sub>.2.KAM [MU.x.KAM]
- 8'. [<sup>md</sup>AG-NÍ]G. DU'-ÙRU LUGAL E<sup>[ki]</sup>
- L. 3. Because in l. 4 the *lubār mē qaqqadi* is mentioned, in the lines above we expect the *şibtu* and the *lubāru* for Šamaš, however, because of the atypical quantity it is not certain and l. 3 has no parallels.

.....

[x mina(s) x shek]els, the weight of the *muttatu*-headdress

[1 mina(s) 10] shekels, the weight of 1 [sūnu-belt] (and)

[10 sash]es for Adad and [Šala]

[Nabû]-bēl-šumāti, the weaver [has deli]vered [to the house of the god. Mo]nth Ulūlu, 2<sup>nd</sup> day, [n<sup>th</sup> year of Nebu]chadnezzar, king of Babylon.

## 102. BM 61916 (82-9-18,1885)

 $6.7 \times 5.6$  cm

## 30.[5].Nbn 11

- 1. [dul-lu BABBAR<sup>ú</sup> šá lu-bu]-uš-<tu<sub>4</sub>> šá ITI.KIN <sup>md</sup>AG-DU-A 2. [SUM<sup>na</sup> ITI.NE U]<sub>4</sub>.30. KAM MU.11.KAM <sup>md</sup>AG-I LUGAL E<sup>ki</sup> 3. [20 ma-na KI.LAL TÚG.ḤI.A] šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA 4. [10 ma-na KI.LAL <sup>túg</sup>sib-t]u<sub>4</sub> šá <sup>d</sup>UTU · -5. [2 ma]-[na KI].[LAL T]ÚG.[HI].[A me SAG.D]U [šá] [d]UTU \_\_\_\_\_\_ 6. [1 ma-na] <sup>1</sup>/<sub>1</sub>/<sub>3</sub> GÍN KI.LAL <sup>4</sup> TÚG.ÚR.<MEŠ> šá <sup>d</sup>UTU u  $[^{d}A-a]$ 7. [1 ma-na] KI.LAL 6 hu-ṣa-ni-e šá <sup>d</sup>UTU \_\_\_\_\_ 8. [x ma-na K]I.LAL TÚG. [x] šá d!U[TU] \_ \_ \_ **. . . .** 9. [1 *ma-na* KI.LAL] 10 *ḥu-ṣa-ni-e šá* <sup>d</sup>гА-а<sup>1</sup> 10. [2 ma-na KI.LAL TÚG.HI.A u] [túgsib]-tu<sub>4</sub> [šá] <sup>d</sup>B[u-ne]-ne 12. [1 ma-na KI.LAL 10 hu-ṣa-ni-e šá] dGAŠAN Sip-parki
- Edge Rev.

-----

13. [1 ma-na 10 GÍN KI.LAL 1 TÚG]. 「ÚR ì ù 10 hu-ṣa-「ni-e ì [šá <sup>d</sup>IM u] <sup>d</sup>Ša-la

- 15. [½ ma-na 5] 「GÍN¹ KI.LAL 1<sup>en</sup> TÚG.ÚR 「ù¹
- 16. [5]  $\lceil hu \rceil$ -sa-ni-e  $\langle \check{s} \acute{a} \rangle$   $^{\mathrm{d}} G[u-l]a$

The tablet is joined from two pieces along line 5, which is heavily damaged. The graymuddy colour of the tablet hinders its reading.

L. 8. This badly preserved line has no parallels in other texts.

[White work for the *lubu*]štu ceremony of the month Ulūlu, (which) Nabû-mukīnapli has delivered. Month of Abu], 30th day, 11th year of Nabonidus, king of Babylon.

[20 minas, the weight of the lubāru]-garment for Šamaš, with addition of ½ minas of purple wool [10 minas, the weight of the sib]tu-garment for Šamaš [2 mi]nas, the wei[ght of the lu]bā[r mē qaqqadi-headdress for] Šamaš [1 mina] 20 shekels, the weight of 4 sūnu-belts for Šamaš and [Aya] [1 mina], the weight of 6 sashes for Šamaš [x mina, the wei]ght of [....] for Šamaš [1 mina, the weight of] 10 sashes for Aya [2 minas, the wei]ght of [the lubāru and] sibtu-garments for B[une]ne [1 mina, the weight of 10 sashes for] the Queen of Sippar [1 mina 10 shekels, the weight of 1] sūnu-belt and 10 sashes [for Adad and] Šala [35] shekels, the weight of 1 sūnu-belt and [5] sashes <for> G[ul]a. **103. BM 76771** (83-1-18, 2143)  $4.4 \times 6.5$  cm  $30.[x.Nb]^{r}n\ 10+x^{3}$ 1'. [....  $^{m}La$ ]-ba- $^{\Gamma}a$ - $\check{s}i$   $^{1\acute{u}}x$  $^{7}$  [....] 2'. [....] U<sub>4</sub>.30.KAM MU.<sup>[</sup>10+x<sup>]</sup>.[KAM] 3'. [mdAG]- 'I' LUGAL TIN. 'TIR' [ki] 4'. [20 ma-na KI.LAL TÚG.HI.A šá <sup>d</sup>UTU] 5'. [ina lìb-bi ½ ma-na] SÍG.[ZA].GÌN.KUR.RA 6'. [10] *ma-na* KI.LAL <sup>túg</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>UTU 7'. [1] ma-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>rd</sup>¹[UTU] \_\_\_\_\_\_ 8'. [2] ma-na KI.LAL TÚG.ḤI.A me SAG.[DU šá <sup>d</sup>UTU] \_\_\_\_\_ 9'. [1] *ma-na* 1/3 GÍN KI.LAL 4 [TÚG.ÚR.MEŠ]  $\check{s}\acute{a}^{\rm d}$ UTU  $u^{\rm d}A$ -[a] 11'. [1] ma-na KI.LAL 10 TÚG.NÍG.Í[B.LÁ.MEŠ] Rev. 12'. *šá* <sup>d</sup>*A-a* 13'. [1] ma-na 1/3 GÍN KI.LAL TÚG.HI.A 14'. [šá] <sup>d</sup>HAR ina lìb-bi 6 GÍN SÍG.ZA.GÌN.<KUR>.R[A]

## 15'. <sup>[2/3]</sup> ma-na KI.LAL <sup>túg</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>Ḥ[AR] 16'. [1 m]a-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 17'. [šá] <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> 18'. [PAP ½] GÚ.UN 7 5/6 ma-na 4 GÍN 19'. [dul-l]u<sup>?</sup> gam-mar it-ta-din a-na 20'. [x GÚ.U]N 53 ma-na 12 GÍN S[ÍG.HI.A] 21'. [x x x m]a-na 8 $^{?}$ GÍN SÍG.HI.A [x $x^{j}$ 22'. $[x x x x x x SU]M^{nu}$ L. 21. The numeral 8 is written 4 under 4. [....] Lābāši, the [.... has delivered. Month x] 30<sup>th</sup> day, 11+x year of [Nabo]nidus, king of Babylon. [20 minas, the weight of the *lubāru*-garment for Šamaš, with addition of ½ mina] of blue-purple wool [10] minas, the weight of the *şibtu*-garment for Šamaš \_\_\_\_\_ [1] mina, the weight of 6 sashes for [Šamaš] ..... [2] minas, the weight of the *lubār mē qaq[qadi-headdress for Šamaš]* \_\_\_\_\_ [1] mina 20 shekels, the weight of 4 [sūnu-belts] for Šamaš and Ay[a] [1] mina, the weight of 10 sas[hes] for Aya [1] mina 20 shekels, the weight of the *lubāru*-garment [for] Bunene, with addition of 6 shekels of blue-purple wool 40 shekels, the weight of the *şibtu*-garment for Bu[nene] -----

ered. For [x talen]t 53 minas 12 shekels of w[ool .... (and x mi]na(s) 8 shekels of wool [....] was given.

[Total ½] talent 7 minas 54 shekels, the completed w[ork] he (Lābāši) has deliv-

**104. Cyr 201** = BM 75202; cf. Salonen, NUVI 3, No.118; Giovinazzo 1981, No.10 Collated

[1 mi]na, the weight of 10 sashes [for] the Queen of Sippar

[x.x].Cyr 5

- 1. [dul-lu] BABBAR $^{\acute{u}}$  šá lu-bu-uš- $tu_4$  šá  $U_4$ .3.KAM šá ITI.KIN
- 2.  $[\check{s}\acute{a} \times \times \times]$  A- $\check{s}\acute{u}$   $\check{s}\acute{a}$   $^{md}$ AG-DU  $^{l\acute{u}}$ UŠ.BAR id-din ina muh-hi
- 3. [U<sub>4</sub>.3.KAM šá<sup>?</sup>] MU.5.KAM <sup>m</sup>Ku-ra-áš LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

\_\_\_\_\_

- 4. [20 ma-na] 「KI¬.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA
- 5. [10 ma]-<sup>r</sup>na<sup>1</sup> KI.LAL TÚG.MÁŠ\* šá <sup>d</sup>UTU
- 6. [2 ma]-na KI.LAL TÚG.HI.A SAG.DU šá <sup>d</sup>UTU
- 7. [1 ma]-na 1/3 GÍN KI.LAL 4 TÚG.ÚR.MEŠ šá <sup>d</sup>UTU
- 8. [1 ma]-na KI.LAL 6 NÍG:TÚG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
- 9. [2 ma]-na 1/3 GÍN KI.LAL TÚG SAG šá <sup>d</sup>UTU <sup>m</sup>Ba-ku-<sup>r</sup>ú¹-a it-ta-din
- 10. [1 m]a-na KI.LAL 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a
- 11. [1]+ <sup>[1]</sup> ma-na KI.LAL TÚG.ḤI.A ù TÚG.MÁŠ\* šá <sup>d</sup>ḤAR ina lìb-bi [6 GÍN]
- 12. SÍG.ZA.GÌN.[KUR.RA]
- 13. [1] ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá $^{\mathrm{d}}\mathrm{GAŠAN}$   $Sippar^{[\mathrm{ki}]}$

Rev. 14. <sup>1</sup>/<sub>3</sub> GÍN KI.LAL TÚG. <sup>1</sup>ÚR <sup>1\*</sup> <sup>1</sup>5\* GÍN KI.LAL 5! (T: 10) TÚG. NÍG. ÍB.LÁ. MEŠ

.5. šá <sup>d</sup>Gu-la

16. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 1/3 GÍN KI.LAL TÚG.ÚR

17.  $\check{s}\check{a}^{\mathrm{d}}\mathrm{IM}\;u^{\mathrm{d}}\check{S}a^{-1}la^{-1}$ 

18. PAP 5<sup>!</sup> 2/3<sup>!</sup> ma-na 5 GÍN dul-lu <sup>m</sup> Ba-kú¹-ú-a it-ta-din

- L. 5 and 11. Contra Strassmaier's copy, MÁŠ sign has typical Neo-Babylonian shape.
- L. 8. Salonen, NUVI 3, No.118 read 6 4 TÚG.ÍB.LÁ.MEŠ. In fact the scribe wrote mistakenly NÍG.TÚG instead of TÚG.NÍG.
- L. 9. For the reconstruction of the numeral, cf. BM 63993 (= 106): 15.
- L. 11. The reconstruction of <sup>1</sup>6<sup>1</sup> [GÍN], opposed to 2 [*ma-na*] suggested by Salonen, NUVI 3, No.118, is based on the fact that 6 shekels of blue-purple wool was used for the manufacturing of the *lubāru* of Bunene, see Zawadzki, *Garments of the Gods*, Vol. I, p. 88.
- L. 14. The numeral 10, emended to 5, is evidently the scribe's mistake because Gula received only 5 *husannus* weighing 3 shekels each, i.e. a total of 15 shekels, confirmed by the badly preserved, but still readable numeral [15].
- L. 18. The numeral preceding 2/3 is written over an erasure. Bongenaar, *Ebabbar*, p. 353 reads  $4\ 2/3\ ma$ - $na\ 5\ GÍN$ , but I opt for  $5\ 2/3\ ma$ - $na\ 5\ GÍN$ , because it includes the weight of garments beginning from line 10:  $[1\ mina] + {}^{r}2^{1}\ minas + 1\ mina + [20\ shekels] + 15\ shekels + 50\ shekels + 20\ shekels = 5\ minas\ 45\ shekels.$

White [work] for the *lubuštu* ceremony for the 3<sup>rd</sup> day of Ulūlu, (which) [PN], the son of Nabû-ukīn has delivered. For [3<sup>rd?</sup> day], 5<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

[20 minas], the weight of the  $lub\bar{a}ru$ -garment for Šamaš, with addition of ½ minas of purple wool

[10 mi]nas, the weight of the *şibtu*-garment for Šamaš

- [2 mi]nas, the weight of the *lubār*  $< m\bar{e} > qaqqadi$ -headdress for Šamaš
- [1 mi]na 20 shekels, the weight of 4 sūnu-belts for Šamaš
- [1 mi]na, the weight of 6 sashes for Šamaš

 $[2\ mi]$ nas  $20\ shekels$ , the weight of the SAG-garment, (which) Bakûa has delivered

[1 mi]na, the weight of 10 sashes for Aya

- 2 minas, the weight of the  $lub\bar{a}ru$  and sibtu-garments for Bunene, with addition of 6 shekels of blue-pur[ple wool]
- [1] mina, the weight of 10 sashes for the Queen of Sippar
- 20 shekels, the weight of the *sūnu*-belt
- 15 shekels, the weight of 5' sashes for Gula
- 50 shekels, the weight of 10 sashes
- 20 shekels, the weight of the *sūnu*-belt for Adad and Šala

Total 5<sup>!</sup> minas 45 shekels, the work which Bakûa has delivered.

## **105. BM 70333** (82-9-18, 10334)

 $4.8 \times 3.6$  cm

## 30.5.Cyr [x]

- 1. dul-lu BABBARi šá lu-bu-uš-[tu4]
- 2.  $\delta a^{md}I$ - $\delta um$ - $D\dot{U}u^{m}La$ -qip-[pi]
- 3. id-din-nu ITI.NE U<sub>4</sub>.30.KAM [MU.x.KAM]
- 4. <sup>m</sup>Ku-ra-áš LUGAL

-----

- 5. 20 ma-na KI.LAL TÚG[.HI.A šá <sup>d</sup>UTU]
- 6. 10 ma-na KI.LAL si[b-tu<sub>4</sub> šá <sup>d</sup>UTU]
- 7. <sup>r</sup>2 *ma*<sup>1</sup>-[*na* KI.LAL TÚG.ḤI.A SAG.DU <sup>d</sup>UTU]

Rest lost

Rev.

- 1'. [x x] [....]
- 2'. ½ ma-na K[I.LAL ....]
- L. 2. Maybe the same Išum-ibni appears in BM 83329 (= 149):  $1 \binom{md}{I-\delta[um-x]}$ .

White work for the *lubuš*tu ceremony, which Išum-ibni and Lāqīpi have delivered. Month of Abu, 30<sup>th</sup> day [n<sup>th</sup> year] of Cyrus, king.

\_\_\_\_\_

20 minas, the weight of the *lub*[āru-garment for Šamaš]

10 minas, the weight of the *şi[btu*-garment for Šamaš]

2 mi[nas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš]

.....

½ mina, the wei[ght of ....]

## **106. BM 63993** = Bertin 1867

 $9.4 \times 6.2$  cm

## 1.6.Cam 5

1. *dul-lu* BABBAR<sup>ú</sup> šá TÚG.ḤI.A šá U<sub>4</sub>.3.KAM šá ITI.[KIN] 2. šá <sup>m</sup>Kal-ba-a <u> <sup>md</sup>UTU-NUMUN-BA<sup>šá lú</sup>UŠ.BAR.MEŠ *id-din-*<sup>r</sup>nu<sup>1</sup> Rev.

- 3. ITI.KIN U<sub>4</sub>.1.KAM MU.5.KAM <sup>m</sup>Kam-bu-zi-ja
- 4. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

5. 20 ma-na KI.LAL TÚG.UD.A šá

<sup>d</sup>UTU

6. 10 ma-na KI.LAL <sup>rtúg</sup>ṣib¹-tu₄ šá

 $^{\rm d}$ UTU

- 7. 1 ma-na KI.LAL 6 TÚG.NÍG.ÍB.L[Á.MEŠ] šá <sup>d</sup>UTU
- 8. 2 ma-na KI.LAL TÚG.UD.A me SAG šá <sup>d</sup>[UTU]
- 9. 1 1/3 ma-na KI.LAL 4 TÚG.ÚR.MEŠ šá [<sup>d</sup>UTU]
- 10. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá [dA-a]
- 11. 2 ma-na KI.LAL TÚG.UD.A <sup>túg</sup>ṣib-t[u<sub>4</sub> šá <sup>d</sup>ḤAR]
- 12. 1 ma-na KI.LAL 10 TÚG.[NÍG.ÍB.LÁ.MEŠ šá dGAŠAN Sip-

par<sup>ki</sup>l

13. ½ ma-na KI.LAL ku-lu(T:ṭu)-lu [u me-ṭu šá  $^{\rm m}$ Kal-ba-a] 14.  $u^{\rm md}$ UTU-NUMUN-BA Šá [ $^{\rm l\acute{u}}$ UŠ.BAR.MEŠ SUM $^{\rm nu}$ ]

One line free

15. 2 1/3 ma-na KI.LAL TÚG SAG <sup>d</sup>UTU <sup>m</sup>rÌR¹- <sup>d</sup>EN

16. <sup>lú</sup>UŠ.BAR

17. <sup>[50]</sup> GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>IM

- L. 1. Note that the word *lubuštu* is replaced here with TÚG.ḤI.A, which is usually translated
- L. 9. The numeral 4 is written over erasure.
- L. 13. Bongenaar, Ebabbar, p. 349 identifies Šamaš-zēr-iqīša as belonging to the išpar birme group, and Kalbā, as the son of Kabtīya, the išparu (p. 328). However, because at the same time another Kalbā, the išpar birme was active, I suggest identifying our Kalbā with the second one.

L. 15. Cf. Cyr 201 (= 104): 9.

White work for the *lubuštu* ceremony for the 3<sup>rd</sup> day of the month [Ulūlu], which Kalbā and Šamaš-zēr-iqīša, the weavers have delivered. Month of Ulūlu, 1<sup>st</sup> day, 5<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

20 minas, the weight of the *lubāru*-garment for Šamaš

10 minas, the weight of the *sibtu*-garment for Šamaš

1 mina, the weight of 6 sash[es] for Šamaš

2 minas, the weight of the *lubār mē qaqqadi*-headdress for [Šamaš]

1 mina 20 shekels, the weight of 4 *sūnu*-belts for [Šamaš]

1 mina, the weight of 10 sashes for [Aya]

2 minas, the weight of the *lubāru*-garment and *şib[tu*-garments for Bunene]

1 mina, the weight of 10 s[ashes for the Queen of Sippar].

½ minas, the weight of the < lubār> kulūlu [and < lubār> mēţu-headbands, which Kalbā and Šamaš-zēr-iqīša, [the weavers have delivered].

2 minas 20 shekels, the weight of the SAG-garment for Šamaš, Arad-Bēl, the weaver (has delivered).

50 shekels, the weight of 10 sashes for Adad and Šala.

## **107. BM 65159** (82-9-18, 5140)

PLATE 28

 $8.4 \times 6.7$  cm

#### 2.6.Dar 23

- 1. [dul]- $[lu BABBAR^{\acute{u}} < \check{s}\acute{a} > lu-bu-u\check{s}^{\dagger}-tu_4 \check{s}\acute{a} U_4.2[+1.KAM]$
- 2. [šá IT]I.KIN U<sub>4</sub>.[x.KAM] MU.23.KAM <sup>md</sup>UT[U-MU-MU<sup>?</sup>]
- 3. [ $^{\text{lú}}$ ]UŠ.BAR it-[ta-din] ITI.KIN U<sub>4</sub>.2.KAM  $^{\text{r}}$ MU $^{\text{l}}$ .[23.KAM]
- 4. <sup>rm</sup>Da-ri-mu¹-šú LU]GAL TIN.TIR<sup>ki</sup> LUGAL KUR.[KUR]
- 5. [20 ma-na K]I.LAL TÚG.UD.A šá  $^{\rm d}$ UTU
- 6. 10 m[a-na K]I.LAL ṣib-tu<sub>4</sub> šá <sup>d</sup>UTU
- 7. [2 ma-na KI].LAL TÚG.UD.A me-si-iq [šá <sup>d</sup>UTU]
- 8. [1 ma-na] KI.LAL 6 ḫu-ṣa-nu<sup>meš</sup>
- 9. [1 ma-na 1/3] 「GÍN¹ KI¹.LAL 4 TÚG.ÚR.[MEŠ šá <sup>d</sup>UTU]
- 10. [1 *ma-na* KI.LAL 10 TÚG].NÍG¹.ÍB¹.[LÁ. MEŠ šá <sup>d</sup>A-a]

#### Rest lost

The beginning of the reverse is lost, however, there may have been no more than 2-3 lines, because about 90% of the original measurement is preserved and is uninscribed. Only one sign, perhaps a ku exists.

- L. 2. The badly preserved day date seems redundant.
- L. 9. KI is written over easy recognizable ÚR.

L. 10. The first fragmentarily preserved sign looks like *me* and the second like SAG, however, we expect here 10 *huṣannus* for Aya.

White work for the *lubuštu* ceremony for the <sup>r3¹rd</sup> day of the month Ulūlu [....], 23<sup>rd</sup> year Šamaš-[šum-iddin]², the weaver has deli[vered]. Month of Ulūlu, 2<sup>nd</sup> day, [23<sup>rd</sup> year] of Dari[us, ki]ng of Babylon, king of Lands.

[20 minas, the wei]ght of the *lubāru*-garment for Šamaš

10 mi[nas, the welight of the *sibtu*-garment for Šamaš

10 milinas, the welight of the *stotu*-garment for Samas

[2 minas, the wei]ght of the *lubār mēsiqu*-headdress [for Šamaš]

[1 mina], the weight of 6 sashes

[1 mina 20] shekels, the weight of 4 sūnu-belt[s for Šamaš]

\_\_\_\_\_

[1 mina, the weight of 10 sa]she[s for Aya].

## **108. CT 55, 806** = BM 56099 Collated

<sup>[1]</sup>.6.[KN x]

- 1. dul-lu BABBAR[ $^{\acute{u}}$  šá lu-bu-uš-tu4 šá ITI.KIN U4.3.KAM  $^{md}$ AG- $\dot{\mathbf{U}}$ RU-A]
- 2.  $^{\text{lú}}$ UŠ.BAR  $i[t^?$ -ta-din ....]
- 3. ITI.KIN U4.  $^{1}$ 1.KAM MU $^{1}$ . [x.KAM KN LUGAL  $B\bar{a}bili$  (LUGAL KUR.KUR)

\_\_\_\_\_

4. 20 ma-na KI.LAL TÚG.ḤI.A šá $^{\rm d}$ UTU ina 「lìb-bi¹ [½ ma-na

	SÍG.ZA.GÌN.KUR.RA]
	5. 10 ma-na KI.LAL <sup>túg</sup> ṣib-tu <sub>4</sub> šá <sup>d</sup> UTU
	6. 1 ma-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> UTU
	7. 1 <i>ma-na</i> KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup> [ <i>a</i> ]
	8. 2 ma-na KI.LAL TÚG.ḤI.A me SIG <sup>qá</sup> /.GA šá <sup>d</sup> [UTU]
	9. 2 ½ ma-na KI.LAL 5 su-ni-e šá <sup>d</sup> [DN]
Edge Rev.	10. 1 ma-na 1/3 GÍN KI.LAL TÚG.ḤI.A šá <sup>d</sup> Bu-n[e-ne] 11. ina lìb-bi 6* GÍN SÍ[G.ZA.GÌN.KUR.RA]
	12. 2/3* ma-na KI.LAL <sup>túg</sup> ṣib-tu <sub>4</sub> šá <sup>d</sup> [Bu-ne-ne]
	13. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB. <lá>.MEŠ šá <sup>d</sup>[GAŠAN Sip-par<sup>ki</sup>] 14. PAP ½ GÚ.UN 「81 ma-na dul*-l[u*gam-ru]</lá>
	15. 2 ma-na 1/3 GÍN KI.LAL <sup>túg</sup> mu-[ut-ta-tu <sub>4</sub> ] 16. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.[LÁ.MEŠ šá <sup>d</sup> IM u <sup>d</sup> Ša-la] 17. 15 GÍN KI.LAL 5 TÚG.NÍG.Í[B.LÁ.MEŠ šá <sup>d</sup> Gu-la] 18. 5/6 ma-na KI.LAL 2 TÚG [] 19. u* 「5/6¹ ma-na 「KI.LAL x¹[] 20. <sup>md</sup> AG-ÙRU-「A¹ ¹[ <sup>ú</sup> UŠ.BAR]
read <sup>191</sup> (r that 2,5 m this positi accept suc Šamaš and L. 13. The	weight of items from lines 4–13 is 39 minas 30 shekels. Although in 1. 14 we can also not $^{81}$ ) <i>ma-na</i> , the result of adding them together is 30 shekels lower than the total. Note ina as the weight of 5 $s\bar{u}nu$ , i.e. 30 shekels per each $s\bar{u}nu$ is atypical; usually we have in on 4 $s\bar{u}nu$ weighing 1 mina 20 shekels, i.e. 20 shekels for each $s\bar{u}nu$ . However, if we chan emendation, we do not reach the total from 1. 14. In 1. 9 we expect the $s\bar{u}nu$ s for d Aya and maybe one for Bunene. The numeral is written over erasure; it looks like 1 written over 10. The numeral $^{1}5/6^{1}$ is preceded by sign $u$ , or 10.
White w	ork [for the <i>lubuštu</i> ceremony for the 3 <sup>rd</sup> day Ulūlu, (which) Nabû-nāṣir-e weaver h[as delivered]. Month Ulūlu, 1 <sup>st</sup> day, year [
	s, the weight of the $lub\bar{a}ru$ -garment for Šamaš with addition of [½ mina of ple wool]

10 minas, the weight of the *ṣibtu*-garment for Šamaš

1 mina, the weight of 6 sashes for Šamaš		
1 mina, the weight of 10 sashes for [A]ya		
2 minas, the weight of the <i>lubār mēsiqu</i> -headdress [for Šamaš]		
2 ½ mina, the weight of 5 sūnu-belts for [DN]		
1 mina 20 shekels, the weight of the <i>lubāru</i> -garment for Bun[ene] with addition of 6 shekels of [blue-purple wool]		
40 shekels, the weight of the <i>şibtu</i> -garment for [Bunene]		
1 mina, the weight of 10 sashes for [the Queen of Sippar] Total 38 minas, the [completed] work []		
2 minas 20 shekels, the weight of the <i>mu</i> [ <i>ttatu</i> -headdress] 50 shekels, the weight of 10 sash[es for Adad and Šala] 15 shekels, the weight of 5 sashe[s for Gula] 50 shekels, the weight of 2 [] and 50 shekels, the weight of [ which] Nabû-nāṣir-apli, [the weaver has delivered].		
<b>109. BM 59227</b> (82-7-14, 3636) 3.2 × 2.9 cm		
	<ol> <li>dul-lu BABBAR<sup>ú</sup> šá [lu-bu-uš-tu<sub>4</sub>]</li> <li>šá ITI.KIN U<sub>4</sub>.3.KAM []</li> <li>šá <sup>m</sup>Kal-ba-a <sup>lú</sup>ΓUŠ.BAR it¹-[ta-din]</li> </ol>	
Post lost	4. [20 ma-n]a KI.LAL TÚG.UD.A [šá <sup>d</sup> UTU] 5. [10] <sup>r</sup> ma-na <sup>1</sup> [KI.LAL] <sup>túg</sup> ṣib-tu <sub>4</sub> šá [šá <sup>d</sup> UTU]	
Rest lost Rev.	1'. nothing is here preserved	
	2'. 1 ma-na KI.LAL 10 TÚG.NÍG. Í[B.LÁ.MEŠ <i>šá</i> <sup>d</sup> DN]	
Rest of rev. uninscribed		
White work [for the <i>lubuštu</i> ceremony] for 3 <sup>rd</sup> Ulūlu [], which Kalbā, the weaver has de[livered].		
[20 min]as, the weight of the <i>lubāru</i> -garment [for Šamaš]		
[10] minas, [the weight of] the <i>şibtu</i> -garment [for Šamaš]		
1 mina, the weight of 10 sas[hes for DN].		

```
110. BM 76468 (83-1-18, 1836)
5.2 \times 3.7 \text{ cm}
                         1.6^{?}.[KN x]
             1. dul-lu BABBAR^{u} [(x \times x)^{?}]
             2. lu-bu-uš-t[u4 ....]
             3. 2 ma-na 12 GÍ[N
             4. 20 ma-na [KI]. LAL [TÚG. HI. A šá dUTU]
                    「ina lìb-bi¹ [½ ma-na SÍG.ZA.GÌN.KUR.RA]
             6. 9<sup>?</sup> ma-na KI.LAL <sup>rtúg</sup>1[....]
             7. 5 <sup>5</sup>/6 ma-na [....]
             8. 4 <sup>túg</sup>[....]
             9. 10 TÚ[G ....]
             1'. 1 [....]
Rev.
             2'. ½ ma-n[a ....]
             3'. blank [....]
             4'. síg mu-ta-tu4 [....]
             5'. šá <sup>d</sup>IM u <sup>d</sup>[Ša-la]
             6'. 30 GÚ.UN 6 5/6 ma-n[a ....]
             7'. \hat{u}^{\text{md}}U+GUR-\check{S}E\check{S}-M[U....]
             8' <sup>[30]</sup> 1/3 ma-na 6 GÍ[N ....]
             9'. ITI.<sup>r</sup>KIN<sup>?</sup><sup>1</sup> U<sub>4</sub>.1.KAM [....]
           10'. blank LUGAL TIN.[TIR<sup>ki</sup> ....]
Edge
Beginning of rev. 8' is written over erasure.
White work for [.....] the lubuš[tu ceremony ....]
2 minas 12 shek[els ....]
20 minas, [the wei]ght of the [lubāru-garment for Šamaš with addition of [½ mina
of blue-purple wool]
9<sup>?</sup> minas, the weight of [....]
5 minas 50 shekels [....]
4 [...]-garments [....]
10 [...]-garments [....]
.....
1 [....]
½ [mina ....]
the muttatu-headdress [....]
for Adad and [Šala]
30 talents 6 minas 50 sheke[ls ....]
```

```
and Nergal-aḫa-idd[in ....]
30 minas 26 shek[els ....]
Month of Ulūlu, 1<sup>st</sup> day [n<sup>th</sup> year of KN], king of Ba[bylon ...].
```

#### 6. Garments for the Tašrītu *lubuštu* ceremony

# **111. CT 55, 841** = BM 57451 Collated

#### 5.7.Nbn 5

- 1. [dul-lu] BABBAR<sup>i</sup> šá [lu-bu]-uš- $tu_4$  šá  $U_4$ .7. [KAM šá] ITI.D $U_6$ \*
- 2. [šá <sup>m</sup>] dAG-EN-MU.MEŠ a-na É-babbar-ra id-din-nu
- 3. ITI.DU $_6$ U $_4$ .5.KAM MU.5.KAM  $^{md}$ AG-I LUGAL  $^{\Gamma}E^{ki}$
- 4. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.<KUR>.[RA]
- 5. [10 ma-n]a KI.LAL TÚG.MÁŠ šá <sup>d</sup>UTU
- 6. [2 ma-na K]I.LAL TÚG me SAG.DU šá <sup>d</sup>UTU
- 7. [1 ma-na K]I.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
- 8. [1 ma-na KI].LAL 10 TÚG.NÍG.ÍB.LÁ.「MEй šá <sup>d</sup>A-a
- 9. [2 ma-na KI.LA]L<sup>!</sup> TÚG.ḤI.A ù MÁŠ šá <sup>d</sup>ḤAR
- 10. [1 ma-na KI.LA]L 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 11. [1 ma-na KI.LA]L [10] TÚG.<NÍG>.ÍB.LÁ.MEŠ šá dA-nu-ni-tu4

Edge

12. [50 GÍN KI.LAL 10] 'TÚG'!.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>IM <*u* <sup>d</sup>Š*a-la*>

Rev. uninscribed

[White] work for the [*lubu*]*štu* ceremony for the 7<sup>th</sup> Tašrītu, [which] Nabû-bēlšumāti has delivered to the Ebabbar temple. Month of Tašrītu, 5<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, king of Babylon.

20 minas, the weight of the  $lub\bar{a}ru$ -garment for Šamaš with addition of ½ mina of blue-purple wool

[10 min]as, the weight of the *şibtu*-garment for Šamaš

- [2 minas, the we]ight of the lubār mē qaqqadi-headdress for Šamaš
- [1 mina, the we]ight of 6 sashes for Šamaš
- [1 mina, the we]ight of 10 sashes for Aya
- [2 minas, the weig]ht of the *lubāru* and *sibtu*-garments for Bunene
- [1 mina, the weigh]t of 10 sashes for the Queen of Sippar
- [1 mina, the weigh]t of 10 sashes for Anunītu
- [50 shekels, the weight of 10] sashes for Adad < and Šala>.


# **112. BM 62582+BM 65419** (82-9-18, 2551+5405)

PLATE 29

(joined by M. Jursa)  $7.5 \times 5.9$  cm

4.7.Nbn 10

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-<tu<sub>4</sub>> šá ITI.DU<sub>6</sub> <sup>m</sup>Ba-ku-[ú-a]
- 2.  $^{\text{l\'u}}$  aal-la  $\check{s}\acute{a}$   $^{\text{md}}$  AG-na-sir-< A>  $^{\text{l\'u}}$   $U\check{S}$ .BAR it-[ta-din]



1 mina, the weight of 6 sashes for Šamaš			
1 mina <20> shekels, the weight of 4 <i>sūnu</i> -belts for Šamaš and Aya			
1 mina, the weight of 10 sashes for Aya			
1 mina, th	1 mina, the weight of 10 sashes for the Queen of Sippar		
2 minas, the weight of the <i>lubāru</i> and <i>ṣibtu</i> -garments for Bunene with addition of 6 shekels of blue-purple wool			
1 mina, the weight of 10 sashes for Anunītu 20 shekels, the weight of the <i>sūnu</i> -belt for Anunītu			
20 shekel	s, the weight of the <i>sūnu</i> -belt for Gul[a]		
20 shekel	s, the weight of the <i>sūnu</i> -belt for Adad		
50 shekel	s, the weight of 10 sashes for Adad and Šala		
15 shekel	s, the weight of <5> sashes for Gula.		
113. BM 3.3 × 4.0	68982 (82-9-18, 8981) cm [x].7.Nbn 14  1. [dul-lu BABBAR <sup>ú</sup> šá <sup>md</sup> A]G <sup>?</sup> -na-ṣ[ir-A] 2. [a-na lu-bu-uš-tu <sub>4</sub> ] <sup>r</sup> šá <sup>1</sup> ITI.DU <sub>6</sub> it-[ta-din] 3. [ITI.DU <sub>6</sub> U <sub>4</sub> .x.KAM M]U.14.KAM <sup>md</sup> AG-I [LUGAL TIN.TIR <sup>ki</sup> ]		
	4. [20 <i>ma-n</i> ] <i>a</i> KI.LAL TÚG.ḤI.A <i>šá</i> <sup>d</sup> [UTU]		
	5. [10 ma-n]a KI.LAL $^{\text{túg}}$ $sib$ - $t[u_4 šá ^{\text{d}}$ UTU]		
	6. [2 ma]-na KI.LAL TÚG.ḤI.A me [SAG.DU šá <sup>d</sup> UTU]		
Rest lost Rev.	7. [1 <i>ma-n</i> ] <i>a</i> 1/3 GÍN K[I.LAL 4 TÚG.ÚR.MEŠ šá <sup>d</sup> UTU <i>u</i> <sup>d</sup> <i>A-a</i> ] 8. [] <sup>r</sup> x <sup>1</sup> []		
	1'. [x x x] GÍN [] 2'. [x x x] GÍN <i>šá</i> <sup>r</sup> x¹ []		
	3'. [1/3 ma-na KI.L]AL TÚG.ÚR 15 GÍ[N KI.LAL]		

	4'. [5 TÚG.NÍG.ÍB.LÁ.MEŠ šá] <sup>d</sup> Gu-la
	5'. [16 $ma$ - $na$ KI.LAL $^{t\acute{u}g}$ ] $^{\Gamma}$ $sib^{\gamma}$ - $tu_4$ $s\acute{a}$ $^dA$ - $[nu$ - $ni$ - $tu_4$ ]
	6'. No signs preserved.
	ork, which Na]bû-nāṣ[ir-apli] has deli[vered for the <i>lubuštu</i> ] ceremony onth of Tašrītu. [Month of Tašrītu, n <sup>th</sup> day], 14 <sup>th</sup> year of Nabonidus, [king n].
[20 min]as	s, the weight of the <i>lubāru</i> -garment for [Šamaš]
[10 min]as	s, the weight of the sibt[u-garment for Šamaš]
[2 mi]nas,	the weight of the <i>lubār mē</i> [ <i>qaqqadi</i> -headdress for Šamaš]
[1 min]a 2	0 shekels, the wei[ght of 4 <i>sūnu</i> -belts for Šamaš and Aya]
[] sheke [] sheke	ls []
[20 shekels, the weig]ht of the <i>sūnu</i> -belt 15 shek[els, the weight of 5 belts for] Gula	
[16 minas,	the weight of] the <i>şibtu</i> -garment for A[nunītu].
114. BM 6 5.2 × 5.3 c	55503 (82-9-18, 5489) em
	5.7.N[bn] 16
	1. $[dul$ - $lu$ BABBAR $^{\acute{u}}$ šá $lu$ - $b]u$ - $u$ - $s$ - $tu$ 4 šá ITI.DU $_6$ $^{md}$ AG- $na$ - $[sir$ -A] 2. $[^{l\acute{u}}$ UŠ.BAR SUM $^{na}$ IT]U.DU $_6$ U $_4$ .5.KAM MU.16.KAM $^{md}$ A[G-I LUGAL E $^{ki}$ ]
	3. [20 ma-na KI.LA]L TÚG.ḤI.A <ina lìb-bi=""> ½ ma-na SÍG.ZA.GÌN.KUR.<rā> šá [dUTU]</rā></ina>
	4. [10 ma-na KI.LAL] $^{\text{túg}}$ $\hat{s}ib$ -tu <sub>4</sub> $\hat{s}a$ $^{\text{d}}$ [UTU]
	5. [2 ma-na KI.LAL TÚG.ḤI.A] me SAG šá [ <sup>d</sup> UTU]
	6. [1 ma-na KI.LAL 6] TÚG.NÍG.ÍB.LÁ. <meš> šá [<sup>d</sup>UTU]</meš>
	7. [1 ma-na 1/3 GÍN KI.LAL 4 TÚG].ÚR.MEŠ šá [ <sup>d</sup> UTU]
	8. [1 ma-na KI.LAL 10 TÚG].NÍG.ÍB.LÁ.ME[Š šá <sup>d</sup> A-a]

Rest lost

9. [2 ma-na KI.LAL TÚG.ḤI.A] ù  $^{\mathrm{túg}}$ şib-t[u<sub>4</sub> šá  $^{\mathrm{d}}$ ḤAR] 10. [....].<sup>r</sup>ÍB<sup>?</sup><sup>1</sup>[....] Rev. in preserved part uninscribed

[White work for the lub] $u\check{s}tu$  ceremony for the month of Tašrītu, Nabû-nāṣ[ir-apli, the weaver, has delivered. Mon]th of Tašrītu,  $5^{th}$  day,  $16^{th}$  year of Nab[onidus, king of Babylon].

[20 minas, the weig] ht of the *lubāru*-garment for Šamaš <with addition> of ½ mina of blue-purple wool for [Šamaš]

[10 minas, the weight] of the *sibtu*-garment for [Šamaš]

[2 minas, the weight of the *lubār mē qaqqadi*-headdress for [Šamaš]

[1 mina, the weight of 6] sashes for [Šamaš]

-----

[1 mina 20 shekels, the weight of 4] sūnu-belts for [Šamaš] -----

[1 mina, the weight of 10 sa]she[s for Aya]

[2 minas, the weight of the *lubāru*-garment] and *şibt*[*u*-garments for Bunene]

 $[\dots huşa]n[nu-sashes^2 \dots].$ 

# 115. BM 66746 (82-9-18, 6740)

 $4.3 \times 3.3 \text{ cm}$ 

$$[x].7$$
<sup>?</sup>.Nbn  $[x]$ 

1'. [1/3 GÍN] KI.LAL 1<sup>en</sup> TÚG.ÚR [....] 2'. [15 G]ÍN KI.LAL 5 TÚG.<NÍG>.ÍB.LÁ.MEŠ

3'. [šá <sup>d</sup>]*Gu-la* 

4'. [x x x] KI.LAL 1<sup>en</sup> TÚG [....]

5'. [1 ma-na KI.L]AL 10 TÚ[G.NÍG.ÍB.LÁ.MEŠ

Rest lost

Rev.

1'. [IT]I.「DU<sub>6</sub>?¬ U[<sub>4</sub>?.x.KAM]

2'. [MU.x].KAM <sup>md</sup>AG- <sup>T</sup>I

3'. LUGAL 'TIN.TIR' ki

Rev. 1'. The reading of the badly preserved month is uncertain, maybe [IT]I. IŠU 1.

[20 shekels], the weight of 1 sūnu-belt [....] [15 she]kels, the weight of 5 sashes [for Gula

[....], the weight of 1 [....] [1 mina, the wei]ght of 10 s[ashes ....] [Mon]th of Tašrītu<sup>?</sup>, [n<sup>th</sup> d]ay, [n<sup>th</sup> year] of Nabonidus, king of Babylon. **116. BM 64673+BM 66633** (82-9-18, 4653+6626) PLATE 29  $8.3 \times 5.3$  cm 2.7.Cyr <-> 1. dul-luBABBAR $^{\acute{u}}$  šá  $lu\text{-}bu\text{-}u\dot{s}\text{-}tu_4$  šá U[4.7.KAM šá ITI.DU<sub>6</sub>] 2. šá  $^{md}$ AG-PAP-A $^{l\acute{u}}$ UŠ.BAR šá  $^{md}$ UTU-MU-M[U $e\text{-}pi\dot{s}\text{-}\dot{s}\acute{a}\text{-}nu$  $SUM^{nu}$ ] 3. ITI.DU<sub>6</sub> U<sub>4</sub>.2.KAM <sup>m</sup>Kur-raš LUGAL E<sup>ki</sup> LUGAL 「KUR¹.[KUR] 4. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.'KUR.RA 5. [10 m]a-na KI.LAL TÚG.MÁŠ šá <sup>rd</sup>¹UTU 6. <sup>1</sup>2 ma-na KI<sup>1</sup>.LAL TÚG.ḤI.A me SAG šá <sup>d</sup>UTU 7. 1 ma-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>rUTU<sup>1</sup> 8. 1 ma-na 1/3 GÍN KI.LAL 4 TÚG.ÚR.M[EŠ šá <sup>d</sup>UTU] 9. 1 ma-na KI.LAL 「10¹ [TÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{\mathrm{d}}A\text{-}a]$ 10. 2 ma-na KI.LAL [TÚG.ḤI.A TÚG.MÁŠ šá <sup>d</sup>ḤAR] 11. 1 ma-na KI.LAL 10 TÚ[G.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>] 12. 1 ma-na KI.LAL 10 TÚG.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>] Rev. 13. 10 GÍN KI.LAL 1<sup>en</sup> TÚG.[....] 14. 1/3 GÍN KI.LAL 1 $^{en}$  TÚ[G.ÚR  $\check{s}\check{a}^{d}$ DN] 15. 1/3 GÍN KI.LAL [x] (ras.) TÚG.ÚR šá d[Gu-la] 16. 15 GÍN KI.LAL 5 TÚG.NÍG.Í[B.LÁ.MEŠ šá <sup>d</sup>Gu-la] 17. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.M[EŠ šá <sup>d</sup>IM u <sup>d</sup>Ša-la] 18. 1/3 GÍN KI.LAL TÚG.ÚR *šá* <sup>d</sup>I[M<sup>?</sup>]

L. 3. The year is missing in the tablet.

19. 1/3 GÍN dul-lu it-iq it-ta-<sup>r</sup>din<sup>1</sup>

L. 13. For parallels, see BM 61762 (= 167): 12: 10 GÍN SÍG. ḤÉ.ME.DA KI.LAL TÚG.NÍG. İB.LÁ¹ and BM 61938 = 168): 12–12a: 10 GÍN KI.LAL TÚG. NÍG. İB.LÁ / 1 GÍN e-te-qu.

The broken part of 1. 14 might be filled with the name of the Queen of Sippar or Anunītu. L. 15. I decided to fill the broken part of the line with the name of Gula, because the entry (separated from other entries with horizontal lines) usually concerns one god or goddess. L. 19. The sense of the line is not fully clear. Most probably it was an indication that the performer gave back the wool left over after he completed his task.

White work for the *lubuštu* ceremony for [7th Tašrītu] of Nabû-nāṣir-apli, the weaver, which Šamaš-šum-id[din, the performer has delivered]. Month of Tašrītu, 2<sup>nd</sup> day, <nth> year of Cyrus, king of Babylon, king of Lands.

20 minas, the weight of the  $lub\bar{a}ru$ -garment for Šamaš with addition of ½ mina of blue-purple wool

[10 mi]nas, the weight of the *sibtu*-garment for Šamaš

2 minas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš

1 mina, the weight of 6 sashes for Šamaš

1 mina 20 shekels, the weight of 4 sūnu-belt[s for Šamaš]

\_\_\_\_\_

1 mina, the weight of 10 [sashes for Aya]

.....

2 minas, the weight of [the *lubāru* (and) *ṣibtu*-garments for Bunene]

1 mina, the weight of 10 [sashes for the Queen of Sippar]

1 mina, the weight of 10 [sashes for Anunītu]

10 shekels, the weight of 1 [....]

20 shekels, the weight of 1 [sūnu-belt for DN]

·-----

20 shekels, the weight of 1 *sūnu*-belt for [Gula]

15 shekels, the weight of 5 sash[es for Gula]

-----

50 shekels, the weight of 10 sashe[s for Adad and Šala]

20 shekels, the weight of (one) *sūnu*-belt for A[dad<sup>?</sup>]

20 shekels, the missing work, he has delivered.

**117.** Cam 312 = BM 60770; cf. NUVI 3, No. 158 Collated 6.2 x 4.8 cm

PLATE 30

#### 5.7.Cam 6

- 1. [mi]-ih!-su šá-hu-u šá  $^{m}$ ÌR- $^{d}$ EN  $^{lu}$ UŠ.BAR
- 2. [šá] i-ḫi-liq-qu-ma <sup>md</sup>UTU-MU-MU
- 3. *a-na lu-bu-uš-tu*<sub>4</sub> *šá* 「ITI.DU<sub>6</sub><sup>1</sup> U<sub>4</sub>.7.<KAM>
- 4. id-din-nu ITI.DU<sub>6</sub> U<sub>4</sub>.5.KAM MU.6.<KAM>
- 5.  $^{\rm m}$ Kám-bu-zi-iá LUGAL TIN.TIR $^{\rm ki}$  LUGAL KUR.KUR

\_\_\_\_\_

- 6. 20 ma-na KI.LAL TÚG.UD.A šá <sup>d</sup>UTU
- 7. 2 ma-na dul\*-lu\* LAL\*

8. 2 ma-na KI.LAL {KI.LAL} TÚG.UD.A SIG<sub>5</sub>\*
9. 5/6\* ma-na LAL

Rev. 10. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ
11. šá <sup>d</sup>A-a 5 GÍN dul\*-lu\* LAL\*

12. 2 ma-na KI.LAL TÚG.ḤI.A<sup>! túg</sup>ṣib-tu<sub>4</sub>
13. šá <sup>rd</sup>ḤAR\*<sup>1</sup>

14. 16 ma-na KI.LAL <sup>túg</sup>ṣib-tu<sub>4</sub>
15. šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>

Edge 16. 2/3\* ma-na KI.LAL 2 TÚG.ÚR.MEŠ\*
17. šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>

It seems to me that the improved reading reveals the reason why Arad-Bēl decided to escape. He manufactured items far below the fixed weight and when his swindle had been discovered, he decided to run away to avoid penalty.

The scribe of the tablet made no distinction between LAL and *bar*, i.e. LAL in KI.LAL looks like *bar* (l. 12) and in line 7 another LAL also resembles *bar*. The numeral in l. 9 is written over an erasure. In l. 16 the numeral is slightly damaged, and the first impression is that it is 5/6, but careful observation ascertains that it is 2/3, which accords with the weight of 2 *sūnus* amounting to 40 shekels.

The reading of the date in 1. 3 and 4 was already corrected by Bongenaar, Ebabbar, p. 347.

Woven garments of Arad-Bēl, the weaver, who escaped and which Šamaš-šumiddin has delivered for the *lubuštu* ceremony for 7<sup>th</sup> Tašrītu. Month of Tašrītu, 5<sup>th</sup> day, 6<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

-----

18. 10\* GÍN\* e\*-te\*-qu\*

20 minas, the weight of the  $lub\bar{a}ru$ -garment for Šamaš; 2 minas of work are missing

\_\_\_\_\_

2 minas, the weight of the *lubār damqi*-headdress; 50 shekels are missing 1 mina, the weight of 10 sashes for Aya; 5 shekels of work are missing

2 minas, the weight of the *lubāru* (and) *sibtu*-garments for Bunene

\_\_\_\_\_

16 minas, the weight of the *şibtu*-garment for Anunītu 40 shekels, the weight of 2 *sūnu*-belts for Anunītu; 10 shekels are missing.

## 118. BM 72875 (82-9-18, 12883)

 $6.3 \times 5.4$  cm

6.7.[Dar<sup>?</sup>] 9

- 1. [dul-lu] BABBAR<sup>ú</sup> šá lu-bu-[uš-tu<sub>4</sub> šá <sup>d</sup>UTU]
- 2. [*u* DINGIR.MEŠ] UD.KIB.NUN<sup>ki</sup> [....]
- $3.\ [ITI].DU_6\ U_4.6.KAM\ MU.9.K[AM\ ....]$

```
4. 20 ma-na KI.LAL TÚG.[HI.A šá <sup>d</sup>UTU]
          5. 10 ma-na KI.LAL <sup>túg</sup>ṣib-tu₄ šá [<sup>d</sup>UTU]
          6. 2 ma-na KI.LAL TÚG.UD.A me S[IG<sup>qá</sup>/.(GA) šá <sup>d</sup>UTU]
          7. [1] ma-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup>UTU]
          ------
          8. [1] ma-na 1/3 GÍN KI.LAL TÚG.ÚR.[MEŠ šá ^{\rm d}UTU]
          9. <sup>1</sup>1 ma-na <sup>r</sup>KI<sup>1</sup>.LAL 10 TÚG.NÍG.Í[B.LÁ.MEŠ šá <sup>d</sup>A-a]
         10. 2 ma-na KI.LAL TÚG.UD.A ù [<sup>túg</sup>ṣib-tu4 šá <sup>d</sup>Bu-ne-ne]
Rev.
         11. <sup>[1/3]</sup> GÍN KI.LAL TÚG.ÚR šá <sup>d</sup>Bu-n[e-ne]
         -----
         12. 1 ma-[na] 「KI¹.LAL 10 「TÚG¹.NÍG.ÍB.[LÁ.MEŠ šá dGAŠAN
                 Sip-par<sup>ki</sup>]
         13. 1/3 G[ÍN] KI.LAL TÚG. 「ÚR」 šá [dGAŠAN Sip-parki]
         _____
         14. 50 「GÍN¹ KI.LAL 10 [TÚG.NÍG].Í[B.LÁ.MEŠ šá <sup>d</sup>IM <sup>d</sup>Ša-la]
         15. 1/3 GÍN KI.LAL TÚG.Ú[R šá <sup>d</sup>IM]
         _____
         16. [15] GÍN KI.LAL 5 TÚG.N[ÍG.ÍB.LÁ.MEŠ šá dGu-la]
         17. <sup>[1/3]</sup> GÍN KI.LAL TÚG.ÚR [šá <sup>d</sup>Gu-la]
         Blank space of one line
         18. [x] GÍN dul-lu <sup>r</sup>x¹ [....]
L. 16. The numeral is clearly 20, which I emended to 15 because 5 husannus, each
weighting 3 shekels belong to Gula's vestment.
L. 18. At the end of the line the head of two vertical strokes are preserved.
White [work] for the lubu[štu ceremony for Šamaš and the gods of] Sippar [....]
Month] of Tašrītu, 6<sup>th</sup> day, 9<sup>th</sup> year of [....]
20 minas, the weight of the lu[b\bar{a}ru-garment for Šamaš]
10 minas, the weight of the şibtu-garment for [Šamaš]
2 minas, the weight of the lubār mēs[iqu-headdress for Šamaš]
[1] mina, the weight of 6 sashe[s for Šamaš]
  -----
[1] mina 20 shekels, the weight of 4 sūnu-belt[s for Šamaš]
1 mina, the weight of 10 sash[es for Aya]
2 minas, the weight of the lubāru and [the şibtu-garments for Bunene]
20 shekels, the weight of (one) sūnu-belt for Bun[ene]
1 mi[na], the weight of 10 sash[es for the Queen of Sippar]
20 shekels, the weight of the sūnu-belt for [the Queen of Sippar]
50 shekels, the weight of 10 [sas]he[s for Adad (and) Šala]
20 shekels, the weight of the s\bar{u}[nu\text{-belt for Adad}]
_____
```

15! shekels, the weight of 5 sa[shes for Gula] 20 shekels, the weight of the *sūnu*-belt [for Gula]

[x] shekels, the work [...].

# **119. BM 62528** (82-9-18, 2497)

 $2.9 \times 4.1 \text{ cm}$ 

#### [x.x.Ach] 2

- 1. [dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub> šá U<sub>4</sub>.7.KAM šá ITI].DU<sub>6</sub> MU.2.KAM
- 2. [KN LUGAL Bābili (LUGAL KUR.KUR) PN] it-ta-din
- 3. [ITI.DU $_6$  U $_4$ .x.KAM MU.2.KAM KN LUGAL E] $^{ki}$  LUGAL KUR.KUR
- 4. [20 ma-na KI.LAL TÚG.HI.A šá <sup>d</sup>UTU ina lìb-bi ½] ma-na SÍG.ZA.GÌN.KUR.RA
- 5. [x x x KI.LAL TÚG.ḤI.A ku-l]u-lu šá  $^{\rm d}$ UTU
- 6. [x x x KI.LAL TÚG.ḤI.A me]-<sup>r</sup>tu<sup>?</sup>¹ [šá] <sup>d</sup>UTU
- 7. [.... KI.LAL .... *šá*] <sup>d</sup>UTU

8. [1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá] <sup>d</sup>A-a

[i-na] [lìb-bi] 6 GÍN SÍG. [ZA]. GÌN. KUR. [RA] 9.

Rest lost

Rev. in preserved part uninscribed

[White work for the *lubuštu* ceremony for 7<sup>th</sup>] day of Tašrītu, 2<sup>nd</sup> year [of KN, king of Babylon, (king of Lands) PN] has delivered.
[Month of Tašrītu, n<sup>th</sup> day, 2<sup>nd</sup> year of KN, king of Babylon], king of Lands.

[20 minas, the weight of the *lubāru*-garment for Šamaš with addition of ½] mina of blue-purple wool

[...., the weight of the *lubār kul*]ūlu-garment for Šamaš

[...., the weight of *lubār me*]*ţu*-garment for Šamaš

[...., the weight of .... for] Šamaš

[1 mina, the weight of 10 sashes for] Aya including 6 shekels of blue-purple wool.

**120. BM 74324** (82-9-18, 14347)

# 7. Garments for the Addaru *lubuštu* ceremony

PLATE 31

```
6.0 \times 5.8 cm
                          15.12.Nbk [x]
              1'. [20 ma-na KI.L]AL TÚG.ḤI.A [\check{s}\acute{a}^{\rm d}UTU]
Obv.
              2'. [10 ma-na KI.LA]L túg şib-「tu4¹ [šá dUTU]
              3'. [1 ma-na KI].LAL 6 TÚG.NÍG.ÍB.L[Á.MEŠ šá <sup>d</sup>UTU]
              ______
             4'. [2 ma]-^{\Gamma}na^{\Gamma} KI.LAL 1^{en!} TÚG.ḤI.A SAG.D[U šá ^{d}UTU] 5'. [1 ^{1/3} ma-na KI.LA]L <4> TÚG.ÚR.MEŠ šá ^{d}UTU
              6'. [1 ma-na] KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a
              7'. [x x (x)] KI.LAL 10 TÚG.NÍG.ÍB.L[Á.MEŠ]
              8'.
                                        [šá <sup>d</sup>N]IN-ŠA
              9'. [2 ma-na KI.LA]L TÚG.ḤI.A u T[ÚG.MA]Š<sup>?</sup>
            10'.
                                     [\check{s}\acute{a}^{d}B]u-ne-n[e]
Rev.
              1'. [....] 「x x <sup>1</sup> [....]
              2'. [....] 「dul¬-lu 「še^{?!}¬ [....]
              3'. [....] 'ITI'.ŠE U<sub>4</sub>.15.KAM
              4'. [....] ITI.ŠE
              5'. [....] <sup>md</sup>]AG-NÍG.DU-ÙRU
              6'. [....].「TIR<sup>?ki?</sup>」
              7'. [....] <sup>[</sup>x<sup>]</sup>
In 1. 7' we might reconstruct [1 ma-na] if the weight of the huṣannus for Nin-ŠA was the
same as for Aya.
[20 minas, the wei]ght of the lubāru-garment [for Šamaš]
[10 minas, the wei]ght of the sibt]u-garment [for Šamaš]
[1 mina, the wei]ght of 6 sash[es [for Šamaš]
[2 mi]nas, the weight of 1 lubār \langle m\bar{e} \rangle gagga[di]-headdress [for Šamaš]
[1 mina 20 shekels, the wei]ght of <4> s\bar{u}nu-belts for Šamaš
[1 mina], the weight of 10 sashes for Aya
[....], the weight of 10 sashes for Nin-ŠA
[2 minas, the weight of] the lub\bar{a}ru [and sibtu-garments for B]unen[e] [....] the work [.... for<sup>2</sup>], month of Addaru, 15<sup>th</sup> day [.... Month] Addaru [....] Nebu-
chadnezzar, [king of Baby]lon?.
```

## **121. BM 72963** (82-9-18, 12972)

 $6.0 \times 5.8$  cm

#### 12.12.Nbn 1

- 1. [20] <sup>r</sup>ma-na<sup>7</sup> KI.LAL TÚG.ḤI.A [šá <sup>d</sup>UTU]
- 2. [10] [ma]-na KI.LAL [TÚG.MÁŠ] šá d[UTU]
- 3. [1] ma-na KI.LAL 6 TÚG. NÍG. ÍB¹. [ÍB.LÁ.MEŠ šá dUTU]
- 4. <sup>[2]</sup> ma-na <sup>[5]</sup> GÍN KI.LAL <sup>[20]</sup> TÚG.[NÍG.ÍB.LÁ.MEŠ]
- 5. šá <sup>d</sup>A-a u <sup>d</sup>GAŠAN 'UD.KIB'.[NUN<sup>ki</sup>]
- 6. 「1¹½ ma-na 5 GÍN [KI.LAL]
- 7. TÚG.HI.A SAG.DU [šá] [dUTU]
- 8. [1] [*m*]*a-na* KI.[LAL ....]
- 9. [1] <sup>1</sup>/3 GÍN K[I.LAL TÚG.ḤI.A]

Edge Rev. 10. *šá* <sup>d</sup>*Bu*-[*ne-ne*]

11. 2/3 ma-na KI.[LAL TÚG.MÁŠ]

- 12. šá <sup>d</sup>Bu-ne-ne [1 1/3 ma-na]
- 13. KI.LAL 4 TÚG.ÚR.MEŠ [dUTU (u dA-a)]
- 14. PAP ½ GÚ.UN 9 5/6 ma-[na]
- 15. ITI.ŠE U<sub>4</sub>.12.KAM MU.1.KAM
- 16. mdAG-I LUGAL TIN.TIRki
- L. 8. Maybe K[I.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá  ${}^{\rm d}$ GAŠAN  $Sip\text{-}par^{\rm ki}$ ]
- L. 14. Note that the total of individual entries makes only 39 minas.
- [20] minas, the weight of the *lubāru*-garment [for Šamaš]
- [10] minas, the weight of the *ṣibtu*-garment for [Šamaš]
- [1] mina, the wei]ght of 6 sa[shes for Šamaš]
- 2 minas 5 shekels, the weight of 20 sash[es] for Aya and the Queen of Sip[par]
- 1 mina 35 shekels, [the weight] of the  $lub\bar{a}r < m\bar{e} > qaqqadi$ -headdress for [Šamaš] 1 mina, the wei[ght of ....]
- [1] mina 20 shekels, the wei[ght of the *lubāru*-garment] for Bu[nene]
- 40 shekels, the wei[ght of the *sibtu*-garment] for Bunene
- [1 mina 20 shekels], the weight of 4 *sūnu*-belts [for Šamaš (and Aya)], total 39 minas 50 shekels.

Month of Addaru, 12<sup>th</sup> day 1<sup>st</sup> year of Nabonidus, king of Babylon.

# **122. BM 61629+BM 62119** (82-9-18, 1601+2088)

 $8.5 \times 5.8$  cm

# 11.12.Nbn 5

- 1.  $[dul-lu \ BABBAR]^{\Gamma}{}^{\acute{u}_{1}}\check{s}\acute{a}^{md}AG-PAP-A^{l\acute{u}}U\check{S}.BAR$  a-na
- 2. [É-babbar-ra it-ta]-din ITI. ŠE U<br/>4.11.KAM MU.5.KAM $^{\rm md}$ AG-I LUGAL  $E^{\rm ki}$

3. [20 ma-na] K[I.LA]L <sup>r</sup>lu<sup>1</sup>-bar-ra <sup>r</sup>šá <sup>d</sup>UTU<sup>1</sup> ina lìb-bi <sup>1</sup>/<sub>2</sub> ma-na SÍG, <sup>r</sup>ZA,GÌN, <KUR>,RA<sup>1</sup>

```
4. [10 ma-n]a K[I.LAL şib-tu<sub>4</sub>] 「šá<sup>1 d</sup>UTU
```

5. [1 ma]-na 'KI.LAL' [6 TÚG.NÍG.ÍB].'LÁ'.MEŠ šá <sup>d</sup>UTU

6. <sup>[2]</sup> ma-na KI.LAL TÚG.[HI.A me SA]G.DU šá <sup>d</sup>UTU

7. 1 ma-na 1/3 GÍN KI.LAL 4 < TÚG>. 「ÚR¹.MEŠ šá dUTU u dA-a

8. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a

9. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{\rm d_{\rm f}}$ GAŠAN  $Sip^{\rm 1-}$   $[par^{\rm ki}]$ 

10. 1 ma-na 1/3 GÍN [KI].LAL TÚG. [HI].A šá dBu-n[e-ne]

11. ina lìb-bi 6 GÍN [SÍG.ZA.GÌN.<KUR>.RA]

Edge 12. 2/3 ma-na KI.LAL šá şib-tu<sub>4</sub> šá <sup>d</sup>HAR

13. 「50」 GÍN KI.LAL 「10<sup>!</sup>」 [TÚG].「NÍG」.ÍB.LÁ.MEŠ 「šá¹ [dIM u dŠa-la]

Rev. 14. 15 GÍN 'KI.LAL {KI.LAL}' 5 [TÚG].'NÍG.ÍB'.LÁ.[MEŠ]

15.  $[\check{s}\acute{a}]^{\mathsf{r}^{\mathsf{d}}}G[u\text{-}la]$ 

16. 1/3 GÍN [KI].LAL [<TÚG>.ÚR šá <sup>d</sup>IM]

17. 1/3 GÍN 「KI.LAL¹ [<TÚG>.ÚR šá <sup>d</sup>Gu-la]

18.  $^{\text{r}}$ x x x  $ku^{?}$  x  $lu^{?}$ 

19. [x] <sup>[</sup>x<sup>1</sup>

They are some problems with line 13, where at the beginning the numeral 50 is partly broken, but the reading seems certain. Also the slightly broken numeral 5 follows KI.LAL, which I decided to emend to 10 because we know that 10 *huṣannus* for Adad and Šala weighed 50 shekels, and, just like here, are usually preceded with 5 *huṣannus* for Gula weighing 15 shekels.

Ll. 18–19. We expect here the garments for Šala, but signs, although preserved very badly, do not confirm such possibility.

[White work], which Nabû-nāṣir-apli, the weaver has delive[red to the Ebabbar temple]. Month of Addaru, 11<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, king of Babylon.

[20 minas], the we [ig]ht of the  $lub\bar{a}ru\text{-garment}$  for Šamaš with addition of  $\frac{1}{2}$  mina of blue-purple wool

[10 mi]nas, the we[ight of the *şibtu*]-garment for Šamaš

[1 mi]na, the weight of [6 sash]es for Šamaš

2 minas, the weight of the *lub*[ār mē qaq]qadi for Šamaš

1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš and Aya

1 mina, the weight of 10 sashes for Aya

1 mina, the weight of 10 sashes for the Queen of Sip[par]

1 mina 20 shekels, [the wei]ght of the *lubāru*-garment for Bun[ene] with addition of 6 shekels of [blue-purple wool]

40 shekels, the weight of the *şibtu*-garment for Bunene

50 shekels, the weight of 10' sashes for [Adad and Šala]

15 shekels, the weight of 5 sash[es for G[ula]

20 shekels, the [wei]ght of [the *sūnu*-belt for Adad]

20 shekels, the weight [of the *sūnu*-belt for Gula].

. . . . . . . . . . . . . . . .

**123. BM 74440** = Bertin 1395; cf. Bongenaar, *Ebabbar*, pp. 304f. 7.5 × 5.3 cm

#### 12.12.Nbn 10

	1. $dul$ - $lu$ BABBAR $^{\acute{u}}$ šá $^{m}Ba$ - $ku$ - $\acute{u}$ - $a$ $^{l\acute{u}}qal$ - $la$ šá 2. $^{md}$ AG- $na$ - $sir$ - $<$ A $>$ $^{l\acute{u}}$ UŠ.BAR $id$ - $di$ - $nu$ ITI.ŠE 3. U $_{4}$ .12.KAM MU.10.KAM $^{md}$ AG-I LUGAL TIN.TIR $^{ki}$
	4. 20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup> UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA
	5. 10 ma-na KI.LAL <sup>túg</sup> ṣib-tu <sub>4</sub> šá <sup>d</sup> UTU
	6. 2 ma-na KI.LAL TÚG.ḤI.A me SAG.DU šá <sup>d</sup> UTU
	7. 1 ma-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> UTU
	8. 1 ma- <na> 1/3 GÍN KI.LAL 4 TÚG.ÚR.MEŠ šá <sup>d</sup>UTU u <sup>d</sup>A-a</na>
	9. 「1 <sup>1</sup> [ <i>m</i> ] <i>a-na</i> KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> A-a
Edge	10. [1] <i>ma-na</i> KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup> GAŠAN <i>Sip-</i> [ <i>par</i> <sup>ki</sup> ]
Rev.	11. $^{\text{I}}$ 1 ma-na $^{\text{I}}$ 10 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LA.MEŠ $^{\text{I}}$ 12. TÚG.ÚR šá $^{\text{d}}$ 1M ù $^{\text{d}}$ Ša-la
	13. 15 GÍN KI.LAL 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> Gu-la
	14. 1/3 GÍN KI.LAL 1 TÚG.ÚR šá <sup>d</sup> ḤAR
	15. 1/3 GÍN KI.LAL 1 TÚG.ÚR šá <sup>d</sup> Gu-la
	16. <sup>r</sup> 2* <sup>1</sup> ma-na KI.LAL TÚG.ḤI.A ù <sup>túg</sup> ṣib-tu <sub>4</sub> šá <sup>d</sup> ḤAR

Note the atypical place of the garments of Bunene (usually it follows the husannus for Aya). In l. 11 the numeral 1/3 is emended to  $10^!$ 

White work, which Bakûa, the slave of Nabû-nāṣir-<apli>, the weaver has delivered. Month of Addaru,  $12^{th}$  day,  $10^{th}$  year of Nabonidus, king of Babylon.

20 minas, the weight of the  $lub\bar{a}ru\text{-}\mathrm{garment}$  for Šamaš with addition of ½ mina of blue-purple wool

10 minas, the weight of the *ṣibtu*-garment for Šamaš

2 minas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš

1 mina, the weight of 6 sashes for Šamaš

1 mi<na> 20 shekels, the weight of 4 sūnu-belts for Šamaš and Aya

1 mina, the weight of 10 sashes for Aya

1 mina, the weight of 10 sashes for the Queen of Sip[par]

1 mina 10' shekels, the weight of 10 sashes and the sūnu-belt for Adad and Šala

15 shekels, the weight of 5 sashes for Gula

20 shekels, the weight of 1 sūnu-belt for Bunene

20 shekels, the weight of 1 sūnu-belt for Gula

21 minas, the weight of 1 sūnu-belt for Gula

22 minas, the weight of the *lubāru*-garment and *sibtu*-garments for Bunene.

## **124. Nbn 1015** = BM 75967; cf. NUVI 3, No. 93 Collated

## 11.12.Nbn 16

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub> šá ITI.ŠE <sup>md</sup>AG-ſÙRU¬-A
- 2. u <sup>m</sup>Ba-ku-ú-a id-din-nu ITI.ŠE U<sub>4</sub>.11.KAM MU.16.KAM
- 3. dAG-I LUGAL TIN.TIRki

\_\_\_\_\_

- 4. <sup>[</sup>20] *ma-na* KI.LAL TÚG.HI.A *šá* <sup>d</sup>UTU
- 5. [10] ma-na KI.LAL TÚG.MÁŠ! šá <sup>d</sup>UTU
- 6. 1 ma-na 1/3 GÍN KI.LAL 4\* TÚG\*.ÚR.MEŠ šá <sup>d</sup>UTU
- 7. 2 ma-na KI.LAL TÚG.ḤI.A SAG.DU šá <sup>d</sup>UTU
- 8. 2 ma-na KI.LAL TÚG.ḤI.A u TÚG.MÁŠ šá <sup>d</sup>[ḤAR]
- 9. 1 ma-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá [<sup>d</sup>UTU]
- 10. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>[A-a]
- 11. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LA.MEŠ šá <sup>d</sup>[GAŠAN Sip-par<sup>ki</sup>]
- 12. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá [dIM u dŠa-la]
- 13. 15 GÍN KI.LAL 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá [<sup>d</sup>Gu-la]

White work for the *lubuštu* ceremony for the month of Addaru Nabû-nāṣir-apli and Bakûa have delivered. Month of Addaru, 11<sup>th</sup> day, 16<sup>th</sup> year of Nabonidus, king of Babylon.

10 minas, the weight of the *şibtu*-garment for Šamaš

<sup>20</sup> minas, the weight of the *lubāru*-garment for Šamaš

1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš 2 minas, the weight of the  $lub\bar{a}r < m\bar{e} > qaqqadi$ -headdress for Šamaš 2 minas, the weight of the *lubāru* and *sibtu*-garments for [Bunene] 1 mina, the weight of 6 sashes for [Šamaš]

1 mina, the weight of 10 sashes [for Aya]

1 mina, the weight of 10 sashes [for the Queen of Sippar]

50 shekels, the weight of 10 sashes [for Adad and Šala]

15 shekels, the weight of 5 sashes [for Gula].

## 125. BM 76129 (83-1-18, 1494)

 $5.6 \times 5.9$  cm

# 12.12.[Nbn x]

- 1. [dul-lu] BABBAR<sup>ú</sup> šá lu-bu-uš-t[u<sub>4</sub> šá U<sub>4</sub>.15.KAM šá ITI.ŠE]
- 2. [ $\check{s}\check{a}^{m}B$ ]a-ku- $\acute{u}$ -a  $^{l\acute{u}}qal$ -la  $\check{s}\check{a}^{md}AG$ -na-[ $\check{s}ir$ -A  $^{l\acute{u}}U\check{S}.BAR$ ]
  3. [it]-ta-din ITI.ŠE U<sub>4</sub>.12.KAM MU.x.[KAM  $^{md}AG$ -I LUGAL  $E^{ki}$ ]

-----

- 4. [20] ma-na KI.LAL TÚG.HI.A šá [<sup>d</sup>UTU]
- 5. [10] ma-na KI.LAL sib-tu<sub>4</sub> šá [<sup>d</sup>UTU]
- 6. 1 ma-na KI.LAL 6 TÚG.NÍG.ÍB.[LÁ.MEŠ  $š\acute{a}^{\rm d}$ UTU]
- 7. [1] 1/3 *ma-na* KI.LAL 4 TÚG.ÚR.[MEŠ *šá* <sup>d</sup>UTU] \_\_\_\_\_
- 8. [1] ma-na 「KI.LAL<sup>1</sup> 10 TÚG.NÍG.ÍB.LÁ.M[EŠ šá <sup>d</sup>A-a] \_\_\_\_\_
- 9. [2 m]a-na KI.LAL TÚG<sup>!</sup> (T:KI).HI.A u TÚG<sup>!</sup>(T: KI).[MÁŠ šá <sup>d</sup>Bu-ne-ne]

10. nothing preserved

Beginning of Rev. damaged (at least two lines)

- 1'. [....] 'x' TÚG.NÍG.[....]
- 2'. [x ma-na x] GÍN KI.LAL [x] TÚG.<NÍG>.Í[B.L]Á.M[EŠ
- 3'. [1/3 m]a-na KI.LAL  $1[^e]^{n?}$  TÚG.Ú[R (x x x)] 4'. [x G]ÍN KI.LAL 2+[x] TÚG.NÍG.Í[B.LÁ.MEŠ ....]

5'. [....] 'dul'\-lu BAB[BAR ....]

White [work] for the *lubuštu* ceremony [for the 15<sup>th</sup> day of the month Addaru, which B]akûa, the slave of Nabû-nā[sir-apli, the weaver has de]livered. Month of Addaru, 12<sup>th</sup> day, [n<sup>th</sup>] year of [Nabonidus, king of Babylon]. \_\_\_\_\_

1 mina, the weight of 6 sash[es for Šamaš]

[1] mina 20 shekels, the weight of 4 sūnu-belt[s for Šamaš]

<sup>[20]</sup> minas, the weight of the *lubāru*-garment for [Šamaš]

<sup>[10]</sup> minas, the weight of the *sibtu*-garment for [Šamaš]

[1] mina, the weight of 10 sashe[s for Aya] [2 mi]nas, the weight of the *lubāru* and *şibtu*-garments [for Bunene] [....] sas[hes? ....] [....] shekels, the weight of [x] sashes? [....] [20] shekels, the weight of  $1^2 s\bar{u}[nu\text{-belt ....}]$ [x she]kels, the weight of 2+x sas[hes ....] [....] white work [....]. **126. BM 63745** (82-9-18, 3712)  $5.7 \times 6.5$  cm  $10.12.\text{Cyr }1[+x^{?}]$ 1.  $[dul-lu\ BABBAR^{\acute{u}}\ \check{s}\acute{a}\ l]u-bu-u\check{s}-tu_4\ \check{s}\acute{a}\ ^dUTU\ [\check{s}\acute{a}\ ITI.\check{S}E]$ 2. [MU.x.KAM <sup>m</sup>Kur]-<sup>r</sup>raš<sup>†</sup> LUGAL NUN<sup>ki</sup> LUGAL KUR.KUR <sup>m</sup>Ba-[x x] 3. <sup>lú</sup>UŠ.BAR<sup>1</sup> *id-din-nu* ITI.ŠE U<sub>4</sub>.10.KAM MU.1[+x<sup>?</sup>.KAM] \_\_\_\_\_ 4. 20 TÚG.HI.A šá <sup>d</sup>UTU ina lìb-[bi ½ ma-na SIG.ZA.GÌN.KUR.RA] 5. 10 ma-na KI.LAL ˈTÚG.MÁŠ ʾ šá dUTU 2 ʿ ma ʾ - [na TÚG.HI.A me SAG.(DU) šá <sup>d</sup>UTU] 6. [1] 1/3 ma-na KI.LAL <sup>r</sup>4 TÚG.ÚR<sup>?</sup> <sup>1</sup>.MEŠ 1 <sup>r</sup>ma <sup>1</sup>-[na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>UTU] 7. 1 ma-na KI<sup>?</sup>[LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a] 8. 2 [ma-na KI.LAL TÚG.HI.A TÚG.MÁŠ šá <sup>d</sup>HAR] 9. fully eroded 10. fully eroded 11. fully eroded 12. [x x x] KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 「šá<sup>!</sup>」[....] Rev. Rest of rev. uninscribed [White work for the *l*]ubuštu ceremony for Šamaš [for the month of Addaru, n<sup>th</sup> year of Cy]rus, king of Babylon, king of Lands, Ba-[x x], the weaver, has delivered. Month of Addaru, 10<sup>th</sup> day, year 1+[x] 20 minas, the weight of the *lubāru*-garment for Šamaš with addi[tion of ½ mina of blue-purple wool] 10 minas, the weight of the *şibtu*-garment for Šamaš 2 mi[nas, the weight of the *lubār mē qaqqadi*-headdress for Šamaš] [1] mina 20 shekels, the weight of 4 sūnu-belts

1 mi[na, the weight of 6 sashes for Šamaš] 1 mina, the we[ight of 10 sashes for Aya] 2 [minas, the weight of the *lubāru* (and) *şibtu*-garments for Bunene]

[x shekels], the weight of 10 sashes for [....].

#### **127. BM 61162** (82-9-18, 1138)

PLATE 32

 $5.0 \times 3.5$  cm

## 12.12.Dar 15

- 1. dul-lu BABBAR<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub>
- 2. šá ITI.ŠE MU.15.KAM <sup>m</sup>Da-ri-muš LUGAL <KUR.KUR>
- 3.  $^{\rm md}$ UTU-MU-MU id-din-nu
- 4. ITI.ŠE U<sub>4</sub>.12.KAM MU.1<sup>r</sup>5<sup>1</sup> <KAM>

\_\_\_\_\_

- 5. 20 ma-na KI.LAL TÚG.UD.ḤI.A [šá $^{\rm d}$ UTU]
- 6. <sup>[2]</sup> ma-na <sup>[KI.LAL]</sup>

Edge Rev.

7. ľTÚG¹.UD.ḤI.[A u TÚG.MÁ]Š

8.  $\lceil \check{s} \acute{a} \rceil$  <sup>d</sup>Bu-ne-[ne]

9. 2 ma-na KI.[LAL]

10. TÚG.HI.A me-e SIG<sub>5</sub>

L. 5. The missing [ $\delta a^{d}$ UTU] must have been written on right destroyed edge.

White work for the *lubuštu* ceremony, which for the month Addaru, 15<sup>th</sup> year of Darius, king of Lands, Šamaš-šum-iddin has delivered. Month of Addaru, 12<sup>th</sup> day, 15<sup>th</sup> year.

20 minas, the weight of the *lubāru* [for Šamaš]

- 2 minas, the weight of the *lubār[u* (and) *sibtu*-garments for] Bune[ne]
- 2 minas, the weight of the *lubār mē damqi*-headdress.

# **128. BM 66250** (82-9-18, 6241)

PLATE 33

 $5.2 \times 5.7$  cm

## [x.12].Dar [x]

- 3. [MU.x.KAM] <sup>m</sup>Da-ri-ja-muš 4. [LUGAL TIN.TIR<sup>k</sup>]<sup>i</sup> LUGAL KUR.KUR šá x (erased) 5. [<sup>md</sup>UTU-MU-M]U<sup>? lú</sup>UŠ.BAR id-din-<nu>
- 6. [ITI.ŠE  $U_4.x.KAM MU.x+^?$ ] $^12^1.KAM$

- 7. [20 ma-na K]I.LAL TÚG.UD.A šá <sup>d</sup>UTU
- 8. [2 ma-na] KI.LAL TÚG.UD.A me SAG šá <sup>d</sup>UTU

Edge 9. [1 ma-na KI.LA]L 6 hu-ṣa-nu<sup>meš!</sup>

Rev. 10. [10 ma-na KI.LAL] sib-tu<sub>4</sub> šá <sup>d</sup>UTU

11. [šá <sup>md</sup>HAR-ši-m]an<sup>an</sup>-ni it-ta-din

Blank space for one line

12. [1 ma-na] KI.LAL <10> túg hu-ṣa-nu meš šá dGAŠAN Sip-par ki

Free space for about 2 lines

13.  $[x \times x \times x] dul-lu LAL$ 

Stamp seal on Rev.

There is a serious problem with filling the gaps in ll. 2-6 because the wording of these lines has no exact parallels. The suggested reconstruction is only a proposal. For partial parallelism, see BM 79745 (= 61).

L. 5. The reading of [ŠE]Š cannot be also excluded.

Note that the *huṣannu*-sashes for Aya are missing but for the Queen of Sippar are present.

[White work for the *lub*]*uštu* ceremony [for Šamaš and the gods of Sippar for the 1]5<sup>th</sup> of Addaru, [n<sup>th</sup> year of] Darius, [king of Babylon], king of Lands, which [Šamaš-šum-id]din<sup>?</sup>, the weaver has delivered. [Day x, month of Addaru, year x<sup>?</sup>]+ 2.

\_\_\_\_\_

[20 minas, the we]ight of the lubāru for Šamaš

[2 minas], the weight of the lubār mē qaqqadi-headdress for Šamaš

[1 mina, the weig]ht of 6 sashes

[10 minas, the weight] of the *şibtu*-garment for Šamaš, [which Bunene-šim]anni has delivered.

[1 mina], the weight of <10> sashes for the Queen of Sippar;

[....] work is missing.

# **129. BM 68154** (82-9-18, 8152)

 $5.7 \times 3.7$  (thick 3.0) cm

 $[x].12^{?}.Ach[x]$ 

- 1. dul-lu 「BABBAR」  $^{i}$  [ $\check{s}\check{a}$ ] lu-bu- $u\check{s}$ - $tu_4$  「 $\check{s}\check{a}$ 1 [ITI.x  $U_4$ .x.KAM  $\check{s}\check{a}$ ]
- 2. [m]<sub>\(\int\_0\)</sub>d<sub>\(\int\_0\)</sup>UTU-MU-MU *id-din-nu* ITI.Š[E MU.x.KAM KN]</sub>
- 3. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

- 4. 20 ma-na KI.LAL TÚG.UD.A šá! [dUTU]
- 5. 10 ma-na KI.LAL sib-tu<sub>4</sub> šá [<sup>d</sup>UTU]

Rest lost

The preserved upper part of the reverse is uninscribed. Below there is

1'. [x] ma-na 52 GÍN KI.[LAL ....]

L. 2. After ITI only one *Winkelhaken* is preserved, however l. 2 (one *şibtu*) suggests that the text listed the garments for the month VI, or VII or XII and most probable the month should be read as Š[E.

White work for the *lubuštu* ceremony [.....which] Šamaš-šum-iddin has delivered. Month of Ad[daru, year x of KN], king of Babylon, king of Lands.

-----

20 minas, the weight of the *lubāru* for [Šamaš] 10 minas, the weight of the *şibtu*-garment for [Šamaš]

[x mina(s) 52 shekels, the wei[ght ....].

# 8. Garments for the *lubuštu* ceremony in cycle B (Ulūlu, Tašrītu or Addaru)

#### **130. CT 55, 803** = BM 56147

[x.x].Nbn 15

- 1. dul-lu BABBAR $^{\acute{u}}$  šá  $lu^!$ (T: mu)-bu- $u\check{s}$ - $tu_4$  [šá ITI.x U<sub>4</sub>.x.KAM]
- 2. [šá] <sup>md</sup>AG<sup>!</sup>-ÙRU<sup>!</sup>-A <sup>lú</sup>UŠ.BAR *id-*[din]-nu [ITI.x U<sub>4</sub>.x.KAM]
- 3. MU.15.KAM <sup>md</sup>AG-I LUGAL <sup>[E][ki]</sup>
- 4. 「20」 ma-na KI.LAL TÚG.HI.A šá <sup>d</sup>UTU
- 5. [10<sup>?</sup>]ma-na KI.LAL <sup>túg</sup>sib-tu<sub>4</sub> šá [<sup>d</sup>UTU]
- 6. [1+]1 ma-na KI.LAL TÚG.ḤI.A [me SAG.DU šá  $^{\rm d}$ UTU]
- 7. [1] *ma-na* KI.LAL [6 TÚG.NÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>UTU]

Rev. uninscribed

L. 2. I accept here the reading suggested by Bongenaar, Ebabbar, p. 337.

White work for the *lubuštu* ceremony [of the month x,  $n^{th}$  day] which Nabû-nāṣirapli, the weaver has delivered. [Month of x,  $n^{th}$  day],  $15^{th}$  year of Nabonidus, king of Babylon.

\_\_\_\_\_

20 minas, the wei]ght of the *lubāru*-garment for Šamaš <sup>7</sup>10<sup>?1</sup> minas, the weight of the *şibtu*-garment for [Šamaš]

[2] minas, the weight of the *lubār* [mē qaqqadi-headdress for Šamaš]

[1] mina, the weight of [6 sashes for Šamaš].

# **131. BM 63710** (82-9-18, 3677)

 $7.5 \times 4.5 \text{ cm}$ 

- 3'. [10] ma-na KI.LAL 1<sup>en túg</sup>ṣib-tu<sub>4</sub> [šá <sup>d</sup>UTU]
- 4'. [2] <sup>r</sup>ma<sup>1</sup>-na KI.LAL TÚG.ḤI.A me SAG [šá <sup>d</sup>UTU]
- 5'. [1 *ma*]-*na* 1/3 GÍN KI.LAL 4 TÚG.ÚR.MEŠ *šá* [<sup>d</sup>UTU]
- 6'. [1 ma-n]a KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>[UTU]
- 7'. [1 ma-na KI].LAL 「10<br/>¹ TÚG.NÍG.ÍB.LÁ.[MEŠ šá  $^{\rm d}A$ -a]

Edge Rev.	8'. lost 9'. [] <sup>r</sup> x x <sup>1</sup> [] 10'. [x (x)] <sup>r</sup> x <sup>1</sup> KI.LAL 10 TÚG.NÍ[G.ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup> DN]
	11'.[x x x KI.L]AL TÚG.ÚR $\dot{u}^!$ TÚG.NÍG.¹ÍB.LÁ.MEŠ $\check{s}\acute{a}^{d_1}$ [DN]
	12'. [1 ma]- <sup>[</sup> na <sup>]</sup> 10 GÍN KI.LAL TÚG.ÚR ù TÚG.NÍG.ÍB.LÁ.[MEŠ] 13'. šá <sup>d</sup> IM u <sup>d</sup> Ša-[la]
well as G. L. 10'. Fr ing [x ma L. 11'. A dul). Bec	e preserved tiny fragment of the first sign has such a shape that the reading $U[R]$ as $I[N]$ is possible; the second might be the bottom part of numeral 2 or $a$ . To om the sign preceding KI.LAL only one vertical stroke is preserved, and the read- $I[n]$ or $I[n]$ is possible. Very unclear sign, which I suggest emending to $I[n]$ (it looks like $I[n]$ ) or $I[n]$ ause we expect here a list of garments for Gula, who received 5 $I[n]$ has sense.
$[\dots n^{th} y e$	e[ar]
[20 min]	as, the weight of the <i>lubāru</i> -garment [for Šamaš]
[10] min	as, the weight of 1 <i>şibtu</i> -garment [for Šamaš]
[2] minas, the weight of the <i>lubār mē qaqqadi</i> -headdress [for Šamaš]	
[1 mi]na 20 shekels, the weight of 4 sūnu-belts for [Šamaš]	
	, the weight of 6 sashes for [Šamaš]
[1 mi]na	, the weight of 10 sashe[s for Aya]
[x sheke]	ls], the weight of 10 sas[hes for DN]
[ the	wei]ght of the <i>sūnu</i> -belt (and) the sashes for [DN]
[1 mi]na and Ša[l	10 shekels, the weight of the <i>sūnu</i> -belt and the sashes for Adad
<b>132. BM</b> 6.2 × 4.3	(a. 67311 (82-9-18, 7307)) c cm
	1'. [20 ma-n]a 「KI'.LAL TÚG.ḤI.A šá <sup>d</sup> UTU ina l[ìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA] 

	2'. [10 $ma$ - $n$ ] $a$ KI.LAL $<$ túg $>$ $sib$ - $tu$ 4 $šá$ dUTU	
	3'. [2 <i>ma</i> ]- <i>na</i> KI.LAL TÚG.ḤI.A <i>me</i> SAG.DU <sup>r</sup> šá <sup>d</sup> ¹[UTU]	
	4'. [1 <i>ma</i> ]- <i>na</i> 1/3 GÍN KI.LAL 4 < TÚG>. ÚR.MEŠ šá <sup>d</sup> UTU <i>u</i> <sup>d</sup> <i>A-a</i>	
	5'. [1 m]a-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> UTU 6'. [1 m]a-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> A-a	
Edge	7'. [2] $ma$ - $na$ KI.LAL TÚG. $H$ I.A $<$ $^{túg}>$ $sib$ - $tu_4$ $sa$ $^dH$ AR	
Rev.	8'. [1 <i>m</i> ] <i>a-na</i> KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 9'. [1/3 GÍN] KI.LAL <túg>.ÚR <i>šá</i> <sup>d</sup>GAŠAN <i>Sip-par</i><sup>ki</sup></túg>	
	10'. [15 GÍN KI].LAL 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> Gu-la 11'. [1/3 GÍN] KI.LAL [TÚ]G.ÚR šá <sup>d</sup> Gu-la	
	12'. [1/3 GÍN KI.LAL TÚG.ÚR] <sup>r</sup> x 5/6 <sup>1</sup> ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 13'. [šá <sup>d</sup> IM u] <sup>rd</sup> 1Ša-la	
	14'. nothing preserved (probably not written)	
[20 min]as, the weight of the $lub\bar{a}ru$ -garment for Šamaš with ad[dition of ½ mina of blue-purple wool		
[10 min]as, the weight of the <i>şibtu</i> -garment for Šamaš		
	as, the weight of the <i>lubār mē qaqqadi</i> -headdress for [Šamaš]	
[1 mi]na 20 shekels, the weight of 4 sūnu-belts for Šamaš and Aya		
[1 mi]na, the weight of 6 sashes for Šamaš [1 mi]na, the weight of 10 sashes for Aya		
[2] minas, the weight of the <i>lubāru</i> (and) <i>ṣibtu</i> -garments for Bunene		
[1 mi]na, the weight of 10 sashes [20 shekels], the weight of the <i>sūnu</i> -belt for the Queen of Sippar		
[15 shekels, the wei]ght of 5 sashes for Gula [20 shekels], the weight of the <i>sūnu</i> -belt for Gula		
[20 shekels, the weight of the <i>sūnu</i> -belt]; 50 shekels, the weight of 10 sashes [for Adad and] Šala.		

# **133. BM 101169** (83-1-21, 2830)

 $3.4 \times 4.0$  cm

## [x.x].Cam [x]

- 1'. ["Kam-b]u-zi-[ja LUGAL ....]
- 2'. 20 ma-na KI.LAL [TÚG.ḤI.A šá <sup>d</sup>UTU]
- 3'. 10 ma-na KI.L[AL TÚG.MÁŠ šá <sup>d</sup>UTU]
- 4'. 2 ma-na KI.[LAL TÚG.ḤI.A me SAG.(DU) šá <sup>d</sup>UTU]
- 5'. 1 ma-na KI.LAIL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTUI
- 6'. 1 1/3 ma-na KI.LA[L 4 TÚG.ÚR.MEŠ šá <sup>d</sup>UTU]

Rev. Rest lost 7'. 1 ma-na [KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]

[.... Camb]ys[es, king ....]

20 minas, the weight of the [lubāru-garment for Šamaš] 10 minas, the weig[ht of the *ṣibtu*-garment for Šamaš]

2 minas, the wei[ght of the *lubār mē qaqqadi*-headdress for Šamaš]

1 mina, the wei[ght of 6 sashes for Šamaš]

1 mina 20 shekels, the weig[ht of 4 *sūnu*-belts for Šamaš] 1 mina, [the weight of 10 sashes for Aya].

#### **134. BM 78926** (88-5-12, 112)

 $7.0 \times 4.3 \text{ cm}$ 

- 1'. [20 ma-na KI.LAL <sup>túg</sup>]lu-bar-ra [šá <sup>d</sup>UTU]
- 2'. [10 ma-na KI.LAL]  $^{\text{túg}}$  sib-tu<sub>4</sub> [ $s\acute{a}$   $^{\text{d}}$ UTU] 3'. [2 ma-na KI.LAL]  $^{\text{túg}}$  lu-ba-ra me SAG.[(DU)  $s\acute{a}$   $^{\text{d}}$ UTU]
- 4'. [1 ma-na KI.LA]L 6 hu-ṣa-an-ni-e [šá <sup>d</sup>UTU]
- 5'. [1 1/3 ma-na KI.LAL] 4 <sup>túg</sup>su-ni-e [šá <sup>d</sup>UTU (u <sup>d</sup>A-a)]

- 6'. [1 ma-na K]I.LAL 10 hu-ṣa-an-ni-e šá [dA-a]
- 7'. [2 ma-na] KI.LAL <sup>túg</sup>lu-ba-ra ù ṣib-tu<sub>4</sub> šá <sup>d</sup>[ḤAR]
- 8'. [1 ma-n]a KI.LAL 10 hu-sa-an-ni-e šá <sup>d</sup>GAŠAN UD.[KIB.NUNki]
- 9'. [1 ma-n]a KI.LAL 10 hu-sa-an-ni-e sa  $^dA$ -nu-[ni-tu4]
- 10'. [1/3 m]a-na KI.LAL <sup>túg</sup>su-ni-e [šá] <sup>d</sup>[DN]

Rev. uninscribed

The broken beginning included:  $dullu\ peṣũ\ ša\ lubuštu\ ša\ ITI.x\ (ana)\ PN\ ^{lú}x\ SUM^{na}\ ITI.x\ U_4.x.KAM\ MU\ x.KAM\ KN\ LUGAL\ Bābili\ (LUGAL\ mātāte).$  Because only 6 huṣannus were destined for the lubuštu ceremony it is certain that the text included the list of garments for the second cycle (i.e. month VI, or VII or XII).

```
[20 minas, the weight of] the [lubāru-garment [for Šamaš] [10 minas, the weight of] the sibtu-garment [for Šamaš] [2 minas, the weight of] the lubār mē qaqqa[di for Šamaš] [1 mina, the weight of 6 sashes [for Šamaš] [1 mina 20 shekels, the weight of] 4 sūnu-belts [for Šamaš (and Aya)] [1 mina, the weight of 10 sashes for [Aya] [2 minas], the weight of the lubāru and sibtu-garments for [Bunene] [1 mi]na, the weight of 10 sashes for the Queen of Si[ppar] [1 mi]na, the weight of 10 sashes for Anu[nītu] [20 she]kels, the weight of the sūnu-belt for [DN].
```

## 135. BM 62219 (82-9-18, 2188)

 $6.8 \times 3.7 \text{ cm}$ 

- 1. [20] ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>[UTU]
- 2. ina lìb-bi ½ ma-na 「SÍG¹.[ZA.GÌN.KUR.RA]
- 3. 10 ma-na KI.LAL <sup>túg</sup>ṣib-[tu<sub>4</sub> šá <sup>d</sup>UTU]
- 4. 2 ma-na KI.LAL [TÚG.HI.A me SAG.DU šá <sup>d</sup>UTU]
- 5. 1 ma-na 'KI'.[LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
- 6. 1 ma-<sup>r</sup>na<sup>1</sup> [KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]
- 7. [1/3] [....]

Rev.

1'.\( x^\ [....]

Lower part of the reverse is uninscribed.

Rev. 1'. Only one horizontal stroke is preserved.

[20] minas, the weight of the  $lub\bar{a}ru$ -garment for [Šamaš] with addition of  $\frac{1}{2}$  mina of [blue-purple wool]

10 minas, the weight of the *şib*[tu-garment for Šamaš]

2 minas, the weight of the [lubār mē qaqqadi-headdress for Šamaš]

1 mina, the wei[ght of 6 sashes for Šamaš]

1 mina, [the weight of 10 sashes for Aya]

20 [shekels ....].

#### **136. BM 69144** (82-9-18, 9143)

 $5.2 \times 3.1$  cm

- 1'. 2 ma-na [KI.LAL TÚ]G.Ḥ[I.A me SAG.(DU) šá <sup>d</sup>UTU]
- 2'. 1 1/3 ma-na KI. LAL 4 TÚG. Ú[R.MEŠ šá dUTU]
- 3'. 1 ma-na KI.LAL 6 TÚG.NÍG.Í[B.LÁ.MEŠ šá <sup>d</sup>UTU]

\_\_\_\_\_

4'. 2 ma-na 「KI¹.LAL TÚG.HI.A ù TÚG. 「MÁй [šá dHAR] 5'. 15 GÍN KI.LAL 5 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup>Gu-la] 6'. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 「šá¹ [dA-a] Rev. 7'. 50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ 1/3 [GÍN KI.LAL TÚG.ÚR1 8'. šá <sup>d</sup>IM u <sup>d</sup>Ša-la Rest of rev. uninscribed Rev. 6'. The usual place of this line is after l. 3'. Evidently the scribe forgot to write this line there and added it later, when he recognized his mistake. 2 minas, [the weight of the lu]bā[r mē qaqqadi-headdress for Šamaš] 1 mina 20 shekels, the weight of 4 sūn[u-belts for Šamaš] 1 mina, the weight of 6 sash[es for Šamaš] [2 minas], the weight of the *lubāru*-garment and *ṣibtu*-garment [for Bunene] \_\_\_\_\_ 15 shekels, the weight of 5 sashes [for Gula] 1 mina, the weight of 10 sashes for [Aya] 50 shekels, the weight of 10 sashes 20 [shekels, the weight of the *sūnu*-belt] for Adad and Šala. **137. CT 55, 847** = BM 56062 1'. [2 ma-na KI.LAL TÚG].ḤI.A SAG.DU 「šá¹ [ $^{\rm d}$ UTU] 2'. [1 ma-na KI.LAL] 6 TÚĞ.NÍG.ÍB. LÁ¹.MEŠ šá d[UTU] 3'. [1 ma-na KI.LA]L 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>[A-a] 4'. [1] <sup>[1/3]</sup> [GÍ]N<sup>?</sup> KI.LAL 4 TÚG.ÚR.MEŠ *šá* <sup>d</sup>UTU 5'. [1 m]a-na KI.LAL 10 TÚG<sup>!</sup>.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN [Sip-par<sup>ki</sup>] 6'. 1 ma-na 1/3 GÍN TÚG. ḤI.A šá <br/>  $^{\rm rd}$ ḤAR¹ ina lìb-bi 6 GÍN [SÍG.ZA.GÌN.KUR.RA] 7'. 2<sup>!</sup>/3 GÍN KI.LAL *şib-tu*<sub>4</sub> *šá* <sup>d</sup>HAR 8'. PAP ½ GÚ.UN 7 ma-na dul-[lu gam-ru ....] Rev. uninscribed The numeral in 1. 7 is written over erasure. [2 minas, the weight of the  $lu]b\bar{a}r < m\bar{e} > qaqqadi$ -headdress for [Šamaš] [1 mina, the weight of] 6 sashes for [Šamaš] [1 mina, the weig]ht of 10 sashes for [Aya] [1] mina <sup>7</sup>20<sup>7</sup> shekels, the weight of 4 *sūnu*-belts for Šamaš [1 mi]na, the weight of 10 sashes for the Queen of [Sippar] 1 mina 20 shekels, the weight of the *lubāru-g*arment for Bunene with addition of 6

```
shekels of [blue-purple wool]
40! shekels the weight of the şibtu-garment for Bunene
Total 37 minas, the comple[ted work ....].
138. BM 75993 (83-1-18, 1356)
6.9 \times 3.0 \text{ cm}
           1'. [....] KI.L[AL ....]
           2'. [.... 4] 「ÚR」.MEŠ 6 「TÚG」.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
           _____
           3'. [1 ma-na KI.LAL 10 TÚG.NÍG].ÍB.LÁ.MEŠ šá <sup>d</sup>A-a
           _____
           4'. [1 ma-na KI. LAL 10 TÚG.NÍG]. 'ÍB.LÁ¹.MEŠ šá dGAŠAN
                 UD.KIB. \ulcorner NUN \urcorner^{ki}
           5'. [1 ma-na 10] GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ
Rev.
           6'. [ù TÚG.Ú]R šá <sup>d</sup>IM u <sup>d</sup>Ša-la
           7'. [½ ma-na] 5 GÍN KI.LAL 5 TÚG.NÍG.ÍB.LÁ.MEŠ
                 「1 TÚG.ÚR」
                  \check{s}\acute{a}^{\rm d}G[u-la]
           9'. [.... K]I.LAL [....]
[....], the wei[ght of [....]
[.... 4] sūnu-belts, 6 s[ashes for Šamaš]
[1 mina, the weight of 10 sas]hes for Aya
[1 mina, the weight of 10 sas]hes for the Queen of Sippar
[1 mina 10] shekels, the weight of 10 sashes
[and the s\bar{u}]nu-belt for Adad and Šala
[3]5 shekels, the weight of 5 sashes (and) 1 sūnu-belt for G[ula]
[....] the weight [....].
139. BM 52353 (82-3-23, 3387)
3.7 \times 2.1 cm
           1'. [2 ma-na KI.LAL] TÚG.ḤI.A me-e S[AG.(DU) šá <sup>d</sup>UTU]
           2'. [1 ma-na KI.LAL] <sup>[6]</sup> TÚG.NÍG.ÍB.LÁ.MEŠ [šá <sup>d</sup>UTU]
           3'. [1 ma-na KI.LAL] 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>rA¹-[a]
           4'. [1 ma-na KI.LAL] 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-
                 [par^{ki}]
```

```
5'. [x x x KI].LAL] 2' x] [....]
Rev.
              1'. [x x x x x] [....]
              2'. 1<sup>en</sup> TÚG.ÚR [....]
              3'. 「šá <sup>d</sup>Bu-ne-ne<sup>1</sup>
              4'. [....].ÍB. LÁ x x Sip-par lki
              5'. [x \ x] [x \ x] [....]
              6'. [x x x 1 [....]
Rev. is heavily eroded.
L. 5. Only the upper parts of the signs are preserved.
```

```
[2 minas, the weight] of the lubār mē qaq[qadi-headdress for Šamaš]
[1 mina, the weight of] 6 sashes [for Šamaš]
[1 mina, the weight of] 10 sashes for [Aya]
[1 mi]na, the weight of 10 sashes for the Queen of Sip[par]
[\dots] the weight of 2^{?} [\dots]
1 sūnu-belt [....] for Bunene
[.... sas]hes? [x x] Sippar [....].
```

#### **140. BM 53743** (83-3-23, 4783)

 $4.4 \times 2.9 \text{ cm}$ 

- 1'. [TÚG.HI]. [A<sup>?</sup>] TÚG.MÁŠ *šá* [dUTU]
- 2'. 6 NÍG:TÚG.ÍB.LÁ.<MEŠ> šá <sup>d</sup>UTU 4 TÚG.[ÚR.MEŠ]
- 3'. šá <sup>d</sup>UTU TÚG.ḤI.A me-e SAG.[DU šá <sup>d</sup>UTU]
- 4'. [10] NÍG:TÚG.ÍB.LÁ.<MEŠ> šá  $^{\rm d}A$ -a 5'. [10] NÍG]:TÚG.ÍB.LÁ.<MEŠ> šá  $^{\rm d}G$ AŠAN Sip-par $^{\rm ki}$
- 6'. [TÚG.ḤI].「A¹ u (T: šá) TÚG.MÁŠ šá dBu-ne-n[e]
- 7'. [1 ma-na 10 GÍN KI].LAL 1<sup>en</sup> TÚG.Ú[R]
- 8'. [10 TÚG.NÍG.ÍB.LÁ.MEŠ šá  ${}^{d}$ IM  $u^{d}$ ] ${}^{r}$ Ša ${}^{1}$ -l[a]

Rev. completely damaged.

[the lubār]u<sup>?</sup>-garment (and) the *şibtu*-garment for [Šamaš], 6 sashes for Šamaš, 4 [sūnu-belts] for Šamaš, the lubār mē qaqqa[di-headdress for Šamaš], [10] sashes for Aya, [10 sa]shes for the Queen of Sippar, [the lubā]ru and sibtu-garments for Bunen[e];

[1 mina 10 shekels, the wei]ght of 1  $s\bar{u}[nu\text{-belt}]$  (and) [10 sashes for Adad and] Šala.

#### **141. BM 83801** (83-1-21, 964)

 $5.3 \times 3.8$  cm

[x.x.KN].3

- 1. *ép-pu-*[*uš* ....]
- 2. MU.3.KAM [....]

```
3. LUGAL TIN. TIR ki1 [....]
                4. 20 ma-na KI.LAL lu-ba-ri šá [^{d}UTU]
5. 10 ma-na KI.LAL ^{\Gamma}1^{en}] şib-tu<sub>4</sub> šá ^{d}UTU
                6. 2 ma-na KI.LAL lu-<sup>r</sup>ba-ru u MÁŠ<sup>?</sup>¹
                                             \check{s}\acute{a}^{d}B[u\text{-}ne\text{-}ne]
                8. 1 ma-na {10 GÍN} K[I.LAL]
Edge
                9. [6 TÚG].NÍG.ÍB.LÁ.M[EŠ šá <sup>d</sup>UTU]
Rev.
               10. 1 <sup>r</sup>ma-na<sup>1</sup> 1/3 GÍN KI.LAL <sup>r</sup>4<sup>1</sup> [TÚG.ÚR.MEŠ]
               11. šá <sup>d</sup>UTU
               12. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.<MEŠ>
               13. šá <sup>d</sup>A-a
Rest uninscribed
```

L. 8. One *sibtu* for Šamaš suggests that the text belongs to this cycle. However, in this cycle only 6 huşannus were delivered, in consequence 1 ma-na 10 GÍN (l. 8) must be emended to 1 ma-na {10 GÍN}.

```
Ac[count ....] 3<sup>rd</sup> year [....], king of Babylon [....]
```

20 minas, the weight of the *lubāru*-garment for [Šamaš]

10 minas, the weight of 1 *şibtu*-garment for Šamaš

2 minas, the weight of the *lubāru* and *şibtu*-garments for B[unene]

1 mina {10 shekels}, the we[ight of 6 sa]she[s for Šamaš]

1 mina 20 shekels, the weight of 4 [sūnu-belts] for Šamaš

1 mina, the weight of 10 sashes for Aya.

# **142. BM 73764** (82-9-18, 13775)

 $5.5 \times 3.9 \text{ cm}$ 

```
1'. 「7<sup>?</sup>¬ ma-na KI.LAL [....]
```

2'. 2 ma-na 1/3 5 GÍN KI.[LAL ....] 3'. 「4<sup>?</sup>¹ <sup>túg</sup>su-ni-e 6 TÚG.[NÍG.ÍB.LÁ.MEŠ 4'.[x] <sup>túg</sup>ḫu-ṣa-ni-e 「šá¹ [<sup>d</sup>UTU (u <sup>d</sup>A-a)]

5'. [x *m*]*a-na* 「KI.LAL<sup>¬</sup> [....]

Rev. completely eroded

```
[...] ½ mina, the weight of [...]
2 minas 25 shekels, the wei[ght of ....]
[4<sup>?</sup>] sūnu-belts, 6 s[ashes], [x] sashes for [Šamaš (and Aya)]
[x mi]na(s), the weight of [....].
```

# 9. Garments for not recognized *lubuštu* ceremonies (cycle A or B)

#### **143. BM 68353** (82-9-18, 8351)

PLATE 33

 $3.6 \times 4.8$  cm

#### [x.x.Nbk] 23

- 1. [x ma-na KI.LAL TÚG.Ḥ]I.A u <sup>túg</sup>ṣib-ti 「šá <sup>d</sup>UTU<sup>1</sup>

- 1. [x ma-na KI.LAL 1UG.Ḥ]I.A u sib-n sa U1U
  2. [x ma-na] K]I.LAL 1en TÚG.ḤI.A SAG<sup>qa</sup>
  3. [x ma-na KI.LAL x] túg hu-ṣa-nu-ni-e šá dUTU
  4. [x ma-na KI.LAL 10 túg hu-ṣa-nu-ni-e] šá dA-a
  5. [x ma-na KI.LAL 10 túg hu-ṣa-nu-ni-e] šá dGAŠAN Sip-parki
  6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [5. [x ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG.ḤI.A u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG. u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG. u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG. u túg ṣib-t[i šá] [dBu]-ne-<ne>
  [6. [2 ma-na] KI.LAL TÚG. u túg ṣib-t[i šá] [dBu]-ne-<ne>
- 7. [1 ma-na 10 GÍN] KI<sup>!</sup>.LAL<sup>!</sup> (T: a-di) TÚG.ÚR.MEŠ <sup>túg</sup>hu-[şani]- $e \check{s} \acute{a} ^{\mathrm{d}} \mathrm{IM} ^{!} (\mathrm{T:}\mathrm{UTU}) \, u ^{\mathrm{d}} \check{S} a\text{-} la$
- 8. [x ma-na KI.LAL  $5^{?}$   $t^{\acute{u}g}hu$ ]- $^{r}$  $sa^{1}$ -ni-e  $sa^{\acute{d}}Bu$ -ne-ne

Edge

9. [1 ma-na KI.LAL 10 túghu-sa-ni-e šá dDUMU.MÍ.MEŠ É-babbar\-ra

10. [ITI.x.U<sub>4</sub>.x.KAM] MU.23.KAM Rev.

- 11. [dAG-NÍG.DU-ÙRU LUGAL TIN.TIR]ki
- L. 1. This is the only text where the *lubāru* and *şibtu* garments for Šamaš are treated together. Because the fixed quantity of wool for the manufacture of these items was not always indicated at that time, the initial amount cannot be reconstructed.
- L. 2. The signs are very clear and the reading is not. We expect here lubār mē qaqqadi or lubār mē damga.
- L. 7.  $\delta a^{d}$ IM! (T: UTU)  $u^{d}\delta a$ -la is written on the reverse.

Maybe there was an additional line after l. 9 that is now completely destroyed.

[x minas, the weight of the lu]bāru-garment and sibtu-garment for Šamaš;

[x minas], the weight of 1 *lubār* SAG<sup>qa</sup>-headdress

[x minas the weight of x] sashes for Šamaš

[x minas the weight of 10 sashes] for Aya

[x minas the weight of 10 sashes] for the Queen of Sippar

[2 minas], the weight of 1 lubāru and sibtu-garments for Bunene

[1 mina 10 shekels], the weight of the sūnu-belts (and) sashes for Adad and Šala

[1 mina, the weight of 10 sashes for the Daughters of the Ebab]bar

[Month x, n<sup>th</sup> day], 23<sup>rd</sup> year of [Nebuchadnezzar, king of Babyl]on.

# 144. BM 66247 (82-9-18, 6238)

PLATE 34

 $4.8 \times 5.8$  cm

[x.x].Nbn 4

- 1. [dul-lu BABBAR<sup>ú</sup> šá <sup>md</sup>AG-na-ṣ]ir-IBILA a-na É-babbar-ra
- 2. [ $\it it$ -ta-din ITI.x U<sub>4</sub>.x.KAM MU].4.KAM  $\it ^{md}$ AG-I LUGAL E $\it ^{ki}$

- 3. [20 ma-na KI.LAL TÚG.HI.A] šá <sup>d</sup>UTU ina lìb-bi ½ ma-na SÍG.ZA.GÌN.KUR.RA
- 4. [x ma-na KI.LAL túg șib]-tu4 šá dUTU
- 5. [1 ma-na (10 GÍN) KI.LAL 6 (or: 7) TÚG.NÍG].ÍB.LÁ.MEŠ
- 6. [2 ma-na KI.LAL TÚG.HI.A] me SAG.DU šá <sup>d</sup>UTU
- 7. [1 ma-na 1/3 GÍN KI.LAL 4 TÚG.Ú]R.MEŠ šá <sup>d</sup>UTU
- 8. [1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ].MEŠ šá <sup>d</sup>A-a
- 9. [1 1/3 ma-na KI.LAL TÚG.ḤI.A šá]  $^{\text{rd}_1}Bu$ -ne-ne 10. [2/3 ma-na KI.LAL  $^{\text{túg}}$ sib-tu<sub>4</sub> šá]  $^{\text{rd}_1}Bu$ -ne-ne
- 11. [1 ma-na KI.LAL 3 $^{?}$  TÚG.ÚR.MEŠ]  $^{r}$   $\acute{s}\acute{a}$   $^{1}$  dIM u  $^{1}$ HAR Edge 12. [50 GÍN KI.LAL 10 TÚG.NÍG.ÍB.LÁ].MEŠ šá <sup>d</sup>IM Rev.

[u]  $\int_{0}^{1} d\tilde{S}a - la$ 13.

Rest lost

L. 11, cf. BM 59405 (= 146): 9'-10' and BM 66247 (= 144): 11.

[White work which Nabû-nā]ṣir-apli [has delivered] to the Ebabbar temple. [Month x, n<sup>th</sup> day] 4<sup>th</sup> [year] of Nabonidus, king of Babylon.

[20 minas, the weight of the *lubāru*-garment] for Šamaš with addition of ½ mina of blue-purple wool

[x minas, the weight of the sib]tu-garment for Šamaš

[1 mina (10 shekels?), the weight of 6 (or 7) sas lhes for Šamaš

[2 minas, the weight of the *lubār*] *mē qaqqadi*-headdress for Šamaš

[1 mina 20 shekels, the weight of  $4 s\bar{u}$ ]nu-belts for Šamaš

[1 mina, the weight of 10 sash]es for Aya

[1 mina 20 shekels, the weight of the *lubāru*-garment for] Bunene

[40 shekels, the weight of the *şibtu*-garment for] Bunene

[1 mina, the weight of 3<sup>?</sup> sūnu-belts] for Adad and Bunene

[50 shekels, the weight of 10 sash]es for Adad [and] Šala.

#### **145. BM 83436** (83-1-21, 599)

 $3.8 \times 5.8$  cm

6.[x.KN] 4

- 1. [dul-lu BABBAR<sup>ú</sup> šá PN <sup>lú</sup>] [Uй.BAR a-[na É-babbar-ra]
- 2. [it-ta-din ITI.x U<sub>4</sub>]. [6]. KAM MU.4. KAM <sup>m</sup>[KN LUGAL E<sup>ki</sup>]

- 3. [20 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU ina lì]b-bi ½ ma-na [SÍG.ZA.GÌN.KUR.RA šá <sup>d</sup>UTU]
- 4. [x ma-na KI.LAL TÚG.MÁŠ] 「šá¹ dUTU

- 5. [1 ma-na (10 GÍN) KI.LAL 6 (or: 7) TÚG.NÍG.Í]B.LÁ.MEŠ šá  $^{\rm d}$ UTU
- 6. [2 ma-na KI.LAL TÚG.ḤI.A me SA]G.DU šá <sup>d</sup>UTU
- 7. [1 1/3 ma-na KI.LAL 4 TÚG.Ú]R.MEŠ šá <sup>d</sup>UTU u <sup>d</sup>A-a
- 8. [1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ] 「šá<sup>1 d</sup>A-a
- 9. [1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ  $š\acute{a}$ ]  ${}^{d}$ GAŠAN Sip- $par^{ki}$
- 10. [x ma-na KI.LAL x x x šá  ${}^{\rm d}$ GAŠAN Sip]- $par^{\rm ki}$
- 11. [x ma-na KI.LAL x x x šá <sup>d</sup>GAŠAN Sip-p]ar<sup>ki</sup>

Rest lost

The text was identified by M. Kunert.

[White work which PN], the weaver [has delivered to the Ebabbar temple. Month x], 6<sup>th</sup> [day], 4<sup>th</sup> year of [KN, king of Babylon].

-----

[20 minas, the weight of the  $lub\bar{a}ru$ -garment for Šamaš with addi]tion of  $\frac{1}{2}$  mina of blue-purple wool

[x minas, the weight of the sibtu-garment(s)] for Šamaš

- [1 mina (10 shekels), the weight of 6 (or 7) sas]hes for Šamaš
- [2 minas, the weight of the *lubār mē qaqq*]adi-headdress for Šamaš
- [1 mina 20 shekels, the weight of  $4 s\bar{u}]nu$ -belts for Šamaš and Aya
- [1 mina, the weight of 10 sashes] for Aya

1 mina, the weight of 10 sashes for] the Queen of Sippar [x mina, the weight of x x x for the Queen of Sip]par.

# **146. BM 59405** (82-7-14, 3814)

PLATE 34

 $7.2 \times 5.7$  cm

Rev.

- 1'. [.... SÍG.Z]A.GÌN.<KUR>.RA
- 2'. 10 [....]
- 3'. [x T]ÚG.[....]
- 4'. 2 ma-na 「KI.LAL¹ TÚG.ḤI.[A me-(e) SAG.DU šá dUTU]

-----

- 5'. [1 m]a-na 10 GÍN KI.LAL 10 TÚG.NÍG.ÍB.L[Á.MEŠ šá <sup>d</sup>DN]
- 6'. [1 ma-na 1/3 GÍ]N KI.LAL 4 TÚG.ÚR.[MEŠ šá <sup>d</sup>UTU]
- 7'. [50 GÍN] 「KI.LAL¹ 10 TÚG.NÍG.ÍB.LÁ šá $^{\text{r}}$  d¹[IM u]

8'.  $\lceil d \check{S} \rceil a - la$ 

\_\_\_\_\_

- 9'. 1 ma-na KI.LAL 3 TÚG.ÚR.M[EŠ]
- 10'. šá <sup>d</sup>IM u <sup>d</sup>Bu-ne-ne

- 11'. 2 ma-na 15 GÍN KI.LAL TÚG.ḤI.A
- 12'.  $\lceil \dot{u} \rceil^{\text{túg}} sib t[u_4 \check{s} \acute{a}^{\text{d}} B] u ne ne \{\lceil x \rceil\}$
- 13'. [PAP] ½ GÚ.UN 8 5/6 ma-na 6 GÍN

The tablet was previously broken into three parts. The beginning of the obverse (two or three lines) is fully eroded.

L. 3'. Or: [1] *m*[*a* 

L. 5' It is difficult to say to whom belonged the husannus mentioned in this line. The weight 70 shekels suggests that it should be the *huṣannus* for Šamaš, but the numeral 10 that the husannus for Aya were meant.

L. 9'-10' Cf. BM 66247 (= 144): 11 and BM 68413 (= 59): 13-14.

L. 11'. Note that the typical weight of the *lubāru* and the *sibtu* for Bunene was 2 minas.

## [....] of blue-purple wool

10 [....]

2 minas, the weight of the *lubā*[r mē qaqqadi-headdress for Šamaš]

[1 m]ina 10 shekels, the weight of 10 sash[es [for DN] [1 mina 20 shek]els, the weight of 4 sūnu-belts [for Šamaš]

[50 shekels, the w]eig[ht of] 10 sashes for [Adad and Š]ala

1 mina, the weight of 3 sūnu-belts for Adad and Bunene

2 minas 15 shekels, the weight of the *lubāru* and *şibtu*-garments for Bunene, [total] 38 minas, 56 shekels.

#### **147. CT 55, 839** = BM 56080 Collated

- 1. 1 ma-na KI.[LAL 10 TÚG].NÍG.ÍB.LÁ.[MEŠ]
- 2. *šá* [<sup>d</sup>GAŠAN UD].KIB.NUN<sup>ki</sup>
- 3. 52\* GÍN KI.LAL TÚG.BAR.SI šá  $<^d>$ GAŠAN 「 $S\hat{i}p$ - $par^{ki}$ 」
- 4.  $\lceil 1/3 \rceil$  GÍ[N KI.LAL] TÚG. $\lceil \text{ÚR} \rceil$  šá  $<^d > \text{GAŠAN } Sip-p[ar^{ki}]$

- 5. [x x] KI.LAL  $^{\text{túg}}$ sib-tu<sub>4</sub> šá  $^{\text{d}}$ [x]-[x]
- 6. [x x] KI.LAL 10 TÚG.NÍG.ÍB.LÁ.[MEŠ] šá <sup>rd</sup>¹[x]-la
- 7. [1/3 GÍN K]I.LAL TÚG. ÚR <br/>šá [ $^{\rm d}$  DN]

\_\_\_\_\_

- 8. [15 ma-n]a KI.LAL TÚG.UD.A šá <sup>d</sup>I[M]
- Rev.
- 9. [5 ma-n]a KI.LAL <sup>túg</sup>ṣib-tu₄ šá <sup>d</sup>I[M] 10. [50 GÍ]N KI.LAL TÚG.NÍG.ÍB.LÁ.MEŠ
  - šá <sup>d</sup>IM u <sup>d</sup>Ša-la 11.
  - 12. <sup>[1/3]</sup> 4 GÍN KI.LAL TÚG.ÚR TÚG.BAR.SI
  - šá <sup>d</sup>IM
  - 14.  $[x \times x \times x \times h]a$ -a- $tu \check{s}\acute{a}^m \mathring{S}LA$ -a- $tu \check{s}\acute{a}^m \mathring{S}LA$
  - 15. [....].「LÁ<sup>1</sup>

The identification of the gods' names, which are mostly broken, presents a real problem. In 1. 5 the reading <sup>d</sup>UTU suggested by Pinches's copy is unacceptable, because in fact three Winkelhaken are followed with two horizontal and one vertical strokes, which resembles IM. Lines 5-7 must concern the garments of one god, or a god and a goddess, if they were a couple. The last sign in l. 6 seems to be -la and the only possible reconstruction is [G]u-la or  $[\check{S}a]-la$ , however both are excluded because husannus for Adad and Šala appear in l. 10 while Gula received only 5 husannus.

1 mina, the wei[ght of 10 sa]shes for [the Queen of Sippar] 52 shekels, the weight of the *paršīgu*-headdress for the Queen of Sippar 20 shek[els, the weight of] the *sūnu*-belt for the Queen of Sippar

[...], the weight of the *ṣibtu*-garment for [...

[...], the weight of 10 sashes for [x]-la

[20 shekels, the weight of (one) *sūnu*-belt for [....]

.....

[15 min]as, the weight of the  $lub\bar{a}ru$ -garment for Ad[ad]

[5 min]as, the weight of the *şibtu*-garment Ad[ad]

[50 sheke]ls, the weight of <10> sashes for Adad and Šala

<sup>7</sup>2<sup>1</sup>4 shekels, the weight of the *sūnu*-belt (and) the *paršīgu*-headdress for Adad

[.... sup]ply, which Sūqaya [....].

#### **148. BM 58641** (82-7-14, 3050)

PLATE 35

 $3.8 \times 3.1$  cm

1'. [....] <sup>d</sup>UTU 7 T[ÚG.

2'. [.... x TÚG.NÍG].ÍB.LÁ.<MEŠ> šá <sup>d</sup>UTU

3'. [1 ma-na 1/3 GÍN KI.LAL 4] 「ÚR」.MEŠ šá  $^{d}$ UTU  $u < ^{d} > A-a$ 

4'. [....]  $u^{d}A-a$ 

5'. [1 ma-na KI.LAL 10] TÚG.NÍG.ÍB.LÁ.<MEŠ> šá <sup>d</sup>A-a

Edge 6'. [1 ma-na KI.LAL 10 TÚG.NÍG].ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

Rev. 7'. [50 GÍN KI.LAL 10 TÚ]G.NÍG.ÍB.LÁ.MEŠ

8'. [šá <sup>d</sup>I]M u <sup>d</sup>Ša-la

9'. [2 ma-na KI.LAL ṣib]-tu4 šá <sup>d</sup>Gu-la 7 GÍN a-tar

10'. [....] <sup>г<sup>d</sup>¹</sub>ІМ 10 GÍN LAL*-ţi*</sup>

11'. [....] <sup>[</sup>x<sup>]</sup>

- L. 3'. u A-a (the second a has an atypical shape) is written on the right edge in such a way that it gives the impression that it belongs to 1. 2', however, the parallels show that it must belong to 1. 3'. Note the atypical writing of the sign after UTU in 1. 3 which is transliterated as  $u < ^{4} > A$ . I have no idea how to fill the gap in this line.
- L. 9' a-tar, from  $(w)at\bar{a}ru$  "to exceed in number or size" (as a counterbalance of  $mat\hat{u}$ , "to be short a given quality, to be missing" (1.10').

[.... for] Šamaš, 7 [....]

.. sa]shes for Šamaš

[1 mina 20 shekels, the weight of 4] sūnu-belts for Šamaš and Ava

[....] and Aya

[1 mina, the weight of 10] sashes for Aya

[1 mina, the weight of 10 sash]es for the Queen of Sippar

[50 shekels, the weight of 10 sa]shes [for A]dad and Šala [2 minas, the weight of (one) *şib*]*tu* for Gula exceeding in 7 shekels [....] Adad, 10 shekels are missing [....].

#### 149. BM 83329 (83-1-21, 492)

 $4.5 \times 3.7$  cm

#### [x.x].Nbn 7

- 1. [dul-lu BABBAR<sup>ú</sup> šá] <sup>m</sup>IDIM-ja u <sup>md</sup>I-š[um-x]

  <sup>lú</sup>[UŠ.BAR.MEŠ SUM<sup>nu</sup>]
- 2. [ITI.x  $U_{4.}$ X.KAM] MU.7.KAM  $^{md}$ AG-I [LUGAL TIN.TIR $^{ki}$ ]
- 3. [20 ma-na KI.LAL TÚG].ḤI.A šá <sup>d</sup>UTU ina <sup>r</sup>lìb¹-bi ½ ma-[na SÍG.ZA.GÌN.KUR.RA]
- 4. [x ma-na KI.LAL sib]- $tu_4$   $s\acute{a}$   $^d$ UTU {x}
- 5. [2 ma-na KI.LAL TÚG.ḤI].A me SAG.DU šá [<sup>d</sup>UTU]
- 6. [1 1/3 ma-na KI.LAL] 4 TÚG.ÚR [šá <sup>d</sup>UTU u <sup>d</sup>A-a]
- 7. [x ma-na (x GÍN) KI.LAL 6 (or: 7) TÚG.[NÍG.ÍB.LÁ.MEŠ šá  $^{\rm d}$ UTU]

#### Rest lost

L. 1. Maybe  $^{\rm md}I$ - $\check{s}[um$ -D $\check{U}]$ , cf. BM 70333 (= 105): 2 or  $^{\rm md}I$ - $\check{s}[um$ -MU], cf. BM 49416 (= 19): 6.

[White work which] Kabtīya and Išu[m-x], the [weavers have delivered. Month of x, n<sup>th</sup> day], 7<sup>th</sup> year of Nabonidus, [king of Babylon].

[20 minas, the weight of the  $lub\bar{a}$ ]ru-garment for Šamaš with addition of ½ min[as of blue-purple wool]

[x minas, the weight of the *şib*]tu-garments for [Šamaš]

[2 minas, the weight of the *lubā*] r mē qaqqadi-headdress for [Šamaš]

[1 mina 20 shekels, the weight of] 4 sūnu-belts [for Šamaš and Aya]

[1 mina (10 shekels) the weight of 6/7] s[ashes for Šamaš].

#### 150. BM 66817 (82-9-18, 6810)

 $5.8 \times 4.3$  cm

- 1' [....] x [....]
- 2'. [1 ma-na (10  $GÍN^?$ ) KI.LAL 6 (or:7) TÚG.NÍG.ÍB.LÁ].MEŠ šá  $^{\rm d}$ U[TU]
- 3'. [1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ].MEŠ šá <sup>d</sup>A-a

```
4'. [2 ma-na KI.LAL TÚG.ḤI.A ù túg]ṣib-tu4 šá dBu-ne-ne
5'. [ina lìb-bi 6] GÍN SÍG.ZA.GÌN.KUR.RA
```

6'. [1 ma-na KI.LAL 10] TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

7'. [1/3 GÍN KI.LAL TÚG].ÚR šá <sup>d</sup>GAŠAN *Sip-par*<sup>ki</sup>

8'. [1/3 GÍN KI.LAL TÚG.BAR].SI šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> Edge Rev.

9'. [50 GÍN KI.LAL 10] TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>IM u <sup>d</sup>Ša-la

10'. [1/3 GÍN KI.LAL] TÚG.ÚR šá <sup>d</sup>IM 11'. [1/3 GÍN KI.LAL] TÚG.BAR.SI šá <sup>d</sup>IM 12'. [2 ma-na KI.LAL túgṣib]-「tu41 šá dGu-la

13'. [15 GÍN KI.LAL] <sup>[5]</sup> TÚG.NÍG.ÍB.LÁ.<MEŠ> šá <sup>d</sup>Gu-<la>

#### Rest uninscribed

L. 1'. Only tiny fragment of horizontal line is preserved.

[1 mina, (10 shekels), the weight of 6 (or 7 sashels for Ša[maš]

[1 mina, the weight of 10 sashe]s for Aya

[2 minas, the weight of the *lubāru* and] *sibtu*-garments for Bunene with addition of 6 shekels of blue-purple wool

[1 mina, the weight of 10] sashes for the Queen of Sippar

[20 shekels, the weight of the] sūnu-belt for the Queen of Sippar

[20 shekels, the weight of the par]šīgu-headdress for the Queen of Sippar

[50 shekels, the weight of 10] sashes for Adad and Šala

[20 shekels, the weight of] the sūnu-belt for Adad

[20 shekels, the weight of] the paršīgu-headdress for Adad

[2 minas, the weight of the sib]tu-garment for Gula

[15 shekels, the weight of] 5 sashes for Gu<la>.

#### **151. BM 72376** (82-9-18, 12382)

 $6.0 \times 3.9$  cm

```
1'. [x ma]-na [....]
```

2'. [x *ma-n*]*a* KI.[LAL ....]

3'. [1 ma]-na KI.LAL 10 TÚG.[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]

4'. [2 ma-n]a KI.LAL TÚG.HI.[A TÚG.MÁŠ]

5'. [šá] <sup>[d</sup>]*Bu-ne-ne* 

6'. [x] GÍN SÍG.ZA.<GÌN>.KUR.RA Edge

7'. [x *ma-na* KI.LAL] 10 TÚG.[....] Rev.

8'. [x x x] x [x (x)]  ${}^{\Gamma}U_4^{?}.2^{?}{}^{\Gamma}[...]$ 

9'. [x x x x]  $[x^1-a^{1\acute{u}}[x^1[...]]$ 

10'. [x x x x x] šá U<sub>4</sub>.3+x [....]

11'.  $[x \times x \times x] 1/3 ma^{?} [....]$ 

L. 9'. The sign a is preceded by a damaged sign, maybe la, ma or šu while  $l\~u$  is followed by the fragment of sign looking like ni with one vertical stroke. There is a large hole on the left side of rev. 8'–11'.

```
[...., x mi]na [....]
[.... x mi]na, the wei[ght of ....]
[1 mi]na, the weight of 10 s[ashes for Aya]
[2 min]as, the weight of the lubāru (and) [the ṣibtu-garments for] Bunene
[x] shekels of blue-purple wool
[x mina, the weight of] 10 [sashes for ....].

152. BM 101793 (83-1-21, 3454)
3.3 × 3.7 cm
```

```
1'. [....] x TÚG.ḤI.A
2'. [....TÚ]G.NÍG.[ÍB.LÁ].MEŠ šá <sup>d</sup>UTU
3'. [1.ma.na.KII.AI. 10 TÚG.NÍG. ÍIB.I.
```

3'. [1 *ma-na* KI.LAL 10 TÚG.NÍG. Í]B.LA.MEŠ *šá* <sup>d</sup><sup>r</sup>*A*¹-*a* 4'. [.... KI.LAL 10 TÚG.NÍG.Í]B.LÁ.MEŠ 1 TÚG.BAR.SI

5'. [.... d]GAŠAN Sip-par,ki

6'. [2 ma-na KI.LAL] TÚG.HI.A

Edge Rev. 7'. [TÚG.MÁŠ *šá* <sup>d</sup>*Bu*]-*ne-ne* 8'. [....].<sup>r</sup>x¹.MEŠ

9'. [....] šá <sup>d</sup>Gu-la

10'. [....  $^{d}$ ]A- $^{\Gamma}a^{?!}$  $^{\dagger}$ 

11'. [....] TှÚG.BAR.SI 1 TÚG.ÚR

12'. [....] <sup>rd</sup>IM<sup>1</sup>

```
[....] lubāru-garment
```

[....] sashes for Šamaš

[1 mina, the weight of 10] sashes for Aya

[.... the weight of 10 sas]hes, 1 paršīgu-headdress [.... for] the Queen of Sippar

[2 minas, the weight of] the *lubāru* (and) [*sibtu*-garments for Bu]nene

[....] for Gula

[....] A[ya<sup>?</sup>]

[....] paršīgu-headdress, 1 sūnu-belt

[.... for] Adad.

#### 153. BM 69973 (82-9-18, 9973)

 $4.3 \times 2.8$  cm

- 1. [x ma]-na KI.LAL ˈTÚG¹.ḤI.「A¹
- 2. [u TÚ]G.MÁŠ šá <sup>d</sup>Bu-ne-ne
- 3. [x] *ma-na* 6 GÍN KI.LAL [....]

```
4. [1/3] ma-na 1<sup>en</sup> TÚG.ÚR [....]
               5. [x]^{\lceil}x x^{\rceil} [x x]^{\lceil}x^{\rceil} [...]
[x mi]na, the weight of the lubāru [and] şibtu-garments for Bunene
[x] mina 6 shekels, the weight [....]
[20] shekels, <the weight of> 1 sūnu-belt [....].
154. CT 55, 846 = BM 57985
               1'. [....] \check{s}\acute{a}^{? t\acute{u}g}e-ri u T\acute{U}[G ....]
               2'. [....] <sup>r</sup>x<sup>1</sup>šá <sup>d</sup>[....]
              3'. [.... SÍG.ZA].GÌN.KUR.RA KI.LAL TÚG.[....]
               4'. [....] šá {}^{d}GAŠAN Sip-pa[r^{ki}]
              1'. [....] {}^{T}x x^{1}[....]
2'. [x ma-n]a^{2} 5 GÍN KI.[LAL [....]
               3'. [....] 3 GÍN KI.LAL x [....]
               4'. [....] GÍN KI.L[AL ....]
               5'. [....] 1 TÚG/ku [....]
               6'. [....] GÍN KI.LAL TÚG.[....]
               7'. \check{s}\acute{a}^{\rm d}\check{S}a-l[a]
[....] of erru-headband and [....]
```

[....] for [....]

Rest lost

Rev.

[....] blue-purple wool, the weight of [....]

[....] for the Queen of Sippa[r]

[.... x min]a 5 shekels, the weight of [....]

[....] 3 shekels, the weight of [....]

[....] shekels, the weight of [....]

[....] 1 [....]

[....] shekels, the weight of [....]

[....] for Šal[a].

#### **155. BM 59981** (82-7-14, 4391)

```
1. [x x x] <sup>r</sup>x<sup>1</sup> šá U<sub>4</sub>.7.[KAM ....]
```

2. [x x x]-PAP a-n[a ....]

3. [x ma-na KI.LAL TÚG me]- $\lceil e^{?!} \rceil$  SAG.DU [....]

4. [x ma]-na KI.L[AL x TÚG.H]I.A<sup>?</sup> šá <sup>d</sup>UTU

5. [x *ma*]-*na* KI.[LAL x x].UD.A [....]

5. [x *ma*]-*na* KI.[LAL ....]

6. [x ma]-na KI.LAL [....]

7. [x ma]-na KI.LAL [....]

Rest lost

L. 3. The fragmentarily preserved sign preceding SAG.DU resembles TÚG. The preserved fragments of signs suggest that the order of counting of garments was atypical.

```
[....] for the 7^{th} [....]
[....]-nāṣir fo[r ....]
[x mina, the weight of lubār m]ē qaqqadi-headdress [....]
[x mi]na, the wei[ght of the lubā]ru for Šamaš
[x mi]na, the wei[ght of ....]
[x mi]na, the wei[ght of ....]
[x mi]na, the wei[ght of ....].
```

#### **156. BM 73661** (82-9-18, 13672)

 $4.5 \times 2.6$  cm

- 1'. [....] <sup>[</sup>x x<sup>]</sup>
- 2'. 「x x x<sup>1</sup> <sup>md</sup>UTU-MU-MU <sup>lú</sup>TÚG.BABBAR
- 3'. [x x x x] TÚG.NÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>UTU
- 4'. [x x x TÚG.HI.A me-e] SIG<sub>5</sub> šá <sup>d</sup>UTU
- 5'. erased

6'. [1 ma-na 1/3 GÍN KI.LAL] [4] TÚG.ÚR.MEŠ šá  $^{\rm d}$ UTU 7'. [1 ma-na KI.LAL 10 TÚG.NÍG].ÍB.[LÁ] šá  $^{\rm d}$ A-aRev.

- 8'. [.... TÚG.NÍG].ÍB.LÁ.MEŠ šá
- 9'. [....] [x] GÍN<sup>?</sup> ina IGI-šú
- [....] Šamaš-šum-iddin, the ašlāku
- [....] sashes for Šamaš
- [.... lubār mē] damqi-headdress for Šamaš
- [1 mina 20 shekels, the weight of] 4 sūnu-belts for Šamaš
- [1 mina, the weight of 10 sash]es for Aya
- [...., the weight of x sash]es for [....]
- [....] shekels at his disposal.

#### **157. BM 100720** (83-1-21, 2381)

 $4.6 \times 5.5$  cm

Obv. is almost completely eroded, and except for one line, only a few isolated signs are preserved.

```
[.... KI].LAL 10 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup>DN]
Obv.
              1. 1/3 [ma-na KI.LAL] 1 < TÚG>. ÚR šá <sup>d</sup>[DN]
Rev.
              2. 1/3 G[ÍN KI.LAL TÚ]G.ÚR šá [....]
              3. 1/3 \text{ G\'{I}N} [x x x]^{\mathsf{r}} x^{\mathsf{r}} \check{s} \check{a} [....]
              4. 1 5/6 ma-na KI.[LAL ....]
```

- 5. 1/3 G[ÍN KI.LAL [x][x x d][IM<sup>?</sup>]
- 6. [2] ma-na KI.LAL ṣib-tu4 「šá <sup>d</sup>]Gu-la

```
7. 「15<sup>?</sup>」 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>「IM<sup>?</sup>」
8. [1 ma-na KI].LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ [....]
```

Rev. 3. Before šá two heads of vertical strokes are preserved.

Rev. 6. The numeral 4 is written with four horizontal lines.

Rev. Only one slightly damaged vertical stroke is preserved, so the expected numeral  $^{1}5^{1}$  is doubtful.

[...., the we]ight of 10 sashes for [....] 20 sh[ekels, the weight of the s]ūnu-belt for [....] 20 sh[ekels, ....] 1 mina 50 shekels, [....] 20 sh[ekels, the weight of the sūnu-belt for] Adad<sup>?</sup> [2] minas, the weight of the sibtu-garment for Gula [15<sup>?</sup>] minas, the weight of the lubāru-garment for Adad<sup>?</sup> [1 mina, the wei]ght of 10 sashes [....].

#### **158. BM 59328** (82-7-14, 3737)

 $4.3 \times 5.2$  cm

4'. [šá] <sup>d</sup>GAŠAN [Sip-par<sup>ki</sup>]

5'. [15] GÍN KI.LAL 5 TÚG .[NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>Gu-la]

6'. [50 G]ÍN KI.LAL 10 TÚG.NÍG.Í[B.LÁ.MEŠ] 7'. [šá] <sup>d</sup>IM¹ [u <sup>d</sup>Ša-la]

[....] the weight of [....] for [....]

[1 mi]na, the weight of 10 sa[shes for] the Queen of Sippar

[15] shekels, the weight of 5 s[ashes for Gula]

[50 she]kels, the weight of 10 sas[hes for] [Adad] [and Šala]

#### **159. BM 71732** (82-9-18, 11735)

 $4.3 \times 4.0 \text{ cm}$ 

Cam 7

- 1. [du]l-lu BABBAR $^{\acute{u}}$  šá lu-bu-u[ $\check{s}$ -tu4 šá U4.x.KAM]
- 2. ITI.[x] MU.7.KAM <sup>m</sup>Kam-[bu-zi-ja]

```
3. LUGAL [TIN.TIR<sup>ki</sup>] LUGAL KUR.KUR <sup>m</sup>r<sup>d</sup>¹[....]
4. [id-din-nu ITI.x] U<sub>4</sub>.11[KAM MU7.KAM]

5. [20 ma-na KI].LAL.T[ÚG.ḤIA šá <sup>d</sup>UTU]
6. [x ma-na K]I.L[AL. TÚG.MÁŠ šá <sup>d</sup>UTU]

Rev. 1'. [.... KI.LA]L 10 TÚ[G ....]
2'. [....] KI.LAL 10 TÚ[G ....]
3'. [....] KI.LAL TÚG.BAR.SI [....]
4'. [....] r<sup>túg¹</sup>ṣib-t[u₄²! ....]

5'. [....] ma-na dul-lu [....].
```

Rest of rev. uninscribed

Rev. 1'-4'. The preserved lines include the final part of the tablet, which suggests that the sashes for minor gods and goddesses were enumerated there (i.e. the Queen of Sippar or Anunītu, next Adad and Šala; such place of the *şibtu* is not known, and the identification is doubtful, maybe for Gula.

White [wo]rk for the  $lubu\check{s}[tu]$  ceremony [for the n<sup>th</sup> day, nth] month, 7<sup>th</sup> year of Cam[byses], king [of Babylon], king of Lands, (which) [PN has delivered. Month x],  $11^{th}$  day, [7<sup>th</sup> year]

```
[20 minas, the weight of] the l[ubāru-garment for Šamaš] [x minas, the w]eigh[t of the şibtu-garment for Šamaš]
```

```
[...., the w]eigh[t of 10 sashes for ....]
[...., the weight of] 10 s[ashes for [....]
[...., the weight of] the paršīgu-headdress [for ....]
[...., the weight of] the sibtu-garment for [....]
[...., mina(s), [the completed] work [....].
```

#### **160. CT 55, 854** = BM 58175 Collated

```
1'. [1 ma-na] 「KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEй [šá <sup>d</sup>A-a]
2'. [x ma-na x] 「GÍN¹ KI.LAL TÚG.ḤI.A 「ù¹

Edge 3'. [<sup>túg</sup>ṣib]-tu₄* ina* lìb*-「bi¹* 6 GÍN S[ÍG.ZA.GÌN.KUR.RA]

1'. [.... KI.LAL] 「10¹ TÚG.NÍG.ÍB.LÁ.MEŠ šá [<sup>d</sup>DN]
2'. [.... Š]a²-la 1/3 GÍN KI.[LAL ....]
3'. [.... s]u-ú-nu šá <sup>d</sup>IM
```

Rev. 1' TÚG and ÍB.LÁ are written over erasure.

```
[1 mina], the weight of 10 sashes [for Aya] [x mina x] shekels, the weight of the lubāru and [ṣib]tu-garments with addition of 6 shekels of b[lue-purple wool]
```

```
[.... the weight of 10 sashes for [....] [.... for Š]ala 20 shekels, the we[ight of ....] [.... s]ūnu-belt for Adad.
```

#### **161. BM 84490** (83-1-21, 1653)

 $3.8 \times 3.5$  cm

#### [x.x].Nbn 1

- 1. [x ma-na x x x] KI.LAL
- 2. [x x x x x].MEŠ šá <sup>d</sup>UTU
- 3.  $[1/3^{?} m]a^{-1}na^{-1}$  5 GÍN KI.LAL
- 4. 1 *su-ni-e šá* { <sup>d</sup>}
- 5.  $\int_{0}^{d} A a$
- 6. [1 *ma-n*]*a* KI.LAL 10 TÚG.<sup>r</sup>x x x<sup>1</sup>.MEŠ<sup>?</sup>

Edge Rev. .  $[\check{s}\acute{a}]^{\mathsf{r}^{\mathsf{d}}\mathsf{l}}A-a$ 

8. [20 m]a-na KI.LAL 9.  $[^{\text{túg}}]lu$ -ba-ri u  $^{\text{túg}}$ sib- $^{\Gamma}tu$ 4 $^{\Gamma}$ 

10.  $[\check{s}\check{a}]^{\mathsf{r}^{\mathsf{d}}\mathsf{l}}\mathrm{IM}$ 

- 11. [2 ma]-na KI.LAL şib-tu4 šá <sup>d</sup>ME.ME
- 12. [ITI.x U<sub>4</sub>.x.KAM] MU.1.KAM
- 13. [mdAG]-I LUGAL Eki
- L. 3. Because the normal weight of the  $s\bar{u}nu$  was 20 shekels, most probably this one was a little heavier.
- L. 6. We expect here 10 TÚG.NÍG.ÍB.LÁ.MEŠ, however, all three signs looks erased and do not conform to the expected reading.
- L. 7. The second a is written over lu.
- L. 12. MU is written over erasure.

<sup>d</sup>ME.ME in l. 11 and E<sup>ki</sup> in l. 12 are written on the right edge.

[x mina ....], the weight of [....] for Šamaš

[2]5 shekels, the weight of 1 sūnu-belt for Aya

[1 min]a, the weight of 10 [sashes?!] for Aya

[20 m]inas, the weight of the lubāru and the sibtu-garments [for] Adad

[2 mi]nas, the weight of the *sibtu*-garment for Gula.

[Month of x, n<sup>th</sup> day] 1<sup>th</sup> year of [Nabo]nidus, king of Babylon.

#### 162. BM 68324 (82-9-18,8322)

Fragment of a tablet of irregular shape with large signs and with quite large distance between the signs. A school text?

- 1'. [....] TÚG.[....]
- 2'. [....]  $^{rd}$  GAŠAN UD.[KIB.NUN $^{ki}$
- 3'. [.... KI.LA]L TÚG.ÚR [....]

```
4'. [.... KI.LA]L TÚG.BAR.SI [....]
5'. [.... KI.LA]L TÚG.ÚR [....]
6'. [.... KI.LA]L <sup>túg</sup>ṣib-tu₄ [....]
7'. [15 GÍN KI.LA]L 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá [<sup>d</sup>Gu-la]
8'. [....] 「x¹ SÍG.ZA.{SÍG.ZA}.GÌN².[KUR.RA
9'. [....] 「GÌN²¹.KUR [....]
Rev. 1'. [.... KI.LA]L 4 [....]
2'. [.... KI.LA]L 1 TÚG.「ḤI.A¹ [....]
3'. [.... KI.LA]L 「TÚG¹.ÚR² [....]
4'. [....].RA x[....]
5'. [....] šá <sup>d</sup>UTU [....]
6'. [....] x x [....]
7'. [....] x x [....]
```

The signs in obv. 8' except the last one are clear. In obv. 9 there is a large distance between both signs.

```
[.... for] the Queen of Si[ppar ....]
[.... the weigh]t of the sūnu-belt [....]
[.... the weigh]t of the paršīgu-headdress [....]
[.... the weigh]t of the sūnu-belt [....]
[.... the weigh]t of the sibtu-garment [....]
[15 shekels, the weigh]t of 5 sashes for [Gula]
[.... blue-purple wool [....]
[.... the weigh]t of 4 [....]
[.... the weigh]t of the lubāru-garment [...
[.... the weigh]t of the sūnu-belt [....for Šamaš [....]
```

## III. The ēpeš nikkassi accounts

#### 163. BM 76590+BM 79793+BM 99874

**PLATE 35-36** 

(83-1-18, 1961+89-10-14, 341+83-1-21, 2236)

 $7.2 \times 8.6$  cm

The text, divided into two columns, is preceded with the heading (ll. 1-2) running across the whole tablet.

 $[x.x.Nbn 8^?]$ 

Obv.

- 1. 「e¹-peš NÍG.[KA<sub>9</sub> šá SÍG.ḤI.A šá it-ti <sup>md</sup>AG-na-ṣi]r-<A>  $^{\Gamma^{l\acute{u}}}U\check{S}.BAR^{7}$
- 2. *ul-*<sup>r</sup>*tu*<sup>1</sup> [ITI.x.U<sub>4</sub>.x.KAM *a-di* ITI.x.U<sub>4</sub>.x.KAM MU.8<sup>?</sup>.KAM mdAG-I LU]GAL TIN.TIRki

Col. I.

- 3. [1] GÚ.UN [5] *ma-na a-na* [*dul-lu*]
- 4. šá [lu-bu-u]š-tu4 ITI.KIN
- 5. 「šá¬ a-na 「md AG¬-na-sir x (er.)
- 6. [m]  $Ba-ku^{\dagger}-\acute{u}-a$   $[\mathring{u}]$
- 7.  ${}^{m}A$ -na- $[{}^{d}A]G$ -ub-ni-ja SUM $[{}^{in}]$
- 8. 2 GÚ.UN SÍG.HI.A a-na lu-bu-uš-tú
- 9. šá ITI. <sup>r</sup>ŠE¹ MU.7.KAM ù
- 10. [ITI.BÁR] MU. [8]. KAM a-na
- 11. [ $^{\mathrm{md}}$ UTU-NUM]UN-GÁL $^{\check{s}i}$  A [ $^{\mathrm{m}}$ Sil-la-a] 12. [ $\grave{u}$   $^{\mathrm{m}}$ ]Ba-ku-ú-a SUM $^{in}$
- 13. [1 GÚ.UN] 20 ma!-<na> SÍG.HI.A a-na dul-lu
- 14. [šá IT]I.GU<sub>4</sub> MU.8.KAM a-na
- 15. [<sup>md</sup>U]TU-NUMUN-GÁL<sup>ši m</sup>Ba-ku-ú-a
- 16.  $\lceil \hat{u} \rceil$   $\stackrel{\text{md}}{=}$  AG-ub-ni- $\{ni\}$ -ja SUM
- 17. [IT]I.ŠE U<sub>4</sub>.<sup>[2]</sup>(or: <sup>[5]</sup>).KAM MU.8.KAM
- 18. [1] GÚ.UN <sup>[6</sup><sup>?</sup> ma-na <sup>[</sup>SÍG.ḤI.A]
- 19. [a]-na dul-lu šá ITI.KIN  $[u^?]$
- 20. [IT]I.DU<sub>6</sub> MU.8.KAM a-na
- 21. <sup>m</sup>Ba-<sup>r</sup>ku<sup>1</sup>-ú-a ù <sup>md</sup>AG-ub-ni-ja
- 22. 1 GÚ.UN 15 ma-na SÍG.HI.A
- 23. *a-na lu-bu-*<sup>[</sup>*uš*<sup>]</sup>*-tu*<sup>4</sup> *šá*
- 24. [IT]I.「APIN<sup>?</sup>1 M[U.8.KAM]

Rest lost

```
Obv. col. II (after heading common for both columns of the obvers)
                  3. 2 GÚ.UN 10 ma-na SÍG.HI.A<sup>!</sup> d[ul]-lu
                  4. šá ITI.ŠE šá 「MU.7<sup>?</sup>¬.KAM ù
                  5. ITI.BÁR MU.<sup>[8]</sup>.KAM a-na
                 6. ^{\text{rm}}Ba\text{-}ku\text{-}\acute{u}^{\text{1}}\text{-}a\ \grave{u}\ ^{\text{md}}\text{AG-}[ub\text{-}ni\text{-}ja]
                  7. [x GÚ.UN x m]a-na [SÍG].[HI.A]
                  8. a-na lu-bu-<sup>r</sup>uš<sup>1</sup>-tu<sub>4</sub> šá ITI.G[U<sub>4</sub> M]U.<sup>r</sup>8<sup>1</sup>.KAM
                  9. 2 GÚ.UN SÍG.ḤI.A ri-ḥi pap-pa-[su]
                10. šá ITI. 「SIG<sub>4</sub>?」 MU.8.KAM ù ITI. [x M]U. 「8?」.KAM
                11. a-na <sup>m</sup>B[a?-ku]-\lceil \acute{u} \rceil-a <sup>md</sup>[....]
                12. \lceil x \rceil \lceil \dots \rceil \lceil x \mid x \rceil \lceil (x \mid x) \rceil
                13. e-pe[š ....]
                14. 5 ma-na [....]
                15. dul-l[u ....]
                16. 1/ina [....]
               17. a-[....]
               18. [....]
               19. [....]
               20. [....]
               21. <sup>[15]</sup> [....]
               22. 2 [....]
Rest lost
Rev. col. I
                  1'. [x][....]
                  2'. 11 [....]
                  3'. PAP 1<sup>[5<sup>?</sup>]</sup> [....]
                  4'. 2 2/3 [....]
                  5'. dul-l[u ....]
                  6'. ½ m[a-na\ mu]t-ta-tu_4\ 1\ ni-bi-\lceil hi\rceil
                  7'. [1/2] ma-na TÚG.ḤI.A me-ṭu ù
                  8'. TÚG.ḤI.A kul-lu-lu šá <sup>d</sup>UTU
                  9'. 6 ½ ma-na ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a
                10'. 1 ma-na 10 GÍN TÚG.HI.A kul-lu-lu
               11'. 2 < ^{\text{túg}} > par-ši-gu < ^{\text{meš}} > \grave{u} \ e-ri \ \check{s}\acute{a} \ ^{d}A-[a]
12'. 1 ma-na \ 2 < ^{\text{túg}} > par-\check{s}i-gu < ^{\text{meš}} > \text{TÚG.HI.A} \ kul-lu-^{\text{r}}lu^{\text{l}}
               13'. 1 e-ri šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
                14'. ½ ma-na TÚG.HI.A me-ţu ù
                15'. TÚG.ḤI.A kul-<sup>r</sup>lu<sup>1</sup>-lu šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
                16'. ½ ma-na 5 GÍN ni(T:ir)-bi-h[i]
                17'. [x \times x \times x \times \delta a^d Bu]-ne-ne
                18'. [x x TÚG.HI.A k]ul-lu-lu [....]
                19'. [x x x x x x]^{T} x x^{T} [....]
```

```
20'. 1^{5} [x x x x x] lu^{2} x [....]
L. e.
            21'. par-ši-g[u SÍG.ZA.GÌ]N. KUR.RA<sup>?!</sup>1
            22'. PAP 9 m[a-na \times \times \times \times] \lceil x \rceil<sup>meš?</sup>
            23'. \lceil 2 \frac{1}{2} ma^{1} - [na \times x \times x] \lceil x^{1} \rceil
Rev. col. II.
              1'. [M]U<sup>?</sup>.'7'.K[AM ....]
              2'. ITI.NE U<sub>4</sub>.[x.KAM]
              3'. 8 GÚ.UN 4<sup>r</sup>5<sup>1</sup> [ma-na
              4'. dul-lu <sup>síg</sup>ta-bar-ra
              5'. ù SÍG.<ZA>.GÌN.KUR.RA šá <sup>m</sup>Ba-k[u-ú-a]
              6'. \dot{u}^{\text{md}}AG-up-ni-i\acute{a} a-n[a]
              7'. É-kur-ra id-din-[nu]
              _____
             9'. [x] <sup>r</sup>ma-na<sup>1</sup> 1/3 GÍN KI.LAL
            10'. [1<sup>et</sup> k]u-si-tu<sub>4</sub> šá <sup>d</sup>A-a
            11'. 4 ma-na 17 GÍN KI.LAL
            12'. [T]ÚG.GÚ.UD.DU šá <sup>d</sup>A-a
            13'. [x] ma-na KI.LAL lu-bar-ru me-tu
            14'. 「ù lu-bar-ru ku-lu-lu
            15'. [šá <sup>d</sup>HA]R<sup>?</sup> <sup>[1]</sup> ma-na 4 GÍN<sup>1</sup>
            16'. KI.LAL ku-si-tu4 ù
            17'. 「4¹ TÚG.GÚ.UD.DU šá dDUMU.MÍ.MEŠ É-babbar-ra
            18'. 1 ma-na 10 GÍN KI.LAL
            19'. TÚG.ḤI.A ku-lu-lu e-ri
            20'. ù 2 TÚG.BAR.SI.MEŠ
            21'. šá {}^{\rm d}A-a 1 ma-na KI.LAL
            22'. TÚG.ḤI.A ku-lu-lu 2 < tig>par-ši-gu< meš>
            23'. ù e-ri šá <sup>d</sup>[GAŠAN Sip-par<sup>ki</sup>]
```

Col. I, 1. 3. The numeral is broken, and it is difficult to say if it was 1 or only  $\frac{1}{2}$ , however, by comparison with 1. 22 I decided to read it as 1.

24'. ½ ma-na K[I.LAL TÚG.ḤI.A me-ṭu]

25'. ù [TÚG.ḤI.A *ku-lu-lu*] 26'. [*šá*] <sup>d</sup>[*A*]-*nu-ni-tu*<sub>4</sub>

Ll. 8–12, cf. BM 65047 (= 393): 1–8.

L. e.

L. 13 The numeral after 20 is written over an erasure and is similar to ma, but na is not written.

Rev. col I. It is not excluded that between l. 5' and 6' there was an additional line, now completely missing. In this column because of lack of space KI.LAL is regularly omitted. Rev. col. I 7'-8', cf. BM 83511 (= 464): 1-7.

Rev. col. II 7'. In this line the temple's name  $\acute{E}$ -kur-ra is mentioned and the following lines enumerate precisely the type of garments for the gods and goddesses, i.e. Aya, Bunene, the

Daughters of the Ebabbar, the Queen of Sippar and Anunītu. According to the present state of research Aya and Bunene dwelled in Ebabbar, while other goddesses in the ekurrāte, i.e. in small sanctuaries. Can we understand this information to mean that, at least at this time Bakûa and his colleagues worked in a workshop in these "small sanctuaries"

Note that BM 83281 (= 429), written in 8<sup>th</sup> year of Nabonidus, might be the source for this account although its operative section included a slightly different amount (1 talent 40 minas) given to Bakûa only.

Settlement of acco[unt for wool with Nabû-nāṣi]r-<apli>, the weaver from [nth day of the month x till n<sup>th</sup> day, 8<sup>?th</sup> year of Nabonidus], king of Babylon.

#### Col. I

<sup>7</sup>1<sup>?</sup>1 talent 5 minas < of wool> for the [wor]k for the [lubuš]tu ceremony of the month Ulūlu which was given to Nabû-nāṣir, Bakûa and Ana-Nabû-upnīya.

2 talents of wool for the *lubuštu*-ceremony for the month [Addaru], 7<sup>th</sup> year, and the month [Nisan]nu, 8<sup>th</sup> year, was given to [Šamaš-z]ēr-ušabši, son of 「Şillāya<sup>1</sup>

[1 talent] 20 mi<nas> of wool for the work [of the month] of Ayaru, 8th year, was given to Šamaš-z]ēr-ušabši, Bakûa and Nabû-upnīva. Month of Addaru, 2<sup>nd</sup> (or 5<sup>th</sup>) day, 8th year.

[1 talent [6]] minas of wool for the work for the month of Ulūlu [and] Tašrītu, 8<sup>th</sup> year, was given to Bakûa and Nabû-upnīya.

1 talent 15 minas of wool for the *lubuštu*-ceremony [for the mont]h Arahsamna, [8<sup>th</sup> year ....].

#### Col. II

2 talents 10 minas of wool, (for) the w[or]k for the month Addaru, [7th?] year and the month Nisannu, 8th year (was given) to Bakûa and Nabû-[upnīya]. [x talent x m]ina of wool for the *lubuštu* ceremony for the month Ayaru, 8<sup>th</sup> year. 2 talents of wool, the rest of the prebendary income for the month [Simanu], 8<sup>th</sup> year, and the month [x], [8<sup>th</sup>? year was given] to B[ak]ûa [....]

account [....], 5 minas [....] work [....] 15 [....] 2 [....].

#### Rev. Col. I

11 [....] total 1<sup>r</sup>5<sup>1</sup> [....] 2 2/3 [mina [....] the wor[k ....]

½ m[ina, <the weight of> the mu]ttatu-headdress (and) 1 nēbehu-belt

½ mina, <the weight of> the lubār mētu and the lubār kulūlu-headbands for Šamaš 6 ½ mina, <the weight of> the robe for Aya

1 mina 10 shekels, the weight of the *lubār kulūlu*-headband, 2 *paršīgu*-headdresses and the  $\langle lub\bar{a}r \rangle$  erru-headband (for) A[ya]

1 mina, <the weight of> 2 paršīgu-headdresses, the lubār kulūlu-headband (and) 1 < lubār > erru-headband for the Queen of Sippar

½ mina, <the weight of> the *lubār mēṭu* and the *lubār kulūlu*-headbands for Anunītu 35 shekels, <the weight of> the *nēbehu*-belt [.... for Bu]nene

```
[.... the lubār] kulūlu-headband [....]
1<sup>[5]</sup> [....]
[blue-purp]le paršīgu-headdress, total 9 mi[nas ....] 2 ½ mi[na ....].
Rev. col. II
```

[....] 7<sup>th</sup> [ye]ar [....] month Abu, [n<sup>th</sup>] day [....] 8 talents, 45 [minas ....]

Red and blue-purple work, which Bakûa and Nabû-upnīya have delivered to the Ekurra.

3 ½ mina, [the weight of the] *nēbehu*-belt for Šamaš

[x] minas 20 shekels, the weight of [1] robe for Aya

4 minas 17 shekels, the weight of the *nahlaptu*-cloak for Aya.

[x] mina, the weight of the lubār mēţu and the lubār kulūlu-headbands [for Bunlene

1 mina 4 shekels, the weight of (1) robe and 4 nahlaptu-cloaks for the Daughters of the Ebabbar

1 mina 10 shekels, the weight of the *lubār kulūlu*, the *<lubār> erru*-headbands and 2 paršīgu-headdresses for Aya

1 mina, the weight of the *lubār kulūlu*-headband, 2 *paršīgu*-headdresses and the < lubār > erru headband for [the Queen of Sippar]

½ mina, the w[eight of the lubār mētu] and [the lubār kulūlu-headbands for] Anunītu.

#### **164. BM 68788** (82-9-18, 8787)

PLATE 36

 $3.0 \times 3.7 \text{ cm}$ 

- 1. [x] *ma-na* 10 [GÍN KI.LAL ....]
- 2. GÚ.UD.DU [ $\check{s}\acute{a}^{d}x$ ]
- 3. 1 *ma-na* 10 G[ÍN KI.LAL]
- 4. túge-ri 1 [+1 TÚG.BAR.SI.MEŠ]
- 5.  $\hat{u}$  TÚG ku-lu-l[u šá <sup>d</sup>A-a]
- 6. 55 [x] [....]

Edge Rev.

7. *ku-us-sa-sa-*[....]

- 8. TÚG.GÚ.UD.DU.MEŠ
- 9. <sup>d</sup>DUMU-*rat* <sup>r</sup>É<sup>†</sup>-[*babbar-ra*
- 10. 1/3 GÍN *ti-[mu ....]*
- 11. 「TÚG¹.BAR.SI 「x¹
- 12. [*šá*] <sup>d</sup>*Gu-l*[*a*]
- 13. [x] *ma-na* [....]
- 14.  $\begin{bmatrix} t^{\text{tíg}} \end{bmatrix} e ri \ ^{\text{t}} \begin{bmatrix} u^{\text{g}} m e t u \end{bmatrix}$ 15.  $\begin{bmatrix} t^{\text{tíg}} k u \end{bmatrix} l u l u \ \check{s} [\acute{a}^? \dots]$

It seems that the document belongs to the category of texts which were the basis for periodic settlements as presented in BM 76590+.

L. 3-4, cf. above BM 76590+. rev. col. II 18'-20'.

[x] mina(s) 10 [shekels, the weight of *naḥlaptu-cloak* [for GN]

1 mina 10 sh[ekels, the weight of the < lubār> erru, < lubār> mēṭu] and < lubār>  $[ku]l\bar{u}l[u$ -headbands for Aya]

55 shekels [....]

robes [....]

naḥlaptu-cloak [....] of the Daughters of the E[babbar]

20 shekels of *tī[mu*-yarn ....], *paršīgu*-headdress [... for] Gula [x] mina [....] the *erru*-headband, the [....], the *kulūlu*-headband for [....].

## IV. The dullu peşû and tabarru texts

**165. BM 61580** (82-9-18, 1552)

PLATE 37

 $6.3 \times 4.4$  cm

#### 6.2.Cam 5

- 1. [dul]-lu BABBAR  $^{\acute{u}}$  ù SÍG.ḤÉ.M[E.D]A 2. šá  $^{d}A$ -nu-ni-tu<sub>4</sub> šá UD.KIB.NUN  $^{ki}$
- 3. <sup>d</sup>A-nu-ni-tu<sub>4</sub> šá lu-bu-uš-tu<sub>4</sub>
- 4.  $\check{s}\check{a}$  ITI.GU<sub>4</sub> MU.5.KAM  $<\check{s}\check{a}>$  <sup>m</sup>ŠEŠ.MEŠ-MU-[<sup>d</sup>AMAR.UTU]
- 5. *id-din-nu* ITI.GU<sub>4</sub> U<sub>4</sub>.<sup>1</sup>6<sup>1</sup>.K[AM MU.5.KAM]
- 6. <sup>m</sup>Kam-bu-zi-ja LUGAL [TIN.TIR<sup>ki</sup> LUGAL KUR.KUR]

\_\_\_\_\_

- 7. [16] *ma-na* KI.LAL <sup>túg</sup>ṣib-[tu<sub>4</sub> ....]
- 8. [1 ma-na K]I.LAL 10 TÚG. [NÍG.ÍB.LÁ.MEŠ]
- 9. [2/3 ma-na K]I.LAL 2 TÚG.Ú[R.MEŠ]

Rest lost

1'. [x x x (x)]-*tu*<sub>4</sub> *šá* SÍG.HÉ.ME.D[A] Rev.

- 2'. 5/6 ma-na KI.LAL gú-hal-su
- 3'. 10 GÍN KI.LAL TÚG.NÍG.ÍB.LÁ [SÍG.HÉ].ME.DA
- 4'. 10 GÍN SÍG.HÉ.ME.DA [KI.LAL ti-mu šá] TÚG.HI.A [qab-lu]
- 5'. ù TÚG. [x ] 10 TÚG. NÍG. ÍB. LÁ x ]
- 6'. [2/3] *ma-na* KI.[LAL 2 T]ÚG.BAR.SI SÍG.ḤÉ.ME.[DA]

Rev. l. 4', compare below BM 61762 (= 167): 13.

White and r[ed wo]rk for Anunītu-ša-Sippar-Anunītu for the *lubuštu* ceremony of the month Ayaru of the 5<sup>th</sup> year which Ahhē-iddin-Marduk has delivered. Month of Ayaru, 6<sup>th</sup> d[ay, 5<sup>th</sup> year] of Cambyses, king of [Babylon, king of Lands].

[16] minas, the weight of the sib[tu]-garment

[1 mina, the welight of 10 sas[hes]

[40 shekels, the wei]ght of  $2 s\bar{u}[nu]$ -belts

Rest lost.

[....] of red colour

- 50 shekels, the weight of the scarf
- 10 shekels, the weight of <1> red sash
- 10 shekels of red wool, [the weight]of *timu*-yarn for] the *lubār qablu* and [..., 10
- [40] shekels, the wei[ght of 2] red paršīgu-headdress.

#### **166. BM 83904** (83-1-21, 1067)

PLATE 37

 $4.0 \times 4.4 \text{ cm}$ 

#### 12.[x].Ach 5

- 1. [dul-lu SÍG.ḤÉ.ME.DA ù BABBA]R<sup>ú</sup> šá lu-bu-uš-tu<sub>4</sub>
- 2. [šá ITI.x šá UGU  $^{\rm d}A$ -nu-ni-tu<sub>4</sub> šá UD.KIB.NUN<sup>ki</sup>] šá  $^{\rm d}A$ -nu-ni-tu<sub>4</sub> 3. [šá  $^{\rm m}$ ŠEŠ.MEŠ-M]U- $^{\rm d}$ AMAR.UTU A  $^{\rm m}$ SU- $^{\rm d}$ AMAR.UTU
- 4.  $[(x \times x^?) id$ -din-nu ITI.x]  $[U_4]$ 1.12.KAM MU.5.KAM
- [KN LUGAL TIN.TIR<sup>k]i</sup> LUGAL KUR.KUR

\_\_\_\_\_

- 6. [16 ma-na KI.LAL TÚG.MÁŠ] šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 7. [1 ma-na KI.LAL 10] 'TÚG'.NÍG.ÍB.LÁ.[MEŠ]
- 8. [10 GÍN KI.LAL TÚ]G.NÍG.ÍB.LÁ SÍG.「HÉ」.[ME.DA]

Rev. uninscribed

Cf. lines 1-5 with BM 61762 (= 167): 1-5 and BM 61580 (= 165): 1-5. The name of Ahhēiddin-Marduk suggests that the text was written in the fifth year of Cyrus or Cambyses, but not in the fifth year of Darius because in this year the prebend was in the hands of his son, Uballissu-Gula (cf. Bongenaar, Ebabbar, p. 243 and pp. 259-60).

L. 8. Compare below BM 61762 (= 167): 12 and 61938 (= 168): 12.

[Red and whi]te [work] for the lubuštu ceremony [for the month x on account of Anunītu-ša-Sippar]-Anunītu, [which Aḥhē-id]din-Marduk, son of Erība-Marduk [.... has delivered. Month x], 12<sup>th</sup> day, 5<sup>th</sup> year [of KN, king of Babylo]n, king of Lands.

[16 minas, the weight of the *sibtu*-garment] for Anunītu

[1 mina, the weight of 10] sashes

[10 shekels, the weight of] (one) red sash.

#### **167. BM 61762** (82-9-18, 1702)

PLATE 38

 $6.8 \times 5.2$  cm

#### 7.2.Dar 2

- 1. dul-lu BABBAR<sup>ú</sup> ù dul-lu SÍG.Ḥ[É.ME.DA]
- 2. *šá lu-bu-uš-tu*<sub>4</sub> *šá* ITI.GU<sub>4</sub> *šá* UG[U <sup>d</sup>A-nu-ni-tu<sub>4</sub>]
  3. *šá* UD.KIB.NUN<sup>ki</sup> <sup>d</sup>A-nu-ni-tu<sub>4</sub> *šá* <sup>m</sup>Ú-bal-[liṭ-su-<sup>d</sup>Gu-la]
  4. A-šú *šá* <sup>m</sup>ŠEŠ.MEŠ-MU-<sup>d</sup>AMAR.UTU *id-din-nu*
- 5. ITI.GU<sub>4</sub> U<sub>4</sub>.7.KAM MU.2.KAM <sup>m</sup>Da-ri-mu-šú LUGAL E<sup>ki</sup> LUGAL KUR.KUR

\_\_\_\_\_\_

6. 16 ma-na KI.LAL <sup>túg</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>

7. 2/3<sup>!</sup> ma-na KI.LAL 「TÚG¹.ÚR.MEŠ

8. <sup>5</sup>/6<sup>1</sup> ma-na KI.LAL gú-hal-<sup>5</sup>su BABBAR<sup>ú</sup>

- 9. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ
- Rev. 10. 5/6 ma-na SÍG.HÉ.ME.DA KI.LAL 2 TÚG.[x x.MEŠ]
  - 11. 5/6 ma-na SÍG.ḤÉ.ME.DA KI.LAL 1<sup>et</sup> gú-[ḥal-ṣu<sup>?</sup>]
  - 12. 10 GÍN SÍG.HÉ.ME.DA KI.LAL TÚG.NÍG.Í[B.LÁ]
  - 13. 5 GÍN SÍG.HÉ.ME.DA KI.LAL ti-mu šá TÚG.HI.A gab-lu

Free space for one line

- 14. ina lìb-bi 1 ma-na dul-lu BABBAR<sup>ú</sup> LAL-[ti]
- 15. ina IGI <sup>m</sup>Ú-bal-liţ-su-<sup>d</sup>[Gu-la]
- L. 7. The numeral at the beginning of line is 5/6, which I have emended to 2/3 because according to CT 44, 73 (= 67): 12, the weight of 1  $s\bar{u}nu$  of Anunītu was 1/3 mina, just like the  $s\bar{u}nu$  of all the other gods and goddesses.
- L. 8. The badly preserved numeral seems to be  $\lceil 2/3 \rceil$ , however, because the *guḥaṣṣu* mentioned in l. 11, made of red wool, weighed 5/6 mana, I also decided to read  $\lceil 5/6 \rceil$  here. Another idea is that the scribe wrote 5/6 in line 7 by mistake (instead of 2/3) and 2/3 in l. 8 (instead of 5/6).
- L. 10. The filling of the gap in this line is uncertain, it maybe TÚG.[ÚR.MEŠ] or TÚG. [BAR.SI.MEŠ].
- L. 13. Concerning the *lubār qablu* of Anunītu, cf. also BM 74479 (= 441): 11.
- Ll. 14–15. Because as is stated here that 1 mina of white wool was left at the disposal of Uballissu-Gula "the missing" must have meant the amount that was not used.

White work and re[d] work for the *lubuštu* ceremony for the month of Ayaru, on acco[unt of Anunītu]-ša-Sippar-Anunītu which Ubal[lissu-Gula], son of Aḫḫē-iddin-Marduk has delivered.

Month of Ayaru, 7<sup>th</sup> day, 2<sup>nd</sup> year of Darius, king of Babylon, king of Lands.

16 minas, the weight of the *şibtu*-garment for Anunītu

To minus, the weight of the plotte guillent for rindinta

40! shekels, the weight of 2] *sūnu*-belts

50' shekels, the weight of the white scarf

1 mina, the weight of 10 sashes

50 shekels of red wool, the weight of 2 [paršīgu]-headdresses

- 50 shekers of fed woor, the weight of 2 [parsign]
- 50 shekels of red wool, the weight of 1 sc[arf] 10 shekels of red wool, the weight of (1) sash
- 5 shekels of red wool, the weight of varn for the *lubār qablu*-belt

in addition to 1 mina of white fabric, which is missing, at disposal of Uballissu-Gula.

168. BM 61938 (82-9-18, 1907)

PLATE 39

 $6.8 \times 5.3$  cm

[x].4.<KN>[x]

- 1. mi-iḥ-ṣu šá-ḥu-ú šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 2. <sup>m</sup>Ú-bal-<sup>r</sup>lit-su-<sup>d</sup>Gu-la it-ta<sup>-</sup>lin
- 3. ITI.ŠU [U<sub>4</sub>.x.KAM] 「MU.x.KAM「

```
4. 16 [ma-na KI.LAL túgṣib-tu4 šá d] [A]-nu-ni-tu4 1/3 [GÍN] LAL
```

5. [2/3] [ma-na KI.LAL] 2 < TÚG>. ÚR.MEŠ

6. [1 ma-na KI.LAL 10 TÚG.NÍG].Í[B.LÁ].<MEŠ>

7. [2/3 ma-na KI.LAL gú-h]al-şu BABBAR<sup>ú</sup>

8. [....]

9. [.... x] GÍN *e-te-qu* Edge

10. [x x x] <sup>r</sup>x x x <sup>1</sup> MURUB<sub>4</sub> Rev.

11. [x G]ÍN SÍG.HÉ.ME.DA KI.LAL TÚG.BAR.SI

2 GÍN e-te-qu 11a.

12. 10 GÍN KI.LAL {KI.LAL}TÚG.NÍG.ÍB.LÁ

1 GÍN e-te-qu

13. ½ GÚ.UN 1 ma-na KI.LAL GADA gi-da-<lu>-ú

14.  $\check{s}\acute{a}^{\rm d}Gu\text{-}la\ \{a\}\ ({\rm erased})$ 

L. 3. Note that the king's name was not written by the scribe.

Ll. 4–7. Cf. BM 61762 (= 167): 6-9; CT 44, 73 (= 67): 10–12.

L. 9. The last two signs are written on the right edge.

L. 12. Note that the weight of the *huṣannu* for Anunītu is higher than the typical 7 shekels. It is not excluded that, just like Ištar in Uruk, also Anunītu received additionally one huṣannu which was made of red wool and weighed 10 shekels.

L. 13. gi-da-u, most probably gi-da-< lu>-<math>u. It is the first proof that Uballissu-Gula owned also the weaver's prebend of this goddess. Concerning the translation, see Beaulieu, The Pantheon in Uruk, p. 381.

Woven šahû fabrics for Anunītu, which Uballissu-Marduk has [deli]vered. Month of Du'ūzu, [nth day, nth year].

16 [minas, the weight of the *ṣibtu* for Anunītu; 20 shekels are missing.

40 s[hekels, the weight of] 2 sūnu-belts

[1 mina, the weight of 10 sas]he[s],

\_\_\_\_\_

[40 shekels, the weight of white sc]arf

[...., x] shekels is missing;

[....] *qablu*;

[x] shekels of red wool, the weight of the *paršīgu*-headdress; 2 shekels are missing;

10 shekels <of red wool>, the weight of (one) sash; 1 shekel is missing;

31 minas the weight of the gidlu<sup>!</sup>-door curtain for Gula.

#### **169. BM 73723** (82-9-18, 13734)

 $6.6 \times 4.5$  cm

1. [....]  $[x \times x]$ 

2. [....] blank

- 3. [.... KI.LAL TÚG.ḤI.A] 「 $\grave{u}$ 1  $\ifmmode 1 \ifmmode 1$
- 5. [.... KI].LAL 4<sup>!</sup> (T:2) TÚG.ÚR.MEŠ 5 <GÍN> e-<te>-qu

```
6. [.... KI.L]AL 1^{en} túg gú-hal-ṣu BABBAR ^{\acute{u}}
                                                                     BABBAR^{\acute{u}}
               7. [....] \lceil su \rceil
               8. [x ma]-na KI.LAL 1<sup>en</sup> gú-ḥal-ṣu 「SÍG.Ḥɹ.[ME.DA]
               9. [x(x)]
Edge
                                                                             SÍG.[....]
                                                                      šá <sup>túg</sup>par-[ši-gu]
              10.
                                   5 GÍN e-<te>-qu
L.h.e.
             11.
e-< te>-qu in l. 5 is written on the right edge.
L. 10. Instead of ^{\text{túg}}par-[\check{s}i-gu] one can read TÚG.UD.[A].
[...., the weight of the lubāru-garment] and 1 șibtu-garment
[...., the weigh]t of 10 sashes [...., the wei]ght of 4' sūnu-belts; 5 <shekels> are missing
[...., the weig]ht of 1 white scarf
[....] white
[x mi]na, the weight of 1 red scarf
[....] of par[šīgu-headdress]<sup>?</sup>; 5 shekels are missing.
```

## V. The dullu tabarru and takiltu texts

**170. BM 62626** (82-9-18, 2595)

PLATE 40

$11.1 \times 7.8$ The table	8 cm twas joined earlier from 3 separate fragments.
	8.2.Nbk 39
	1. 「dul¬-lu SÍG.ḤÉ.ME.DA ù SÍG.ZA.GÌN. <kur>.RA [šá lu-bu-uš-tu4 ITI.GU4] 2. 「šá¹ <sup>m</sup>r<sup>d</sup>¹AG-EN-MU.MEŠ <sup>lú</sup>UŠ.BAR a-na 「ɹ-ba[bbar-ra] 「it¹-[ta-din] 3. 「ITI¹.GU4 U4.8.KAM MU.39.KAM <sup>d</sup>AG-NÍG.DU-「ÙRU¹ LUGAL 「TIN¹.TIR<sup>ki</sup></kur>
	4. 1 2/3 ma-na 5 GÍN SÍG.ḤÉ.ME.[DA] KI.LAL TÚG.'ÍB¹.LÁ šá <sup>d</sup> UTU
	5. 1 ma-na 1 GÍN SÍG.ZA.GÌN. <kur>.RA KI.LAL TÚG.ḤI.A me-e-ṭu TÚG.ḤI.A ku-lu-lu šá <sup>d</sup>UTU</kur>
	6. 8 ma-na 2/3 5 GÍN SÍG.ḤÉ.ME.DA KI.LAL TÚG.BAR.DUL <sub>5</sub> šá <sup>d</sup> A-a
	7. 5 ma-na 10 GÍN SÍG.ḤÉ.ME.DA KI.LAL TÚG.GÚ.UD.DU.A šá <sup>d</sup> A-a
	8. 54 GÍN KI.LAL 3 [TÚ]G.BAR.SI.MEŠ 1 <i>a-a-ri pa-ni šá</i> <sup>d</sup> <i>A-a</i>
	9. 「1 <sup>1</sup> 8 GÍN KI.LAL TÚG.「ÍB.LÁ <sup>1</sup> šá <sup>d</sup> Bu-ne-ne
	10. [x x x GÍN KI].LAL TÚG.ḤI.A me-e-ṭu 11. [TÚG.ḤI.A ku-lul-lu] šá <sup>d</sup> Bu-ne-ne
	12. [x x x x SÍ]G.ZA.GÌN. <kur>.RA KI.LAL 2 TÚG.BAR.SI.MEŠ 13. [1 túg ku-si-t]u4 šá dGAŠAN Sip-parki</kur>
Rev.	14. [x x x x x SÍG.ḤÉ.ME.D]A KI.LAL 「2¹-ta TÚG.BAR.「SI¹.MEŠ 15. [2-ta TÚG.GÚ.UD.DU.A].MEŠ šá <sup>d</sup> DUMU.MÍ.MEŠ 「ɹ-babbar-ra
	16. [x ma-na] <sup>1</sup> 6 <sup>1</sup> G[ÍN <sup>?</sup> SÍG.ḤÉ.M]E.DA KI.LAL

ku- $s[i^{?}]$ - $tu^{?!}$  (T: tu) TÚG.GÚ.U[D.DU]. [A] 17. [TÚG.HI.A] [ku]-lu-lu 1+[1 TÚG.BAR.S]I<sup>?</sup>.MEŠ šá <sup>d</sup>Gu-la šá É-ul-lu

18. <sup>[1/3]</sup> GÍN KI.LAL S[ÍG.ZA.GÍN.<KUR>.] RA šá TÚG.HI.A me-e- $^{\Gamma}tu$ 

19. TÚG.ḤI.A ku-lu-[lu šá] dIM

20. ½ ma-na 3 GÍN 「SÍG¹.HÉ.ME.DA 2 TÚG.BAR.S[I].MEŠ

21. 1 *a-a-ri pa-ni šá* <sup>d</sup>Š*a-la* 

Blank space for at least 2 lines

- 22. [PAP ½ GÚ.UN] 4 5/6 ma-na 5{[5]} GÍN dul-lu SÍG.HÉ.ME.DA
- 23. [ù SÍG.ZA.<GÌN>.KU]R.RA ITI.GU4 U4.8.KAM MU.39.KAM
- 24. [mdA]G-NÍG.DU-ÙRU LUGAL TIN.TIRki

Lines 4-5, cf. CT 4, 38a (= 178): 1-3 and VS 6, 26 (= 287): 9-11 (which enumerates also the patinnu).

Lines 6-8, cf. VS 6, 26: 12-15 (see the reading in our edition) and CT 4, 38a: 4-8.

L. 9, cf. CT 4, 38a: 12–13 and BM 51148 (= 177): 7' (1/2 ma-na 7 GÍN TÚG.ÍB.LÁ 「šá¹

Lines 10–11, cf. CT 4, 38a: 14–16. The content of lines 9–11 appears also in VS 6, 26: 18–19. Lines 14-15, cf. VS 6, 26: 20-21.

Lines 16–17. The only parallel I know is CT 44, 73 (= 67): 28 (½ GÍN KI.LAL e-ri ku-lu-lu u TÚG.BAR.SI.MEŠ SÍG.ḤÉ.ME.DA). The MEŠ before the name of Gula excludes the reading kusītu here and the only place for this garment is in the preceding line. Note a few tiny signs (maybe erased) between Rev. 19 and 20.

Lines 18–19, cf. VS 6, 26: 16–17 (only 15 shekels and the colour of wool is not mentioned); CT 44, 73 (= 67): 25 (the same quantity and weight).

Lines 20–21, cf. VS 6, 26: 22–23; BM 51148 (=177): 11'–13' and BM 51274: 15.

L. 22. Between 5 and GÍN the numeral 5 is still recognisable, but because earlier 5/6 of mina is written the numeral before GÍN must be treated as the rest of the erased numeral, repeated by mistake by the scribe and then erased.

Red and blue-purple work for [the lubuštu ceremony of the month Ayaru], which Nabû-bēl-šumāti, the weaver, has de[livered to the Ebab]bar temple. Month of Ayaru, 8<sup>th</sup> day, 39<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

1 mina 45 shekels of red wool, the weight of the nēbehu-belt for Šamaš

1 mina 1 shekel of blue-purple wool, the weight of the lubār mēţu (and) lubār *kulūlu*-headbands for Šamaš

8 minas 45 shekels of red wool, the weight of the kusītu-robe for Aya

\_\_\_\_\_

5 minas 10 shekels of blue-purple wool, the weight of 1 nahlaptu-cloak for Aya

\_\_\_\_\_

54 shekels, the weight of 3 paršīgu-headdresses (including) 1 (with) the front rosette for Aya

18 shekels, the weight of (one) nēbehu-band for Bunene

\_\_\_\_\_

[x minas x] shekels, the weight of the *lubār mētu* (and) [*lubār kulūlu*]-headbands for Bunene.

[....] of blue-purple wool, the weight of 2 paršīgu-headdresses (and) [1 ro]be for the Queen of Sippar.

-----

[x minas x shekels] of blue-purple wool, the weight of 2 paršīgu-headdresses and 2 [nahlaptu]-cloaks for the Daughters of the Ebabbar.

-----

[x minas] 6 shekels of red wool, the weight of the robe?!, the nahla[ptu]-cloak, the [ $lub\bar{a}r$ ]  $kul\bar{u}lu$ -headband,  $\lceil 2^{?} \rceil$  [ $par \tilde{s}\tilde{t}$ ] gu-headdresses? for Gula of the Eulla temple. -----

20 shekels of blu[e-purple] wool, the weight of the lubār mēṭu (and) the lubār *kulūlu*-headbands [for] Adad.

33 shekels of red wool, <the weight> of 2 paršīgu-headdresses (including) 1 with the front rosette for Šala

Total 3] 4 minas 55 shekels, the red [and blue-purp]le work Month of Ayaru, 8<sup>th</sup> day, 39<sup>th</sup> year of [Ne]buchadnezzar, king of Babylon.

## **171. BM 50031+BM 50209** (82-3-23, 1022+ 82-3-23, 1200)

PLATE 41

 $5.9 \times 5.2$  cm

[x.x].Kand 15

1.  $[x \times x \times (x)] \Gamma x^{1 \text{meš}} < \check{s} \acute{a} > \text{MU.15.KAM}$ 

- 2. [x GÚ.UN x ma]-na KI.LAL 4 TÚG.ḤI.A.「MEй
- 3. [x x (x x)] 4 TÚG.HI.A 4 TÚG.MÁŠ.MEŠ
- 4. [x x (x x) 4 TÚG].ÚR.MEŠ <sup>túg</sup>hu-sa-ni-e šá 6 (sic') 5. [dUTU u d]A-a dBu-ne-ne u r $^{d}$ 1GAŠAN Sip-par $^{ki}$
- 6. [x TÚG].BAR.SI šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> ina IGI <sup>md</sup> UTU-MU- $D\dot{U}^{\dagger}u^{m}BA^{\Gamma\check{\delta}\acute{a}}-a^{\dagger}$
- 7.  $\lceil 11 \text{ } ma^{1}\text{-}na \text{ }^{\text{túg}}\text{ku-si-ti } \text{šá} \text{ }^{\text{d}}\text{A-a}$
- 8. <sup>[1]</sup> ni-bi-ḥu šá iz-ḥi šá <sup>d</sup>UTU
- 9. [x x-t]i šá an(sic¹)-za-hu-ri-e-tú
- 10. [x x x] ta-kil-ti ma-la i-šaq-qu-ú
- 11.  $[x \times h]a$ -a- $tu \times SIG.HI.A u \times SUM <math>[x \times x]$

12. [x x x ta-k]il-ti ul i-šá-an-ni Edge

- 13. [x ma-na] KI.LAL <sup>túg</sup>ku-si-ti Rev.
  - 14. [x *ma-n*]*a* KI.LAL <sup>túg</sup>*ni-bi-hu*
  - 15. [x x x].HI.A ha-a-tu šá [túg]ta-hap-šú
  - 16. [x x]<sup>[</sup>A<sup>1</sup> 1 GÚ.UN ta-bar-ri KI.LAL-šú-nu
  - 17.  $[ina\ MU.1]^{\lceil 5^2 \rceil}$ .KAM  $^{md}$   $\Gamma$ UTU-MU $^{\rceil}$ -DÙ  $u^{m}$ BA $^{\check{s}\acute{a}}$ - $a\ ab$ -lu
  - 18. [x] ma-na ni-bi-<sup>r</sup>hu<sup>1</sup> ha-a-tu
  - 19. [x x x] MU.15.KAM ina IGI <sup>m</sup>Du-um-mu-qu
  - 20. [x x x] <sup>r</sup>x¹ šá ITI.[x] <sup>r</sup>MU¹.[15².KAM ina IGI] <sup>m</sup>Du-um-mu-qu
  - 21. [x x x M]U.1<sup>r</sup>5<sup>1</sup>.KAM Kan-da-la-nu
  - 22. [LUGAL] TIN.TIR<sup>ki</sup>
  - 23.  $[x \times x \times x^{sig}t]a$ -bar-ri 5 ma-na [KI].LAL- $[\check{s}\check{u}]$ -[nu]
  - 24. [x x x x]-<sup>r</sup>bi¹ ina É 'DINGIR¹ [....]

#### L. 1. We expect here the general term for garments.

- Ll. 2–3. It is important to note that 4 lubārus and 4 sibtus are mentioned here. The comparison with BM 91002: 3, where 4 sibtus for Šamaš are also mentions, suggests that the norms established in the time of Nabû-apal-iddina were known and kept at least in respect to this garment in the time of Kandalanu. BM 91002, which concern the miḥṣu tenû list of garments, does not mention the lubāru garment. Still, it is interesting to note that BM 50209+ (= 171) mentions 4 lubāru, while according to the texts from time of the rule of Chaldean kings Šamaš received two, or only one sibtu. However, the text concerns "work with tabarru and takiltu in the 15<sup>th</sup> year" of Kandalanu and it is not clearly said that the lubārus and sibtus were destined for a particular ceremony, although it is not excluded. It is known that the summary texts included the data extracted from the individual text, compare e.g. BM 76590+ (= 163) from the time of Nabonidus.
- L. 4. The numeral 6 in tighu-sa-ni-e šá 6 is probably written mistakenly after instead before the word. Note, however, that Šamaš and 3 goddesses received 36 (or 37) husannus during each lubuštu ceremony.
- L. 6. Iqīša is identical with (Bēl)-Iqīša (Bongenaar, Ebabbar, p. 322), but thanks to the new text we know that his activity began about 10 years earlier. The same concerns Dummuqu (ll. 19–20), which was known from the texts from 5<sup>th</sup> year of Nabopolassar (see Bongenaar, Ebabbar, p. 326).
- L. 8. The reading of the line corrects that in Zawadzki, Garments of the Gods, Vol. I, p. 120, n. 364. cf. also comments to No. 175.
- L. 10 and l. 12 the word *šaqû* and *šanû* appear in such content for the first time here.
- L. 17. maybe "dry" in contrast to "soaked" in 1. 10<sup>2</sup>

### [....]-garments for the 15<sup>th</sup> year.

[x talent(s) x mi]nas, the weight of 4 lubāru-garments

- [x talent, the weight of] 4 *lubāru*-garments of 4 *şibtu*-garments [x x 4] *sūnu*-belts, 6<sup>?!</sup> sashes [for Šamaš], Aya, Bunene and the Queen of Sippar.
- [x] paršīgu-headband(s) for the Queen of Sippar at disposal of Šamaš- šum-ibni and Iqīša.
- 11 minas (the weight) of (one) robe for Aya [and?] 1 tied nēbehu-belt of Šamaš [....] of inzahurēti (wool?) ... blue-purple wool as much as he has soaked [....] the outstanding amount of wool and [....] blue-purple wool he does not need (to soak)

[x mina(s)], the weight of robe

Edge

[x min]a(s)], the weight of the *nēbeḥu*-belt [....woo]l<sup>?</sup>, the outstanding amount for the *tahapšu*-blanket [....] 1 talent of red wool is their weight, [which in the 1]5<sup>th</sup> year have been taken by Šamaš-šum-ibni and Iqīša [....] [x] mina(s) (for) the  $n\bar{e}behu$ -belts<sup>!</sup>, the outstanding amount [....] of the  $15^{th}$  year at disposal of Dummuqu [...] of month the 15<sup>th</sup> year at disposal of Dummuqu [...] the 15<sup>th</sup> year of Kandalanu, [king] of Babylon. [.... r]ed wool 5 mina is their weight, [....] in the temple [....]. **172.** Cyr **191** = BM 62403; cf. NUVI 3, No. 117; Giovinazzo 1981, No. 9. Collated 6.2.Cyr 5 1. dul-lu SÍG.ZA.GÌN.KUR.RA TÚG.SÍG.[ḤÉ.MÉ.DA] 2. 「šá¹\* lu-bu-uš-tu šá ITI.GU<sub>4</sub> 3. <sup>m</sup>Ba-ku-ú-a id-din-nu ITI.GU<sub>4</sub> U<sub>4</sub>.8.KAM 4. MU.5.KAM <sup>m</sup>*Ku-raš* LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR -----5. ½ ma-na KI.<LAL> TÚG.HI.A me-ţu TÚG.HI.A ku-lu-lu 6. šá <sup>d</sup>UTU 7. 9 1/3\* *ma-na* 5 GÍN KI.LAL 8. ku-si-tu<sub>4</sub>  $\check{s}\acute{a}$   ${}^{d}A$ -a9. 1 ma-na KI.LAL TÚG.HI.A ku-lu-lu Rev. 10. 2 TÚG.BAR.SI.MEŠ šá  ${}^{\rm d}$ GAŠAN UD.KIB.NUN $^{\rm ki}$ 11. 1/3 ma-na KI.LAL TÚG.HI.A me-tu 12. TÚG.HI.A *ku-lu-lu šá* <sup>d</sup>IM \_\_\_\_\_ 13. ½ ma-na KI.LAL TÚG.HI.A me-tu 14. TÚG.ḤI.A ku-lu-lu šá <sup>d</sup>A-nu-<sup>r</sup>ni-tu<sub>4</sub><sup>1</sup>

L. 8. In the Strassmaier's copy there is the numeral 1 before *kusītu*, but nothing is seen there. L. 14. Note that the typical weight of the *huṣannu* of Anunītu was 7 shekels.

Blue-purple and r[ed] work for the *lubuštu* ceremony of the month Ayaru, which Bakûa has delivered. Month of Ayaru, 8<sup>th</sup> day, 5<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

-----

15. 10 GÍN SÍG.ḤÉ.ME.DA K[I.LAL] 16. TÚG.NÍG.ÍB.<LÁ> šá du[l²-lu² ....] 17. 3 GÍN KI.LAL {KI.LAL} šá [....]

18.  $\check{s}\acute{a}^{\rm d}A$ -nu-ni-t[u<sub>4</sub>]

30 shekels, the weight of the  $lub\bar{a}r$   $m\bar{e}tu$  (and) the  $lub\bar{a}r$   $kul\bar{u}lu$ -headbands for Šamaš

\_\_\_\_\_

9 minas 25 shekels, the weight of the robe for Aya

------

1 mina, the weight of the  $lub\bar{a}r$   $kul\bar{u}lu$ -headband (and) 2  $par\bar{s}\bar{t}gu$ -headdresses for the Queen of Sippar

20 shekels, the weight of the  $lub\bar{a}r\ m\bar{e}tu$  (and)  $lub\bar{a}r\ kul\bar{u}lu$  -headbands for Adad

30 shekels, the weight of the *lubār mēṭu* (and) *lubār kulūlu*-headbands for Anunītu 10 shekels of red wool, the wei[ght] of the sash for wo[rk? ....]

3 shekels, the weight of the [...] of Anunītu.

### **173. BM 61690** (82-9-18, 1661)

 $6.3 \times 5.5$  cm

#### 7.2.Nb[n] 11

- 1. dul-lu ta-bar-ri ù ta-[kil-tu<sub>4</sub>]
- 2.  $\check{s}\check{a}^{\mathrm{md}}\mathrm{U}+\mathrm{GUR}-\mathrm{MU}^{\mathrm{l}\check{u}_{\lceil}}e-pi\check{s}^{\dagger}-\check{s}\check{a}^{-\lceil}nu^{\rceil}$  [SUM<sup>na</sup>]
- 3. ITI.GU<sub>4</sub> U<sub>4</sub>.7.KAM [MU].11KAM  $^{md}$ AG-[I LUGAL  $E^{ki}$ ]

\_\_\_\_\_

- 4. 5 ma-na 1/3 GÍN 「ta-bar¹-ri KL.LAL
- 5. na-ḥi-lap-[tu<sub>4</sub>] šá <sup>d</sup>A-a
- 6. 1 ma-na 5 GÍN KI.LAL 2 [x x]
- 7. 2-*ta na-hal-lap-tu*<sub>4</sub> *šá* [....]
- 8. *ina* ŠU<sup>ii md</sup>[....]
- 9. 9 2/3 ma-na KI.LAL ku-[si-tu<sub>4</sub>]
- 10. ina lìb-bi 2 5/6 ma-[na a-na ú-za-ri šá]

Rev. 11. *a-di-la-nu* [x x] [....]

- 12. 「šá<sup>?</sup>¹ TÚG.[x] LAL 「x¹ [....]
- 13. [x] hal [x]  $i^{?}$  [x] [....]
- 14. [x] <sup>[6]</sup> [x x] *ni-bi-hu*
- 15. [x] *ma-na* 3 GÍN [KI].LAL <sup>r</sup>x<sup>1</sup> [....]
- 16. [x x] TÚG ku-lu-[lu ....]
- 17. [x x x x] *lu* [....]
- 18. [x GÍN ta-bar]-ri KI.LAL
- 19. [....] <sup>r</sup>x x<sup>1</sup>
- 20. [.... <sup>d</sup>]IM
- 21.  $[x] \lceil x \rceil \lceil ku \rceil lu lu x$
- L. e. 22. [.... TÚG] [ku]-lu-[lu<sup>?</sup>]
  - 23.  $[x \ x] [x \ x] d\check{S}[a]-la$
  - 24. 5 GÍN ZA.GÌN.KUR.RA KI.LAL TÚG.HI.[A me-ţu]
  - 25. TÚG.ḤI.A ku-lu-lu

The tablet is blackened by smoke, badly preserved and very difficult to read.

Red and blu[e-purple] work, which Nergal-iddin, the performer [has delivered]. Month of Ayaru, 7<sup>th</sup> day, 11<sup>th</sup> [year] of Nabo[nidus, king of Babylon].

5 minas 20 shekels of red wool, the weight of the *naḥlaptu*-cloak for Aya

1 mina 5 shekels, the weight of 2 [...] (and) 2 nahlaptu-cloaks of [...] from [PN]

9 minas 40 shekels, the weight of the [ro]be with addition of 2 minas 50 shekels f[or the *uzāru* of the tassel<sup>?</sup> [....]

(Text in lines 12–23 is preserved to badly to be translated).

[.... for] Šala

5 shekels of blue-purple wool, the weight of the lubār [mēṭu] (and) lubār kulūluheadbands.

#### 174. BM 73185 (82-9-18, 13196)

PLATE 42

 $4.6 \times 5.2$  cm

#### 7.2.Nbn 7

- 1. [dul-lu ta-bar]-ri ù ta-k[il-tu4 ša ina lu-bu-uš-tu4 ITI.GU4]
- 2.  $[^{m}Ba-ku-\acute{u}]^{-1}a^{1}u^{md}AG^{-1}up^{1}-ni-j[a\ a-na\ \acute{E}-babbar-ra]$
- 3. [SUM<sup>na</sup> ITI].GU<sub>4</sub> U<sub>4</sub>.7.KAM MU.7.KAM <sup>md</sup>AG-<sup>[I]</sup>
- \_\_\_\_\_ 4. [x ma-n]a KI.LAL  $ku-si-tu_4$  šá  ${}^{d}$ [A]-[a]
- \_\_\_\_\_

5. [x ma-na x] GÍN KI.LAL na-ḥal-lap-tu<sub>4</sub> <sup>r</sup>šá <sup>d</sup>A<sup>1</sup>-[a]

\_\_\_\_\_

6. [x ma-na (x GÍN) K]I.LAL SÍG.ZA.GÌN.KUR.RA šá  $^{\rm d}$ UTU

7. [x x x KI.LAL]  $1^{en}$  par-ši-gu  $1^{en}$  a-a-r[i pa-ni] 8. [....]  $\lceil \check{s} \acute{a}^{d_1} GA \check{S} AN \ Sip-par^{k_1}$ 

9. [.... TÚG.ḤI]. [A] me-ṭi šá [d] [....]

1'. [....] [x] a-a-r[ $i^{?!}$  ....] Rev.

2'. [.... KI].LAL 2-ta [....]

3'. [....] <sup>r</sup>x<sup>1</sup>.MEŠ

4'. [1 p]ar-si-gu lu-ba-ri ku-lu-lu sa f x x [....]

\_\_\_\_\_

5'. [x ma-na x] GÍN KI.LAL 2 ni-bi-ḥu šá <sup>d</sup>UTU

6'.  $[u^{?} {}^{d}Bu-n]e-ne$ 

7'. [.... KI.LA]L par-ši-gu šá <sup>d</sup>GAŠAN Sip-par<sup>k[i]</sup>

8'. [.... KI.LA]L 2-ta pa-tin-na-tu4 [....]

9'. [....] [x]-GI it-t[a-din ....]

10'. [.... par]-ši-gu<sup>meš</sup>

11'. [....] gú-ḥal-ṣu š[á ....]

For the reading of line 1-3, cf. BM 62626 (cf. above) and Cyr 191 (= 172). Lines 4–5. It is the only text where the garments for Aya precede the garments for Šamaš. Rev. 4'. Only a tiny upper part of the name is preserved. Note, that garments for the Queen of Sippar are mentioned twice (l. 8 and rev. 7). L. 6. The name of the garment is missing.

Rev. 8'. The plural of patinnu is mentioned here for the first time.

[Re]d and blue-pu[rple work for the *lubuštu* ceremony of the month Ayaru], which [Bakû]a and Nabû-upnīya [have delivered to the Ebabbar temple. Month] of

Ayaru, 7 <sup>th</sup> day, 7 <sup>th</sup> year of Nabonidus.
[x mina]s, the weight of the robe for Aya
[x mina(s) x] shekels, the weight of the <i>naḥlaptu</i> -cloak for Ay[a]
[x mina(s) x shekels, the wei]ght of blue-purple <> of Šamaš
[x mina, the weight] of 1 paršīgu-headdress (and one) with the front rosette [] for the Queen of Sippar; [] lubār mēṭu-headband for the [] [] front rosette? [] [] the weight of 2 [] [1] paršīgu-headdress, (and) the lubār kulūlu-headband for []
[x mina(s) x] shekels, the weight of 2 $n\bar{e}behu$ -belts for Šamaš; [ for Bun]ene []
[x mina, the weig]ht of the <i>paršīgu</i> -headdress for the Queen of Sippar; [x mina, the weight of x] <i>patinnu</i> -belts []-ušallim has deliv[ered]. [] x <i>paršī]gu</i> - headdresses [] scarf []

# VI. BM 91002 (BBST 36): Nabû-apal-iddina's regulation concerning garments for Šamaš: No. 175

- 1. <sup>d</sup>UTU EN GAL-*ú a-šib É-babbar-ra* EN UD.KIB.NUN<sup>ki</sup>
- 2. TÚG.NÍG.MU4 $^{\rm d}$ UTU EN GAL- $\acute{u}$  EN UD.KIB.NUN $^{\rm ki}$
- 3. ITI.BÁR U<sub>4</sub>.7.KÁM 2 GADA sal-hu 4 <sup>túg</sup>sib-ti
- 4. ki-tin-nu 40 ma-na KI.LAL-šú-nu 1<sup>en</sup> GADA hu-la-nu
- 5. 1<sup>en</sup> me-zi-hu GADA 7 TÚG.NÍG.ÍB.LÁ.<MEŠ>
- 6. 1 ma-na 10 GÍN KI.LAL-<šú-nu> 1<sup>en</sup> TÚG.ÍB.LÁ iz-hi
- 8. 1  $^{en}$  TÚG.UD. A zi-qu<br/> 1 me-zi-hu GADA
- 9. 1<sup>en</sup> ku-lu-lu ZA.GÌN.<KUR>.RA ku-lu-lu šá
- 10. KÙ.GI *iz-ḥi ina* UGU-*šú* 1<sup>en</sup> TÚG.UD.A ZA.GÌN.<KUR>.RA
- 11. *iz-ḥi* KÙ.GI KÁ TÚG.UD.A ITI.GU<sub>4</sub> U<sub>4</sub>.10.KÁM *ki-ma* ITI.BÁR KI.MIN
- 12. ITI.KIN U<sub>4</sub>.3.KÁM 2 GADA sal-hu 3 túgsib-ti
- 13. 1<sup>en</sup> GADA *hu-la-nu* 1 *me-zi-hu* GADA
- 14. 6 TÚG.NÍG.ÍB.LÁ 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ 1<sup>en</sup> TÚG.UD.A
- 15. 1<sup>en</sup> mut-ta-tu<sub>4</sub> šá ta-bar-ri
- 16. ZA.GÌN.<KUR>.RA bu-ṣu ṭi-mi-tu4 ITI.DU<sub>6</sub> U4.7.KÁM KI MIN
- 17. ITI.APIN U<sub>4</sub>.15.KÁM ki-ma ITI.BÁR ITI.ŠE U<sub>4</sub>.15.KÁM
- 18. *ki-ma* ITI.KIN *gaba-ri a-su-ú-mi-it šá* <sup>d</sup>UTU EN UD.KIB.NUN<sup>ki</sup>
- 19. šá <sup>md</sup>AG-DUMU.UŠ-MU<sup>?</sup> LUGAL TIN.TIR<sup>ki</sup>

Cf. the new translation of the text by Woods 2004, 100f. where previous editions are quoted. Because Wood's article was not available to me when I finished the first volume of my *Garments of the Gods*, I will comment on it briefly here. The idea of reading *izhi* in 1. 6, 10 and 11 was also taken into consideration by me but I abandoned it because such a description of the *nēbeḥu* was not known from other texts. However, after I read Woods' article, I compared all my texts and recognized that such a description appears in fact in BM 50209+: 8 (「1¹ ni-bi-ḥu šá iz-ḥi), badly transliterated in *Garments of the Gods*, Vol. I, p. 120, n. 364 (「1¹ ni-bi-ḥu šá GIŠ.BAN). It is important to know that such a description appears only in this text dated to the 15<sup>th</sup> year of Kandalanu, and in BM 50963 (= 383), rev. 5' which might be dated to the time of Nabopolassar, but no later, which suggests that such a specific form of *nēbeḥu* was probably not in use later.

The reading KÅ as "itemization" would be justifiable if it had been used at the beginning of the counting, i. e. in l. 2. Concerning the question of the reading of the king's name, and the

interpretation of l. 18, I still maintain the opinion expressed in *Garments of the Gods*, Vol. I, p. 142, n. 447. Discussing the meaning of TÚG.MURUB<sub>4</sub>.ÍB.LÁ, the author did not consider my idea of identifying patinnu as its Akkadian equivalent.

L. 5. Concerning mēzehu, see now Tawil 2009, p. 203. As noted by Tawil the mēzehu could be worn over upper torso" and even "over the *şibtu*-garment".

Šamaš, the great lord who dwells in the Ebabbar, lord of Sippar.

Wardrobe of Šamaš, the great lord, lord of Sippar.

(For) the 7<sup>th</sup> Nisannu: 2 linen tunics, 4 *sibtu*-garments made of *cotton*? weighting 40 minas; 1 linen hullānu-cloak, 1 linen mēzehu-sash, 7 sashes weighting 1 mina 10 shekels; 1 tied nēbehu-belt, 1 red patinnu-belt, 1 lubāru-garment weighting 20 minas, 1 lubār ziqqu-garment, 1 linen mēzehu-sash, 1 blue-purple kulūlu-headband with golden (ornament) fastened on it; 1 blue-purple lubāru-garment with golden ornament in shape of the gate fastened to it.

(For) the 10<sup>th</sup> Ayaru: the same as for the month Nisannu.

(For) the 3<sup>rd</sup> Ulūlu: 2 linen tunics, 3 *şibtu*-garments, 1 linen *hullānu*-belt, 1 linen mēzehu-sash, 6 sashes, 1 patinnu-belt, 1 lubāru-garment, 1 red muttatu-headband, the blue-purple yarn of byssus.

(For) the 7<sup>th</sup> Tašrītu: the same.

(For) the 15<sup>th</sup> Araḥsamna: the same as for the month Nisannu (For) the 15<sup>th</sup> Addaru: the same as for the month Ulūlu.

The copy of the inscribed slab of Šamaš, lord of Sippar (from the time) of Nabûapal-idinna, king of Babylon.

## VII. The early mihşu tenû texts

#### **176. ZA 4 (1889) No. 4** = BM 72276 Collated

5.1.Nbp 7

1. 7 TÚG GADA

2. *šá* <sup>d</sup>UTU <sup>d</sup>A-a

4. ni-bi-hu pa-tin-nu

5. GADA gú-ḥaṣ-ṣa šá <sup>d</sup>UTU

6. pa-tin-ni gú-haṣ-ṣa

7. šá <sup>d</sup>Bu-ne-ne

8. 1 TÚG.BAR.DUL<sub>8</sub> 2 GÚ.UD.DU

SÍG.HÉ.ME.DA

10. šá <sup>d</sup>A-a

11. 2 TÚG GADA šá dul-<la>

12. ina IGI <sup>lú</sup>TÚG.BABBAR

Rev. 13. ITI.BÁR U<sub>4</sub>.5.KAM

14. MU.7.KAM

15. dAG-A-PAP

LUGAL

17. 2 *ḥu-ṣa-ni-e šá* <sup>d</sup>UTU

18. 1 *šá* <sup>d</sup>*A-a* 

19. PAP 3 <sup>túg</sup>ħu-ṣa-ni-e 20. šá <sup>md</sup>EN-BA<sup>šá</sup>-a 21. <sup>lú</sup>UŠ.BAR

Cf. the similar texts BM 82581 (= 180); CT 55, 811 (= 182); BM 68361 (= 277) and BM 50282

L. 1. The description of the garment is atypical, however, the identification with salhu, the garment mentioned in all mihṣu tenû lists on the first position seems possible (probably 2 pieces for Aya and Bunene, 3 for Šamaš).

L. 11. Two pieces of  $k\bar{\imath}tu$  ša dulla are also mentioned in BM 82581 (= 180): 8, however, the ašlāku is not mentioned there.

Ll. 17-18. Note also the small number of huṣannus; usually Šamaš received 6 or 7 and Aya 10 sashes.

7 linen garments for Šamaš, Aya and Bunene

(one) nēbehu-belt, (one) patinnu-belt, (one) linen scarf for Šamaš

(one) patinnu-belt, (one) linen scarf for Bunene

1 kusītu-robe, 2 red naḥlaptu-cloaks for Aya

2 knock-about clothes at disposal of the *ašlāku*Month of Nisannu, 5<sup>th</sup> day, 7<sup>th</sup> year of Nabopolassar, the king.
2 sashes for Šamaš, 1 for Aya, total 3 sashes from Bēl-iqīša, the weaver.

#### **177. BM 51148** (82-3-23, 2144)

PLATE 43

 $6.1 \times 3.3 \text{ cm}$ 

#### [x].2.Nbk 11

1'. [....] [x] [....]

2'. [1 m]a-[na] [x] [GÍN] KI.LAL 2-ta TÚG.BAR. DUL<sub>8</sub>¹. [MEŠ]

3'. [2]-ta GÚ.UD.DU.MEŠ šá <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-[ra]

\_\_\_\_\_

- 4'. 2 ma-na 10 GÍN KI.LAL TÚG.ÍB.LÁ šá <sup>d</sup>UTU
- 5'. 1/3 7 GÍN TÚG.SÍG.ZA.GÌN.<KUR>.RA TÚG.HI.A ku-lu-l[u]
- 6'. TÚG.HI.A me-tu šá <sup>d</sup>UTU

7'. ½ ma-na 2 GÍN TÚG.ÍB.LÁ 「šá<sup>?</sup>」 [dBu-ne-ne]

8'. [x] GÍN TÚG.ḤI.A ku-lu-lu TÚG.Ḥ[I.A [me-ṭu šá <sup>d</sup>Bu-ne-ne]

9'. [x] GÍN TÚG.HI.A *ku-lu-*[*lu* (x x x)] Edge

10'. [SÍG.ZA.<GÌN>.K]UR.RA šá dIM

11'. [x] ma-na TÚG.ḤI.A ku-lu-l[u (x x)]

12'. [2<sup>túg</sup>]par-si-gu<sup>meš</sup> šá <sup>d</sup>[Ša-la]

13'.  $\lceil ina \ lib-bi \rceil$   $1^{en} \ ša \ \lceil a \rceil - a-ri \ pa-[ni]$ 

14'. md AG-EN-「MU」[.MEŠ e-la]t ina É [DINGIR it-ta-din]

15'. ITI. 「GU4 U[4.x.KAM MU].11.KAM

16'. <sup>d</sup>[AG]-N[ÍG.DU-ÙRU LUGAL TIN.TI]R<sup>ki</sup>

Lines 2'-3', cf. VS 6, 26 (= 287): 20–21 weighing 1 ma-na  $^{\dagger}x^{\dagger}$  GÍN and CT 4, 38a (= 178): 9-11 where, however, according to the copy instead of 2 TÚG.BAR.SI there are 2 kusītus (TÚG.BAR.DUL<sub>8</sub>) weighing only 50 shekels.

Lines 7'-8', cf. CT 4, 38a: 12-16 and VS 6, 26: 18-19.

Lines 9'-10', cf. CT 4, 38a: 17-19, where the weight of the same items is 40 shekels and CT 4, 73: 25 where their weight is only 20 shekels.

Lines 11'-12', cf. CT 4, 38a: 20-22 weighing 24 shekels and VS 6, 26: 22-23 weighing 27 shekels.

Rev.

[1 mi]na [x] shekels, the weight of 2 robes (and) 2 nahlaptu-cloaks for the Daughters of the Ebabbar

2 minas 10 shekels, the weight of the *nēbeḥu*-belt for Šamaš

27 shekels of blue-purple wool (for) the *lubār kulūlu* (and) *lubār mēṭu*-headbands for Šamaš

32 shekels, <the weight of > the  $n\bar{e}behu$ -belt for [Bunene]

[x] shekels, <the weight of > the  $lub\bar{a}r \ kul\bar{u}lu$  (and)  $lub\bar{a}r \ [m\bar{e}tu]$ -headbands [for Bunene]

[x] shekels of [blue-purp]le wool, <the weight of> the lubār kulūlu-headband (x x) for Adad

[x] mina(s), <the weight of > the  $lub\bar{a}r \ kul\bar{u}[lu$ -headband (x x) 2]  $par s \bar{i} g u$ headdresses for [Šala], including one 1 with the fro[nt] rosette,

Nabû-bēl-šumā[ti has delivered] to the 'house of the god'.

Month Ayaru, [n<sup>th</sup> da]y, 11<sup>th</sup> [year] of Nebu[chadnezzar, king of Ba]bylon.

#### 178. CT 4, 38a (Bu 88-5-12, 608); cf. NUVI 3, No. 248 Collated

#### 9.2.Nbk 13

- 1. [1/2] GÍN KI.LAL TÚG.HI.A me-tu
- 2. TÚG.ḤI.A ku-lu-lu SÍG.ZA.GÌN.KUR.RA šá <sup>d</sup>UTU
- 3. 3 ma-na KI.LAL TÚG.ÍB.LÁ ina pa-<pa>-hi šá <sup>d</sup>UTU
- 4. 8 ma-na KI.LAL TÚG.BAR.DUL<sub>8</sub> SÍG.HÉ.ME.DA šá [dA-a]
- 5. 4 ma-na KI.LAL TÚG.GÚ.UD.DU KI.MIN <šá> dA-a
- 6. 2/3 ma-na KI.LAL TÚG.HI.A ku-lu-l[u]
- 7. 3  $^{\text{túg}}par$ - $\check{s}i$ -gu(T: sal) $^{\text{meš}}$  SÍG.ḤÉ.ME.DA 8.  $\check{s}\acute{a}^{\text{d}}A$ -a
- 9. 50 GÍN KI.LAL 2-ta TÚG.BAR.SI<sup>!</sup>.MEŠ
- 10. 2-ta TÚG.GÚ.UD.DU.MEŠ SÍG.HÉ.ME.DA
- 11. šá <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra*{meš}
- 12. ½ ma-na KI.LAL TÚG.ÍB.LÁ.{MEŠ?}
- 13. šá <sup>d</sup>Bu-ne-ne
- 14. 6\* GÍN KI<sup>¹</sup>LAL TÚG.HI.A me-tu
- 15. TÚG.HI.A ku-lu-lu SÍG.ZA.GÌN.<KUR>.RA
- 16. šá <sup>d</sup>Bu-ne-ne
- 17. 2/3 GÍN <KI.LAL> TÚG.HI.A ku-lu-lu
- 18. TÚG.HI.A me-ţu SÍG.ZA.GÌN.<KUR>.RA

#### 19. *šá* <sup>d</sup>IM Edge

20. 1/3 4 [GÍN] <KI.LAL> TÚG.ḤI.A ku-lu-luRev.

- 21. <sup>túg</sup>par-ši-gu<sup>meš</sup> SÍG.ḤÉ.ME.DA
- 22. šá <sup>d</sup>Ša-la
- 23. PAP 18 ma-na 2/3\* 3 GÍN
- 24. SÍG.HÉ.ME.DA ù SÍG.ZA.GÌN.<KUR>.RA
- 25. md AG-EN-<MU>.MEŠ lúUŠ.BAR
- 26. a-na É DINGIR it-ta-din
- 27. ITI.GU<sub>4</sub> U<sub>4</sub>.9.KAM MU.13.KAM
- 28. dAG-NÍG.DU-ÙRU LUGAL TIN.TIRki
- 29. <sup>túg</sup>par-ši-gu<sup>meš</sup> SÍG.HÉ.ME.[DA]

- 30. šá <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra*
- 31. <sup>md</sup>AG-EN-MU.MEŠ *šá la h*[*a-a-tu*]
- 32. i-nam-din

The total of the individual data gives only 18 minas 40 shekels, i.e. 3 shekels less than in comparison with the total given in 1. 23.

- [30] shekels, the weight of the blue-purple lubār mēţu (and) lubār kulūluheadbands for Šamaš
- 3 minas, the weight of the *nēbeḥu*-belt from the shrine of Šamaš
- 8 minas, the weight of red robe for [Aya]
- 4 minas, the weight of ditto nahlaptu-cloak <for> Aya
- 40 shekels, the weight of the *lubār kulūlu* -headband and 3 red *paršīgu*-headdresses for Aya
- 50 shekels, the weight of 2 paršīgu-headdresses, 2 red nahlaptu-cloaks for the Daughters of the Ebabbar
- ½ mina, the weight of the *nēbeḥu*-belt for Bunene
- 6 shekels, the weight of the blue-purple *lubār mēṭu* (and) *lubār kulūlu*-headbands for Bunene
- 40 shekels, <the weight of> the blue-purple lubār kulūlu (and) lubār mēţuheadbands for Adad
- 24 [shekels], <the weight of> the lubār kulūlu-headband (and) red paršīguheaddresses for Šala

total 18 minas 43 shekels, <the weight of garments> made of red and blue-purple wool, Nabû-bēl-šumāti, the weaver, has delivered to the 'house of the god'.

Month of Ayaru, 9<sup>th</sup> day, 13<sup>th</sup> year of Nebuchadnezzar, king of Babylon. The red *paršīgu*-headdress for the Daughters of the Ebabbar will be delivered by Nabû-be-šumāti without (earlier) supply.

#### **179. BM 65979** (82-9-18, 5971)

 $6.4 \times 4.6$  cm

	na 「KI.LAL¹ []	
2'.	<i>šá</i> [ <sup>d</sup> UTU]	
3'. 6 2/3 m	a-na 5 GÍN KI.[LAL]	
4'.	$T\dot{U}G.BAR.DUL_8 \check{s}\acute{a}^dA^!-a$	
5'. 3 ma-na 55 GÍN KI.LAL		
6'.	TÚG.GÚ.UD.DU <i>šá</i> <sup>d</sup> A-a	
7'. 2/3 ma-	na KI.LAL 2 TÚG.BAR.SI.MEŠ	
8'. 1 <sup>en</sup> TÚ	G.HI.A ku-lu-lu 1 <sup>en</sup> pa-ši-ir <sup>!</sup> (T: ni)	
9'.	$\check{s}\acute{a}^{\rm d}A$ - $a$ (erasure)	
10'. 「5 <sup>?</sup> 」2 GÍN KI.LAL 10 TÚG.NÍG.ÍB. <lá>MEŠ</lá>		
11'.	$[\check{s}\check{a}^{\mathrm{d}}]A$ - $^{r}a^{?q}$	

12'. 2 ma-na [KI.LAL TÚG.HI.A TÚG.MÁŠ] Rev. šá <sup>d</sup>Bu-n[e-ne] 14'. 1/3 7 GÍN KI.LAL ni-bi-hu šá <sup>rd</sup>Bu-ne-ne<sup>1</sup> 15'. 4 「GÍN¹ [KI.LAL TÚG.ḤI.A] 「me¹-e-ṭu 「TÚG.ḤI.A¹ ku-lu-lu 16'. 1 ma-[na 10] 「GÍN「 [KI.LAL] 10 TÚG.「NÍG.ÍB.LÁ」.MEŠ

17'. 1<sup>en</sup> TÚG.ÚR šá [<sup>d</sup>IM u <sup>d</sup>Ša-la] 18'. [1 ma-na] KI.LAL 2 'TÚG'.[BAR.SI.ME]Š

19'. [TÚG]. [HI.A] [ku-lu-lu] šá dGAŠAN Sip-parki 20'. [x] GÍN KI.LAL 2 <sup>túg</sup>par-š[i<sup>?</sup>-gu šá <sup>d</sup>DN]

L. 8'. Or *pa-tin*!-*ni* instead of *pa-ši-ir*!.

L. 15'. The clear numeral at the very beginning is followed with the tiny traces of the sign, i.e. head of vertical and head of horizontal, most probably 「GÍN1.

Ll. 18'-19', cf. Cyr 191 (= 172): 9-10.

[.... x m]ina(s), the weight of [....] of [Šamaš.

6 minas 45 shekels, the we[ight] of the robe for Aya

3 minas 55 shekels, the weight of the nahlaptu-cloth for Aya

40 shekels, the weight of 2 paršīgu-headdresses, 1 lubār kulūlu-headband, 1 paširu<sup>?</sup> for Aya.

<sup>1</sup>5<sup>?</sup><sup>1</sup>2 shekels, the weight of 10 sashes of A[ya<sup>?</sup>]

2 minas, [the weight of the *lubāru* (and) *şibtu*-garments] for Bunene

27 shekels, the weight of *nēbehu*-belt for Bunene

4 shekels, [the weight of the *lubār*] *mētu* (and) *lubār kulūlu*-headbands

1 mina [10] shekels, [the weight] of 10 sashes, 1 sūnu-belt for [Adad and Šala] [1 mina], the weight of 2 [paršīgu-headdresses (and) lu]bār [kulūlu]-headband for the Queen of Sippar

[x] shekels, the weight of 2 paršī[gu-headdresses for [DN].

#### **180. BM 82581** (93-10-14, 33)

 $3.5 \times 5.9$  cm

[x].6.Nbk 13

1. <sup>[4]</sup> GADA *sal-hi* GAL.MEŠ

šá <sup>d</sup>UTU u <sup>ď</sup>A-a

3. 2 GADA 「sal-hi¬šá

<sup>d</sup>[DUMU.MÍ].MEŠ *É-babbar-ra* 

5. 2 GADA [sal-hi šá <sup>d</sup>B]u-ne-ne

6.  $1^{en} \, {}^{t}[{}^{u}gx \, x \, x] \, GADA \, \check{s}\acute{a} \, {}^{d}UTU$ 7.  $1^{en} \, {}^{tu}g_{1}[x \, x \, GADA \, \check{s}\acute{a}] \, {}^{d}Bu\text{-}ne\text{-}ne$ 

8. 2 GADA šá dul-la

9. 1<sup>en</sup> mu-ut-ta-tu<sub>4</sub> la-bi-ri

10. 1<sup>en</sup> TÚG.BAR.DUL<sub>5</sub> SÍG.HÉ.ME.DA

11. 4 TÚG.GÚ.UD.DU.MEŠ SÍG.HÉ.ME.DA

PLATE 43

- 12. 1et TÚG.GÚ.UD.DU bir-mu
- 13. pa-tin-nu šá <sup>d</sup>UTU
- 14. pa-tin-nu šá <sup>d</sup>Bu-ne-ne
- 15.  $\lceil ni \rceil$ -bi-hu  $\lceil x \rceil$  (erased)
- 16. <sup>r</sup>šá<sup>¹</sup> <sup>d</sup>Bu-ne-<sup>r</sup>ne<sup>¹</sup>

17. [2] TÚG.BAR.DUL<sub>5</sub> SÍG.HÉ.ME.DA Rev.

- 18. <sup>[4]</sup> TÚG.GÚ.UD.DU.MEŠ KI.MIN
- 19. *šá* <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra*
- 20. [ina IG]I  $^{\rm m}$ Şil-la-a 21. [ $^{\rm l\acute{u}}$ TÚ]G.BABBAR ITI.KIN
- 22. [U<sub>4</sub>.x. KAM] MU.13.KAM
- 23. [mdAG-NÍG.D]U-ÙRU LUGAL Eki

Cf. the similar texts ZA 4, No. 4 (= 176); CT 55, 811 (= 182); BM 68361 (= 277) and BM 50282 (= 359).

Note that the sequence in which the garments are enumerated in other texts of this group is not observed here. The scribe began from salhu-tunics (lines 1-5), next, in ll. 6-7, follow the other garments for Šamaš and Bunene, whose names are, however, damaged. It is not clear for which god the garments from 11. 8-9 are destined. For the kītu ša dulli garment, see above ZA 4 (1889) No. 4 = BM 72276 (= 176): 11. The *muttatu*-headdress according to BM 90002 was destined for Šamaš. Garments from lines 10-12 belong to the goddesses' attire, probably of Aya, cf. for example BM 64651 (= 221). The missing salhu appeared already in 1. 1. Below these garments the scribe goes back to the garments of Šamaš and Bunene, and next the set of garments of the Daughters of the Ebabbar, again without salhu, mentioned in 1. 3.

- 4 large linen tunics for Šamaš and Aya
- 2 linen tunics for the [Daught]ers of the Ebabbar
- 2 linen tunics for Bunene
- 1 linen [....] for Šamaš
- 1 linen [....] for Bunene
- 2 knock-about cloths
- 1 old *muttatu*-headdress
- 1 red robe, 4 red nahlaptu-cloaks, 1 multicoloured nahlaptu-cloak
- <1> patinnu-belt for Šamaš, <1> patinnu-belt for Bunene
- <1> nēbeļu-belt for Bunene
- 2 red robes, 4 ditto *nahlaptu*-cloaks for the Daughters of the Ebabbar [at dispo]sal of Şilla, the ašlāku.

Month of Ulūlu, [n<sup>th</sup> day], 13<sup>th</sup> year of [Nebuchad]nezzar, king of Babylon.

# **181. CT 55, 808** = BM 55846 Collated

## 8.2.Nbk 20

- 1. <sup>r</sup>mi¹-ih-su šá a-na <sup>lú</sup>TÚG.BABBAR SUM<sup>na</sup> ITI.GU<sub>4</sub>
- 2. [U<sub>4</sub>].8.KAM MU.20.「KAM<sup>1</sup> dAG-NÍG.DU-ÙRU \_\_\_\_\_
- 3. [2] GADA hu-la-nu 4 GADA sal-hi

```
4. [5] GÚ.UD.DU.MEŠ 1<sup>et</sup> GÚ.UD.DU bir-<mu>
 5. [1] ^{\text{túg}}BAR.DUL<sub>5</sub> \check{s}\acute{a}^{\text{d}}A-a
 6. [x] TÚG.<NÍG>.ÍB.LÁ.MEŠ 1<sup>en</sup> pa-tin-nu 1<sup>en</sup> gú-ḥal-ṣu
 7. <sup>[2]</sup>-ta <sup>túg</sup>BAR.DUL<sub>5</sub>.MEŠ 4 GÚ.ŪD.DU.MEŠ šá
           <sup>d</sup>GAŠAN.MEŠ
 8. 1[+x<sup>?</sup> GADA] sal-ḫi<sup>meš</sup> šá a-na <sup>lú</sup>TUG.BABBAR 「SUM<sup>1</sup>"
 9. [x] šá UGU šub-ti 1<sup>en</sup> kib-su [a]-<sup>[</sup>na<sup>]</sup>
10. [x] GADA ta-hap-šú šá <sup>d</sup>UTU bu-<sup>r</sup>x<sup>1</sup>
11. GADA gal bu x (erased)
12. [x] sal-hi eš-šu-tu a-na GADA <sup>r</sup>x e<sup>1</sup>
13. [x x x] <sup>r</sup>x<sup>1</sup> TÚG.HI.A 2 <sup>r</sup>x x<sup>1</sup>.MEŠ
```

Rest of Obv. broken.

Rev.

1'. [TÚG]. [HI.A] [me]-tu [ $1^{en?}$ ] [TÚ]G.HI.A ku-lu-lu

2'.  $[x m]a-[n]a^? < pa>-ši-ir [a-na] ^dA-a$ 

3'. [1/2] ma-na KI.LAL [ni]-bi-hu

4'. TÚG.ḤI.A me-tu TÚG.ḤI.A <ku-lu-lu> šá <sup>d</sup>Bu-ne-ne

5'. 17 GÍN TÚG.HI.A me-tu TÚG.HI.A ku-lu-lu

6'. šá <sup>d</sup>IM

7'. ½ ma-na KI.[LAL] 2 TÚG. BAR.SI .[MEŠ]

8'. TÚG.HI.A ku- $\lceil lu \rceil$ - $\langle lu \rangle$   $\lceil \check{s} \acute{a} \rceil$   $\stackrel{d}{\circ} \check{S} a$ - $la^! \rceil$ 

9'. 55 GÍN KI.LAL 2-ta TÚG.BAR\*.SI\*.[MEŠ]

10'. 2-ta GÚ.UD.<DU>.MEŠ šá <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-ra

11'. 1 ma-na KI.LAL TÚG.HI.A ku-lu-lu

12'. TÚG.BAR.SI.MEŠ šá  ${}^{d}$ GAŠAN  $Sip\text{-}par^{ki}$ 

13'. 「PAP¹ 19 ma-na 12 GÍN SÍG.ḤÉ.ME.DA 14'. u síg sad-ra

L. e.

L 6. I emended TÚG.ÍB.LÁ to TÚG.<NÍG>.ÍB.LÁ because nēbehu is never mentioned in the lists of garments for Bēlete/mārāt Ebabbar and because in many texts from the time of Nebuchadnezzar the sign NÍG is missing in the context where it is certain that huşannu, not nēbehu was meant.

L. 11. Pinches' copy seems to be correct, however, I cannot suggest any sense here.

Rev. 2'. <pa>-ši-ir. Cf. BM 65979 (= 179): 8'.

Rev. 8'. The suggested reading  $ku^{-1}lu^{1} < lu > \lceil \check{s}\check{a}^{1} \stackrel{\text{d}}{\circ} \check{S}a - la^{1}$  is uncertain.

Rev. 13'. One can recognize here a part of [PAP].

Woven garments, which were given to the ašlāku. Month of Ayaru, 8<sup>th</sup> [day], 20<sup>th</sup> year of Nebuchadnezzar

[2] linen hullānu-cloaks, 4 linen tunics; [5] nahlaptu-cloaks, 1 multicoloured nahlaptu-cloak, [1] robe for Aya

[x] huşannu'-sashes, 1 patinnu-belt, 1 scarf, 2 robes, 4 nahlaptu-cloaks for Ladies

1 [+x linen] tunics which were given to the  $a\bar{s}l\bar{a}ku$ .

[x] for covering of the cultic seat, 1 kibsu-fabric for [x] linen blankets for Šamaš

[x] new tunics for linen [....]

[....], x *lubāru*-garment [....]; 2 [....]

[....], the lubār mēṭu, lubār [erru, (and) lu]bār kulūlu-headbands

x mina, (the weight of) the pašir? for Aya

½ mina, the weight of the nēbēhu-belt, the lubār mēţu (and) lubār <kulūlu>headbands for Bunene

17 shekels, <the weight of> the lubār mēṭu (and) lubār kulūlu-headbands for Adad 1/2 mina, the we[ight] of 2 paršīgu-headdresses (and) the lubār kulūlu-headband for Šala

55 shekels, the weight of 2 paršīgu-headdresses (and) 2 nahlaptu-cloaks for the Daughters of the Ebabbar

1 mina, the weight of the lubār kulūlu-headband (and) 2 paršīgu-headdresses for the Queen of Sippar

<sup>1</sup>Total<sup>1</sup> 18 minas 12 shekels of red and *sadru*-wool.

#### **182. CT 55, 811** = BM 56367

#### 13.2.Nbk 22

- 1. *mi*-<sup>r</sup>*iḫ*-ṣu a¹-na <sup>lú</sup><sup>r</sup>Uй.[BAR] 2. SUM<sup>nu</sup> ITI.GU[4 U4].<sup>r</sup>13¹.[KAM] 3. MU.22.KAM <sup>md</sup> AG-[NÍG.DU-ÙRU]
- 4. LUGAL TIN.TIR<sup>ki</sup>

- 5. 1<sup>en</sup> GADA hu-[la]-nu
- 6. 4 GADA sal-「hu7
- 7. 1<sup>et</sup> TÚG.GÚ.UD.DU bir-<sup>[</sup>mu]
- 8. <sup>[5]</sup> TÚG.GÚ.UD.DU.MEŠ *šá na-b[a-su*]
- 9. <sup>[2]</sup> *ku-sa-a-tú* 2 GADA *šá dul-l*[*u* (x x)]
- 10. 2 mu-ut-ta-tu<sub>4</sub>
- 11. 2 *ni-bi-hi-nu*
- 12. 1<sup>en</sup> [ni]-bi-hi šá <sup>d</sup>Bu-ne-ne Rev.
  - 13. 4 ku-sa-a-tú 4 TÚG. GÚ. UD DU. MEŠ
  - 14. [šá] <sup>rd</sup>¹DUMU.MÍ.MEŠ É-<sup>r</sup>babbar¹-[ra]
  - 15. [x GADA] sal-hi šá <sup>d</sup>DUMU.MÍ.ME[Š *É-babbar-ra*]
  - 16. [2] pa-tinnu<sup>m[eš]</sup> [a-n]a dG[u-la]

Cf. the similar texts ZA 4, No. 4 (= 176); BM 82581 (= 180); BM 68361 (= 277) and BM 50282

- L. 2. The readings 23, 26 or 29 are also possible.
- L. 16. Or <sup>d</sup>*N*[*in*-x].

Woven garments, which were given to the wea[ver]; month of Ayaru, [13th] [day], 22<sup>nd</sup> year of Nebu[chadnezzar], king of Babylon.

1 linen *ḫullānu-*cloak, 4 linen tunics, 1 multicoloured *naḥlaptu-*cloak, <sup>「5¹</sup> r[ed] nahlaptu-cloaks, 2 robes, 2 knock-about clothes, 2 muttatu-headdresses, 2 nēbehubelts, 1 nēbehu-belt for Bunene, 4 robes, 4 naḥalaptu-cloaks [for] the Daughters of the Ebabbar, [x linen] tunics for the Daughters of the [Ebabbar], 2 patinnu-belts for G[ula].

#### 183. BM 49931 (82-3-23, 922)

PLATE 44

3.8 x 5.9 cm

- 1'. [x GADA] 「hu-ul¬-la-nu šá d「UTU¬
- 2'. [1<sup>?</sup> TÚG].ÍB.LÁ *šá* <sup>d</sup>UTU
- 3'. [1<sup>?</sup>] pa-tin-nu SÍG.ḤÉ.ME.DA šá <sup>d</sup>UTU
- 4'. 1 GADA gú-ḥal-ṣu šá <sup>d</sup>UTU
- 5'. TÚG.HI.A ku-lu-lu
- 6'. TÚG.ḤI.A me-tu SÍG.ḤÉ.ME.DA šá  $^{\rm d}$ UTU
- 7'. 2 GADA sal-hi šá <sup>d</sup>A-a
- 8'. TÚG.BAR.DUL<sub>8</sub> SÍG.HÉ.ME.DA šá <sup>d</sup>A-a
- 9'. 3 TÚG.GÚ.UD.DU.MEŠ SÍG.HÉ.ME.DA
- 10'. 1et TÚG.GÚ.UD.DU bir-mu šá dA-a
- 11'. 2 「GADA<sup>¬</sup> sal-hi
- 12'. 2 TÚG.BAR.DUL<sub>8</sub>.MEŠ
- 13'. 3 TÚG.GÚ.UD.DU.MEŠ
- 14'. 「šá¹ dDUMU.MÍ.MEŠ É-babbar-ra
- 15'. [1 GADA sa] $l^2$ - $[hi^2]$
- 15'. [x x x x x]. [MEŠ<sup>?</sup>] 16'. [šá <sup>d</sup>B]u-ne-n[e]

Edge

Rev. uninscribed

[x linen] hullānu-cloak(s) for Šamaš;

- [1<sup>?</sup> nēbe]hu-belt for Šamaš
- [1<sup>?</sup>] red *patinnu*-belt for Šamaš
- 1 linen scarf for Šamaš
- 1 lubār kulūlu
- 1 red *lubār mēţu*-headbands for Šamaš.
- 2 linen tunics for Aya,
- red robe for Aya,
- 3 red nahlaptu-cloaks,
- 1 multicoloured *nahlaptu*-cloak for Aya.
- 2 linen tunics.
- 2 robes.
- 3 nahlaptu- cloaks for the Daughters of the Ebabbar.
- [1 linen tu]nic<sup>?</sup>, [....] for Bune[ne].

# VIII. The classical miḥṣu tenû texts

## GARMENTS FOR CYCLE A

1. Garments for the Nisannu lubuštu ceremony

## **184. CT 55, 809** = BM 57445

Rev.

#### 2.1.Nbn 4

1. mi-ih-ṣu šá te-nu-ú šá a-na  $^{l\acute{u}}$ TÚG.BABBAR SUM $^{in}$ 2. ITI.BÁR U<sub>4</sub>.2.KAM MU.4.KAM <sup>d</sup>AG-I LUGAL TIN.TIR<sup>ki</sup> · 3. 2 GADA sal-hi 1<sup>en</sup> GADA hu-la-nu 1<sup>en</sup> GADA gú-hal-și 4. 「1<sup>en</sup> túgpa-ti-in-nu 1 TÚG.ÍB.LÁ TÚG.HI.A ku-「lu4¬-lu4 5. [TÚG.HI]. [A] me-e-tu a-na dUTU 6. [2 GADA sal-ḫi 4]-ta  $^{\text{túg}}$ na-ḫal-ap-tu<sub>4</sub>  $1^{et}$   $^{\text{túg}}$ na-ḫal-ap-tu<sub>4</sub> bir-ri 7. [2  $^{\text{túg}}$ ku-si-t]u<sub>4</sub> a-na  $^{\text{d}}$ A-a 8. 1 GADA [sal-ḥi 1] GADA ḥu-la-nu 1 gú-ḥal-ṣu 1 <sup>túg</sup>pa-ti-nu 10. [2 GADA sa]l-hi 6-ta <sup>túg</sup>na-hal-ap-tu<sub>4</sub> [2]-ta ku-s[i-tu<sub>4</sub>] 11. a-na <sup>d</sup>[DUMU.M]Í.<MEŠ> É-babbar-ra 12. 1 GADA sal-ḥi 1 gú-ḥal-ṣu 1 <sup>túg</sup>pa-ti-[in-nu] 13. 1 TÚG.ÍB.LÁ *a-na* <sup>d</sup>IM

Woven garments for the change (for the lubuštu ceremony), which were given to the *ašlāku*.

Month of Nisannu, 2<sup>nd</sup> day, 4<sup>th</sup> year of Nabonidus, king of Babylon

14. 1 GADA sal-ḥi 1<sup>et</sup> [túg]na-[ḥal-ap-tu<sub>4</sub>]

15.  $1^{et}$  ku-si-tu<sub>4</sub> [a-na <sup>d</sup>Ša-la]

2 linen tunics, 1 linen hullānu-cloak, 1 linen scarf, 1 patinnu-belt, 1 nēbehu-belt, the *lubār kulūlu* and [*lubār*] *mēṭu*-headbands for Šamaš

[2 linen tunics, 6] nahlaptu-cloaks, 1 multicoloured cloak, [2 rob]es for Aya

1 linen [tunic, 1] linen hullānu-cloak, 1 scarf, 1 patinnu-belt, [1 nēbeh]u-belt for [Bu]nene

[2 linen tuni]cs, 6 nahlaptu-cloaks, [2] rob[es] for [the Daugh]ters of the Ebabbar 1 linen tunic, 1 scarf, 1 pati[nnu]-belt, 1 nēbeḥu-belt for Adad 1 linen tunic, 1 *naḥlaptu*-cloak, 1 robe [for Šala] **185. BM 61914** (82-9-18, 1883) PLATE 44  $7.8 \times 4.5$  cm 3.1.Nbn 11 1. mi-ih-sute-nu-ú šá a-na $^{\mathrm{md}}\mathrm{UTU}\text{-}\mathrm{NUMUN}\text{-}\mathrm{G\acute{A}L}^{[\tilde{s}i]}$ 2.  $^{\text{lú}}$ TÝG.BABBAR SUM $^{na}$  ITI.BÁR U $_{4}$ .3.KAM MU.11.KAM  $^{md}$ AG-I LUGAL  $^{\Gamma}$ E $^{[ki]}$ 3. 2 GADA sal-hi 1 GADA hu-ul-la-nu 1 GADA gú-hal-şu 4. 1 pa-tin-nu 1 ni-bi-hu TÚG.HI.A me-tu TÚG.HI.A ku-lu-lu 「a-na <sup>d</sup>UTU¹ 5. 2 「GADA sal-hi<sup>1</sup> 4-ta na-hal-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA 6.  $[1 \text{ na-hal-lap-tu}_4 \text{ b}]ir\text{-mu} < 1 > ku\text{-si-tu}_4 \text{ a-na}^d \text{-A-a}$ 7. [1 GADA sal-hi 1 GADA hu-ul]-la-nu 1 GADA g[ú-hal-șu] Rest of obv. lost 1'. [1 *pa-tin-n*]*u* <sup>r</sup>*a-na* <sup>d</sup>IM<sup>1</sup> Rev. 2'. [1 GAD]A sal-hi 1 <sup>túg</sup>na-hal-lap-tu4 <1> k[u-si-tu4] 3'. *a-na* <sup>d</sup><sup>r</sup>Š*a*<sup>1</sup>-*la* Rest of Rev. uninscribed Woven garments for the change (for the lubuštu ceremony), which were given to Šamaš-zēr-ušabši, the *ašlāku*. Month of Nisannu, 3<sup>rd</sup> day, 11<sup>th</sup> year of Nabonidus, king of Babylon. 2 linen tunics, 1 linen hullānu-cloak, 1 linen scarf, 1 patinnu-belt, 1 nēbehu-belt, the lubār mēţu (and) lubār kulūlu-headbands for Šamaš [2] linen tunics, 4 red *naḥlaptu-*cloaks, [1 mu]lticoloured [cloak], [<1> robe for Aya [1 linen tunic, 1 linen hu]llānu-cloak, 1 linen s[carf ....] [1 patinn]u-belt for Adad [1] linen tunic, 1 nahlaptu-cloak, <1> r[ob]e for Gula.

## **186. BM 83985** (83-1-21, 1148)

 $3.9 \times 4.0 \text{ cm}$ 

# 2.1.Nbn [x]

- 1. [mi-iḥ-ṣ]u te-nu-ú šá a-na [lu-bu-uš-tu4 šá ITI.BÁR a-na]
- 2.  $[x \times x \times SU]M^{nu}$  ITI.BÁR U<sub>4</sub>.2.KAM MU.[x.KAM]
- 3. [mdAG-na-']-id LUGAL TIN.TIR[ki]

\_\_\_\_\_

- 4. [2 GADA sal-ḥu] 1 ḥu-ul-la-nu 1 gú-ḥal-[ṣu]
- 5. [1 pa-tin-nu] 「1 ni-bi-hu lu-ba-ri ku-[lu-lu]
- 6. [lu-ba-ri me-ṭ]u šá <sup>d</sup>U[TU]

-----

7. [2 GADA *sal-hu* 1 *ku*]-<sup>r</sup>*sa*<sup>1</sup>-*tu*<sub>4</sub> 1 *na-ah-lap-tu*<sub>4</sub> [....]

Rest lost

Rev. in preserved part uninscribed

L. 7. There is ku]- $\lceil sa \rceil$ - $tu_4$  instead of expected ku]- $\lceil si \rceil$ - $tu_4$ .

[Wove]n garments for the change for [the *lubuštu* ceremony for the month Nisannu, which were giv]en [to PN]. Month of Nisannu, 2<sup>nd</sup> day, [n<sup>th</sup>] year of [Naboni]dus, king of Babylon.

-----

[2 linen tunics], 1 hullānu-cloak, 1 sca[rf],

[1 patinnu-belt], 1  $n\bar{e}behu$ -belt, the  $lub\bar{a}r$   $ku[l\bar{u}lu]$  (and)  $[lub\bar{a}r$   $m\bar{e}t]u$ -headbands for Šamaš

-----

[2 linen tunics, 1 ro]be, 1 nahlaptu-cloak, [....].

# **187. BM 68964** (82-9-18, 8963)

 $6.3 \times 4.0 \text{ cm}$ 

[x].1.Cyr 2

- 1. mi-ih-ṣi te-nu-ú šá lu-bu-uš-tu4 šá [U4.7.KAM]
- 2. šá ITI.BÁR MU.2.KAM  $^{\rm m}$ Ku-ra-áš LUGAL E $^{\rm ki}$  [LUGAL KUR.KUR]
- 3. a-na  $^{\rm md}$ UTU-MU-MU  $^{\rm lú}$ TÚG.BABBAR SUM $^{nu}$  ITI.[BÁR. U<sub>4</sub>.x.KAM]

-----

- 4. 2 GADA sal-ḫu 1 GADA ḫu-la-nu 1 GADA gú-ʿḥal<sup>!</sup>¬-[ṣu]
- 5. 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ 1 TÚG.ḤI.A me-tu 1 TÚG.Ḥ[I.A ku-lu-lu šá  $^{\rm d}$ UTU]

------

- 6. 2 GADA sal-hu 4-ta 「GÚ.UD.DU」 [SÍG.HÉ.ME.DA]
- 7. 1<sup>et</sup> [GÚ.UD.DU *bir-mu* 1 *ku-si-tu*<sub>4</sub> *šá* <sup>d</sup>*A-a*]

Rev. uninscribed

Ll. 4–5. Note the lack of a *nēbeḥu*-belt in the list of Šamaš garments.

L. 4. At the end of the line one can expect  $g\acute{u}$ -hal-su, however, after  $g\acute{u}$  there is a fragmentary preserved sign, which looks exactly like the beginning of repeated  $g\acute{u}$ .

Woven garments for the change for the *lubuštu* ceremony [for the  $7^{th}$  day] of Nisannu,  $2^{nd}$  year of Cyrus, king of Babylon, [king of Lands], which were given to Šamaš-šum-iddin, the *ašlāku*. [Month of Nisannu,  $n^{th}$  day].

-----

2 linen tunics, 1 linen *ḫullānu*-cloak, 1 linen sca[rf], 1 *patinnu*-belt, 1 *lubār mēṭu* and *lub*[*ār kulūlu*]-headbands [for Šamaš]

\_\_\_\_\_

[2] linen tunics, 4 [red] *naḥlaptu-*cloaks,

1 [multicoloured nahlaptu-cloak, 1 robe for Aya].

```
188. BM 75397 = Str. II 178/4
```

 $5.0 \times 3.7$  cm

```
1. mi-ih-hi-iș te-nu-ú [....]
```

2. 
$$[x \ x] \check{s} \check{a} \ [x] (er.) a-na \ ^m Sil-[la]-[a (...)]$$

3. 
$$[SUM^{nu} IT]I.BÁR [x]$$

4–8 unreadible traces of signes.

Rev. 1–6 eroded almost completely, so that reading is impossible.

\_\_\_\_\_

```
7. [1] GADA sal-[hi] t^{tig}[x] [....]
```

8. [x] TÚG.BAR<sup>!</sup>.SI [....]

9. [*šá* <sup>d</sup>]IM *u* <sup>d</sup>*Ša*-[*la*]

The surface of this completely preserved tablet is heavily eroded, probably much more than in the time when Strassmaier has made his copy.

Woven garments for the change [....] for Şillāya [were given. Mon]th of Nisannu [....].

-----

1 linen tunic, [..., x] paršīgu-headdress(es), [.... for] Adad and Ša[la].

# 2. Garments for the Ayaru *lubuštu* ceremony

<b>189.</b> CT <b>55, 805</b> = BM 57416
3.2. [Nbn] 5
1. [mi-iḫ-ṣu te-nu]-ú šá a-na <sup>md</sup> [] 2. [SUM <sup>na</sup> ITI.G]U <sub>4</sub> U <sub>4</sub> .3.KAM MU.5.[KAM <sup>md</sup> AG-I LUGAL Bābili]
3. [2 GADA sal-ḫu 1 GADA] ḫu-ul-la-nu 1 GADA g[ú-ḫal-ṣu] 4. [1 pa-tin-nu 1] ni-bi-ḫu TÚG.ḤI.A me-ṭu TÚG.ḤI.A ku-lu-l[u šá <sup>d</sup> UTU]
5. [1 GADA sal-ḫu x n]a-ḫal-lap-tu <sub>4</sub> SÍG.ḪÉ.ME.DA 1 na-ḫal-la[p-tu <sub>4</sub> b]ir-ri 6. [1 ku-si-t]u <sub>4</sub> a-na <sup>d</sup> A-a
7. [1 GADA <i>sal-ḥu</i> 1 GADA <i>ḫu-ul</i> ]-「la¹-[nu] 「1¹ GADA gú-ḥal-[ṣu] 8. [1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 TÚG.ÍB.LÁ <i>a-na</i> <sup>d</sup> Bu]-「ne¹-[ne]
Rest of Obv. lost.
Rev. 1'. []- $^{\Gamma}ni^{?}$ 2'. [] $^{\Gamma}$ šam $^{\Gamma}$ -ma-mu [a-na $^{d}$ A-nu-ni-tu <sub>4</sub> ]
3'. [ $k$ ] $u$ - $si$ - $tu$ 4 $a$ - $na$ ${}^{d}G[u$ - $la$ ]
4'. [1 GADA sal-ḫu 1 GADA gú-ḫal-ṣu] 1 pa-tin-nu 1 ni-bi-[ḫ]u [a-na <sup>d</sup> IM]
5'. [1 GADA sal-ḫu 1 na-ḫal-lap-tu <sub>4</sub> SÍG.ḤÉ.ME.DA 1 $^e$ ] $^f$ ku-si-tu <sub>4</sub> $a$ -na $^{r^d}$ 1[Ša-la]
6'. [] 「x¹ šá <sup>d</sup> ḤAR a []
[Woven garments for the chan]ge for [PN, the were given. Month of Aya]ru, 3 <sup>rd</sup> day, 5 <sup>th</sup> year [of Nabonidus, king of Babylon]
[2 linen tunics, 1 linen] $hull\bar{a}nu$ -cloak, 1 linen s[carf, 1 $patinnu$ -belt, 1] $n\bar{e}behu$ -belt, the $lub\bar{a}r$ $m\bar{e}tu$ and $lub\bar{a}r$ $kul\bar{u}[lu]$ -headbands [for Šamaš]
[1] linen tunic, [x] red [n]ahlaptu-cloaks, 1 multicol[oured] nahla[ptu]-cloak, [1 rob]e for Aya

```
[1 linen tunic, 1 linen hul]lā[nu]-cloak, 1 linen scarf, [1 patinnu-belt,
1 nēbeḥu-belt for Bu]ne[ne]
[.... the lubār] šammamu-garment [for Anunītu]
 [...., 1] robe for Gul[a]
[1 linen tunic, 1 linen scarf], 1 patinnu-belt, 1 nēbeḥu-belt [for Adad]
  _____
[1 linen tunic, 1 red nahlaptu-cloak, 1] robe for [Šala]
_____
[....] for Bunene [....].
190. BM 101060 (83-1-21, 2721)
5.1 \times 4.5 \text{ cm}
                   [x].2.Nbn 13
          1. mi-iḥ-ṣu te-nu-ú šá a-「na¬
          2. [m]<sub>[</sub>d]<sub>1</sub>U+GUR-MU SUM<sup>na</sup> ITI.GU<sub>4</sub>
          3. [U_4.x.KAM] MU.13.KAM ^dAG-I LUGAL E^{ki}
          _____
          4. [2 GADA sa]l-hi 1 GADA hu-ul-la-nu
          5. [1 GADA g]ú-hal-ṣu ni-bi-hu pa-tin-nu
          6. [TÚG.HI.A me]-tu TÚG.HI.A ku-lu-lu a-na <sup>d</sup>UTU
          _____
          7. [2 GADA sal-h]i 4 na-hal-lap-tu4 SÍG.HÉ.ME.DA
          8. [1 \ na]-[hal-lap-tu] bir-mu
          9. [1 ku-si-tu_4 a]^{-1}na^{-1}A^{-1}a^{-1}
Rest of Obv. lost
Rev.
          1'. [.... -t]u_4
          2'. [1 ku-si-t]u4 a-na {}^{d}ME.ME
          3'. [1 GADA sal-hi 1 GADA] gú-hal-ṣu <1> ni-bi-hu
          4'. [1 pa-tin-nu a-n]a <sup>d</sup>IM
          _____
          5'. [1 GADA sal-hi] 1<sup>et</sup> na-hal-lap-tu<sub>4</sub>
          6'. [1 ku]-si-tu<sub>4</sub> a-na <sup>d</sup>Ša-la
          _____
          7'. [x GADA] <sup>r</sup>sal<sup>n</sup>-hu šá <sup>d</sup>UTU (sic) 1 ni-bi-hu
          8'. šá <sup>d</sup>[x a]-na GIŠ.GU.ZA
          9'. TÚG.HI.A [a-na] <sup>d</sup>A-nu-ni-tu<sub>4</sub>
```

L. 8'. GIŠ is written over erasure.

Woven garments for the change were given to Nergal-iddin. Month of Ayaru, $[n^{th}$ day], $13^{th}$ year of Nabonidus, king of Babylon
[2 linen tun]ics, 1 linen <i>ḫullānu</i> -cloak, [1 linen s]carf, the <i>nēbeḥu</i> -belt, the <i>patinnu</i> -belt, [the <i>lubār mē</i> ] <i>ţu</i> (and) <i>lubār kulūlu</i> -headbands for Šamaš
[2 linen tun]ics, 4 red <i>naḥlaptu</i> -cloaks, [1] multicoloured [ <i>na</i> ] <i>ḥlaptu</i> cloak, [1 robe f]or Aya
[, 1 rob]e for Gula
[1 linen tunic, 1 linen] scarf, <1> nēbeļu-belt, [1 patinnu-belt fo]r Adad
[1 linen tunic], 1 <i>naḥlaptu-</i> cloak, [1 ro]be for Šala
[x linen] tunics for Šamaš, 1 <i>nēbehu</i> -belt of the god(dess) [x fo]r the throne, the <i>lubāru</i> -garment [for] Anunītu.
<b>191. BM 100764</b> (83-1-21, 2425) 6.1 × 2.3 cm
(-).2. <kn> 17</kn>
1. [mi-iḥ]-ṣu te-nu-ú šá ITI.GU <sub>4</sub> MU.17.K[AM
2. [2 GADA <i>s]al-ḫu</i> 1 GADA <i>ḫu-ul-la-nu <sup>r</sup>1<sup>?</sup>¹</i> [] 3. [1 GADA gú-ḫal]-ṣu TÚG.ḤI.A me-ṭu TUG.ḤI.A [ku-lu-lu šá <sup>d</sup> UTU]
4. [x x x] $1^{et}$ ku-si-tu <sub>4</sub> 5 TÚ[G] 5. [] <sup>r</sup> x x x <sup>1</sup>
Woven garments for the month Ayaru, the 17 <sup>th</sup> ye[ar].
[2 linen tu]nics, 1 linen <i>ḫullānu</i> -cloak, 1 [, 1 linen sca]rf, the <i>lubār mēṭu</i> (and) <i>lubār</i> [kulūlu]-headbands [for Šamaš]
[], 1 robe, 5 [].
<b>192.</b> CT <b>55, 838</b> = BM 57305
1. [TÚG].ÍB.LÁ TÚG.MURUB <sub>4</sub> .ÍB.LÁ 2. [] $\sin^2 \sin^2 \sin^2 \sin a$ Sá $\sin^2 \sin a$ Sú.UD.DU.A $\sin^2 \sin a$ Sá $\sin^2 a$ Sá $\sin^2 a$ Sá $\sin^2 a$ Sá $\sin^2 a$ Sí Sí Sí Sí Sí Sí Sí Sí Sí Sí Sí Sí Sí

- 4. [....] TÚG.MURUB<sub>4</sub>.ÍB.LÁ gú-hal-şu šá <sup>d</sup> Bu-ne-ne<sup>1</sup>
- 5. [2 GADA sal-hi 3 GÚ.UD.DU.A SÍG.HÉ.ME.D]A  $1^{et}$  GÚ.UD.DU.A bir-m[u]
- 6. [....]. ME<sup>?</sup>. DA<sup>?</sup> J GÚ. UD. DU. A SÍ[G ....] 7. [.... GAŠAN UD. KIB]. NUN<sup>[ki]</sup>

Rest of obv. lost. Because the beginning of the tablet is preserved it means that in comparison with other *mihsu tenû* texts this one had a different organisation of the content. The dating of the text suggests that only the *lubuštu* ceremony of the month Ayaru can be taken into account. The clothes mentioned in the first line cannot be recognized as garments for Aya, as nēbeļu and patinnu did not appear in the list of her garments.

1'. nothing is preserved Rev.

- 2'. [.... GÚ].UD.DU.A  $\lceil na \rceil$ -ba-s[u (...)]
- 3'. [.... TÚG.ÍB].LÁ *šá* <sup>d</sup>*Bu-ne-n*[*e*]
- 4'. [....] a-na lu-bu-u $\check{s}$ -t[u4 ...]
- 5'. [.... a-n]a <sup>md</sup>UTU-NUMUN-GÁL <sup>ši</sup>
- 6'. [lúTÚG.BABBAR SUM<sup>na</sup> ITI].BÁR U<sub>4</sub>.29.KAM
- 7'. [MU.x.KAM <sup>d</sup>AG-IM].TUKU LUGAL TIN.TIR<sup>ki</sup>
- [....  $n\bar{e}$ ] behu-belt, the patinnu-belt
- [....] robe, multicoloured *naḥlaptu*-cloak [....] for Aya

\_\_\_\_\_

[....] patinnu-belt (and) scarf for Bunene \_\_\_\_\_

[2 tunics, 3 red nahlap]tu-cloaks, 1 multicoloured nahlaptu-cloak, [.... re]d?, the [....] nahlaptu-cloak [for the Queen of Sip]par

[....] red naḥlaptu-cloak, [...., nēbe]ḥu-belt for Bunene [....] for the lubuštu ceremony [....] for Šamaš-zēr-ušabši, [the ašlāku were given. Month] of Nisannu, 29<sup>th</sup> day, [nth year of Nabon]idus, king of Babylon.

#### 3. Garments for the Arahsamna *lubuštu* ceremony

# **193. Nbn 78** = BM 55674; cf. NUVI 3, No. 1 Collated

#### 8.8.Nbn 2

```
1. [mi]-^{\Gamma}ih-^{\Gamma}su te-nu-ú šá a-na ^{\text{lú}}TÚG.BABBAR [\text{SUM}^{na}] 2. ITI.APIN U<sub>4</sub>.8.KAM MU.2.KAM ^{\text{d}}AG-I LUGAL [\text{E}^{ki}]
```

\_\_\_\_\_

```
3. <sup>r</sup>2<sup>1*</sup> GADA sal-hu 1 GADA hu-ul-la-nu 1 [GADA gú-hal-ṣu]
```

- 4. 1  $^{\text{túg}}$  pa-ti-in-nu 1  $^{\text{en}}$  TÚG.HI.A ku- $^{\text{r}}$  lu<sub>4</sub>  $^{\text{l}}$  -[lu<sub>4</sub>]
- 5. TÚG.[HI.A me]-<sup>r</sup>e¹-tu TÚG.ÍB.LÁ a-na <sup>d</sup>[UTU] · ------

6. 2 GADA  $\lceil sal \rceil$ -[hu]  $1^{en}$  ku-si-tu4  $1^{et}$  tu9 na-[hal-ap-tu4 bir-mu]

7.  $5*-ta^{t\acute{u}g}[na-hal]-ap-tu_4$  na-ba-su  $a-na^{d}[A-a]$ 

8. 1 GADA sal-ḥu 1 GADA ḥu-ul-la-nu 1 gú\*-ḥal\*-[ṣu]

9. 1 <sup>túg</sup>pa-ti-in-nu 1<sup>en</sup> TÚG.ÍB.<LÁ> a-na <sup>d</sup> Bu¹\*-[ne-ne]

10. 2 GADA sal-hu 6-ta <sup>túg</sup>na-hal-「ap-tu4<sup>1</sup>

11. 2-ta ku-si-tu<sub>4</sub> a-na <sup>d</sup>DUMU.MÍ.</br>

12. 2 GADA sal-hu  $[1^{et \text{ túg}}]$ na-hal-ap-tu<sub>4</sub> bir\*-[mu]Rev.

13. 3- $ta^{rtig}*\eta na-hal-rap^{\eta}-[tu_4]$  na-hal-s[u]

13. 3-ta ha-ŋat- ap -[tu₄] na-bat-s[tu]
14. 1<sup>et túg</sup>na-ḥal-「ap¹-[tu₄] SÍG.ZA\*.GÌN\*.KUR\*.R[A]\*
15. 1<sup>et</sup> ku-si-tu₄ 1<sup>en</sup> TÚG.ḤI.A IGI 1<sup>en</sup> TÚG [....]
16. 3 <sup>túg</sup>pa-ri-ši-i a-na <sup>d</sup>GAŠAN Sip-par<sup>ki!</sup>

-----

17. <sup>[2]</sup> GADA sal-hu 1<sup>et túg</sup>na-hal-<sup>[</sup>ap<sup>]</sup>-tu<sub>4</sub> 1<sup>et</sup> ku-si-tu<sub>4</sub>

a-na <sup>d</sup>Gu-la

19. [1] GADA sal-hu 1  $t^{tig} gu^*-hal^*-su^*$  1  $t^{tig} pa-ti-[in-nu]$ 

20. [1] <sup>tág</sup>ni-bi-ḫu a-<sup>[</sup>na] <sup>d</sup>IM

21. [1] GADA sal-hu 1<sup>et túg</sup>na-hal-ap-tu<sub>4</sub>

22.  $1^{e\bar{t}}$  ku-si-tu<sub>4</sub> a-na <sup>d</sup> $\Gamma$ Ša<sup>1\*</sup>-l[a]

Strassmaier's copy is in general accurate, however, a few corrections have been made.

L. 2. There is no place for [TIN.TIR<sup>ki</sup>]
L. 13. *na-bal-s*[*u*] is certain and nothing is missing.

L. 16. túgpa-ri-ši-i, maybe a mistake for pa-ši-ri-i (see Index).

L. 21. Contra Strassmaier's copy nothing is missing in this line.

Woven garments, which [were given] to the ašlāku. Month Araḥsamna, 8th day, 2<sup>nd</sup> year of Nabonidus, king of Babylon

2 linen tunics, 1 linen <i>ḫullānu</i> -cloak, [1 linen scarf], 1 <i>patinnu</i> -belt, 1 <i>lubār kul</i> (and) <i>lu[bār mē]ṭu</i> -headbands (and) <i>nēbeḥu</i> -belt for Šamaš	ūlu		
2 linen tu[nics], 1 robe, 1 [multicoloured na]hlaptu-cloak, 5 red [nahl]aptu-cloaks for Aya			
1 linen tunic, 1 linen <i>ḫullānu</i> -cloak, 1 linen sc[arf], 1 <i>patinnu</i> -belt, 1 <i>nēbeḫu</i> -for Bu[nene]	oelt		
2 linen tunics, 6 <i>naḥlaptu</i> -cloaks, 2 robes for the Daughters of the E[babbar]			
2 linen tunics, [1] multicoloured <i>naḥlaptu</i> -cloak, 3 red <i>naḥlaptu</i> -cloaks, 1 bl purple <i>naḥlaptu</i> -cloak, 1 robe, 1 <i>lubār pāni</i> -veil, 1 []-garment, 3 <i>pariši</i> -garme for the Queen of Sippar			
2 linen tunics, 1 <i>naḥlaptu</i> cloak, 1 robe for Gula 1 linen tunic, 1 scarf, 1 <i>pati</i> [ <i>nnu</i> ]-belt, 1 <i>nēbeḥu</i> -belt for Adad			
1 linen tunic, 1 <i>naḥlaptu</i> -cloak, 1 robe for Ša[la].			
194. BM 65708 (82-9-18, 5698) 7.3 × 5.9 cm  13.8.[Nb]n [x]  1. [mi-ih-şu te-nu-ú šá l]u-bu-uš-tu4 šá ITI.APIN [U4.15.KAM] 2. [šá <sup>md</sup> UTU-MU]-MU SUM <sup>na</sup> ITI.APIN U4.13.KAM MU.[x.KAM] 3. [dAG]-II LUGAL [TIN].TI[R <sup>ki</sup> ]			
4. [2 GADA sal-hu 1 GADA hu-ul]- <sup>r</sup> la-nu <sup>1</sup> 1 GADA gú-hal-şu 1 TÚG.MURUB <sub>4</sub> .Í[B.LÁ 1 ni-bi-hu] 5. [a]- <sup>r</sup> na <sup>1</sup> [ <sup>d</sup> UTU]			
6. [2 GADA sal-ḥu 6 TÚG].「GÚ.UD.DU <sup>1</sup> šá SÍG.ḤÉ.ME.DA 1 SÍG.Z[Aʾ.GÌN.KUR.RA] 7. [a]-「na <sup>1 d</sup> A-a			
8. [2 GADA sal-ḫu 2 TÚG]. ʿGÚ.UDʾ.DU SÍG.ḤÉ.ME.DA 2 ʿ[ʿa-na dDUMU.MÍ.MEŠ] ʿÉʾ-babbar-ra Rest lost			
Rev. 1'. Nothing preserved			

#### 

[Woven garments for the change for the *lu*]*buštu* ceremony for the month Araḥsamna, [15<sup>th</sup> day, which were given to Šamaš-šum]-iddin. Month of Araḥsamna, 13<sup>th</sup> day, [nth] year of [Nabo]nidus, king of Babyl[on].

[2 linen tunics, 1 linen hul]  $l\bar{a}nu$ -cloak, 1 linen scarf, 1 patin[nu]-belt, [1  $n\bar{e}behu$ -belt for

Šamaš

[2 linen tunics, 6] red *naḥlaptu*-cloaks, 1 bl[ue-purple<sup>?</sup>] <*naḥlaptu*-cloak>, [.... robe] for Aya

[2 linen tunics, 2] red *naḥlaptu*-cloaks, 2 [robes for the Daughters of] the Ebabbar

.....

[1 tunic, 1] red *nahlaptu*-cloak, 1 [robe] for Šala.

#### 195. BM 61504 (82-9-18, 1478)

 $8.55 \times 5.95$  cm

# 9.8.Cyr 5

- 1.  $\lceil mi$ -ih $\rceil$ - $\lceil su\ te$ -nu-u $\check{s}$  $\acute{a}\ l$  $\rceil u$ -bu-u $\check{s}$ -tu4 $\mathring{s}$  $\acute{a}\ ITI.[APIN\ PN]$
- 2.  $^{\text{l\'u}}$ TÚG.BABBAR [SUM $^{na}$ ] ITI.APIN U4.9.KAM MU.5.KAM  $^{\text{m}}$ Ku-ra-[áš LUGAL E $^{\text{ki}}$  LUGAL KUR.KUR]
- 3. 2 GADA sal-ḥu [1 GAD]A ḥu-ul-la-nu 1 GADA gú-ḥal-ṣu 1 pa-ti[n-nu]
- 4. 1 <sup>túg</sup>ni-bi-ḥu [2 TÚG].BAR.「SII.MEŠ <sup>túg</sup>lu-<bar> me-ṭu <sup>túg</sup>lu-bar ku-lu-lu šá <sup>d</sup>UTU
- 5. 2 GADA sal-hu 4 TÚG.GÚ.「UD¹.DU SÍG.HÉ.ME.DA  $1^{et}$  <TÚG>.GÚ.UD.DU bir-mu
- 6.  $[1^{et}]$  ku-si-tu<sub>4</sub> SÍG.ḤÉ.ME.DA 2 TÚG.BAR.SI.MEŠ a-na  ${}^{d}A$ -a
- 7. [2 GADA] sal- $^{1}hu$ 1 6 GÚ. $^{1}$ UD1.DU SÍG.HÉ.ME.DA 2 ku-sa-a-tu4 SÍG.HÉ.ME.DA  $\check{s}\check{a}$   $^{d}$ GAŠAN.MEŠ
- 8. [1] GADA sal-ḥu 1 GADA ḥu-u[l]-la-nu 1 GADA ˈgú-ḥal-ṣu 1 pa-tin-nu SÍG.ḤÉ.ME.DA
- 9. [1] <sup>r</sup>ni-bi-ḫu <SÍG>.ḪÉ.[ME].DA<sup>1</sup> a-na <sup>d</sup>Bu-ne-ne
- 10. [x] GADA sal-ḫu 3 「GÚ.UD.DU ta-bar¹-ri 1<sup>et</sup> GÚ.UD.DU bir-「mu¹

- 11. 1<sup>et</sup> G[Ú.U]D.DU SÍG.ZA.GÌN.KUR.RA [x] <sup>túg</sup>lu-bar pa-ni SÍG.ZA.GÌN.KUR.RA 1 ku-si-tu<sub>4</sub>] SÍG.ZA.GÌN.KUR.RA
- 12. e-ri SÍG.ZA.GÌN.KUR.RA lu-bar  $^{r}ku$ -lu-lu  $^{1}$  SÍG.ZA.G[ÌN.KUR.RA  $š\acute{a}$   $^{d}$ GAŠAN Sip-par  $^{k}$   $^{i}$

Rev. 13. 1 GADA sal-hu 1 $^{et}$  GÚ. $^{t}$ UD $^{t}$ .D[U SÍG.HÉ.ME.DA]  $^{t}$ 1 $^{et}$  ku-si-tu4 $^{t}$  ša4 $^{t}$ [Gu-la]

14. 1 GADA *sal-ḥu* 1 GADA <sup>r</sup>gú-ḥal-ṣu<sup>l-</sup>
[1 TÚG]. <sup>r</sup>MURUB<sub>4</sub>. ÍB.LÁ (T:DU) 1 *ni-bi-ḥu šá* <sup>d</sup><sup>r</sup>IM

- 15. 1 GADA sal-ḥu 1et GÚ.UD.DU SÍG.ḤÉ.ME.DA 1et ku-si-tu4 šá dŠa-la
- L. 8. GADA before  $g\acute{u}$ - $\acute{p}al$ - $\acute{s}u$  looks like qa.
- L. 12. [Anunītu] is also possible.

Wov[en garments for the change for the lu]buštu ceremony for the month [of Araḥsamna, which Šamaš-šum-iddin<sup>?</sup>], the  $ašl\bar{a}ku$  [has delivered]. Month of Araḥsamna,  $9^{th}$  day,  $5^{th}$  year of Cyru[s, king of Babylon, king of Lands].

-----

2 linen tunics, [1 lin]en  $hull\bar{a}nu$ -cloaks, 1 linen scarf, 1 patin[nu-belt], 1  $n\bar{e}behu$ -belt, [2  $pa]r\bar{s}\bar{i}gu$ -headdresses, the  $lu < b\bar{a}r > m\bar{e}tu$  (and)  $lub\bar{a}r$   $kul\bar{u}lu$ -headbands for Šamaš

\_\_\_\_\_

2 linen tunics, 4 red *naḥlaptu*-cloaks, 1 multicoloured *naḥlaptu*-cloak, [1] red robe, 2 *paršīgu*-headdresses for Aya

[2] tunics, 6 red *nahlaptu*-cloaks, 2 red robes for the Ladies

-----

[1] linen tunic, 1 linen *ḫullānu*-cloak, 1 linen scarf, 1 red *patinnu*-belt, 1 red *nēbeḫu*-belt for Bunene

[x] linen tunics, 3 red *naḥlaptu*-cloaks, 1 multicoloured *naḥlaptu*-cloak, 1 blue-purple cloak, [x] blue-purple front veil, 1 blue-purple [robe], the blue-purple *erru* (and) blue-[purple] *lubār kulūlu*-headbands for [the Queen of Sippar]

1 linen tunic, 1 r[ed] *nahlaptu*-cloak, <sup>[1]</sup> robe for [Gula]

1 linen tunic, 1 linen scarf, [1] patinnu-belt, 1 nēbehu-belt for Adad

1 linen tunic, 1 red *nahlaptu*-cloak, 1 robe for Šala.

196. BM 61182 (82-9-18, 1158)

PLATE 45

 $6.0 \times 8.8$  cm

11.8.Cyr 8

- 1. dul-lu lúUŠ.BAR te-nu-ú
- 2. šá lu-bu-uš-tu<sub>4</sub> šá ITI.APIN

```
3. ^{\mathrm{md}}UTU-MU-MU SUM^{nu} ITI.APIN U<sub>4</sub>.11.KAM
              4. MU.8.KAM <sup>m</sup>Kur-raš LUGAL E<sup>ki</sup> LUGAL KUR.KUR
              5. 2 sa-al-hu šá <sup>d</sup>UTU 1 hu-<sup>r</sup>la<sup>¬</sup>-nu
              6. 1 gu-hal-şú GADA 1 TÚG.MURUB4.ÍB.LÁ
              7. 1 TÚG.{LÁ}.ÍB.LÁ lu-bar me-ṭu lu-bar ku-lu-lu
              8. 2 sib-ba-tu4 < š\acute{a} > {}^{d}UTU
              9. 2 sa-al-ḥu 4-ta <sup>túg</sup>na-aḥ-lap-tu<sub>4</sub> ta-bar-<sup>r</sup>ri<sup>1</sup>
10. 1 na-aḥ-lap-tu<sub>4</sub> bir-mu 2 par-ši-ḥu<sup>meš</sup>
            11. 1 ku-si-i-tu<sub>4</sub> ta-bar-ri šá <sup>d</sup>A-a
            12. 2 sa-al-hu 6-ta na-ah-lap-tu4 ta-bar-ri
            13. 2 ku-sa-a-tu<sub>4</sub> <šá <sup>d</sup>>DUMU.MÍ.MEŠ É-babbar-ra
            _____
            14. 1 sa-al-ḥu 1 ḫu-la-nu 1 g[u-ḥal-ṣu]
            15. [1] TÚG.MURUB4 ÍB.LÁ 1 TÚG.{LÁ}. 「ÍB¹.[LÁ]
                      <\check{s}\acute{a}>^{\rm d}Bu-ne-ne
Rev.
            17. 2 sa-al-hu 3-ta n[a-ah-lap-tu_4] < ta-bar-ri>
            18. 1 na-ah-lap-tu4 ta-kil-tu4
            19. 1 na-ah-lap-tu<sub>4</sub> bir-mu 1-ta ku-si-i-tu<sub>4</sub>
            20. lu-bar pa-ni 2 pár-ši-gu<sup>meš</sup> ta-kil-tu<sub>4</sub>
            21. 1 lu-bar ku-lu<sub>4</sub>-lu<sub>4</sub> e-ri šá ta-kil-tu<sub>4</sub>
            22. <šá> dGAŠAN Sip-parki
            23. 1 sa-al-hu 1 gu-hal-su 1 TÚG.MURUB<sub>4</sub>.[ÍB.LÁ]
            24. 1 ni-bi-hu < š\acute{a} > {}^{d}IM
            25. 1 sa-al-hu <1> na-ah-lap-tu<sub>4</sub> 1 ku-si-i-tu<sub>4</sub>
            26. \langle \check{s}\acute{a} \rangle d\check{\check{S}}a-la
            27. 2 sa-al-hu 1 na-ah-lap-tu<sub>4</sub>
            28. 1 ku-si-i-tu4 < š\acute{a} > {}^{d}Gu-la
```

The content of the heading and the order of the words are a little strange. Firstly, the responsibility for the preparation of this garment for the *lubuštu* ceremony rested on  $a šl\bar{a}ku$ , i.e. on the Šamaš-šum-iddin, mentioned in l. 3. Although the first certain attestation of his responsibility for the preparation of the garment from *dullu peṣû* lists is known already from the first year of Cambyses (CT 44, 73 = 67), BM 61182 shows that he acted in this role already a few months earlier.

The document gives the basis for a definite reading of sal-hu instead of šalhu.

L. 17. <ta-bar-ri> because there is no space on tablet, however, the synonym <na-ba-su> is also possible.

Note that the last three signs in 1. 19 are written over erasure.

The work of the weaver (for) the change for the *lubuštu* ceremony of the month of Araḥsamna delivered from Šamaš-šum-iddin. Month of Araḥsamna, 11<sup>th</sup> day, 8<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

2 tunics for Šamaš, 1 hullānu-cloak, 1 linen scarf, 1 patinnu-belt, 1 nēbehu-belt, the lubār mēţu (and) lubār kulūlu-headbands, 2 şibtu-garments for Šamaš -----

2 tunics, 4 red nahlaptu-cloaks, 1 multicoloured nahlaptu-cloak, 2 paršīguheaddresses, 1 red robe for Aya

2 tunics, 6 red nahlaptu-cloaks, 2 robes for the Daughters of the Ebabbar -----

1 tunic, 1 hullānu-cloak, 1 sc[arf], 1 patinnu-belt, 1 nēbehu-belt for Bunene

2 tunics, 3 <red> na[hlaptu]-cloaks, 1 blue-purple nahlaptu-cloak, 1 multicoloured naḥlaptu-cloak, 1 robe, the lubār pāni-veil, 2 blue-purple paršīgu-headdresses, 1 blue-purple lubār kulūlu (and) 1 < lubār> erru-headband <for> the Queen of Sippar

1 tunic, 1 scarf, 1 patinnu-belt, 1 nēbehu-belt <for> Adad

1 tunic, <1> nahlaptu-cloak, 1 robe <for> Šala

2 tunics, 1 nahlaptu-cloak, 1 robe <for> Gula.

# **197. CT 55, 850** = BM 57653

13.8.Dar 27

- 1. [mi-iḫ-ṣu te-nu-ú ša lu-bu]-「uš¹-tu4 šá <sup>d</sup>UTU šá U4.15.「KAM¹
- 2. [šá ITI.APIN MU.27.KA]M <sup>m</sup>Da-ri-mu-šú LUGAL a-na <sup>md</sup>UTU-AŠ-ÙRU
- 3. [SUM $^{na}$ ] ITI.APIN U $_4$ .13.KAM MU.27.KAM 4. [ $^{\mathrm{m}}Da$ -ri- $mu\check{s}$  LUGAL] TIN.TIR $^{\mathrm{ki}}$  LUGAL KUR.KUR
- 5. [1 GADA sal-hi 1] GADA hu-la-nu 1 gú-hal-șu 1 TÚG.MURUB<sub>4</sub>!.ÍB.LÁ
- 6. [1 TÚG.ÍB.LÁ a-n]a dUTU

- 7. [2 GADA sal]-hi <4> TÚG.GÚ.UD.DU SÍG.HÉ.ME.[DA]
- 8. [1 TÚG.GÚ.UD.D]U *bir-mu* 1 <sup>túg!</sup>*ku-si*!-*t*[*u*<sub>4</sub> *a-na* <sup>d</sup>*A-a*]

9. [1 GADA sal-hi 1 GADA hu-la]-nu 1 GADA gú-h[al-su]

Rest of obv. broken

1'. [1 GADA sal-hi 1 TÚG.GÚ.UD.DU SÍG.H]É. ME.DA Rev.  $[1 ku-si-tu_4 a-na dGu-la]$ 

2'. [1 GADA *sa-al*]-*la-a*[*h*<sup>?</sup>] 1 gú-ḥal-ṣu 1 TÚ[G.MURUB<sub>4</sub>.ÍB.LÁ]

3'. [	1 TÚG.ÍB.LÁ <i>a-na</i> ] <sup>d</sup> [IM <sup>1</sup>
4'. [ 5'. [	1 GADA <i>sal-ḫi</i> 1 TÚG].GÚ.UD.DU SÍG.ḪÉ.ME.DA 1 <i>ku-si-tu</i> 4 SÍG.Ḫ]É.「ME.DA <sup>1</sup> <i>a-na</i> <sup>d</sup> Ša-la
belongs to the ca	a-uşur (Bongenaar, <i>Ebabbar</i> , p. 343) or Šamaš-nādin-aḥi. Because the text ategory of the <i>mihşu tenû</i> list, the expected title is < <i>ašlāku/ēpīšanu</i> >, contra <i>aru</i> or <i>lamutānu/ēpīšanu ša išpari</i> >.
[Woven garmeday [of Arahsa of Arahsamna]	ents for the change for the <i>lubu</i> ] <i>štu</i> ceremony of Šamaš for the 15 <sup>th</sup> mmna, 27 <sup>th</sup> yea]r of Darius, king, [given to] Šamaš-apla-uṣur. Month 13 <sup>th</sup> day, 27 <sup>th</sup> year [of Darius, king] of Babylon, king of Lands.
[1 linen tunic, Šamaš	1] linen <i>ḫullānu</i> -cloak, 1 scarf, 1 <i>patinnu</i> -belt, [1 <i>nēbeḥu</i> -belt fo]r
[2 linen tun]io 1 rob[e for Aya	cs, <4> red <i>naḫlaptu</i> -cloaks, [1] multicoloured <i>na[ḫlap]tu</i> cloak, a]
[1 linen tunic, Rest of obv. is	1 linen <i>ḫullā</i> ] <i>nu-</i> cloak, 1 linen sc[arf] broken
Rev.	
[1 linen tunic,	1] re[d <i>naḥlaptu-</i> cloak, 1 robe for Gula]
[1 linen tun]ic,	1 scarf, 1 <i>pa</i> [ <i>tinnu</i> -belt, 1 <i>nēbeḥu</i> -belt for] Adad
[1 linen tunic,	1] red <i>naḥlaptu</i> cloak, [1 r]ed [robe] for Šala.
<b>198. BM 6261</b> 7.4 × 5. <i>3</i> cm	<b>3</b> (82-9-18, 25882)
	10+x.8.[KN x]
1. <i>n</i> 2. <sup>li</sup>	ni- <sup>r</sup> iḫ¹-ṣu te-nu- <sup>r</sup> ú šá¹ [lu-bu-uš-tu4 šá PN] ¹TÚG.BABBAR SUM <sup>na</sup> ITI.APIN U4.10+[x².KAM MU.x.KAM KN]
	e GADA sal-ḥi 1 GADA ḥu-ul-la-nu 1 [GADA gú-ḥal-ṣu] ni-bi-ḥu pa-tin-nu TÚG.ḤI.A ku-lu-lu [TÚG.ḤI.A me-ṭu a-na dUTU]
5. 2 6. <sup>r</sup>	CGADA sal-ḥi 4 na-ḥa[l]- <lap>-tu<sub>4</sub> SÍG.ḤÉ.ME.ʿDAʾ 1 naʾ-[ḥal-la]p-tu<sub>4</sub> bir-mu ʿ1ʾ ku-si-tu<sub>4</sub> a-n[a <sup>d</sup>A-a]</lap>
7. [ 8.	

```
7. [1 GADA sal-hi 1 GADA hu]-[la]-nu 1 GADA [gú]-[hal-su]
                    [a-na^{d}Bu-ne]^{-1}
Rev.
            1'. [2 GADA sal-hi 3 na-hal-lap-tu<sub>4</sub> SÍG.H]É.ME.DA
            2'. [1^{et} na-hal-lap-tu<sub>4</sub> ta-kil-t]u<sub>4</sub> 1^{et} na-hal-lap-[tu<sub>4</sub>]
            3'. [bir-mu lu-bar pa-ni pa]r-ši-gu 「SÍG¹ (ras.) 4'. [1 a-a-ri pa-ni 1 k]u-si-tu<sub>4</sub> a-na ^{\rm d}GAŠAN Sip-par ^{\rm ki}
            -----
            5'. 「2 GADA¬ sal-hi 1^{et} na-hal-lap-tu_4 1^{et} ku-si-tu_4 6'. a-na ^{d}ME.ME
            7'. 1 GADA sal-hi 1 GADA gú-hal-su 1 pa-tin-nu
            8'. 1 ni-bi-hu a-na <sup>d</sup>IM
            9'. 1 GADA sal-hi 1<sup>et</sup> na-hal-lap-tu<sub>4</sub>
           10'. 1^{et} ku-si-tu<sub>4</sub> a-na \lceil d \rceil \lceil \check{S}a-la
Woven garments for the change for [the lubuštu ceremony, which PN], the ašlāku
has given. Month of Arahsamna, 10+[x day, n<sup>th</sup> year of KN, king of ....]
2 linen tunics, 1 linen hullānu-cloak, 1 [linen scarf], <1> nēbehu-belt, <1> patinnu-
belt, the lubār kulūlu [(and) lubār mēţu]-headbands [for Šamaš]
2 linen tunics, 4 red nahlaptu-cloaks, 1 multicoloured na[hlap]tu cloak, 1 robe fo[r
[2 linen tunics, x na]hlaptu-cloaks, 2 robes for the Daughters of the Ebabbar
[1 linen tunic, 1 linen hu]llānu-cloak, 1 linen sc[arf for Bune]ne
[2 linen tunics, 3 r]ed [nahlaptu]-cloaks, [1 blue-purp]le [nahlaptu-cloak], 1 [multi-
coloured] naḥlaptu-cloak, [1 lubār pāni-veil, 1 pa]ršīgu-headdress, 1 (with) ayar
pāni, 1 r]obe for the Queen of Sippar
[2 linen tunics, 1 nahlaptu-cloak, 1 robe for Gula
1 linen tunic, 1 linen scarf, 1 patinnu-belt, 1 nēbehu-belt for Adad
1 linen tunic, 1 naḥlaptu-cloak, 1 robe for [Šala].
199. BM 73720 (82-9-18, 13731)
5.3 \times 3.1 cm
                        [x].8.[KN x]
             1'. ^{\text{lú}}x<sup>1</sup> [x]-^{\text{r}}x<sup>1</sup>-tu_4 [....]
             2'. SUM<sup>in</sup> ITI. [APIN] [....]
```

D1	3'. 2 [GADA] <i>sal-ḫu</i> [] 4'. [x] GADA <sup>r</sup> x <sup>1</sup> []				
Rest lost Rev.	1'. [1 GADA <i>sal</i> ]- <sup>[</sup> hu <sup>]</sup> []				
	2'. [x] GADA sal-ḫu <sup>t</sup> [ <sup>úg</sup> ] 3'. 1 <sup>et</sup> ku-si-tu <sub>4</sub> SÍG.ḪÉ.ME.DA []				
	4'. 「1¹ GADA <i>sal-ḫu</i> 1 [] 5'. 1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ SÍG.ḤÉ.ME.DA				
	6'. 1 「GADA sal¬-[ḫu]				
[] the [	] was given. Month of Araḫsamna []				
2 [linen] to	unics [], 1 linen []				
[x] linen to	un]ic []				
[x] linen to	un]ic [], 1 red robe []				
1 linen tunic, 1 [], 1 red <i>patinnu</i> -belt []					
1 linen tur	 l[ic]				

 $8.2 \times 6.3$  cm

**200. BM 78893** (88-5-12, 79)

4.[x].Nbn 4

# 4. Garments for the *lubuštu* ceremony in cycle A (Nisannu, Ayaru or Araḫsamna)

	1. [ <i>mi-iḫ-ṣu</i> ] <i>te-nu-ú šá a-na</i> <sup>md</sup> UTU-NUMUN-GÁL <sup>ši</sup> 2. [ <sup>lú</sup> TÚG.BABBAR SU]M <sup>na</sup> ITI.「x <sup>1</sup> U <sub>4</sub> .4.「KAM <sup>1</sup> MU.4.KAM <sup>md</sup> AG-I LUGAL E <sup>ki</sup>
	3. [2 GADA] sal-ḫi 1 GADA ḫu-ul-la-nu 1 GADA gú-ḥal-ṣu 4. 「pa-tin¹-nu 1 [ni]-bi-ʿḥu¹ [TÚG].ḤI.A me-ṭu TÚG ḤI.A ku-lu-lu šá <sup>d</sup> UTU
	5. 「2 GADA sal-ḫi 4 na-aḫ-lap-tu₄ ¹ 1 na-ḫal-lap-tu₄ bir-mu 6. [ 1 ku-si]-tu₄ 「x x ¹ d ſ A-a ¹
	are eroded so heavily that the identification of signs was impossible to me, although it certain that the garment for Bunene and probably for the <i>mārāt Ebabbar</i> were here.
Edge Rev.	11. 2 「GADA sal-ḫi¹ [5 na-aḫ-lap-tu₄ 1] TÚG.ḤI.A pa-ni 12. [1] TÚG.ḤI.A ku-lu-lu 2 par-š[i-gu <sup>meš</sup> 1] a-a-ri pa-ni 13. 1 <sup>et</sup> ku-si- <sup>t</sup> tu₄¹ a-na [ <sup>d</sup> GAŠAN UD.KIB].「NUN <sup>ki</sup> ¹
	14. 2 GADA sal-ḥi 1 na-aḥ-lap-tu <sub>4</sub> 1 ku-si-tu <sub>4</sub> a-na <sup>d</sup> Gu-[la]
	15. 1 GADA sal-ḥi 1 GADA gú-ḥal-ṣu 1 <sup>en</sup> pa-tin-nu 16. 1 <sup>en</sup> ni-bi-ḥu a-na <sup>d</sup> IM
	17. 1 GADA sal-ḥi 1 na-aḥ-lap-tu <sub>4</sub> 1 <sup>et</sup> ku-si-tu <sub>4</sub> 18. a-na <sup>d</sup> Ša-la
[Woven to Šama of Baby:	garments] for the change (for the <i>lubuštu</i> ceremony), which [were given] š-zēr-ušabši, [the <i>ašlāku</i> . N <sup>th</sup> ] month, 4 <sup>th</sup> day, 4 <sup>th</sup> year of Nabonidus, king lon
	] tunics, 1 linen <i>ḫullānu</i> -cloak, 1 linen scarf, <1> <i>patinnu</i> -belt, 1 <i>nēbeḫu-lubār mēṭu</i> (and) <i>lubār kulūlu</i> -headbands for Šamaš
	tunics, 4 <red> nahlaptu-cloaks, 1 multicoloured nahlaptu-cloak, b]be [for] Aya</red>

2 linen tunics, [5 naḥlaptu-cloaks, 1] lubār pāni-veil, [the lubār kulūlu-headband, 2 parš[īgu]-headdresses (including) 1] with front rosette, 1 robe for [the Queen of Sip]par 2 linen tunics, 1 nahlaptu-cloak, 1 robe for Gu[la] 1 linen tunic, 1 linen scarf, 1 patinnu-belt, 1 nēbehu-belt for Adad 1 linen tunic, 1 nahlaptu-cloak, 1 robe for Šala. **201. BM 54909+BM 73078** (82-5-22, 1239+82-9-18, 13088)  $6.0 \times 6.0$  cm [x.x].Nbn 4 1. [mi- $i\dot{h}$ - $\dot{s}\acute{u}$  te-nu- $\acute{u}$   $\dot{s}\acute{a}$  lu-bu- $u\dot{s}$ -tu4]  $\dot{s}\acute{a}$  a-na  $^{md}$ UTU-NUMUN-GÁL $^{\dot{s}[i]}$ 2. [lúTÚG.BABBAR SUM<sup>na</sup> ITI.x U<sub>4</sub>.x].KAM MU.4.KAM <sup>md</sup>AG-I [LUGAL E<sup>ki</sup>] 3. [2 GADA sal-ḥi 1 GADA ḥu-u]l-la-nu 1 gú-ḥal-ṣu 1 'TÚG'.[ÍB.LÁ] 4. [1 pa-tin-nu TÚG.HI.A me-tu TÚG].HI.A ku-lu-lu a-na <sup>d</sup>[UTU] \_\_\_\_\_ 5. [2 GADA sal-hi 4 n]a-hal-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA<sup>!</sup>(T: DU)  $1 \lceil na \rceil - [hal - lap - tu_4]$ 6.  $[bir-mu\ 1\ ku-si-t]u_4\ a-na\ ^dA-a$ 7. [1 GADA sal-hi 1 GAD]A 「hu-ul¬-la-¬nu¬ 1 GADA gú-hal-ṣu 1 T[ÚG<sup>?</sup> ....]  $[a-n]a^{d}Bu-ne-ne$ 9. [2 GADA sal-hi 6-ta na-hal]-lap-tu4 2-ta ku-si-tu4 a-na [d DUMU.MÍ.MEŠ É-babbar-ra] \_\_\_\_\_

Rest lost

a-na <sup>d</sup>「DN¹

Rev. is preserved to badly to be transliterated (only a few partially preserved signs in 7 lines).

10. [x GADA sal-hi x na-hal]-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA<sup>!</sup> (T:DU)

11. [....] 「ZA.GÌN.KUR.RA¹ [x x] 「x x ni<sup>?¹</sup>

[Woven garments for the change for the <i>lubuštu</i> ceremony], which [were given] to Šamaš-zēr-ušabši, [the <i>ašlāku</i> . N <sup>th</sup> month, n <sup>th</sup> day], 4 <sup>th</sup> year of Nabonidus, [king of Babylon].
[2 linen tunics, 1 linen <i>hul</i> ] <i>lānu</i> -cloak, 1 scarf, 1 <i>nēb</i> [ <i>eḥu</i> ]-belt, [1 <i>patinnu</i> -belt, the <i>lubār mēṭu</i> (and) <i>lub</i> ] <i>ār kulūlu</i> -headbands for [Šamaš]
[2 linen tunics, 4] red <i>naḥlaptu</i> -cloaks, 1 [multicoloured] <i>naḥ[laptu</i> -cloak, 1 rob]e for Aya
[1 linen tunic, 1 lin]en <i>ḫullānu</i> -cloak, 1 linen scarf, 1 [ f]or Bunene
[2 linen tunics, 6 <i>naḥla</i> ] <i>ptu</i> -cloaks, 2 robes for [the Daughters of the Ebabbar]
[x linen tunic(s), x] red [nah]laptu- cloak(s) for [] [] blue-purple [].
<b>202. BM 61783</b> (82-9-18, 1752) 6.3 × 5.0 cm
3.[x].Nbn 8
<ol> <li>[mi-iḥ-ṣú te-nu-ú šá lu-bu-uš-tu<sub>4</sub>] šá a-na <sup>md</sup>UTU-NUMUN-GÁL<sup>ši</sup></li> <li>[l<sup>lú</sup>TÚG.BABBAR SUM<sup>na</sup> ITI.x U] 4.3.KAM MU.8.KAM <sup>md</sup>AG-I LUGAL <sup>r</sup>E<sup>rli</sup></li> </ol>
3. [2 GADA sal-ḫi 1 GADA ḫ]u-ul-la-nu 1 GADA gú-ḫal-ṣu 4. [1 pa-tin-nu] 1 ni-bi-ḫu TÚG.ḤI.A ku-lu-lu TÚG.ḤI.A me-ṭu šá <sup>d</sup> UTU
5. [1 GADA sal]- ${}^{\Gamma}hi^{1}$ 5 na-hal-lap-tu <sub>4</sub> 1 <sup>et</sup> ku-si-tu <sub>4</sub> 6. a-na ${}^{d}A$ -a
7. [1] GADA sal-ḫi 1 GADA ḫu-ul-la-nu [1 GADA gú-ḫal-ṣu] 8. 「1¹ [TÚG].「ÍB².LÁ x x x¹ [a-na <sup>d</sup> Bunene]
Lower edge is broken, however, nothing is most probably missing.
Rev. 9. 2 [GADA sal-ḫi x na-ḥal-lap-t]u <sub>4</sub> 10. 2 [ku-si-tu <sub>4</sub> SÍG.ḤÉ.ME.DA a-na <sup>d</sup> ]DUMU.MÍ.[MEŠ É-babbar-ra 11. 「1 GADA sal¬-ḥi 1 GADA 「gú-ḥal-ṣu¬ 1 「túg²¬[ni-bi-ḥu] 12. 1 [túg pa]-tin-nu a-na <sup>d</sup> IM

13. [1 GADA sal-ḫi] 1 <sup>en</sup> na-ḫal-lap-tu <sub>4</sub> [SÍG.ḤÉ.ME.DA] 14. [1 ku-si-tu <sub>4</sub> ] a-na <sup>d</sup> Ša-la
15. [] 「GÍN KÙ.BABBAR <sup>1</sup> ina ka-li-šú šá MU.8.KAM 16. []「x <sup>1</sup> șir <sup>?</sup> -iá
Rev. 9. Between <i>salhi</i> and <i>nahlaptu</i> there is some space to be filled, but I have no good proposal.
Woven garments for the change for the <i>lubuštu</i> ceremony], which [were given] to samaš-zēr-ušabši, [the <i>ašlāku</i> . N <sup>th</sup> month], 3 <sup>rd</sup> day, 8 <sup>th</sup> year of Nabonidus, king of Babylon.
2 linen tunics, 1 linen $h$ ] $ull\bar{a}nu$ -cloak, 1 linen scarf, [1 $patinnu$ -belt], 1 $n\bar{e}behu$ - belt, the $lub\bar{a}r$ $kul\bar{u}lu$ (and) $lub\bar{a}r$ $m\bar{e}tu$ -headbands for Šamaš
1 linen tun]ic, 5 <i>naḥlaptu-</i> cloaks, 1 robe for Aya
1] linen tunic, 1 linen <i>ḫullānu</i> -cloak, [1 linen scarf, 1 <sup>r</sup> nēbeḫu¹-belt [ for Bunene]
2 [linen tunics, $x$ $nahlapt$ ] $u$ -cloaks, 2 [red robes for] the Daughters of the Ebabbar]
linen tunic, 1 linen scarf, 1 $[n\bar{e}behu]^2$ -belt, 1 $[pa]tinnu$ -belt for Adad
1 linen tunic], 1 [red] <i>naḥlaptu-</i> cloak, [1 robe] for Šala
] shekels of silver in whole 8 <sup>th</sup> year of [].
<b>203. BM 73134</b> (82-9-18, 13144) 6.5 × 4.5 cm
10.[x.KN] 5
1. $[mi]$ - $ih$ - $^{r}$ su $^{1}$ $te$ - $nu$ - $u$ šá $^{r}$ a- $na$ 1 $^{m}$ r $^{d}$ 1 $[DN$ ] 2. $[SU]M^{na}$ $[ITI.x U_4].10.KAM MU.5.KAM [KN LUGAL B\bar{a}bili^{ki}]$
3. 2 GADA s[al-ḥi 1] GADA hu-ul- <sup>r</sup> la <sup>1</sup> -nu <sup>r</sup> 1 GADA gú <sup>1</sup> -[hal-ṣu] 4. [1 pa-tin-ni] <sup>r</sup> 1¹ ni-bi-hu TÚG.ḤI.A ku- <sup>r</sup> lu-lu¹ T[ÚG.ḤI.A me-ṭu šá <sup>d</sup> UTU]
5. [2 GADA <i>sal-ḥi</i> ] 「4 <sup>¬</sup> <i>na-ḥal-l</i> [ <i>ap-t</i> ]u <sub>4</sub> SÍG.「ḤÉ.ME.DA <sup>?</sup> <sup>¬</sup> 6. [1 <i>ku-s</i> ]i-tì <i>a-na</i> <sup>d</sup> A-a
7. [1 GADA sal-ḫi] 1 GADA ḫu-ul-la-nu 1 GADA g[ú-ḫal-ṣu]

8. [1 ni-bi]-hu 1 pa-tin-ni a-na <sup>d</sup>Bu-[ne-ne] 9. [2 sal-hi] 6 na-hal<sup>1</sup>(T: an)-lap-tu<sub>4</sub> 2 [ku-si-tu<sub>4</sub> SÍG.ḤÉ.ME.DA] 10. [a-n]a <sup>d</sup>DUMU.MÍ. MEй É-babbar-ra Edge \_\_\_\_\_\_ 11. [2 GADA sa]l-hi 3 na-hal-lap-tu<sub>4</sub> SÍG. [HÉ]. [ME.DA] Rev. 12. [1] na-hal-lap- $tu_4$  ta-kil- $tu_4$  x (er) 13. [1 na]-ḥal-lap-tu<sub>4</sub> [bir]-mu TÚG.ḤI.A pa-ni 2 par-ši-g[u<sup>meš</sup> TÚG.ḤI.A] 14. [k]u-lu-lu  $1^{en} \lceil e^{!} \rceil$ -ri  $1^{en} \lceil x \rceil$  (er.) ku-si-tu<sub>4</sub>  $< \check{s}\acute{a} > {}^{d}GA\check{S}AN$ Sip-par<sup>[ki]</sup> 15. 1 GADA sal-ḥi 1[et] na-ḥal-lap-tu<sub>4</sub> 1et ku-si-tu<sub>4</sub> 16. a-na <sup>d</sup>Gu-la 17. 1 GADA sal-ḥi 1 [GADA] gú-ḥal-ṣu <1> ni-bi-ḥu <1> pa-tin-[nu] 18. *a-na* <sup>d</sup> [IM] 1 GADA *sal-ḥi* 1 *na-ḥal-la*[*p-tu*<sub>4</sub>] 19. 1 et ku-si-tu<sub>4</sub> *a-na* d*ša-la* 

Because before the conquest of Babylonia by the Persians in year 539 B.C. the *patinnu* was written mostly syllabically, and later in the Achaemenid period mostly ideographically, this text should be dated to the earlier period, probably to the time of Nabonidus' reign. Note that this time Aya received only *sallju*, *naljlaptu* and *kusītu*, but no *paršīgu*.

Woven garments for the change <for the *lubuštu* ceremony>, which were given to [PN, the .... Month x],  $10^{th}$  day,  $5^{th}$  year of [KN, king of Babylon].

2 linen *s*[*alḫu*]-tunics, [1] linen *ḫullānu*-cloak, 1 linen sc[arf, 1 *patinnu*]-belt, 1 *nēbeḥu*-belt, the *lubār kulūlu* (and) *lub*[*ār mēṭu*]-headbands for Šamaš]

[2 linen tunics], 4 red *naḥl*[aptu]-cloaks, [1 ro]be for Aya

[1 linen tunic], 1 linen *ḫullānu-*cloak, 1 linen s[carf], 1 [*nēbe*]*ḫu-*belt, 1 *patinnu-*belt for Bu[nene]

[2 linen tunics], 6 naḥlaptu-cloaks, 2 [red robes f]or the Daughters of the Ebabbar

[2 linen tun]ics, 3 re[d] *naḥlaptu*-cloaks, [1] blue-purple *naḥlaptu*-cloak, [1 multi] coloured [*na*]*ḥlaptu*-cloak, the *lubār pāni*-veil, 2 *paršīgu*-headdresses, [the *lubār*] *kulūlu*-headband, 1 *<lubār> erru*-headband, 1 robe *<*for> the Queen of Sippar

1 linen tunic, 1 *naḥlaptu*-cloak, 1 robe for Gula

· ·

1 linen tunic, 1 [linen] scarf, <1>  $n\bar{e}behu$ -belt, <1> patin[nu]-belt for Adad; 1 linen tunic, 1 nahla[ptu]-cloak, 1 robe for Šala.

# **204. BM 63661** (82-9-18, 3624)

 $7.3 \times 4.2 \text{ cm}$ 

	_			_
4	ĺν	K	N	v

1'. [] 「x¹ U <sub>4</sub> .4.KAM <sup>m</sup> 「x¹ []
2'. [2 GADA sal-ḫu 1 GADA ḫu-ul-la-nu 1 GADA] gú-ḫal-ṣu 1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 3'. [1 TÚG.ÍB.LÁ TÚG.ḤI.A me-ṭu T]ÚG.ḤI.A ku-lu-lu 2 ṣib-t[u <sub>4</sub> ] <šá> <sup>d</sup> UTU
4'. [ $-t$ ] $u_4$ $na$ - $ba$ - $su$ 5'. [ TÚG.BAR].SI.MEŠ 1 $^{et}$ $ku$ - $si$ - $tu_4$ $< š\acute{a} > {}^{d}A$ - $a$
6'. [ 2]- <sup>r</sup> ta <sup>1</sup> ku-sa-tú <šá> <sup>d</sup> DUMU.MÍ. <meš> É-babbar-ra</meš>
7'. [ $\$$ ] $u$ 1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 TÚG. $\$$ NÍG $\$$ .ÍB.LÁ 7a'. $\{<\check{s}\acute{a}>\}$ $^d$ $\$$ AR
8'. [ MURUB <sub>4</sub> ].ÍB.LÁ 1 TÚG.{NÍG}.ÍB.LÁ 9'. [<šá> dIM]
10'. [ ku-si]-tu <sub>4</sub> <šá> <sup>d</sup> Ša-la

Rev. damaged completely except  ${}^{\Gamma}E^{1^{ki}}$  or  $[TI]R^{ki}$  written over edge. Note the lack of garments for the Queen of Sippar and Anunītu in this text.

[....], 4<sup>th</sup> day, [....]

[2 linen tunics, 1 linen hullānu-cloak, 1 linen] scarf, 1 patinnu-belt, [1 nēbehu-belt, the *lubār mēṭu* (and) *lu]bār kulūlu*-headbands (and) 2 *ṣibt*[*u*]-garments for Šamaš

[x tunics, x] red [naḥlapt]u-cloaks [...,1 parš]īgu, 1 robe <for> Aya -----

[2 linen tunics, x nahlaptu-cloaks, 2] robes <for> the Daughters of the Ebabbar

-----

[x linen tunics, 1 linen hullānu-cloak, 1 scar]f, 1 patinnu-belt, 1 nēbehu-belt [for]

[1 linen tunic, 1 linen scarf, 1 patin]nu-belt, 1 nēbehu!-belt [for Adad]

[1 linen tunic, 1 nahlaptu-cloak, 1 rob]e for Šala.

# **205. BM 59491** (82-7-14, 3901)

 $4.6 \times 4.6 \text{ cm}$ 

1'. [2 GADA sa]l-<sup>r</sup>hu<sup>1</sup> 1 GADA hu-la-[nu 1 GADA gú-hal-şu 1 *ni-bi-hu*]

2'. [1 TÚG].MURUB.ÍB.LÁ 1 lu-bar ku-[lu-lu 1 lu-bar me-ṭu šá dUTU1

3'. [2] 「GADA<sup>1</sup> sal-hu 4-ta TÚG.GÚ.UD.「DU<sup>1</sup> [SÍG.HÉ.ME.DA]

4'.  $[1^{et}]$  ku-si-tu<sub>4</sub> šá <sup>d</sup>[A-a]

5'. <sup>[2]</sup> GADA *sal-hu* 6-*ta* TÚG.GÚ.UD.[DU]

6'. 2-ta ku-si-tu<sub>4</sub> <sup>meš</sup> šá <sup>rd</sup> [DUMU.MÍ.MEŠ *É-babbar-ra*]

7'. 1 GADA sal-hu 1 GADA hu-la-nu 1 n[i-bi-hu]

8'. 1 GADA gú-hal-şu šá <sup>d</sup>B[u-ne-ne]

9'. 1 GADA sal-hu 3-ta TÚG.GÚ.UD.D[U SÍG.HÉ.ME.DA]

10'. 1 TÚG.GÚ.UD.DU SÍG.ZA.GÍN.KUR.RA

11'. 1 TÚG.ḤI.A pa-ni SÍG.ZA.GÍN.KUR.RA 1 k[u-si-tu4] Rev. šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

13'. 2 GADA sal-hu 1et TÚG.GÚ.UD.DU SÍG.H[É.ME.DA]

14'.  $[1^e]^t ku$ -si-tu<sub>4</sub> SÍG.HÉ.ME.D[A šá <sup>d</sup>Gu-la]

15'. [1 GADA sal]-<sup>r</sup>hu<sup>1</sup> 1 TÚG.ÍB.LÁ 1 TÚG.M[URUB<sub>4</sub>.ÍB.LÁ] šá <sup>d</sup>[IM] 16'.

17'. [1 GADA sal-hu] 1et TÚG.GÚ.UD.D[U

18'. [1<sup>et</sup> ku]-si-tu<sub>4</sub> SÍG. [HÉ]. [ME.DA šá <sup>d</sup>Ša-la]

L. 15'. We expect here also the guhaṣṣu-scarf, but it seems that there is not enough space in the tablet.

[2 linen tu]nics, 1 linen hullā[nu-cloak, 1 linen scarf, 1 nēbehu-belt,] 1 patinnubelt, 1 lubār ku[lūlu (and) 1 lubār mētu-headbands for Šamaš]

\_\_\_\_\_

[2] linen tunics, 4 [red] nahlaptu-cloaks, [1] robe for [Aya] \_\_\_\_\_

2 linen tunics, 6 nahlaptu-cloaks, 2 robes for [the Daughters of the Ebabbar]

1 linen tunic, 1 linen *hullānu*-cloak, 1 *n*[*ēbeḥu*]-belt, 1 linen scarf for B[unene]

1 linen tunic, 3 [red] nahlaptu-cloaks, 1 blue-purple nahlaptu-cloak, 1 blue-purple *lubār pāni*-veil, 1 r[obe] for the Queen of Sippar

```
2 linen tunics, 1 re[d] naḥlaptu-cloak, <sup>1</sup>1 red robe [for Gula]
[1 linen tun]ic, 1 nēbeḥu-belt, 1 pati[nnu]-belt for [Adad]
[1 linen tunic], 1 naḥlaptu-cloak, [1 r]ed [ro]be [for Šala].
206. BM 68200+BM 70749 (82-9-18, 8198+ 10750)
7.0 \times 6.2 cm
          1'. [....] <sup>r</sup>na x x<sup>1</sup> [....]
          2'. [2 GADA sal-hu 1 GADA] 「hu-la-nu 1 1 GADA gú-h[al-su]
                    TÚG.ḤI.A]<sup>r</sup>ku-lu-lu<sup>1</sup> TÚG.ḤI.A me-ṭu
          3'. [
                SÍG.[.... šá <sup>d</sup>UTU]
           -
          4'. [2 GADA sal-hu 4 TÚG]. GÚ.UD.DU<sup>?</sup> SÍG.HÉ.ME.DA 1<sup>et</sup>
                [TÚG.GÚ.UD.DU]
          5'. [SÍG.ZA.GÌN.<KUR>.RA 1 ku-si]-tu4 a-na dA-a
          -----
          6'. [2 GADA sal]-hu 6-ta 'TÚG'.GÚ.UD.DU SÍG.HÉ.ME.DA
          7'. [2 ku-si-tu<sub>4</sub> SÍG.Ḥ]É.ME.DA a-na <sup>d</sup>[DUMU.MÍ.<MEŠ>
                É-babbar¹-[ra]
          8'. [1 GA]DA sal-ḥu 1 GADA ḥu-la-nu 1 [GADA gú-ḥal-ṣu]
          9'. \lceil 1^{et_{\gamma}} ni-bi-hu a-na \lceil d_{\gamma} \mid Bu-ne-ne]
          10'. [2 GA]DA sal-hu 3-ta TÚG.G[Ú.UD.DU SÍG.HÉ.ME.DA]
         11'. [1 TÚG. G]Ú.UD.DU SÍG.ZA.GÌ[N.<KUR>.RA
         12'. [.... BAR]. 「SI 1 ku-s[i-tu<sub>4</sub> a-na dGAŠAN Sip-par<sup>ki</sup>]
         13'. [1 GADA] sal-ḫu 1<sup>et</sup> TÚG.GÚ.UD.DU [1<sup>et</sup> ku-si-tu<sub>4</sub> a-na
Rev.
                <sup>d</sup>Gu-la1
         14'. [1 GADA sal]-hu 1 GADA gú-hal-[ṣu TÚG.MURUB4.Í[B.LÁ
               a-na <sup>d</sup>IM]
         15'. [1 GADA sal]-hu 1[^{en}] 'TÚG'.[GÚ].UD.DU 1^{et} ku-si-tu4
                S[ÍG.ḤÉ.ME.DA a-na <sup>d</sup>Ša-la]
         _____
L. 14'. We expect here the nēbehu instead of the patinnu.
[2 linen tunics, 1 linen] hullānu-cloak, 1 linen sca[rf, ...., the lubār] kulūlu (and)
lubār mēṭu-headbands [.... for Šamaš]
```

[2 linen tunics, 4] red nahlaptu-cloaks, 1 [blue-purple nahlaptu-cloak, 1 ro]be for Aya [2 linen tu]nics, 6 red nahlaptu-cloaks, [2] r[ed robes] for the Daughters of the Ebabbar [1 lin]en tunic, 1 linen *hullānu*-cloak, 1 [linen scarf], 1 *nēbehu*-belt for [Bunene] [2 lin]en tunics, 3 [red] nah[laptu]-cloaks, 1 blu[e-purple nah]laptu-cloak, [... paršī]gu-headdress, 1 ro[be for the Queen of Sippar] [1 linen] tunic, 1 naḥlaptu-cloak, [1 robe for Gula] [1 linen tun]ic, 1 linen sca[rf], 1 patin[nu]-belt [for Adad] [1 linen tun]ic, 1 nahlaptu-cloak, 1 r[ed] robe [for Šala]. **207. BM 68317** (82-9-18, 8315) PLATE 46  $5.2 \times 5.5$  cm 1'. [....] 「hu¬-la-nu 2'. [.... H]É.ME.DA 1 TÚG.Í[B/MU[RUB<sub>4</sub>] 3'. [....] TÚG.ḤI.A me-ṭu TÚG.[ḤI.A ku-lu-lu] 4'. [*a-na*] <sup>d</sup>UTU 5'. [2 GADA sal-hu 5]-ta TÚG.GÚ.UD.DU.A SÍ[G.HÉ.ME.DA] 6'. [1 TÚG.GÚ].UD.DU.A bir-mu 2 TÚG.BAR.S[I.MEŠ] 7'.  $[1 \ ku-si]-tu_4 \ a-na^{d}A-a$ 8'. [2 GADA sal-hu] <sup>[6]</sup>-ta TÚG.GÚ.UD.DU.A SÍ[G.HÉ.ME.DA] 9'. [2 ku-si-tu<sub>4</sub>] 「SÍG.HÉ.ME¹.DA a-na <sup><d></sup>DUMU.[MÍ.MEŠ É-babbar-ral 10'. [1 GADA sal-ḥu 1 GADA] ḥu-la-nu 1 GADA gú-ḥa[l-ṣu] Rev. 11'. [1 TÚG.ÍB.LÁ 1 T]ÚG.MURUB<sub>4</sub>.ÍB.LÁ SÍG.HÉ.ME.[DA a-na <sup>d</sup>ḤAR] 12'. [x GADA sal-h]u 3-ta TÚG.GÚ.UD.DU.A SÍG.HÉ.ME.[DA] 13'. [1 TÚG.GÚ.U]D.DU.A SÍG.ZA.GÌN.KUR.RA 1 [....] 14'. [.... SÍ]G.ZA.GÌN.KUR.RA 2 TÚG.B[AR.SI.MEŠ] 15. [1 ku-si-tu<sub>4</sub> SÍG.ZA.GÌN.K]UR.RA a-na <sup>d</sup>GAŠAN UD.[KIB.NUN<sup>ki</sup>] 16'. [1 GADA sal-hu 1 TÚG.GÚ.UD.D]U.A SÍG.HÉ.<ME>.D[A] 17'.  $[1 ku-si-tu_4 a-na {}^{d}G]u-la$ 18'. [....] <sup>[</sup>x x<sup>]</sup> [....] Rest lost

[...., 1] hullānu-cloak, [x ....] re[d ....], 1 nē[beḥu (or: pa[tinnu]-belt [...., the lubār mēṭu (and) lub[ār kulūlu-headbands for] Šamaš [2 linen tunics, 5 re]d nahlaptu-cloaks, [1 blue-purple nahla]ptu-cloak, 2 paršīg[u]headdresses, [1 ro]be for Aya [2 linen tunics], 6 r[ed] nahlaptu-cloaks, [2] red [robes] for the Daug[hters of the Ebabbarl [1 linen tunic, 1 linen] hullānu-cloak, 1 linen sca[rf], 1 [nēbehu]-belt, 1 red patin*nu*-belt [for Bunene] [x linen tunic(s)], 3 red nahlaptu-cloaks, [1] blue-purple [nahla]ptu-cloak, 1 [multicoloured<sup>?</sup> nahlaptu-cloak<sup>?</sup>], [x] blue-purple [....], 2 pa[ršīgu]-headdresses, [1 blu]e-purple [robe] for the Queen of Sip[par] [1 linen tunic, 1] red [nahlap]tu-cloak, [1 robe for G]ula]. **208. BM 68144** (82-9-18, 8142) PLATE 47  $4.6 \times 5.2$  cm [x].8.[KN] 21'.  $[x] [x x^{7} [...]$ 2'. [1] pa-ti-in [....] 3'. TÚG.ÍB.LÁ TÚG.ḤI.[A me-tu] 4'. TÚG.ḤI.A ku-lu<sub>4</sub>-lu<sub>4</sub> [šá <sup>d</sup>UTU] 5'. 2 GADA sal-hu TÚG.BA[R.SI] 6'. 4-ta TÚG.GÚ.UD.DU.[MEŠ SÍG.ḤÉ.ME.DA] 7'. 1<sup>et</sup> TÚG.GÚ.UD.DU.A bi[r-mu 1 ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a] \_\_\_\_\_ 8'. 2 < GADA> sal-hu 「6-ta¹ TÚG.GÚ.<UD>.DU [2 ku-si-tu4] 9'. [ $\check{s}\check{a}$ ]  $^{\mathrm{d}_{1}}$ DUMU.MÍ.<MEŠ>  $\acute{E}$ -babbar-r[a]10'. 1 GADA sal-hu 1<sup>en</sup> GADA hu-u[l-la-nu] 11'. pa-ti-in túg gú-hal-s[u]Edge 12'. šá <sup>d</sup>Bu-ne-[ne] Rev. 13'. 2 GADA sal-hu 3-ta [TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA] 14'. 1et TÚG.GÚ.UD.DU.A SÍG.[ZA.GÍN.KUR.RA 15'. 1<sup>et</sup> TÚG.GÚ.UD.[DU].「A bir¹-ri 16'. 1<sup>en túg</sup>BA[R.DUL<sub>6/8</sub> a-na <sup>d</sup>GAŠAN] Sip-par<sup>k[i]</sup> 17'. [1] GADA *s*[*al-hu*] 18'. [x x x x  $^{\text{túg}}$ ] $g\acute{u}$ -[ $\rlap/\mu al$ - $\rlap/su$ ] 19'. [1 TÚG.ÍB.LÁ *šá* <sup>d</sup>]ГІМ<sup>1</sup>

20'. [1 GADA *sal-hu*] [1<sup>en túg</sup>] [....]

```
21'. [x x x pa-t]i^{?}-in [....]
            22'. [x x x \check{S}]a^{?}-l[a^{?}....]
            23'. U_4.8.KAM MU.2.[KAM^{m}x x x]
L.h.e.
            24'. [LU]GAL TIN.TIR<sup>ki</sup>
Rev. is heavily destroyed.
[....], 1 patinnu-belt, [....] nēbehu-belt, the lub[ār mēṭu] (and) lubār kulūlu-
headbands [for Šamaš]
2 linen tunics, [the parš[īgu-belt], 4 [red] nahlaptu-cloaks, 1 multicolo[ured]
nahlaptu-cloak, [1 robe for Aya]
2 < linen> tunics, 6 nahlaptu-cloaks, [2 robes for] the Daughters of the Ebabbar
1 linen tunic, 1 linen hul[lānu]-cloak, <1> patinnu-belt, <1> sca[rf] for Bune[ne]
2 linen tunics, 3 [red nahlaptu]-cloaks, 1 bl[ue-purple] nahlaptu-cloak,
1 multicoloured nahla[ptu]-cloak, 1 ro[be for the Queen of] Sippar
[1] linen tu[nic ...], 1 linen sc[arf, 1 nēbehu-belt for] Adad
[1 linen tunic<sup>?</sup>], 1 [...., 1 patin]nu<sup>?</sup>-belt for Š[al]a<sup>?</sup>
8<sup>th</sup> day, 2<sup>nd</sup> year [of KN], king of Babylon.
209. BM 72305 (82-9-18, 12311)
                                                                                       PLATE 47
5.0 \times 5.2 cm
                         [x.x].Cam [x]
             1. [mi-ih-su t]e-nu-u ša ^{t}lu^{1}-[bu-u]š-tu4 ša ^{d}UTU u DI[NGIR.MEŠ] 2. [UD.KIB.N]UN^{k[i} a]-na ^{md}UTU-MU-MU ^{lu}TÚG.[BABBAR
                     SUM<sup>na</sup> ITI.x]
             3. [U<sub>4</sub>.x.KAM MU.x].KAM <sup>m</sup>Kam-bu-zi-ja LUGAL [E<sup>ki</sup> LUGAL
                 KUR.KUR1
             4. [2 GADA sal-hi] 1 GADA hu-la-nu 2 ^{t\acute{u}g}rṣib^{1}-tu_{4} r_{X^{1}} [....]
             5. [x \ x^{túg}]^{\Gamma} lu^{1}-bar-ru me-tu^{!} túg lu-bar-ru ku-[lu-lu šá ^{\dot{d}}UTU]
             6. [1 GADA sal-hi] 1 na-^{\Gamma}ah1-lap-tu_4 SÍG.HI(sic^!).ME.DA [....]
             7. [.... TÚ]G.BAR.SI [\check{s}\check{a}^{\dagger}A-a]
             8. [\dots na]^{-1}ah^{1}-lap-tu_{4} SÍG.HI.ME.D[A ....]
             9. [.... GADA] <sup>[</sup>gú<sup>]</sup>-hal-ṣu 1 [....]
            10. [.... MURU]B<sub>4</sub>.ÍB.LÁ [....]
Rest lost
```

The preserved bottom of the reverse is uninscribed.

The scribe made quite a lot of mistakes, i.e., in l. 5 and 6 *tu* is written over DA, in L. 7 SI is written over another character and in l. 8 the partly preserved *lap* was also written over another sign. Note that SÍG.HE.ME.DA is written SÍG.HI.ME.DA.

L. 7. Because the *kusītu* is never omitted, it must be placed before the *paršīgu*.

Ll. 8–9. Because the *naḥlaptu*-cloaks and the *guḥaṣṣu*-scarf are listed in this entry, it is certain that here the garments for Anunītu-ša-Sippar-Anunītu were listed. The place is atypical, because we expected first the list of garments for Bunene. His garments were probably listed in next entry (1.10–[11]).

[Woven garments for the cha]nge for the lu[buštu] ceremony of Šamaš and [the gods of Sip]pa[r, which were given] to Šamaš-šum-iddin, the  $aš[l\bar{a}ku.\ N^{th}$  month,  $n^{th}$  day,  $n^{th}$  year] of Cambyses, king [of Babylon, king of Lands].

[2 linen salhu]-tunics, 1 linen hullānu-cloak, 2 şibtu-garments [.... x] lubār mēṭu (and) lubār ku[lūlu-headbands for Šamaš]

[1 tunic, 1 red nahlaptu-cloak, 1 [..., 1 robe, x] paršīgu-headdress [for Aya]

[...., x]nahlaptu-cloak, [.... lin]en scarf, 1 [....]

# **210. BM 65484+BM 68961** (82-9-18, 5470+8960)


PLATE 48

 $8.5 \times 7.1$  cm

[x.x].Cam [x]

- 1. [mi-iḫ-ṣu] te-nu-ú šá lu-[bu-uš-tu4 šá U4.x.KAM šá ITI.x]
- 2. [a-na  $^{\mathrm{md}}$ ]UTU-MU-MU $^{\mathrm{lú}}$ TÚG.BABBAR SU[M ITI.x U<sub>4</sub>.x.KAM]
- 3. [MU.x.KA]M $^{\text{in}}$ Kam-bu-zi-ja [LUGAL TIN.TIR $^{\text{ki}}$  LUGAL KUR.KUR]
- 4. [2 GADA sal-h]u 1 GADA hu-ul-la-nu 1 [GADA gú-hal-șu]
- 5. [1 TÚG.MURU]B<sub>4</sub>.ÍB.LÁ SÍG.ḤÉ.ME.DA 1 TÚG.[BAR.SI] 「SÍG.Ḥɹ.ME.「DA¹
- 6. [1 TÚG].ÍB.<LÁ> TÚG.UD.A me-ṭu TÚG.「UD.A ku-lu-lu SÍG.ZA.GÌN.<KUR>.RA
- 7. [*a-na*] <sup>d</sup>UTU
- 8. [2 GADA s]al-ḥu 4 GÚ.UD.DU SÍG.ḤÉ.ME.DA 1 GÚ.UD.DU bir-mu
- 9. [2 TÚG]. BAR.SI SÍG.ḤÉ.ME.DA 1 ku-si-i-tu4 SÍG.ḤÉ.ME.DA 0. [a-n]a  $^d$ A-a

\_\_\_\_\_



[1 linen] tunic, 3 red *naḥlaptu*-cloaks, 1 multicoloured *naḥlaptu*-cloak, [1] blue-purple *naḥlaptu*-cloak, 1 blue-purple *lubār pāni*-veil, [1] blue-purple robe, 2 red *paršīgu*-headdresses [for] the Queen of Sippar

\_\_\_\_\_

[2 linen tuni]cs, 1 *naḥlaptu-*cloak, 1 robe [for] Gula

[1 linen tun]ic, 1 linen scarf, 1 red patinnu-belt, [1 nēbe]hu-belt for Adad

[1 linen tu]nic, 1 nahlaptu-cloak, 1 red robe [for] Šala.

#### **211. CT 55, 818** = BM 57812 Collated

```
1'. MU<sup>?</sup> [....]
         2'. 2 GADA sal-hi 1 GADA h[u-(ul)-la-nu 1 GADA gú-hal-su]
         3'. 1<sup>en</sup> pa*-tin-ni 1<sup>en</sup> [ni-bi-hu]
         4'. TÚG.HI.A ku-lu-lu [TÚG.HI.A me-tu a-na dUTU]
         _____
         5'. 1 GADA sal-hi 4 na-h[al-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA]
         6'. 1<sup>et</sup> na-hal-lap-tu<sub>4</sub> [bir-mu 1 ku-si-tu<sub>4</sub> a-na <sup>d</sup>A-a]
         _____
         7'. 2 GADA sal-hi 6 na-hal-lap-tu<sub>4</sub> [1 ku-si-tu<sub>4</sub>]
         8'. a-na <sup>d</sup>[DUMU.MÍ É-babbar-ra]
         -----
         9'. 1 GADA sal-ḥi 1 GADA h[u-(ul)-la-nu, [.... a-na <sup>d</sup>ḤAR]
         _____
Rev.
        10'. 1 GADA sal-hi <1 GADA gú>-hal-ṣu 1 [ni-bi-hu
        11'. a-n[a 	ext{ }^{d}DN]
        12'. 2 GADA sal-hi 3 na-[hal-lap-tu4 SÍG.HÉ.ME.DA]
        13'. 1<sup>et</sup> na-hal-lap-tu<sub>4</sub> bi[r-mu 1 na-hal-lap-tu<sub>4</sub>
               SÍG.ZA.GÌN.KUR.RA]
        14'. <1>-ta <ku>-si-tu<sub>4</sub> TÚG.ḤI.A me*-[tu]
        15'. TÚG.HI.A ku-lu-l[u a-na dGAŠAN Sip-parki]
        _____
        16'. 2 GADA sal-[hi ....]
```

The present state of preservation of the text is much worse than in time of Pinches. The tablet is broken in three parts with some fragments missing in comparison with Pinches' copy. The transliteration is based on copy in CT 55 with one change in 1. 3' and 14' where it is clear *pa* and less clear *me*.

Ll. 10'-11'. It is difficult to identify to whom these garments were destined, however, the mention of the *guḥaṣṣu*-scarf suggests that the garments for Anunītu-ša-Sippar-Anunītu were listed here.

[] year <sup>?</sup> []
2 linen tunics, 1 linen $h[ull\bar{a}nu$ -cloak, 1 linen scarf], 1 $patinnu$ -belt, 1 $[n\bar{e}behu]$ -belt, the $lub\bar{a}r$ $kul\bar{u}lu$ (and) $[lub\bar{a}r$ $m\bar{e}tu$ -headbands for Šamaš]
1 linen tunic, 4 [red] $nah[laptu]$ -cloaks, 1 [multicoloured] $nahlaptu$ -cloak, [1 robe for Aya]
2 linen tunics, 6 <i>naḥlaptu</i> -cloaks, [1 robe] for [the Daughters of the Ebabbar]
1 linen tunic, 1 linen $h[ull\bar{a}nu\text{-cloak}, 1 \text{ linen scarf}, 1 \text{ patinnu-belt}, 1 \text{ red } n\bar{e}behu\text{-belt for Bunene}]$
1 linen tunic, <1 linen s>carf, 1 [nēbeḥu-belt] for [DN]
2 linen tunics, 3 [red $na[hlaptu]$ -cloaks, 1 mul[ticoloured] $nahlaptu$ -cloak, [1 blue-purple $nahlaptu$ -cloak], <1> robe, the $lub\bar{a}r$ $m\bar{e}[tu]$ (and) $lub\bar{a}r$ $kul\bar{u}l[u$ -headbands for the Queen of Sippar]
2 linen tunics [].
212. BM 72982 (82-9-18, 12991) 5.4 × 5.3 cm  1. [mi-iħ-ṣu te]-nu-ú šá [lu-bu-uš-tu <sub>4</sub> šá IT]I.ŠE <sup>?</sup> 2. [] ITI.「x¹ [U <sub>4</sub> .x.KAM] 「MU.x.KAM¹ 3. [KN LUGAL] TIN.TIR「 <sup>ki</sup> ¹
4. [2 GADA sal-ḫu 1] GADA ḫu-ul-la-nu 1 GADA gú-ḫal-ṣu 5. [x x x TÚG.ḤI.A me-ṭu TÚG.ḤI.A] ku-lu-lu [šá <sup>d</sup> UTU]
6. [2 GADA sal-ḫu x na-ḫal-lap]-tú SÍG.ḤÉ.ME.DA 7. [1] <sup>túg</sup> ku-si-tu <sub>4</sub> šá <sup>d</sup> A-a
8. [1 GADA <i>sal-ḥu</i> 1 GADA] <i>ḥu-ul-[la-nu</i> ] 1 GADA gú-ḥal-ṣu 9. [] <sup>г</sup> x¹ [šá] <sup>гð</sup> ¹ḤAR
Edge 10. [2 GADA sal-hu 6] 「na¹-hal-lap-tú 11. [2 ku-si]-tu4 a¹-[na dDUMU].MÍ. <meš> É-babbar-ra Rev. 12. [2 GADA sal-hu 3] na-hal-lap-tú SÍG.HÉ.ME.DA 13. 1 na-hal-lap-tú] ta-kil-tú 14. [1 na-hal-lap-t]ú bir-mu TÚG.HI.A pa-ni 15. [x x x x x] ta-kil-tú 16. [x x x x x t]a-kil-tú TÚG.HI.A ku-lu-lu</meš>

17. [x x x x x x *a-na* <sup>d</sup>GAŠ]AN Sip-par<sup>ki</sup> 18. [1 GADA sal-hu 1 na]-hal-[lap-tú 1 ku]-si-tu4 a-na <sup>d</sup>ME.ME \_\_\_\_\_ 19. [1 GADA sal-hu 1 GADA g]ú-hal-ṣu [pa-tin-nu] ni-bi-ḥu šá <sup>d</sup>IM \_\_\_\_\_ 20. [1 GADA *sal-hu* 1 *n*]*a-hal-[lap-tú* 1 *ku-si-t*]*u*<sub>4</sub> *a-na* <sup>d</sup>[Š*a-la*] \_\_\_\_\_\_

The obverse of the tablet is heavily eroded.

In 1. 19, I reconstruct [pa-tin-nu] although place is a little too narrow. For this reason I exclude number 1, which is sometimes omitted. L. 20. Four or five signs, now completely illegible.

[Woven garments for the cha]nge for [the lubuštu for the mont]h Addaru? [....]. Month [x], [nth day], [nth year] [of KN, king] of Babylon.

[2 linen tunics, 1] linen hullānu-cloak, 1 linen scarf, [...., the lubār mētu (and) *lubār*] *kulūlu*-headbands [for Šamaš]

[2 linen tunics, x] red [nahlap]tu-cloaks, [..., 1] red robe for Aya

[1 linen tunic, 1 linen] hul[lānu]-cloak, 1 linen scarf, [.... for] Bunene

[2 linen tunics, 6] nahlaptu-cloaks, [2 rob]es fo[r the Daugh]ters of the Ebabbar

[2 linen tunics, 3] red *nahlaptu*-cloaks, 1 blue-purple [*nahlaptu*]-cloak, [1] multicoloured [nahlapt]u-cloak, the lubār pāni-veil, [1] blue-purple [....], <1> bluepurple [....], the *lubār kulūlu* (and) [*lubār mēṭu*]-headbands [for Ša]rrat Sippar

-----

[1 linen tunic, 1 na]h[laptu-cloak, 1 ro]be for Gula

[1 linen tunic, 1 linen s]carf, [<1> patinnu]-belt, <1> nēbehu-belt for Adad

[1 linen tunic, 1 n]ah[laptu-cloak, 1 rob]e for [Šala].

## 213. BM 61601 (82-9-18, 1573)

 $4.6 \times 5.9$  cm

## 6.[x].Nb[n] 12

- 1'.  $^{\text{l\'u}}$ TÚG.BABBAR  $^{\text{r}}$ x $^{\text{l}}$  [....] 2'. U<sub>4</sub>.6.KAM MU.12.KAM  $^{\text{d}}$ A[G-I $^{\text{l}}$ LUGAL  $B\bar{a}bili^{ki}$ ]
- 3'. 2 GADA sal-hi 1 GADA [hu-ul-la-nu]
- 4'. 1 GADA gú-hal-su  $<1> \lceil pa\rceil [tin-nu]$
- 5'. TÚG.ḤI.A me-ṭu TÚG.ḤI.A ku-lu-lu [šá <sup>d</sup>UTU]

```
6'. 2 GADA sal-hi1^{et}na-hal-lap-tu_4 [bir-mu]
            7'. 4 na-hal-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA 「šá <sup>d</sup>1[A-a]
            8'. 2 GADA sal-hi 6 na-hal-lap-tu4
            9'. 2-ta ku-sa-tu<sub>4</sub> a-na <d>DUMU.MÍ.<MEŠ> É-babbar-<sup>r</sup>ra<sup>1</sup>
           10'. 1 GADA sal-hi 1 GADA hu-ul-la-nu
           11'. <1> ni-bi-ḥu 1 GADA gú-[ḥal-ṣu]
           12'. <1> pa-tin-nu a-na [dBu-ne-ne]
           _____
           13'. 2 [GADA sal-h]i [....]
Rest of Obv. lost
Rev. preserved extreemely badly.
            1'. [....]<sup>[</sup>x<sup>1</sup> [....]
            2'. [.... -t]u_4'' [x] [....]
            3'. [....] 1 GADA [x] [....]
            4'. [....] [x] [x] ni-bi-hu
            5'. [....].ÍB.LÁ
            6'. [....] <sup>[</sup>bir<sup>]</sup>-mu
            7'. [....] [x \ x] [....]
            8'. [....] hi [x x n]a-hal-< lap>-t[u_4] 9'. {}^dM]E.ME
           10'. [....] 1 GADA gú-ḥal-ṣu
           11'. [.... ni]-bi-hu
           unreadible traces
Obv. ll. 6'-7'. Note the lack of the kusītu-robe in the list of Aya's garment.
[....], the ašlāku [....]
6<sup>th</sup> day, 12<sup>th</sup> year of Nabo[nidus<sup>?</sup>, kng of Babylon]
2 linen tunics, 1 linen [hullānu]-cloak, 1 linen scarf, <1> pa[tinnu]-belt, the lubār
mētu (and) lubār kulūlu-headbands [for Šamaš]
2 linen tunics, 1 [multicoloured] nahlaptu-cloak, 4 red nahlaptu-cloaks for [Aya]
2 linen tunics, 6 nahlaptu-cloaks, 2 robes for the Daughters of the Ebabbar
1 linen tunic, 1 linen hullānu-cloak, <1> nēbehu-belt, 1 linen sca[rf], <1> patinnu-
belt for [Bunene]
2 [linen tuni]cs, [....].
Rev. preserved too badly to be translated.
```

# **214. BM 70279** (82-9-18, 10280) PLATE 49 $5.3 \times 3.2 \text{ cm}$ 1'. [....] 'x x' [TUG.HI.A] 'ku-lu'-lu'' 2'. [TÚG.HI.A me-e]-<sup>[tu]</sup> a-na <sup>d</sup>UTU 3'. [2 GADA sal-hu] [x1-ta TÚG.GÚ.UD.DU.A SÍG.HÉ.ME.DA 4'. [1 TÚG.GÚ].UD.DU bir-mu 1<sup>et</sup> 「ku-si¹-tu4 SÍG.ḤÉ.ME.DA 5'. [1 par]-ši-gu SÍG.HÉ.M[E.DA a]-na <sup>d</sup>[A]-a 6'. [2 GADA *sal-h*]*u* 6-*ta* < TÚG>.GÚ.UD.D[U.A SÍG.ḤÉ].ME.DA 7'. [2] ku-sa-a-tu4 a-na d DUMU¹.MÍ.<MEŠ $> \acute{E}$ -babbar-ra¹ -----Rev. 8'. [1 GADA sal-h]u 1 GADA hu-la-nu 1 GADA gú-hal-s[u] 9'. [1 TÚG.MURUB4].ÍB.LÁ SÍG.HÉ.ME.DA 1 TÚG.ÍB.[LÁ] a-na <sup>d</sup>Bu-ne-<sup>r</sup>ne<sup>1</sup> 10'. 11'. [1 GADA sal-hu 1 GAD]A gú-hal-șu 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ SÍG.HÉ.ME.DA 12'. [1 TÚG.ÍB.LÁ ....] TÚG.HI.A *a-na* <sup>d</sup>IM 13'. [1 GADA sal-hu 1 T]ÚG.GÚ.UD.DU.A SÍG.[ḤÉ.ME].「DA<sup>1</sup> 14'. [1 *ku-si-t*]*u*<sub>4</sub> 「SÍG.HÉ.ME.DA¹ [*a-na* <sup>d</sup>Š*a-la*] Rest lost [...., the *lubār*] *kulūlu* (and) [*lubār mē*]*ṭu*-headbands for Šamaš [2 salhu]-tunics, [x] red nahlaptu-cloaks, [1] multicoloured [nahlap]tu-cloak, 1 red robe, [1] re[d par]šīgu-headdress for Aya [2 tun]ics, 6 r[ed] nahlaptu-cloaks, [2] robes for [the Daugh]ters of the Ebabbar [1 linen tun]ic, 1 linen hullānu-cloak, 1 linen scarf, [1] red [patin]nu-belt, 1 *nēbeḥu*-belt for Bunene [1 linen tunic, 1 lin]en scarf, 1 red patinnu-belt, [1 nēbeḥu-belt, ....] (and) lubārugarment for Adad [1 linen tunic, 1] red nahlaptu-cloak, [1] red [ro]be [for Šala]. **215. CT 55. 824** = BM 57988 Collated 1'. 1<sup>en</sup> pa-tin-nu [.... TÚG.ḤI.A me-ṭu] 2'. TÚG.HI.A ku-lu-lu a-na [dUTU]

3'. 2 GADA sal-hi 4-ta na-hal-lap-tu<sub>4</sub> S[ÍG.HÉ.ME.DA

```
4'. 1^{et} TÚG. \lceil GÚ*.UD*.DU* \rceil \lceil bir-mu \rceil \lceil 1 \rceil ku-si-t \lceil u_4 a-na \rceil^d A-a \rceil
              5'. 2 GADA sal-hi 6 na-hal-lap-tu<sub>4</sub> SÍG.[HÉ.ME.DA]
              6'. [2] 「ku¹-sa-tu4 a-na drDUMU.M͹.[MEŠ É-babbar-ra]
Rest of obv. and rev. are lost.
[...., 1 patinnu-belt, [..., the lubār mēṭu] (and) lubār kulūlu-headbands for [Šamaš]
2 linen tunics, 4 r[ed] nahlaptu-cloaks, 1 [multicoloured] nahlaptu-cloak, 1 rob[e
for Aya]
2 linen tunics, 6 r[ed] nahlaptu-cloaks, [2] robes for the Daughter[s of the Ebabbar].
216. BM 58846 (82-7-14, 3255)
3.5 \times 3.7 cm
              1'. \lceil x \ x \rceil \lceil x \rceil \lceil x \rceil \lceil x \rceil
              2'. [1 \ g] \acute{u}-hal-s[u ....]
              3'. [1] ni-bi-hu TÚG.HI.[A me-ţu]
              4'. [TÚ]G.ḤI.A ku-lu-lu a-na [dUTU]
              5'. [2 GAD]A sal-hu 4 <sup>túg</sup>na-[hal-lap-tu<sub>4</sub>]
              6'. [1^{et \text{ túg}}]na-hal-lap-tu<sub>4</sub> bir-m[u]
              7'. [1 \ k]u-si-tu<sub>4</sub> a-na [{}^{d}A-a]
Edge
              8'. [1 GADA sal]-hu 1 GA[DA hul-la-nu]
Rev.
              9'. [1 <sup>tú]g</sup>gú-ḥal-ṣu [....]
            10'. [1] <sup>túg</sup>ni-bi-ḥu 1<sup>en t</sup>[<sup>úg</sup>pa-tin-nu a-na <sup>d</sup>ḤAR]
            11'. 2 GADA sal-「hul 6 [na-hal-lap-tu4]
            12'. 2 ku-si-tu<sub>4</sub> a-na <sup>rd</sup>
<sup>1</sup>D[UMU.MÍ.MEŠ É-babbar-ra]
            13'. 1 GADA sal-ḥu 1 gú-ḥal-[ṣu]
            14'. 「1 <sup>túg</sup> ni-bi-ḥu a-na [dIM]
            15'. [x x x] [x x^{\dagger} [....]
[1 (linen) s]car[f, ...], [1] nēbeḥu-belt, the lubār [mēṭu] (and) [lu]bār kulūlu-
headbands for [Šamaš]
[2 line]n tunics, 4 na[hlaptu]-cloaks, [1] multicoloured nahlaptu-cloak, [1 r]obe for
[Aya]
```

[1 linen tuni]c, 1 lin [en $\mbox{\it hull}\mbox{\it \bar{a}}$ nu-cloak, 1] scarf, [], 1 $\mbox{\it n\bar{e}}$ belt, 1 [patinnu-belt for Bunene]
2 linen tunics, 6 [naḥlaptu-cloaks], 2 robes for the Dau[ghters of the Ebabbar]
1 linen tunic, 1 sca[rf], 1 <i>nēbeḥu</i> -belt for [Adad]

**217. BM 70252** (82-9-18, 10253)

#### GARMENTS FOR CYCLE B

## 5. Garments for the Ulūlu *lubuštu* ceremony

```
5.7 x 5.7 cm
                   28.5.Nbn 16
          1. mi-iḥ-ṣi te-nu-ú šá lu-[bu-uš-tu4 šá U4.3.KAM]
          2. šá ITI.KIN a-na ^{\rm m}Ba-la-ţu ^{\rm lú} [TÚG.BABBAR¹ [SUM^{\rm na} ITI.NE] 3. U<sub>4</sub>.28.KAM MU.16.KAM ^{\rm d}AG-I LU[GAL TIN.TIR^{\rm ki}]
          _____
          4. 2 GADA sal-hu 1 GADA hu-la-nu 1 GADA gú-hal-șu
               [1 TÚG.ÍB.LÁ]
          5. 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ a-na <sup>d</sup>UTU
          6. 2 GADA sal-hu 1<sup>et</sup> TÚG.GÚ.UD.DU bir-mu
               4 [TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA]
          7. 1 ku-si-tu4 SÍG.HÉ.ME.DA a-n[a ^{d}A-a]
          _____
          8. 2 GADA sal-hu 6 TÚG.GÚ.UD.DU.MEŠ [2-ta?] [ku-sa-a-tu4]
          9. a-na <sup>d</sup>DUMU.MÍ.MEŠ É-[babbar-ra]
          _____
         10. 1 GADA sal-hu 1 GADA hu-l[a-nu 1 GADA gú-hal-su
               TÚG.MURUB<sub>4</sub>.ÍB.LÁ]
         11. 1 TÚG.ÍB.LÁ SÍG. Hɹ. [ME.DA a-na dBu-ne-ne]
         _____
        12. <sup>[2]</sup> GADA <sup>[sal-hu]</sup> 4 [TÚG.GÚ.UD.DU.MEŠ
Edge
        13. lost
Rev.
        14. 1 GADA sal-hu [....]
        15. 1<sup>et</sup> ku-si-tu<sub>4</sub> [....]
         16. 1 GADA sal-hu 1 GADA gú-[hal-ṣu
         17. blank [....]
```

18. 1 GADA *sal-ḫu* 1<sup>et</sup> TÚG [x x] [....] 19. 1<sup>et</sup> *ku-si-tu*<sub>4</sub> SÍG.Ḥ[É.ME.D]A [....]

7'. ITI.NE U $_4.2^{\text{f}}$ 8.KAM¹ MU.16.KAM $^{\text{md}}$ AG-[I LUGAL

Free space for one line

TIN.TIR<sup>ki</sup>]

The last four entries enumerate most probably the garments for the Queen of Sippar, Gula, Adad and Šala.

Woven garments for the change for the $lu[bustu$ ceremony for the $3^{th}$ day] of Ulūlu [given to] Balāṭu, the $aslāku$ . [Month of Abu], $28^{th}$ day, $16^{th}$ year of Nabonidus, ki[ng of Babylon].
2 linen tunics, 1 linen <i>ḫullānu-</i> cloak, 1 linen scarf, [1 <i>nēbeḥu</i> -belt],

2 linen tunics, 1 multicoloured nahlaptu-cloak, 4 [red nahlaptu]-cloaks, 1 red robe fo[r Aya]

2 linen tunics, 6 *nahlaptu*-cloaks, <sup>7</sup>2 robes for the Daughters of the E[babbar]

\_\_\_\_\_

1 linen tunic, 1 linen hul[lānu-cloak, 1 linen scarf, 1 patinnu-belt], 1 re[d] nēbehubelt [for Bunene]

\_\_\_\_\_ 2 linen tunics, 4 [naḥlaptu-cloaks, ....]

1 linen tunic, [....], 1 robe [....]

1 patinnu-belt for Šamaš

1 linen tunic, 1 linen sc[arf, ....]

1 linen tunic, 1 [....] 1 r[e]d robe [....]

Month of Abu, 28<sup>th</sup> day, 16<sup>th</sup> year of Nabo[nidus, king of Babylon].

218. BM 83534 (83-1-21, 697)

 $6.2 \times 2.3$  cm

[x.x].Cyr 5

- 1. [mi-ih-și te-nu-ú šá lu-bu-uš-tu4 šá U4.3.KÁM šá] ITI.KIN a-na
- 2. [PN lúx MU].5.KAM mKur-raš LUGAL Eki LUGAL KUR.KUR -----

3. [2 GADA sal-hu 1 GADA hu-la-nu 1 GADA gú-hal-s]u 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ SÍG.HÉ.ME.DA

[1 TÚG.ÍB.LÁ šá <sup>d</sup>]UTU

\_\_\_\_\_

5. [2 GADA sal-hu x GÚ.UD.DU 1 TÚG.GÚ.UD].DU bir-mu 1 ku-si-tu<sub>4</sub> šá] <sup>d</sup>A-a

- 7. [....] *ku-si-tu*<sub>4</sub> SÍG.HÉ.ME.DA
- 8. [šá <sup>d</sup>DUMU.MÍ.MEŠ *É-babbra-ra*] (blank)

	9. [1 GADA sal-ḫu 1 GADA ḫu-la-nu 1 GADA gú-ḫal-ṣ]u 1 TÚG.MURUB₄.ÍB.LÁ SÍG.ḪÉ.ME.DA
	10. [1 TÚG.ÍB.LÁ šá <sup>d</sup> Bu-ne]-ne
	11. [ <i>l</i> ] <i>u-bar-ra</i> 12. [] (blank)
Rev.	13. [] <sup>f</sup> x <sup>1</sup> [] 1'. [] blank 2'. []
Rest unin	scribed
	arments for the <i>lubuštu</i> ceremony for the 3 <sup>rd</sup> day] of Ulūlu for [], the of Cyrus, king of Babylon, king of Lands.
	unics, 1 linen <i>ḫullānu</i> -cloak, 1 linen sca]rf, 1 red <i>patinnu</i> -belt, <i>u</i> -belt for] Šamaš
[2 linen t for] Aya	unics, x <i>naḥlaptu</i> -cloaks, 1] multicoloured [ <i>naḥlap</i> ]tu-cloak, [], 1 robe
[2 linen to	unics, 6 <i>naḥlaptu</i> -cloaks, 2] red robes [for the Daughters of the Ebabbar]
belt for B	unic, 1 linen <i>ḫullānu</i> -cloak, 1 linen sca]rf, 1 red <i>patinnu</i> -belt, [1 <i>nēbeḫu</i> -tune]ne.
<b>219. BM</b> 4.3 × 4.8	<b>74002</b> (82-9-18,14013) PLATE 49 cm
	$10+x^2.5.Cam[x]$
	1. mi- <sup>r</sup> iḫ-ṣi <sup>¬</sup> te-nu-ú [šá lu-bu-uš-tu₄] 2. šá U <sub>4</sub> .3.KAM šá ITI.KIN a-[na <sup>md</sup> UTU-MU-MU] 3. <sup>lú</sup> TÚG.BABBAR SUM <sup>nu</sup> <iti>.NE U<sub>4</sub>.10.[+x<sup>?</sup>KAM MU.x.KAM] 4. <sup>m</sup>Ka-am-bu-zi-ja LUGAL TI[N.TIR<sup>ki</sup>]</iti>
	5. 2 GADA sal-ḥu 1 GADA ḥu-ul-l[a-nu 1 GADA gú-ḥal-ṣu] 6. 1 SÍG.TÚG.'MURUB <sub>4</sub> ¹.ÍB.LÁ SÍG.ḤÉ.ME.[DA 1 TÚG.ÍB.LÁ] 7. šá <sup>d</sup> UTU
	8. [2 GADA <i>sa</i> ] <i>l-¹ḥu</i> ¹ 4 TÚG.GÚ.UD.D[U SÍG.ḤÉ.ME.DA] 9. [1 TÚG.GÚ.UD.DU <i>b</i> ] <i>ir-ri</i> [ 1 <i>ku-si-tu</i> 4 <i>šá</i> <sup>d</sup> <i>A-a</i> ]
Rest lost	
Rev. in p	reserved part uninscribed

Woven garments for the change [for the  $lubu\check{s}tu$ ] ceremony for the  $3^{rd}$  day of Ulūlu given t[o Šamaš-šum-iddin], the  $a\check{s}l\bar{a}ku$ . Month Abu,  $10[+x^{th}]$  day,  $n^{th}$  year of] Cambyses, king of Ba[bylon ....]. 2 linen tunics, 1 linen hul[lānu-cloak, 1 linen scarf], 1 red patinnu-belt, [1 nēbehubelt] for Šamaš [2 tun]ics, 4 [red] nahlaptu-cloaks, [1 multi]coloured [nahlaptu-cloak, [....., 1 robe for Aya]. 220. BM 62667 (82-9-18, 2636) PLATE 50  $8.3 \times 8.0$  (thick ca. 3.0) cm 1. [mi-i]h-「ṣu¬ te-nu-ú šá lu-bu-uš-tu4 [šá U4.3.KAM šá ITI.KIN] 2. [M]U.5.KAM <sup>m</sup>Da-ri-mu-šú LUGAL E<sup>ki</sup> LUGAL KUR.KUR 3. lúTÚG.BABBAR SUM<sup>na</sup> ITI.KIN U<sub>4</sub>.1.KAM \_\_\_\_\_ 4. 2 GADA sal-hu 1 GADA hu-la-nu 1 gú-hal-ṣu  $[(x \times x)^?]$ 5. mu-ta-ta 2 <sup>túg</sup>ṣib-ba-tu<sub>4</sub> a-na <sup>d</sup>[UTU] 6. 2 GADA sal-hu 4-et na-ah-lap-tu4 na-ba-[su] 7. 1<sup>et</sup> na-ah-lap-tu<sub>4</sub> bir-mu 2 BAR.SI.[MEŠ 1 ku-si-tu<sub>4</sub> a-na <sup>d</sup>A-a] 8. 4 GADA sal-hu 6  $^{\text{túg}}$ na-ah-lap-tu<sub>4</sub> na-[ba-su] 9.  $2^{\text{et}}$  ku-si-tu<sub>4</sub>  $^{\text{meš}}$  <a-na>  $^{\text{d}}$ DUMU.MÍ.<MEŠ> E-babbar-[ra] 10. 1 GADA sal-hu 1 GADA [hu]-[la-nu 1 gú-hal-su] 11. 1 TÚG.MURUB<sub>4</sub> (T:NÍG).[ÍB.LÁ 1 TÚG.ÍB.LÁ a-na <sup>d</sup>Bu-ne-ne] 12. 2 GADA [sal-hu 3 <sup>túg</sup>na-ah-lap-tu4na-ba-su] Rev. 13. 1<sup>en túg</sup>n[a-aḥ-lap-tu<sub>4</sub> ta-kil tu<sub>4</sub> 1 ku-si-tu<sub>4</sub> a-na <sup>d</sup>GAŠAN Sip-parki]? 14. 2 GADA sal-hu [1en na-ah-lap]-t[u4 1 ku-si-tu4 ana dGu-la] 15. 1 GADA *sal-ḥu* 1 gú-ḥal-ṣu [....] 16. 1 TÚG.MURUB<sub>4</sub> TÚG.UD.ḤI.A *a-* <sup>r</sup>*na* <sup>d</sup> <sup>1</sup> [IM] 17. 2 GADA *sal-hu* 2<sup>*et*</sup> *na-[ah-lap-tu<sub>4</sub>]* 

The *na* <sup>d</sup> in l. 5 and TÚG.UD.ḤI.A in l. 16 are written over an erasure.

18.  $1^{et}$  ku-si-tu<sub>4</sub> a-na [<sup>d</sup>Ša-la]

Lines 4–5 concern garments for Šamaš, and lines 6–7 for the goddess Aya. The *muttatu* for Šamaš appears in this type of list for the first time, although in accordance with BM 90002 in the month of Ulūlu, i.e. in the second cycle.

Note that 4 salhus for mārāt Ebabbar is exceptional, instead of the permanent 2 salhus.

L. 14 concerns most probably Gula and lines 15–16 Adad and 17–18 Šala, although 2 *sallyus* and 2 *na[hlaptu*]s is most probably a scribe's mistake for 1 *salhu* and 1 *na[hlaptu*]. Ll. 10–11, although badly preserved, concern the garments for Bunene. It is however uncertain whether ll. 12–13 enumerate the garments for the Queen of Sippar or Anunītu. In line 16 TÚG.MURUB<sub>4</sub> TÚG.UD.ḤI.A (the last four signs are written over an erasure) is a scribe's mistake for TÚG.MURUB<sub>4</sub>.ÍB.LÁ.

There is no dividing line between 16 and 17, however, the separation from the next entry is achieved by a larger distance between the lines.

[Wov]en garments for the change for the *lubuštu* ceremony [for the  $3^{rd}$  day of Ulūlu],  $5^{th}$  year of Darius, king of Babylon, king of Lands, given [to] the  $a\bar{s}l\bar{a}ku$ . Month of Ulūlu,  $1^{st}$  day.

2 linen tunics, 1 linen *hullānu*-cloak, 1 scarf, [...., x] *muttatu*-headress(es), 2 *şibtu*-garments for [Šamaš]

\_\_\_\_\_\_

2 linen tunics, 4 red *naḥlaptu-*cloaks, 1 multicoloured *naḥlaptu-*cloak, 2 *paršīgu-*headdresses, [1 robe for Aya]

4 linen tunics, 6 r[ed] *naḥlaptu*-cloaks, 2 robes for the Daughters of the Ebabbar

1 linen tunic, 1 linen *ḫul*[*lānu*-cloak, 1 linen> scarf], 1 *patin*[*nu*-belt, 1 *nēbeḥu*-belt for Bunene]

-----

2 linen [tunics, 3 red *naḥlaptu*-cloaks, 1 blue-purple] *na[hlaptu*-cloak, 1 robe for the Queen of Sippar]?

-----

2 linen tunics, *naḥlaptu-*cloak, [1 robe for Gula]

-----

- 1 linen tunic, 1 linen> scarf, [....], 1 patinnu¹-belt, [for Adad]
- 2 linen tunics, 2 *nah*[*laptu*]- cloaks, 1 robe for [Šala].

PLATE 51


## 6. Garments for the Tašrītu *lubuštu* ceremony

## $7.4 \times 4.9$ cm 3.7.Nb[n] 12 1. mi-ḥi-ṣu te-nu-ú šá <sup>md</sup>UTU[-MU-MU <sup>lú</sup>TÚG.BABBAR] 2. SUM<sup>na</sup> ITI.DU<sub>6</sub> U<sub>4</sub>.3.KAM MU.12.KAM <sup>rd</sup>AG<sup>1</sup>-[I LUGAL E<sup>ki</sup>] \_\_\_\_\_ 3. 2 GADA sal-ḥi 1 GADA ḥu-[ul-la]-nu 1 GADA gú-ḥal-ṣu 4. 1 pa-tin-nu 1<sup>en</sup> ni-b[i-ḥu a-n]a <sup>d</sup>UTU 5. 2 GADA sal-hi 4 na-[hal-la]p-tú SÍG.ḤÉ.ME.DA 6. 1 na-hal-lap-[tú bir]-mu < 1 > ku-si- $tu_4 a$ -na $^dA$ -a7. [1 GADA sal-hi] [1] [GADA hu-ul]-la-nu 1 GADA gú-hal-șu 8. [1 pa-tin-nu 1 ni-bi-hu a]-na <sup>d</sup>HAR \_\_\_\_\_ 9. [2 GADA sal-hi 3 TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA] [2]-ta Edge 10. [TÚG.GÚ.UD.DU bir-mu 1 TÚG.GÚ.UD.DU SÍG.Z]A.<GÌN>.KUR.RA 11. [1 ku-si-tu<sub>4</sub> a-na <sup>d</sup>GAŠAN] Sip-par<sup>ki</sup> \_\_\_\_\_ Rev. 12. [2 GADA sal-hi 3 na-hal-lap-tu<sub>4</sub> 1 hu-la-nu] 1 pa-tin-nu 13. [TÚG.HI.A] <sup>r</sup>x x x x *bi*<sup>1</sup> 1<sup>ren</sup> TÚG.HI.A MURUB<sub>4</sub> 14. TÚG.[x x TÚ]G.ḤI.A šá šam-ma-mu TÚG.ḤI.A 「ku-lu-lu 15. T[ÚG.HI.A] me-tu a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub> \_\_\_\_\_\_ 16. 2 GADA sal-hi 1<sup>et</sup> na-hal-lap-tu<sub>4</sub> 1<sup>et</sup> ku-si-tu<sub>4</sub> <a-na> dME.ME 17. 1 GADA sal-[hi] 1 GADA gú-hal-ṣu 1 pa-tin-nu 18. 1 *ni-bi-*<sup>r</sup>*hu*<sup>¬</sup> *a-na* <sup>d</sup>IM 19.1 GADA sal-hi [1et] TÚG.GÚ.UD.DU [SÍG.HÉ.ME.DA 1 ku-si- $tu_4$ 20. a-na <sup>d</sup>Ša-la

221. BM 64651 (82-9-18, 4631)

L. 4. The sign tin is written over erasure.

L. 9. The reading <sup>1</sup>2<sup>1</sup>-ta is certain and the reconstruction is based on many parallels, however, in light of other texts the Queen of Sippar has received only one multicoloured *naḥlap-tu-*cloak.



2 linen tunics, 1 linen *hul[lā]nu-*cloak, 1 linen scarf, 1 *patinnu-*belt, 1 *nē[behu-*belt fo]r Šamaš

2 linen tunics, 4 red *nah[lap]tu*-cloaks, 1 multicoloured *nahlaptu*-cloak, <1> robe

·

[1 linen tunic], 1 [linen hul]lānu-cloak, 1 linen scarf, [1 patinnu-belt, 1 nēbehubelt] for Bunene

[2 linen tunics, 3 red nahlaptu-cloaks], 2 [multicoloured nahlaptu-cloaks, 1 bluepu|rple [nahlaptu-cloaks, 1 robe for the Queen] of Sippar

[2 linen tunics, 3 nahlaptu-cloaks, 1 hullānu-cloak], 1 patinnu-belt, [....], 1 lubār qabli-loincloth, the ....-garment, the lubār ša šammamu-garment, the lubār kulūlu and  $lu[b\bar{a}]r$   $m\bar{e}tu$ -headbands for the Anunītu

\_\_\_\_\_

2 linen tunics, 1 nahlaptu-cloak, 1 robe <for> Gula

\_\_\_\_\_

1 linen tunic, 1 linen scarf, 1 patinnu-belt, 1 nēb[eh]u-belt for Adad \_\_\_\_\_

1 linen tunic, [1 red] *naḥlaptu*-cloak, [1 robe] for the Šala.

#### **222.** BM 57613[CT 55, 840]+BM 59013 (82-7-14, 2024 +3422)

 $8.3 \times 4.9$  cm

#### 3.7.Cyr 4

- 1. [mi-ih-s]u te-nu-ú šá lu-bu-u $[s-t]u_4$  šá ITI.DU $_6$  2.  $^{md\Gamma}$ UTU $^1$ -MU-MU $^{l\acute{u}}$ TÚG.BABBAR SUM $^{na}$  ITI.[D]U $_6$ U<sub>4</sub>.3.KAM MU.4.KAM
- 3.  $^{[m]}$   $\Gamma$   $Ku^1$  -ra- $\acute{a}$   $\acute{s}$  LUGAL  $E^{ki}$  LUGAL KUR.KUR

\_\_\_\_\_

4. 2 「GADA <i>sal¬-ḫi</i> (long blank s	space) <i>a-na</i> <sup>d</sup> UTU
5. 1 <sup>en</sup> [GADA ḫ]u-ul-la-nu	<i>a-na</i> <sup>d</sup> UTU
6. 1 <sup>en</sup> []	<i>a-na</i> <sup>d</sup> UTU
7. 1 <sup>en túg</sup> []	a-na [ <sup>d</sup> A-a]
8. []	a-na [ <sup>d</sup> A-a]
9. []	a-[na <sup>d</sup> A-a]

Rest of Obv. lost.

a-na  $^{d}Bu$ ]-ne-[ne]Rev. 1'. [....]

- Rev. 2'. Obviously, in this line the garments for the Daughters of the Ebabbar were enumerated. Note that most probably like in 1. 7' the robes were mentioned before the *naḥlaptu*-cloaks.
- L. 3'. There is quite a large gap between *sal-ḥi* and 1 TÚG.GÚ.UD.DU, however, I have no idea how to fill it.
- L. 7'. Note the atypical sequence of words (usually the kusītu is quoted as the last one).
- L. 8'. Or {TÚG.HÎ.A} TÚG.ÌB.LÀ.

[Wov]en garments for the change for the  $lubu[\S t]u$  ceremony of the month Tašrītu, (which) Šamaš-šum-iddin, the  $a\S l\bar{a}ku$  has delivered. Month of [Taš]rītu,  $3^{rd}$  day,  $4^{th}$  year of Cyrus, king of Babylon, king of Lands.

2 linen tunics 1 [linen h]ullānu-cloak 1 []	for Šamaš for Šamaš for Šamaš
1 [tunic] [x naḥlaptu-cloaks] 1 [robe]	for [Aya] for [Aya] f[or Aya]
[]	for Bu]ne[ne]

[2 linen tunics, 2 robes, 6] red [naħ]laptu-cloaks for [the Daughters of the Ebabbar]

[2 linen tu]nics, [....], 1 red nahlaptu-cloaks, 1 red  $hul[l\bar{a}nu]$ -cloak, 1  $n\bar{e}behu$ -belt, 1 patinnu-belt, the  $lub\bar{a}r$  qabli-loincloth, the  $lub\bar{a}r$   $m\bar{e}$  qaqqadi-headdress, the  $lub\bar{a}r$   $m\bar{e}tu$  (and)  $lub\bar{a}r$   $kul\bar{u}lu$ -headbands, the  $lub\bar{a}r$  sammamu-garment for Anunītu

2 lin[en tunics, 1] ro[be, 1 n]aḥlaptu-cloak for Gula

```
1 linen tunic, 1 scarf, the lubār nēbeḥu-belt, the patinnu-belt for Adad
[1] linen tunic, <1> nahlaptu-cloak, 1 robe for Š[ala].
223. BM 59871 (82-7-14, 4281)
4.5 \times 3.3 \text{ cm}
                     2.7.[KN x]
           1. [mi-ih-su te-nu]-u šá lu-b[u-uš-tu4 šá]
2. [^{md}UTU-NUMUN-GÁL^{\tilde{j}}1 ^{lu}TÚG.BABBAR SUM^{[na]}
           3. [2 GADA sal-h]i 1 GADA hu-ul-la-n[u ....]
           4. 1 \operatorname{rmut}^{1}-ta-tu<sub>4</sub> a-na <sup>d</sup>[UTU]
           _____
           5. 2 GADA sal-hi 4 na-ah-lap-t[u_4 \dots a-na <sup>d</sup>A-a]
           _____
           6. [1 GADA sa]l-hi 1 GADA hu-ul-l[a-nu
Rest lost
Rev.
           1'. [x x] [....]
           2'. [x]-uh hu [x] [....]
           3'. [IT]I.DU<sub>6</sub> U<sub>4</sub>.2.KAM M[U ....]
[Woven garments for the cha]nge for the lub[uštu ceremony, which Šamaš-zēr-
ušabš]i, the ašlāku has delivered. [....
[2 linen tuni]cs, 1 linen hullānu-cloak, [....], 1 muttatu-headdress for Šamaš
2 linen tunics, 4 naḥlaptu-cloaks [.... for Aya]
[1 linen tuni]cs, 1 linen hull[ānu-cloak, ....]
[Mont]h Tašrītu, 2<sup>nd</sup> day, ye[ar .....].
224. BM 73981 (82-9-18, 13992)
3.0 \times 5.0 cm
                     [x].7.[KN x]
           1. [mi-i]h-sú te-nu-[ú šá lu-bu-uš-tu4 šá a-na PN]
           2. [SU]M^{na} ITI. DU_6 U[_4.x.KAM MU.KAM KN]
           _____
           3. [2] GADA sal-hi 1 GADA [hul-la-nu 1 GADA gú-hal-ṣu]
           4. 1 pa-tin-nu 1 [ni-bi-hu .... šá <sup>d</sup>UTU]
           5. [2 GADA sal-hi 4 [na-hal-lap-tu<sub>4</sub> ....]
           6. 1^{et} ku-s[i-tu<sub>4</sub> .... šá <sup>d</sup>A-a]
```

```
7. 1 GADA sal-hi [....]
           8. 1 ni-bi-h[u .... šá <sup>d</sup>Bunene]
           9. [1+]1 GADA sal-hi
Rest lost
Rev.
           1'. TÚG.ḤI.A x [....]
           2'. [TÚ]G.HI.A ku-lu-lu [....]
           3'. [TÚ]G.ḤI.A 「šá¹ [....]
           _____
           4'. 1 GADA sal-hi 1 na-[hal-lap-tu<sub>4</sub> ....]
           5'. 1 GADA sal-ḥi 1 <sup>r</sup>gú<sup>γ</sup>-[ḥal-ṣu ....]
           _____
           6'. [1 GADA] [sal]-hi 1 na-hal-[lap-tu<sub>4</sub> ....]
Free space to the end of tablet
It seems that the sequence of garments was typical, in obv. Šamaš, Aya, Bunene, the Daugh-
ters of the Ebabbar, and in rev. probably Anunītu and next Gula, Adad and Šala.
[Wo]ven garments for the change [for the lubuštu ceremony, which PN... has
deli]vered. Month Tašrītu, n[th day, nth year of KN, king of Babylon (king of
Lands?)
[2] linen tunics, 1 linen [hullānu-cloak, 1 linen scarf], 1 patinnu-belt, 1 [nēbehu-
belt .... for Šamaš]
[2] linen tunics, 4 [nahlaptu-cloaks ....], 1 ro[be for Aya]
1 linen tunic [....], 1 nēbeḥ[u-belt .... for Bunene]
[1+]1 linen tunics [....]
[...., the lubār...., [lu]bār kulūlu [....], the lubāru ša [šamamu-garment<sup>?</sup> ....]
1 linen tunic, 1 na[hlaptu-cloak ....]
1 linen tunic, 1 sc[arf ....]
[1 linen] tunic, 1 naḥla[ptu-cloak ....].
225. BM 84254 (83-1-21, 1417)
5.2 \times 4.4 cm
                     3.7.[KN x]
           1. mi-ih-și te-[nu-ú] šá [lu-b]u-[uš-tu<sub>4</sub> šá]
           2. ITI.DU<sub>6</sub> [PN SUM<sup>na</sup> ITI. x]
           3. \Gamma U_4<sup>1</sup>.3.KAM MU.[x.KAM x x x x] LUGAL [....]
           _____
```

```
4. 2 GADA sal-[hu] [1 GADA hu]-la-nu [....]
           5. [1] TÚG.MUR[UB4.ÍB.LÁ 1 GADA gú]-ḥal-ṣu [....dUTU]
           _____
           6. 2 GADA sal-<sup>[</sup>hi<sup>]</sup> 4 [na-hal-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA]
           7. [x+]1 \text{ TÚG.}[.... ku-si-tu_4 a-na ^dA-a]
           8. fully lost
           1'. 「1 GADA sal-hi¬ 3 n[a-hal-lap-tu<sub>4</sub>]
Rev.
           2'. '1' TÚG.ḤI.A MURUB<sub>4</sub> 1 'TÚG<sup>?</sup>.ḤI<sup>?</sup>' [....]
           3'. 「TÚG¹.ÍB.「LÁ 2 TÚG.ḤI.A 「x¹ [....
           4'. TÚG.HI.A ku-lu-lu SÍG.ZA.GÌN.[KUR.RA]
           5'. TÚG.x a-na <sup>d</sup>[A-nu-ni-tu<sub>4</sub>]
           6'. 1 GADA sal-ḫu <1> gú-ḫal-ṣu 1 [.... a-na ^{\mathrm{d}}IM]
           -----
          7'. [1 GADA] sal-hu 1 ^{\text{túg}}[na-hal-lap-tu<sub>4</sub> 1 ku-si-tu<sub>4</sub>]
           8'. a-na^{d}[\check{S}a-la]
Obv. ll. 6-7 concern of garments for Aya.
Rev. 5'. The badly preserved and unrecognized sign follows TÚG.
Rev. 6'. 1 [nēbeḥu] or 1 [patinnu].
Rev. 8'. Or {}^{d}[Gu-la] (less probable).
Woven garments for the cha[nge] for the [lub]u[štu] ceremony for the month
Tašrītu, [which were given to PN. Month of x], 3<sup>rd</sup> day, [n<sup>th</sup>] year [of KN], king of
[Babylon, (king of Lands?)].
2 linen tunics, [1 linen hu]llānu-belt, [1 nēbehu-belt], 1 patin[nu-belt, 1 linen sc]arf
[for Šamaš]
2 linen tunics, 4 [nahlaptu-cloaks, x+] 1 [....,1 robe for Aya]
1 linen tunic, 3 na[hlaptu-cloaks], 1 lubār qabli-loincloth, 1 [....], nēbehu-belt,
2 lubār [....], the blue-pu[rple] lubār kulūlu-headband [....] for [Anunītu]
_____
1 linen tunic, <1> scarf, 1 [.... for Adad]
_____
[1 linen] tunic, 1 [nahlaptu-cloak, 1 robe] for [Šala].
```

## 7. Garments for the Addaru lubuštu ceremony

### 226. BM 61968 (82-9-18, 1937)

 $5.1 \times 4.6$  cm

## $12.12. < Nbk > 40 + [xth^?]$

- 1. 1 GADA sal-hu 1 GADA hu-la-[nu]
- 2. 1 GADA gú-ḥal-ṣu [....]
- 3. [x] mut-ta-tu<sub>4</sub> [....  $\check{s}\check{a}^{d}UTU$ ]
- 4. 1 GADA *sal-hu* 1<sup>*et*</sup> [....]
- 5. [x TÚG].  $^{\dagger}$ GÚ.UD $^{\dagger}$ .DU.A.  $^{\dagger}$ 1 $^{et}$  x $^{\dagger}$  [....]
- 6. [šá <sup>d</sup>A-a] 2 GADA <sup>r</sup>sal<sup>1</sup>-hi [....]
- 7. [x x x x TÚG].ÚR.MEŠ  $\check{s}\acute{a}^{\rm d}$ [DN]
- 8. [1 GADA *sal-hu* 1] GADA *hu-la-na* [....]

Rest of Obv. lost

Rev. in preserved part uninscribed

L.e.

1. [m]i-hi-iş te-nu-ú šá a-n[a lu-bu-uš-tu šá ITI.x]

2. ITI.ŠE U<sub>4</sub>.12.KAM MU.40[+x<sup>?</sup>.KAM]

LUGAL TIN.TIR.[KI

1 linen tunic, 1 linen *hullā*[nu]-cloak, 1 line scarf

[...., x] *muttatu*-headdress [.... for Šamaš]

1 linen tunic, 1 [...., x] nahlaptu-cloak(s), 1 [.... for Aya]

2 linen tunics [...., x] *sūnu*-belts for [....]

[1 linen tunic, 1] linen *hullānu*-cloak [....]

Woven garments which [were delivered fo[r the *lubuštu* ceremony for the [month ....] Month Addaru, 12<sup>th</sup> day, 40+[n<sup>th?</sup>] year <of Nebuchadnezzar>, king of Babylon.

## **227. BM 66535** (82-9-18, 6528)

 $4.9 \times 6.0$  cm

## 8.12. $Nb[n^{?}x]$

- 1. mi-ih-su šá a- $n[a^{?}$  x (x)]  $\lceil x \rceil lu^{!}$ -b[u-uš-tu šá ITI.ŠE]
- 2. ITI.ŠE U<sub>4</sub>.8.K[AM MU.x].KAM <sup>md</sup>AG-[....]

3. 2 G[ADA] sal- $h[u \times \times \times 1 GA]DA$  hu-la-nu

- 4. [1 gú]-ḥal-「ṣi 1<sup>1en</sup> pa-ti-in-[nu] 5. [1 TÚG.Í]B.「LÁ a-na <sup>d</sup>1[UTU]
- 6. completely damaged
- 7. [1]  $\lceil na-ah-lap-tu_4 \ bir \rceil \lceil mu \rceil$
- 8.  $[1 \ k]u$ -si-tu<sub>4</sub> a- $[na \ ^{d}A$ -a]
- 9. [x x x] [x] [....]

```
Rest lost
              1'. [a-na dGAŠAN Sip]-parki
Rev.
              2'. [1 GADA sal]-hu 1<sup>et</sup> na-a[h-lap-tu<sub>4</sub>]
              3'. [1 k]u-si-tu<sub>4</sub> a-na [^{d}Gu-la]
              4'. [1 GADA sa]l-hu 1 G[ADA gu-hal-ṣu]
              5'. [1<sup>et</sup> p]a-ti-in-nu ni-[bi-ḥu]
              6'. a-na <sup>d</sup>IM
              7'. [1 GA]DA sal-hu 1^{et} na-[ah]-lap-t[u<sub>4</sub>]
             8'. 1<sup>et</sup> ku-si-tu<sub>4</sub> [a]-<sup>r</sup>na<sup>1</sup>
9'. <sup>d</sup>Ša-la
Woven garments which f[or ... the lub]uštu ceremony for the [month Addaru].
Month Addaru, 8<sup>th</sup> d[ay, n<sup>th</sup> year] of Nabo[....]
2 li[nen] tuni[cs ..... 1 lin]en hullānu-cloak, [1 sc]arf, 1 patinnu-belt, [1 nēbe]hu-
belt for [Šamaš]
[....], 1 multicolo[ured] nahlaptu-cloak, [1 r]obe f[or Aya]
[.... for the Queen of Sip]par
[1 linen tun]ic, 1] nah[laptu]-cloak, [1] robe for [Gula]
[1 linen tun]ic, 1 li[nen scarf, 1 p]atinnu-belt, 1 nē[behu]-belt for Adad
[1 lin]en tunic, 1 nahlaptu-cloak, 1 robe for Šala.
228. Cyr 7 = BM 92772; cf. NUVI 3, No. 106; Giovinazzo 1981, No. 1
                          10.12.Cyr 0
              1. [mi-h]i^?-și te-nu-ú lu-bu-uš-tu<sub>4</sub> šá ITI.
ŠE a-na 2. [^{md}]^\GammaUTU¹-MU-MU ^{lú}TÚG.BABBAR SUM ^{nu} ITI.
ŠE
                      U_4.10.KAM
              3. MſU.SAÌG.NAM.LUGAL.LA <sup>m</sup>Ku-ra-áš LUGAL KUR.KUR
              4. 2 「GADA sal-hi 1 GADA hu-ul-la-nu 1 GADA gú-hal-șu
              5. 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ 1 SÍG.BAR.「SI<sup>†</sup> šá <sup>d</sup>UTU
              6. 2 「GADA<sup>¬</sup> sal-hi 4 GÚ.UD.DU SÍG.ḤÉ.ME.DA
              7. 1 GÚ.UD.DU <sup>síg</sup>bir-mu 1 <sup>síg</sup>ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a
```

8. 1 GADA sal-hi 1 GADA hu-ul-la-nu 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ

1 GADA gú-hal-șu

	9. 1 TÚG.ÍB.LÁ šá <sup>d</sup> Bu-ne-ne
	10. 2 GADA <i>sal-ḥi</i> 6 SÍG.GÚ.UD.DU SÍG.ḤÉ.ME.DA 2 <sup>síg</sup> ku-si-tu <sub>4</sub> 11. šá <sup>d</sup> DUMU.MÍ. <meš> É-babbar-ra</meš>
	12. 1 GADA <i>sal-ḥi</i> 3 GÚ.UD.DU SÍG.ḤÉ.ME.DA 1 GÚ.UD.DU SÍG.ZA.GÌN.KUR.RA
	13. [1] GÚ.UD.DU <i>bir-mu</i> 1 TÚG.UD.A <i>pa-ni</i> 1 <i>ku-si-tu</i> <sub>4</sub> <i>šá</i> SÍG.ZA.GÌN.KUR.RA
	14. 「šá <sup>d</sup> ¬GAŠAN Sip-par <sup>ki</sup>
Rev.	15. [1 GADA $sa$ ] $l$ - $hi$ 1 「GÚ¹.UD.DU SÍG.ḤÉ.ME.DA 「1 $^{en}$ ¹ $ku$ - $si$ - $tu$ 4 $šá$ $^d$ $Gu$ - $la$
	17. šá <sup>d</sup> IM
	18. [1 GADA <i>sal</i> ]- <i>ḫi</i> 1 GÚ.UD.DU SÍG.ḤÉ.ME.DA 1 <i>ku-si-tu</i> <sub>4</sub> <i>šá</i>
	ly the text is preserved much better than is suggested by Strassmaier's copy, proba- ause the tablet was later cleaned.
given t	en garments for the change for the <i>lubuštu</i> ceremony for the month Addaru o Šamaš-šum-iddin, the $a\bar{s}l\bar{a}ku$ . Month Addaru, $10^{th}$ day, the accession year as, king of Lands.
	n tunics, 1 linen <i>ḫullānu</i> -cloak, 1 linen scarf, 1 <i>patinnu</i> -belt, 1 <i>paršīgu</i> -ess for Šamaš
2 linen	tunics, 4 red <i>naḥlaptu</i> -cloaks, 1 multicoloured <i>naḥlaptu</i> -cloak, 1 robe for Aya
1 linen Bunene	tunic, 1 linen <i>ḫullānu-</i> cloak, 1 <i>patinnu-</i> belt, 1 linen scarf, 1 <i>nēbeḫu-</i> belt for
1 liner	tunics, 6 red <i>naḥlaptu</i> -cloaks, 2 robes for the Daughters of the Ebabbar tunic, 3 red <i>naḥlaptu</i> -cloaks, 1 blue-purple <i>naḥlaptu</i> -cloak, [1] multied <i>naḥlaptu</i> -cloak, 1 <i>lubār pāni</i> -veil, 1 blue-purple robe for the Queen of
[1 liner	n tun]ic, 1 red <i>naḥlaptu</i> -cloak, 1 robe for Gula
[1 liner	n tun]ic, 1 linen scarf, 1 <i>patinnu</i> -belt, 1 <i>nēbeḫu</i> -belt for Adad
[1 liner	n tun]ic, 1 red <i>naḥlaptu-</i> cloak, 1 robe for the Šala.

Rev.

**229. Cyr 241** = BM 92768 (83-1-18, 833); cf. NUVI 3, No. 121; Giovinazzo 1981, No. 13 8.9 × 6.3 cm

#### 12.12.Cyr 6

- 1. mi-ih-și te-nu-ú šá lu-bu-uš-tu4 šá U4.15.KAM 2. šá ITI.ŠE a-na <sup>md</sup>UTU-MU-MU <sup>lú</sup>TÚG.BABBAR SUM<sup>na</sup> 3. ITI.ŠE U<sub>4</sub>.12.KAM MU.6.KAM <sup>m</sup>Ku-raš LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR 4. 2 GADA sal-hu 1 GADA hu-la-nu 1 TÚG SAG 1 TÚG.MURUB<sub>4</sub>.ÍB.[LÁ] 5. 1 GADA gú-ḥal-ṣu 2 TÚG.ḤI.A a-na  $^{\rm d}{\rm UTU}$ \_\_\_\_\_ 6. 2 GADA sal-ḥu 1<sup>et</sup> TÚG.GÚ.UD.DU bir-mu 4 TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA 7. 1<sup>et</sup> ku-si-tu<sub>4</sub> 2 TÚG.BAR.SI.<MEŠ> SÍG.HÉ.ME.DA a-na <sup>d</sup>A-a 8. 2 GADA sal-hu 6 TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA 9. 2-ta ku-si-tu<sub>4</sub> SÍG.HÉ.ME.DA a-na <sup>d</sup>DUMU.MÍ.<MEŠ> É-<sup>r</sup>babbar-ra<sup>1</sup> 10. 1 GADA sal-hu 1 GADA hu-la-nu 1 TÚG.ÍB.LÁ 1 TÚG.MURUB<sub>4</sub>.ÍB.[LÁ] 11. 1 GADA {<sup>túg</sup>} gú-ḥal-ṣ[u] 「a¹-na <sup>d</sup>Bu-ne-ne 12. 2 GADA sal-ḥu 3 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.[DA] 13. 1et TÚG.GÚ.UD.DU bir-mu 1et TÚG.GÚ.UD.DU SÍG.Z[A.GÌN.KUR.RA] 14. 2 TÚG.HI.A [pa]-ni<sup>!</sup> SÍG.ZA.GÌN.KUR.RA 1<sup>et</sup> ku-si-tu<sub>4</sub> SÍG.ZA.GÌN.[KUR.RA]

  a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> 15. 16. 2 GADA sal-hu 1et TÚG.<GÚ>.UD.DU SÍG.HÉ.ME.DA  $1^{et}$  ku-si-tu<sub>4</sub> 17. SÍG.HÉ.ME.DA a-na <sup>d</sup>Gu-la 18. 1 GADA sal-hu 1 TÚG.ÍB.LÁ 1 TÚG.MURUB<sub>4</sub>.ÍB.<LÁ> 1 <sup>túg</sup>gú-hal-su
- L. 4. TÚG SAG, cf. the list in Index ("Terms written ideographically"). According to BM 63912 (= 535) for manufacturing of TÚG SAG the red wool (*tabarri*) was used.

20. <sup>[1]</sup> GADA<sup>[]</sup> sal-hu 1<sup>et</sup> TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA

21. 1<sup>et</sup> ku-si-tu<sub>4</sub> SÍG.HÉ.ME.DA a-na <sup>d</sup>Ša-la

L. 14. Before ir there is space for only one sign. My first idea was to fill the gap with [e], i.e. to see there the erru-garment but this cannot be accepted because the erru is known exclusively as a part of attire in the cycle A. Note 2 salhus for Queen of Sippar and Gula, while normal is 1 salhu for each of them. Similar in BM 66196+ (= 231).

Woven garments for the change for the *lubuštu* ceremony for the 15<sup>th</sup> day of Addaru given to Šamaš-šum-iddin, the *ašlāku*. Month Addaru, 12<sup>th</sup> day, the 6<sup>th</sup> year of Cyrus, king of Babylon, king of Lands

-----

2 linen tunics, 1 linen *hullānu*-cloak, 1 SAG-garment, 1 *patinnu*-belt, 1 linen scarf, 2 *lubāru*-garments for Šamaš

\_\_\_\_\_

2 linen tunics, 1 multicoloured *naḥlaptu*-cloak, 4 red *naḥlaptu*-cloaks, 1 robe, 2 red *paršīgu*-headdresses for Aya

-----

2 linen tunics, 6 red *naḥlaptu*-cloaks, 2 red robes for the Daughters of the Ebabbar

1 linen tunic, 1 linen hullanu-cloak, 1  $n\bar{e}behu$ -belt, 1 patinnu-belt, 1 linen scarf for Bunene

2 linen tunics, 3 red *naḥlaptu*-cloaks, 1 multicoloured *naḥlaptu*-cloak, 1 blue-p[urple] *naḥlaptu*-cloak, two blue-purple  $lub\bar{a}r$  [ $p\bar{a}$ ] $ni^!$ -veils, 1 blue-pur[ple] robe for the Queen of Sippar

.-----

2 tunics, 1 red *naḥlaptu*-cloak, 1 red robe for Gula

1 linen tunic, 1 nēbehu-belt, 1 patinnu-belt, 1 scarf for Adad

-----

1 linen tunic, 1 red nahlaptu-cloak, 1 red robe for the Šala.

## **229a. BM 65504** (82-9-18, 5490)

 $5.9 \times 4.8$  cm

- 1. mi-iḥ-ṣi te-nu-<sup>r</sup>ú¹ [šá lu-bu-uš-tu<sub>4</sub> šá U<sub>4</sub>.15.KAM šá ITI.ŠE a-na PN]
- 2.  $^{\text{lú}}$ TÚG.BABBAR SUM $^{na}$  ITI.ŠE  $^{\text{r}}$ U $_{4}$ <sup>1</sup>.[x.KAM ....]
- 3. 2 GADA sal-hi 1 GADA hu-ul-la-[nu 1 GADA gú-hal-ṣu]
- 4. 1  ${}^{\mathsf{r}}$  mu-ut- $ta^{\mathsf{l}}$ - $tu_4$  1 pa-tin-nu a-n[a  ${}^{\mathsf{d}}$  UTU]

\_\_\_\_\_

- 5. 2 GADA sal-hi 4 na-hal-lap-tu<sub>4</sub> [SÍG.ḤÉ.ME.DA]
- 6.  $1 \text{ na-hal-lap-tu}_4 \text{ }^{\text{f}} bir\text{-mu}^{\text{I}} [1 \text{ ku-si-tu}_4 \text{ a-na}^{\text{d}} A\text{-a}]$

É-babbar-ra]

7. [1]+1 sal-ḥi 6 n[a-ḥal-lap-tu<sub>4</sub> 2 ku-si-tu<sub>4</sub> a-na <sup>d</sup>DUMU.MÍ.MEŠ

\_\_\_\_\_\_

Rev.	8. 1 GADA <i>sal-ḥi</i> [] 9. [x] <sup>r</sup> x¹ [] 1'. nothing preserved
	2'. 1 GADA 「sal¬-[ḫi]
	3'. 1 「GADA <i>sal</i> ¹-[ <i>ḫi</i> ]
	4'. 1 GADA <i>sal-ḫi</i> []
wedge is p	A list of garments for Bunene is expected here. In l. 9 only a "head" of vertical preserved.  Most probably the entries included garments for Gula, Adad and Šala.
	arments for the change [for the <i>lubuštu</i> ceremony for the 15 <sup>th</sup> day of Addaru PN], the <i>ašlāku</i> . Month Addaru, [x] day []
	nics, 1 linen 2 linen tunics, 1 linen <i>ḫullānu</i> -cloak, [1 linen scarf], 1 <i>muttatu</i> -s, 1 <i>patinnu</i> -belt fo[r Šamaš]
for Aya]	nics, 4 [red] <i>naḥlaptu-</i> cloaks, 1 multicoloured <i>naḥlaptu-</i> cloak, [one robe
	tunics, 6 n[ahlaptu-cloaks, 2 robes for the Daughters of the Ebabbar]
1 linen tu	
1 linen tu	
1 linen tu	
1 linen tu	nic []

# 8. Garments for the *lubuštu* ceremony in cycle B (Ulūlu, Tašrītu or Addaru)

# 230. BM 69774 (82-9-18, 9774) $4.4 \times 2.7$ cm [x.x].Nbn 1 1. [2 GADA] sal-ḫi 1<sup>en</sup> GADA ḫu-ul-la-nu <sup>túg</sup>[....] 2. [1 gu]-hal-şu šá <sup>d</sup>UTU 2 sal-h[i ....] 3. [x TÚG.G]Ú.UD.DU.A na-ba-su [....] 4. [.... 1] $\lceil ku - si \rceil - tu_4 \lceil 1^{?_1} \rceil$ [....] 5. [....] nothing preserved Rest lost 1'. [a-na PN <sup>1</sup>]<sup>ú</sup>TÚG.BABBAR SUM<sup>in</sup> ITI.[x] Rev. 2'. [U<sub>4</sub>.x.KAM] MU.1.KAM <sup>md</sup>AG-IM.[TUKU LUGAL *Bābili*] [2 linen] tunics, 1 linen *hullānu*-cloak, [...., 1 sc]arf for Šamaš; 2 tunics [...., x] red *nahlaptu*-cloaks, [...., 1] robe 1<sup>?</sup> [....] [....] given [to] the ašlāku. Month [x, nth day], 1st year of Nabon[idus, king of Babylon]. **231. BM 66196+BM 67633** (82-9-18, 6187+7631) PLATE 52-53 $7.8 \times 5.3$ cm [x.x].Nbn 7 1. [2] GADA 「sal¬-ḥu 1<sup>en</sup> GADA ḥu-ul-la-nu 2. $1^{en}$ GADA $g\acute{u}$ -hal- $\langle su 1 \rangle$ $t\acute{u}g$ mut-ta- $tu_4$ 3. *a-na* <sup>d</sup>UTU 4. [1+] 1 GADA sal-ḥu 4 <sup>túg</sup>na-aḥ-lap-tú na-ba-su 5. [1]<sup>et túg</sup>na-ah-lap-tú bir-ri 6. $[1]^{et}$ túgku-si-tu<sub>4</sub> š $\acute{a}$ <sup>d</sup>A-a7. $1^{en}$ GADA sal-hu $1^{en}$ GADA $hu-u[l^?-la-nu]$ 8. $1^{en}$ TÚG.MURUB<sub>4</sub>.ÍB.LÁ [ $1^{en}$ ] [TÚG.ÍB.LÁ] 9. *šá* <sup>d</sup>*Bu-*<sup>r</sup>*ne*<sup>¬</sup>*-*[*ne*]

10. <sup>[2]</sup> GADA sal-ḫu 6 <sup>túg</sup>na-a[ḥ-lap-tú]

12. šá <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra* 

13. 2 GADA sal¹-hu 3 <sup>rtúg</sup>¹na-ah-lap-tu<sub>4</sub>

11. <sup>[2]</sup>-ta <sup>túg</sup>ku-sa-a-tú

```
14. 1<sup>et túg</sup>ku-si-tu<sub>4</sub>
15. 1<sup>en túg</sup>lu-ba-ri pa-ni
                   16. a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
Edge
                  17. 2 GADA! sal-hu 1 túgna-ah-lap-tú
Rev.
                   18. 1<sup>et túg</sup>ku-si-tu<sub>4</sub> šá <sup>d</sup>Gu-la
                   19. 1^{en} GADA sal-hu 1^{en} 「GADA gu¹-hal-ṣu
                   20. 1<sup>en</sup> TÚG. MURUB<sub>4</sub> '.ÍB.LÁ 1<sup>en túg</sup>ni-bi-'hu
                   21. 1^{en \text{ túg}} [lu-ba-ri] \check{s} \acute{a}^{\text{d}} [\text{IM}]
                   22. [2] GADA sal-[hu] [....]
                   24. ku-\lceil si^2 \rceil-\lceil tu_4 \dots \check{s} \acute{a} \overset{d}{\check{S}} \check{a}-la \dots \rceil
                   25. SUM<sup>nu</sup> IT[I.x] <sup>r</sup>x x<sup>1</sup>
26. [MU].7.KAM <sup>md</sup> rAG-I<sup>1</sup> LUGAL TIN. rTIR <sup>ki</sup>
```

At the end of 1. 7 1 GADA gu-hal-şu is expected, however, there is not enough space for the

Ll. 24–26. The formula belonging to the heading was atypically written at the end of this text.

[2] linen tunics, 1 linen hullānu-cloak, 1 linen scarf, <1> muttatu-headdress for Šamaš

[1] + 1 linen tunics, 4 red nahlaptu-cloaks, [1] multicoloured nahlaptu-cloak, <sup>[1]</sup> robe for Aya

1 linen tunic, 1 linen hu[llānu]-cloak, 1 patinnu-belt, 1 [nēbehu-belt] for Bunene

2 linen tunics, 6 nah[laptu]-cloaks, 2 robes for the Daughters of the Ebabbar

2 linen tunics, 3 nahlaptu-cloaks, 1 robe, 1 lubār pāni veil for the Queen of Sippar

2 linen tunics, 1 nahlaptu-cloak, 1 robe for Gula

1 linen tunic, 1 scarf, 1 patinnu-belt, 1 scarf, 1 nēbehu-belt 1 [lubāru]-garment for [Adad]

2 linen tun[ics ...., 1] rob[e for the Šala ....] was given. Mon[th x, n<sup>th</sup> day, year] 7<sup>th</sup> of Nabonidus, king of Babylon.

## 232. BM 54258 (82-5-22,409)

 $6.6 \times 5.7$  cm

#### 5.[x].Nbn 5

- 1. [mi-ih-su te-nu]-u sa a-na  $^{md}$ UTU-SIG $_5$   $^{iq}$  [SUM $^{na}$ ] 2. [ITI.x] U $_4$ .5.KAM MU.5.KAM  $^{md}$ AG-I LUGAL E.[KI]

	3. [2 GADA sal-ḫu 1 GADA] ḫu-ul-la-nu 1 GADA gú-ḫal-ṣu 4. [x x x 1] mu-ut-ta-tu4 a-na <sup>d</sup> UTU
	5. [2 GADA sal-ḫu x-t]a na-ḫal-lap-tu <sub>4</sub> SÍG.ḤÉ.ME.DA <sup>!</sup> (T:DU) 1 na-ḫal- <sup>[</sup> lap <sup>1</sup> -[tu <sub>4</sub> bir-mu] 6. [1 ku-s]i-tu <sub>4</sub> <sup>[</sup> a <sup>1</sup> -na <sup>d</sup> A-a
	7. [1 GADA sal-ḫu] 1 GADA ḫu-ul-la-nu 1 GADA gú-ḫal-ṣu 8. [1 ni-bi-ḫ]u 1 pa-tin-ni a-na <sup>d</sup> Bu-ne-ne
	9. [2 GADA sal-h]u 6 na-hal-lap-tu <sub>4</sub> 2 <sup>r</sup> ku <sup>1</sup> -sa-tu <sub>4</sub> a-[na <sup>d</sup> GAŠAN].MEŠ
	10. [2 GADA sal-ḥu] 5 na-ḥal-lap-[tu <sub>4</sub> 1 ku-si-tu <sub>4</sub> a-na] <sup>d</sup> GAŠAN Sip <sup>1</sup> -[par <sup>ki</sup> ]
Rev.	11. [2 GADA <i>sal-ḫu</i> 1 GADA] <i>ḫu-ul-la-nu</i> SÍG.ḤÉ.[ME.DA] 12. [x x x] <sup>r</sup> 2¹ <i>pa-tin-na-a-tu</i> <sub>4</sub> 5 <i>na-ḫal-lap-[tu</i> <sub>4</sub> ] 13. [TÚG.ḤI.A <i>ku-lu-lu</i> ] 1 TÚG.ḤI.A <i>me-ṭu</i> 1 <i>par-ši-gu</i> 1 <i>ni-</i> <sup>r</sup> <i>bi-ḫu</i> ¹ 14. [x x x] x (erased) <i>a-na</i> <sup>d</sup> A-nu-ni-tu <sub>4</sub>
	15. [1 GADA sal-ḫu 1 na-ḫal-lap-t]u <sub>4</sub> 1 <sup>et</sup>
	16. [1 GADA sal-ḥu 1 GADA gú-ḥal-ṣu] 1 pa-tin-「nu¬ 1 「ni¬-bi-ḥu šá <sup>d</sup> IM
	17. [1 GADA sal-ḫu 1 na-ḫal-lap-tu₄] 1 <sup>et</sup> ku-si-tu₄ a-na <sup>d</sup> Ša-la
In 1. 9 I f	is clearly written with one vertical stroke. illed the gap with $[na\ ^d\text{GAŠAN}]$ because there is not enough place for $[na\ ^d\text{DU-IEŠ}\ \acute{E}\ -babbar\ -ra]$ .
[Woven to] Šama	garments which for the chan]ge <for <i="" the="">lubuštu ceremony&gt; [were given <math>\S</math>-udammiq. [Month x], <math>\S</math><sup>th</sup> day, the <math>\S</math><sup>th</sup> of Nabonidus, king of Babylon.</for>
[2 linen t Šamaš	tunics, 1 linen] <i>ḫullānu</i> -cloak, 1 linen scarf, [, 1] <i>muttatu</i> -headdress for
[2 linen to for Aya	tunics, x] red <i>naḥlaptu-</i> cloaks, 1 [multicoloured] <i>naḥlaptu-</i> cloak, [1 ro]be
	unic], 1 linen <i>ḫullānu-</i> cloak, 1 linen scarf, [1 <i>nēbeḫu</i> ]-belt, u-belt for Bunene
[2 linen t	unic]s, 6 red <i>naḥlaptu</i> -cloaks, 2 robes f[or Ladi]es

[2 liner	tunics], 5 naḥlap[tu-cloaks, 1 robe for] the Queen of Sip[par]
1 lubār	a tunics, 1] re[d linen] <i>ḫullānu</i> -cloak, [], 2 <i>patinnu</i> -belts, 5 <i>naḫlap[tu</i> -cloaks, · <i>kulūlu</i> ] (and) 1 <i>lubār mēṭu</i> -headband, 1 <i>paršīgu</i> -headdress, 1 <i>nēbeḥu</i> -belt, · Anunītu
[1 liner	tunic, 1 naḥlapt]u-cloak, 1 robe for G[ula]
[1 liner	n tunic, 1 scarf], 1 patinnu-belt, 1 nēbeļu-belt for Adad
[1 liner	n tunic, 1 <i>naḥlaptu</i> ]-cloak, 1 robe for the Šala.
<b>233.</b> BI 8.1 × 6.	<b>M 54227</b> (82-5-22, 378) .2 cm
	1'. [] <sup>r</sup> x <sup>1</sup> [x] <sup>r</sup> x <sup>1</sup> 2'. [2 GADA <i>sal-ḥu</i> 1 GADA <i>ḫu-la-nu</i> 1 GADA <i>gú</i> ]- <i>ḫal-ṣu</i> TÚG.MURUB <sub>4</sub> .ÍB.LÁ 3'. [x x x x x 1 <i>mu</i> ] <i>t-ta-tu</i> <sub>4</sub> <i>a-na</i> <sup>d</sup> UTU
	4'. [2 GADA <i>sal-ḫu</i> x TÚG].GÚ.UD.DU SÍG.「Ḥɹ.ME.DA 1 <sup>et</sup> [TÚG.GÚ.UD.D]U <i>bir-mu</i> 5'. [1 TÚG.GÚ.UD.DU SÍ]G.ḤÉ.ME.DA lu <sup>!</sup> (T: ṭu)-bar-「ri¹ SÍG.ḤÉ.ME.DA 「a-na¹ <sup>d</sup> A-a
	6'. [2 GADA sal-ḥu 4]+2 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA 2 ku-si-tu <sub>4</sub> 7'. [a-na <sup>d</sup> ]DUMU.MÍ.MEŠ É-babbar-ra
	8'. [1 GADA <i>sal-ḥu</i> 1 GA]DA <i>ḫu-la-nu</i> 1 GADA <i>gú-ḥal-ṣu</i> 1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 9'. [1 TÚG.ÍB.LÁ] <i>a-na</i> <sup>d</sup> ḤAR
Rev.	10'. [1 GADA <i>sal-ḥu</i> x+] 2 <i>-ta</i> TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA 11'. [1 <i>lu-b</i> ]a <sup>?-r</sup> ru <sup>?!-1</sup> a-na <sup>d</sup> GAŠAN UD.KIB.NUN <sup>ki</sup>
	12'. [1 GADA <i>sal-ḫ</i> ]u 1 <sup>et</sup> TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA 1 <sup>et</sup> ku-si-tu <sub>4</sub> 13'. [SÍG.ḤÉ].ME.DA <i>a-na</i> <sup>d</sup> Gu-la
	14'. [1 GADA <i>sal-ḫu</i> 1 GADA] <i>gú-ḫal-ṣu</i> 1 TÚG.MURUB <sub>4</sub> .LÁ:ÍB 1 TÚG.ÍB.LÁ 15'. <sup>[a¹-na d</sup> IM

16'. [1 GADA sal-hu 1 TÚG.GÚ.UD]. 「DU¹ 1 ku-si-tu4 a-na 17', [dŠa-la]

Note that there are a lot of mistakes in this text:

Ll. 4–5. We expect here the *naḥlaptus* in three colours (*tabarru*, *takiltu* and *birmu*). However, in 1. 5 instead of the expected takiltu (syllabically or ideographically) there is again SÍG.ḤÉ. ME.DA followed by lu-bar-ri with tu for lu and with bar-ri written over an erasure, most probably a mistake for the expected *kusītu*. Note that the whole line 5 is written over an erasure. L. 11'. the reading lu]- $^{1}ba^{2}-ru^{2}$  is very uncertain. The preserved part of  $ba^{2}$  is similar to

GIŠ and  $ru^{2}$  to the upper part of u (three vertical, and one horizontal stroke).

The quite important numbers of mistakes (ll. 4'-5,' 11', 14') suggests that the scribe had little experience in writing such texts. From this point of view the text reminds us of BM 61517 (= 292) (30.5.Cam 7) where the dullu peşû list is written without mistakes but there are many mistakes in the mihşu tenû list. Maybe the same scribe also wrote BM 68348+ (= 291) (5.7 [KN] 7), where the dullu pesû list is written without mistakes; also the mihsu tenû lists in this time are written only with small mistakes. However, while in the dullu peşû list the principle: one entry for a garment of one god (separated from other by dividing lines) is strictly observed, in the *miḥṣu tenû* list in this text there is no division into separate entries and the description of garments for another god starts in the same line as soon as the list of garments for the previous god ended, whereas normally this started with a new line. All this suggests that the scribe who wrote this text had experience only with dullu pesû texts.

[2 linen tunics, 1 linen hullānu-cloak, 1 linen sc]arf, 1 patinnu-belt [...., 1] muttatuheaddress for Šamaš

[2 linen tunics, x] red nahlaptu-cloaks, 1 multicoloured [nahlap]tu-cloak, 1 bluepurple! *nahlaptu*-cloak, <1> red robe?! for Aya

[2 linen tunics, 4]+ 2 red < nahlaptu>-cloaks, 2 robes [for] the Daughters of the Ebabbar

\_\_\_\_\_

[1 linen tunic, 1 lin]en hullānu-cloak, 1 linen scarf, 1 patinnu-belt, [1 nēbehu]-belt for Bunene

[1 linen tunic, x]+ 2 red *nahlaptu*-cloaks, 1 robe?! for the Queen of Sippar

[1 linen tuni]c, 1 red nahlaptu-cloak, 1 [re]d robe for Gula

[1 linen tunic, 1 linen] scarf, 1 patinnu-belt, 1 nēbehu-belt for Adad

[1 linen tunic, 1 nahlap]tu-cloak, 1 robe for [Šala].

**234. CT 55, 826** = BM 58456

 $6.2 \times 2.7 \text{ cm}$ 

1'.  $[x \times x] mu-ut$ - $[ta-tu_4 a]$ -[na dUTU]Obv.

2'. [2] GADA sal-hi 5 na-hal-lap-tu<sub>4</sub> SÍG.[HÉ.ME.DA]

$3'. 1^{et}$ na-ḥal-lap-tu <sub>4</sub> bir-mu $1^{et}$ k[u-si-tu <sub>4</sub> a-na <sup>d</sup> A-a]
4'. <sup>[2</sup> GADA <i>sal</i> <sup>1</sup> - <i>ḫi</i> 6 <i>na-ḫal-lap-tu</i> <sub>4</sub> 2 <sup>[túg</sup> ][ <i>ku-sa-tu</i> <sub>4</sub> <i>a-na</i> <sup>d</sup> GAŠAN.MEŠ]
5'. [] <sup>r</sup> x x x <sup>1</sup> [] Rest Obv. and Rev. lost
, 1] muttatu-headdress fo[r Šamaš]
2] linen tunics, 5 r[ed] <i>naḥlaptu-</i> cloaks, 1 multicoloured <i>naḥlaptu-</i> cloak, 1 r[ob for Aya]
2 linen tunics, 6 <i>naḥlaptu-</i> cloaks, 2 [robes for Ladies].
<b>235. BM 83395</b> (83-1-21, 1119)
1'. [] <sup>r</sup> x x <sup>1</sup> [] 2'. [ U <sub>4</sub> .x+ <sup>?</sup> ].2.KAM M[U <sup>?</sup> ]
3'. [2] GADA sal-ḫi 1 ḫu-ul-la-[nu 1 GADA gú-ḥal-ṣu] 4'. [1 p]a-ti-in 1 <sup>et [</sup> mu <sup>¬</sup> -ut- <sup>[</sup> ta-tu <sub>4</sub> <sup>¬</sup> [(x x x) šá <sup>d</sup> UTU]
5'. [2 GAD]A sal-ḥi 4 na-aḥ-lap-tu₄¹ na-ba-[su] 6'. [1 n]a-aḥ-lap-tu₄ bir-mu <1> ku-si-t[u₄ 7'. [mi²]-iḥ-ṣu šá dA-a
8'. [1 GADA <i>sal-\hat{h}</i> ]i 1 <sup>en</sup> \hat{h}u-ul-la-nu 1 <sup>en</sup> [] 9'. unreadible upper part of 4-5 signes 10'. nothing exists 11'. nothing exists 12'. [x x x] \hat{sa} []
13'. [x GADA <i>sa</i> ] <i>l-hi</i> 3 [] 14'. [x x] <sup>r</sup> x x x <sup>1</sup> []
15'. [x GADA sa]-hi 1 []
] 2 <sup>?nd</sup> [day], ye[ar]
2] linen tunics, 1 <li>1 <li>2] linen tunics, 1 <li>2] linen scarf, 1 p]atinnu-belt, 1 muttatuneaddress [for Šamaš]</li></li></li>

```
[2 line]n tunics, 4 red nahlaptu-cloaks, [1] multicoloured nahlaptu-cloak,
<1> [wo]ven robe for Aya
[x linen tuni]c, 1 hullānu-cloak, 1 [....]
[x linen tun]ic, 3 [naḥlaptu-cloaks, ....]
[x linen tun]ic, 1 [....].
236. BM 61956 (82-9-18, 1925)
6.3 \times 6.5 cm
             1'. [1 \ mu]t^{?}-\lceil ta^{\rceil}-tu_4 \lceil x^{\rceil} [....]
             2'. [2 GADA] [sal-hu 4] [TÚG. GÚ.UD.DU SÍG.HÉ.ME.DA]
             3'. [1^{et}] TÚG.[GÚ.UD.DU] [bir^1-mu [1^{et}] [a-na] [a-na] [a-na]
             4'. 2 GADA sal-hu 6 túgna-hal-lap-tu4
             5'. 2-ta ku-sa-a-t[u4 a]-na <sup>d</sup>DUMU.MÍ.MEŠ 「É-babbar-ra<sup>¬</sup>
            6'. 1 GADA sal-ḫu 1 <sup>túg</sup>ḫu-la-nu 1 <sup>túg</sup>gú-ḫal-ṣu 7'. 1 <sup>túg</sup>pa-t[i-i]n-nu 1 <sup>túg</sup>ſni¹-bi-「ḫu¹ a-na <sup>d</sup>ḤAR
             8'. [x GADA] sal-h[u x]^{túg}na-hal-lap-tu_4 [...]
             9'. [x GADA sal-hu x <sup>túg</sup>] na-hal-[lap-tu<sub>4</sub> ....]
Rest of Obv. lost
Rev. in preserved part uninscribed
[...., 1] muttatu-headdress [for Šamaš]
[2 linen] tunics, 4 red nahlaptu-cloaks, [1] [multicoloured] na[hlaptu]-cloak,
1 robe [for Aya]
2 linen tunics, 6 nahlaptu-cloaks, 2 robes for the Daughters of the Ebabbar
1 linen tunic, 1 hullānu-cloak, 1 scarf, 1 patinnu-belt, 1 nēbehu-belt for Bunene
[x linen] tuni[cs, x] naḥlaptu-cloaks, [....]
[x linen tunic, x] nah[laptu-cloak, ....].
```

PLATE 54

**237. BM 61785+BM 66800** (82-9-18, 1754+6793)

## $7.4 \times 9.0$ (thick 3.2) cm [x.x]. $\lceil Dar \rceil [x]$ 1. [.... <sup>m</sup>] 「Da-ri¬-[iá-muš] 2. [LUGAL TIN.TIR]<sup>ki</sup> LUGAL KUR.K[UR] -----3. [2] GADA sa-al-ah a-na <sup>d</sup>[UTU] 4. [1] GADA *hu-la-an-na a-na* <sup>d</sup>UT[U] 5. $[1^{t\acute{u}}]^g gu-ha-as$ (erasure) 6. $[1^{en}]^{u}$ 7. [1<sup>en</sup> $t^{\text{túg}}ni$ ]- $^{\Gamma}bi$ ]-iha-na <sup>d</sup>UTU 8. [2 GADA] $sa^{-1}al^{-1}-ah$ $a-na^{-1}A-a$ 9. [4] na-aḥ-la-ap-<sup>r</sup>tu<sub>4</sub> na-ba<sup>¬</sup>-as-su na-「aḫ¹-la-ap-ta bir-ri 10. [1] ku-s]i-ti a- ${}^{\mathsf{L}}$ na ${}^{\mathsf{L}}$ A-a11. [1 12. [x GADA] sa-al-ah a-n[a $^{d}DN]$ 13. [x] $\lceil na-ah\rceil$ -la-ap-t[ $u_4$ ....] 14'. [....] 「x¹ [....] 1'. [1] $\int_{0}^{t \cdot g} pa-ti-in [a-na]^{d} Bu-ne-ne$ Rev. 2'. $[2^{?}]$ GADA sa-a[l]-ah [....] $\lceil x \ x \ x \ x \rceil$ 2a'. 3'. 3 $^{\text{túg}}$ na-ah-la-[ap-t]u<sub>4</sub> na-ba-su 4'. 1 na-ah-la-[ap- $t]u_4$ ta-kil- $tu_4$ 5'. 1 na-ah!-la-ap-[tu<sub>4</sub> bi]r-ri 6'. 1 lu-ba-<sup>[</sup>ri<sup>1</sup> pa-<sup>[</sup>ni<sup>?</sup>] [....] 7'. [1 ku-s]i-tu<sub>4</sub> šá <sup>d</sup>GAŠAN UD.[KI]B.NUN<sup>ki</sup> -----7'. 「2¹ GADA sa-al-「aḫ a¹-[na] $^{\mathrm{d}!}$ A-nu-ni-tu $_4$ 8'. 2 na-aḥ-<la>-ap-ta-na [....] 9'. 1 <sup>rsíg</sup>hu<sup>¬</sup>-la-an-na [....] [....] Dar[ius, king of Babylon], king of Lan[ds] [2] linen tunics for [Šamaš] [1] linen *hullānu*-cloak for Šam[aš] [1] scarf [1] patinnu-belt [1] *nēbeḥu*-belt for Šamaš [2 linen] tunics for Aya

[4] red nahlaptu-cloaks

[1] multicoloured <i>naḥlaptu</i> -cloak [1 ro]be for Aya
[x lin]en tunic for [] [x] naḥlaptu-cloak(s) []
[1] patin[nu-belt for Bunene]
[2 <sup>2</sup> ] linen tunics [] 3 red <i>naḥlaptu</i> -cloaks 1 blue-purple <i>naḥ[laptu</i> ]-cloak 1 [multicolou]red <i>naḥlaptu</i> -cloak 1 <i>lubār pāni</i> -veil [] [1 ro]be for the Queen of Sippar
2 linen tunics for Anunītu 2 <i>naḥlaptu-</i> cloaks 1 <i>ḫullānu-</i> cloak [].

### 9. Garments for not recognized *lubuštu* ceremony

# **238. BM 70834** (82-9-18, 10835) $5.3 \times 3.5$ cm 27.[x].Nbn 6 1. [mi-iḫ-ṣu te-nu-ú šá lu-bu-uš-tu4 šá] a-na <sup>md</sup>UTU-NUMUN- $G\acute{A}L^{\check{s}i}$ 2. [ $^{\text{l\'u}}$ TÚG.BABBAR SUM $^{na}$ ITI.x U<sub>4</sub>].27.KAM MU.6.KAM $^{md}AG\text{-I LUGAL }E^{ki}$ 3. [2 GADA sal-hi 1 GADA hu-(ul)-l]a-nu 1 GADA gú-hal-șu 4. [1 *ni-bi-hu* ....] [x] *a-na* dUTU 5. [2 GADA sal-hi 4 na-hal-lap-tu<sub>4</sub> SÍG.H]É.ME.DA 6. [1 na-hal-lap-tu<sub>4</sub> bir-mu 1 ku]-<sup>r</sup>si<sup>1</sup>-tu<sub>4</sub> šá <sup>d</sup>A-a Rest lost Rev. in preserved part uninscribed [Woven garments for the change for the *lubuštu* ceremony were given] to Šamašzēr-ušabši, [the *ašlāku*. Month x], 27<sup>th</sup> day, 6<sup>th</sup> of Nabonidus, king of Babylon. · [2 linen tunics, 1 linen hull]ānu-cloak, 1 linen scarf, [1 nēbehu-belt ....] for Šamaš ------[2 linen tunics, 4 r]ed [nahlaptu-cloak, 1 multicoloured nahlaptu-cloak, 1 ro]be for Aya. 239. BM 71925 (82-9-18, 11928) $6.7 \times 5.9$ cm Nbn 15 1. [mi]- $\dot{h}i$ - $\dot{s}i$ te-[nu]- $[\acute{u}$ $\check{s}\acute{a}$ lu-bu- $u\check{s}$ -tu4 ....] 2. $[a-n]a^{m}Ba-la-tu^{1\acute{u}}T[\acute{u}G.BABBAR]^{r}SUM^{nu_{1}}[ITI.x]$ $U_4.x.KAM$ 3. $\lceil MU \rceil$ .15.KAM $\rceil$ $\rceil$ $\rceil$ AG- $\rceil$ IN $\rceil$ TUKU $\rceil$ LUGAL TIN.T[IR $\rceil$ IN $\rceil$ 4. 「2」 GADA sal-ḥu 1 GADA ḥu-la-nu 1 $^{\text{túg}}g\acute{u}$ ?-[ḥal-ṣu] 5. 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ¹ TX X X X¹ *a-na* T<sup>d</sup>¹UTU

6. 2 GADA sal-hu 1<sup>et</sup> 「GÚ.UD.DU<sup>¬</sup> [....]

7.  $1^{et}$  ku-si-tu<sub>4</sub> [a-na <sup>d</sup>A-a]

- 8. 2 GADA sal-hu <sup>[6</sup> TÚG<sup>]</sup>.GÚ.UD.DU [SÍG].HÉ.M[E.DA 2 ku-si-tu<sub>4</sub> 9. a-na <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-ra 10. 1 GADA sal-ḥu 1 GADA ḥu-la-n[u 1 ni-bi-ḥu] 11. [1 GADA] gú-ḥal-ṣu a-na <sup>d</sup>[Bu-ne-ne] \_\_\_\_\_ 12. [1 GADA sal]-hu 3 TÚG. GÚ. UD. DU [SÍG. HÉ. ME. DA] 13. [1 TÚG.G]Ú.UD.D[U SÍG.ZA.GÌN.KUR.RA 1 TÚG.GÚ.UD.DU] 14. [bir-mu 1<sup>et</sup> ku-si-tu<sub>4</sub> a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>] Rev. (nothing over line is preserved, but probably one line with the garments for Gula is missing) 1'. 1 GADA sal-h[u] 1 TÚG.ÍB.LÁ 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ SÍG.Ḥ[É.ME.DA] 2'. 1 GADA gú-ḥal-ṣu a-na <sup>d</sup>IM \_\_\_\_\_\_ 3'. 1 GADA sal-hu 1et TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA 4'. 1<sup>et</sup> ku-si-tu<sub>4</sub> a-na <sup>d</sup>Ša-la Obv. is heavily eroded. L. 5. After TÚG.MURUB<sub>4</sub>.ÍB.LÁ one can read TÚG.ÍB.LÁ, however only a tiny part of the upper part of the signs are preserved, which makes identification of the signs uncertain; additionally the text is written with very small wedges.
- Woven garments for the change [for the lubuštu ceremony ....] were given to

Balāṭu, [the ašlāku. Month x, n<sup>th</sup> day], 15<sup>th</sup> year of Nabonidus, king of Babylon \_\_\_\_\_\_

2 linen tunics, 1 linen hullānu-cloak, 1 sc[arf], 1 [....] patinnu-belt for Šamaš ·

2 linen tunics, 1 [....] nahlaptu-cloak, [....], 1 robe [for Aya]

2 linen tunics, 6 <sup>red¹</sup> nahlaptu-cloaks, [2 robes] for the Daughters of the Ebabbar

\_\_\_\_\_

1 linen tunic, 1 linen *hullānu*-cloak, [1 *nēbehu*]-belt, 1 linen scarf for [Bunene]

[1 linen tun]ic, 3 [red] nahlaptu-cloaks, [1 blue-purple] nahlaptu-cloak, [1 multicoloured *nahlaptu*-cloak, 1 robe for the Queen of Sippar] (Probably one line, where the garments for Gula were counted, is missing)

-----

1 linen tunic, 1 nēbeḥu-belt, 1 r[ed] patinnu-belt, 1 scarf for Adad

1 linen tunic, 1 red *nahlaptu*-cloak, 1 robe for Šala.

## **240. BM 99951** (83-1-21, 2313)

 $2.5 \times 5.7$  cm

 $28.6^{?}.[x]$ 

- 1. [mi-ih-ṣu te-nu-ú šá lu]-bu-uš-tu4 [šá ITI.x]
- 2. [.... ITI.K]IN<sup>?</sup> U<sub>4</sub>.28.KAM 「MU¹.[x.KAM]
- 3. [2 GADA sal-ḥi 1 GADA ḥu-la-nu 1] GADA gú-ḥal-ṣ[u]
- 4. [1 *ni-bi-ḫu*] *a-na* <sup>d</sup>U[TU]
- 5. [2 GADA *sal-ḥi* 4 TÚG.GÚ.UD.DU SÍG.Ḥ]É.ME.DA 1 <TÚG>.GÚ.UD.[DU *bir-mu*]
- 6. [1 ku-si-tu<sub>4</sub> SÍG.ḤÉ].ME.DA a-na <sup>d</sup>[A-a]
- 7. [2 GADA sal-hi 6 TÚG.GÚ.UD.DU SÍG.H]É.ME.DA 2-ta
- 8. [ku-si-tu<sub>4</sub> a-na <sup>d</sup>DUMU.MÍ.MEŠ É-babba]r-ra
- 9. [1 GADA sal-ḥi 1 GADA ḥu-la-nu] 1 GADA gú-ḥal-ṣu
- 10. [1 *ni-bi-ḥu a-na*] <sup>d</sup>*Bu-ne-*[*ne*]
- 12. [....] <sup>r</sup>x<sup>1</sup> [....]

Rest lost

Rev. in preserved lower part is uninscribed

L. 11–12. One can expect here the list of garments for the Queen of Sippar.

[Woven garments for the change for the  $lu]bu\check{s}tu$  ceremony [.... Month Ulū]lu,  $28^{th}$  day, [ $n^{th}$  year ....].

- [2 linen tunics, 1 linen *hullānu*-cloak, 1] linen scarf, [1 *nēbehu*]-belt for Ša[maš]
- [2 linen tunics, 4] <sup>rred¹</sup> [naḥlaptu]-cloaks, 1 [multicoloured] naḥlaptu-cloak, [1 re]d [robe] for [Aya]
- [2 linen tunics, 6 r]ed [nahlaptu-cloaks, 2 [robes for the Daughters of the Ebabbar]
- [1 linen tunic, 1 linen *ḫullānu*]-cloak, 1 linen scarf, [1 *nēbeḫu*-belt for] Bunene
- [2<sup>?</sup> linen tunics, 3] <sup>red¹</sup> [naḥlaptu]-cloaks, [....].

## **241. BM 70999** (82-9-18, 11001)

 $3.3 \times 3.3$  cm

Nbn

- 1. mi-ih-șu te-[nu-ú šá lu-bu-uš-tu šá ITI.x a-na PN]
- 2.  $^{\text{lú}}$ TÚG.BABBAR SUM $^{na}$  I[TI. x U<sub>4</sub>.x.KAM MU.x.KAM]

	3. <sup>md</sup> AG-I LU[GAL <i>Bābili</i> ]
	4. 2 GADA <i>sal-ḥi</i> 1 [GADA <i>ḫu-la-nu</i> 1 GADA <i>gú-ḫal-ṣu</i> ] 5. 1 <sup>en</sup> ni-bi-[ḥu] 6. 「x¹ 1 <sup>en túg</sup> []
	7. [2 GADA <i>sal</i> ]- <i>hi</i> []
Rest lost Rev.	1'. 「2 GADA sal-ḫi 1 <sup>et</sup> na-x¹ []
Woven ga given to Babylon].	arments for the cha[nge for the <i>lubuštu</i> ceremony of the month x] were [PN], the $a\bar{s}l\bar{a}ku$ . M[onth x, n <sup>th</sup> day, n <sup>th</sup> year] of Nabonidus, ki[ng of
2 linen t	unics, 1 [linen <i>hullānu</i> -cloak, 1 linen scarf], 1 <i>nēbe</i> [hu]-belt, [], Šamaš]
[2 linen tu	ın]ics, []
2 linen tui	n]ics, 1 naḫ[laptu-cloak].
	<b>67149+BM 99925</b> PLATE 55 7145+83-1-21, 2287)
	Cyr 7
	1. [mi-iḫ-ṣ]u te-nu-ú šá l[u-bu-uš-tu <sub>4</sub> šá ITI.x] 2. [MU.x.KA]M a-na <sup>md</sup> UTU-MU-MU <sup>lú</sup> [TÚG.BABBAR SUM <sup>na</sup> ] 3. [ITI.x U <sub>4</sub> .x.KA]M MU.7.KAM <sup>m</sup> Ku-raš LUGAL TIN.「TIR <sup>ki</sup> ] [LUGAL KUR.KUR]
	4. [2 GADA sa]l-ḥu 1 GADA ḥu-la-nu 「1 GADA gú-ḥ[al-ṣu] 5. [1 p]a-te-en TÚG.SAG <sup>?!</sup> 2 <sup>túg</sup> 「ṣib -bá-tu4 a-[na dUTU]
	6. [2 GADA <i>sa</i> ] <i>l-ḫu</i> 4- <i>ta</i> <gú.ud.du.a> SÍG.ḤÉ.ME.DA 1<sup>et</sup> TÚG.GÚ.UD.D[U <i>bir-mu</i>] 7. [1 <i>k</i>]<i>u-si-tu</i><sub>4</sub> 2 TÚG.BAR.S[I].MEŠ <i>a-na</i> <sup>d</sup>A-<i>a</i></gú.ud.du.a>
	8. [2 GADA sa]l-ḫu 6-ta GÚ.UD.ʿDUʾ.A SÍG.ḤÉ.ME.DA 2-ta ku-sa-tu <sub>4</sub> 9. ʿaʾ-na <d>DUMU.MÍ.<meš> ʿÉʾ-babbar-ra</meš></d>
Rest lost	10. [1 GADA sal-ḫu 1 GA]DA ʿḫu-la¹-[nu 1 GA]DA ʿgú-ḫal-ṣu¹ []

1'. [....] [x] [(x x)] Rev. d[GAŠA]N Sip-par [ki] 3'. [x GADA sal-hu] 「1<sup>et</sup>] G[Ú.UD.DU.A SÍG.HÉ.ME].「DA]  $1^{et} ku$ -si- $tu_4$ a-na [ $^{d}Gu$ -la] 5'. [1 GADA sa]l-hu 1 GADA gu-hal-[su x x] [x pa-te]-e[n]6'. [1 TÚG.Í]B.LÁ *a-na* 1<sup>en</sup> [x x].HI.A [a]-[na dIM] \_\_\_\_\_ 7'. [1 GADA sa]l-hu 1 GADA GÚ.「UD.DU.A」 [SÍG.H]É.ME.DA [1 ku-si-tu<sub>4</sub>] a-na <sup>d</sup> $\check{S}[a$ -la]8'. L. 5. The shape of the sign transliterated as SAG? is exactly the same as in Cyr 241: 4.

[Wove]n garments for the change for the lu[buštu ceremony for the month x, n<sup>th</sup> day were given] to Šamaš-šum-iddin, [the ašlāku. Month x, n<sup>th</sup> day], 7<sup>th</sup> year of Cyrus, king of Babylon, [king of Lands].

[2 linen tun]ics, 1 linen hullānu-cloak, 1 linen sc[arf, 1 p]atinnu-belt, the SAGgarment, 2 *şibtu*-garments fo[r Šamaš]

[2 linen tun]ics, 4 red <nahlaptu>-cloaks, 1 [multicoloured] nahlaptu-cloak, [1 ro]be, 2 paršīgu-headdresses for Aya

[2 linen tun]ics, 6 red *nahlaptu*-cloaks, 2 robes for the Daughters of the Ebabbar

[1 linen tunic, 1 lin]en hullā[nu-cloak, 1 lin]en scarf [.... for Bunene]

[.... for] the Queen of Sippar

[x linen tunic(s)], 1 re[d nahlap]tu-cloak, 1 robe for [Gula]

[1 linen tun]ic, 1 linen sca[rf],  $^{\dagger}$ 1 patinnu-belt, [1  $n\bar{e}$ ]behu-belt for [.... Adad]

[1 linen tun]ic, 1 red linen *nahlaptu*-cloak, [1 robe] for the Š[ala].

#### **243. BM 70916** (82-9-18, 10918)

9.  $3 \times 5.4$  cm

Fragment of a very large tablet, badly preserved (central part of tablet is fully detached).

- 1. mi-iḥ-iṣ te-[nu-ú šá l]u-bu-uš-[tu4 šá U4.x.KAM šá ITI.x]
- 2. [a-na <sup>md</sup>]UTU-MU-MU <sup>lú</sup>TÚG.BABBAR SUM<sup>nu</sup>

## 'ITI'.[x U<sub>4</sub>].8.'KAM' M[U.x.KAM] 3. <sup>m</sup>Ku-ra-áš LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR 4. 2 GADA s[al-hu 1 GADA hu-ul]-[la1-[nu 1] GADA gú-[hal]-su 1 TÚG.[....] 5. 2 'TÚG' [....] <sup>d</sup>UTU -----6. <sup>[2]</sup> [GADA sal-hu 4 TÚG.GÚ.UD.DU.A SÍG]. <sup>[</sup>HÉ.ME.DA] 1<sup>et</sup> TÚ[G.GÚ.UD.DU] 7. [bir-mu 1 ku-si-tu4] 2 TÚG.B[AR]. $^{\Gamma}SI^{\Gamma}$ a-na $^{d_{\Gamma}}A^{\Gamma}$ -[a] 8. [2<sup>?</sup> GADA sal-hu 3] TÚG.GÚ. 「UD.DU.A SÍG.HÉ.ME.DA šá¹ [....] 9. [....] <sup>r</sup>UD<sup>?</sup>.DU<sup>?</sup><sup>1</sup> [....] [a]- $\lceil na \rceil$ dIM Rev. 1'. 2'. [1 GADA sal-hu] 1 TÚG.GÚ.UD.DU.A SÍG.HÉ.ME.DA $[1 ku-si-tu_4]$ 「а¬-na <sup>d</sup>Ša-la 3'. Rest of rev. uninscribed Ll. 8–9 concern the garments for the Daughters of the Ebabbar. Woven garments for the cha[nge for the lu]buš[tu ceremony for the month x, nth day] given [to] Šamaš-šum-iddin, the ašlāku. Month [x,] 8th day, [nth ye]ar of Cyrus, king of Babylon, king of Lands 2 linen tu[nics, 1 linen hul]lā[nu]-cloak, [1] linen scarf, 1 [....], 2 [.... for] Šamaš 2 [linen tunics, 4] red [nahlaptu]-cloaks, 1 [multicoloured] na[hlaptu-cloak, 1 robe], 2 <sup>r</sup>paršīgu¹-headdresses for A[ya] [2<sup>?</sup> linen tunics, 3] red *naḥlaptu*-cloaks, [....] [.... f]or Adad [1 linen tunic], 1 red *naḥlaptu*-cloak, [1 robe] for Šala. **244. BM 68670** (82-9-18, 8669) $5.2 \times 4.8 \text{ cm}$ 1. <sup>r</sup>mi-iḥ-ṣu<sup>1</sup> te-nu-ú šá [lu-bu-uš-tu4 a-na] 2. ${}^{m}\Gamma^{d}U+GUR^{1}-MU SUM\Gamma^{na_{1}}$ [ITI.x U<sub>4</sub>.x.KAM] 3. MU.13+x. [KAM md][DN-....] Rest of obv. completely damaged. 1'. Nothing preserved Rev. 2'. 2 GADA sal-hi [3 na-hal-lap-tu<sub>4</sub> SÍG.HÉ.ME.DA] 3'. 1<sup>et</sup> na-hal-lap-<sup>r</sup>tu<sub>4</sub><sup>1</sup> [SÍG.ZA.GÌN.KUR.RA]

Woven garments for the change [for the *lubuštu* ceremony] given to Nergal-iddin. [Month x,  $n^{th}$  day], year 13+[x ....]

2 linen tunics, [3 red *naḥlaptu*-cloaks], 1 [blue-purple] *naḥlaptu*-cloak, <1> multicoloured *naḥlaptu*-cloak, 2 *paršīgu*-headdresses, [<1> robe] for the Queen of Si[ppar]

-----

1 linen tunic, 1 *naḥlaptu*-cloak, 1 ro[be for Gula]

1 linen tunic, 1 linen scarf, <1>  $n\bar{e}beb[u$ -belt for Adad]

1 linen tunic, 1 nahlap]tu-cloak, <1> ro[be] for Šala.

#### **245. BM 101251** (83-1-21, 2912)

PLATE 56

 $3.5 \times 2.7$  cm

- 1. mi-iḥ-ṣi te-[nu-ú ....]
- 2. šá lu-bu-uš-tu<sub>4</sub> [šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> šá Sip-par<sup>ki</sup>
- 3.  $\check{s}\acute{a}^{d}A$ -nu-ni- $tu_4$  [ $\check{s}\acute{a}^{m(d)}$ x x x]
- 4. lúTÚG.BABBAR SUM<sup>nu</sup> ITI.[x U<sub>4</sub>.x.KAM]
- 5. 「MU.2.KAM <sup>md?</sup>x x¹[....]

Rest lost

Rev.

- 1. 1 'TUG.UD.A SÍG.Ḥɹ.[ME.DA]
- 2. TÚG.UD.A me-tu '\hat{u}\] [TÚG.UD.A ku-lu-lu]
- 3. SÍG.ZA.GÌN.KUR.RA [....]
- 4. 1 TÚG.BAR.SI SÍG.HÉ.[ME.DA]
- 5. ú-x-da-áš [....]

Rev. 5. The second sign is written over an erasure and for this reason it is difficult to identify.

Woven garments for the chan[ge] for the *lubuštu* ceremony [of Anunītu-ša-Sippar]-Anunītu, [were given to PN], the  $a \check{s} l \bar{a} k u$ . Month [x, n<sup>th</sup> day],  $2^{nd}$  year of [....]

[....] red *lubāru*-garment, the blue-purple *lubār mēṭu* and [*lubār kulūlu*]-headbands, 1 red *paršīgu*-headdress [....].

# **246. BM 64469** (82-9-18, 4449) $8.1 \times 3.5 \text{ cm}$ 1'. [2 GADA sal-hi x-t]a 'TÚG.GÚ.UD.DU SÍG.Hɹ.[ME.DA] 2'. [1 k]u-si-tu<sub>4</sub> šá $[{}^{d}A$ -a] 3'. [2] GADA sal-hu 6 TÚG.GÚ.UD.DU SÍG.HÉ.ME.「DAT $[2 ku-si-tu_4]$ 4'. šá <sup>d</sup>DUMU.MÍ.MEŠ É-[babar-ra] 5'. 1 GADA sal-hu 1 GADA hu-la-nu 1 GADA gú-hal-șu [1 TÚG.ÍB.LÁ] 6'. 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ šá <sup>d</sup>Bu-ne-ne 7'. 1 GADA sal-hu 1 GADA gú-hal-șu 1 TUG.ÍB.LÁ 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ šá <sup>d</sup>IM 8'. 9'. 1 GADA sal-hu 1et TÚG.GÚ.UD.DU SÍG.HÉ.ME.[DA] Rev. 10'. 「1<sup>et</sup>」 ku-si-tu<sub>4</sub> SÍG.ḤÉ.ME.DA šá <sup>d</sup>Ša-[la] Rest of Rev. uninscribed [2] tunics, x] [red] nahlaptu-cloaks, [1 ro]be for [Aya] [2] linen tunics, 6 red *nahlaptu*-cloaks, [2 robes] for the Daughters of the E[babbar] 1 linen tunic, 1 linen hullānu-cloak, 1 linen scarf, 1 [nēbeḥu-belt], 1 patinnu-belt for Bunene 1 linen tunic, 1 linen scarf, 1 nēbeļu-belt, 1 patinnu-belt for Adad 1 linen tunic, 1 red *nahlaptu*-cloak, 1 red robe for the Ša[la]. **247. BM 69843** (82-9-18, 9843) $5.5 \times 2.7 \text{ cm}$ 1'. [...] [x] 1 [pa-tin-nu] [...]2'. [2 GADA sal-hu] 「5¬ na-hal-lap-tu4 1<sup>et</sup> na-hal-lap-t[u4 bir-mul

3'.  $[1 ku-s]i-tu_4 a-na {}^{d}A-a$ 

```
4'. [1 GADA sal-hu] <sup>[1]</sup> GADA hu-ul-la-nu 1 g[ú-hal-su]
            5'. [x \times x \times 1]^{\lceil pa-tin-ni^{\rceil}} [x]^{\lceil x^{\rceil}} [...]
Rev. completely lost
[...., 1 patinnu-belt [....]
[2 linen tunics], 5 red nahlaptu-cloaks, 1 [multicoloured] nahlap[tu-cloak, [1 ro]be
[1 linen tunic], 1 linen hullānu-cloak, 1 s[carf ...., 1] patinnu-belt, [....].
248. BM 70544 (82-9-18, 10545)
3.6 \times 3.8 (thick ca. 3 cm)
            1'. [....] <sup>[</sup>x x<sup>1</sup> [....]
            _____
            2'. [1 GADA sal-hu 1 GADA hu-la-nu] 1 GADA gú-hal-şu
            3'. [.... 2] <sup>túg</sup>ṣi-bat-tu<sub>4</sub>
            4'. [TÚG.MURUB<sub>4</sub>.ÍB.LÁ SÍG].ḤI<sup>!</sup>.ME.DA a-na <sup>d</sup>UTU
            5'. [.... SÍG.ḤÉ].ME.DA
            6'. [....] TÚG.[x x]
            7'. [.... TÚG.GÚ.UD.D]U SÍG.HÉ.ME.「DA1
Edge
            8'. [....] <sup>rd</sup><sup>1</sup>DUMU.MÍ.MEŠ É-babbar-<sup>r</sup>ra<sup>1</sup>
            9'. [1 GADA sal-hu 1 GADA hu-la-nu] 1 GADA gú-hal-su
Rev.
           10'. [1 TÚG.ÍB.LÁ a-na] <sup>d</sup>IM
           11'. [.... TÚG.GÚ.UD.D]U SÍG.HÉ.ME.DA
           12'. [.... T]ÚG.GÚ.UD.DU SÍG.ZA.GÌN.<KUR>.RA
           13'. [....]-^{\Gamma}tu_4^{\Gamma} [....]
L 4. Instead HÉ.ME.DA there is clear HI.ME.DA, cf. BM 72305 (= 209): 6, 8.
[1 linen tunic, 1 linen hullānu-cloak], 1 scarf [...., 2] sibtu-garments [.... r]ed
[patinnu-belt] for Šamaš
[.... red [nahlapt]u-cloaks [.... for] the Daughters of the Ebabbar
[1 linen tunic, 1 linen hullānu-cloak], 1 linen scarf, [1 nēbehu-belt for] Adad
[....] red [nahla]ptu-cloak [....] blue-purple nahlaptu-cloak, [....].
```

# **249. BM 73072** (82-9-18, 13082) $5.2 \times 5.7$ cm 1'. [....] 「1et TÚG.BAR.DUL81 2'. [(....) *a-na*] <sup>d</sup>*A-a* 3'. [1 GADA sal-h]u 1 GADA hu-ul-la-nu 4'. [1 GADA $g\acute{u}$ -ha]l-su 1 TÚG.MURUB $_4$ !ÍB.LÁ $^{t\acute{u}g}$ ni-bi-h[u] $\lceil a \rceil$ -na <sup>d</sup>Bu-ne-ne 5'. 6'. [2 GADA sal]-hu 6 < TÚG>.GÚ.UD.DU.A [SÍG.HÉ.ME.DA] 7'. [2 TÚG.BAR.D]UL<sub>8</sub>.MEŠ a-na <sup>d</sup>DUMU.MÍ.<MEŠ> É-[babbar-ra] 8'. [2 GADA sal]-hu 3 TÚG.GÚ.UD.'DU'.[A SÍG.HÉ.ME.DA] 9'. [1 TÚG.GÚ].UD.DU.A 'SÍG'.[ZA.GÌN.KUR.RA] 10'. [1 TÚG.GÚ.UD].DU.A [bir-mu] 11'. [.... lu-bar pa]-ni 「1<sup>et</sup>」 [....] 12'. [....] šá <sup>d</sup>GAŠAN Sip-[par<sup>ki</sup>] 13'. [1 GADA sal]-hu 5 TÚG.G[Ú.UD.DU.A Rev. 14'. [....] $[x \ x]$ [....] 15'. [1 GADA *sal*]-*hu* <sup>г</sup>х х<sup>¬</sup> *ku* [....] 16'. fully eroded 17'. fully eroded 18'. fully eroded 19'. [....] TÚG.ÍB.L[Á] 20'. [....] <sup>d</sup>IM L. 4. Between TÚG and ÍB there is only one vertical wedge. [...], 1 robe $[(x \times x) \text{ for}]$ Aya [1 linen tuni]c, 1 linen hullānu-cloak, [1 linen sca]rf, 1 patinnu-belt, <1> nēbehubelt for Bunene [2 linen tun]ics, 6 [red] nahlaptu-cloaks, [2 rob]es for the Daughters of the E[babbar] [2 linen tun]ics, 3 [red] nahlaptu-cloaks, [1 blue-purple nahla]ptu-cloak, [1 multicoloured *naḥlap]tu*-cloak, [...., the *lubār pā]ni*, 1 [....] for the Queen of Sip[par] [1 linen tun]ic, 5 nah[laptu]-cloaks [....]

[1 linen tun]ic, [....]

[.... nēbeḥu-belt [.... for] Adad.

```
250. BM 59277 (82-7-14, 3636)
```

```
1. mi-ih-su te-nu-u1 [šá lu-bu-u8-tu4 šá ITI.x U4.x.KAM a-na PN]
```

2.  $^{\text{l\'u}}$ TÚG.BABBAR SUM $^{na}$  ITI.NE [U<sub>4</sub>.x.KAM MU.x.KAM ....]

3. 2 GADA *sal-hi* 1 *hu-ul-l*[*a-nu* ....]

4. 1 pa-tin-nu 1  $\lceil gu^{\uparrow}$ - $\lceil hal$ -su .... a-na  $^d$ UTU]

-----

5. 1 [....]

Rest lost

Woven garments for the change [for the  $lubu\check{s}tu$  ceremony of the month,  $n^{th}$  day] were given to [PN], the  $a\check{s}l\bar{a}ku$ . Month of Abu, [....]

2 linen tunic, 1 linen hul[lānu-cloak], 1 patinnu-belt, 1 sc[arf .... for Šamaš]

------1 [....].

### **251. BM 99494** (83-1-21, 1856)

 $4.8 \times 4.2$  cm

Fragment of thick tablet (ca. 2.5 cm) of irregular shape

1'. [.... h]u-ul-[la-nu

2'. [....  $\check{\mathbf{I}}$ ]B.L $\acute{\mathbf{A}}$ 1<sup>en</sup> par- $\check{\mathbf{s}}$ [i-gu .... <sup>d</sup>UTU]

\_\_\_\_\_

3'. [2 GADA sal-hi 4] <sup>r</sup>na<sup>1</sup>-hal-lap-tu<sub>4</sub> SÍG.H[É.ME.DA

4'. [1 na-hal-lap-tu<sub>4</sub>] bir-mu <1> ku-si-tu<sub>4</sub>

5'. [1 na-hal]-lap- $tu_4$  2 [x]  $\lceil x \rceil$  [... a-na  $^dA$ -a]

-----

6'. [1 GADA sal-hi 1 GADA h]u-ul-la-nu [ni<sup>?</sup>]-[bi-hu]

7'. [....] *a-na* <sup>d</sup>Ḥ[AR<sup>?</sup>]

8'. [x GADA sal-hi x na-hal]-[lap-tu<sub>4</sub>]

9'. [....] [tu<sub>4</sub><sup>?</sup>] [....]

Rev. 10'. [2 GADA sal-hi 1]  $na-hal-lap-t[u_4]$ 

11'.  $a-na^{\lceil d\rceil}[Gu-la]$ 

-----

12'. [1 GADA sal-hi 1  $^{t}$ ]<sup>úg</sup> gú-hal-ṣu ni-b[i-hu]

13'. [....] <sup>r</sup>x<sup>1</sup> *a-na* <sup>d</sup>IM

-----

14'. [1 GADA sa]l-hi 1<sup>et</sup> na-hal-lap-tu<sub>4</sub>

15'. [1 ku-si]- $tu_4$  a-na  ${}^{d}\check{S}[a^?$ -la]

```
The dividing line between l. 2' and l. 3' is hardly visible.
L. 5'. We expect here ta-kil-tu<sub>4</sub> but 2 is clear.
```

[.... linen h]ull[ānu-cloak, [.... nē]behu-belt, 1 paršī[gu]-headdress [.... for Šamaš]

[2 linen tunics, 4] re[d] nahlaptu-cloaks, [1] multicoloured [nahlaptu] cloak, <1> robe, [1 nahla]ptu-cloaks, 2 [.... for Aya]

[1 linen tunic, 1 linen h] $ull\bar{a}nu$ -cloak,  $<1>n\bar{e}[behu$ -belt ....] for Bu[nene]

[x linen linen tunic(s), x nah]laptu-cloak [....]

[2 linen tunics, 1] nahlaptu-cloak, [....] for [Gula]

[1 linen tunic, 1] scarf,  $\langle 1 \rangle n\bar{e}b[ehu\text{-belt}....]$  for Adad

[1 linen tu]nic, 1 nahlaptu-cloak, [1 rob]e for Š[ala].

#### 252. BM 99512 (83-1-21, 1874)

 $2.6 \times 3.0 \text{ cm}$ 

18'. nothing preserved

17'. nothing preserved

```
[....], [1] nahlap[tu-cloak ....], [1 multicolou]red [nahlap]tu-cloak [....]
[.... 6] naḥlaptu-cloaks [.... for] the Daughter[s of the Ebabbar]
[1 linen tunic, 1 linen hullānu-cloak], [1] sca[rf, 1 nēbehu-belt f]or Bunene
 _____
[.... r]ed [.... nah]laptu-cloak, <1> n\bar{e}[behu-belt, .... r]obe [....]
[.... for] the Queen of Si[ppar]
[....r]ob[e, ....].
253. BM 61765 (82-9-18, 1734)
6.4 \times 4.1 cm
            1'. [....]-tu<sub>4</sub> SÍG.Ḥ[É.ME.DA]
            2'. [....].DA 2-ta k[u- ....]
            3'. [....] rat \, ^{\Gamma}E^{\Gamma}-[babbar-ra]
            4'. [....] <sup>[</sup>x x<sup>]</sup> [....]
Rev.
            1'. [.... SÍ]G.'ḤÉ'.[ME.DA]
            2'. [.... SÍG.ZA.GÌN.KU]R.RA <sup>túg</sup>par<sup>?</sup>-[....]
            3'. [....] SÍG.HÉ.ME.D[A 1 TÚG.HI].「A¹ šam-ma-ma
               [\dots a-na^{d}A-nu-ni-tu_{4}]
            4'. [1 GADA sal-hu] 1et GÚ.UD.DU SÍG.HÉ.ME.「DAT
                   1^{et} ku-s[i-tu_4]
                                                            a-na <sup>d</sup>Gu-[la]
            6'. [1 GADA sal-hu] 1 GADA gú-hal-ṣu 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ
                [21 [....]
            7'. [....] <sup>r</sup>x<sup>1</sup> a-na <sup>d</sup>IM
            8'. [....]<sup>r</sup>x<sup>1</sup> [....]
Obv. 3. The second partially preserved sign looks like É.
[.... re[d naḥlap]tu [.... for Aya]
[.... re]d [....], 2 [.... for the Daught]ers of the E[babbar]
_____
[....] re[d .... blue-pur]ple [....] (one?) par[\tilde{s}\bar{t}gu-headdress? ....] red [...., 1 lub\bar{a}]r
šammamu-garment [.... for Anunītu]
```

[1 linen t	runic] 1 red naḥlaptu-cloak, 1 ro[be] for Gu[la]	
[1 linen t	runic], 1 linen scarf, 1 <i>patinnu</i> -belt, 2 [] for Adad	
<b>254. BM</b> 5.1 × 2.9	<b>100733</b> (83-1-21, 2394) cm	PLATE 56
	1'. 2-ta ku-sa-[a-tu <sub>4</sub> a-na <sup>d</sup> A-a]	
	2'. 2 GADA sal-ḫi 1 GADA ḫ[u-la-nu] 3'. 1 GADA gú-ḫal-ṣu pa- <sup>r</sup> tin-nu <sup>1</sup> 4'. 1 ni-bi-ḫu a-na <sup>d</sup> Bu-ne- <sup>r</sup> ne <sup>1</sup>	
Rev.	5'. 2 GADA sal-ḥi 3 na-ḥal-lap-tú SÍG.ḤÉ.ME.DA 6'. 1 <sup>et</sup> na-ḥal-lap-tu <sub>4</sub> bir-mu 7'. 1 <sup>et</sup> na-ḥal-lap-tu <sub>4</sub> ta-kil-tu <sub>4</sub> 8'. <1> ku-si-tu <sub>4</sub> <1> TÚG.ḤI.A pa-ni a-na <sup>d</sup> GAŠAN Sip-par <sup><ki></ki></sup>	
	9'. [1 GADA sa]l-ḫi 5 na-ḫal-lap- <sup>r</sup> tu4 <sup>1</sup> [] 10'. [x x x ḫ]u-la-n[u <sup>d</sup> A-nu-ni-tu4]	
Ll. 9'-10'	constituted most probably the list of garments of Anunītu.	
[, 2 ro[	[bes for Aya]	
1 linen tu	unic, 2 linen <i>h</i> [ <i>ullānu</i> ]-cloak, 1 linen scarf, <1> <i>patinnu</i> -bel	lt, 1 <i>nēbeḫu</i> -belt
	tunics, 3 red <i>naḫlaptu</i> -cloaks, 1 multicoloured <i>naḫlaptu</i> -aḥlaptu-cloak, <1> robe <1 > lubār pāni veil for the Queen	
[1 linen tu]nic, 5 naḥlaptu-cloaks, [, 1 ḫ]ullā[nu-cloak, for Anunītu].		
<b>255. BM</b> 5.4 × 4.3	<b>100954</b> (83-1-21, 2615) cm	
	1'. [] <sup>[</sup> x <sup>1</sup> [] <sup>[</sup> x <sup>1</sup>	
	2'. [2 GADA <i>sal-ḥi</i> 1 GADA] <i>ḥu-ʿla¹-nu¹</i> (T: PAP) [1 <sup>en</sup> TÚG].ÍB.LÁ SÍG.[ḤÉ.ME.DA] 3'. [x x x 1] TÚG.MURUB <sub>4</sub> .'ÍB¹.L[Á x x] ʿA me²¹ [x x	$x]-tu_4$ ?

	4'.	šá <sup>r<sup>d</sup>¹UT</sup>	TU	
	1	ADA <i>sal-ḥi</i> 4 TÚ <sup>et</sup> TÚG.GÚ.UD.D <i>ı-si-t]u</i> 4 šá <sup>d</sup> A-a	G].GÚ.UD.DU SÍG.ḪÉ.N U bir-mu	ME.DA
Rest lost	[/	ADA <i>sal-ḥi</i> 6 TÚ ku-si-tu <sub>4</sub> ] DUMU.MÍ.MEŠ	G].GÚ.UD.DU SÍG.ḪÉ.N	ME.DA 2-ta
Rev.		ADA <i>sal-ḥi</i> 1 TÚ ı-si]-tu <sub>4</sub> šá <sup>d</sup> Ša-la	G].GÚ.UD.DU SÍG.HÉ.N	ME.DA
[2 linen [] for §		inen] <i>ḫullānu</i> -clo	oak, [1] re[d <i>nē]beḥu</i> -belt	t [, 1] patinnu-belt
[2 linen for Aya		red <i>naḫlaptu</i> -clo	aks, 1 multicoloured <i>naḫ</i>	alaptu-cloak, [1 rob]e
[2 linen t			cs, 2 [robes] for the Daugl	hters of the Ebabbar
F1 12		1 11 ( 1.1.		
[1 lillell t	ume, ijie	а падиарии-стоак,	[1 rob]e for Šala.	
<b>256. BM</b> 3.0 × 3.1		3-1-21, 1570)		
	1'. [ a	<i>n-na</i> ] <sup>rd</sup> A-a <sup>¬</sup>		
		D]A 2- <i>ta ku-sa-a-</i> a <sup>d</sup> DUMU.MÍ.ME		
	SÍG.	HÉ.ME.DA	G.MURUB <sub>4</sub> .ÍB.LÁ	
	5'. [ 6	a-na <sup>d</sup> ]Bu-ne-ne		
	6'. [ ]	D]A <i>a-na</i> <sup>d</sup> GAŠA		
Rev.		SÍG.HÉ].ME.DA 1-na <sup>d</sup> ]Gu-la		
		1 TÚG.MURUB <i>a</i> a-na <sup>d</sup> I]M	ı.ÍB.LÁ SÍG.ḪÉ.ME.DA	

```
11'. [.... SÍG.HÉ].ME.DA (and about 3 signs erased)
           12'. [... a-na] <sup>d</sup>Ša-la
L. 4. şu<sup>!</sup>, clearly only šal.
[... for] Aya
[.... re]d [....], 2 robes [for the Daughters of the Ebabb]ar
             _____
[.... sc]arf, 1 red patinnu-belt, [.... for] Bunene
[.... re]d [....] for the Queen of Sippar
[.... re]d [....] for Gula
[...., 1 red patinnu-belt, [.... for Ad]ad
[.... re]d [.... for] Šala.
257. BM 100792 (83-1-21, 2453)
4.7 \times 3.2 cm
Obv./Rev?.
             1'. [....] 「x x <sup>1</sup> [....]
             2'. [.... na-ḥal]-rlap¹-tu4 šá <sup>d</sup>GAŠAN [Sip-par<sup>ki</sup>]
             3'. [x] GADA sal-hi 1-ta < na > -\lceil ah \rceil - lap - tu_4 [.... š\acute{a} ^dGu-la]
             4'. [1 GADA] sal-ḥi 1 gú-ḥal-ṣu 1 pa-tin-nu [.... šá <sup>d</sup>IM]
             5'. [x GADA] sal-hi 1 na-hal-lap-tu<sub>4</sub> 1 ku-si-[tu<sub>4</sub> .... šá <sup>d</sup>Ša-la]
[.... nah]laptu-cloak for the Queen of [Sippar]
[x] linen tunic, 1 nahlaptu-cloak [.... for Gula]
[1 linen] tunic, 1 < linen> scarf, 1 patinnu-belt [.... for Adad]
[1 linen] tunic, 1 naḥlaptu-cloak, 1 ro[be for Šala].
258. BM 71735 (82-9-18, 11738)
3.5 \times 4.4 cm
             1'. [....] 「x x ¬ [....]
             2'. [....] <sup>[</sup>x<sup>]</sup>
```

	3'. [] $ku$ - $si$ - $tu$ 4 $a$ - $na$ $^{d}$ [DN $^{1}$ []
	4'. [ p]a-tin-nu 1 ni-bi-ḫu 「x
	5'. [] <sup>r</sup> x <sup>1</sup> <i>ku-si-tu</i> <sub>4</sub> <i>šá</i> <sup>d</sup> <sup>r</sup> DN <sup>1</sup> []
Rev. co	6'. [] $^{\Gamma}it^{2_1}a$ - $na$ $^{\Gamma^{d_1}}[DN]$ ompletely eroded
L. 2' is L. 3' th every to	end of $tu_4$ or $yu$ . e broken sign looks like ME, however, Gula (ME.ME) took usually the last place in ext.
	be for []
_	p] <i>atinnu-</i> belt, 1 <i>nēbeḫu-</i> belt []
[, 1]	robe for [DN]
	or [DN].
<b>259.</b> C	T 55, 812 = BM 55896  1. mi-iḫ-ṣu te-[nu-ú šá] lu-[bu-uš-tu <sub>4</sub> 2.–5. fully eroded 6. 2 [GADA sal-ḫi]
	7. 1 [GADA <i>sal-ḫi</i> ]
	8. 1 [GADA <i>sal-ḥi</i> ]
	9. 1/3 <sup>?</sup> []
Rev.	10.–11. fully eroded 12. 2 GADA <i>sal-ḥi</i> 6 <i>na-ḥal-lap-tu</i> <sub>4</sub> 2 <i>-ta</i> 13. <i>ku-sa-tu</i> <sub>4</sub> <i>a-na</i> <sup>d</sup> GAŠAN.MEŠ
	14. 1 GADA sal-ḥi 1 GADA gú-ḥal-ṣu 1 pa-tin-nu 15. 1 ni-bi-ḥu a-na <sup>d</sup> IM

	17. $[1]^{et}$ ku-si-tu <sub>4</sub> a-na <sup>d</sup> Ša-la
	18. <sup>[1]</sup> GADA sal-ḫi 1 <sup>et</sup> GÚ.UD.DU <sup>[1et]</sup> ku-si-tu <sub>4</sub> 19. a-na <sup>d</sup> Gu-la
Woven	garments for the cha[nge for the] $lu[buštu$ ceremony []
	–5 fully eroded tunics,]
l [linen	tunic,]
1 [linen	tunic,]
1/3 <sup>?</sup> [	
2 linen	fully eroded tunics, 6 <i>naḥlaptu-</i> cloaks, 2 robes for Ladies
l linen	tunic, 1 linen scarf, 1 patinnu-belt, 1 nēbeḥu-belt for Adad
l linen	tunic, 1 <i>naḥlaptu</i> -cloak, <sup>r</sup> 1¹ robe for Šala
	tunic, 1 <i>naḫlaptu</i> -cloak, 1 robe for Gula.
260. CT	Γ <b>55, 817</b> = BM 58318 Collated
	1'. <sup>d</sup> [DN]
	2'. 2 GADA <sup>r</sup> sal <sup>¬</sup> -[hi 4 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA] 3'. 1 <sup>et</sup> TÚG.GÚ.UD.DU bir*-[mu 1 ku-si-tu <sub>4</sub> a-na <sup>d</sup> A-a] 4'. 2 GADA sal-ḥi 6 TÚG.GÚ.[UD.DU] 5'. 2-ta ku-sa-a-ta [a-na <sup>d</sup> DUMU.MÍ.MEŠ É-babbar-ra]
Rev.	6'. [1 GADA sa]l-ḫi 1 <sup>en túg</sup> [] 7'. [] <sup>r</sup> x¹ [] 1'. [] <sup>r</sup> x¹ [] 2'. šá <sup>d</sup> Nin-[ŠA
	3'. <i>a-na lu-bu-uš-[tu</i> <sub>4</sub> ] 4'. <i>a-na</i> <sup>mdf</sup> AG¹-[] 5'. ITI.[x]

Rev. 4'. Bongenaar, *Ebabbar*, p. 342 suggests to identify here the name of Ṣillāya.

[....]

```
2 linen tun[ics, 4 red nahlaptu-cloaks], 1 multicolo[ured] nahlaptu-cloak, [1 robe
2 linen tunics, 6 nahl[aptu]-cloaks, 2 robes [for the Daughters of the Ebabbar]
[1 linen tun]ic, 1 [....]
[....] for Nin-ŠA
[....] for the lubuš[tu ceremony [....] for Nabû-[....]. Month [x ....].
261. CT 55, 819 = BM 56332
            1'. [x (x)] ^{\mathsf{T}} x x^{\mathsf{T}} [....]
            2'. [2 GADA] 「sal-ḥi¹ 4 TÚG.G[Ú.UD.DU SÍG.ḤÉ.ME.DA
                   1 TÚG.GÚ.UD.DU bir-mu]
            3'. [1]^{\text{ret túg}}[ku]-si-tu<sub>4</sub> [a-na ^{\text{d}}A-a]
            4'. 2 GADA sal-hi 6<sup>!</sup>-rta TÚG.GÚ¹.[UD.DU SÍG.HÉ.ME.DA
                   2 ku-si-tu<sub>4</sub>]
                    a-na <sup>d</sup>DUMU.MÍ.MEŠ É-[babbar-ra]
            6'. 1^{en} GADA sal-hi1^{en} GADA hu-ul-[la-nu 1 GADA gú-hal-ṣu] 7'. ^{\Gamma}1^{et_1} TÚG.ÍB.LÁ 1^{en} TÚG.MURUB_4.Í[B.LÁ a-na ^dBu-ne-ne]
            8'. [1 GAD]A sal-hi 3-ta G[Ú.UD.DU SÍG.HÉ.ME.DA
                    1 TÚG.GÚ.UD.DU]
            9'. [SÍG.ZA.GÌN.KUR.RA 1 TÚG]. [GÚ.UD.DU¹ [bir-mu]
           10'. [.... G]Ú [a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>]
           11'. [x GAD]A sal-[hi .... <sup>d</sup>Gu-la]
Rev.
           12'. 1^{en} GADA sal-hi 1^{en} GADA gu'-h[al<sup>?!</sup>-su ....]
                           a-na <sup>d</sup>[IM]
           14'. [1 GADA s]al-ḫi 1^{en} TÚG.GÚ.UD.DU [1 ku-si-tu<sub>4</sub> a-na ^{d}Ša-la]
           -----
```


L. 4'. The badly preserved sign was emended to the typical 6!-ta (the remnants suggest rather 2-ta).

Ll. 8'-9' included the list of garments for Queen of Sippar. L. 13'. The rest of the signs preserved suggest reading  $1^{en}$  GADA  $hu-u[l^2-la-nu]$ . However, in accordance with the structure of such texts, the list of garments for Adad is expected here, but *hullānu* is not attested as part of Adad's attire.

[2 line tunics, 4 [red] nahla[ptu]-cloaks, 1 multicoloured nahlaptu-cloak], [1] [r]obe [for Aya] 2 linen tunics, 6 [red] nahla[ptu-cloaks, 2 robes] for the Daughters of the E[babbar] 1 linen tunic, 1 linen hull[ānu-cloak, 1 linen scarf], 1 nēbehu-belt, 1 patin[nu-belt for Bunene] \_\_\_\_\_ [1 line]n tunic, 3 [red nahlaptu-cloaks, 1 blue-purple nahlaptu-cloak, 1 multicoloured] nahlaptu-cloak [.... for Queen of Sippar] [x linen tu[nic ....for Gula] 1 linen tunic, 1 linen s[carf ....] for [Adad] [1 linen t]unic, 1 naḥlaptu-cloak, [1 robe for Šala]. **262. BM 73418** (82-9-18, 13429)  $4.2 \times 3.9$  cm 1'. [.... GADA] 「gú-hal-su<sup>¬</sup> 2'. [....] *a-na* <sup>d</sup>*Bu-n*[*e-ne*] 3'. [....] TÚG.BAR.DUL<sub>8</sub> *a-na* 4'. [....<sup>d</sup>DUMU.MÍ.MEŠ] 「ɹ-babbar-ra 5'. [....].DUL<sub>8</sub> 1<sup>et</sup> pa[r- ....] Rev. 6'. [.... lu]- $^{\Gamma}bar^{\Gamma}pa-ni$  TÚG.BAR.S[I ....] 7'. a-na <sup>d</sup>GAŠAN UD.KIB].NUN<sup>ki</sup> \_\_\_\_\_ 8'. [....] 1 GADA gú-ḥal-ṣu 9'. [....] <sup>[</sup>x x<sup>]</sup> [....] L. 8'. The guḥaṣṣu makes certain that the garments for Adad were enumerated here. [.... 1 linen] scarf [....] for Bun[ene] [.... 2] robes [for the Daughters of the] Ebabbar [....1 ro]be, 1 [...., lu]bār pāni-veil, the paršī[gu headdress .... for the Queen of Sip]par \_\_\_\_\_ [...., 1 linen] scarf [.... for Adad].

### **263. BM 73159** (82-9-18, 13170)

 $6.0 \times 5.2 \text{ cm}$ 



```
for [....] for Anunītu
[1 linen tunic, 1 nahlapt]u-cloak, 1 robe [for Gula]
[1 linen tunic, 1 sca]rf, 1 nēbeḥu-belt, [1 patinnu-belt for Adad]
[1 linen tunic, 1 nahlap]tu-cloak, [1 r]obe [for Šala].
264. BM 73347 (82-9-18, 13358)
5.1 \times 7.5 cm
Extremely badly preserved tablet.
               1. [....] [x \ x^{\dagger} [....]
               2. [....]-^{\Gamma}tu_4 ^{\Gamma} [....]
               3. [....] ^{\mathsf{r}}a-na ^{\mathsf{d}}[\mathsf{UTU}]
               4. [2 GADA sal]-hu 1<sup>et</sup> [x<sup>1</sup> [....]
              5. [\mathbf{x}^{\text{túg}}]^{\Gamma}na-hal-la¹-[ap-tu_4 \dots]
6. [\mathbf{x}]^{-r^{en_1}}^{\text{túg}}na¹-[hal]-[lap-tu_4 SÍG¹.[\dots]
               7. [a-n]a^{d}A-a
               8. [2 GA]DA sal-ḥi 2-ta ku-us-sa-<sup>[</sup>tu<sub>4</sub><sup>]</sup> [....]
               9. [6 túg] [na-hal]-lap-tu<sub>4</sub> a-na [d] [DUMU.MÍ.MEŠ É-babbar-ra]
             10. [1 GADA sal-hu 1] 「GADA hu-ul-[la-nu]
11. [1 ni-bi-hu 1 GADA gú]-「hal -su
             12. [.... a-na <sup>d</sup>Bu]-ne-ne
             13. [x GADA sal-hu x <sup>túg</sup>na-ha]l-la-ap-tu<sub>4</sub>
             14. [\dots]^{\text{túg}} na]-\lceil hal-la-ap-tu4\rceil [\dots]
Rev. completely eroded
L. 14. The blue-purple or multicoloured naḥlaptu-cloak was enumerated there.
[....] for [Šamaš]
[2 linen salhu]-tunics, 1 [..., x] nahlaptu-cloak(s), 1 [blue-purple] nahlaptu-cloak,
[.... 1 robe fo]r Aya
[2 lin]en tunics, 2 robes, [x] nahlaptu-cloaks for [the Daughters of the Ebabbar]
[1 linen tunic, 1] linen hu[llānu]-cloak, [1 nēbehu-belt, 1 linen sc]arf for Bu]nene
[x linen tunic(s), x red] nahlaptu-cloaks [x ....] nahlaptu-cloak [....].
265. BM 73474 (82-9-18, 13485)
4.6 \times 4.6 cm
               1'. [.... a]-<sup>[</sup>na] <sup>d</sup>UTU
```

2'. [2 GADA sal-hu 4 TÚG.GÚ.UD.DU SÍG.HÉ].ME.「DA<sup>1</sup> 1et

TÚG.GÚ.UD.DU bir-ri

	3'. [ a]-na <sup>d</sup> A-a
	5'. [a-na <sup>d</sup> DUMU.MÍ.MEŠ <i>É-babbar-ra</i> ]
	6'. [1 GADA <i>sal-ḥu</i> 1 GADA <i>ḫu</i> ]- <i>la-nu</i> 1 <sup>en</sup> GADA <i>gú-ḥal-ṣu</i> 7'. [1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 TÚG.ÍB.L]Á <i>a-na</i> <sup>d</sup> Bu-ne-ne
Rev.	8'. [1 GADA <i>sal-ḫu</i> 1 TÚG.GÚ.UD.DU SÍG].ḤÉ.ME.DA 9'. [1 <i>ku-si-tu</i> 4] <sup>[</sup> a-na <sup>] d</sup> Gu-la
	10'. [1 GADA <i>sal-ḫu</i> 1 GADA <i>gú-ḫal-ṣu</i> 1 TÚG.ÍB.LÁ]  「1 <sup>en</sup> 」TÚG.MURUB <sub>4</sub> .ÍB.LÁ <i>a-na</i> <sup>d</sup> IM
	11'. [1 GADA <i>sal-ḥu</i> 1 TÚG.GÚ.UD.DU 1 <i>ku-si</i> ]- <i>tu</i> <sub>4</sub> <i>a-na</i> <sup>d</sup> Ša-la
[ f]01	r Šamaš
	n tunics, 4 r]ed [naḥlaptu-cloaks], 1 multicoloured naḥlaptu-cloak, [, for Aya
[2 linen	tunics, 6 r]ed [naḥlaptu-cloaks], 2 robes [for the Daughters of the Ebabbar]
[1 liner for Bur	n tunic, 1 linen $hu$ ] $ll\bar{a}nu$ -cloak, 1 linen scarf, [1 $patinnu$ -belt, 1 $n\bar{e}beh$ ] $u$ -belt nene
[1 liner	tunic, 1 r]ed [naḥlaptu-tunic, [1 robe] for Gula
[1 liner	tunic, 1 linen scarf, 1 <i>nēbeḥu</i> -belt], 1 <i>patinnu</i> -belt for Adad
[1 liner	tunic, 1 <i>naḥlaptu-</i> cloak, 1 ro]be for Šala.
266. BI	M 73673 (82-9-18, 13684) PLATE 57
	1'. [] <sup>r</sup> na <sup>?</sup> ¹ []
	2'. [x GADA sal-ḫu 1 GADA ḫu-u]l-la-[nu 3'. [ <sup>t]úg</sup> ziq-[] 4'. [ a-n]a <sup>d</sup> Bu-n[e-ne]
	5'. [x GADA sal-hu 3 <sup>tú]g</sup> na-ah-lap-t[u <sub>4</sub> ] 6'. [1 <sup>túg</sup> na-ah-la]p-tú SÍG.ZA.GÌN.KUR.RA 7'. [1 <sup>túg</sup> na-ah-lap-tu <sub>4</sub> bi]r-ri 1 <sup>túg</sup> ku-si-tu <sub>4</sub> 8'. [1 TÚG. ḤI.A p]a-ni a- <sup>1</sup> na <sup>d</sup> GAŠAN <sup>1</sup> S[ip-par <sup>ki</sup> ]

L. 7'. The numeral 1 is followed by two $\textit{Winkelhaken}$ , probable $\textit{Winkelhaken}$ , probable $\textit{Vinkelhaken}$ , probable $Vink$	ably traces of an erased sign.
[] for <sup>?</sup> []	
[x linen tunic, 1 linen hul]lānu-cloak, [] ziq[qu-garr	ment fo]r Bun[ene]
[x linen tunics, 3 <red>] naḥlaptu-cloaks, [1] b [1 multicol]oured [naḥlaptu-cloak], 1 robe, [1 lubār S[ippar].</red>	
<b>267. BM 59270</b> (82-7-14, 3679) 5.9 × 3.2 cm	PLATE 57
Obv. 1'. [].ÍB.[LÁ] 2'. [ <sup>d</sup> Bu-ne]-ne	
3'. [ 2] <sup>síg</sup> ku-sa-tu <sub>4</sub> SÍG.ḤÉ.ME.DA 4'. [a-na <sup>d</sup> DUMU.MÍ.MEŠ <i>É-babbar-ra</i> ]	
5'. [x GADA sal-ḫu 3 TÚG.G]Ú.UD.DÚ.A 1 TÚG.GÚ.UD.DU.A ta-kil-tu <sub>4</sub> 6'. [1 TÚG.GÚ.UD.DU.A bir-mu] 「x¹ 1 <sup>? sí</sup>	<sup>'g</sup> ku-si-tu <sub>4</sub> <sup>1</sup> .A SÍG.ḪÉ.ME.DA LÁ 「SÍG.Ḫɹ.ME.DA
12'. [ SÍG.Ḥ]É.ME.DA Rest of rev. lost	
L. 1'. [TÚG].ÍB.[LÁ], or [TÚG.MURUB <sub>4</sub> ].ÍB.[LÁ]. L. 7'. Part of sign: $m$ ] $a$ , $k$ ] $u$ , $l$ ] $u$ or similar.	
[ for Bune]ne	. <u>-</u>
[ 2] red robes [for the Daughters of the Ebabbar]	<del>.</del>
[x linen tunics, 3] red [nahlap]tu-cloaks, 1 blue-pur coloured nahlaptu-cloak], 1° blue-purple robe [] for	rple <i>naḥlaptu-</i> cloak [1 multi- the Queen of Sippar
[x linen tunic, 3] red [nahla]ptu-cloaks, 1 [red] hullār [1] red [], 1 lubār šammamu-garment [] for Anur	
[] <sup>r</sup> red <sup>1</sup> [].	

# **268. BM 59048** (82-7-14, 3457) $3.0 \times 3.8$ cm 1'. [.... GÚ.DU.D]U SÍG.[....] 2'. [.... šá] <sup>rd</sup>7*A-a* 3'. [.... GÚ.DU.D]U SÍG.HÉ.ME.DA 4'. [.... $\check{s}\check{a}$ ] $\lceil^{d_1}$ DUMU.MÍ.MEŠ $\acute{E}$ -babbar-r[a]5'. [.... TÚ]G.ÍB.LÁ 1 TÚG.MURUB $_4$ .ÍB. 「LÁ $^\dagger$ 6'. [.... šá <sup>d</sup>B]u-ne-ne 7'. [.... SÍ]G.ḤÉ.ME.DA 8'. [.... 1]<sup>[et]</sup> GÚ.DU.DU *bir-mu* 9'. [.... 1<sup>e</sup>]<sup>t</sup> *ku-si-tu*<sub>4</sub> SÍG.ZA.GÌN.KUR.RA 10'. [šá <sup>d</sup>GAŠAN *Sip-par*<sup>ki</sup>] blank Rev. 11'. [....SÍG.Ḥ]É.ME.DA 12'. [.... -t]ú<sup>?</sup> šá <sup>d</sup>Gu-la 13'. [.... MU]RUB4.ÍB.LÁ 1 GADA gú-hal-şu 14'. [.... *šá*] <sup>Γ<sup>d</sup></sup>IΜ 15'. [....] SÍG.HÉ.ME.DA 16'. [.... a]-rna<sup>?</sup> drŠa-la [.... nahlap]tu-cloak [.... for] Aya [....] red [naḥlap]tu-cloak .... for] the Daughters of the Ebabbar [.... 1 n]ēbeḥu-belt, 1 patinnu-belt [for] Bunene [....] red [....], 1 multicoloured nahlaptu-cloak], [....] 1 blue-purple robe [.... for Queen of Sippar] [.... r]ed [naḥlaptu-cloak, 1 rob]e for Gula [.... 1 pa]tinnu-belt, 1 linen scarf [.... for] Adad [....] red [.... f]or Šala. **269. BM 59067** (82-7-14, 3476) $4.6 \times 3.2$ cm 1'. nothing preserved

2'. 1 GADA sal < hi > 1 GADA  $\lceil gu' \rceil - \lceil hal - su \rceil$ 

	3'. 1 pa-tin-nu a-na <sup>d</sup> [IM]	
	4'. 1 GADA sal-ḫi 1 na-rḥal <sup>¬</sup> -[lap-tu <sub>4</sub> ] 5'. 1 <sup>et</sup> ku-rsi <sup>¬</sup> -[tu <sub>4</sub> a-na <sup>d</sup> Ša-la]	
Rest lost		
L. 2'. It is di	ifficult to decide whether the $guhassu$ was followed or not by the $na$	ēbeķu.
1 linen tur	nic, 1 linen sc[arf], 1 patinnu-belt for [Adad]	
1 linen tur	nic, 1 naḫ[laptu-cloak], 1 ro[be for Šala].	
<b>270. BM</b> 5 5.3 × 4.0 c	<b>59175</b> (82-7-14, 3584) cm	PLATE 57
	1'. [].LÁ <sup>túg</sup> BA[R]	
	2'. [] 「 $1^{en}$ 」 TÚG.GÚ.UD.D[U] 3'. [ $2^{?}$ ] $par$ - $ši$ - $ga$ - $ni$ SÍG.H[É.ME.DA $a$ - $na$ $^{d}A$ - $a$ ]	
	4'. [2 GADA <i>sal</i> ]- <sup>[</sup> hu <sup>!</sup> ] 6 TÚG.GÚ.UD.DU.A <i>a-na</i> d[DUMU.MÍ.MEŠ <i>É-babbar-ra</i> ]	
	5'. [ 1 <i>ḫu-la</i> ]-nu 1 <sup>en</sup> GADA gú-[ <i>ḫal</i> ]-「ṣu¹ 6'. [a-na <sup>d</sup> Bu-ne-ne] blank	
Rest lost Rev. in pro	7'. [ TÚG.G]Ú.UD.DU.A [] reserved part uninscribed	
L. 4'. Before the lack of	G.BA[R.SI or TÚG.BA[R.DUL <sub>6/8</sub> ] ore the numeral 6 the partly preserved sign is rather $na$ , emende the $kus\bar{\imath}tu$ in the list. the garments for the Queen of Sippar were probably enumerate	
[]		
[], 1 [	.] <i>naḥlaptu-</i> cloak, [, 2 <sup>?</sup> ] <i>paršīgu-</i> headdresses [for Aya]	
[2 linen tu	nn]ics, 6 <i>naḥlaptu-</i> cloaks for [the Daughters of the Ebabb	ar]
[,1 <i>hull</i> ]	]ānu-cloak, 1 sc[arf for Bunene]	
[] naḫla	<i>uptu-</i> cloak [].	

#### 271. BM 59963 (82-7-14, 4373)

 $3.6 \times 4.1$  cm

#### Nbn 5

- 1. [mi-ih-su te-nu-u] šá a-na  $^{md}$ UTU-NUMUN- $^{\Gamma}$ GÁL  $^{!_{1}[\check{s}i]}$ 2. [ $^{lu}$ TÚG.BABBAR SUM $^{na}$  ITI.x U $_{4}$ .x.].KAM MU.5.KAM  $^{md}$ AG-I LUGAL E $^{[ki]}$
- -----
- 3. [2 GADA <br/> sal-hi1 GADA hu-ul-la]-nu1 GADA <br/> gú-hal-su

4. [.... *a-n*]*a* <sup>d</sup>UTU

5. [2 GADA sal-hi 5 na-hal-lap-tu $_4$  SÍG.Ḥ]É.ME.DA

- 6.  $[1^{et}$  na-ḥal-lap-tu<sub>4</sub> bir-mu  $1^{et}$  ku-s]i-tu<sub>4</sub> a-na  $\Gamma^{d_1}[A-a]$
- 7. [2 GADA sal-hi 6 na-hal-lap- $tu_4$  2]- $^{\Gamma}ta^{\Gamma}$  ku-sa- $tu_4$  [a-n]a  $^{\mathrm{d}}$ GAŠAN.MEŠ

GASAIV.IVILS

8. [....] <sup>[1]</sup> GADA  $g\acute{u}^{1}$ - $\dot{h}[al$ - $s\acute{u}]$  <sup>[1]</sup> [....]

Rest of Obv. lost

Rev. 1'. [1 GADA sal-ḫi 1 <sup>túg</sup>na-ḫal-lap-tu<sub>4</sub> 1 ku-si-t]u<sub>4</sub> a-na <sup>d</sup>Gu-la

2'. [....] <sup>[</sup>x<sup>7</sup>

3'. [.... *a-na* <sup>d</sup>IM] blank

4'. [1 GADA sal-ḫi 1 na-ḫal-lap-tu4 1] ku-si-tu4 <<br/>a-na>  $^{\rm d}\check{S}a$ -la

- L. 1. The last preserved element of the name is similar to ni, which makes no sense. Because in this period the  $mih\bar{y}u$   $ten\hat{u}$  lists were prepared by Šamaš-zēr-ušabši, the  $^{\Gamma}ni^{\Gamma}$  has to be emended to  $G\Delta I$
- Ll. 5–6. There usually Aya received 4 *naḥlaptu tabarri*, 1 *naḥlaptu takilti* and 1 *naḥlaptu birmu*, or 5 *naḥlaptu tabarri* and 1 *naḥlaptu birmu*. In our text there is enough place only for 5+1.
- L. 7. The sign before  $kus\bar{a}tu$  is more similar to  $\lceil na^{?1} \rceil$  than to  $\lceil ta^{?1} \rceil$ , however, in the parallel texts it is always 2(-ta).

In the almost completely missing rev. 2'-3 we expect the list of garments for Adad (usually before Šala, but after Gula, if the list included her garments). The list of garments for Adad is always the same: salhu, guhassu, patinnu and  $n\bar{e}behu$  (this order is most typical but sometimes  $n\bar{e}behu$  precedes patinnu and both could be written ideographically with LÁ as the last element of the ideogram). The broken sign could be only su, nu, hu or LÁ, but the first three seems to be excluded. It could be LÁ (end of [TÚG.MURUB4.ÍB].LÁ or [TÚG.ÍB].LÁ).

[Woven garments, which [were given] to Šamaš-zēr- $^{\Gamma}$ ušabši $^{!\eta}$ , [the ašlāku.  $N^{th}$  month,  $n^{th}$  day],  $5^{th}$  year of Nabonidus, king of Babylon.

[2 linen tunics, 1 linen  $\mbox{\it hull}\mbox{\it \bar{a}}\mbox{\it lnu-cloak},$  1 scarf [.... fo]r Šamaš

[2 linen tunics, 5 r]ed [nahlaptu-cloaks, 1 multicoloured nahlaptu-cloak, 1 ro]be for [Aya]

\_\_\_\_\_

[2 linen tunics, 6 naḥlaptu-cloaks, 2] robes [fo]r Ladies		
[], 1 linen sc[arf], 1 [ for Bunene]		
[1 linen tunic, 1 naḥlaptu-cloak, 1 rob]e for Gula		
[ for Adad]		
[1 linen tunic, 1 <i>naḥlaptu-</i> cloak, 1] robe <for> Šala.</for>		
<b>272. BM 58874</b> (82-7-14, 3283) PLATE 58 3.6 × 4.4 cm		
1'. []. $HI.A^{T}x \times a a^{T}$ [] 2'. [ M]E.DA 1 $^{túg}Tx \times^{T}$ [] 3'. [ 1 $ku$ ]- $si$ - $tu_4$ [ $š\acute{a}^dA$ - $a$ ]		
4'. [2 GAD]A sal-ḥi 6 <sup>túg</sup> na-a[ḥ-lap-tu <sub>4</sub> ] 5'. [2-t]a <sup>túg</sup> ku-sa-a-[tu <sub>4</sub> a-na <sup>d</sup> DUMU.MÍ.MEŠ É-babbar-ra]		
6'. [1 GA]DA sal-ḥi 1 GADA ḫu-[(ul)-la-nu 7'. [1 GAD]A gú-ḥal-ṣu 1 [TÚG.MURUB <sub>4</sub> .ÍB.LÁ] 8'. [1 TÚG].ÍB.LÁ a-n[a <sup>d</sup> Bu-ne-ne]		
9'. [2 GADA s]al-ḥi 3-[ta <sup>túg</sup> na-aḥ-lap-tu <sub>4</sub> a-na <sup>d</sup> GAŠAN Sip-par <sup>ki</sup> Rev. Lost		
L. 1. Maybe TÚG].ḤI.A <sup>r</sup> šá <sup>d</sup> A-a <sup>1</sup> .		
[ r]ed [], 1 [, 1 ro]be [for Aya]		
[2 line]n tunics, 6 <i>nah</i> [laptu-cloaks, 2] ro[bes for the Daughters of the Ebabbar]		
[1 lin]en tunic, 1 linen $hu[ll\bar{a}nu$ -cloak, 1 lin]en scarf, 1 [patinnu-belt, [1 n] $\bar{e}behu$ -belt fo[r Bunene]		
[2 linen t]unics, 3 [naḥlaptu-cloaks for the Queen of Sippar].		
<b>273. BM 61953</b> (82-9-18, 1922) 5.8 × 6.0 cm		
Tablet in extremely bad condition		
1. <i>mi-iḫ-ṣi</i> [ <i>a na</i> PN ()] 2. 「SUM <sup>na</sup> 」 []		

	3. 2 GADA <i>sal-ĥi</i> [1 GADA <i>ḫu-ul</i> ]- <sup>r</sup> <i>la-nu</i> <sup>1</sup> 4. [] <i>a-na</i> <sup>d</sup> [UTU]
	5. [2] GADA sal-[hi 3 n]a-hal-lap-tu <sub>4</sub> 1 <sup>r</sup> na <sup>1</sup> -[hal-lap-tu <sub>4</sub> ] 6. [ 1 ku-si-tu <sub>4</sub> ] a-na <sup>d</sup> [A-a]
Rest of Ob Rev.	7. [2 GADA sal-ḥi 6] 「na¬-[ḥal-la]p-tu4 [] ov. lost. 1'. [] 「x x¬ [] 2'. []
	3'. [1 GADA sa]l-hi 1 GADA gú-hal-ṣ[u] 4'. []
	5'. 1 GADA <i>sal-ḥi</i> 1 <i>na-ḥal-lap-t</i> [ <i>u</i> <sub>4</sub> , 1 <i>ku-si-tu</i> <sub>4</sub> ] 6'. <i>a-na</i> <sup>r<sup>d</sup></sup> [DN]
	7'. 1 ni-bi-ḥu šá <sup>d</sup> UTU 1 ni-bi-ḥu [] 8'. a-na [ <sup>d</sup> DN]
Woven ga	rments [] given [to PN]
	nics, [1 linen <i>ḫul</i> ]lānu-cloak, [] for [Šamaš]
[2] linen tu	uni[cs, 3 < red> naḥlaptu-cloaks, 1 na[ḥlaptu-cloak 1 robe] for [Aya]
[2 line]n tu	unics, 6] $na[hlap]tu$ -cloaks, [2 robes for the Daughters of the Ebabbar]
[1 linen tu	nic, 1 linen sca[rf]
	nic, 1 naḥlap[tu-cloak, 1 robe] for []
1 nēbeķu-l	pelt for Šamaš, 1 <i>nēbeḫu</i> -belt [] for []
<b>274. BM</b> 6 5.5 × 3.1 c	<b>59077</b> (82-9-18, 9076) m
Beautiful si	nall signs
	nothing preserved
	1'. [1 GADA sal-ḫu 1 GADA] ḫu-la-nu 1 gú-ḫal-ṣu 2'. [1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 TÚG].ÍB.LÁ a-na <sup>d</sup> Bu-n[e-ne]

- 3'. [2 GADA sal-h]u 3 TÚG.GÚ.UD.DU SÍG.HÉ.ME.DA 1et T[ÚG.GÚ.UD.DU *bir-mu*]
- 4'. [1 TÚG.GÚ.UD.D]U SÍG.ZA.GÌN.KUR.RA 1 TÚG.ḤI.A pa-ni 1<sup>et</sup> [ku-si-tu<sub>4</sub> a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>]

\_\_\_\_\_\_

- 5'. [2<sup>?</sup> GADA sal-hu 3-t]a TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA
- 6'. [1 GADA *hu-la-nu* 1] TÚG.MURUB<sub>4</sub>.ÍB.LÁ 1 TÚG.BA[R<sup>?</sup>
- 7'. [....] <sup>r</sup>x¹ TÚG.ḤI.A [.... <sup>d</sup>*A-nu-ni-tu*<sub>4</sub>]

#### Rest lost

On rev. small traces of three lines, with no sign complete. For 2 GADA in 1. 3', cf. BM 73073 (= 281): 11.

- [1 linen tunic, 1 linen] hullānu-cloak, 1 scarf, [1 patinnu-belt, [1 n]ēbehu-belt for Bun[ene] \_\_\_\_\_
- [2 linen tun]ics, 3 red nahlaptu-cloaks, 1 [multicoloured nahlaptu-cloak, 1 blue purple [nahlap]tu-cloak, 1 lubār pāni veil, 1 [robe for the Queen of Sippar]
- [2<sup>?</sup> linen tunics, 3] red *naḥlaptu-*cloaks, [1 linen *ḥullānu-*cloak, 1] *patinnu-*belt, 1 [....] *lubār* [.... for Anunītu].

## **275. BM 65146** (82-9-18, 5143)

 $7.7 \times 4.8$  cm

### 15.[x.KN] 2

- 1. [mi]-ih-su t[e-nu-u ....]
- 2. [šá] ta-hap-š[ú ....]
- 3.  $[\check{s}\acute{a}]$   ${}^{\Gamma}U_4{}^{1}.15.KAM MU.2[+x^{?}....]$

\_\_\_\_\_

- 4. [2 GAD]A *sal-hu* 1 [....]

5. 1 <sup>túg</sup>gú-ḥal-ṣu TÚ[G .... šá <sup>d</sup>UTU]

- 6. 2 GADA sal-hu 4 <sup>túg</sup>[na-ah-lap-tu<sub>4</sub> ....]
- 7. 1 <sup>túg</sup>ku-si-tu<sub>4</sub> 2 TÚ[G.BAR.SI.MEŠ šá <sup>d</sup>A-a]

- 8. 2 GADA sal-ḥu 6-ta <sup>tú</sup>[<sup>g</sup>na-aḥ-lap-tu<sub>4</sub> 2 <sup>túg</sup>ku-si-tu<sub>4</sub> a-na <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-ra]
- 9. 1 GADA sal-hu 1 GADA hu-l[a-nu 1 pa-tin-nu 1 ni-bi-hu šá  $^{d}Bu$ -ne-ne]

```
10. 2 GADA sal-hu 3-ta túgn[a-ah-lap-tu4 SÍG.HÉ.ME.DA
             1 na-ah-lap-tu₄ bir-mu]
         11. [1^e]^n na-\lceil ah \rceil-lap-tu<sub>4</sub> SÍG.ZA.GÌN.KUR.RA [1 \text{ ku-si-tu}_4 \text{ a-na}]
                dGAŠAN Sip-parki
         ______
         12. [2^{?} GADA sal]-hu 1 GADA hu^{!}-la-nu 3 [^{\mathrm{t\acute{u}g}}na-ah-lap-tu_{4}
                SÍG.HÉ.ME.DA]
         13. [1 TÚG.MURU]B<sub>4</sub>.ÍB.LÁ 1 TÚG.Í[B.LÁ ....]
         14. [x \times lu-ba]-ru šá šam-[ma-mu šá {}^{d}A-nu-ni-tu_4]
Rev.
         15. [x GAD]A \lceil sal \rceil-hu 1-ta n[a-ah-lap-tu_4 1 ku-si-tu_4 a-na ^dGu-la]
         16. 1 GADA sal-ḥu 1 <GADA> gú-ḥal-ṣ[u 1 pa-tin-nu 1 ni-bi-ḥu
         _____
         17. 1 GADA sal-hu 1 na-ah-lap-[tu4 1 ku-si-tu4 šá <sup>d</sup>Ša-la]
         _____
         18. 2 TÚG.ÍB.BAL šá <sup>d</sup>I[M ....]
         ______
         19. 1 TÚG.ÍB.BAL ina UGU N[Á<sup>?</sup> ša <sup>d</sup>DN]
L. 2. Note the word tahapšu instead of expected lubuštu. For possible Biblical parallel, see
Tawil 2009, p. 116.
L. 12. After [sa]l-hu we see numeral "1" written over GADA. Instead of hu there is na.
L. 14. The reconstruction is based on fact that lubār šammamu is known exclusively in the
set of Anunītu's garment.
[Wo]ven garments .... for] tahapš[u] .... for the 15^{th} day, 2+[x] year ...
[2 line]n tunics, 1 [....], 1 scarf, [.... for Šamaš]
    [2 linen tunics, 4 [naḥlaptu-cloaks ....], 1 robe, 2 pa[ršīgu-headdresses for Aya]
2 linen tunics, 6 [nahlaptu-cloaks, 2 robes for the Daughters of the Ebabbar]
1 linen tunic, 1 linen hul[lānu-cloak, 1 patinnu-belt, 1 nēbehu-belt for Bunene]
2 linen tunics, 3 [red] n[ahlaptu-cloaks, 1 multicoloured nahlaptu-cloak], [1] blue
purple nahlaptu-cloak, [1 robe for the Queen of Sippar]
[2] linen tun]ics, 1 linen hullānu-cloak, 3 [red nahlaptu-cloaks, 1 patin]nu-belt,
1 nē[behu-belt, .... 1 lub]ār šamm[amu-garment for Anunītu]
[x line]n tunic, 1 n[ahlaptu-cloak, 1 robe for Gula]
1 linen tunic, 1 linen> sca[rf, 1 patinnu-belt, 1 nēbehu-belt for Adad]
```

1 linen tunic, 1 naḥlap[tu-cloak, 1 robe for Šala]		
2 nēbettu-girdles for Ad[ad]		
1 <i>nēbettu</i> -girdle for the be[d of the god(dess)].		
<b>276. BM 63687</b> (82-9-18, 3654) 5.9 × 4.3 cm		
Fragment of a very thick tablet		
1'. 2 GADA <i>sal-ḥ</i> [u] 2'. 1 <sup>et</sup> TÚG.GÚ.U[D]		
3'. [1+] 1 GADA sal-ḫu 6 T[ÚG.GÚ.UD.DU 4'. <sup>[2]et</sup> (sic) ku-si-tu <sub>4</sub> <sup>[a]</sup> -[na <sup>d</sup> DUMU.MÍ.MEŠ É-babbar-ra]		
5'. 1 GADA sal-ḥu 1 GADA ḥ[u-ul-la-nu 1 gú-ḥal-ṣu 1 pa-tin-nu] 6'. 1 TÚG.ÍB.LÁ a-[na <sup>d</sup> Bunene]		
7'. '1 GADA' [] Rest of obv. and rev. lost.		
2 linen tuni[cs, 1 nah[laptu-cloak for Aya		
[1+]1 tunics, 6 n[aḥlaptu-cloaks], 2 robes [for the Daughters of the Ebabbar]		
1 linen tunic, 1 linen <i>ḫ[ullānu-</i> cloak, 1 scarf, 1 <i>patinnu-</i> belt], 1 <i>nēbeḫu-</i> belt f[or Bunene]		
1 linen [].		
<b>277. BM 68361</b> (82-9-18, 8359) 3.9 × 3.5 cm		
5.[x.Nbk] 32		
1. [ ḫu]-la-nu GADA šá <sup>d</sup> UTU 2. [ TÚG].MURUB <sub>4</sub> .ÍB.LÁ 3. [] TÚG.ḤI.A ku-lu-lu 4. [] šá <sup>d</sup> UTU 3 šá dul-lu <sub>4</sub>		
5. [] SÍG.ME.ḤÉ.DA 1 GÚ.UD.DU <i>bir-mu</i> 6. [] SÍG.ME.ḤÉ.DA 2 <i>sal-ḥi</i> 「GADA <i>šá</i> <sup>d</sup> 1A-a 7. [] 「x¹ []		

```
Rest lost
             1'. [.... k]u-\lceil sa^{?!} \rceil-\lceil tu_4 \rceil
Rev.
             2'. [.... šá <sup>d</sup>GAŠ]AN UD.KIB.NUN<sup>ki</sup>
             3'. [.... TÚG.ḤI].
A me-tu šá ^{\mathrm{d}}\mathrm{IM}
             4'. [.... 1^e]<sup>n?</sup> TÚG.BAR.DUL<sub>8</sub> TÚG.ḤI.A ku-lu-lu 5'. [.... šá <sup>d</sup>Š]a-la 2 sal-ḫi GADA 1 gú-ḫal-ṣu
             5 a'.
             6'. [....] GÚ.UD.DU 1 SÍG.BAR.DUL<sub>8</sub>
             7'. [.... 1+]1 TÚG.BAR.SI.MEŠ
             8'. [....] <sup>[9]</sup> ți-mi-ti
             9'. [....] U<sub>4</sub>.5.KAM
            10'. [.... MU].32.KAM
Cf. the similar texts ZA 4, No. 4 (= 176); BM 82581 (= 180); CT 55, 811 (= 182); and BM
50282 (= 359).
The partially preserved first and last lines of the text make clear that the name of the king
was not written there. Presumably the text was continued on the left hand edge, now com-
pletely missing. Note that the scribe wrote the determinative GADA after salhi, although in
all other texts it is placed before it. Note also TÚG.BAR.DUL8 in rev. 4', but cf.
SÍG.BAR.DULg in rev. 6'.
[....] linen [hu]llānu-cloak for Šamaš
[....] patinnu-belt, [....], the lubār kulūlu-headband [....] for Šamaš; 3 ordinary
garments
[....] red [nahlaptu-cloaks], 1 multicoloured nahlaptu-cloak, [....] red [....],
2 linen tunics for Aya
[.... r]ob[es<sup>?</sup> [.... for Šar]rat Sippar
[....] lub]ār mēṭu-headband for Adad
[....] [1] robe, the lubār kulūlu-headband [.... for Š]ala;
2 linen tunics, 1 scarf for Adad
[....] nahlaptu-cloak, 1 robe [...., 1]+1 parš\bar{\imath}gu-headdresses, [....] 9 yarn [....] 5^{th} day [....], 32^{nd} [year].
278. BM 73408 (82-9-18, 13419)
3.6 \times 4.9 \text{ cm}
Obv. completely eroded
             1'. nothing preserved over ruling line
```

2'. [1 GADA sal]-ḥu 1 gú-ḥal-ṣu 1 [pa-tin-nu]

3'.  $[1^{t\acute{u}}]^g$ ni-bi-hu a-na  $^d$ I[M]

	4'. 1 GADA $sal-hu$ [1- $ta$ ] $^{túg}[nahlaptu]$ 5'. 1- $ta$ $ku$ - $^{r}si$ - $tu$ 4 $^{1}$ $a$ - $n$ [ $a$ $^{d}$ Š $a$ - $la$ ] ev. uninscribed
[1 linen	tu]nic, 1 scarf, 1 [patinnu-belt, 1] nēbeļju-belt for Ad[ad]
	unic, [1 <i>naḥlaptu</i> -cloak], 1 robe fo[r Šala].
279. BM 2.8 × 4.3	I <b>101340</b> (83-1-21, 3001)
	1'. $[1 \stackrel{\text{túg}}{=} k]u$ -si-t $[u_4 \check{s} \acute{a} \stackrel{\text{d}}{=} A$ - $a]$
	2'. 2 GADA sal-ḫi 6-ta [naḫalptu 3'. 2-ta ku-sa-a-ta [šá <sup>d</sup> DUMU.MÍ.MEŠ É-babbar-ra]
	4'. 1 GADA sal-ḫi 1 GADA [ḫu-la-nu] 5'. 1 GADA gú-ḫal-ṣu 6'. 1 ni-bi-ḫi a-na [ <sup>d</sup> ḤAR]
Edge	7'. 1 GADA <i>sal-ḥi</i> 1 <i>n</i> [ <i>a-</i> ] 8'. 1 TÚG.MURUB <sub>4</sub> .Í[B.LÁ] 9'. <i>a-na</i> []
Rev. con	npletely damaged (no sign preserved).
[, [1 r]	lob[e for Aya]
2 linen tu	unics, 6 [naḥlaptu-cloaks], 2 robes [for the Daughters of the Ebabbar]
1 linen tu	unic, 1 linen [ħullānu-cloak], 1 linen scarf, 1 nēbeḥu-belt for [Bunene]
1 linen tu	unic, 1 <i>n[aḫlaptu-</i> cloak], 1 <i>patinnu-</i> belt [] for [].
280. BM 7.3 × 2.7	I <b>67859</b> (82-9-18, 7857) cm
	1'. [1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 TÚG.Í]B.LÁ <i>a-na</i> <sup>d</sup> Bu-ne-ne
	2'. [x GADA <i>sal-ḥu</i> 3 TÚG.GÚ].'UD.DU¹ SÍG.ḤÉ.ME.DA 1 TÚG.GÚ.UD.'DU <i>bir</i> ¹-[ <i>mu</i> ]

	3'. [1 TÚG.GÚ.UD.DU SÍG.ZA.GÌN.KUR.RA] 1 ku-si-tu <sub>4</sub> a-na [ <sup>d</sup> GAŠAN Sip-par <sup>ki</sup> ]
Rev.	4'. [x GADA sal-hu 3 TÚG.GÚ.UD.DU SÍG]. HÉ.ME DA  1 túg hu-la-[nu]  5'. [1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 TÚG]. HI.A MURUB <sub>4</sub> 1 TÚG.BAR.SI []  6'. [ 1 l]u-bar-ra a-na dA-nu-Ini-tu <sub>4</sub>
	7'. [2 <sup>?</sup> GADA sal-ḫu 1 TÚG.GÚ.UD.DU 1 ku-si]-tu <sub>4</sub> a-na <sup>d</sup> Gu-la
	8'. [1 GADA <i>sal-ḥu</i> 1 GADA <i>gú-ḥal-ṣu</i> 1 TÚG.ÍB.LÁ 1 TÚG.MURUB <sub>4</sub> ]. <sup>r</sup> ÍB.LÁ <i>a¹-na</i> <sup>d</sup> IM
Rest los	
[], [1	patinnu-belt, 1 nē]behu-belt for Bunene
	tunic(s), 3 red [nah]laptu-cloaks, 1 multicol[oured] nahlaptu-cloak, [1 blue nahlaptu-cloak], 1 robe for [the Queen of Sippar]
	en tunics, 3] red <sup>r</sup> nahlaptu <sup>1</sup> -cloaks], 1 hullā[nu-cloak, 1 patinnu-belt, r qablu-belt, 1 paršīgu-headdress [, 1 l]ubāru-garment for Anunītu
[2 linen	tunics, 1 <i>naḥlaptu-</i> cloak, 1 ro]be for Gula
[1 linen	tunic, 1 linen scarf, 1 <i>nēbeḥu</i> -belt, 1 <i>pati</i> ] <i>nnu</i> -belt for Adad.
<b>281. BN</b> 3.7 × 6.	<b>A 73073</b> (82-9-18, 13083) 3 cm
	1. <i>mi-iḥ-ṣu <sup>r</sup>te-nu<sup>1</sup>-[ú šá lu-bu-uš-tu</i> <sub>4</sub> <i>šá</i> ITI.x U <sub>4</sub> .x.KAM <i>šá</i> PN] 2. <sup>lú</sup> TÚG.BABBAR <sup>r</sup> SUM <sup>na</sup> ITI.[x]
	3. 「2 <sup>1</sup> sal-ḫi 「1 <sup>!</sup> GADA <sup>!</sup> <sup>1</sup> ḫ[u-ul-la-nu] 4. [1] GADA gú-ḫal-ṣu 1 [ a-na <sup>d</sup> UTU]
	5. [2] GADA sal-ḫi 4-[ta] na-a[ḫ-lap-tu <sub>4</sub> SÍG.ḤÉ.ME.DA] 6. [1 <sup>et</sup> ] <sup>r</sup> ku <sup>1</sup> -si-tu <sub>4</sub> <sup>r</sup> a <sup>1</sup> -[na <sup>d</sup> A-a]
	7. 2 GADA sal-ḫi 「3²-ta¹ [na-aḫ-lap-tu₄ a-na <sup>d</sup> DUMU.MÍ.MEŠ É-babbar-ra]
	8. 1 GADA sal-ḫi 1 「GADA¹ ḫ[u-ul-la-nu]

	9. 1 pa-tin-nu 1 ni-[bi-ḫu a-na <sup>d</sup> Bu-ne-ne]	
	10. 1 GADA sal-ḥi 5- <sup>r</sup> ta <sup>1</sup> [na-aḥ-lap-tu <sub>4</sub> a-na <sup>d</sup> GAŠAN Sip-par <sup>ki</sup>	
Rev.	11. 2 GADA <i>sal-ḥi</i> 1- <i>ta ḥ</i> [ <i>u-ul-la-nu</i> ] 12. blank [ <i>a-na</i> <sup>d</sup> A- <i>nu-ni-tu</i> <sub>4</sub> ]	
	13. 1 GADA sal-ḫi 1 GADA gú-[ḫal-ṣu 14. 1 ni-bi-ḫu a-n[a <sup>d</sup> IM]	
	15. 1 GADA <i>sal-ḥi</i> 1- <i>ta n</i> [ <i>a-aḥ-lap-tu</i> <sub>4</sub> 16. blank [ <i>a-na Ša-la</i> ]	
Free space to the end of the reverse.		
<ul> <li>L. 3. The broken signs after sal-bi look like šá and qa followed by the beginning of one horizontal wedge.</li> <li>L. 5. Note the lack of one multicoloured nahlaptu in this list.</li> </ul>		
Woven garments for the change [for the <i>lubuštu</i> ceremony of the month $x$ , $n^{th}$ day] were given [to PN], the $a\bar{s}l\bar{a}ku$ . Month $[x,]$		
2 linen tunics, 1 linen $h[ull\bar{a}nu$ -cloak, 1] linen scarf, 1 [ for Šamaš]		
[2] linen tunics, 4 [red] $nah$ [laptu-cloaks, [1] robe fo[r Aya]		
2 linen tunics, 3 <sup>?</sup> [ <i>naḥlaptu</i> -cloaks, 2 robes for the Daughters of the Ebabbar]		
1 linen tunic, 1 linen $h[ull\bar{a}nu\text{-cloak}]$ , 1 patinnu-belt, 1 $n\bar{e}[behu\text{-belt for Bunene}]$		
1 linen tunic, 5 [naḥlaptu-cloaks for the Queen of Sippar]		
2 linen tunics, 1 <i>h</i> [ <i>ullānu</i> -cloak for Anunītu]		
1 linen tunic, 1 linen sc[arf], 1 nēbeḥu-belt fo[r Adad]		
1 linen tunic, 1 <i>na</i> [ <i>hlaptu</i> -cloak, 1 robe for Šala].		
282. Deleted		
<b>283. BM 83275</b> (83-1-21, 438) 4.5 × 3.0 (x 2. 3) cm		
	1'. 「TÚG <sup>?</sup> 」[]	
	2'. 2 GADA sa[l-ḫu	

```
3'. blank
                          [....]
           4'. 1 GADA sal-hu 1 GADA \lceil gu^{1}-h[al-su ....]
           5'. 1 TÚG.ÍB.LÁ a-na [<sup>d</sup>Bu-ne-ne]
           _____
           6'. 2 GADA sal-hu 3-ta TÚG.GÚ.UD.D[U SÍG.HÉ.ME.DA]
           7'. [1]<sup>[et]</sup> TÚG.<GÚ>.UD.DU.A SÍG.ZA.GÌN.KUR.RA [....]
                            a-na <sup>d</sup>GAŠAN UD.K[IB.NUN<sup>ki</sup>]
Edge
           9'. 2 GADA sal-ḥu 1<sup>et</sup> TÚG.GÚ.UD.D[U 1 ku-si-tu<sub>4</sub>]
10'. a-na <sup>d</sup>Gu-[la]
Rev.
          10'.
         11'. 1 GADA sal-hu 1 GADA gú-[hal-ṣu]
          12'. 1 TÚG.ḤI.A a-na [<sup>d</sup>IM]
          _____
          13'. 1 「GADA<sup>†</sup> [sal]-「hu<sup>†</sup> [1 naḥlaptu 1 kusītu a-na <sup>d</sup>Ša-la]
Rest lost
L. 7'. DU is written with two vertical wedges.
L. 12'. There is TÚG.HI.A instead of expected ni-bi-hu.
2 linen tu[nics .... for Aya]
1 linen tunic, 1 linen sc[arf, ....], 1 nēbeḥu-belt for [Bunene]
2 linen tunics, 3 [red] nahlaptu-cloaks, [1] blue-purple nahlaptu-cloak [....] for the
Queen of Sippar
2 linen tunics, 1 nahlaptu-cloak [...., 1 robe] for Gu[la[
1 linen tunic, 1 linen sc[arf ....], 1 lubāru-garment for [Adad]
1 linen [tu]nic [1 naḥlaptu-cloak, 1 robe for Šala].
284. BM 83803 (83-1-21, 966)
                                                                        PLATE 58
4.0 \times 4.0 cm
           1'. [x x x x x x x x x -t]u_4 2 [ku-si-tu_4]
           2'. [a-na <sup>d</sup>DUMU.MÍ.MEŠ] É-babbar-ra
           _____
           3'. [1 GADA sal-ḥu 1 GAD]A ḥu-ul-la-nu 1<sup>en</sup> GA[DA gú-ḥal-ṣu]
           4'. [TÚG.MURUB<sub>4</sub>.Í]B.LÁ TÚG.HI.A me-tu TÚG.HI.「A¹
                 [ku-lu-lu a-na dHAR]
           5'. [2<sup>?</sup> GADA sal-hu 1 ku]-si-tu<sub>4</sub> SÍG.ZA.GÌN.KUR.RA [....]
```

	6'. [1 TÚG.GU.UD.DU] <sup>r</sup> bir¹-ri <sup>r</sup> 1 <sup>en</sup> ¹ TÚG.GÚ.UD.D[U SÍG.ZA.GÌN.KUR.RA] 7'. [3 TÚG.GU.UD.DU SÍG.HÉ.ME.DA] <i>a-na</i> <sup>d</sup> GAŠA[N <i>Sip-par</i> <sup>ki</sup> ]	
Rev.	8'. [2 <sup>?</sup> GADA <i>sal-ḫu</i> 1 GADA] <sup>r</sup> ḫu¹-ul-la-nu SÍG.[ḤÉ.ME.DA] 9'. [x TÚ]G.GU.UD.DU 1 <sup>?</sup> [] 10'. [TÚG.ḤI.A] <i>šá šam-ma-mu</i> [a-na <sup>d</sup> A-nu-ni-tu <sub>4</sub> ]	
	11'. [1 GADA <i>sal-ḥu</i> 1 <i>ku</i> ]- <i>si-tu</i> <sub>4</sub> <sup>r</sup> x <sup>1</sup> [] 12'. [1 GADA <i>sal-ḥu</i> 1 GADA <i>gú</i> ]- <i>ḥal-ṣu</i> <sup>r</sup> x <sup>1</sup> []	
	ote the atypical sequence of the garments. The reconstructed words in 1. 7 might syllabically, because it seems that there was not enough space for ideographical	
[, x naḫ	lap]tu-cloaks, 2 [robes for the Daughters of the] Ebabbar	
	nic, 1 linen] <i>ḫullānu</i> -cloak, 1 lin[en scarf, 1 <i>patin</i> ] <i>nu</i> -belt, the <i>lubār mēṭu ir</i> [ <i>kulūlu</i> -headbands for Bunene]	
	unics, 1] blue-purple [ro]be, [1] multicoloured [naḥlaptu-cloak], 1 [blue- ḥlaptu-cloak, [3 red naḥlaptu-cloaks] for Šarra[t Sippar]	
šammamu	tunics, 1] r[ed² linen] <i>ḫullānu-</i> cloak, [x <i>naḫlaptu-</i> cloaks], <i>lubār</i> -garment [for Anunītu]	
[1 linen tu	nic, 1 ro]be, <sup>r</sup> x¹ []	
[1 linen tunic, 1 linen sc]arf, [].		
<b>284a. BM 66394</b> (82-9-18, 6387) PLATE 59 4.8 × 3.1 cm		
Edge Rev.	1'. [] <sup>r</sup> x¹ 2'. [ TÚG.ḤI.A me]-ṭu 3'. [ a-a]-ri pa-ni šá <sup>d</sup> GAŠAN Sip-par <sup>ki</sup> 4'. [ TÚG.NÍ]G.ÍB.LÁ šá <sup>d</sup> rBu¹-ne-ne 5'. [] SÍG.ZA.GÍN.KUR.RA 6'. [x GÍN KI.LAL TÚG.ḤI]. <sup>r</sup> A¹ me-ṭu TÚG.ḤI.A ku-lu- <sup>r</sup> lu¹ 7'. [() šá <sup>d</sup> B]u-ne-ne 8'. [x GÍN KI.LAL] TÚG.ḤI.A me-ṭu TÚG.ḤI.A <sup>r</sup> ku¹-lu-lu šá <sup>d</sup> IM 9'. [x GÍN] KI.LAL TÚG.ḤI.A ku-lu-lu	

```
10'. [.... a-a]-ri pa-ni šá <sup>d</sup>Ša-la
            11'. [.... t]a-bar-ri KI.LAL 2-ta TÚG.BAR.DU<sub>8</sub>.MEŠ
            12'. [.... me] š ſšá dDUMU.MÍ.<MEŠ> É-babbar-ra¹
Ll. 3' and 10'. Or instead of a-a]-ri to read lu-ba]-ri?
[...., lubār mē]tu headband [.... (one) with] front [ro]sette for Queen of Sippar
[....] belt for Bunene
[....] blue-purple
[x shekels, the weight of the lubā] r mēṭu (and) lubār kulūlu headbands for Bunene
[x shekels, the weight], the lubār mēţu (and) lubār kulūlu headbands for Adad
[x shekels], the weight of the lubār kulūlu [(including one) with] front ro[sette] for Šala
[..... r]ed wool, the weight of two robes [....] for the Daughters of the Ebabbar.
285. BM 71048 (82-9-18, 11050)
3.1 \times 5.0 cm
              1. [....] <sup>r</sup>x<sup>1</sup> šá a<sup>?</sup>-na
             2. [....] U<sub>4</sub>.27.KAM
             3. [....] LUGAL TIN.TIR<sup>ki</sup>
             4. [....]-nu na-ba-as-su
             5. [....]-ṣu 1<sup>en</sup> pat-ti-in
             6. [....] 1<sup>en</sup> TÚG.ḤI.A
Rest broken
Rev. uninscribed
[....] the 27<sup>th</sup> day [....], king of Babylon
[....] red [....]
[.... sca]rf, 1 patinnu-belt [....], 1 lubār [....]
286. BM 71903 (82-9-18, 11906)
7.3 \times 3.6 cm
Obv.
             1'. [....] 2-ta [kusītu]
             2'. [a-na <sup>d</sup>DUMU].MÍ.<MEŠ> \acute{E}-babbar-[ra] 3'. [.... g\acute{u}]-\rlap/pal-\rlap/su 1 <sup>túg</sup>[....]
             4'. [a-na^d]^rBu^1-ne-ne
             5'. [....] SÍG.ḤÉ.ME.DA 1 TÚG.UD.A BABBAR-ú
             6'. [.... <sup>d</sup>GAŠAN UD.K]IB.NUN<sup>ki</sup>
L.e.
             7'. [.... t]u<sub>4</sub><sup>?</sup> SÍG.ḤÉ.ME.DA 1 ku-si-tu<sub>4</sub>
Rev.
             8'. [....] TÚG.ÍB.LÁ¹ SÍG.HÉ.ME.DA
```

```
9'. [....] 「x <sup>túg</sup>lu-ba-ru¹ SÍG.ḤÉ.ME.DA
           10'. [....] 4<sup>?</sup> TÚG.Ú[R ....]
           11'. [....] [x x x 1 [....]
L. 5'. A white lubāru-garment for the Queen of Sippar appears only in this text.
L. 10'. The signs are very badly preserved and the reading TÚG.Í[B is also possible.
[....], 2 [robes for the Daugh]ters of the Ebabbar
[.... s]carf, 1 [.... for] Bunene]
[....] red [....], 1 white lubāru-garment [.... for the Queen of Si]ppar
[....] red [....], 1 robe [....] red nēbeḥu-belt
_____
[....] red lubāru-garment, [....] 4 sūnu-belts [....].
286a. BM 58779 (82-7-14, 3188)
                                                                              PLATE 59
3.9 \times 4.2 \text{ cm}
            1'. [....] <sup>rd¹</sup>[DN]
            2'. [....] 「šá¹ <sup>d</sup>DUMU.MÍ 「É-babbar-ra¹
            3'. [.... pa-t]i-in-nu
            4'. Blank in preserved part
            _____
            5'. [\dots 1^e]^t na-hal-lap-tu<sub>4</sub> bir-mu
            6'. [....]-ni 1<sup>et</sup> ku-si-<sup>[tu4]</sup> šá <sup>d</sup>GAŠAN S[ip-par<sup>ki</sup>]
            1'. [....] - [in - [....]
2'. [.... d] IM
Rev.
            3'. [.... 1]^{et} [ku-si]-tu4 šá dŠa-la 4'. [....] ^{\mathrm{md}}UTU-NUMUN]-[GÁ]L^{\tilde{s}i}
Rest lost
In. Obv. 4' the name of Bunene is expected.
L. 6'. Maybe [lu-bar pa]-ni.
Rev. 1'. Probably [pa-ti]-in-[nu].
[....] the Daughters of Ebabbar
 -
[....] patinnu-belt [for Bunene<sup>?</sup>]
[....] one multicoloured cloak, [....], 1 robe for Queen of S[ippar]
[.... pat]in[nu]-belt, [.... for] Adad
```

```
[...., o]ne robe for Šala
[.... were given to?] 「Šamaš-zēr-ušabši1.
286b. BM 58810 (82-7014, 3219)
                                                                                     PLATE 60
4.7 \times 3.7 cm
             1'. [....] 「3<sup>?¹ t</sup>[<sup>úg</sup> ....]
             2'. [....] 「ḫu-la-nu [..]
             3'. [....] 「GADA<sup>?</sup>」「x¹
             4'. [.... h]u^2-la [x x x] [....]
            1'. [.... n]a-hal-ap-tu_41-ta {}^{t\acute{u}g}k[u-si-tu_4?]
2'. a-na {}^d Gu1-[la]
Rev.
             3'. [.... gú]-ḥal-ṣu 1 pa-t[in-nu]
             4'. [.... š]á <sup>d</sup>IM
             ______
             5'. [.... 1 na-hal]-lap-tu_4 1 t^{[úg?}....]
Rev. 1'. Or 1-ta ku-[si-tu_4]?
[....] 3 [naḥlaptu-cloaks ....]
[....] hullānu-cloak [....]
[....] linen [....]
[\dots hu]ll\bar{a}[nu-cloak^{?}[\dots]]
[...., 1] naḥlaptu-cloak, 1 r[obe] for Gula
[...., 1 sc]arf, 1 pati[nnu-belt f]or Adad
```

[...., 1 *nah*] *laptu*-cloak, 1 [....].

# IX. The mixed classical dullu peşû and miḥşu tenû texts

287. VS 6, 26 (VAT 161); cf. NUVI 3, No. 242

27. LUGAL E<sup>ki</sup>

## 8.2.Nbk 6

1. 37 ma-na KI.LAL TÚG.HI.A 2. 2 TÚG.MÁŠ.MEŠ 4 TÚG.ÚR.MEŠ 7 TÚG.NÍG.ÍB.LÁ.MEŠ 3. šá <sup>d</sup>UTU 10\* TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a 4. TÚG.ḤI.A TÚG.MÁŠ *šá* <sup>d</sup>Bu-ne-ne 5. 19 5/6 ma-na [KI.LA]L TÚG.HI.A 6. 1<sup>en</sup> TÚG.MÁŠ 1<sup>en</sup> TÚG.ÚR 7. 1<sup>en</sup> TÚG.BAR.SI 10 TÚG.NÍG.ÍB.LÁ.MEŠ 8. šá <sup>d</sup>IM u <sup>d</sup>Ša-la 9. 2 ma-na 50 GÍN KI.[LAL] 10. TÚG.MURUB<sub>4</sub>.ÍB.LA TÚ[G.ÍB.LÁ] 11. TÚG.ḤI.A ku-lu-lu [TÚG.ḤI.A me-ṭu šá <sup>d</sup>UTU] Edge 12. 12 *ma-na* 50 GÍN KI.[LAL] Rev. 13. TÚG.BAR.[DUL<sub>5/8</sub>] 1 TÚG.GÚ.UD.DU 14. TÚG.HI.[A k]u-lu-lu 3 TÚG.BAR.「SI¹.M[EŠ] 15. *šá* <sup>d</sup>*A-a* 16. 15 GÍN KI.LAL TÚG.HI.A ku-lu-lu TÚG. HI.A me-tu<sup>1</sup> 17. *šá* <sup>d</sup>IM 18. ½ ma-na KI.LAL TÚG.{「MURUB<sub>4</sub>.}ÍB¹.[LÁ TÚG.ḤI].「A<sup>¹</sup>¹ ku-lu-lu 19. TÚG.ḤI.A me-<sup>r</sup>tu¹ šá <sup>d</sup>Bu-ne-ne 20. 1 ma-na <sup>r</sup>x<sup>1</sup> [GÍN] KI.LAL 2-ta TÚG.BAR.SI.MEŠ 21. 2-ta TÚG.GÚ.UD.DU.MEŠ šá DUMU.MÍ.MEŠ É-babbar-ra 22. ½ ma-na 7 GÍN KI.LAL TÚG.HI.A ku-lu-lu 23. 2<sup>!</sup>(T: 3)TÚG.BAR.SI.MEŠ *šá* <sup>d</sup>Š*a-la* L. e. 24. md AG-EN-MU.MEŠ lúUŠ.BAR ma-hir 25. ITI.GU<sub>4</sub> U<sub>4</sub>.8.KAM MU.6.KAM L. h.e. 26. md AG-NÍG.DU-ÙRU

- L. 9. Salonen, NUVI 3, No. 242 added also TÚG.ḤI.A, however, because *patinnu* (TÚG.MURUB<sub>4</sub>.ÍB.LÁ) is never written as *lubār patinni*, I prefer to read KI.[LAL]. Cf. also BM 51274 (= 288): 13-14.
- Ll. 12–13. Salonen's reading 12 *ma-na* 50 GÍN KI.[LAL TÚG.ḤI.A] <sup>13</sup>TÚG.「MAŠ<sup>?</sup>¹ cannot be accepted because *lubāru* and *şibtu* appear exclusively as the items of the gods' clothing. The suggested reading has parallel in CT 4, 38a (= 178): 4–7, where *kusītu* is followed by *naḥlaptu* and 3 *paršīgu*<sup>meš</sup>. Also the weight of these three garments in VS 6, 26 (= 287) is similar to the weight of the same garments in CT 4, 38a, i. e. respectively 12 minas 50 shekels and 12 minas 43 shekels.
- L. 16. I read TÚG. ḤI.A *me-ṭu*¹, contra Salonen's TÚG. ḤI.A BAR.SI <sup>??</sup> because BAR.SI is never preceded with TÚG. ḤI.A. and the suggested reading has a parallel in CT 4, 38a: 17–19. L. 18 is written over erasure. The numeral <sup>†</sup>1¹ before *ku-lu-lu* in Salonen, NUVI 3, No. 242, is in fact the rest of the sign A in TUG. ḤI. <sup>†</sup>A¹. For reading, cf. BM 51274 (= 288): 13–14. L. 23. Concerning the numeral, cf. below BM 51274 (= 288): 15.
- 37 minas, the weight of the *lubāru*-garment, 2 *ṣibtu*-garments 4 *sūnu*-belts, 7 sashes for Šamaš, 10 sashes for Aya, the *lubāru* (and) *ṣibtu*-garments for Bunene 19 minas, 50 shekels, [the we]ight of the *lubāru*-garment, 1 *ṣibtu*-garment, 1 *sūnu*-belt, 1 *paršīgu*-headdress, 10 sashes for Adad and Šala.
- 2 minas 50 shekels, the wei[ght] of the *patinnu*-belt, the *nēbeḥu*-belt, the *lubār kulūlu* (and) [the *lubār mēṭu*]-headbands for Šamaš]

12 minas 50 shekels, the weig[ht] of ro[be], 1 *naḥlaptu-*cloak, the *lubār kulūlu-*headband, 3 *paršīgu-*headdresses for Aya

\_\_\_\_\_

15 shekels the weight of the *lubār kulūlu* (and) the *lubār mēṭu*-headbands for Adad

 $\frac{1}{2}$  mina, the weight of the  $n\bar{e}behu$ -belt, the  $[lub\bar{a}r]$   $kul\bar{u}lu$  (and) the  $lub\bar{a}r$   $m\bar{e}tu$ -headbands for Bunene

-----

1 mina  $\lceil x \rceil$  [shekels], the weight of 2 *paršīgu*-headdresses (and) 2 *naḥlaptu*-cloaks for the Daughters of the Ebabbar

-----

37 shekels, the weight of *lubār kulūlu* (and) 2<sup>!</sup> *paršīgu*-headdresses for Šala (all these garments) are received from Nabū-bēl-šumāti.

Month of Ayaru, 8<sup>th</sup> day, 6<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

**288. BM 51274** (82-3-23, 2308)

PLATE 61

 $6.8 \times 5.5$  cm

8.2.Nbk 2+[x]

- 1. 45 2/3 ma-[na KI.LAL TÚG.ḤI.A]
- 2. <sup>[2]</sup> [TÚ]G.MÁŠ.[MEŠ 4 TÚG.ÚR.MEŠ]
- 3. 7 TÚG.NÍG.ÍB.LÁ.<MEŠ> 「šá <sup>d</sup>UTU¹ [10 TÚG.NÍG·ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]

4. 19 <sup>5</sup>/6 [ma-na KI].LAL 1 TÚG.ḤI.'A 1 TÚG.'MAŠ 1

# 5. 1 TÚG. TÚR 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>IM 6. [2<sup>?</sup>] ma-na 15 GÍN ta-bar-ri 7. [u ta-ki]l²-ti KI.LAL 1 ni-bi-iḫ-'ħu¹ 8· 「1 TÚG.ḤI.A¹ ku-lu-lu TÚG.ḤI.A me-ṭu š[á <sup>d</sup>UTU] 9. [1] 「TÚG¹.BAR.DUL<sub>8</sub> 1 GÚ.UD.DU <1> TÚG.ḤI.A k[u-lu-lu] 10. [3 par-ši]-ga-nu šá <sup>d</sup>「A¹-[a] 11. [1+]1 TÚG.BAR.SI.MEŠ 2 TÚG.GÚ.UD.D[U.MEŠ] 12. šá <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-r[a] 13. ni-bi-iḫ-ḫu <1> TÚG.ḤI.A 「ku¹-[lu-lu] 14. TÚG.ḤI.A me-ṭu šá <sup>d</sup>Bu-n[e-ne]

15. TÚG.ḤI.A ku-lu-lu 2 par-ši-ga-nu [šá <sup>d</sup>Ša-la]

..... 100.iji.A ku-tu-tu 2 par-st-ga-nu [sa ˈsa-ta]

16. <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>ΓUŠ.BAR<sup>1</sup> [*ma-ḥir*]

17. ITI.GU<sub>4</sub> U<sub>4</sub>.8.KAM MU.2+[x.KAM]

Rev.

18. <sup>md</sup>AG-NÍG.DU-ÙRU LUGAL TIN.TIR<sup>[ki]</sup>

The text is very similar to VS 6, 26 (= 287) and partly to CT 4, 38a (= 178).

Ll. 1–3, cf. VS 6, 26 (= 287): 1–3. The date (8<sup>th</sup> Ayaru) suggests that the garments were destined for the *lubuštu* ceremony on the 10<sup>th</sup> day of the month. According to other texts in this cycle Šamaš received 1 *lubāru* (20 minas) + 2 *şibtus* (in total 20 minas) + 4 *sūnus* (together with Aya, in total 1 mina 20 shekels) + 7 *huṣannus* (1 mina 10 shekels) + 10 *huṣannus* for Aya (1 mina), which gives in total 43 minas 30 shekels, as against 45 minas 40 shekels. The comparison with BM 50626 (= 308): 1–5 suggests that the scribe forgot to write the *lubār mē qaqqadi*, but this would give only 45 minas 30 shekels, i.e. still 10 shekels too little. An alternative possibility is that the scribe omitted by mistake the *lubāru* and *şibtu* for Bunene (cf. VS 6, 26: 1–4), which according to BM 50626 (= 308): 5–6 weighed exceptionally 2 minas 10 shekels. Note however, that at the beginning of Nebuchadnezzar's reign the weight of some items was sometimes lower, but occasionally also higher.

Ll. 4–5, cf. VS 6, 26: 5–7. In both texts the weight is the same (in BM 51274 (= 288) it lacks paršīgu) and in both, taking into account the typical total weight of items, it is too small. 1 lubāru for Adad (15 minas) + 1 şibtu (5 minas) + 1 paršīgu (20 shekels) + 1 sūnu (20 shekels) + 10 huṣannus for Adad and Šala (50 shekels) gives in VS 6, 26 21 minas 30 shekels and 21 minas 10 shekels [without paršīgu] in BM 51274. 10 huṣannus in 1. 5, although only the name Adad is quoted, belonged evidently to both Adad and his spouse Šala, cf. for example BM 51099 (= 293) obv. I 9'–10'; BM 51447 (= 294) obv. I 1'–2'; BM 51659 (= 296) Col. II 5'–6' and many other.

Ll. 6–8 should be compared with VS 6, 26: 9–11. Both texts include *lubār kulūlu* and *lubār mētu*, but in BM 51274: 7 only *nēbeḥu* is mentioned, while in VS 6, 26: 10 a *patinnu* and most probably also a *nēbeḥu* (TÚG.[ÍB.LÁ]).

Ll. 9–10, cf. VS 6, 26: 12–15. BM 51274 makes possible the proper reconstruction of VS 6, 26 as against Salonen, NUVI 3, 242. By comparison with VS 6, 26: 14, I reconstruct the numeral <sup>13</sup> 1, although only two vertical strokes are preserved. This entry is followed in VS 6, 26 by the entry including *lubār kulūlu* and *lubār mēţu* for Adad, which in BM 51274 appears in. l. 15.

LÎ. 11–12, cf. VS 6, 26: 20–21. BM 51274 gives no information about the weight, while in VS 6, 26, according to Ungnad's copy, there is 1 ma-na [x1] [GÍ]N, which seems far too little

for 2 paršīgus and 2 naḥlaptus. Is only the coloured wool mentioned there? Note also that a few years later Nabû-bēl-šumāti delivered again 2 nahlaptus, and 2 kusītus (instead of 2 paršīgus) weighing 50 shekels (CT 4, 38a dated to 13th year of Nebuchadnezzar).

Ll. 13-14, cf. VS 6, 26: 18-19. The comparison of these lines suggests that MURUB<sub>4</sub> in VS 6, 26: 18 was written by mistake and the scribe probably tried to erase it.

L. 15, cf. VS 6, 26: 22–23. The reconstruction [Ša-la] is suggested by the comparison with VS 6, 26: 23 and CT 4, 38a: 20–21. The reconstruction [IM] is rather excluded, because he received only 1 paršīgu. As in this text and in CT 4, 38a there are 2 paršigānu, in VS 6, 26 the numeral 3 was amended to 2. Note that according to VS 6, 26: 22 for manufacturing these garments 37 shekels is given, whereas in CT 4, 38a: 20 only 34 shekels of wool was

45 minas 40 she[kels, the weight of  $<1> lub\bar{a}ru$ -garment] <sup>[2]</sup> *şibtu*-garments, [4 *sūnu*-belts], 7 sashes for Šamaš [10 sashes for Aya].

19 minas 50 [shekels], the weight of 1 lubāru garment, <1> sibtu garment, 1 sūnubelt, 10 sashes for Adad.

\_\_\_\_\_

[2<sup>?</sup>] mina 15 shekels of red wool [and blue-p]urple wool, the weight of 1 nēbehubelt, 1 lubār kulūlu (and) <1> lubār mēṭu-headbands for [Šamaš]

[1] robe, 1 naḥlaptu-cloak, <1> lubār kulūlu headband (and) 3 paršīgu-headdresses for Ay[a]

2 paršīgu-headdresses, 2 nahlaptu-cloaks for the Daughters of the Ebabbar

\_\_\_\_\_

<1> nēbeļu-belt, a lubār kulūlu (and) a lubār mēţu-headbands for Bunene

\_\_\_\_\_

A lubār kulūlu-headband (and) 2 paršīgu-headdresses for [Šala]

\_\_\_\_\_

(all these) [were received] from Nabû-bēl-šumāti, the weaver. Month of Ayaru, 8th day, 2+[x] year of Nebuchadnezzar, king of Babylon.

# 289. BM 65975 (82-9-18, 5967)

PLATE 62

 $5.0 \times 4.8 \text{ cm}$ 

Nbk

1'. [x m]a-na KI.LAL [TÚG.HI.A šá <sup>d</sup>UTU] Obv.

2'. [x m]a- $\lceil na \rceil$  KI.LAL [ $^{\text{túg}}$ sib]- $tu_4$  [š $\acute{a}$   $^{\text{d}}$ UTU] 3'. [x TÚG]. $\lceil \text{NÍG.ÍB} \rceil$ .LÁ.MEŠ š $\acute{a}$   $^{\text{d}}$  $\rceil$ UTU $\rceil$ 

4'. 「TÚG¹.[HI].「A me¹-e SAG.DU šá <sup>d</sup>[UTU]

5'. 10 TÚG.[NÍG.ÍB].LÁ.MEŠ šá <sup>d</sup>A-[a]

6'. 10 TÚG.[NÍG.ÍB.LÁ].MEŠ [šá d][GAŠAN Sip-parki]

Rest lost

Rev. 1'. 「31 [....]

2'. [x] [....]

```
3'. 「6¹ GÍN KI.LA[L ....]
3a'. TÚG.MÁŠ [....]
4'. 54 GÍN KI.LAL 3 <sup>túg</sup>[na¹-[aħ]-[lap¹-[tu₄]]
5'. 1 TÚG.ḤI.A <sup>túg</sup>ku-lu-lu 「TÚG.SÍG¹.ZA.GÌN.<KUR>.RA šá <sup>d</sup>「x¹ [x x]
6'. 59 GÍN KI.LAL 2-ta TÚG.BAR.DUL<sub>8</sub>.M[EŠ ....]
7'. [x]-[ta¹ [G]Ú.UD.DU.MEŠ TÚG.ḤÉ.ME.DA šá <sup>d</sup>「DUMU¹.[MEŠ]
8'. [x x x] KI.LAL TÚG.ḤI.A ku-lu-lu TÚG.[ḤI.A MEŠ I.A me-ṭu]
8a'. [šá <sup>d</sup>DUMU.MÍ.MEŠ] É-babbar-ra
9'. [x x x x x] KI.LAL 2 TÚG.「SI²:BAR x¹ [....]
10'. [x x x x x x x SÍG.Ḥ]É.ME.DA 「šá¹ [....]
```

Rest lost

L.h.e. 11'. [mdAG-NÍ]G.DU-ÙRU LUGAL TIN.TIRki

Rev. 3a' is written between 3' and 4' and 8 a' between 8' and 9' lines.

Rev. 5'. TÚG and SÍG are written over an erasure.

Rev. 7'. Only the beginning of the name of the goddess(es) is preserved and many different identification are possible:  ${}^{d}GA[\check{S}AN.ME\check{S}]$  (because here it lacks place for DU[MU.MÍ. MEŠ  $\acute{E}$ -babbar-ra] or even  $\check{S}[a$ -la], which is rather improbable because she never preceded "the Daughter of Ebabbara" mentioned in 1. 8'.

L. 9'. Instead of the reading SI also lu is not excluded; the BAR looks like written over erasure.

[x mi]nas, the weight [of the *lubāru*-garment for Šamaš]

[x mi]nas, the weight [of the sib]tu-garment [for Šamaš (and)]

the sashes for Šamaš, the *lubār mē qaqqadi*-headdress [for Šamaš], 10 sa[she]s for A[ya] (and) 10 sa[she]s for [the Queen of Sippar]

3 [....]

[....] 6 shekels, the weig[ht ....], the *sibtu*-garment [....]

54 shekels, the weight of 3  $nahla[ptus-cloaks^2, 1]$  blue-purple  $lub\bar{a}r$   $kul\bar{u}lu-headdress$  for the goddess [x]

59 shekels, the weight of 2 robe[s  $(x \ x \ x)$ ] [x] red *naḥlaptu-cloak*(s) for the Dau[ghters of the Ebabbar<sup>?</sup>]

[....], the weight of  $lub\bar{a}r\ kul\bar{u}lu$  (and)  $lub\bar{a}r\ [m\bar{e}tu]$ -headbands [for the Daughters of the] Ebabbar

[....], the weight of 2 paršīgu-headdresses [....] of red [....]

[.... Nebu]chadnezzar, king of Babylon.

**290.** Cyr **232** = BM 92787; cf. NUVI 3, No. 120; Giovinazzo 1981, No. 12 Collated  $8.6 \times 6.7$  cm

4.VII.Cyr 6

- 1.  $[dul-lu\ BABBAR^{\acute{u}}\ \check{s}\acute{a}\ lu-b]u-u\check{s}-tu_4\ \check{s}\acute{a}\ U_4.7.KAM\ \check{s}\acute{a}\ ITI.DU_6$
- 2. [šá <sup>m</sup>Ba-k]u-ú-[a <sup>lú</sup>ga]l-la šá <sup>md</sup>AG-PAP-A <sup>lú</sup>UŠ.BAR

	3. [ $id$ - $d$ ] $in$ *- $nu$ ITI.DU $_6$ [U $_4$ ].4*.KAM MU.6.KAM $^{\rm m}$ $Ku$ - $ra$ š LUGAL E $^{\rm ki}$ LUGAL KUR.KUR
	4. 「20」 ma-na KI.LAL TÚG.ḤI.A šá <sup>d</sup> UTU e-lat ½ ma-na SÍG.ZA.GÌN.KUR.RA 5. [10 m]a-na KI.LAL TÚG.MÁŠ šá <sup>d</sup> UTU 6. [1 ma]-na KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> UTU 7. [2 ma]-na KI.LAL TÚG.ḤI.A me SIG <sup>qá</sup> /.GA šá <sup>d</sup> UTU 8. [1 ma-n]a 1/3* GÍN KI.LAL TÚG.ḤI.A 4 TÚG.ÚR.MEŠ šá <sup>d</sup> UTU
	9. [1 ma-n]a KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> A-a
	10. [1 <i>ma-n]a</i> KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup> GAŠAN <i>Sip-par</i> <sup>ki</sup>
	11. [1 ma-na K]I.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> A-nu-ni-tu <sub>4</sub>
	12. [2 ma-na KI.LAL TÚG.ḤI.A] u TÚG.MÁŠ šá <sup>d</sup> Bu-ne-ne { <sup>r</sup> ta <sup>?</sup> 1 din }
Edge Rev.	13. [] x GÍN 10 TÚG SA5 <i>it-ta-din</i> 14. [ <i>mi-iḫ-ṣu</i> ] <i>te-nu-ú šá</i> ITI.DU <sub>6</sub> <i>a-na</i> <sup>md</sup> UTU-MU-MU <sup>lú</sup> TÚG.BABBAR SUM <sup>na</sup>
	15. [2] GADA <i>sal-ḫu</i> 1 GADA <i>ḫu-la-nu</i> 1 TÚG.SAG <sup>?</sup> SÍG.ḤÉ.ME.DA 16. [1] GADA <i>gú-ḫal-ṣu</i> 2 TÚG.MÁŠ <i>a-na</i> <sup>d</sup> UTU
	17. [2] GADA sal-ḫu 4 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA 1 <sup>et</sup> TÚG.GÚ.UD.DU bir-mu 18. [1+]1 TÚG.BAR.SI.MEŠ 1 <sup>et</sup> ku-si <sup>!</sup> -tu <sub>4</sub> * SÍG.ḤÉ.ME.DA a-na <sup>d</sup> A-a
	19. [1+]1 GADA sal-ḫu 6 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA 2 ku-si-tu <sub>4</sub> SÍG.ḤÉ.ME.DA 20. a-na <sup>d</sup> DUMU.MÍ.MEŠ É-babbar-ra
	21. 1 GADA <i>sal-ḥu</i> 1 GADA <i>ḥu-la-nu</i> 1 GADA <i>gú-ḥal-ṣu</i> 1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ SÍG.ḤÉ.ME.DA 22. [1 TÚ]G.ÍB.LÁ <i>a-na</i> <sup>d</sup> Bu-ne-ne
	23. [1 GAD]A <i>sal-ḫu</i> 5 TÚG.GÚ.UD.DU SÍG.ḪÉ.ME.DA 1 TÚG.ḤI.A <i>a-na</i> <sup>d</sup> GAŠAN <i>Sip-par</i> <sup>ki</sup>

```
24. [2<sup>?</sup> GADA sal-ḫ]u 3 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA
1 <sup>túg</sup>hu-la-nu SÍG.ḤÉ.ME.DA
25. [1 pa-tin-nu SÍ]G.ḤÉ.ME.DA 1 TÚG.ḤI.A MURUB<sub>4</sub>
1 TÚG.ḤI.A SÍG.ḤÉ.ME.DA taš-kis
26. [x x x] áš 2* TÚG.BAR.SI.MEŠ a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub>
27. [2 GADA sal-ḫu 1 TÚG.GÚ.UD.DU] 「SÍG.ḤÉ.ME.DA¹
1 ku-si-tu<sub>4</sub> SÍG.ḤÉ.ME.DA a-na <sup>d</sup>「ME*¹.ME*
28. [1 GADA sal-ḫu 1 GADA gú-ḫal-ṣu 1] TÚG.ÍB.LÁ
1 TÚG.MURUB<sub>4</sub>.ÍB*.LÁ a-na <sup>d</sup>[IM]
29. [1 GADA sal-ḫu 1 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.D]A¹
```

The left side of the text is broken a little more than is suggested by Strassmaier's copy. L. 7. *me* in *me* SIG looks in fact as *bar*.

1 ku-si-tu<sub>4</sub> KI.MIN a-na <sup>d</sup>Ša-la

- L. 12. At the end of the line there are two signs, the first evidently erased (similar to *ta*), the second is clearly *din*. Probably the scribe tried to erase it but it possibly went uncorrected for some reason.
- L. 14. [mi-iḥ-ṣu] te-nu-ú, contra Bongenaar, Ebabbar, p. 347 who reads GADA.[ḤI.A] te-nu-ú L. 25. taš-kis is missing in NUVI 3, No. 120 as well as in AHw 1330 b, s. v. tarkīsu. G. Giovinazzo 1981, p. 554 reads UR.MAḤ (most probably under of influence of NUVI 3, No. 120, where the taš-kis is missing, however, in the translation it appears "(für) die Löwe". Apart from this text it appears also in Cam 36: 4 (so already AHw 1330 b, s.v. tarkīsu, contra Bongenaar, Ebabbar, p. 335), in BM 68348+ (= 291): 17, and maybe in BM 64651 (= 221): 13. Concerning this ornament, see Beaulieu, Orientalia 67 (1998), p. 182 and n. 18. L. 26. The reading [KI].MIN at the beginning of line, suggested by Salonen, is excluded.
- Strassamier's copy seems accurate, however, I have no idea how to read it.

  L. 28. The god's name, which Salonen and Giovinazzo have read as <sup>d</sup>BE does not exist at all and the reading IM is suggested on the basis of many parallels.

[White work for the *lub*]*uštu* ceremony for the 7<sup>th</sup> day of Tašrītu, [which Bak]û[a, the sla]ve of Nabû-nāṣir-apli, the weaver [has delive]red. Month Tašrītu, 4<sup>th</sup> [day], 6<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

6" year of Cyrus, king of Babylon, king of Lands.

20 minas, the weight of the *lubāru*-garment for Šamaš with addition of ½ mina of blue-purple wool

[10 mi]nas, the weight of the *şibtu*-garment for Šamaš

[1 mi]na, the weight of 6 sashes for Šamaš

[2 mi]nas, the weight of the *lubār mēsiqu*-headdress for Šamaš

[1 min]a 20 shekels, the weight of 4 *sūnu*-belts for Šamaš

[1 min]a, the weight of 10 sashes for Aya

[1 min]a, the weight of 10 sashes for the Queen of Sippar

[1 min]a, the weight of 10 sashes for Anunītu

[2 minas, the weight of the *lubāru*] and *ṣibtu*-garments for Bunene

[.....] shekel, 10 red garment he (Bakûa?) has given

Woven garments for the change for the month Tašrītu given to Šamaš-šum-iddin, the ašlāku

[2] linen tunics, 1 linen  $hull\bar{a}nu\text{-}cloak$ , 1 red SAG-garment, [1] linen scarf, 2 sibtugarments for Šamaš

[2] linen tunics, 4 red *naḥlaptu*-cloaks, 1 multicoloured *naḥlaptu*-cloak, <sup>7</sup>2<sup>7</sup> *paršīgu*-headdresses, 1 red robe for Aya

<sup>7</sup>2<sup>7</sup> linen tunics, 6 red *naḥlaptu*-cloaks, 2 red robes for the Daughters of the Ebabbar

.----

1 linen tunic, 1 linen *ḫullānu*-cloak, 1 linen scarf,

1 red *patinnu*-belt, [1 *nē*]*beḫu*-belt for Bunene

[1 line]n tunic, 5 red nahlaptu-cloaks, 1  $lub\bar{a}ru$ -garment for the Queen of Sippar

.....

[2] linen tuni]cs, 3 red *naḫlaptu*-cloaks, 1 red *ḫullānu*-cloak, [1] red [*patinnu*-belt], 1 *lubār qabli*-loincloth, 1 red *lubāru*-garment with *tarkīsu*-ornament, [.....], 2 *paršīgu*-headdresses for the Anunītu

-----

[2 linen tunics, 1] red [naḥlaptu]-cloak, 1 red robe for Gula

[1 linen tunic, 1 linen scarf, 1] *nēbeḥu*-belt, 1 *patinnu*-belt for [Adad]

[1 linen tunic, 1 re]d [nahlaptu- cloak], 1 robe for the Šala.

## 291. BM 68249+BM 68348+BM 101457

PLATE 63

(82-9-18, 8247+8346+83-1-21,3118)

 $7.2 \times 6.0 \text{ cm}$ 

## 5.7.[Cyr/Camb] 7

- 1. [mi-iḥ-ṣ]i te-nu-ú šá lu-bu-u<br/>š-tu<sub>4</sub> šá 'U<sub>4</sub>'.[7.KAM šá IT]I.DU $_6$  MU.7.KAM
- 2.  $^{[m]_{\Gamma}}$   $^{d_1}$ UTU-MU-MU  $^{l\acute{u}}$ TÚG.BABBAR SUM $^{na}$  I[TI.DU $_6$ ]  $^{\Gamma}$ U $_4$ .51.KAM

-----

- 3. [2 GADA *sal-h*]*u* 1 GADA *hu-la-nu* 1 GADA *gú-hal-*<sup>r</sup>*su*<sup>1</sup> 1 TÚG.ÍB.LÁ SÍG.HÉ.ME.DA
- 4. [1 TÚG.MURUB<sub>4</sub>.ÍB.L]Á 2 <sup>túg</sup> șib-tu<sub>4</sub> a-na <sup>d</sup>UTU 1[+1]GADA sal-ḫu
- 5. [4 TÚG.GÚ.UD.D]U SÍG.ḤÉ.ME.DA  $1^{et}$  TÚG.GÚ.「UD¹.DU bir-mu  $1^{et}$   $ku-si-tu_4$
- 6. [SÍG.HÉ.M]E.DA 2 TÚG.BAR.SI.<MEŠ> SÍG.HÉ.ME.DA  $^{72}$ 7 TÚG.BAR.SI a-na  $^{d}A$ -a

- 7. [2 GADA sal]-ḫu 4 TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA [1+]1-ta ku-si-tu<sub>4</sub> a-na MÍ:DUMU.MEŠ É-babbar-ra
- 8. [1 GADA sal]-hu 1 GADA hu-la-nu 1 GADA gú-[hal-ṣ]u 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ
- 9. [1 TÚG.Í]B.LÁ *a-na* <sup>d</sup>*Bu-ne-ne* 2 G[ADA *sal-hu*] <sup>75</sup> TÚG.GÚ.UD.DU SÍG.ḤÉ.ME.DA
- 10. [1 ku-si-tu<sub>4</sub> a-na <sup>d</sup>]GAŠAN Sip-par<sup>ki</sup> 2 GADA sal-<sup>†</sup>ḫu<sup>†</sup> [1<sup>et</sup> TÚG.GÚ.U]D.DU SÍG.ḤÉ.ME.DA
- 11. [1 ku-s]i-tu<sub>4</sub> SÍG.ḤÉ.ME.DA a-na [<sup>d</sup>Gu-la] 2 GADA sal-ḥu
- 12. [3 TÚG.G]Ú.UD.DU SÍG.ḤÉ.ME.DA 1 ħu-[la-nu SÍG.ḤÉ].ME.DA 1 TÚG.MURUB4.ÍB.LÁ
- 13. [1 TÚG].ÍB.LÁ TÚG.ḤI.A MURUB $_4$  SÍG.ḤÉ.[ME.DA x x x x] SÍG.ḤÉ.ME.DA
- 14. [x TÚG].ḤI.A {*a-na*} *taš-ki*[*s* TÚG.ḤI.A *ku-lu-lu*] 'TÚG.ḤI'.A *me-ṭu* SÍG.'ZA'.GÌN.KUR.RA *a-na* <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 15. [1 GADA *sal*]-<sup>[</sup>*hu*] [1 GADA *gú-ḥal-ṣu* 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ 1 TÚG.ÍB.LÁ *a-na*] <sup>[d</sup>IM]
- 16. [1 GADA sal-ḫu 1 TÚG.GÚ.UD.DU 1 ku-si-tu<sub>4</sub> a-na <sup>d</sup>]Ša-la
- 17. [dul-lu BABBAR-ú šá lu-bu-uš-tu<sub>4</sub> šá U<sub>4</sub>.7.KAM šá IT]I.DU<sub>6</sub> šá MU.7.[KAM]
- 18. [KN LUGAL TIN]. TIR i LUGAL [KUR.KUR šá PN] idi-din-nu ITI.DU<sub>6</sub> U<sub>4</sub>.5.KAM

·

Rev.

- 19. [20 ma-na KI.LAL T]ÚG.ḤI.A šá  $^{\rm rd}$ UTU $^{\rm l}$  [10 ma-na KI.LAL  $^{\rm túg}$ ] $sib^!$ - $tu_4$  šá  $^{\rm d}$ UTU
- 20. [2 ma-na KI.LAL TÚG.Ḥ]I.A me S[IG]<br/> $^{q\acute{a}}$ /.GA [šá $^{d}$ UTU 1] ma-na 1/3 GÍN KI.LAL
- 21. [4 TÚG.ÚR.MEŠ šá <sup>d</sup>]UTU 1 [*ma*]-*na* [KI.LAL 6] TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
- 22. [1 ma-na KI.LAL 10 TÚG].NÍG.ÍB.LÁ.MEŠ [a-na d][A]-a
- 23. [2 ma-na KI.LAL TÚG.ḤI]. 「A EN¹ ṣib-tu4 [a-na] 「d¹Bu-ne-ne
- 24. [1 *ma-na* KI.LAL 10 TÚG].NÍG.ÍB.LÁ.MEŠ [*a-na*] <sup>d</sup>GAŠAN *Sip-par*<sup>ki</sup>
- 25. [x ma-na (x GÍN) KI.LAL TÚG].NÍG.ÍB.LÁ.MEŠ  $^{\dagger}$  $^{\iota}$  $^{\iota}$ 1 TÚG.ÚR 11 GÍN KI.LAL
- 26. [SÍG.Ḥ]É.ME.DA šá <sup>d</sup>A-<sup>r</sup>nu<sup>¬</sup>-[ni]-tu<sub>4</sub> šá Sip-par<sup>ki</sup>-šá
  <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- L. 6. Note that the scribe repeated by mistake [2] BAR.SI before the goddess' name.

[Woven garmen]ts for the change for the  $7^{th}$  Tašrītu of the  $7^{th}$  year, given to Šamaššum-iddin, the  $a š l \bar{a} k u$ . [Month Tašrītu],  $5^{th}$  day

\_\_\_\_\_

- [2] linen tunic]s, 1 linen *hullānu*-cloak, 1 linen scarf, 1 red *nēbehu*-belt, [1 patin]nu-belt, 2 șibtu-garments for Šamaš
- <sup>[2]</sup> linen tunics, [4] red [nahlap]tu-cloaks, 1 multicoloured nahlaptu-cloak, 1 [re]d robe, 2 red paršīgu-headdresses, {[2] paršīgu-headdresses} for Aya
- [2 linen tun]ics, 4<sup>1</sup> red *naḥlaptu*-cloaks, <sup>7</sup>2<sup>1</sup> red robes for the Daughters of the Ebabbar
- [1 linen tun]ic, 1 linen hullānu-cloak, 1 linen s[ca]rf, 1 patinnu-belt, [1 nē]behubelt for Bunene
- 2 li[nen tunics], 5 red *naḥlaptu-*cloaks, [1 robe for] the Queen of Sippar
- 2 linen tunics, [1] red *nahlaptu*-cloak, [1] red [rob]e for [Gula]
- 2 linen tunics, [3] red nahlaptu-cloaks, 1 re[d hul]lānu-cloak, 1 patinnu-belt, [1 nē]behu-belt, <1> red lubār qabli-loincloth, <1> red [....], 1 lu]bāru-garment with tarkis[u-ornament, the blue-purple lubār kulūlu] (and) lubār mēţu-headbands for the Anunītu
- [1] linen tunic, 1 [linen scarf, 1 patinnu-belt, 1 nēbeḥu-belt for] Adad
- [1] linen tunic, [1 nahlaptu-cloak, 1 robe for] Šala.

[White work for the *lubuštu* ceremony for the 7<sup>th</sup> day of] Tašrītu, 7<sup>th</sup> year [of KN, king of Ba]bylon, king of [Lands, which PN] has delivered. Month Tašrītu, 5th day \_\_\_\_\_

[20 minas, the weight of the lu]bāru-garment for Šamaš

[10 minas, the weight of the] *sibtu*-garment for Šamaš

[2 mi]nas, the weight of the *lubār mēsiqu*-headdress [for Šamaš]

- [1] mina 20 shekels, the weight of [4 sūnu-belts for] Šamaš
- [1 mi]na, [the weight of 6] sashes for Šamaš
- [1 mina, the weight of 10] sashes [for] Aya
- [2 minas, the weight of the  $lub\bar{a}$ ]ru-garment together with the *şibtu*-garment [for]
- [1 mina, the weight of 10] sashes [for] the Queen of Sippar
- [x mina (x shekels), the weight of x] sashes and the  $s\bar{u}nu$ -belt {11 shekels}, the weight of red [....] for Anunītu-ša-Sippar-Anunītu.

## **292. BM 61517** (82-9-18, 1490)

PLATE 64

 $11.5 \times 7.6 \text{ cm}$ 

## 30.5.Cam 7

- 1. [dul-lu BABBAR<sup>ú</sup> šá lu-b]u-uš-tu<sub>4</sub> šá U<sub>4</sub>.3.KAM šá ITI.KIN MU.7.KAM šá  $^{\rm m}Kal$ -ba-a 2. [A-šu šá  $^{\rm m}$ x x x u  $^{\rm md}$ DN]-TIN $^{it}$  A  $^{\rm md}$ AG-ki-šìr a-na É-babbar-ra
- id-din-nu
- 3. [i-na muh-hi<sup>?</sup> x x]  $\lceil x \rceil$ - $t\acute{u}$  SUM<sup>na</sup> ITI.NE U<sub>4</sub>.30.KAM MU.7.KAM <sup>m</sup>Kam-bu-zi-ja LUGAL KUR.[KUR] \_\_\_\_\_
- 4. [20 ma-na KI.LAL TÚG]. [UD]. A šá d[UTU] x x x x x (erased) \_\_\_\_\_
- 5. [10 ma-na KI.LAL  $^{\text{túg}}$ ṣib]- $^{\text{r}}$ tu $_4$  šá  $^{\text{d}}$ UTU

	6. [2 m]a-na KI.'LAL TÚG.UD.A' me 'SIG' šá <sup>d</sup> UTU
	7. 「1 <sup>1</sup> <i>ma-na</i> KI.LAL 6 TÚG.NÍG.ÍB.LÁ.MEŠ <i>šá</i> <sup>「d1</sup> UTU
	8. 1 ma-na 1/3 GÍN KI.LAL 4 ľTÚG.ÚR¹.MEŠ šá <sup>d</sup> UTU
	9. 1 ma-na KI.LAL 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>rd</sup> A¹-a
	10. [1+] 1 ma-na KI.LAL TÚG.UD.A ù $^{\text{túg}}$ [šá $^{\text{d}}$ Bu-n]e-ne
	11. [1/3] GÍN KI.LAL <sup>túg</sup> su-ú-n[u]
Edge	12. [1 ma-n]a KI.LAL 10 TÚG.NÍG.ÍB.[LÁ.MEŠ šá <sup>d</sup> GAŠAN Sip-par <sup>ki</sup> ]
Rev.	13. [x <i>ma-na</i> x] GÍN <i>dul-lu it-qu</i>
	14. [mi-iḥ-ṣu te-nu]-rú¹ šá U₄.3.KAM šá ITI.KIN šá a-na <sup>md</sup> UTU- MU-MU <sup>lú</sup> TÚG.BABBAR SUM
	15. [x x x 2 GAD]A <i>sal-ḫu</i>
	16. [2 GADA <i>sal-ḫu</i> 1] GADA <i>ḫu-la-n[u</i> ] 1 GADA <i>gú-ḫal-ṣu</i> 1 TÚG.'MURUB <sub>4</sub> '.ÍB.LÁ 'SÍG.ḤÉ'.ME.DA
	17. $2^{! \text{ túg}} sal^{!}(T: hu) - hi^{\lceil x \rceil} [x x]^{\lceil x \rceil} 2^{\text{ túg}} sib - tu_{4} a - na^{d} U[TU]$
	18. 2 GADA <i>sal-ḫ</i> [ <i>u</i> 4- <i>ta</i> ] TÚG.GÚ.UD.DU.A SÍG.ºḤÉ.ME.DA¹
	19. <sup>r</sup> 1 ku¹-[si-tu <sub>4</sub> x TÚG]. <sup>r</sup> BAR¹.SI a-na <sup>d</sup> A-a
	20. [2 GADA sal-ḫu 6]-rtar TÚG.GÚ.UD.DU.A SÍG.ḤÉ.ME.DA 2-rta kur-si-tu4 šá <d>DUMU.MÍ.<meš> É-babbar-ra</meš></d>
	21. [1 GADA <i>sal-ḫu</i> 1 GADA] <sup>r</sup> ḫu <sup>¬</sup> -la-nu 1 GADA gú-ḫal-ṣu 1 TÚG.MURUB <sub>4</sub> .ÍB.LÁ 1 <sup>túg</sup> ni-bi-ḫu šá <sup>d</sup> rḤAR <sup>¬</sup>
	22. [1 GADA <i>sal-ḫu</i> 5 TÚG.GÚ].「UD.DU¹.A SÍG.ḤÉ.ME.DA 1 TÚG.UD.A <i>a-na</i> <sup>d</sup> GAŠAN UD.KIB.NUN <sup>ki</sup>
	23. [2 GADA <i>sal-ḫu</i> 1 TÚG.G]Ú.UD.DU.A 1 <sup>et</sup> ku-si-tu <sub>4</sub> a-na <sup>d</sup> Gu-la <sup>r</sup> A-nu-ni-tú¹ (erased)

L. e. 24. [1 GADA sal-hu 1 GADA g]ú-hal-şu 1 TÚG.MURUB<sub>4</sub>.ÍB.LÁ

1 TÚG. TUD¹.A a-na dIM

25. [1 GADA sal-hu 1 TÚ]G.GÚ.UD.DU.A 1<sup>et túg</sup>ku-si-tu<sub>4</sub> a-na

dŠa-la

L.h.e. 26. [ITI.KIN U<sub>4</sub>]. T2¹.KAM MU.7.[KAM Kam-bu-zi-ja]

27. [LUGAL] TIN.TIR<sup>ki</sup> LU[GAL KUR.KUR]

L. 15. Probably the content of the beginning of this line was identical with the broken beginning of l. 16. which means that l. 15 is redundant. MURUB<sub>4</sub>.ÍB.LÁ in l. 16 is written

ginning of l. 16, which means that l. 15 is redundant. MURUB<sub>4</sub>.ÍB.LÁ in l. 16 is written over an erasure.

In l. 17 instead of numeral 2 one can recognize the erased  $\delta i$  (did the scribe intended to write the number syllabically?) and instead of the expected sal we see a slightly erased  $\hbar u$ .

The dividing line between lines 18 and 19 is redundant.

šá in. l. 20 and 21 is written with only one vertical stroke.

L. 22. TÚG.UD.A is there, instead of the expected kusītu, probably another scribe's error.

In 1. 23 after Gu-la one can see erased, however, still readable <sup>d</sup>A-nu-ni-tu<sub>4</sub>.

L. 24. TÚG.ÍB.LÁ instead of TÚG.UD.A is expected here.

[White work for the *lub*]*uštu* ceremony for the 3<sup>rd</sup> day of Ulūlu, 7<sup>th</sup> year, which Kalbā, [son of x and DN]-uballit, son of Nabû-kēšir have delivered to the Ebabbar temple [....] was delivered. Month Abu, 30<sup>th</sup> day, 7<sup>th</sup> year of Cambyses, king of Babylon, king of Lan[ds].

\_\_\_\_\_ [20 minas, the weight of the *lubā*]ru-garment for Šamaš \_\_\_\_\_ [10 minas, the weight of the sib]tu-garment for Šamaš -----[2 mi]nas, the weight of the *lubār mēsigu*-headdress for Šamaš -----1 mina, the weight of 6 sashes for Šamaš \_\_\_\_\_ 1 mina 20 shekels, the weight of 4 sūnu-belts for Šamaš \_\_\_\_\_ 1 mina, the weight of 10 sashes for Aya \_\_\_\_\_ <sup>r</sup>2<sup>r</sup> minas, the weight of the *lubāru* and *şibtu*-garments [for Bun]ene \_\_\_\_\_ [20] shekels, the weight of the *sūnu*-belt [....] \_\_\_\_\_ [1 min]a, the weight of 10 sash[es for the Queen of Sippar] \_\_\_\_\_ [x mina x] shekels, the missing work [Woven garments for the chan]ge for the 3<sup>rd</sup> day of Ulūlu, which were given to Šamaš-šum-iddin, the *ašlāku* 

[ 2 line]n cloaks
[2 linen tunics, 1 linen] <i>ḫullānu</i> -cloak, 1 linen scarf, 1 red <i>patinnu</i> -belt
2 <sup>!</sup> linen tunics, [], 2 <i>șibtu</i> -garments for Ša[maš]
2 linen tunics, [4] red <i>naḥlaptu</i> -cloaks, 1 ro[be, x] <i>paršīgu</i> -headdress(es) for Aya
[2 linen tunics, 6] red <i>naḥlaptu</i> -cloaks, 2 robes for the Daughters of the Ebabbar
[1 linen tunic, 1 linen] <i>ḫullānu</i> -cloak, 1 linen scarf, 1 <i>patinnu</i> -belt, 1 <i>nēbeḥu</i> -belt for Bunene
[1 linen tunic, 5] red <i>naḥlaptu</i> -cloaks, 1 <i>lubāru</i> -garment for the Queen of Sippar
[2 linen tunics, 1 naḥ]laptu-cloak, 1 robe for Gula
[1 linen tunic, 1 linen] scarf, 1 patinnu-belt, 1 lubāru-garment for Adad
[1 linen tunic, 1] <i>naḥlaptu-</i> cloak, 1 robe for Šala
[Month Ulūlu], 2 <sup>nd</sup> [day], 7 <sup>th</sup> [year of Cambyses, king] of Babylon, ki[ng of Lands].

# X. The texts of Nabû-bēl-šumāti

<b>293. BM 51099</b> (82-3-232, 2095) 7.4 × 6.1 cm	PLATE 65
12.12. <nbk> 2</nbk>	
Obv. Col. I.  1'. [x x x x] <sup>md</sup> [AG <sup>1</sup> -[]	
2'. [20 ma-na K]I.LAL TÚG.ḤI.A [šá <sup>d</sup> UTU] 3'. [x ma-na] KI.LAL TÚG.MÁŠ 「šá¹ [ <sup>d</sup> UTU] 4'. [x ma-n]a 10 GÍN KI.LAL TÚG.ḤI.A me-「e¹ [SAG. 5'. 「4 TÚG¹.ÚR.MEŠ 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> [UT 6'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ 7'. 3 ½ ma-na 4 GÍN KI.LAL TÚG.ḤI.A TÚG.MÁ[Š] 8'. šá <sup>d</sup> Bu-ne-ne	
9'. 1 <i>ma-na</i> 10 GÍN KI.LAL 1 <sup>en</sup> TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ 10'. <i>šá</i> <sup>d</sup> IM 5 TÚG.NÍG.ÍB.LÁ.MEŠ <i>šá</i> <sup>d</sup> Ša-la	
11'. PAP 38 <i>ma-na</i> 54 GÍN <i>dul-lu gam-ru</i> 12'. <sup>md</sup> AG-EN-MU.MEŠ <sup>lú</sup> UŠ.BAR <i>a-na</i> É DINGIR 13'. <i>it-ta-din</i> ITI.BÁR (erasure) 「MU.2.KAM <sup>1</sup>	
14'. ½ <i>ma-na</i> TÚG.SÍG.ZA.GÌN. <kur>.「RA¹ []</kur>	
Obv. Col. II.  1'. 3 「ma¹ []  2'. 8 ma-na K[I.LAL]  3'. 4 ma-na []  4'. 50 GÍN K[I.LAL]  5'. 2-「ta¹ šá []  6'. ½ [ma-na TÚG.SÍG.ZA.GÌN. <kur>.RAšá TÚG.Ḥ  dUTU]</kur>	I.A šá
Rev. Col. I.  1'. <sup>[8]</sup> [TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup> DUMU.MÍ.MEŠ É-ba 2'. <sup>[8]</sup> [la ḥa-a]-tu <sup>[e]</sup> -[lat <sup>md</sup> AG-EN-MU.MEŠ] 3'. a-na É DINGIR i-n[am-din]	abbar-ra]
4'. 20 ma-na KI.LAL [TÚG.ḤI.A šá <sup>d</sup> UTU]	

- 5'. 「8¹ ma-na KI.LAL TÚ[G.MÁŠ  $š\acute{a}$   $^d$ UTU]
- 6'. 5 ½ ma-na KI.LAL [TÚG.ḤI.A me-e SAG.DU]
- 7'. 4 TÚG.ÚR.MEŠ 4+[2 TÚG.NÍG.ÍB.LÁ.MEŠ  $\check{s}\check{a}^{d}$ UTU]
- 8'. 10 TÚG.N[ÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a]
- 9'. [x+]<sup>[1]</sup> [ma-na x GÍN KI.LAL TÚG.ḤI.A TÚG.MÁŠ]

## Rev. Col. II

- 1'.  $\lceil \frac{1}{2} \rceil^2 ma^{1}$ -na TÚ[G.ZA.GÌN.<KUR>.RA šá TÚG.ḤI.A šá  $^{\mathrm{d}}$ UTU]
- 2'. <sup>r</sup>6¹ GÍN TÚG.ZA.GÌN.<KUR>. <sup>r</sup>RA šá TÚG¹.[ḤI.A šá <sup>d</sup>ḤAR]
- 3'. TA TÚG.HI.A.MEŠ

[na-si-ih]

- 4'. 1<sup>en</sup> TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ [(x x x x)]
- 5'. 1<sup>en</sup> TÚG.BAR.SI BABBAR<sup>ú</sup> šá <sup>d</sup>Bu-ne-ne
- 6'. <sup>[8]</sup> TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>DUMU.MÍ.MEŠ É-<sup>[babbar-ra]</sup>
- 7'. <sup>md</sup>AG-EN-MU.MEŠ *šá la ḫa-a-ṭu*
- 8'. [e<sup>!</sup>]-lat a-na É DINGIR i-nam-din
- 9'. ITI.ŠE U<sub>4</sub>.12.KAM MU.2.KAM

The total sum of 38 minas 54 shekels in Col. I 11' is possible only if we fill the gaps in the beginning of line 3' and 4' with the total sum of 14 minas 10 shekels.

Rev. Col. II 4'. The comparison with BM 51447 (= 294) obv. Col. I 9' suggests that nothing is missing here.

Rev. Col. II 8'. The sign is badly preserved but it ends clearly with one full vertical wedge.

## Obv. Col. I.

[.... Nabû-[bēl-šumāti ....]

-----

[20 minas, the wei]ght of the *lubāru*-garment [for Šamaš] [x minas] the weight of the *şibtu*-garment [for Šamaš]

[x mina]s 10 shekels, the weight of the *lubār mē* [*qaqqadi*]-headdress, 4 *sūnu*-belts, 6 sashes for [Šamaš], 10 sashes for A[ya]

3 minas 34 shekels, the weight of the *lubāru* (and) *şibtu*-garments for Bunene

\_\_\_\_\_

1 mina 10 shekels, the weight of 1  $s\bar{u}nu$ -belt, 5 sashes for Adad (and) 5 sashes for Šala

Total 38 minas 54 shekels, the completed work, which Nabû-bēl-šumāti, the weaver has delivered to the temple. Month of Nisannu, 2<sup>nd</sup> year.

or mas don't orda to the temple. Month of Misamia, 2

 $\frac{1}{2}$  mina of the blue-purple wool [from the  $lub\bar{a}ru$ -garment for Šamaš] . 1 [....]

(Obv. Col. II, not translated)

## Rev. Col. I

8 [sashes for the Daughters of the Ebabbar], [Nabû-bēl-šumāti], whom [no supp]ly (is given) except for these (items), which he de[livers] to the temple (of Šamaš).

```
20 minas, the weight of the lu[b\bar{a}ru-garment for Šamaš]
```

8 minas, the weight of the [sibtu-garment for Šamaš]

5 minas 30 shekels, the weight of the *lubār mē qaqqadi*]-headdress,

4 sūnu-belts, [6] [sashes for Šamaš],

10 sash[es for Aya]

[x]+1 [minas, the weight of the *lubāru* (and) *şibtu*-garments for Bunene ....]

## Rev. Col. II

 $\frac{1}{2}$  mina [of the blue-purple wool from the  $lub\bar{a}ru$ -garment of Šamaš]  $\frac{1}{6}$  shekels of blue-purple wool from the  $lub\bar{a}r[u$ -garment of Bunene] - from (these)  $lub\bar{a}ru$ -garments (wool) was removed

1 sūnu-belt, 5 sashes, 1 white paršīgu-headdress for Bunene

8 sashes for the Daughters of the Ebabbar, Nabû-bēl-šumāti, whom no supply (is given), except for (these items) which he delivers to the temple (of Šamaš). Month of Addaru, 12<sup>th</sup> day, 2<sup>nd</sup> year.

## **294. BM 51447** (82-3-23, 2481)

PLATE 66

 $6.6 \times 6.1$  cm

[x.12]. <Nbk> 3

Obv. Col. I.

- 1'. [x ma]-na 10 GÍN [KI.LAL 1 TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ]
- 2'. [šá <sup>d</sup>] 「IM¹ 5 TÚG. 「NÍG. ÍB¹. [LÁ.MEŠ šá <sup>d</sup>Ša-la]

\_\_\_\_\_

- 3'. [PAP 3]<sup>[8]</sup> ma-na 54 GÍN [dul-lu gam-ru]
- 4'. [mdAG-E]N-MU.MEŠ a-na É DINGIR it-[ta-din]
- 5'. ITI.BÁR MU.3.K[AM]

6'. [½ ma-na TÚ]G.「SÍG¹.ZA.GÌN.<KUR>.RA šá TÚG.ḤI.A šá

7'. [6 GÍN TÚG.SÍ]G.ZA.GÌN.<KUR>. 「RA¹ šá TÚG.ḤI¹.A¹(T: TÚG.MÁŠ) šá <sup>d</sup>Bu-ne-<ne>

8'. [TA TÚG.ḤI].「A¹.<MEŠ>

na-si-ih

- 9'. [1 $^{en}$  TÚG.Ú]R 5 TÚG.NÍG.ÍB.LÁ.MEŠ TÚG.BAR.SI BABBAR $^{\acute{u}}$
- 10'. [šá <sup>d</sup>Bu-n]e-ne 8 TÚG.NÍG.ÍB.LÁ.MEŠ (erasure)
- 11'. [šá <sup>d</sup>DUMU.MÍ.M]EŠ *É-babbar-ra* <sup>md</sup>AG-EN-MU.MEŠ
- 12'. [šá la ḥa-a-ṭ]u e-lat a-na É DINGIR i-nam-din [....]-----[....]
- 13'. [20 ma-na KI.LA]L TÚG.ḤI.A šá <sup>d</sup>UTU
- 14'. [x ma-na KI.LAL] 2 TÚG.MÁŠ šá <sup>d</sup>U[TU]

```
15'. [x ma-na KI.LAL TÚG.ḤI]. [A] me-e SAG.D[U] 16'. [1 ma-na 10 GÍN KI.LAL 7 TÚG.NÍG.ÍB.LA].MEŠ šá ^{\rm d}[UTU] 17'. [10 TÚG.NÍG.ÍB.LÁ.MEŠ] šá [^{\rm d}A-a]
```

Rest lost

Obv. Col. II

1'. 「šá¬ [....]

2.'. PAP [....]

Rev. Col. I completely lost.

Rev. Col. II.

- 1'. [.... <sup>md</sup>AG-EN]-「MU¹.MEŠ <sup>lú</sup>UŠ.BAR
- 2'. [a-na É DINGIR i]t-ta-din ITI.ZÍZ U4.16.KAM MU.3.KAM

\_\_\_\_\_

- 3'. [20 ma-na] KI.LAL TÚG.ḤI.A šá  $^{\rm d}$ UTU
- 4'. [x ma-na] KI.LAL TÚG.MÁŠ šá <sup>d</sup>UTU
- 5'. [x ma-n]a KI.LAL TÚG.HI.A me-e SAG.DU
- 6'. [4 TÚG.Ú]R.MEŠ 6 TÚG.NÍG.ÍB.LÁ.[MEŠ] šá <sup>d</sup>[UTU]
- 7'. [10 TÚG].NÍG.ÍB.LÁ.MEŠ  $\check{s}\check{a}^{\mathrm{d}_{\Gamma}}A^{1}$ -[a]
- 8'. [x m]a-na KI.LAL TÚG. [ $\Pi$ I]. A [x] [x (x)] šá [ $\Pi$ ...]
- 9'. [x m]a-na KI.LAL 1<sup>e[n</sup> TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ]
- 10'. [šá <sup>d</sup>]IM 5 TÚG.NÍG.[ÍB.LÁ.MEŠ šá <sup>d</sup>Ša-la]

11'. [PAP x+<sup>?</sup>] 26 ma-[na dul-lu gam-ru <sup>md</sup>AG-EN-MU].M[EŠ<sup>?</sup>]

12'. [a-na] 'É' [DINGIR it-ta-din ITI.ŠE U<sub>4</sub>.x.KAM MU.3.KAM]

13'. [...] <sup>[</sup>x<sup>]</sup> [....]

14'. [x] [GÍN<sup>?</sup>] [....]

Rev. Col. II 13'-14'. The repetition of Obv. Col. I 6'-7' is expected here.

## Obv. Col. I

[x mi]nas 10 shekels, [the weight of 1 *sūnu*-belt, 5 sashes for] Adad, 5 sash[es for Šala]

Total [3]8 minas 54 shekels, the com[pleted work, Nabû-b]ēl-šumāti has delivered to the temple. Month of Nisannu, 3<sup>rd</sup> year.

[½ mina of the] blue-purple wool from the  $lub\bar{a}ru$ -garment for Šamaš [6 shekels of b]lue-purple wool from the  $lub\bar{a}ru$  of Bune<ne> – from (these)  $lub\bar{a}ru$ -garments (wool) was removed.

------

[1  $s\bar{u}$ ]nu-belt, 5 sashes, <1> white  $par\check{s}\bar{t}gu$ -headdress [for Bun]ene, 8 sashes [for the Daughter]s of the Ebabbar, Nabû-bēl-šumāti, whom [no supp]ly (is given) except for these (items) which he delivers to the temple (of Šamaš).

\_\_\_\_\_

[20 minas, the weigh]t of the *lubāru*-garment for Šamaš [x minas, the weight] of 2 sibtu-garments for Šamaš [x minas, the weight the *lubā*] r mē qaqqadi-headdress [1 mina 10 shekels, the weight of 7 sash]es [for Šamaš] [10 sashes] for [Aya ....]

Obv. Col. II, and rev. Col. I are lost

## Rev. Col. II

[Total x minas x shekels, the completed work, Nabû-bēl]-šumāti, the weaver has delivered [to the temple]. Month Šabatu, 16<sup>th</sup> day, 3<sup>rd</sup> year

[20 minas], the weight of the *lubāru*-garment for Šamaš

[x minas], the weight of the sibtu-garment for Šamaš

[x min]as, the weight of the *lubār mē qaqqadi*-headdress

 $[4 \ s\bar{u}]nu$ -belts, 6 sashes for Šamaš

[10 sas]hes for Aya

[x mi]nas, the weight of the *lubāru* [and *sibtu*-garments for Bunene<sup>?</sup>]

[x mi]nas, the weight of 1 [sūnu-belt, 5 sashes for] Adad, 5 sash[es for Šala]

Total [x]+26 min[as, the completed work, Nabû-bēl-šum]āti [has delivered to] the te[mple (of Šamaš)]. [Month of Addaru, n<sup>th</sup> day, 3<sup>rd</sup> year ....].

## **295. BM 50066** (82-3-23, 1057)

PLATE 67

 $6.2 \times 4.4$  cm

12.12.<Nbk> 3

Col. I

1'. [.... <sup>md</sup>AG-EN]-「MU.MEй

2'. [.... ITI]. [x] U4.12.KAM MU.3.KAM

3'. [½ ma-na TÚG.SÍG.ZA.GÌN.<KUR>.RA] 「šá¹ TÚG.HI.A šá <sup>d</sup>UTU

4'. [5 (or) 6 GÍN TÚG.SÍG.ZA.GÌN.<KUR>.RA] 「šá¹ TÚG.HI.A šá <sup>d</sup>Bu-ne-ne

5'. [TA TÚG].HI.A

na-si-ih

- 6'.  $[1^e]^n$  TÚG. ÚR 5 TÚG. NÍG. ÍB. LÁ. MEŠ  $1^{en}$  TÚG. BAR. SI BABBAR<sup>ú</sup>
- 7'. [šá]  $^{\rm r^d}$ Bu-ne-ne 8 TÚG.NÍG.ÍB.LÁ.MEŠ 8'. [šá  $^{\rm d}$ DUM]U.MÍ.MEŠ <É-babbar-ra>  $^{\rm md}$ AG-EN-MU.MEŠ
- 9'. [šá la h]a-a-ṭu e-lat a-na É DINGIR
- 10'. [*i-nam-di*]*n* ITI.ŠE U<sub>4</sub>.12.KAM MU.3.KAM

\_\_\_\_\_\_

Rest lost

```
Col. II
```

1'.  $\lceil \check{s} \acute{a}^{?} \rceil [....]$ 2'.  $\lceil x^{1} [....]$ 

3'. 20 m[a-na KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU]

4'. 7 m[a-na KI.LAL TÚG.MÁŠ šá <sup>d</sup>UTU]

5'. 5 ½ m[a-na KI.LAL TÚG.ḤI.A me-e SAG.DU]

6'. 4 TÚG.Ú[R.MEŠ 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]

7' 10 TÚG.NÍG.Í[B.LÁ.MEŠ šá <sup>d</sup>A-a]

8'. 10 'TÚG<sup>?</sup>¹ [....]

9'. 2/<sup>[</sup>šá<sup>7</sup> [....]

## Col. II 7'. Or 1<sup>[3]</sup> [....]

.... Nabû-bēl]-šumāti [.... month of Addar]u², 12<sup>th</sup> day, 3<sup>rd</sup> year. [½ mina of blue-purple wool from] the *lubāru*-garment for Šamaš (and) [5 (or 6) shekels of blue-purple wool] from the *lubāru* for Bunene – from (these) *lubāru*-garments (wool) was removed

-----

1 sūnu-belt, 5 sashes, 1 white paršīgu-headdress [for] Bunene,

8 sashes [for the Daug]hters of the <Ebabbar>, Nabû-bēl-šumāti, the weaver [whom no sup]ply (is given), except for (these items) which he [deliver]s to the temple (of Šamaš). Month of Addaru,  $12^{th}$  day,  $3^{rd}$  year

· ·

# Col. II

. . . . . . . . . . . . .

20 mi[nas, the weight of the *lubāru*-garment for Šamaš] 7 mi[nas, the weight of the *ṣibtu*-garment or Šamaš] 5 ½ mi[nas, the weight of the *lubār mē qaqqadi*-headdress] 4 *sū*[*nu*-belts, 6 sashes for Šamaš] 10 sas[hes for Aya .....

## **296. BM 51659** (82-3-23, 2693)

## Col. I

1'. [....] <sup>r</sup>x+2.KAM<sup>1</sup>
2'. [....] <sup>r</sup>x<sup>1</sup>
3'. [....]-babbar-ra
4'. [....] e-lat
6'. [....].13.KAM
5'. [....] <sup>r</sup>x<sup>1</sup> ku
7'. [....] <sup>r</sup>x<sup>1</sup> ku
8'. [....] <sup>r</sup>a<sup>2</sup>1

## Col. II

- 1'. šá pa-ni-e šá TÚG.HI.[A ....]
- 2'. gi-nu-ú u pap-[pa-su ....]

- 3'. 2 ma- $\lceil na \rceil [x] \lceil x \rceil 1^{en} x [....]$
- 4'.  $\hat{u}$  KI.LAL tug ri-rx [....]
- 5'. 1 ma-na 8 GÍN KI.LAL [1 TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ]
- 6'. šá <sup>d</sup>IM 5 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup>Ša-la]
- 7'. <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>UŠ.[BAR *a-na* É DINGIR]
- 8'. *it-ta-din* ITI.<sup>r</sup>DU<sub>6</sub><sup>1</sup> [....]

- 9'. 20 ma-na KI.LAL T[ÚG.ḤI. A šá  $^{\rm d}$ UTU]
- 10'. 8 ma-[na KI.LAL TÚG.MÁŠ šá <sup>d</sup>UTU]

## Rest lost

Most probably this tablet might be joined with BM 50066 although a direct join does not exist. Both are written with similar beautiful signs.

Col. II 3'. There is not enough space to reconstruct [KI.LAL] here.

- [....] *pānu* of the *lubāru*-garment ...
- [....] (for) the regular offering and (for) the prebendary income [....]

2 minas [....], 1 [....]

and the weight of the [....]

1 mina 8 shekels, the weight of [1 sūnu-belt, 5 sashes] for Adad, 5 sashe[s for Šala] Nabû-bēl-šumāti, the wea[ver] has delivered [to the temple(of Šamaš)]. Month of Tašrītu [....]

20 minas, the weight of the  $lu[b\bar{a}ru$ -garment for Šamaš] 8 minas, the weight of [the *şibtu*-garment for Šamaš]

# **297. BM 50745** (82-3-23, 1737)

PLATE 67-68

 $8.5 \times 9.8$  cm

12.12. <Nbk> 4

Obv. Col. I

- 1'. ½ ma-na TÚG.<SÍG>. 「ZA¹.G[ÌN.<KUR>.RA šá TÚG.ḤI.A šá dUTU1
- 2'. 6 GÍN TÚG.SÍG.ZA. GÌN. KUR>.RA šá TÚG.HI.A [šá dHAR]
- 3'. TA TÚG. 'HI.A'. MEŠ

na-si-ih \_\_\_\_\_

4'. 1<sup>en</sup> TÚG.[Ú]R [5] 「TÚG¹.NÍG.ÍB.LÁ.MEŠ TÚG.BAR.SI BABBAR<sup>ú</sup>

5'. šá <sup>d</sup>[Bu]-<sup>r</sup>ne<sup>1</sup>-ne 8 TÚG.NÍG.<ÍB>.LÁ.MEŠ

```
6'. šá <sup>d</sup>[DUMU.MÍ].MEŠ É-babbar-ra <sup>md</sup>AG-EN-MU.MEŠ
            7'. a-na <sup>r</sup>ɹ DINGIR šá la ha-a-tu i-nam-din
                             ITI.BÁR MU.4.KAM
            9'. [20 ma-n]a KI.LAL TÚG.ḤI.A šá <sup>d</sup>UTU
           10'. [x ma-na] KI.LAL 2 < TÚG>.MÁŠ šá <sup>d</sup>UTU
11'. [5 ma-na 10] GÍN KI.LAL 1<sup>et!</sup> (T: TÚG.ḤI.A) TÚG.ḤI.A
                    me-e SAG.DU
           12'. [4 TÚG.ÚR].MEŠ 7 <TÚG>.NÍG.「ÍB¹.LÁ.MEŠ šá dUTU
                                                                      šá <sup>d</sup>A-a
           13'. [10 TÚG.NÍG].ÍB.LÁ.MEŠ
           14'. [x ma-na x] GÍN KI.LAL 「TÚG¹.ḤI.A 「TÚG.MÁй ša dḤAR
                                                                      šá <sup>d</sup>IIM
           15'. [x ma-n]a KI.LAL <1> T[ÚG.ÚR
           16'. [5 TÚG].NÍG.Í[B.LÁ.MEŠ šá dIM 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá
                ¹Šá-la1
Obv. Col. II
            1'. [1/2] [....]
            2'. [2] [....]
            3'. [1/3<sup>?</sup>] [....]
            4'. 「šá¹ [....]
            5'. [x x] [....]
            6'. [x x] [....]
            7'. md AG-EN-[MU.MEŠ ....]
            8'. it-ta-din [....]
            9'. <PAP> 22 ½ ma-na [dul]-[lu gam-ru
           10'. [7] ma-na [KI.LAL] [TÚG.MÁŠ šá dUTU]
           11'. 1 ½ ma-<sup>[</sup>na KI.LAL<sup>]</sup> [....]
Rest lost
Rev. Col. I
            1'. <sup>m</sup>[<sup>d</sup>AG-EN-MU.MEŠ ....]
            2'. a-na [É DINGIR ....]
            3'. 20 ma-na K[I.LAL TÚG.ḤI.A šá <sup>d</sup>UTU]
            4'. 7 ma-na KI.LAL [TÚG.MÁŠ šá <sup>d</sup>UTU]
            5'. 5 <sup>r</sup>ma-na KI.LAL¹ TÚG.ḤI. <sup>r</sup>A¹ [me-e SAG.DU]
            6'. 4 'TÚG'.ÚR.<MEŠ> 6 TÚG.NÍG.ÍB. [LÁ.MEŠ šá <sup>d</sup>UTU]
            7'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ (blank space)
                                                                     [šá <sup>d</sup>A-a]
            8'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ (blank space) [šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>]
            9'. 2 ma-na KI.LAL TÚG.HI.「A¹ [u TÚG.MÁŠ šá <sup>d</sup>HAR]
           10'. 1 ma-na KI.LAL 1<sup>en</sup> TÚG.[ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ]
           11'. šá <sup>d</sup>IM 5 TÚG.<NÍG>.ÍB.[LÁ.MEŠ šá <sup>d</sup>Ša-la]
```

- 12'. PAP 36 ma-na [dul-lu gam-ru <sup>md</sup>AG-EN-MU.MEŠ]
- 13'. lúUŠ.BAR [a]-[na É DINGIR it-ta-din]
- 14'. ITI.DU<sub>6</sub> [U<sub>4</sub>.x.KAM MU.4.KAM]

15'. ½ m[a-na TÚG.SÍG.ZA.GÌN.<KUR>.RA TÚG.ḤI.A šá  $^{
m d}$ UTU]

16'. <sup>r</sup>6¹ [GÍN TÚG.SÍG.ZA.GÌN.<KUR>.RA TÚG.ḤI.A šá dHAR]

## Rev. Col. II.

- 1'. [½ ma-na TÚG.SÍG.ZA.GÌN].<KUR>. 「RA šá¹ [TÚG.ḤI.A ša  $^{\rm d}$ UTU]
- 2'. [6 GÍN TÚG.SÍG.ZA.GÌN.<KUR>]. 「RA¹ TÚG.ḤI.A [šá] d[ḤAR]
- 3'. [TA TÚG].ḤI.A.MEŠ

\_\_\_\_\_

na-s[i-ih]

- 4'. [1 $^{en}$  TÚG.Ú]R 5 TÚG.NÍG.ÍB.LÁ.MEŠ <1> TÚG.BAR.SI BAB[BAR $^{u}$ ]
- 5'. [šá <sup>d</sup>Bu]-ne-[n]e <sup>[8</sup> TÚG<sup>1</sup>.NÍG.ÍB.LÁ.MEŠ
- 6'. [šá <sup>d</sup>DUM]U.MÍ.MEŠ *É-babbar-*<sup>r</sup>ra<sup>1 m</sup><sup>rd</sup>AG¹-EN-MU.MEŠ
- 7'. [lúUŠ.BA]R šá la ha-a-tu [e]-[lat] [a]-na É DINGIR
- 8'. <sup>r</sup>i¹-nam-din ITI.APIN [U<sub>4</sub>.x.KAM M]U.4.KAM

-----

- 9'. [x x] TÚG.SÍG.ZA.GÌN.<KUR>.RA TÚG.ḤI.「A¹ [x x x]  ${}^{r}ku^{?}-lu^{?}$ 1
- 10'. [x túgBA]R.SI.MEŠ šá dGAŠAN Sip-parki
- 11'. [x] <sup>r</sup>ma-na<sup>1</sup> 5 GÍN KI.LAL 1<sup>en</sup> TÚG.ÚR
- 12'. [x] TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>md</sup>AG-EN-MU.MEŠ
- 13'. 「a¹-na É DINGIR 「it-ta¹-din ITI.ZÍZ U₄.16.KAM MU.4.KAM

-----

- 14'. 20 ma-na KI.LAL 「TÚG¹.ḤI.A šá dUTU
- 15'. 7 ma-na KI.LAL TÚG.MÁŠ šá <sup>d</sup>UTU
- 16'. 5 ½ ma-na KI.LAL TÚG.HI.A me-e SAG.DU
- 17'. 4 TÚG.ÚR.MEŠ 6 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU
- 18'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ

šá <sup>d</sup>A-a

- 19'. 2 ½ ma-na KI.LAL TÚG.ḤI.A TÚG.MÁŠ šá  $^{\rm d}Bu\text{-}ne\text{-}<\!ne>$
- 20'. 1 ma-na KI.LAL 1<sup>en</sup> TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ
- 21'. *šá* <sup>d</sup>IM 5 TÚG.NÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>Ša-la

\_\_\_\_\_

- 22'. PAP 36 ma-na dul-lu gam-ru <sup>md</sup>AG-EN-MU.MEŠ
- 23'. 「a¹-na É DINGIR it-ta-din ITI.ŠE U4.12.KAM [MU.4.KAM]

\_\_\_\_\_

# 24'. [½] 「ma¹-na TÚG.SÍG.ZA.「GÌN.<KUR>.RA šá <sup>d</sup>UTU¹ 25'. [6 GÍ]N 「TÚG¹.[SÍG.ZA.「GÌN.<KUR>.RA šá <sup>d</sup>HAR]

In Rev. Col. II 20'-21' and Col. I 10'-11' a quantity of 1 ma-na 10 GÍN is expected, i.e. 20 shekels (the weight of 1  $s\bar{u}nu$ ) + 50 shekels (the weight of 10 husannus for Adad and Šala), but in both there is only 1 ma-na.

Obv. Col. I

½ mina of blue-purp[le wool from the *lubāru*-garment of Šamaš],

6 shekels of blue-purple wool from the *lubāru* [of Bunene] – from (these) *lubāru*-garments (wool) was removed.

\_\_\_\_\_

1 [sū]nu-belt, [5] sashes, <1> white paršīgu-headdress for [Bu]nene,

8 sashes [for the Daug]hters of the Ebabbar, will be delivered byNabû-bēl-šumāti to the temple without (earlier) supply. Month of Nisannu, 4<sup>th</sup> year.

[20 min]as, the weight of the *lubāru*-garment for Šamaš

[x minas], the weight of 2 sibtu-garments for Šamaš

[5 minas 10] shekels, the weight of 1 lubār mē qaqqadi-headdress;

[4 sūnu]-belts 7 sashes for Šamaš

[10 sa]shes for Aya

[x minas x] shekels, the weight of the *lubāru* and *ṣibtu*-garments for Bunene

[x min]as, the weight of <1> [ $s\bar{u}nu$ -belt for] Adad, [5 sa]she[s for Adad, 5 sashes for Šala]

Obv. Col. II

[....] Nabû-bēl-šumāti [....] has delivered [....].

.....

<Total> 22 ½ mina, the [completed wo]rk

7 minas, the weight of [the *sibtu*-garment for Šamaš]

1 ½ mina, the weight [....]

Rev. Col. I

.... [Nabû-bēl-šumāti] .... for [the temple ....]

-----

20 minas, the we[ight of the *lubāru*-garment for Šamaš]

7 minas, the weight of [the *şibtu*-garment for Šamaš]

5 minas, the weight of 1 *lubār* [*mē qaqqadi*-headdress]

4 *sūnu*-belts, 6 sash[es for Šamaš]

10 sashes [for Aya]

10 sashes [for the Queen of Sippar]

2 minas, the weight of the *lubāru* [and *sibtu*-garments for Bunene]

1 mina, the weight of 1 [sūnu-belt, 5 sashes] for Adad, 5 sashe[s for Šala]

Total 36 minas, [the completed work, Nabû-bēl-šumāti], the weaver [has delivered to the temple (of Šamaš)]. Month of Tašrītu, [ $x^{th}$  day,  $4^{th}$  year]

\_\_\_\_\_

½ mi[na of blue-purple wool from the *lubāru*-garment for Šamaš] 6 [shekels of blue-purple wool from the *lubāru* for Bunene] . . . . . . . . . . . . Rev. Col. II [½ mina of blue-purp]le wool from the *lubā*[ru-garment for Šamaš] [6 shekels of blue-purp]le wool from the *lubāru*-garment [for Bunene – from (these) *lu*]*bāru*-garments (wool) was rem[oved] [1  $s\bar{u}n$ ]u-belt, 5 sashes, <1> white  $par \tilde{s} \bar{t} g u$ -headdress [for Bu]nene, 8 sashes [for the Daug]hters of the Ebabbar, Nabû-bēl-šumāti, [the weav]er, whom no supply (is given), ex[cept for] (these items), which he delivers to the temple (of Šamaš). Month of Arahsamna, [n<sup>th</sup> day], 4<sup>th</sup> [year]. [x shekels of the] blue-purple wool (for?) the *lubār* [kulūlu]-headband?, [x par]šīgu-headdresses for the Queen of Sippar [x] mina 5 shekels, the weight of 1 sūnu-belt (and) [x] sashes, which Nabû-bēl-šumāti has delivered to the temple. Month of Šabatu, 16<sup>th</sup> day, 4<sup>th</sup> year. 20 minas, the weight of the *lubāru*-garment for Šamaš 7 minas, the weight of the *şibtu*-garment for Šamaš 5 minas 30 shekels, the weight of the *lubār mē qaqqadi*-headdress 4 sūnu-belts, 6 sashes for Šamaš 10 sashes for Ava 2 minas 30 shekels, the weight of the *lubāru* (and) *sibtu*-garments for Bunene 1 mina, the weight of 1 sūnu-belt, 5 sashes for Adad, 5 sashes for Šala Total 36 minas, the completed work, Nabû-bēl-šumāti has delivered to the temple. Month of Addaru, 12<sup>th</sup> day, 4<sup>th</sup> [year] [½] mina of blue-pur]le wool from the lubāru-garment for Šamaš] (and) [6 sheke] Is of the bl[ue-purple wool from the *lubāru*-garment for Bunene]. 298. BM 52475 (82-3-23, 3509) PLATE 69  $5.8 \times 3.4$  cm 8.[x]. Nbk 13 Obv? 1'. [.... T]ÚG.[Ḥ]I.[A ....] 2'. [.... TÚ]G.ḤI.A TÚG.[....] 4'. [.... TÚ]G<sup>?</sup>. 「BAR.SI<sup>?</sup> x x TÚG.MÁŠ 1<sup>en</sup> TÚG.Ú[R<sup>?</sup>

5'. [5 TÚG.NÍG.ÍB.LA.M]EŠ šá <sup>d</sup>I[M] 6'. [5 TÚG.NÍG.ÍB.LA.M]EŠ šá <sup>d</sup>ſŠa-la<sup>1</sup>

ne

7'. [PAP x ma-na dul-lu gam-ru <sup>md</sup>AG-EN]-MU.MEŠ ma-hir 8'. [ITI.x. U<sub>4</sub>].8.<KAM> MU.13.<KAM> 9'. [1<sup>en</sup> TÚG.ÚR BABBAR<sup>ú</sup> 1 TÚG.BAR.SI] 5 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>Bu-ne-ne 10'. [8 TÚG.NÍG.ÍB.LÁ.ME]Š šá <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-ra 11'. [<sup>md</sup>AG-EN-MU.MEŠ e-la]t šá la ḥa-a-ṭu i-nam-din 12'. [ITI.x. U<sub>4</sub>.x.KAM] MU.13.KAM <sup>d</sup>AG-NÍG.DU-ÙRU 13'. [a-na É DINGIR i-n]am-din

Rest lost

L. 11'. The remnants of sign preceding šá la ha-a-tu is certainly not BAR, but rather lat.

[....],  $lub[\bar{a}r]u$ -garment, [....  $lu]b\bar{a}ru$ -garment [....]

[...., par] $\tilde{s}igu$ -headdress,[....], the  $\tilde{s}ibtu$ -garment, 1  $\tilde{s}u$ [nu-belt, 5 sashe]s for Ad[ad, 5 sashes for] Šala

-----

[Total x minas, the completed work which] was received from [Nabû-bēl]-šumāti. Month of x],  $8^{th}$  day],  $13^{th}$  year of Nebuchadnezzar.

[1 sūn]u-belt, 1 white paršigu-headdress], 5 sashes for Bu]nene,

[8 sashe]s for the Daughters of the Ebabbar, [Nabû-bēl-šumāti], whom no supply (is given), [except f]or (these items) which delivers to the temple (of Šamaš). [Month of x, n<sup>th</sup> day], 13<sup>th</sup> year of Nebuchadnezzar [he (Nabû-bēl-šumāti) delive]rs [to the temple].

## 299. BM 50179 (82-3-23, 1170)

 $6.3 \times 4.3$  cm

## 12.[x].Nbk 14

Obv. 1'. [.... <sup>md</sup>] [AG¹-EN-MU.MEŠ 2'. [.... É] DINGIR *it-ta-din* 

3'. [ITI]. [APIN] U<sub>4</sub>.12.KAM MU.14.KAM dAG-NÍG.DU-[ÙRU]

4'. LUGAL E<sup>ki</sup>

\_\_\_\_\_

5'. [1] $^{en}$  「TÚG¹.ÚR 1 $^{en}$  túgpar-si-gu 5 TÚG.「NÍG.ÍB¹.LÁ.MEŠ

6'.  $[a-n]a^{d}Bu-ne-ne$ 

7'. [8 TÚG.NÍG.ÍB]. LÁ¹.MEŠ šá <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-ra

8'. [mdAG-EN-M]U.MEŠ šá la ha-a-ţu [e-lat a-na É DINGIR]

9'. [*i-na*]*m-din* 

.-----

10'. [½ ma-n]a SÍG.ZA.GÌN.<KUR>.RA šá TÚG.ḤI.A šá [dUTU]

11'. [6 GÍ]N SÍG.ZA.GÌN.<KUR>.RA šá TÚG.ḤI.A [šá <sup>d</sup>Bu-ne-

12'. [TA TÚG.ḤI].「A¹.MEŠ na-s[i-iḥ]

Rev. 13'. [20 ma-na KI.LAL TÚG].ḤI.A šá <sup>rd</sup>¹[UTU]
14'. [x ma-na KI.LAL] TÚG.MÁŠ šá <sup>d</sup>[UTU]
15'. [x ma-na x GÍN KI.LAL TÚG.ḤI.A me]-<sup>r</sup>e¹ SAG.D[U]
16'. [4 TÚG.ÚR. MEŠ 6 TÚG.<NÍG>.ÍB].LÁ.MEŠ
17'. [....].MEŠ šá <sup>d</sup>[UTU ....]
18'. [1 ma-na KI.LAL 10 TÚ]G.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>A-a
19'. [1 ma-na KI.LAL] 10 TÚG.<NÍG>.ÍB.LÁ.MEŠ šá <sup>d</sup>GAŠAN
Sip-par<sup>ki</sup>
20'. [.... TÚG]. <sup>r</sup>ÚR.MEŠ šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>¹
21'. [....] <sup>r</sup>x x x x¹ šá <sup>d</sup>[DN]
22'. [.... KI].LAL TÚG.ḤI.A <sup>túg</sup>par-[....]

- L. 8. The expected *e-lat* is missing here.
- Ll. 20–21 are almost completely eroded.

[....] Nabû-bēl-šumāti [....] has delivered to the temple. [Month] Araḥsamna,  $12^{th}$  day,  $14^{th}$  year of Nebuchadne[zzar], king of Babylon

.....

[1] sūnu-belt, 1 paršigu-headdress, 5 sashes [fo]r Bunene,

[8 sash]es for the Daughters of the Ebabbar, [Nabû-bēl-šu]māti whom no supply (is given except for these items), which he deliver[s to the temple] (of Šamaš).

\_\_\_\_\_

[½ min]a of blue-purple wool from the *lubāru*-garment for [Šamaš] [6 shek]els of blue-purple wool from the *lubāru*-garment [for Bunene – from (these) *lu*]*bāru*-garments (wool) was rem[oved]

[20 minas, the weight of the *lubā]ru*-garment for [Šamaš] [x minas, the weight of the] *sibtu*-garment for [Šamaš] [x minas x shekels, the weight of the *lubār m]ē qaqqadi*-headdress] [4 *sūnu*-belts, 6 sash]es, [......]s for Šamaš] [1 mina, the weight of 10 sashe]s for Aya [1 minas the weight 10 sashes for the Queen of Sippar [.... the weight of x] *sūnu*-belts for the Queen of Sippar [....] for [....]

## **300. BM 50938** (82-3-23, 1933)

PLATE 69

A fragment of irregular shape, ca.  $3.4 \times 4.3$  similar to the three above published texts, however, it does not belong to any of them.

## 26.8.[Nbk x]

- 1'. [.... B]u- $\lceil ne \rceil$ - $\lceil ne \rceil$
- 2'. [8 TÚG.NÍG.ÍB.LÁ.MEŠ] šá <sup>d</sup>DUMU.MÍ.MEŠ [É-babbar-ra]
- 3'. [mdAG-EN-M]U.MEŠ šá la ha-a-t[u e-lat]
- 4'. [a-na É] DINGIR i-nam-din ITI.APIN U[D.x.KAM MU.x.KAM]

5'. [x] ma!(T: ku)-na SÍG.ZA.GÌN.<KUR>.RA KI.LAL TÚG.HI.「A¹ [....] 6'. [x TÚG.BAR].SI.MEŠ šá <sup>d</sup>GAŠAN Sip-[par<sup>ki</sup>] 7'. [x x x] <sup>[5]</sup> GÍN KI.LAL 1<sup>en</sup> TÚG.Ú[R (erasure) 8'. [x TÚG.NÍG.Í]B.LÁ.MEŠ <sup>md</sup>AG-EN-MU.MEŠ 9'. [lúUŠ.BA]R *a-na* É DINGIR *it-ta-[din*] 10'. [ITI.x] U<sub>4</sub>.26.KAM [MU.x.KAM] 11'. [.... K]I.LAL TÚG.H[I.A ....] 12'. [.... LA]L<sup>?</sup> [....] (for) Bunene [....] [8 sashe]s for the Daughters of the [Ebabbar], [Nabû-bēl-šu]māti whom no supply (is given), excep[t for (these items), which he delivers to the temple. Month Arahsamna, [n<sup>th</sup> day, n<sup>th</sup> year] [x min]a of the blue-purple wool, the weight of the lubār [...., x par]šīguheaddresses for the Queen of Sippar [x minas] 5 shekels, the weight of 1  $s\bar{u}[nu\text{-belt}$  (and) x sash]es, which Nabû-bēlšumāti, [the weav]er has delivered to the temple. Month [of x], 26<sup>th</sup> day, [x ye]ar [....], the weight of the *lubāru*-garment [....]. **301. CT 55, 844** = BM 56702 Collated  $5.5 \times 4.3$  cm 6.1.Nbk 19 1.  $[x]^{1/2}$  ma- $[na\ dul^{*}]$ -la [gam]-ru 2. [KI.LA]L [(x x x x)] TÚG.HI.A me-e SAG.DU 3. [4 TÚG.ÚR.M]EŠ 7\* TÚG.NÍG.ÍB.LÁ.MEŠ 4. [šá  $^{
m d}$ UTU 1 ma-na KI.LAL 10 TÚG]. NÍG.ÍB.LÁ.MEŠ šá  $^{
m d}$ A-a 5. [2 ma-na KI. LAL TÚG.ḤI.A ù TÚG.MÁŠ] šá <sup>d</sup>Bu-ne-ne 6. [1 ma-na 10 GÍN KI.LAL TÚG.ÚR 10] TÚG.NÍG.ÍB.LÁ.MEŠ 7.  $[\check{s}\acute{a}^{d}I]M[u^{d}\check{S}]a-[l]a$ 8. [mdAG-EN-M]U.MEŠ lúUŠ.BAR a-na 9. [É DINGIR *it-ta-din*] TÚG.ḤI.「A¹ TÚG.MÁŠ *šá* <sup>d</sup>UTU 10. [a-na É] DINGIR [x] (erased?) id-din 11. [ITI.BÁ]R U<sub>4</sub>.6.「KAM MU¹.19.KAM 12. [mdA]G-NÍG.DU-ÙRU LUGAL [Eki] Edge -----

13. 1<sup>en</sup> TÚG.ÚR 5 TÚG.NÍG.ÍB.LÁ.MEŠ

Rev.

- 14. šá <sup>d</sup>Bu-ne-ne
- 15. 8 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra*
- 16. šá la ha-a-ţu i-nam-din
- L. 2. I have no idea how to fill the damaged part of this line. In similar texts TÚG.HI.A me-e SAG.DU is preceded by TÚG.HI.A u (TÚG).MÁŠ, but it seems that the scribe forgot to write these words and added them later in 1. 9.
- L.13. Note that in similar texts 1 *paršīgu* is also counted.
- [x]+  $\frac{1}{2}$  mina, [the comple]ted work, [the weig]ht of [....], the *lubār mē qaqqadi*-headdress,[4 *sūnu*-belts], 7 sashes [for Šamaš]
- [1 mina, the weight of 10] sashes for Aya
- [2 minas, the weight of the *lubāru* (and) *şibtu*-garments] for Bunene
- [1 mina 10 shekels, the weight of the *sūnu*-belt (and) 10] sashes [for Ad]ad [and] 「Šala¹, [Nabû-bēl-šu]māti, the weaver [has delivered] to [the temple]. The *lubāru* (and) *sibtu*-garments for Šamaš he has delivered [to the te]mple.

[Month of Nisan]nu, 6<sup>th</sup> day, 19<sup>th</sup> year of Nabuchadnezzar, king of Babylon.

1 sūnu-belt, 5 sashes for Bunene, 8 sashes for the Daughters of the Ebabbar for

which no supply (is given except for these items which) he (Nabû-bēl-šumāti) delivers <to the temple of Šamaš>.

## **302. BM 53364** (82-3-23, 4399)

 $3.1 \times 4.2 \text{ cm}$ 

16.3.[Nbk x]

- 1'. [.... <sup>md</sup>AG-E]N-M[U.MEŠ ....] 2'. [.... x x]-<sup>r</sup>din<sup>1</sup> ITI.GU<sub>4</sub> [....]
- 2 · [.... x x] · unt · 111.004 [....]
- 3'. [8 TÚG.NÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>DUMU.M]Í.MEŠ É-babbar[-ra]
- 4'. <sup>md</sup>AG-E]N-MU.MEŠ *šá la ḥa-a-ṭu* [*a-na* É DINGIR *i-nam-din*]
- 5'. [x m]a-na KI.LAL TÚG.HI.A me-e SA[G.DU]
- 6'. [x ma-na x GÍN KI.LAL 1 TÚ]G.ÚR 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá  $^{d}$ [DN ....]
- 7'. <sup>md</sup>A]G-EN-MU.MEŠ <sup>lú</sup>UŠ.BAR *a-n*[*a* É DINGIR]
- 8'. [e-lat it]-ta-din ITI.SIG $_4$  U $_4$ .16.K[AM MU.x.KAM]

-----

- 9'. [20] *ma-na* KI.LAL TÚG.ḤI.A *šá* <sup>d</sup>[UTU]
- 10'. [x ma]-na KI.LAL TÚG.MÁŠ šá <sup>d</sup>[UTU]
- 11'. [x ma-na] KI.LAL TÚG.HI.A me-<sup>r</sup>e<sup>1</sup> [SAG.DU]
- 12'. [x *ma-na* KI.LAL TÚG]. 「ÚR<sup>?</sup> [....]

The script and content is similar to that of BM 50938 (= 300) and most probably both fragments belong to the same tablet, although a direct join does not exist.

L. 6'. The comparison with other texts suggest to fill the gap at the end of the line with [IM u <sup>d</sup>Ša-la].

L. 12'. Only a tiny fragment of the sign is preserved and the identification is uncertain.

```
[.... Nabû-bē]l-šu[māti ....], month of Ayaru [....]
```

[8 sashes for the Daught]ers of the Ebabb[ar Nabû-bē]l-šumāti, whom no supply (is given) except for (these items) which] delivers [to the temple (of Šamaš)]

[x mi]nas, the weight of the *lubār mē qaq[qadi*]-headdress

[x minas x shekels, the weight of 1] sūnu-belt, 10 sashes for [..., Na]bû-bēl-šumāti, the weaver [has de]livered to [the temple]. Month of Simanu, 16<sup>th</sup> day, [n<sup>th</sup> year]

[20] minas, the weight of the *lubāru*-garment for [Šamaš] [x mi]nas, the weight of the *şibtu*-garment for [Šamaš]

[x minas], the weight of the *lubār mē* [qaqqadi]-headdress

[x mana, the weight of the] sūnu?-belt.

## 303. BM 51563 (82-3-23, 2597)

PLATE 69

 $4.3 \times 2.9 \text{ cm}$ 

Col. I.

1'. [.... <sup>d</sup>Bu-n]e-ne

2'. [.... TÚG].ÚR

3'. [....] <sup>[</sup>x<sup>]</sup>

Col. II.

1'.  $2^{\lceil 2 \rceil} m[a-n]a$  [....]

2'. 8 ma-na KI.LAL [TÚG.MÁŠ šá <sup>d</sup>UTU]

3'. 5 ma-na KI.LAL TÚG.HI.A [me-e SAG.DU]

4'. 4 TÚG.ÚR.<MEŠ> 6 TÚG.NÍG.ÍB.LÁ.[MEŠ šá <sup>d</sup>UTU]

 $[\check{s}\acute{a}^{d}A-a]$ 5'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ

[šá dGAŠAN Sip-parki] 6'. 「10<sup>1</sup> TÚG.NÍG.ÍB.LÁ.MEŠ

7'. [x m]a-na KI.LAL TÚG.ḤI.A ku-[lu-lu]

8'. [PAP x] ½ ma-na dul-lu gam-[ru]

9'. [šá <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>U]Š.BAR a-na [É DINGIR it-ta-din]

Lines 2-6 of Col. II, cf. BM 50745 rev. II 5'-9'; ll. 6'-7', cf. ll. 12'-13' there.

```
[.... for Bun]ene, [....] sūnu-belt, [....]
```

Col. II

2<sup>r</sup>2<sup>r</sup> m[inas, ....]

8 minas, the weight [of the *ṣibtu*-garment for Šamaš]

5 minas, the weight of [the *lubār mē qaqqadi*-headdress]

4 sūnu-belts, 6 sashes [for Šamaš]

10 sashes [for Aya]

[10] sashes[for the Queen of Sippar]

[x] mina, the weight of the  $lub\bar{a}r \ kul\bar{u}[lu]$ -headband, [total x]+ ½ mina, the completed wor[k, which Nabû-bēl-šumāti, the we]av[er has delivered] to [the temple].

## **304. BM 84509** (82-1-21, 1672)

 $4.7 \times 3.2$  cm

## 10.<sup>6</sup><sup>1</sup>.[Nbk x]

- 1. ½ ma-na TÚG.ZA.GÌN.[KUR.RA TA TÚG.ḤI.A šá <sup>d</sup>UTU]
- 2. 6 GÍN TÚG.SÍG.ZA.GÌN.KUR.RA [TA TÚG.HI.A šá <sup>d</sup>Bu-ne-ne]
- 3. *ul-tu* TÚG.ḤI.A.ME[Š<sup>?</sup>

- 4. 1<sup>en</sup> TÚG.ÚR 1<sup>en</sup> TÚG.BAR.SI <sup>[5]</sup> [TÚG.NÍG.ÍB.LÁ.MEŠ]
- 5. šá <sup>d</sup>Bu-ne-ne
- 6. [8] 'TÚG.NÍG.ÍB¹.[LÁ.MEŠ šá <sup>d</sup>DUMU.MÍ.MEŠ É-babbar-ra]

Rest lost

Rev.

- 1'. [21<sup>?</sup>] [....]
- 2'. md]AG-EN-MU.[MEŠ ....]
- 3'. [ITI. KI]N U<sub>4</sub>.10.KAM [MU.x.KAM]
- 4'. dAG-NÍG.DU-ÙRU [LUGAL *Bābili*]

½ mina of blue-purp[le wool from the *lubāru*-garment of Šamaš] 6 shekels of blue-purple wool [from the *lubāru* of Bunene] – from (these) *lubāru*garments (wool) [was removed]

1 sūnu-belt, 1 paršīgu-headdress, 5 [sashes] for Bunene,

[8] sash[es for the Daughters of the Ebabbar]

[....] 21<sup>?</sup> [....]

Nabû-bēl-šumā[ti, ....]

[Month of Ul]ūlu, 10<sup>th</sup> day [n<sup>th</sup> year of] Nebuchadnezzar, [king of Babylon].

## **305. BM 61920** (82-9-18, 1889)

 $5.6 \times 4.2 \text{ cm}$ 

- 1. [20 m]a-na 「KI.LAL¹ TÚG.「HI¹.[A šá <sup>d</sup>UTU]
- 2. <sup>[8]</sup> ma-na KI.LAL TÚG.M[ÁŠ šá <sup>d</sup>UTU]
- 3. 5<sup>!</sup> 2/3 ma-na KI.LAL T[ÚG].ÚR.M[EŠ TÚG.HI.A me SAG.DU]
- 4. TÚG.NÍG.ÍB.LÁ.MEŠ šá [d]UTU u [dA-a]
- 5. <sup>[2]</sup> ma-na 5 GÍN KI.LAL TÚG. <sup>[HI]</sup>. [A TÚG. MÁŠ]

- L. 2. Only two vertical wedges from the bottom row are preserved, but I reconstruct the numeral as 8 because only with such a reconstruction the total in l. 9 is accurate.
- L. 3. The numeral in 1. 3 is clearly 4 2/3 mana, which I emend to 5 2/3 mana because 4 sūnus (1 mina 20 shekels), 1 lubār me qaqaadi (possible 2 minas 10 shekels), 7 huṣannus for Šamaš (1 mina 10 shekels) and 10 sashes Aya (1 mina) gives the total 5 minas 40 shekels.
- L. 7. The weight of one *sūnu* and 10 *ḫuṣannus* for Adad and Šala is in fact 1 mina 10 shekels, however, although the first numeral is slightly damaged, the reading 1 *ma-na* 10 GÍN is impossible. The total 36 minas 45 shekels is accurate only if we accept 5 minas 40 shekels in 1. 3 and only 1 mina in 1. 7.

[20 mi]nas, the weight of the *lubāru*-garment [for Šamaš]

8 minas, the weight of the *şib*[tu-garment for Šamaš]

5 minas 40 shekels, the weight of the *sūnu*-belts, the [*lubār mē qaqqadi*-headdress] (and) sashes for Šamaš and [Aya]

2 minas 5 shekels, the weight of the *lubār*[u (and) *ṣibtu*-garments] for Bunene

1 mina, the weight of the *sūnu*-belt, 10 sa[shes] for Adad <and Šala>,

total 36 minas 4[5 shekels, the completed work, which] Nabû-bēl-šum[āti has delive]red [to the temple].

. . . . . . . . . . . . .

## **306. CT 55, 837** = BM 55899 Collated

[x].12.Nbk 22

- 1. [20] ma-na KI.LAL [TÚG.HI].A 7 ma-[na] <KI.LAL>
- 2. [T]ÚG.MÁŠ 1  $ma*-n[a \times GÍ]N < KI.LAL > TÚG.HI.A SA[G.DU]$
- 3. 1 ma-na 1/3 GÍN [KI.LAL] 4 TÚG.ÚR.MEŠ
- 4. <sup>2</sup>/<sub>3</sub> ma-na 5 GÍN [KI.LAL] 6 TÚG.NÍG.ÍB.LÁ.[MEŠ]
- 5. šá <sup>d</sup>UTU 50 GÍN [KI.LAL] 10 TÚG.<NÍG>.Í[B.LÁ.MEŠ]
- 6. šá <sup>d</sup>A-a 2 ma-n[a KI.LAL TÚ]G.[HI.A TÚG.MÁŠ]
- 7.  $[\check{s}\check{a}]^{\mathsf{r}^{\mathsf{d}}}Bu$ -ne-ne  $[\mathsf{x}\ ma$ -na  $\mathsf{KI}.\mathsf{LAL}]$
- 8. [10 TÚG.NÍ]G.ÍB.LÁ.MEŠ šá [dGAŠAN Sip-parki]
- 9. [1 *ma-n*]*a* 10 GÍN K[I.LAL] 1<sup>e</sup>[<sup>n</sup> TÚG.ÚR 10 TÚG.NÍG.ÍB.LÁ.MEŠ]

Edge 10. [ $\check{s}\check{a}^{d}$ IM  $u^{d}\check{S}$ ]a-l[a]

11. [PAP]  $\lceil x \rceil$   $ma^!$ - $\lceil n \rceil a \ d\lceil ul^?$ - $lu \ gam$ - $ru \rceil$ 

Rev. 12. [*šá*] <sup>md</sup>AG-EN-「MU¹.MEŠ 「x¹ [....]

13. [x x]- $lap^2$ - $tu_4$  ITI.ŠE $^1$  MU.22.KAM  $^d$ A[G-N $\acute{I}$ G.DU- $\acute{U}$ RU]

14. LUGAL TIN.TIR<sup>ki</sup> 1/3 4 GÍN <sup>r</sup>áš me<sup>?</sup> x<sup>1</sup> ru a [....]

15. [1<sup>en</sup>] TÚG.ÚR 1 TÚG.BA[R.S]I 5 TÚG.NÍG.ÍB.[LÁ.MEŠ]

16. [ $\check{s}\check{a}$ ]  $^{\mathsf{rd}_1}Bu\text{-}ne\text{-}ne$   $^{\mathsf{r}}8*$  TÚG.NÍG.ÍB¹.LÁ.MEŠ

17. [šá <sup>d</sup>]DUMU.MÍ.MEŠ É-babbar-ra e-lat [....]

18. [a-na É DINGIR] i-nam-din

Ll. 4-5. Note the atypical weight of sashes for Šamaš and Aya

L. 13. The sign copied by Pinches like *lap*, looks in fact like *mal*, what also make no sense.

## [20] minas, the weight of the [lubāru-garment]

7 min[as], <the weight> of the *sibtu*-garment

1 min[a x shek]els, <the weight> of the lubār mē qaq[qadi]-headdress

1 mina 20 shekels, [the weight] of 4 sūnu-belts

45 shekels, [the weight] 6 sashes for Šamaš

50 shekels [the weight] 10 sash[es] for Aya

2 mina[s, the weight of the  $lu]b\bar{a}r[u$  (and)  $\dot{s}ibtu$ -garments for] Bunene

[x mina, the weight of 10 sa]shes for [the Queen of Sippar]

[1 min]a 10 shekels, the we[ight of] [1] [sūnu-belt, 10 sashes for Adad and] [Šala],

[total] [x minas], the co[mpleted work], which Nabū-bēl-šumāti [...

Month of Addaru, 22<sup>nd</sup> year of Ne[buchadnezzar], king of Babylon.

24 shekels ....

1 *sūnu*-belt, 1 *paršīgu*-headdress, 5 sashe[s [or] Bunene, 8 sashes [for] the Daughters of the Ebabbar except for [....] delivers [to the temple].

## **307. BM 67542** (82-9-18, 7540)

 $4.1 \times 3.0 \text{ cm}$ 

1'. [x] TÚG.N[ÍG.ÍB.LÁ.MEŠ *šá* <sup>d</sup>UTU]

2'. 10 TÚG.NÍG.Í[B.LÁ.MEŠ šá <sup>d</sup>A-a]

3'. 2 ma-na KI.LAL TÚG. HI.A [me SAG.DU]

4'. 1 ma-na KI.LAL 5 TÚG.NÍ[G.ÍB.LÁ.MEŠ]

5'. 1<sup>en</sup> TÚG.ÚR šá <sup>d</sup>I[M u]

6'. 5 TÚG.NÍG.ÍB.LÁ.MEŠ [šá <sup>d</sup>Ša-la]

Rev.

7'. PAP ½ GÚ.UN 4 ma-[na dul-lu gam-ru]

8'. <sup>md</sup>AG-EN-MU.MEŠ a<sup>?</sup>-[na É DINGIR]

9'. it-ta-din ½ <ma-na> SÍG.ZA.[GÌN.KUR.RA]

10'. TA TÚG.HI.A šá <sup>d</sup>[UTU 6 GÍN SÍG.ZA.GÌN.KUR.RA]

11'. TA TÚG.HI.A šá <sup>d</sup>[Bu-ne-ne TA TÚG.HI.A.MEŠ na-si-ih]

## Rest lost

The content of 4'-6' is the same as in BM 50745 (= 297) rev. I 10'-11' and I 20'-21'; BM 51447 (= 294) rev. II 9'-10'; BM 61920 (= 305): 7-8. In all these texts the total weight of  $1 \ s\bar{u}nu$ ,  $5 \ husannus$  for Adad and  $5 \ husannus$  for Šala is  $1 \ mina$ , whereas in almost all other cases  $1 \ mina$   $10 \ shekels$ . The exception is BM 51659 (= 296) II 5-6 (1 mina 8 shekels).

Because BM 50745 and BM 51447 were written at the very beginning of Nebuchadnezzar's reign, the same dating should be suggested for this text, too.

L. 8'. The sign recognized as a has the shape of two full vertical wedges, and differs from a in other lines in the text. The reading a'-[na É DINGIR] is based on many parallels.

# [x] h[uṣannu-sashes for Šamaš]

10 sash[es for Aya]

2 minas, the weight of the *lubār* [*mē qaqqadi*-headdress]

1 mina, the weight of 5 sa[shes], 1 sūnu-belt for Ad[ad and] 5 sashes [for Šala], total 34 min[as, the completed work] Nabû-bēl-šumāti has delivered t[o the temple]. ½ <mina> of blue-pur[ple wool] from the lubāru-garment [of Šamaš], [6 shekels of blue-purple wool] from the *lubāru*-garment [of Bunene] – from (these) *lubāru*-garments] (wool) was removed .......

## **308. BM 50626** (82-3-23, 1617)

 $5.3 \times 3.7 \text{ cm}$ 

## [x.x].Nbk[x]

Obv. 1. [x] *ma-na* [KI.LAL TÚG.HI.A] 2. [2 TÚG].MÁŠ.MEŠ '71 [TÚG.NÍG]. 'ÍB.LÁ1.MEŠ 3. [1] TÚG.HI.A me-e SAG.DU 4. [4] TÚG. ÚR. MEŠ šá <sup>d</sup>UTU 10 TÚG. NÍG. 「ÍB¹. [LÁ. MEŠ] 5. *šá* <sup>d</sup>*A-a* 6. 2 ma-na 10 GÍN KI.LAL TÚG.HI.A TÚG. TÚR (sic !) 7. šá <sup>d</sup>Bu-ne-ne

- 8. 19 ma-na 50 GÍN KI.LAL TÚG.[HI.A]
- 9. TÚG. MÁŠ 1<sup>en</sup> TÚG.ÚR 1<sup>en</sup> TÚG.[BAR.SI]
- 10. [10 TÚG.NÍG].ÍB.LÁ.MEŠ šá  ${}^{d}$ I[M] 11. [ $\grave{u}$   ${}^{d}$ Ša-la] 1 ${}^{en}$  <TÚG>.Ú[R ${}^{?}$  ....]

12. [mdAG]-EN-M[U<sup>?</sup>-MEŠ<sup>?</sup> .... ITI.x U<sub>4</sub>.KAM KAM MU.x.KAM]

Edge Rev.

13. [mdA]G-NÍG.DU-Ù[RU LUGAL TIN.TIRki]

14. [1/2] ma-na SÍG.ZA.GÍN.<KUR>.[RA šá TÚG.HI.A šá dUTU] 15. 5 GÍN SÍG.ZA.GÍN.<KUR>.RA [šá TÚG.HI.A šá <sup>d</sup>HAR]

- 16. 1/3 GÍN SÍG.ZA.GÍN.<KUR>.R[A ...
- 17. la ḥa-a-ṭu [e-lat ana É DINGIR i-nam-din]
- 18. 1<sup>en</sup> TÚG.ÚR [....]
- 19. [1<sup>en</sup> TÚG].BAR.SI [šá] [....]
- 20. [x TÚG.NÍG.ÍB].LÁ.MEŠ
- 21. [....] <sup>[</sup>x x<sup>]</sup> [....]
- 22. [....] <sup>[</sup>x x<sup>]</sup> [....]

- L. 1. The reconstruction of the numeral is impossible because the weight of particular items differs in the time of Nebuchadnezzar from text to text. 7 sashes for Šamaš make it possible to identify the issue of garments for the cycle A (i. e. month Nisannu, Ayaru or Araḥsamna). In this cycle also 2 *şibtus* were delivered for him.
- L. 6. Although the last sign is partly damaged there is no doubt that the scribe wrote mistakenly  $\acute{\text{UR}}$  instead of  $\acute{\text{MAS}}$ .

[x] minas, [the weight of the *lubāru*-garment], [2] *şibtu*-garments, 7 sashes, 1 *lubār mē qaqqadi*-headdress, [4] *sūnu*-belts for Šamaš (and) 10 sashes for Aya.

\_\_\_\_\_\_

2 minas 10 shekels the weight of the *lubāru* (and) *sibtu*!-garments for Bunene

19 minas 50 shekels, the weight of the  $lu[b\bar{a}ru]$  (and) sibtu-garments, 1  $s\bar{u}nu$ -belt, 1  $[pars\bar{t}gu$ -headdress, 10 sas]hes for Ad[ad and Šala].

1 *sūnu*-belt, [....]

 $Nab\hat{u}^2$ ]-bēl-š[umāti $^2$  .... Month x,  $n^{th}$  day,  $n^{th}$  year of Ne]buchadnezz[ar, king of Babylon].

<sup>1</sup>/<sub>2</sub> mina of blue-purple wool [from the *lubāru*-garment of Šamaš]

5 shekels of blue-purple wool [from the *lubāru*-garment of Bunene]

20 shekels of blue-purple wool [...., PN, the ...,] with no supply [delivers to the temple].

1 sūnu-belt, [....], 1 paršīgu-headdress, [...., x sas]hes [....].

## **309. BM 66095** (82-9-18, 6086)

 $6.2 \times 3.4 \text{ cm}$ 

## 12.[x x]

- 1. [x ma-na KI.LAL TÚG.ḤI.A] šá <sup>d</sup>UTU
- 2. [x ma-na] KI.LAL TÚG.MÁŠ šá <sup>d</sup>UTU
- 3. [x ma-n]a 50 GÍN KI.LAL TÚG.HI.A SAG!(T: É).DU
- 4. [x TÚG].ÚR.MEŠ *šá* <sup>d</sup>UTU
- 5. [10 TÚG].NÍG.ÍB.LA.MEŠ *šá* <sup>d</sup>UTU
- 6. [10 TÚG.NÍG].ÍB.LA.MEŠ šá <sup>d</sup>A-a
- 7. [10 TÚG.NÍG.ÍB]. LÁ.MEŠ šá  $^{\rm d}$ 1GAŠAN Sip-par  $^{\rm ki}$
- 8.  $[x x x x x x x x x x x] 1^{en} [x] [...]$

## Rest lost

Rev.

- 1'. [x x x x] <sup>r</sup>x x<sup>1</sup> TÚG.<sup>r</sup>x x<sup>1</sup> [....]
- 2'. [x x x x]. [MEŠ  $a^{1}$ -na [x] [....]
- 3'. [x x 5] TÚG.NÍG.ÍB.LÁ.[MEŠ ....]
- 4'. [x x x  $\check{s}\acute{a}$ ]  $\lceil dBu \rceil$ -ne-[ne]
- 5'. [x x x x] šá  $^{\rm d}$ DUMU.MÍ.MEŠ [šá É-babbar-ra]
- 6'. [x x x x] <sup>[</sup>šá la<sup>]</sup> ha-a-[tu ...]
- 7'. [x x x x] U<sub>4</sub>.12.K[AM ....]

Rest completely eroded

```
[x minas, the weight of the lubāru-garment] for Šamaš
[x minas], the weight of the sibtu-garment for Šamaš
[x min] as 50 shekels, the weight of the lubār \langle m\bar{e} \rangle gaggadi-headdress, [x] sūnu-
belts for Šamaš, [10 sa]shes for Šamaš
[10 sa]shes for Aya
[10 sa]shes for the Queen of Sippar
[....], 1 [....]
[....]-garments for [...., 5] sashes [...., ....] for Bunene
[....] for the Daughters [of the Ebabbar ....] with no supply [....]
[....], 12<sup>th</sup> day, [....].
310. BM 51296 (82-3-23, 2330)
6.2 \times 3.0 cm
                        7.[x.x].
Obv.
             1'. [....] 'HI.A'.M[EŠ]
             2'. [....] a-di<sup>?</sup> 2 TÚG.<sup>r</sup>x x<sup>1</sup>
             3'. [x x x TÚG.Ú]R TÚG.BAR.DUL<sub>8</sub> TÚG.GÚ.UD.DU
             4'. [TÚG.HI.A ku-lu]-lu 3 TÚG.BAR.SIG.MEŠ šá <sup>d</sup>A-a
             5'. [x+]1-ta TÚG.BAR.DUL<sub>8</sub>.MEŠ 2-ta TÚG.GÚ.UD.'DU'.MEŠ
             6'. šá <sup>d</sup>DUMU.MÍ.<MEŠ> É-babbar-ra <sup>rmd</sup>AG-EN-MU¹.ſMEŠ
                    lúUŠ.BAR]
             7'. it-ta-[din ....]
             8'. 「3<sup>1</sup>6½ ma-na 「dul<sup>!</sup>-lu<sup>!</sup><sup>1</sup> [gam-ru KI.LAL]
Rev.
             9'. [TÚG.HI.A TÚG].MÁŠ TÚG.HI.A SIG5 「TÚG.ÚR.MEŠ1
           10'. [TÚG.NÍG.ÍB.LÁ].MEŠ šá <sup>d</sup>UTU <sup>d</sup>A-a
           11'. [TÚG.HI.A TÚG].MÁŠ šá <sup>d</sup>Bu-ne-ne
```

## Rest lost

- L. 4'. kulūlu before 3 paršīgus, cf. CT 4, 38a (= 178): 6–7 and VS 6, 26 (= 287): 14.
- L. 6'. From MU only one Winkelhaken is preserved.

14'. [.... K]I<sup>?</sup>

12'. [<sup>md</sup>AG-EN-M]U.MEŠ <sup>lú</sup>UŠ.BAR 13'. [*it-ta-din* ITI.x] U<sub>4</sub>.7.KAM

- L. 13'. Only IV, VI-VIII month can be taken into account because "head" of vertical sign is still visible.
- [... with 2 [x x]-garments, [...., the  $s\bar{u}$ ]nu-belt, the  $kus\bar{t}tu$ -robe, the nahlaptu-cloak, the [ $lub\bar{a}r\ kul\bar{u}$ ]lu-headdress, 3  $par\check{s}\bar{t}gu$ -headdresses for Aya,  $^{r}2^{1}$  robes, 2 nahlaptu-cloaks for the Daughters of the Ebabbar, Nabû-bēl-šumā[ti, the weaver] has deliver[ed ....].
- $36\frac{1}{2}$  minas, the [completed] work, [the weight of the  $lub\bar{a}ru$ ] (and)  $\dot{s}ibtu$ -garments, the  $lub\bar{a}r$  damqi-garment, the  $s\bar{u}nu$ -belts [(and) sashes] for Šamaš and Aya [the  $lub\bar{a}ru$ ] (and)  $\dot{s}ibtu$ -garments for Bunene, [Nabū-bēl-šum]āti, the weaver [has delivered]. Month of [x],  $7^{th}$  day [....].

311. BM 52636 (82-3-23, 3670)

PLATE 70

```
5.2 \times 2.2 \text{ cm}
                        [x.x].10
             1. 20 ma-na <dul-lu> gam-ru lu-bar šá ITI.AP[IN]
             2. 8 ma-na <TÚG>.MÁŠ 2 ma-na lu-bar S[AG<sup>?</sup>...]
             3. [1 1/3] ma-na TÚG.ÚR 3 ma-na [....]
             4. [x x x] <sup>r</sup>x x x 30<sup>?</sup> ma-na 6 G[ÍN ...]
Rest lost
             1'. 2 ni-^{\dagger}bi-hu šá ^{d}{}^{\dagger}[DN]
   Rev.
             2'. PAP 3 GÚ.UN 38 ma-na [SÍG.HI.A]
             3'. šá lu-bu-uš-tu<sub>4</sub> šá ITI. [APIN]<sup>?</sup>]
             4'. 1 2/3 ma-na 2 GÍN ta-hap-ta-šú
            5'. LAL.MEŠ šá <sup>m</sup>BA<sup>šá</sup>-a 5 GÚ.UN 34 lu-bar [x x]
Edge
             6'. LAL.MEŠ 1 GÚ.UN 30 ma-na [iħ]-[ti-it]
             7'. [x x x KA]M MU.10.KAM
L. h.e
Ll. 5'-6' looks like written on the upper edge over first line of obverse.
20 minas, the completed <work> for the month of Arahsamna
8 minas, <the weight of> the sibtu-garment
2 minas <the weight of> the lub\bar{a}r < m\bar{e}> qaq[qadi]-headdress
1 mina 20 shekels <the weight of 3> sūnu-belts
3 minas [....]
[....] 30<sup>?</sup> minas 6 sh[ekels ....]
2 nēbehu of [DN]
Total 3 talents 38 minas [of wool] for the lubuštu ceremony of the month
Arahsamna?
1 mina 42 shekels (for) his blanket.
Missing (from?) Iqīša: 5 talents, 34 garments? [....]
Missing: 1 talents 30 minas [....] [....], 10<sup>th</sup> year.
312. BM 69280 (82-9-18, 9278)
4.5 \times 3.7 \text{ cm}
             1'. [....] \lceil x \rceil [....]
             2'. 'TÚG.ÚR¹.MEŠ 6 TÚG.N[ÍG.ÍB.LÁ.MEŠ šá <sup>d</sup>UTU]
             3'. 10 TÚG.NÍG.ÍB.LÁ.MEŠ šá [<sup>d</sup>A-a]
```

L. 13'. Because 70 shekels is the weight of 10 huṣannus and 1 sūnu for Adad and Šala, the reconstruction seems certain. The name of Šala is often missing in such context.

L. 16'. The presence of Gula suggests that the text was written in or after the 8<sup>th</sup> year of Nebuchadnezzar, see Bongenaar, *Ebabbar*, p. 233, note 212.

[....], the *sūnu*-belts, 6 sa[shes for Šamaš], 10 sashes for [Aya]

-----

1 mina, the weight of 10 s[ashes] for the Queen of Sippar

<sup>[2]</sup> minas, the weight of the *lubāru* [(and) *şibtu*-garments] for Bunene.

[Tot]al 36 minas 20 shekels, the we[ight of .... for Šamaš, Aya and [the Daughters]

of the Ebabbar

[x mi]na(s) 15 shekels, the wei[ght of ....] Nabû<sup>?</sup>-bēl<sup>?</sup>-[šumāti [....]

1<sup>?</sup> mina 10 [shekels], the weig[ht of 10 sashes] (and) 1 *sūnu*-belt for Adad [and Šala] 35 shekels, the weig[ht ....]

[20 shekels], <the weight> of the *sūnu*-belt for G[ula].

#### **313. BM 71337** (82-9-18, 11339)

 $4.4 \times 4.6$  cm

Acc. year

- 1. [....] *a-na*
- 2. [....] 24 [....]
- 3. [....] *mu-ta-tu*<sub>4</sub> *šá* [<sup>d</sup>UTU]
- 4. [....] TÚG.ḤI.A šá <sup>d</sup>UTU
- 5. [....] ma-na 6 GÍN SÍG.ZA.GÌN.<KUR>.RA
- 6. [....] MÁŠ *šá* <sup>d</sup>UTU
- 7. [....] 'TÚG.ḤI.A' 'si-ku<sup>?</sup>'

Rest lost Rev.	8. [] <sup>r</sup> x TÚG <sup>?</sup> <sup>1</sup> []
	1'. [ <sup>d</sup> G]u-la
	2'. [].MEŠ ù TÚG.ÚR.MEŠ 3'. [] x šá <sup>md</sup> AG-EN- <mu>.MEŠ</mu>
	4'. [ dul]-lu gam-ru <sup>m</sup> DUMU.UŠ-a 5'. [] a-na É DINGIR it-[ta-din] 6'. [ SÍG.ZA.GÌN].KUR.RA 7'. [] MU.SAG.[] NAM.LUGAL.LA
[] for 24 [], the <i>muttatu</i> -headdress for [Šamaš]; [], the <i>lubāru</i> -garment for Šamaš; [] mina 6 shekels of the blue-purple [] the <i>şibtu</i> -garment for Šamaš [] the <i>lubāru</i> -garment []	
[] (for) (	Gula
[] the co	ne sūnu-belts [] which Nabû-bēl-<šumāti> [] om]pleted work Aplā [] to the temple has deli[vered]. ue-pu]rple wool, ces[sion year].

### XI. The tabû lists

# **314. BM 63503+BM 64313** (82-9-18, 3470+ 4289) PLATE 70 $6.2 \times 6.7$ cm 1'. [x] GADA sal-hu eš-šú [....] 2'. [x] GADA sal-hu eš-šú a-na [....] 3'. [x] GADA sal-hu eš-šú a-na ${}^{d}$ [A]-[a] 4'. [x] GADA sal-hu eš-šú a-na <sup>d</sup>[HAR] 5'. [GADA.MEŠ šá t]a-bi-e šá $^{\rm d}$ UTU U4.11.KAM šá I[TI.x $^{\rm ?}]$ 6'. [3 GADA sal]- $\lceil hu \rceil$ eš-šú a-na ta-lu- $k[a-a-tu_4(\mathbf{x}\ \mathbf{x})]$ 7'. [x GADA sal-h]u a-na ta-hap-šú a-rna [....] 8'. [x x x x] *a-na ta-[hap]-šú a-na* [...] 9'. [x x x x] [a-na ta-hap]-šú a-na [....] 10'. [x GADA k]ib-su a-na ÚR.MEŠ a- $\lceil na \rceil$ [ $^{d}$ UTU] 11'. 「1' GADA sal-hu a-n[a] ta-hap-šú a-na <sup>d</sup>Bu-<sup>[</sup>ne] 12'. 1 GADA sal-hu a-na <sup>[</sup>ta-hap-šú a-na] <sup>d</sup>[GAŠAN Sip-par<sup>ki</sup>] 13'. 1 GADA sal-ḥu a-na ta-ḥap-šú a-na <sup>d</sup>「A-nu-ni-tu4<sup>1</sup> Rev. 14'. 1 kib-su a-na ta-ḥap-šú a-na <sup>d</sup>[Gu-la] 15'. [x ki]b-su a-na ta-ḥap-šú a-na <sup>d</sup>I[M<sup>?</sup>] 16'. [x kib-su] $\lceil a$ - $na \check{s}u$ -bat $\rceil < a$ - $na > {}^{d}AMAR.UTU u$ <sup>d</sup>[GAŠAN-*ia*] 17'. [1 kib-su SUMUN] a-na šu-bat šá <sup>d</sup>ziq-qu[r-rat] 18'. [x kib-su SUMUN] a-na DUMU.MÍ.<MEŠ> $\acute{E}$ -[babbar]-[ra] 19'. [x kib-su] a-na ta-be-e šá <sup>d</sup>[DN] 20'. [x kib]-su a-na ta-be-e šá <sup>d</sup>Ša-[la] 21'. [x ki]b-su a-na ta-be-e šá ${}^{d}$ ${}^{\Gamma}$ ${}^{\Gamma}$ (-[x)] 22'. [x ki]b-su a-na ÚR.MEŠ a-[na] [....] 23'. [x ki]b-su a-na 「ÚR¹ [....] 24'. [x ki]b-su a-[na ....] 25'. [x kib]-[su] [a-na ....] Ll. 11'-13'. It seems that here, by comparison with other texts, (labīru) salhus were meant. In this text, just like in Nbk 312, Immertu is missing, but the Queen of Sippar is present; however, it is the only argument for the dating of the text to the time of Nebuchadnezzar. [x] new linen tunic [....] [x] new linen tunic for [....] [x] new linen tunic for A[ya] [x] new linen tunic for Bunene -----[Linen garments for] tabû-procession for Šamaš, the 11<sup>th</sup> day of m[onth x<sup>?</sup>]

```
[3] new l[inen tun]ics for the t\bar{a}lu[ku]-processions<sup>?</sup> for [....]
```

[x] new [linen tun]ic for c[ov]er for [....]

[....] for <sup>r</sup>cover for [....]

[.... for cove]r [for ....]

[x linen kib]su-fabric for the sūnu-belts for [Šamaš]

1 linen tunic for cover for Bune[ne]

1 linen tunic for cover for the Queen of Sippar

1 linen tunic for cover for Anunītu

1 kibsu-fabric for cover for Gula

[x ki]bsu-fabric for cover for Ad[ad]

[x used kibsu-fabric] for the cultic seat(s) of Marduk and [Bēltiya]

[x used *kibsu*-fabric] for the cultic socle of ziqqu[rat]

[x used kibsu-fabric] for the Daughters of the Ebabbar

[x kibsu-fabric] for tabû-procession of [DN]

[x ki]bsu-fabric for tabû-procession of Ša[la]

[x ki]bsu-fabric for tabû-procession of [....]

[x ki]bsu-fabric for the sūnu-belts for [....]

[x ki]bsu-fabric for the  $\lceil s\bar{u}nu^{\rceil}$ ? [....]

[x ki]bsu-fabric f[or ....]

[x kib]su-fabric [for ....].

#### **315.** Cam **148** = BM 60626 Collated

 $5.8 \times 7.5$  cm

#### 2.2.Cyr 2

- 1. [GADA.ME]Š <<br/>šá> 「 $ta^{1*}$ -be-e šá  $^{\rm d}$ UTU šá U<sub>4</sub>.「 $10^*$ .KAM\*<br/>1
- 2. [šá ITI G]U<sub>4</sub>\* MU\*.2\*.「KAM\*1  $^{\rm m*}$ Ku\*-raš \* LUGAL\* E\* $^{\rm ki}$ \* LUGAL\* KUR\*.KUR\*
- 3.  $\lceil a \rceil$ -na  $^{\mathrm{md}}$ UTU-TIN $^{it}$  Iú\* TÚG\*.BABBAR\* SUM $^{na}$  [ITI.G]U $_4$ \*
- 4. 「U<sub>4</sub>¹.9.KAM MU.「2¹.KAM <sup>m</sup>「Ku\*-raš \*¹ LUGAL E<sup>ki</sup> LUGAL KUR.KUR

- 5. 1 GADA hu-la-nu [eš-šú 2 GADA sal-hi eš-šú a-na <sup>d</sup>UTU]
- 6. 1 GADA sal-hi [eš-šú a-na <sup>d</sup>A-a]
- 7. 「31 [GADA sal-ḥu a-na ta-lu-ka-a-ta a-na <sup>d</sup>UTU]
- 8. 1 G[ADA ....]
- 9. 1 G[ADA ....]

Ca. half of the tablet of obv. is preserved, but the surface is completely destroyed and no signs remain.

Rev. (beginning lost).

1'. [x+1 GADA.ME<sup>?</sup>] [....]

Free space for ca 2 lines

2'. 5 GADA sal-ḫu a-na ta-lu-ka-a-ta a-na <sup>d</sup>[IM]

- 3'. 3 kib-su šá ÚR.MEŠ a-na <sup>d</sup>UTU
- 4'. 1 GADA kib-su šá ÚR a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 5'. 1 GADA kib-su šá ÚR a-na dIM
- 6'. PAP 31 GADA
- 7'. 4 GADA sal-ḥu eš-šú a-na pu\*-ṣu\*-ú\* 8'. [ina] IGI  $^{\mathrm{md}}$ ḤAR-ši-man  $^{an}$ -ni

[Linen garmen]ts <for>  $tab\hat{u}$ -procession of Šamaš for the  $10^{nd}$  day [of Aya]ru,  $2^{nd}$  year of Cyrus, king of Babylon, king of Lands, were given to Šamaš-uballit, the  $a\bar{s}l\bar{a}ku$ . [Month Ay]aru,  $9^{th}$  day,  $2^{nd}$  year of Cyrus, king of Babylon, king of Lands.

1 [new] linen *hullānu*-cloak, [2 new linen tunics for Šamaš]

- 1 [new] linen tunic for [Aya]
- 3 [linen tunics for *tāluku*-processions? for Šamaš]
- 1 li[nen ....]
- 1 li[nen ....]

.....

- x+1 linen garments [....]
- 5 linen tunics for *tāluku*-processions? for Adad
- 3 kibsu-fabrics for sūnu-belt for Šamaš
- 1 linen *kibsu*-fabric for *sūnu*-belt for Anunītu
- 1 linen kibsu-fabric for sūnu-belt for Adad, total 31 linen garments.
- 4 new linen tunics for bleaching (given) at disposal of Bunene-šimanni.

#### 316. BM 62628 (82-9-18, 2597)

PLATE 71

 $6.3 \times 9.1 \text{ cm}$ 

#### 5.2.Cam 7

- 1. [GADA.MEŠ *šá* ....]
- 2. a-na ta-be-e š[á U<sub>4</sub>.x.KAM] a-<sup>r</sup>na<sup>†</sup> PN [....]
- 3. [lúTÚG.BABBAR] SUM<sup>na</sup> ITI.GU<sub>4</sub> U<sub>4</sub>.<sup>r</sup>51.KAM MU.<sup>[7]</sup>.[KAM]
- 4. ["Kam]-bu-zi-ja LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.[KUR]

- 5. [1] GADA hu-la-nu 2 GADA sal-hu eš-šú a-na [dUTU]
- 6. 2 GADA sal-hu a-na <sup>d</sup>A-a
- 7. 2 GADA sal-hu a-na dDUMU.MÍ.<MEŠ> É-babbar-[ra]
- 8. 1 GADA hu-la-nu 1 GADA sal-hu a-na <sup>d</sup>[Bu-ne-ne]
- 9. 1 GADA *sal-hu a-na* <sup>d</sup>GAŠAN *Sip-par*<sup>ki</sup>
- 10. 2 GADA sal-hu a-na <sup>d</sup>Gu-la

- 11. GADA *šá a-na ta-be-e šá* <sup>d</sup>UTU
- 12. 「3¬ GADA sal-hu eš-šú a-na ta-¬lu¬-ka-t[u4]
- [a-n]a<sup>d</sup>UTU 13.

```
14. [x GADA sa]l-hu a-na ta-hap-šú a-na <sup>d</sup>UTU
15. [x \times x \times a]-na ta-hap-šú [a-na [a]
```

Rest lost

Rev.

```
1'. [x GADA kib-su] [a]-[na ....]
```

- 2'. [x GADA kib]-su a-na <sup>d</sup>[DN]
- 3'. [1 k]ib-su a-na dŠa-[la]
- 4'. 1 ÚR šá GADA 4 GADA kib-su a-na 「ÚR T
- 5'. 2 GADA kib-su a-na <sup>d</sup>šu-bat <sup>d</sup>AMAR.UTU

- 6'. 1 kib-su a-na <sup>d</sup>DUMU.MÍ.<MEŠ> É-babbar-ra
  7'. 2 kib-su a-na <sup>d</sup>ziq-qur-rat
  8'. 2 <sup>r</sup>kib-su<sup>1</sup> a-na <sup>d</sup>Bu-ne-ne
  9'. [x kib-su] <sup>r</sup>a-na<sup>1</sup> <sup>d</sup>GAŠAN UD.KIB.NUN<sup>rki</sup>
  10'. [x kib-su a]-<sup>r</sup>na <sup>d</sup>A-nu-ni-tu<sub>4</sub> <sup>r</sup>šá UD<sup>1</sup>.KIB.[NUN<sup>ki</sup>]-<<sup>d</sup> $^{1}A$ -nu-ni-tu<sub>4</sub>>
- 11'. [x kib-su a-na] <sup>d</sup>Gu-la 12'. [x kib-su a-na <sup>d</sup>]IM ina lìb-bi 1 L[AL<sup>?</sup> ....]
- 13'. [x kib-su a]-「na<sup>¬ d</sup>Ša-la

Only one line is missing; the possible reconstruction is: [GADA.MEŠ a-na PN + title] / a-na ta-be-e šá [U<sub>4</sub>.x.KAM šá ITI.GU<sub>4</sub>].

L. 7. Note the high position of the Daughters of the Ebabbar preceding not only the Queen of Sippar and Gula, but even Bunene. A similar order is observed in the reverse.

[Linen garments ....] for  $tab\hat{u}$ -procession fo[r n<sup>th</sup> day were given to [PN, ....]. Month Ayaru, 5<sup>th</sup> day, 7<sup>th</sup> year of [Cam]byses, king of Babylon, king of Lands.

- [1] linen *hullānu*-cloak 2 new linen tunics for [Šamaš]
- 2 linen tunics for Aya
- 2 linen tunics for the Daughters of the Ebabbar
- 1 linen *hullānu*-cloak, 1linen tunic for [Bunene]
- 1 linen tunic for the Queen of Sippar
- 2 linen tunics for Gula

Linen garments for procession of Šamaš

3 new linen tunics for *tāluku*-processions? f[or] Šamaš

[x linen tu]nic for cover for Šamaš

[.... f]or for cover for [....]

[x linen *kibs*]*u*-fabric f[or ....]

[x linen kib]su-fabric for [....]

[1 ki]bsu-fabric for Ša[la]

- 1 sūnu-belt (made) of linen, 4 linen kibsu-fabrics for sūnu-belt,
- 2 linen kibsu-fabrics for cultic seat of Marduk
- 1 kibsu-fabric for the Daughters of the Ebabbar
- 2 kibsu-fabrics for ziggurat
- 2 kibsu-fabrics for Bunene
- [x kibsu-fabric] for the Queen of Sippar
- [x kibsu-fabric f]or Anunītu-ša-Sippar-<Anunītu>

```
[x kibsu-fabric for] Gula
[x kibsu-fabric for] Adad, including 1 [....]
[x kibsu-fabric f]or Šala.
317. BM 67889 (82-9-18, 7887)
                                                                                            PLATE 72
4.4 \times 3.2 \text{ cm}
              1'. <sup>[2</sup> sal<sup>[]</sup>-hi GADA q[al-la ....]
              2'. a-na <sup>d</sup>UTU \lceil \hat{u} \rceil \lceil d^{\dagger}A-a \rceil
              3'. 1 sal-hi GADA <sup>[</sup>qal-la] [....]
4'. a-na <sup>d</sup>Bu-ne-n[e ....]
              5'. [1] kib-su <sup>[</sup>x<sup>]</sup> [....]
              6'. [(x x)]^{T} x a^{T} - na [...]
Rev.
              1'. 「1 kib-su GADA¬ qal-la [....]
              2'. 1 kib-su GADA qal-la [....]
              3'. 1 kib-su GADA qal-la [....]
                                 a-na dUT[U....]
              5'. 1 kib-su GADA qal-la bu-<sup>[</sup>x<sup>1</sup> [....]
              6'. 「PAP<sup>?</sup> 1 20 GADA.HI.A [ina] IGI <sup>m</sup>[Sil]-[la-a ....]
2 sm[all] linen tunics [....] for Šamaš and [Aya]
1 small linen tunic [....] for Bunene
[1] kibsu-fabric [....] for [....]
1 small linen kibsu-fabric [....]
1 small linen kibsu-fabric [....]
1 small linen kibsu-fabric for Šam[aš ....]
1 small linen kibsu-fabric [....]
total 20 linen fabrics [at] disposal of Şill[ā ....].
318. BM 70870 (82-9-18, 10871)
3.6 \times 3.6 cm
                           г10<sup>7</sup>.6.13
              1. 1 GADA sal-h[i ....]
              2. 1 GADA sal-hi [....]
              3. 1 GADA kib-su šá [....]
              4. 1 GADA kib-su šá [....]
              5. 1 GADA sal-hi^{rd?} [DN?]
Rest lost
              1'. 2 [.....]
2'. IGI {}^{d}_{\Gamma}x^{1} [...]
Rev.
```

```
3'. i-te-\lceil x \rceil \lceil .... \rceil
              4'. ITI.KIN U<sub>4</sub>. [10][+x<sup>2</sup>.KAM]
              5'. MU.13.KAM <sup>m</sup>[....]
              6'. LUGAL [....]
1 linen tuni[c ....]
1 linen tunic [....]
1 linen kibsu-fabric for [....]
1 linen kibsu-fabric for [DN<sup>?</sup>]
1 linen kibsu-fabric [....]
2 [....]
before [....]
Month Ulūlu, 10[+x<sup>?</sup>] day, 13<sup>th</sup> year of [KN], king of [....]
319. BM 74304 (82-9-18, 14327)
3.9 \times 4.3 \text{ cm}
              1'. [x x x] eš-šú šá <sup>d</sup>U[TU ....]
              2'. [x \times h]u \ e\check{s}-\check{s}\check{u} \ 2 \ sal-h[u \dots]
              3'. [x GA]DA sal-hu šá ta-[lu-ka-tu<sub>4</sub> šá <sup>d</sup>UTU]
             4'. [1] kib-su eš-šú šá [d][Bu-ne-ne]
              5'. 1 kib-su la-bir-[ri a-na ta-ḥap-šú a-na dGAŠAN Sip-parki]
              6'. 1 kib-su la-bir-[ri a-na ta-hap-šú a-na dA-nu-ni-tu4]
              7'. 1 kib-su la-b[ir-ri a-na ta-hap-šú a-na <sup>d</sup>Gu-la]
              8'. 2 kib-su la-bi[r-ri a-na ta-ḥap-šú a-na <sup>d</sup>IM]
Rev.
              9'. 2 kib-su la-bir-<ri>šá [ta-hap-šú]
                       \check{s}\acute{a}^{\mathrm{d}}\check{S}a-l[a]
            10'.
            11'. <sup>[1]</sup> sal-ḫu a-na ÚR pu-uš-ku
            12' ina IGI <sup>Ĭú</sup>TU.É šá <sup>d</sup>[DN]
            13'. 1 hu-la-nú PAP 7 sal-hu [eš-šú]
            14'. [11 GAD]A kib-su PAP 18 [GADA.MEŠ ....]
            15'. [.... sa]l-hu a-na ta-[hap-šú ....]
            16' [....] <sup>[</sup>x x<sup>]</sup>
Ll. 5'-10'. The reconstruction is based on Cyr 185 (= 326): 17-22 and BM 66166
(= 333): 13'-14', rev. 2'-7'.
[....] new [....] for Šamaš
[x] new [....] 2 tuni]cs [....]
[x lin]en tunics for tā[luku-processions? for Šamaš]
1 new kibsu-fabric for [Bunene]
1 use[d] kibsu-fabric [for cover for the Queen of Sippar]
1 use[d] kibsu-fabric [for cover for Anunītu]
1 use[d] kibsu-fabric [for cover for Gula]
```

```
2 use[d] kibsu-fabrics [for cover for Adad]
```

2 use[d] kibsu-fabrics for [cover for Šal[a]

1 tunic for the sūnu-belt of one-eight cubit width at disposal of the ērib bīti of

1 hullānu-cloak, total 7 [new] tunics, [11 line]n kibsu-fabrics, grand total 18 [linen cloths ...., x tu]nic for co[ver ....].

#### **320. BM 74325** (82-9-18, 14348)

 $8.8 \times 4.9$  cm

```
1. [....] 「x¹ [...]
```

2. [....]-<sup>r</sup>na ITI<sup>1</sup>.[x ....]

3. [.... h]u-ul- ${}^{\Gamma}$ la ${}^{\Gamma}$ -nu e $\dot{s}$ - $[\check{s}\check{u}$  a-na  ${}^{d}$ UTU

4. [x GADA] *ta-hap-*[šú ....]

5. [x GADA] *ta-ḥap-*[šú ....]

6. <sup>[1]</sup> GADA *kib-su eš-šú* a-n[a ....]a-na <sup>d</sup>[DN] 7. <sup>[1]</sup> GADA ta-hap-šú a-na <sup>d</sup>NIN-<sup>r</sup>x<sup>1</sup> a-na <sup>d</sup>NIN-<sup>r</sup>x<sup>1</sup> a-na <sup>d</sup>Gu-la 8. <sup>[1]</sup> GADA ta-ḥap-šú 9. [x] GADA kib-su eš-šú

10. [1 GA]DA *ta-hap-šú* 

Rest lost

Rev.

1'. [x GADA] kib-su <sup>r</sup> eš <sup>1</sup> -šú	$a$ - $na$ $^{\mathrm{d}_{\Gamma}}\mathrm{DN}^{\gamma}$
2'. [x GADA ki]b-su eš-šú	a-na <sup>d</sup> A-nu-ni-tu <sub>4</sub>
3'. [x GADA] <sup>r</sup> kib¹-su eš-šú	a-na <sup>d</sup> IM
4'. [x GADA $kib$ ]- $\lceil su \rceil$	a-na <sup>d</sup> Ša- <sup>r</sup> la <sup>1</sup>
5'. [2 GADA] <i>kib-su</i> <sup>d</sup> AMAR.UTU [ <i>u</i> ]	
6'. [x GADA] kib-su	<sup>d</sup> ziq-qur-[rat-tu <sub>4</sub> ]
7'. [x GADA] <i>kib-su</i> <sup>r</sup> <i>eš</i> <sup>1</sup> - <i>šú</i>	$a$ - $na^{d_{\Gamma}}DN^{\gamma}$
8'. [] <i>ina</i> IGI <sup>md</sup> U[TU <sup>?</sup>	

Note a quite large distance between the name of garment and the god's name.

The low position of Marduk and Şarpanītu suggests that the text was written in the time of Nabonidus.

```
[.... giv]en?. Month [....]
[.... ne[w h]ullānu-cloak [for Šamaš]
[x line]n cove[r ....]
[x line]n cove[r ....]
1 new linen kibsu-fabric fo[r ....]
1 linen kibsu-fabric for [DN]
1 linen kibsu-fabric for Nin-[....]
[x] new linen kibsu-fabric for Nin-[....]
[1 lin]en blanket for Gula
```

[x] new [linen] kibsu-fabric for [DN]

```
[x] new [linen kib]su-fabric for Anunītu
```

- [x] new [linen] kibsu-fabric for Adad
- [x linen kib]su-fabric for Šala
- [2 linen] kibsu-fabric (for) Marduk [and] Şarpanītu
- [x linen kib]su-fabric (for) ziqqurat
- [x] new [linen] kibsu-fabric for [DN] at disposal of Ša[maš?-....]

#### **321. BM 60307** = Str II 337/4 Collated

 $6.0 \times 7.3 \text{ cm}$ 

#### 5.2.Nbn [x]

- 1. [....] <sup>r</sup>x x<sup>1</sup>
- 2. ITI.  ${}^{r}GU_4{}^{1}U_4. {}^{r}8{}^{1}.KAM MU[.x.KAM]^dAG-I LU[GAL E^{ki}]$ \_\_\_\_\_
- 3. 1 hu-ul-la-nu eš-šú 2 GADA sal-hi eš-ſšú¹ [a-na] dUTU
- 4. 2 GADA sal-hi eš-šú a-na <sup>d</sup>A-a
- 5. 3 GADA sal-hi eš-šú a-na ta-lu-ka-tu<sub>4</sub>
- 6. 1 GADA kib-su eš-šú BAD-ma a-na 「šub\*-tu4¹ [šá <sup>d</sup>A]-a
- 7. 1 GADA sal-ḥi eš-šú a-na kib-「su a¬-na dUTU
- 8. ----  $u \ a$ - $na < ^{d} > A$ -a
- 9. 1 GADA sal-ḥi SUMUN a-na <sup>r</sup>ta<sup>1</sup>-ḥap-šú a-na <sup>d</sup>UTU
- 10. 1 GADA sal-hi SUMUN a-na ta-hap-šú a-na <sup>d</sup>A-a 11. 1 GADA sal-hi SUMUN a-na ta-<sup>r</sup>hap-šú<sup>1</sup> šá<sup>1 d</sup>Im<sup>1</sup>-mir-tu<sub>4</sub>
- 12. 1 kib-<sup>r</sup>su SUMUN<sup>1</sup> a-na ta-ḥap-šú šá <sup>d</sup>HAR
- 13. [1] *kib*-<sup>[</sup>*su*<sup>1</sup> [SUMUN] <sup>[</sup>*a-na*<sup>1</sup> [....]

Rev.

- 1'. 1 *kib-su* [....]
- 2'. 1 kib-su SUMUN [....] (one line fee)
- 3'. PAP 23 GADA.MEŠ <sup>r</sup>ina lìb-bi<sup>1</sup>
- 4'. 7 GADA eš-šú 16 GADA SUMUN
- 5'. e-lat 1 kib-su šá su-ni-e
- 6'. šá É <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 7'. 5 GADA.MEŠ te-nu-ú ku-ú 「GADA1
- 8'. eš-šú <sup>md</sup>UTU-NUMUN-GÁL<sup>ši</sup> it-ta-din 9'. [1 GA]DA *ḫu-ul-la-nu* šá <sup>d</sup>UTU 1 GADA *ḫu-ul-[la-nu* šá <sup>d</sup>ḤAR]
- 10'. [x GADA] sal-hi šá <sup>d</sup>IM 2 GADA sal-hi šá <sup>d</sup>ME.ME
- 11'. [....] [x] dUTU PAP 7 GADA ina IGI mdHAR-[ši²-man]-[ni]
- 12'. [....] PAP [2] [....]
- L. 1. GADA *šá a-na ta-be-e šá* is expected there.

[.... Month Ayaru, 8<sup>th</sup> day, [n<sup>th</sup>] year of Nabonidus, ki[ng of Babylon]

1 new *hullānu*-cloak, 2 new linen tunics [for] Šamaš

323

```
2 new linen tunics for Aya
3 new linen tunics for tāluku-processions?
1 new open linen kibsu-fabric for cultic seat [of Ay]a
1 new tunic for kibsu-fabric for Šamaš and for Aya
1 used tunic for cover for Šamaš
1 used tunic for cover for Ava
1 used tunic for cover for Immertu
1 used kibsu-fabric for cover for Bunene
[1 used] kibsu-fabric for [....]
1 kibsu-fabric [....]
1 used kibsu-fabric [....]
Total 23 linen garments, including 7 new linen cloths (and) 16 used linen cloths.
Except for 1 kibsu-fabric for the sūnu-belt for the chapel of Anunītu, 5 linen fabrics
for exchange for new linen cloth, (which) Šamaš-zēr-ušabši has delivered.
[1 lin]en hullānu-cloak for Šamaš, 1 linen hul[lānu-cloak for Bunene], [x linen]
tunic for Adad, 2 linen tunics for Gula, [....] Šamaš, total 7 linen cloths at disposal
of Bunene-<sup>r</sup>šiman<sup>1</sup>[ni ....], total 2 [....].
322. BM 61964 (82-9-18, 1933)
4.3 \times 6.7 cm
            1'. [x x x x]-^{\Gamma}MU^{1} lú[....]
            2'. [x x x x]-ŠEŠ-MU [....]
            3'. [1 GAD]A 「hu¬-la-nu eš-šú [2 GADA sal-hu eš-šú a-na
            4'. [2 GAD]A sal-hu eš-šú a-n[a <sup>d</sup>A-a]
            5'. [1 GAD]A sal-hu eš-šú a-n[a ....]
            6'. [1] GADA sal-ḫu <eš-šú a-na> ta-ḫap-šú a-[na <sup>d</sup>UTU]
            7'. [1] 「GADA<sup>†</sup> sal-hu < e\check{s}-\check{s}\check{u} a-na> ta-hap-\check{s}\check{u} [a-na ....]
            8'. [1 G]ADA kib-su ta-ḥap-[šú a-na ....]
            9'. 1 [GA]DA kib-su ta-hap-š[ú a-na ....]
           10'. 1 「GADA<sup>1</sup> kib-su ta-ḥap-[šú a-na ....]
           11'. 1 GAD[A k]ib-su ta-h[ap-šú a-na ....]
           12'. 1 GAD[A k]ib-su t[a-ḥap-šú a-na ....]
Rest lost
Rev.
            1'. [1] GADA kib-s[u ....]
            2'. [1] GADA kib-su [....]
            3'. 3 GADA kib-su [....]
            4'. 2 GADA kib-su [....]
            5'. 2 GADA kib-su a-n[a ....]
```

6'. PAP [x] GADA ina lìb-bi 7 GA[DA eš-šú]

```
7'. [e-lat 1 GADA kib-su] šá ÚR.MEŠ [šá É <sup>d</sup>A-nu-ni-tu<sub>4</sub>]
            8'. [....].MEŠ a-na [....]
Rest lost
At the missing beginning GADA ana ta-be-e šá <sup>d</sup>DN is expected.
L. 5'. A possible reconstruction is a-n[a \, ^dHAR] or a-n[a \, ta-lu-ka-a-ta].
In lines \hat{7}'-12' lacks a-na before ta-hap-šú.
Rev. 7'. For the reconstruction, see Nbn 694 (= 325): 25-26 and BM 60307
(= 321), rev. 5'-6'.
[....]-iddin, the [....]-aḥ-iddin [....]
[1] new [lin]en hullānu-cloak, [2 new linen tunics for Šamaš]
[2] new [line]n tunics fo[r Aya]
[x] new [line]n tunics f[or ....]
[1] <new> linen tunic <for> cover f[or Šamaš?]
[1] new linen tunic <for>) cove[r for ....]
[1 li]nen kibsu-fabric <for> cove[r for ....]
1 line[n k]ibsu-fabric <for> cove[r for ....]
1 line[n k]ibsu-fabric <for> cove[r for ....]
1 line[n k]ibsu-fabric <for> co[ver for ....]
1 lin[en k]ibsu-fabric <for> c[over for ....]
[1] linen kibs[u-fabric [....]
[1] linen kibsu-fabric [....]
3 linen kibsu-fabrics [....]
2 linen kibsu-fabrics [....]
2 linen kibsu-fabrics fo[r ....]
Total [x] linen garments, including 7 [new] lin[en cloths, except for 1 linen kibsu-
fabric] for the sūnu-belts [for the chapel of Anunītu]
[....] for [....].
323. BM 69029 (82-9-18, 9028)
                                                                                 PLATE 72
4.2 \times 5.5 cm
            1'. [.... ITI].GU<sub>4</sub>
            2'. [....]
            3'. [1 GADA sal-hu SUMUN a-na ta]-hap-šú a-na <sup>d</sup>UTU
            4'. [1 GADA sal-hu SUMUN a-na t]a-hap-šú a-na <sup>d</sup>A-a
            5'. [1 GADA sal-hu SUMUN a-na] <sup>[ta]</sup>-hap-šú a-na <sup>d</sup>Im-mir-tu<sub>4</sub>
            6'. [1 GADA sal-hu SUMUN a-na] <sup>r</sup>ta<sup>1</sup>-hap-šú a-na <sup>d</sup>Bu-ne-ne
```

7'. [1 GADA sal-hu SUMUN a-na] ta-hap-šú a-na dGAŠAN

UD.KIB.NUNki

8'. [.... a-na t]a-ḥap-šú a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub>

9'. [.... a-na ta-ḥa]p-šú a-na <sup>d</sup>Gu-la

11'. [... a-na t]a-hap-šú a-na dziq-qu]r-ra1-tu4

Reverse is completely eroded (no signs exist more). For reconstruction, cf. Nbn 694 (= 325): 9ff. and Nbn 696 (= 326): 10 ff.

## [.... Month] Ayaru [....]

- [1 used linen tunic for co]ver for Šamaš
- [1 used linen tunic for clover for Aya
- [1 used linen tunic for] cover for Immertu
- [1 used linen tunic for] cover for Bunene
- [1 used linen tunic for] cover for the Queen of Sippar
- [.... for] cover for Anunītu
- [.... for cov]er for Gula
- [.... for cover for Mard]uk and Ṣarpanītu
- [.... for cover for ziqq]urat.

### **324. Nbk 312** = BM 75588 Collated

 $5.3 \times 7.3$  cm

#### 9.2.Nbk 36

- 1. GADA *šá-hu-ú šá a-na*  ${}^{m}$ *Ṣil\*-la-a* 2.  ${}^{l\acute{u}}$ TÚG.BABBAR SUM ${}^{nu}$  ITI. ${}^{l}$ GU $_{4}$  $^{l}$ U $_{4}$ .9.KAM 3. MU.36.KAM  ${}^{d}$ AG-NÍG.DU-ÙRU LUGAL TIN.TIR ${}^{k\acute{u}}$

- 4. 1 GADA *hu-ul-la-nu eš-še šá* <sup>d</sup>UTU
- 5. 3 GADA *sal-ḥi eš-še šá* UGU <sup>giš\*</sup>*šu\*-bat\** <sup>meš</sup>
- 6. šá <sup>d</sup>UTU šá ta-lu\*-ka-a-ta
- 7. 1 GADA sal-hi eš-še a-na 1 kib-su šá <sup>d</sup>UTU
- 8. [1] GADA *ḫu-ul-la-nu eš-še šá <sup>d</sup>Bu-ne-ne*
- 9. [1 GAD]A sal-hi eš-še šá <sup>d</sup>DUMU.MEŠ É-babbar-ra
- 10. [1 GADA ki]b-su eš-še šá <sup>d</sup>Bu-ne-ne
- 11. [1 GADA *kib-s*]*u eš-še šá* <sup>d</sup>GAŠAN *Sip-par*<sup>ki</sup> 12. [1 GADA *kib-s*]*u eš-še šá* <sup>d</sup>*Gu-la*
- 13. [1 GADA *kib-s*]*u la-bir-ri* [*šá* <sup>d</sup>ḤAR]
- 14. [1 GADA kib-s]u la-[bir-ri šá dGAŠAN Sip-parki]

Rev.

- 15. [1 GADA sal]-hi a-na ta-[hap-šú šá <sup>d</sup>UTU]
- 16. [1 GADA sal]-hi a-na ta-hap-šú šá <sup>d</sup>[A-a]
- 17. [2 GADA sal]-hi a-na ta-hap-šú
- 18. [šá <sup>d</sup>B]u-ne-ne u <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 19. [1 GADA] kib-su la-bir-ri šá <sup>d</sup>Gu-la

- 20. 1 GADA kib-su šá UGU šub-tu<sub>4</sub> a-na <sup>d</sup>rAMAR.UTU<sup>1</sup>
- 21. 1 GADA kib-su šá UGU šub-tu<sub>4</sub>{x x} (ras.)
- a-na <sup>d</sup>ziq-qur-<sup>Γ</sup>rat<sup>1</sup> 22.
- 23. 1 GADA kib-su šá UGU GIŠ.BANŠUR KÙ.GI šá <sup>d</sup>UTU
- 24. 1 GADA kib-su šá ÚR.MEŠ
- 25. 1 G[ADA kib-su] pi-tu-ú
- 26. 1 G[ADA a-na giš G]U<sup>?</sup>.ZA šá dA-a
- 27. P[AP x x] [x]

#### L. 5 bat is written over an erasure

The šahûs linen which were given to Şillā, the ašlāku. Month Ayaru, 9th day, 36th year of Nebuchadnezzar, king of Babylon.

1 new linen *hullānu*-cloak for Šamaš

3 new linen tunics for the cultic seat of Šamaš for the *tāluku*-processions?

1 new linen tunic for 1 kibsu-fabric for Šamaš

- [1] new linen hullānu-cloak for Bunene
- [1] new [line]n tunic for the Daughter of the Ebabbar
- [1] new [kib]su-fabric for Bunene
- [1] new [kibs]u-fabric for the Queen of Sippar
- [1] new [kibs]u-fabric for Gula
- [1] used [kibs]u-fabric [for Bunene]
- [1] us[ed *kibs*]*u*-fabric [for the Queen of Sippar]
- [1 linen tun]ic for co[ver for Šamaš]
- [1 linen tun]ic for cover for [Aya]
- [2 linen tun]ics for B]unene and the Queen of Sippar
- [1] used [linen] kibsu-fabric for Gula
- 1 linen kibsu-fabric for cultic seat of Marduk
- 1 linen kibsu-fabric for cultic socle of ziqqurat
- 1 linen *kibsu*-fabric for the golden table of Šamaš
- 1 linen kibsu-fabric for the sūnu-belts
- 1 open li[nen kibsu-fabric]
- 1 li[nen-garment for the cha]ir? of Aya, to[tal ....].

#### **325. Nbn 694** = BM 75531 Collated

 $5.5 \times 7.6$  cm

#### 5.2.[Nbn 13]

- 1. [GADA.MEŠ šá a]-<sup>r</sup>na<sup>1</sup> ta-be-e [šá ITI.GU<sub>4</sub>]
- 2.  $[U_4.x.KAM] MU. 13.KAM a-ranger [^{md}U+GUR-MU]$
- 3. [lúUŠ.BAR] SUM<sup>na</sup> ITI.GU<sub>4</sub> U<sub>4</sub>.<sup>r</sup>5<sup>1</sup>.[KAM MU.13.KAM dAG-I LUGAL E<sup>ki</sup>]

4. [1 GADA] ˈħu¹-ul-la-nu eš-šú 2 GADA sal-ḥu eš-[šú a-na dUTU]

- 5. 2 GADA sal-hi eš-šú a-na <sup>d</sup>A-a
- 6. 3 GADA sal-hi eš-šú a-na ta-lu-ka-tu<sub>4</sub>
- 7. 1<sup>en</sup> kib-su eš-šú BAD-ma a-na šub-tu<sub>4</sub> šá <sup>d</sup>A-a
- 8. 1 GADA sal-hi eš-šú a-na GADA <sup>r</sup>kib-su<sup>1</sup> a-na <sup>d</sup>UTU
- 9. 1 GADA sal-ḥi SUMUN a-na t[a\*-ḥap-šú a]-na <sup>d</sup>[UTU]
- 10. 1 GADA sal-[hi SUMUN a-na ta-ḥap-šú] a-na <sup>d</sup>[A-a]
- 11. 1 GADA sal-ḥi [SUMUN a-na] ta-ḥap-šú a-na dIm-[mir]-[tu4]
- 12. 1 GADA kib-su SUMUN a-na ta-ḥap-šú a-na dHAR
- 13. 1 GADA kib-su SUMUN a-na ta-ḥap-šú a-na <sup>d</sup>GAŠAN Sip-ar<sup>ki</sup>
- 14. 1 GADA kib-su SUMUN a-na ta-ḥap-šú a-na dA-nu-ni-tu4
- 15. 1 GADA kib-su SUMUN a-na ta-ḥap-šú a-na <sup>d</sup>Gu-la
- 16. 1 GADA kib-su eš-šú BAD a-na <sup>d</sup>ḤAR
- 17. 1 GADA kib-su eš-šú BAD a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 18. 1 GADA kib-su SUMUN a-na UGU šub-tu4 šá <sup>d</sup>A-nu-ni-tu4
- L.e. 19. 1 GADA *kib-su* SUMUN *a-na* <sup>d</sup>*Gu-la* 
  - 20. 1 GADA kib-su SUMUN a-na <sup>d</sup>[ziq]-qur-[rat]
- Rev. 21. 1 GADA *kib-su* SUMUN *a-na* É <sup>d</sup> AMAR UTU 17
  - 22. 1 GADA kib-su SUMUN a-na <sup>d</sup>IM
  - 23. 1 GADA kib-su SUMUN a-na <sup>d</sup>Ša-la
  - 24. PAP 23 GADA.MEŠ ina lìb-bi 7 GADA eš-šú
  - 25. 16 GADA SUMUN e-lat 1 GADA kib-su
  - 26. šá su-ni-e šá É <sup>d</sup>A-nu-ni-tu<sub>4</sub>
  - 27. 5 GADA.MEŠ te-nu-ú ku-ú GADA eš-šú
  - 28. 3 signs erased.
- L. 3. There is not enough space here to write the king's name, but the line might have been continued on the reverse, which, however, is damaged in the place where the king's name might have been written.
- L. 11. For reconstruction, cf. Cyr 185 (= 328): 10.
- L. 28. The similar damage can be observed in Nbk 312 (= 324): 27.

[Linen garments fo]r  $tab\hat{u}$ -procession [for the  $10^{th}$  day of Ayaru],  $13^{th}$  year, were given to [Nergal-iddin, the weaver]. Month Ayaru,  $5^{th}$  day, [ $13^{th}$  year of Nabonidus, king of Babylon]

-----

- [1 new linen] hullānu-cloak, 2 ne[w] linen tunics [for Šamaš]
- 2 new linen tunics for Aya
- 3 new linen tunics for the *tāluku*-processions
- 1 new open kibsu-fabric for cultic seat of Aya
- 1 new linen tunic for linen kibsu-fabric for Šamaš
- 1 used linen tunic for co[ver f]or Šamaš
- 1 [used] linen tu[nic for cover] for [Aya]
- 1 [used] linen tunic [for] cover for Immer[tu]
- 1 used linen *kibsu*-fabric for cover Bunene
- 1 used linen *kibsu*-fabric for cover for the Queen of Sippar
- 1 used linen kibsu-fabric for cover for Anunītu

1 used linen kibsu-fabric for cover for Gula

1 new open kibsu-fabric for Bunene

1 new open *kibsu*-fabric for the Queen of Sippar

1 used linen kibsu-fabric for the cultic seat of Anunītu

1 used linen kibsu-fabric for Gula

1 used linen kibsu-fabric for ziqqurat

1 used linen kibsu-fabric for chapel of Marduk!

1 used linen kibsu-fabric for Adad

1 used linen kibsu-fabric for Šala,

total 23 linen garments, including 7 new linen garments (and) 16 used linen garments; except for 1 linen kibsu-fabric for the sūnu-belt for the chapel of Anunītu, 5 linen garments, an exchange for new linen garments.

#### **326. Nbn 696** = BM 75541 Collated

 $5.6 \times 7.7$  cm

#### 9.2.Nbn 13

- 1. GADA.MEŠ *šá a-na ta-be-e šá* U[410<sup>?</sup>.KAM]
- 2. šá ITI.GU<sub>4</sub> šá MU.13.KAM a-na
- 3. <sup>md</sup>U+GUR-MU <sup>lú</sup>UŠ.BAR SUM<sup>in</sup>
- 4. ITI.GU<sub>4</sub> U<sub>4</sub>.9.KAM MU.13.KAM <sup>d</sup>AG-I LUGAL NUN<sup>ki</sup>
- 5. 1 GADA hu-la-nu eš-šú 2 sal-hi eš-šú a<sup>!</sup>-<na> <sup>d</sup>UTU 6. 2 GADA sal-hi eš-šú <a-na> <sup>d</sup>A-a
- 7. 3 GADA sal-hi  $\lceil e\check{s} \rceil \langle \check{s}\acute{u} \rangle$  a-na ta-al-lu-ka-tu<sub>4</sub>
- 8. 1 kib-su eš-šú BAD-ma a-na šub-tu<sub>4</sub> šá <sup>d</sup>A-a
- 9. 1 <GADA> sal-ḥi eš-šú a-na kib-su a-na <sup>d</sup>UTU
- 10. 1 <GADA> sal-ḫi SUMUN a-na ta-ḫap-šú a-na <sup>d</sup>UTU
- 11. 1\* <GADA> sal\*-hi\* SUMUN\* a\*-na\* ta\*-hap\*-šú\* a\*-na\*  $d^*A^*-a^*$
- 12. 1 <GADA> sal-hi SUMUN a-na ta-hap-šú a-na <sup>d</sup>Im-mir-tú
- 13. 1 <GADA> kib-su SUMUN a-na ta-hap-šú a-na <sup>a</sup>HAR
- 14. 1 <GADA> kib-su SUMUN a-na ta-ḥap-šú
- a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 16. 1 <GADA> kib-su SUMUN a-na ta-hap-šú
- a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub>

18. 1 < GADA> kib-su SUMUN a-na ta-hap-su a-na d Gu1-[la]Rev.

- 19. 1 <GADA> kib-su eš-šú {1} BAD (over er.) a-na dHAR
- 20. 1 <GADA> kib-su eš-šú e-lat 1<sup>en</sup> ina IGI <sup>lú</sup>TU.É
- a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> 21.
- 22. <1 GADA kib-su SUMUN ana UGU šub-tu> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> ina IGI <sup>lú</sup>TU.É
- 23. 1 <GADA> kib-su SUMUN a-na <sup>d</sup>Gu-la
- 24. 1 <GADA> kib-su SUMUN a-na <sup>d</sup>ziq-qur-ra-tu<sub>4</sub> 25. 1 <GADA> kib-su SUMUN a-na É <sup>d</sup>AMAR.UTU

- 26. 1 <GADA> kib-su SUMUN a-na dIM
- 27. 1 <GADA> kib-su SUMUN a-na dŠa-la
- 28. PAP 20 GADA.<MEŠ> ina lìb-bi 7 GADA sal-hi <eš-šú>
- 29. 13 <GADA> kib-su

-----

- 30. 2 <GADA> kib-su  $e\check{s}$ - $\check{s}\check{u}$  ina  $\check{S}U^{ii}$   ${}^{md}\check{H}AR$ - $D\grave{U}$
- 31. 1 GADA sal-ḥi šá bat-qa ina IGI <sup>md</sup>ḤAR-ši-man-ni
- 32. a-na <GADA> kib-su a-na <sup>d</sup>UTU SUM<sup>in</sup>
- 33. 1 ÚR *pu-uš-ku* 5 *kib-*<sup>г</sup>*su*<sup>1</sup>
- 34. ina IGI <sup>md</sup>ḤAR-ši-ma[n-ni]
- L. 5. *hu-la-nu*, not *hu-ul-la-nu*, like in Strassmaier's copy. The sign *a* looks like numeral 2. L. 11 is missing in Strassmaier's copy.

Linen garments for procession for the [10<sup>th</sup> day] of Ayaru, 13<sup>th</sup> day, were given to Nergal-iddin, the weaver. Month Ayaru, 9<sup>th</sup> day, 13<sup>th</sup> year of Nabonidus, king of Babylon

\_\_\_\_\_

- 1 new linen *hullānu*-cloak, 2 new linen tunics for! Šamaš
- 2 new linen tunics <for> Aya
- 3 new linen tunics for the *tāluku*-processions?
- 1 new open kibsu-fabric for cultic seat of Aya
- 1 new linen> tunic for the kibsu-fabric for Šamaš
- 1 used linen> tunic for cover for Šamaš
- 1 used linen> tunic for cover for Aya
- 1 used linen> tunic for cover for Immertu
- 1 used linen> kibsu-fabric for cover Bunene
- 1 used linen> kibsu-fabric for cover for the Queen of Sippar
- 1 used linen> kibsu-fabric for cover for Anunītu
- 1 used linen> kibsu-fabric for cover for Gu[la]
- 1 new linen open *kibsu*-fabric for Bunene
- 1 new linen> kibsu-fabric, except for 1 (which is) at disposal of the  $\bar{e}rib$   $b\bar{t}ii$  for the Queen of Sippar
- <1 used linen kibsu-fabric for the cultic seat > of Anunītu, (which is) at disposal of the  $\bar{e}rib$   $b\bar{t}ti$
- 1 used linen> kibsu-fabric for Gula
- 1 used linen> kibsu-fabric for ziqqurat
- 1 used linen> kibsu-fabric for chapel of Marduk
- 1 used linen> kibsu-fabric for Adad
- 1 used sibsu-fabric for Šala,
- total 20 linen cloths, including 7 <new> linen cloths (and) 13 <used linen> kibsu-fabrics

\_\_\_\_\_

- 2 new < linen> kibsu-fabrics from the hands of Bunene-ibni
- 1 linen tunic for repair at disposal Bunene-šimanni for sinen> kibsu-fabric for Šamaš was given.
- 1 sūnu-belt of 1/8 width, 5 kibsu-fabrics (are) at disposal of Bunene-šiman[ni].

Rev.

```
327. BM 75848 (83-1-18, 1203) = Str. II 176/3 Collated 5.1 \times 7.5 cm
```

```
Nbn
```

```
1. GADA.MEŠ [šá a-na ta-be-e šá U<sub>4</sub>.x.KAM]
  2. šá I[TI.x a-na PN]
 3. lúTÚG.BA[BBAR SUM<sup>in</sup> ITI.x U<sub>4</sub>.x.KAM MU.x.KAM]
  4. mdAG-IM.[TUKU LUGAL TIN.TIR<sup>ki</sup>]
  5. 1 hu-la-^{\Gamma}nu^{\Gamma}e[\check{s}^{!}-\check{s}\check{u}\ a-na\ ^{d}UTU]
  6. 1 sal-hi \langle e\check{s}-\check{s}\acute{u}\rangle a-na [^{\mathrm{d}}UTU]
  _____
  7. 1 sal-hi \langle e\check{s}-\check{s}\acute{u}\rangle a-na kib-su [a-na <sup>d</sup>UTU]
  8. 3 sal-ḫi <sup>meš</sup> eš-šu-tu <sup>r</sup>a<sup>1</sup>-[na ta-lu-ka-tu<sub>4</sub>]
  9. 1 sal-hi eš-šú i-na <sup>r</sup>x x x<sup>1</sup> <sup>d</sup>A-a
  ______
10. 1 sal-ḥi la-bi-ri a-na ta-ḥap-šú a-na <sup>d</sup>UTU
11. 1 sal-hi SUMUN a-na ta-hap-šú a-na <sup>d</sup>A-a
12. 1 sal-hi SUMUN a-na ta-hap-šú a-na <sup>d</sup>Im-mir-tú
13. 1 kib-su eš-šú a-na <sup>d</sup>ḤAR
14. 1 kib-su eš-šú a-na [<sup>d</sup>GAŠAN] Sip-par<sup>ki</sup>
15. 「3*1 sal-hi<sup>meš</sup> eš-šu-tu a-na <sup>d</sup>DUMŪ.MÍ.MEŠ* É-babbar*-<ra>š
16. 1 sal-hi eš-šú a-na <sup>d</sup>Gu-la
17. 1 sal-ḥi eš-šú a-na <sup>d</sup>ḤAR
18. 2 kib-su<sup>meš</sup> < e\check{s}-\check{s}u-tu> a-na* \acute{\mathsf{U}}\mathsf{R}.\mathsf{ME}\check{\mathsf{S}}
19. šá la*-IGI <sup>lú</sup>TÚG.KAL*.KAL* na-šá-a'
20. 1 kib-su SUMUN a-na ta-hap-ti* a-na <sup>d</sup>HAR
21. 1 kib-su SUMUN a-na ta-ḥap-šú a-「na<sup>¬</sup>
                     dGAŠAN Sip-parki
23. 1 <sup>r</sup>kib¹-su SUMUN a-na ta-ḥap-šú
                   \lceil a \rceil - na \stackrel{d}{A} - nu - ni - tu_4
25. 1 kib-su SUMUN a-na ta-<hap*>-šú a-<sup>r</sup>na<sup>1</sup>
26. <sup>d</sup>Gu-la
```

Free space for ca. 4 lines

27. PAP\* 23\* GADA\*.[MEŠ\* *i\*-na\* lìb\*-bi\** 16\* GADA\* *eš\*-šú\** 7\*GADA\* SUMUN\*]

In light of l. 27 all the items were manufactured from linen (GADA). I resigned from adding <GADA > in the transliteration, but I added it in translation.

L. 5. The partly preserved sign looks like 1+ši, but the emendation is justified by the similarity with other texts of this group.

- L. 9. Unrecognisable remains of 3 or 4 signs; according to parallel texts we expect here 1 sal-hi eš-šú  $a^{i}$ -na  $g^{ii}$ šub- $tu_4$  šá  $^{d}$ A-a. Ll. 13–14. In the parallel text  $lab\bar{\imath}ri$  (SUMUN) is followed with ta-hap-šú.
- L. 15. At the beginning of line only two vertical strokes are preserved, however the reading 3 is justified by parallel texts. In Strassmaier's copy MEŠ and ra in this line are missing.
- L. 25. Strassmaier's copy suggest the remains of a sign between ta and šú, but is not space for any sign there.
- L. 27 is missing in Strassmaier's copy. The numeral 23 means that all the items were counted (contrary to Nbn 694 (= 325) and 696 (= 326)). Because 7 items are described as old or used, all the others must be new ones, i.e. also these mentioned in lines 6, 7 and 18.

Linen garments [for procession for the nth day, nth month, were given to PN], the

```
ašl[āku. Month x, n<sup>th</sup> day, n<sup>th</sup> year of] Naboni[dus, king of Babylon]
1 n[ew<sup>!</sup>] hullānu-cloak for Šamaš]
1 <new> tunic for [Šamaš]
1 <new> tunic for kibsu-fabric [for Šamaš]
3 new en> tunics fo[r tāluku]-processions?
1 new tunic for [cultic seat] of Aya
1 used linen> tunic for cover for Šamaš
1 used linen> tunic for cover for Aya
1 used linen> tunic for cover for Immertu
1 new kibsu-fabric for Bunene
1 new kibsu-fabric for [the Queen of] Sippar
3 new < linen> tunics for the Daughters of the Ebabbar
1 new linen> tunic for Gula
1 new linen> tunic for Bunene
2 < new linen> kibsu-fabrics for sūnu-belts, which are withdrawn from the menders
1 used linen> kibsu-fabric for cover for Bunene
1 used linen> kibsu-fabric for cover for the Queen of Sippar
1 used linen> kibsu-fabric for cover for Anunītu
1 used linen> kibsu-fabric for cover for Gula
Total 23 linen cloths, [including 16 new cloths and 7 used cloths].
```

**328.** Cyr **185** = BM 60488; cf. NUVI 3, No. 114; Giovinazzo 1981,

No. 6. Collated  $6.1 \times 8.1$  cm

[x.x].4

- 1. [GADA.MEŠ šá U<sub>4</sub>.x.KAM šá ITI.x a-na]
- 2. 「ta¹\*-[be-e šá <sup>d</sup>UTU a-na PN SUM<sup>na</sup> ITI.x U<sub>4</sub>.x.KAM]
- 3. MU.4.KAM [KN LUGAL Bābili (LUGAL KUR.KUR)]

```
4. 1 GADA [sal-ḥi eš]-šú a-na [dUTU 5. 1 GADA sal-ḥi eš-šú a-na dA-[a]
```

- 6. 1 kib-su eš-šú a-na <sup>d</sup>UTU
- 7. 3 GADA kib-su  $e\check{s}$ - $\check{s}\check{u}$  a-na ta- $lu^*$ - $\lceil ka^{\dagger} \lceil a \rceil \lceil -tu_4 \rceil$
- 8. 1 GADA sal-ḥu la-bi-ri a-na ta-ḥap-šú a-na <sup>d</sup>UTU
- 9. 1 GADA sal-ḫu la-bi-ri a-na ta-ḫap-šú a-na <sup>d</sup>A-a
- 10. 1 GADA sal-ḥu la-bi-ri a-na <ta-ḥap-šú> a-na <sup>d</sup>Im-mir-tu<sub>4</sub>
- 11. 1 GADA kib-su eš-šú a-na <sup>d</sup>DUMU.MÍ.<MEŠ> É-babbar-ra
- 12. 2 GADA *kib-su la-bi-ri a-na* <sup>d</sup>AMAR.UTU *u* <sup>d</sup> GAŠAN-*ja* 13. 1 GADA *kib-su la-bi-ri a-na* <sup>d</sup>ziq-qur-rat
- 14. 1 GADA kib-su eš-šú 1<sup>en</sup> kib-su la-bi-ri
- 15. [PAP] <sup>[2]</sup> GADA<sup>[]</sup> a-na <sup>d</sup>Bu-ne-ne
- 16. [1 kib-su] pe-tu-ú a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 17. [1 kib-su] eš-šú 1 kib-su la-bi-ri
- 18.  $[PAP^{?} 2^{?} GADA^{?} a]$ - $[na]^{d} GAŠAN UD.KIB.NUN^{ki}$

19. [1 GADA kib-su SUMUN] 「a¹-na dA-nu-ni-tu4 Edge

20. [1 GADA kib-su SUMUN a-n]a <sup>d</sup>Gu-la Rev.

- 21. [1 GADA kib-su SUMUN a]-na <sup>d</sup>IM
- 22. [1 GADA kib-su la-bi]-<sup>r</sup>ri<sup>1\*</sup> a-na <sup>d</sup>Ša-la
- 23. [1 GADA] kib-su a-na ta-hap-šú a-na <sup>d</sup>Bu-ne-ne
- 24. [1 GADA ki]b-su a-na ta-ḥap-šú a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 25. [1 GAD]A kib-su a-na ta-ḫap-šú a-na dA-nu-ni-tu4
- 26. 1 GADA kib-<sup>r</sup>su<sup>1</sup> a-na ta-ḥap-šú a-na <sup>d</sup>Gu-la
- 27. PAP 26 GADA. MEŠ a-na md uTU-NUMUN-GÁL ši
- 28. <sup>rlú</sup>¹TÚG. FBABBAR¹ SUM<sup>in</sup>

Note that the first line of the list of clothes is missing: 1 GADA *hu-la-nu eš-šu a-na* <sup>a</sup>UTU. L. 6. 1 kib-su eš-šú stands for 1 <GADA sal-hu a-na> kib-su a-na dUTU, cf. CT 55, 814 (= 329): 8; Nbn 694 (= 325): 8; Nbn 696 (= 326): 9 and others.

- L. 7. Here for the tāluku-processions 3 kibsu-fabrics, and not as usually not salhu tunics were used, or it is a scribe's error.
- L. 10. The omitted  $\langle lab\bar{i}ri \rangle$  is added by comparison with other texts, cf. Nbn 694 (= 325): 11, Nbn 696 (= 326): 12 and others.
- L. 12 ff. Note that the group kibsu labīri precedes here the group kibsu labīri ana taḥapšu, while in other texts the sequence is opposite.
- L. 16 is unparalleled.
- L. 19. The comparison with other texts shows that <SUMUN> is missing here.
- Ll. 23-26. Here, just like in BM 66166 (= 333), the kibsu < labīri> ana taḥapšu takes the last position in the texts while in other texts the sequence is opposite.
- L. 27. The total 26 kitê means that all items except for hullānu were counted here.

[The linen cloths for  $n^{th}$  day,  $n^{th}$  month for]  $ta[b\hat{u}$ -procession of Šamaš. were given to PN. Month x,  $n^{th}$  day],  $4^{th}$  year [of KN, king of Babylon, (king of Lands).

<sup>1</sup> ne[w] linen [tunic] for [Šamaš]

<sup>1</sup> new linen tunic for Ay[a]

<sup>1</sup> new kibsu-fabric for Šamaš

```
3 new linen kibsu-fabrics for the [tāluku]-processions]
1 used linen tunic for cover for Šamaš
```

1 used linen tunic for cover for Aya

1 used linen tunic for <cover> for Immertu

1 new linen kibsu-fabric for the Daughters of the Ebabbar

2 used linen kibsu-fabric for Marduk and Bēltiya

1 used linen kibsu-fabric for ziqqurat 1 new linen kibsu-fabric, 1 used kibsu-fabric,

total 2 linen cloths for Bunene

[1] open [kibsu-fabric] for the Queen of Sippar

1 new [kibsu]-fabric, 1 used kibsu-fabric,

[total 2 linen cloths f]or the Queen of Sippar

[1 used linen kibsu-fabric] for Anunītu

[1 used linen kibsu-fabric fo]r Gula

[1 used linen kibsu-fabric fo]r Adad

[1 use]d [linen kibsu-fabric] for Šala

[1 linen] kibsu-fabric for cover for Bunene

[1 linen ki]bsu-fabric for cover for the Queen of Sippar

[1 lin]en kibsu-fabric for cover for Anunītu

1 linen kibsu-fabric for cover for Gula.

total 26 linen cloths given to Šamaš-zēr-ušabši, the ašlāku.

# **329. CT 55, 814** = BM 57447 Collated

 $6.2 \times 8.8$  cm

#### 8.2.Nbn [x]

- 1. [GADA.MEŠ šá U<sub>4</sub>].11.KAM 「šá¹ [IT]I.GU<sub>4</sub>\* a-na
- 2. [ta-be-e] 「šá¹ dUTU SUM<sup>na</sup> ITI.GU<sub>4</sub> U<sub>4</sub>.8.KAM
- 3. [MU.x.KAM] <sup>md</sup>AG-I LUGAL TIN.TIR<sup>ki</sup>

- 4. [1 GADA sal-h]ušá UGU  $^{\rm giš} \check{s}u-ub-tu_4$ šá  $^{\rm d}{\rm UTU}$
- 5. [1 GADA sa]l-hu a-na ta-hap-šú a-na <sup>d</sup>UTU
- 6. [1 GADA sal]-hu šá UGU <sup>giš</sup>šu-ub-tu<sub>4</sub> šá <sup>d</sup>A-a
- 7. 1 GA[DA sal-h]u a-na ta-hap-šú a-na <sup>d</sup>A-a
- 8. 1 GADA sal-hu a-na kib-su a-na <sup>d</sup>UTU eš-šú
- 9. 3 GADA sal-hu a-na ta-lu-uk-ka-tu4 a-na <sup>d</sup>UTU <sup>[e</sup>š-šú]
- 10. 1 GADA a-na ta-ḥap-「šú¬ a-na dBu-ne-ne
- 11. 1 GADA *a-na ta-ḥap-šú* <sup>Γ</sup>*a-na*<sup>1 d</sup>Nin-ŠA
- 12. 2 GADA kib-su šá ÚGU <sup>giš</sup>šu-ub-tu<sub>4</sub> a-na
- <sup>d</sup>AMAR.UTU u <sup>d</sup>GAŠAN-ja eš-šú
- 14. 1 GADA *kib-su ziq-qur-ra-tu*<sub>4</sub> *eš-šú* 15. 1 GADA *kib-su* <sup>d</sup>DUMU.MÍ.MEŠ *É-babbar-ra eš-šú*
- 16. 1 GADA kib-su a-na <sup>d</sup>Bu-ne-ne eš-šú
- 17. 1 GADA kib-su a-na <sup>d</sup>Nin-ŠA eš-šú

18. 1 GADA kib-su a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub> eš-šú

19. 1 GADA *kib-su a-na* <sup>d</sup>IM *u* <sup>d</sup>Š*a-la eš-šú* 

20. PAP 10 GADA 「sal-hu¹ ina lìb-bi 4 eš-šú Rev.

21. PAP 10 GADA kib-su eš-šú

22. 1 GADA a-na ta-ḥap-šú a-na <<sup>d</sup>>Im-mir- tu<sub>4</sub>

23. 1 GADA sal-hi eš-šú a-na <sup>d</sup>UTU u <sup>d</sup>A-a

24. 1 GADA hu-ul-la-nu eš-šú a-na <sup>d</sup>UTU

25. 1 GADA hu-ul-la-nu eš-šú a-na <sup>d</sup>Bu-ne-ne

26. 2 GADA sal-hi eš-šú a-na <sup>d</sup>Gu-la

27. 「PAP<sup>1</sup> 27 GADA *a-na zi-ku-tu* 28. [*a-n*]a <sup>md</sup>UTU-NUMUN-GÁL<sup>ši</sup> SUM<sup>in</sup> {*na*}

29. [1 GADA *kib*]-*su šá* <sup>d</sup>UTU

30. [1 GADA kib]-su šá <sup>d</sup>IM re-hi

The name of person responsible for the items for  $tab\hat{u}$  -procession appears not in the heading, but in 1. 28.

L. 30. re-hi, might be translated "outstanding obligation", or similar.

Interpretation of this text and the total given in lines 20-21 is far from clear because in a few of the lines precise information is missing, e. g. in ll. 6-7 the quality of salhu (new or old) and in ll. 10-11 the quality and the category of items are omitted. Additionally, contrary to the total given in lines 20-21, earlier only 18 items are enumerated. If the number of 4 new salhus in 1. 20 is accurate, in 1. 5 and 7 salhu <labīri> had to be counted. It should be stressed that ll. 22-24 are placed in other texts of this group always after the heading, i.e. after 1. 3, which would give the total of 10 salhus mentioned in 1. 20, however, the new total would be five, not four. Additionally, the comparison of lines 10-11 with Nbn 694 (= 325): 9-11, Nbn 696 (= 326): 10-12; Cyr 185 (= 326): 8-10) and BM 66166 (= 333): 4–5 seems to speak for < salhi labīri>, i.e. the total of 10 salhus in 1. 20 would be accurate (without counting the data from ll. 22–24), however, 2 kibsus would be missing. In parallel texts [sal]ħu <labīri> (l. 7) is followed with salħu labīri for Bunene or for Immertu. Possibly the scribe forgot to write the line and added it later as 1. 22. Because of the disorder and lack of much important information the interpretation of the data is far from clear.

L. 23. In parallel texts there are two new salhus for Šamaš and two for Aya (normally placed just after the heading).

L. 27. The total of garments as reconstructed gives 26, not 27. We can reach 27 items if we reconstruct the numeral in 1. 4 as [2] (just as in many other texts), or if we accept the possibility that in l. 23 one new salhu for each god is mentioned and that the data from ll. 29-30 were included in the total of 27 in l. 27.

L. 28. Of the *na* only the vertical stroke is preserved.

[Linen cloths for]  $11^{th}$  [day] of the [mont]h Ayaru given for [ $tab\hat{u}$ -procession] of Šamaš. Month Ayaru,  $8^{th}$  day, [ $n^{th}$  year] of Nabonidus, king of Babylon are given.

- [1 linen tuni]c for the cultic seat of Šamaš
- [1 linen tu]nic for cover for Šamaš
- [1 linen tun]ic for the cultic seat of Aya
- 1 linen tunic for *kibsu*-fabric for Šamaš, new
- 3 linen tunics for the *tāluku*-processions for Šamaš, new
- 1 linen garment for cover for Bunene

```
1 linen garment for cover for Nin-ŠA
2 linen kibsu-fabrics for the cultic seat(s) of Marduk and for Bēltiya, new
1 linen kibsu-fabric <for> ziqqurat, new
1 linen kibsu-fabric (for) the Daughters of the Ebabbar, new
1 linen kibsu-fabric for Bunene, new
1 linen kibsu-fabric for Nin-ŠA, new
1 linen kibsu-fabric for Anunītu, new
1 linen kibsu-fabric for Adad and Šala, new,
total 10 linen tunics, including 4 new,
total 10 new linen kibsu-fabrics
1 linen garment for cover for Immertu
1 new linen tunic for Šamaš and Aya
1 new linen hullānu-cloak for Šamaš
1 new linen hullānu-cloak for Bunene
2 new linen tunics for Gula,
total 27 linen cloths were given for cleaning [t]o Šamaš-zēr-ušabši.
[1 linen kib]su-fabric for Šamaš
[1 linen kib]su-fabric for Adad, the remnants.
330. CT 55, 813 = BM 57911
3.3 \times 5.0 cm
                     11.1.[x]
           1'. ITI.BÁR U<sub>4</sub>.「11¹.[KAM ....]
           2'. 3 GADA sal-hi [eš-šú ....]
           3'. 3 GADA sal-hi [....]
           4'. 2 GADA kib-su [....]
           5'. 2 GADA sal-hi [....]
           6'. 1 GADA sal-hi šá [....]
           7'. 1 GADA sal-hi šá [....]
           8'. 1 GADA sal-ḥi [....]
           9'. 1 GADA s[al-hi ....]
Edge
          10'. 1 GADA s[al-hi ....]
Rev.
          11'. 1 GADA [sal<sup>?</sup>]-hi ....]
          12'. 2 GADA sa[l-hi ....]
          13'. PAP 10 sal-[hi ....]
          14'. PAP.PAP 19* [....]
```

[....] Month Nisannu, 11<sup>th</sup> day [....]

3 [new] linen tunics [....]
3 linen tunics [....]
2 linen *kibsu*-fabrics [....]
2 linen tunics [....]
1 linen tunics for [....]
1 linen tunics for [....]

```
1 linen tunic [....]
1 linen t[unic ....]
1 linen t[unic ....]
1 linen [tunic] [....]
2 linen tu[nics ....],
grand total 19 [linen cloths ....].
331. BM 68263 (82-9-18, 9261)
4.2 \times 4.3 \text{ cm}
              1. [x] GADA sal-hu a-na ta-[....]
              2. 1 GADA sal-ḫu a-na <sup>d</sup>[GAŠAN]
                       šá UD.KIB.NUN<sup>ki</sup> [....]
              4. 1 kib-su a-na ta-hap-[šú ....]
              5. 1 kib-su a-na ta-ḥap-Γšú<sup>¬</sup> [....]
              6. 1 kib-su a-na ta-ḥap-[šú ....]
              7. 1 kib-su [....]
Rest lost
              1'. [....] \lceil sal^{\dagger} - hu \ a - \lceil na^{\dagger} \rceil [....]
Rev.
              2'. 1 GADA sal-hu a-na [....]
              3'. 1 GADA sal-hu a-na [....]
              4'. a-na <sup>d</sup>[....]
[x] linen tunic for co[ver ....]
1 linen tunic for [the Queen] of Sippar [....]
1 kibsu-fabric for cove[r ....]
1 kibsu-fabric for cove[r ....]
1 kibsu-fabric for cove[r ....]
1 kibsu-fabric [for cover ....]
[x linen] tunic for [....]
1 linen tunic for [....]
1 linen tunic for [....] for [....].
332. BM 83659 (83-1-21, 822)
                                                                                          PLATE 73
5.6 \times 4.2 cm
                          8.2<sup>?</sup>.Cam 2
              1. GADA šá <sup>r</sup>ta-bi<sup>1</sup>-e šá <sup>d</sup>UTU šá U<sub>4</sub>.x+<sup>r</sup>11.KAM<sup>1</sup>.
              2. MU.2.KAM [^{m}Kam]-^{r}bu-zi^{1}-ja [LUGAL TIN.T]IR^{ki}
              3. LUGAL KU[R.KUR SUM<sup>na</sup> IT]I.G[U<sub>4</sub> U<sub>4</sub>].8.KAM
                 M[U.2.KAM]
```

```
4. 1 GADA hu-la-nu [eš-šú] [2 GADA] sal-hu eš-[šú] [a-na dUTU]
5. 2 GADA sal-hu eš-\lceil \check{s}\check{u} \rceil \lceil a-n \rceil a^d A - \lceil a \rceil
6. [x GADA s]al-hu eš-šú a-na <sup>d</sup>DUMU.MÍ.<MEŠ> É-[babbar-ra]
7. [x \times x \times x^{\lceil \check{s}\check{u}^{?} \rceil}] 1 \text{ GADA } \underline{hu}-la-nu e[\check{s}-\check{s}\check{u}]
                                                 \lceil hu - la \rceil - nu \lceil ... \rceil
```

Rev.

3'. 1 GADA sal-ḥu te-nu-ú šá ina IGI <sup>d</sup>U[TU<sup>?</sup>-....]

4'. a-na kib-su na-di

Linen garments for tabû-procession of Šamaš for [x]+11th day, 2nd year [of Cam]byses, king of [Ba]bylon, king of Lands are given.[Mon]th A[yaru], 8<sup>th</sup> day, [2<sup>nd</sup> ye]ar.

1 new linen *hullānu*-cloak

[2] new [linen] tunic [for Šamaš]

2 new linen tunics for Aya

[x] new [lin]en tunic for the Daughters of the E[babbar]

[....], 1 n[ew] linen hullānu-cloak [....]

[.... hul]lānu-cloak [....]

[x salhu]-tunic(s), 8 linen [... at disposal? of PN], the ašlāku.

1 linen salhu (for) the change which at disposal of Ša[maš- ....] for kibsu-fabric was deposited.

## **333. BM 66166** (82-9-18, 82-9-18, 6157)

 $3.3 \times 6.7$  cm

1'. [1 GADA sal-hu eš-šú a-na]  $\lceil dA \rceil$ -a Obv.

2'. [1 GADA sal-hu eš-šú a-na kib-su a]-na <sup>d</sup>UTU

3'. [3 GADA sal-hu eš-š]ú 「a-na¬ ta-la-lu-ka-a-tu<sub>4</sub>

4'. [1 GADA sal-ḥu la]-bir-ri a-na ta-ḥap-šú a-na <sup>d</sup>UTU

5'. [1 GADA sal-ḥu la]-bir-ri a-na ta-ḥap-šú a-na <sup>d</sup>A-a

6'. [1 GADA sal-ḫu la]-bir-ri 「a¹-na dIm-mir-tu4

7'. [x GADA kib-su] eš-šú a-na <sup>d</sup>DUMU.MÍ.<MEŠ> É-babbar-ra

8'. [2 GADA *kib-su la-b*]*ir-ri a-na* <sup>d</sup>AMAR.UTU *u* <sup>d</sup>GAŠAN-*ja* 9'. [1 GADA *kib-su la-b*]*ir-ri a-na* <sup>d</sup>*ziq-qur-ra-tu*<sub>4</sub>

10'. [1 GADA kib-su] eš-šú 1<sup>en</sup> GADA kib-su la-bir-ri

11'. [PAP 2 GADA a]-na <sup>d</sup>Bu-ne-ne

12'. [1 kib-su pe-tu-ú] a-na dGAŠAN Sip-parki

13'. [1 kib-su eš-šú 1 kib-su la]-bir-ri

14'. [PAP<sup>?</sup> 2<sup>?</sup> GADA<sup>?</sup> a-na <sup>d</sup>GAŠAN Sip-par]<sup>rki</sup>

1'. [1 GADA kib-su SUMUN a-na  ${}^{d}G$ ] $u^{?}$ -la Rev.

2'. [1 GADA kib-su SUMUN a]-na <sup>d</sup>IM

3'. [1 GADA kib-su la-bir]-<sup>[</sup>ri<sup>]</sup> a-na <sup>d</sup>Ša-la

The heading and two lines concerning *salhus* and *hullānu* for Šamaš (and maybe *hullānu* for Bunune) are missing.

L. 6'. In the line it lacks  $\langle ta-hap-\check{s}\acute{u}\rangle$ .

[1 linen kibs]u-fabric for ditto for Anunītu

15'. [....]  $[x] GADA^{?}_{1}[x] [x^{e?}_{1}]$ 

The gaps in obv. 12'-14' and in rev. 1'-7' are reconstructed on the basis of Cyr 185 (= 326).

In rev. 6' and 8' at the very beginning of lines only one vertical stroke is preserved. Note that in this text the *kibsu labīri ana taḥapšu* (rev. 4'-7') are enumerated after the *kibsu labīri* (obv. 8'- rev. 3'). A similar order occurs in Cyr 185 (= 326), while in other texts the sequence is opposite.

Obv. 14' was followed with one line or rev. 1' was preceded with one line concerning the *kibsu labīri* for Anunītu.

```
[1 new linen tunic for] Aya
[1 new linen tunic for kibsu-fabric f]or Šamaš
[3 ne]w [linen tunics] for the 'tāluku'-processions'
[1 us]ed [linen tunic] for cover for Šamaš
[1 us]ed [linen tunic] for cover for Aya
[1 us]ed [linen tunic] for <cover> for Immertu
[x] new [linen kibsu-fabric] for the Daughters of the Ebabbar
[2 us]ed [linen kibsu-fabrics] for Marduk and Bēltiya
[1 us]ed [linen kibsu-fabric] for ziggurat
[1] new [linen kibsu-fabric], 1 used kibsu-fabric,
[total 2 linen cloths fo]r Bunene
[1 open kibsu-fabric] for the Queen of Sippar
[1 new kibsu-fabric, 1 us]ed [kibsu-fabric, total 2 linen cloths for the Queen of
Sippar]
[1 used linen kibsu-fabric for G]ula
[1 used linen kibsu-fabric f]or Adad
[1 us]ed [linen kibsu-fabric] for Šala
[1 linen kibsu-fabric] for cover for Bunene
[1 linen kibsu-fabric] for ditto for the Queen of Sippar
```

```
1 linen kibsu-fabric] for ditto for Gula.
[Total x lin]en cloths for Šamaš-zēr-ušabši was given.
[x] new [line]n tunic
[x] new [linen tuni]c
[x] new [tun]ic(s) for linen baldachim [fo]r Šamaš
[x new tunic(s) for] linen baldachim for Aya
[....] linen<sup>?</sup> [....].
334. BM 63250 (82-9-18, 82-9-18, 3219)
                                                                                    PLATE 73
4.5 \times 3.1 \text{ cm}
             1'. [1 GADA sal-hi] [eš-šú] šá <sup>d</sup>A-a
             2'. 1+[2 GADA sal-hu eš-šú a-na ta-lu]-ka-a-tu<sub>4</sub> <šá> <sup>d</sup>U[TU]
             3'. [3<sup>?</sup>] [....] na ÚR pu-uš-ku [x<sup>?</sup>]
             4'. [x x] sal-ḥi a-ri-du [x][....]
             5'. 1 kib-su la-bir-< ri> <math>\check{s}\acute{a} {}^dH[AR^? ....]
L.e.
             6'. 1 kib-su eš-šu 1 kib-su SU[MUN ....]
             7'. 1 kib-su eš-šú 1 kib-su SU[MUN PAP 2 GADA.MEŠ]
Rev.
             8'. šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> ina lìb-bi eš-<sup>[</sup>šú<sup>1</sup> [....]
             9'. 2 kib-su šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> ina l[ìb-bi ....]
            10'. [x] kib-su eš-šú ina É <sup>d</sup>[DN]
            11'. [x ki]b-su šá <sup>d</sup>ME.ME 1 kib-s[u ....]
           12'. [1 GADA kib-s]u <sup>d</sup> [DN¹ [....]
           13'. 1 GADA [x][....]
L. h.e.
            14'. 1 [kib-su] [....]
L. 4' the du at the very end is written over erasure
[1] new [linen tunic] for Aya
[3 new linen tunics for the t\bar{a}l]uku-processions? <for> Š[amaš]
[x][...] sūnu-belt of 1/8 cubit width
[x] a droop tunic [....]
1 used kibsu-fabric for Bu[nene?]
1 new kibsu-fabric, 1 us[ed] kibsu-fabric [for ....]
1 new kibsu-fabric, 1 us[ed] kibsu-fabric, [total 2 linen cloths] for the Queen of
Sippar, including new [....]
2 kibsu-fabrics for Anunītu in[cluding? ....]
[x] new kibsu-fabric(s) for the temple of) [DN]
[1<sup>?</sup>] kibsu-fabric for Gula, 1 kibsu-fabric [for ....]
[1 linen kib]su-fabric (for) [DN]
1 linen [....]
1 kibsu-fabric [....]
```

#### 335. BM 68857 (82-9-18, 8856)

 $5.6 \times 5.7$  cm

```
1'. [....] \lceil hu^2 - ul^{2} \rceil [....]
```

2'. [x GAD]A sal-hu eš-šú a-na <sup>d</sup>UTU

3'. 1 GADA sal-hu ta-hap-šú a-na <sup>d</sup>UTU

4'. 1 GADA sal-hu ta-hap-šú a-na <sup>d</sup>A-<sup>r</sup>a<sup>1</sup>

5'. 1 GADA sal-hu ta-hap-šú a-na <sup>d</sup>Im-mir-tu<sub>4</sub>

6'. [x] GADA sal-hu ta-hap-šú a-na <sup>d</sup>HAR

7'. 1 GADA *kib-su ta-ḥap-šú a-na* <sup>d</sup>GAŠAN UD.[KIB.NUN]<sup>ki</sup> 8'. 1 GADA *kib-su ta-ḥap-šú a-na* <sup>d</sup>GDN<sup>1</sup>

9'. 1 GADA kib-su ta-ḥap-šú 「a-na¹ [....]

10'. 1  $\lceil GADA \rceil$  sal-hu a-na šub-t $\lceil u_4 \ldots \rceil$ 

11'. [x GADA sal]- $\lceil hu^? a \rceil$ -[na ....]

Rev.

11 . [x GADA sai]- yu u'-[nu ....] 12'. [2] GADA kib-su a-na d[x] [(x)] 13'. 2 GADA sal-hu a-na dGAŠAN [UD.KIB.NUN<sup>ki</sup>] 14'. [2] GADA kib-<su> a-na dAMAR.UTU u dṢar-pa-ni-tu4 15'. [x] GADA kib-su a-na dziqu-rat-tu4 16'. [x] GADA kib-su a-na dGu-la

17'. 2 GADA kib-su a-na <sup>d</sup>IM u <sup>d</sup>Ša-[la]

Free space for about 2 lines

18'. [....] <sup>[</sup>x x<sup>]</sup>

The low position of Marduk and Şarpanītu suggests that the text was written in the time of Nabonidus.

[....] hul[lānu-cloak for Šamaš]

[x] new [lin]en tunic(s) for Šamaš

1 linen tunic <for> cover for Šamaš

1 linen tunic <for> cover for Aya

1 linen tunic <for> cover for Immertu

[x] linen tunic <for> cover for Bunene

1 linen *kibsu*-fabric <for> cover for the Queen of Si[ppar]

1 linen kibsu-fabric <for> cover for [DN]

1 linen *kibsu*-fabric <for> cover for [....]

1 linen linen tunic for the cultic seat of [....]

[x linen tu]nic f[or ....]

2 linen kibsu-fabrics for [DN]

2 linen tunics for the Queen of Sippar

2 linen kib<su>-fabrics for Marduk and Sarpanītu

[1<sup>?</sup>] linen *kibsu*-fabric for ziggurat

[1'] linen kibsu-fabric for Gula

2 linen kibsu-fabrics for Adad and Šala.

# 336. BM 101873 (83-1-21, 2534) $5.2 \times 2.4 \text{ cm}$ 1'. [....] blank 2'. [....] $^{d}A$ -a3'. [.... $^{d}$ ]DUMU.MÍ.MEŠ $^{\intercal}\dot{E}^{1}$ -[babbar-ra] 4'. [....] 「x<sup>1</sup> 1'. [....] Rev. 2'. [.... ki]b-su a-na <sup>d</sup>DUMU.MÍ-su É-babbar-<sup>r</sup>ra<sup>1</sup> \_\_\_\_\_ 3'. [.... ki]b-su a-na šu-bat <sup>d</sup>AMAR.UTU [u <sup>d</sup>GAŠAN-ja] \_\_\_\_\_ 4'. [.... ki]b-su a-na É <sup>d</sup>ziq-qur-[rat] -----5'. [.... kib]- $su\ a$ - $na\ ^{rd}Bu$ - $ne^{1}$ -[ne]\_\_\_\_\_ 6'. [.... kib-s]u $\lceil a \rceil$ - $\lceil na \dots \rceil$ Rev. 3'. Or <sup>d</sup>AMAR.UTU [*u* <sup>d</sup>Ṣar-pa-ni-tu<sub>4</sub>] [....] [.... for] Aya [.... for] the Daughters of the E[babbar] [.... ki]bsu-fabric for the Daughters of the Ebabbar [.... ki]bsu-fabric for the cultic seat(s) of Marduk [and Bēltiya] \_\_\_\_\_ [.... ki]bsu-fabric for the chapel of ziqqurat \_\_\_\_\_ [.... ki]bsu-fabric for Bune[ne] $[\dots ki]bsu$ -fabric fo $[r \dots]$ . **337. BM 69406** (82-9-18, 9403) $4.8 \times 3.8$ cm 11. [x.x] 1'. $2 \lceil sal \rceil - [hu...]$ 2'. 「2 sal-ḫu¹ [....] 3'. 1 $s[al^?-hu....]$

```
4'. 「3¬ sal-「ḫu¬ eš-「šu¬ [....]
              5'. 1 hu-la-nu <sup>r</sup>eš-šu <sup>1</sup> a-na [....]
              6'. U<sub>4</sub>.11.KAM SUM<sup>nu</sup> [....]
              _____
              7'. 1 sal-hu a-na [....]
Rest lost
              1'. [x] 「GADA<sup>†</sup> sal-h[u] ....]
Rev.
              2'. PAP 5 GADA sal-h[u\ ...] 3'. a-na ^{md}HAR-\check{si}-[man-ni ^{l\acute{u}}TÚG.BABBAR ....]
              4'. 3 kib-su šá ÚR.M[EŠ ....]
              5'. 1 kib-su šá <sup>d</sup>A-nu-[ni-tu<sub>4</sub>]
              6'. 1 kib-[su] šá <sup>d</sup>IM
              7'. 2 GA[DA x x] \check{s}\check{a} [a-na] \check{d}\check{S}[a-la]
Rest lost
Rev. 7'. At the end of the line only the head of one horizontal and one vertical wedge is
preserved. The reconstruction is based on the fact that Šala follows Adad.
2 tu[nics ....]
```

```
2 tunics [....]
1 tu[nic ....]
3 new tunics [....]
1 new hullānu-cloak for [....]
11<sup>th</sup> day was/were given [....]
1 tunic for [....]
[x] linen tun[ic(s) ....],
total 5 linen tunics [....]
for Bunene-ši[manni, the ašlāku ....]
3 kibsu-fabrics for the sūnu-belt[s ....]
1 kibsu-fabric for Anu[nītu]
1 kib[su-fabric] for Adad
2 lin[en ....] for Šala.
```

# XII. The kitû ša Šamaš u ilāni Sippar

**338. Nbn 848** = BM 60417

- 1. GADA šá ITI.GU<sub>4</sub> MU.15.KAM
- 2. md AG-I LUGAL Eki a-na
- 3. *ta-be-e šá* <sup>d</sup>UTU *u* DINGIR.[MEŠ *Sip-par*<sup>ki</sup>]
- 4. SUM<sup>na</sup> 1 GADA *hu-la-nu*
- 5. 9 GADA sal-hi 7 GADA kib-su
- 6. <sup>md</sup>U+GUR-MU *a-na* É.GUR<sub>7</sub>.MEŠ
- 7. it-ta-din [ina] lìb!-bi
- 8. 1 hu-la-nu 6 sal-hi
- 9. ina nak-ma-ri ina É.ŠU<sup>[ii]</sup>
- 10. 2 GADA sal-hi 7 kib-su
- 11. ina IGI <sup>md</sup>ḤAR-ši-man-ni
- 12. 1 sal-hi a-na su-un-<sup>[</sup>ni<sup>!</sup>]
- 13. a-na <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

Linen cloths, which for the month of Ayaru, 15<sup>th</sup> year of Nabonidus, king of Babylon for the *tabû* ceremony of Šamaš and the god[s of Sippar] were given.

1 linen  $hull\bar{a}nu$ -cloak, 9 linen tunics, 7 linen kibsu-fabrics, Nergal-iddin has given to the  $b\bar{t}t$ -karê-storehouse; out of it 1  $hull\bar{a}nu$ -cloak, 6 tunics are in the chest in the  $b\bar{t}t$   $q\bar{a}ti$ -storehouse;

2 linen tunics, 7 kibsu-fabrics are at disposal of Bunene-šimanni;

1 tunic for the *sūnu*-belt for the Queen of Sippar.

This is a typical administrative document describing exactly what has happened with particular items delivered by Nergal-iddin, probably for the next  $tab\hat{u}$  procession in the same month, i.e. some of them were replaced from the  $b\bar{\iota}t$ -karê-storehouse to the  $b\bar{\iota}t$  qātistorehouse, where they were stored in the nakmaru chest, some were given to the disposal of Bunene-šimanni and one for preparing the  $s\bar{\iota}u$ -belt for the Queen of Sippar. The reading Nergal-iddin, as against Strassamaier's copy was established by Bongenaar, Ebabbar, p. 338.

339. BM 77968 (85-4-30, 161)

PLATE 74

 $7.3 \times 6.5$  cm (thick 3.6 cm)

[x].2.Dar 26

- 1. GADA.MEŠ *šá a-na* <sup>r</sup>*ta-be*<sup>1</sup>-[*e šá* <sup>d</sup>UTU]
- 2. *u* DINGIR.MEŠ UD.KIB.NUN<sup>ki</sup> šá <sup>r</sup>a-na<sup>1</sup> [U<sub>4</sub>.x.KAM]
- 3.  $\check{s}\check{a}$  ITI.GU<sub>4</sub> SUM $^{na_1}$  ITI. $^{r}$ GU<sub>4</sub> $^{1}$  U<sub>4</sub>.[x.KAM]

	4. MU.26.KAM <sup>m</sup> Da- <sup>r</sup> ri <sup>?</sup> 1-[ja-muš LUGAL E <sup>ki</sup> LUGAL KUR.KUR]
	5. 4 GADA sal-「hu <sup>¬</sup> []
	6. 2 GADA $\lceil sal^2 \rceil$ -[ $hu$ ] 7. lost completely 8. [x x x x x] $\lceil a^1$ - $na$ $^d$ GAŠ[AN $^2$ ]
Rev.	9. $[x \times x \times x]^{\lceil a^{1}-na ^{d}}IM^{2}$ 1'. $[x \times x \times a]-na ^{d}Bu-ne-ne$
	2'. [x] GADA sal-ḥu la- <bi-ri> a-na <sup>d</sup>GA[ŠAN UD.KI]B.NUN<sup>ki</sup></bi-ri>
	3'. 1 GADA sal-ḥu la- <bi-ri> a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub></bi-ri>
	4'. 「1 GADA ki-ib-su¹ a-na <sup>d</sup> Gu-la
	5'. 1 GADA <i>ki-ib-</i> <sup>r</sup> <i>su</i> <sup>1</sup> < <i>a-na</i> > <sup>d</sup> IM 6'. [1 GADA <i>ki-ib-s</i> ] <i>u</i> < <i>a-na</i> > <sup>d</sup> <i>Ša-la</i> 7'. 4 GADA [ <i>sal-\beta</i> ] <i>u</i> <sup>mes</sup> <i>a-na</i> <sup>d</sup> UTU 8'. 1 GADA <i>ki</i> !(T: <i>ri</i> )- <i>i</i> [ <i>b-s</i> ] <i>u</i> <sup>?</sup> <i>a-</i> <sup>r</sup> <i>na</i> <sup>d</sup> <sup>1</sup> [x (x)]

The condition of the tablet is very poor, especially rev. 4'-8', where some signs have an extremely atypical shape.

Rev. 2'-3'. Comparison with other texts makes it clear that la is an abbreviation for la- $\langle bi$ - $ri \rangle$ .

Linen cloths which for the  $tab\hat{u}$ -procession [of Šamaš] and the gods of Sippar for  $[n^{th} \text{ day}]$  of the month Ayaru were delivered. Month Ayaru,  $[n^{th}]$  day,  $26^{th}$  year of Dar[ius, king of Babylon, king of the Lands].

4 linen tunics [for]
2 linen tu[nics for the Que[en of Sippar <sup>?</sup>
[ f]or]
[ f]or Bunene
[x] used linen tunic for the Que[en of Sip]par
1 used linen tunic for Anunītu

# 1 linen kibsu-fabric for Gula 1 linen *kibsu*-fabric <for> Adad [1 lin]en kibsu-fabric <for> Šala 4 linen [tuni]cs for Šamaš 1 linen kibsu<sup>!</sup>-fabric for [DN]. **340. BM 73244** (82-9-18, 13255) $6.8 \times 4.8$ cm 8.2.Dar 29 1. GADA $sal-hu^{\text{meš}}$ a-na lu-bu- $[u\check{s}$ - $tu_4$ $\check{s}\check{a}]$ 2. $^{\text{d}}$ UTU $\grave{u}$ DINGIR.<MEŠ> UD.KIB.NUN $^{[\text{ki}]}$ 3. ITI.GU $_4$ U $_4$ .8.KAM MU.29.K[AM] 4. <sup>m</sup>Da-ri-mu-šú LUGAL TIN.TIR<sup>ki</sup> L[UGAL KUR.KUR] \_\_\_\_\_ 5. [x] GADA sal-hu eš-šú 1 GADA hu-la-[nu] 6. [a]- $\lceil na \rceil$ <sup>d</sup>UTU 7 . [x GADA] $\lceil sal-hu \rceil$ eš-šú a-na $\lceil d \rceil$ [A-a] Rest lost 1'. [x GADA] <sup>r</sup>kib-su a<sup>1</sup>-[na <sup>d</sup>DN] Rev. 2'. [x] GADA kib-su a-na $\lceil^{d_1}$ [DN] Rest of rev. uninscribed The text suggests that *tabû*-procession was part of the *lubuštu* ceremony. Linen tunics for the *lubu*[štu ceremony of] Šamaš and the gods of Sippar. Month of Ayaru, 8<sup>th</sup> day, 29<sup>th</sup> year of Darius, king of Babylon, ki[ng of the Lands]. [x] new linen tunic, 1 linen *hullā*[nu]-cloak for Šamaš [x] new [linen] tunic for [Aya] [x linen] *kibsu*-fabric f[or DN] [x] linen kibsu-fabric for [DN]. **341. BM 67734** (82-9-18, 7732)

 $5.3 \times 7.0$  cm (thick ca. 3.3 cm)

9.2.Dar [x]

- 1. [GADA.MEŠ] 「a¹-na [ta-be-e šá <sup>d</sup>UTU]
- 2. [u DINGIR].MEŠ UD.KIB.[NUN<sup>ki</sup>]
- 3. ITI.GU<sub>4</sub> U<sub>4</sub>.9.[KAM MU.x.KAM]

	4. <sup>m</sup> Da-ri-ja-muš [LUGAL TIN.TIR <sup>ki</sup> LUGAL KUR.KUR]	
	5. 1 GADA sal-ḫu <sup>d</sup> U[TU <sup>?</sup> ]	
	6. 1 GADA KI.MIN <sup>d</sup> [DN]	
	7. 1 GADA KI.MIN <sup><d></d></sup> IM []	
	8. 1 GADA KI.MIN <sup>d</sup> [DN]	
Rest lost	9. <sup>[1<sup>2</sup>]</sup> GADA KI.MI[N <sup>d</sup> DN]	
L. 1. Or: [G	$[ADA \ sal-hu^{mes}] \ ^{r}a^{1}$ - $na \ [lu-bu-us-tu_{4} \ s\'a^{d}UTU]$ , cf. the text above.	
[Linen cloths] for [the $tab\hat{u}$ -procession for Šamaš] and the gods of Sippar. Month of Ayaru, $9^{th}$ day, [ $x^{th}$ ] year of Darius, [king of Babylon, king of the Lands].		
1 linen tun	nic <for> Ša[maš]</for>	
1 linen ditto <for> [DN]</for>		
1 linen <i>ditto</i> <for> Adad</for>		
1 linen <i>ditto</i> <for> [DN]</for>		
1 linen ditt[o DN]		

## XIII. The iškāru texts

**342.** Cyr **109** = BM 75525; cf. NUVI 3, No. 111; Giovinazzo 1981, No. 5. Collated  $5.5 \times 7.0$  cm

#### <->.2.Cyr 3

- 1. [iš-ka-ru M]U.AN.NA.3.KAM <sup>lú</sup>ΓUŠ\*.BAR\*1 [GADA]
- 2. 「id¹-din-nu ITI.GU4 U4.3.KAM
- 3. [<sup>m</sup>Ku-ra]š\* LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

------

- 4. [1 GADA hu-u]l-la-nu šá  $^d$ UTU  $^m$ AG-DA (followed by rasure) 5.  $u^{md}$ UTU-SIPA-u-a
- 6. 1<sup>en</sup> GADA sal-hi <sup>m</sup>Lib-lut
- 7. 1<sup>en</sup> GADA sal-ḫi <sup>md</sup>UTU\*-ŠEŠ.ME[Š-x] 8. 1<sup>en</sup> GADA sal-ḫi <sup>md</sup>UTU-ŠEŠ-MU 9. 1<sup>en</sup> GADA sal-ḫi <sup>md</sup>EN-SUM<sup>[na]</sup>

- 10. 1<sup>en</sup> GADA sal-hi 1 hu-ul-la-nu šá <sup>d</sup>[DN]
- 11. 2 GADA sal-hi šá <sup>d</sup>DUMU.MI.ME\* šá\* É-babbar-r[a]
- 12. 2 GADA *sal-hi šá* <sup>d</sup>*Gu-la* <sup>r</sup>x<sup>1</sup> [(....}]
- 13. 1<sup>en</sup> GADA sal-ḥi GAL-ú [....] 14. 1<sup>en</sup> gú-ḥal-ṣ[u ....]
- 15. *ina pa-ni* [....]
- L. 1 and 7. The reading  $^{l\acute{u}_f}$ UŠ.BAR $^1$  [GADA] in l. 1 and UTU in l. 7 was established by Bongenaar, *Ebabbar*, p. 343.
- L. 11. *babbar* is written over erasure.

[Labour assignment (for)] 3 years, (which) the [linen] weavers have delivered. Month Ayaru, 3<sup>rd</sup> day <nth year> [of Cyru]s, king of Babylon, king of Lands.

[1] linen hu]llānu-cloak for Šamaš (from) Nabû-ilēi and Šamaš-rē'ûa

1 linen tunic (from) Liblut

- 1 linen tunic (from) Šamaš-ahhē-[x]
- 1 linen tunic (from) Šamaš-ah-iddin
- 1 linen tunic (from) Bēl-iddina
- 1 linen tunic, 1 linen hullānu-cloak for [DN]
- 2 linen tunics for the Daughters of the Ebabbar
- 2 linen tunics for Gula [(....)]
- 1 large linen tunic [....]
- 1 sca[rf ....]
- at disposal [....].

### 343. BM 62100 (82-9-18, 2069)

PLATE 75

 $4.9 \times 6.9$  cm

#### [x].2.Dar 20

```
1. iš-ka-ru [šá ITI.x]
```

- 2. šá U<sub>4</sub>.9.KAM šá <sup>m</sup>Lib-[lut]
- 3. lúUŠ.BAR GADA *u* lúERÍ[N.MEŠ]
- 4. *id-din-nu* ITI.GU<sub>4</sub> U<sub>4</sub>.[x.KAM]
- 5. MU.20.KAM <sup>m</sup>Da-r[i-ja-muš]
- 6. LUGAL TIN.TIR.K[I LUGAL KUR.KUR]

-----7. [x]+<sup>[1]</sup> GADA *hu-la-nu* <sup>m</sup>[....]

8.  $[x]+\Gamma 1$  GADA < sal > -hu GAL  $^{\mathrm{m}}Ni$ -di[n- $t\acute{u}^{?}]$ mdAG-「TINit?」 9. [x+<sup>?</sup>] 1 GADA *sal-hu* 

mAD-NU-ZU 10. 2 GADA sal-hu <sup>m</sup>Il-tam-meš-11. <sup>[4]</sup> GADA sal-hu

12. i-la-a

mdEN-NUMUN 13. 2 GADA sal-hu

14. 1 GADA sal-<hu> hu-la-nu Rev.

15. <sup>m</sup>Gi-mil-lu

 $^{m}Du$ -um-< mu >-qu16. 1 GADA 「sal¬-hu GAL

17. 4 GADA <sup>r</sup>tu<sup>¬</sup>-ma-nu

18. 「x x<sup>7</sup>

Free space for about 4 lines

19. PAP 2 GADA *sal-h*[*u* ....]

2 GADA sal-h[u ....]

21. 2 「GADA sal-hull GADA h[u-la-nu]

22. 2 GADA  $\lceil sal \rceil - h \lceil u \text{ PAP}^2 \rceil$ 

23. 8 GADA sal-h[u x GADA hu-la-nu]

24. *šá* <sup>d</sup>[DN]

Some persons mentioned in the text appears in BM 61025 (= 346).

- L. 8. The reading <sal>-hu is justified by the comparison with 1. 16. The salhu rabû is known also from BM 82581 (= 180): 1 dated to 13<sup>th</sup> year of Nebuchadnezzar. L. 9. In BM 61025 <sup>m</sup>AD-NU-ZU is preceded by <sup>md</sup>UTU-TIN<sup>if</sup>, but here the theophoric
- element is clearly AG.
- L. 17. In the texts from Sippar the linen tumānu is mentioned also in Nbn 164: 21 (4 ma-na 17 GÍN *tu-ma-na a-na*\* (coll.)) and in BM 65741 (= 626), l. h. e. 2.

Labour assignment of the [month x],  $9^{th}$  day, which was delivered by Liblut, the linen weaver and his workers. Month of Ayaru,  $[x^{th}]$  day,  $20^{th}$  year of Dar[ius], king of Ba[bylon, king of Lands].

<sup>[</sup>x]+1 linen *hullānu*-cloaks (from) [....]

<sup>[</sup>x]+1 large linen tunics (from) Nidi[ntu]

<sup>[</sup>x]+1 linen tunics (from) Nabû-uballiţ

PLATE 76

```
2 linen tunics (from) Abī-ul-īde
4 linen tunics (from) Iltammeš-ilaya
2 linen tunics (from) Bēl-zēri
1 linen tunic, <1?> hullānu-cloak (from) Gimillu
1 large linen tunic (from) Dummuqu
4 < minas? > of yarn
Total 2 linen tunics [....] 2 linen tunics [....]
2 linen tunics, 1 linen h[ullānu-cloak]
2 linen tunics, [total<sup>?</sup>] 8 linen tunics, [x linen hullānu-cloaks] for [DN].
344. BM 65592 (82-9-18, 5579)
7.1 x 7.8 cm
                            9.2.Dar 22
               1. [(x) i]š-ka-ri šá MU.21.K[AM šá]
               2. [<sup>m</sup>Za]-bi-ni ù <sup>lú</sup>ERÍN-šú i[d-din-nu]
               3. [ITI.G]U<sub>4</sub> U<sub>4</sub>.9.<KAM> MU.22.KAM ^{\rm m}Da-^{\rm r}ri-ja1-[mu\check{s}]
               4. [LU]GAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
               4a.
                                                            na-šá ITI.GU<sub>4</sub>
                                                            <sup>m</sup>Za-bi-ni A <sup>m</sup>Lib-luṭ
               5. 3 GADA hu-la-nu
                                                <sup>m</sup>Su-qa-a-a ŠEŠ-šú
               6. 5 GADA sal-hu
                                                <sup>md</sup>UTU-a-na-É-a-ki-tu<sub>4</sub> ŠEŠ-šú
               7. 1 GADA hu-la-nu
                                                <sup>m</sup>Ni-din-<sup>Γ</sup>it<sup>↑</sup> A <sup>m</sup>Na-din
               8. 1 GADA sal-hu šá
               9. <sup>d</sup>HAR (T: ne)
             10. 2 GADA sal-hu šá
                                                <sup>m</sup>Du-<mu>-ú-qu ŠEŠ-šú
                                                           <sup>md</sup>EN-šú-nu A <sup>m</sup>Šu-la-a
             11. <sup>d</sup>DUMU.MÍ.MEŠ
                                               a-na
                                                            {}^{\mathrm{m}}\Gamma\grave{\mathbf{1}}\mathbf{R}^{\mathsf{1}}-{}^{\mathrm{d}}A-nu-ni-{}^{\mathsf{\Gamma}}tu_{4}{}^{\mathsf{1}}
             12. [x+]1 GADA ÚR.MEŠ
             13. [x x <sup>md</sup>E]N-MU šá
                                                            ^{\text{md}}[x x]
Rest lost
               1'. [2] ^{\dagger}kib-su^{\dagger} [....]
2'. 2 kib-su ^{\dagger}a-na^{\dagger} [^{d}AMAR.UTU u ^{d}GAŠAN-ja]
Rev.
               3'. 2 kib-su a-na ziq-[qur-rat]
               4'. 2 kib-su a-na <sup>d</sup>ḤAR
5'. 2 kib-su a-na <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>
               6'. 5 kib-su a-na <sup>d</sup>A-nu-ni-tu<sub>4</sub> ina lìb-bi
                        šá aná šá-lam <É>
               8'. 1 kib-su a-na <sup>d</sup>Gu-la
               9'. [x] kib-su a-na <sup>d</sup>IM ina lìb-bi šá ÚR
             10' [x ki]b-su a-na <sup>d</sup>Ša-la
```

\_\_\_\_\_\_

11'. [x] ta-hap-šú <sup>meš</sup> šá <sup>d</sup>UTU u <sup>d</sup>UTU x x x

12'. [x ta-hap]-šú a-na <sup>d</sup>UTU

```
13'. [x ta-hap-su] \lceil a \rceil-na ^{d}A-\lceil a \rceil
```

14'. [x ta-ḥap-šú] a-na <sup>d</sup>[Bu-ne-ne/ḤAR]

15'. [x ta-ḥap-šú] a-na <sup>d</sup>[GAŠAN UD.KIB.NUN<sup>ki</sup>] 16'. [x ta-ḥap-š]ú a-na <sup>rd</sup>[DN]

17'.  $[x \ kib]$ -su a-na  ${}^{d}Gu$ -l[a]

18'. [x kib-su a-na]{x} dIM 1' kib-[su a-na dŠa-la]

I am grateful to John MacGinnis for bringing this text to my attention.

Ll. 10-12. It is not clear how to coordinate the right side of the text with the left side, complicated additionally by the preposition ana. We can first read the right side, i.e. 2 GADA sal-hu šá dDUMU.MÍ.MEŠ a-na [x+]1 GADA ÚR.MEŠ and recognize in Dummuqu, Bēlšunu, and Arad-Anunītu persons responsible for the fulfilment of these obligations or read the left side of ll. 10–11 GADA sal-hu šá <sup>d</sup>DUMU.MÍ.MEŠ a-na) and continue with the text of the right side (Dummuqu, Bēl-šunu) and next l. 12. However, because it is known that salhu was used for producing sūnu-belts the first possibility seems more probable. It is not excluded that in rev. 11'-16' ta-hap-šú was preceded with GADA or TÚG.

Labour assignment for the  $21^{st}$  ye[ar, which Zā]binu and his workers have de[livered. Month A]yaru,  $9<^{th}>$  day,  $22^{nd}$  year of Darius, [ki]ng of Babylon, king of Lands.

withdrawn; month Ayaru

3 linen hullānu-cloaks (from) Zābinu, son of Liblut

5 linen tunics (from) Suqāya, his brother

1 linen hullānu-cloak (from) Šamaš-ana-bīt-akītu, his brother

1 linen tunic for Bunene (from) Nidintu, son of Nādin

2 linen tunics of the Daughters of the Ebabbar for (making) [x] + 1 linen  $s\bar{u}nu$ -belts (was given to) Dummuqu, his brother (and?) Bēl-šunu, son of Šulā.

[....] (from) Arad-Anunītu

[.... B]ēl-iddin [PN]

[2] *kibsu*-fabrics [for ....]

2 kibsu-fabrics for [Marduk and Bēltiya<sup>?</sup>]

2 *kibsu*-fabrics for zig[qurat]

2 kibsu-fabrics for Bunene

2 kibsu-fabrics for the Queen of Sippar

5 kibsu-fabrics for Anunītu, including that for the šalām <bīti> ceremony

1 kibsu-fabric for Gula

[x] kibsu-fabric for Adad, including that for sūnu-belt

[x] *kibsu*-fabric for Šala

[x] cover for Šamaš and Šamaš x x x

[x cov]er for Šamaš

[x cover] for Aya

[x cover] for [Bunene]

[x cover] for [the Queen of Sippar]

[x cover] for [DN]

[x kib]su-fabric for Gul[a]

[x kibsu-fabric for] Adad, 1 kib[su-fabric for Šala].

# **345. BM 72810** (82-9-18, 12818)

PLATE 77

 $4.4 \times 5.3$  cm

- 1'. 1 GADA *hu-la-nu* [....]
- 2'. 1 GADA sal-ḫu <sup>m</sup>K[i²-....] 3'. 1 GADA sal-ḫu <sup>md</sup>EN-NU[MUN] 4'. 1 GADA sal-ḫu <sup>md</sup>UTU-ŠEŠ-「MU¹ 5'. 1 GADA sal-ḫu <sup>md</sup>UTU-TIN<sup>it</sup>

- 6'. 1 GADA sal-hu <sup>m</sup>Lu-ú-i-di-ja
- 7'. 1 GADA sal-ḥu 1 GADA ḥu-la-nu šá <sup>d</sup>ḤAR 8'. 2 GADA sal-ḥu <sup>d</sup>DUMU-rat <sup><meš></sup> É-babbar-ra
- 9'. 2 GADA *sal-ḥu šá* <sup>d</sup>*Gu-la* <sup>md</sup>UTU-I
- 10. 1 GADA sal-ḫu <sup>md</sup>UTU-ŠEŠ.MEŠ-bul-liṭ
  11'. 1 GADA sal-ḫu <sup>m</sup>AD-NU-ZU
  12'. 1 GADA sal-ḫu <sup>md</sup>Šá-<sup>d</sup>AG-du-qu-šú
  13'. 1 GADA sal-ḫu <sup>m</sup>ÌR- <sup>d</sup>ḤAR

14'. 2 GADA IG AN<sup>e</sup> a-na <sup>d</sup>UTU Rev.

- 15'. [(x x)] <sup>m</sup>Ba-zu-zu u <sup>m</sup>LUGAL-<sup>d</sup>UTU-ja
- 16'. 6 [ma]-<sup>г</sup>па<sup>¬</sup> GADA *ţu-ma-nu*
- 17'. <sup>f</sup>*Mu-ra-na-tu*<sub>4</sub>
- 18'. 1 GADA gú-ḥal-ṣu-ú a-na <sup>d</sup>UTU
- 19'. 1 GADA gú-hal-ṣu-ú a-na <sup>d</sup>HAR
- 20'. 1 GADA gú-hal-ṣu-ú a-na dIM

- 21'. PAP 14 <sup>lú</sup>ERÍN.MEŠ <sup>lú</sup>UŠ.BAR GADA
- 22'. *šá* ŠU<sup>ii md</sup>ḤAR-*ši-[ma-ni* lúUŠ.BAR GADA]
- 23'. 「šá U<sub>4</sub>¹ [....]

# L. 8'. Note the atypical writing ${}^{d}DUMU$ -rat for $m\bar{a}r\bar{a}t$ .

- 1 linen *hullānu*-cloak [(from ....]
- 1 linen tunic (from) K[ī- ....]
- 1 linen tunic (from) Bēl-<sup>r</sup>zēri<sup>1</sup>
- 1 linen tunic (from) Šamaš-ah-iddin
- 1 linen tunic (from) Šamaš-uballit
- 1 linen tunic (from) Lū-idiya
- 1 linen tunic, 1 linen *hullānu*-cloak for Bunene
- 2 linen tunics (for) the Daughters of the Ebabbar
- 2 linen tunics (for) Gula (from) Šamaš-na'id
- 1 linen tunic (from) Šamaš-ahhē-bulliţ
- 1 linen tunic (from) Abī-ul-īde
- 1 linen tunic (from) Ša-Nabû-duqušu
- 1 linen tunic (from) Arad-Bunene
- 2 linen door's curtain for Šamaš

[..] Bazuzu and Šar-šamšaya

6 [mi]nas of linen yarn (from) <sup>f</sup>Muranātu 1 linen scarf for Šamaš 1 linen scarf for Bunene 1 linen scarf for Adad Total 14 workers, the linen weavers, under Bunene-sim[anni, the linen weaver] for day<sup>?</sup> [....]. PLATE 78 **346. BM 61025** (82-9-18, 1001)  $7.0 \times 5.7$  cm -----2'. 1 GADA hu-la-nu 2 GADA sal-hu ți-<sup>r</sup>mi-tú<sup>1</sup> 3'.  $^{\text{md}}$ EN-MU  $u^{\text{mr}}Lib^{\gamma}$ -lut \\_\_\_\_\_ 4'. 1 GADA *hu-la-nu* 2 GADA *sal-h*[*u* ....] 5'. 1 GADA sal-hu bir-<ri>1' GADA! sal-hu<sup>1</sup> mdEN-NUMUN \_\_\_\_\_ <sup>md</sup>UTU-TIN<sup>i‡</sup> 6'. [GAD]A sal-hu \_\_\_\_\_ 7'. [x GADA sal]-[hu] <sup>m</sup>AD-NU-ZU -----<sup>™</sup>ÌR]-<sup>rd</sup>¹Bu-ne-ne 8'. [ Rest lost Rev. 1'. [....]  $\lceil x \rceil$  [(x)] 2'.  $[x \times x \times x]^{\lceil \check{s}\check{u}\rceil - nu} ri^{\lceil hi\rceil}$ -----3'. 「1 GADA<sup>†</sup> sal-hu IGI 「<sup>d</sup><sup>†</sup>A-a \_\_\_\_\_ 4'. PAP 3 GADA sal-hi bir-[mu] iš-ka-ri 5'. šá MU.7.KAM ri-hi ina IGI <sup>md</sup>ḤAR-ši-man<sup>an</sup>-ni

Some persons mentioned in the text appear also in another *iškāru* document, BM 62100 (= 343).

Free space for one line Rest missing (probably only the date).

6'. e-lat 7 GADA sal-ḫu ri-ḫi IGI-t[ú] 7'. šá ina IGI <sup>md</sup>ḪAR-ši-man<sup>an</sup>-[ni]

L. 5'. The signs between 1 GADA *sal-fu* and the personal name are written over an erasure and are partially damaged; for this reason the reading is extremely difficult and uncertain.

[] and	I the []	
1 linen (from)	hullānu-cloak, 2 linen tunics {(made of) ya Bēl-iddin and Libluţ	rn <sup>2</sup> }
1 linen !	hullānu-cloak, 2 linen tuni[cs]	<del></del>
1 linen ı	multicoloured <sup>?</sup> tunic, 1 <sup>!</sup> linen tunic (from) F	 Bēl-zēri
[1] liner	ı tunic (from) Šamaš-uballiţ	<del></del>
[1 linen	tun]ic (from) Abī-ul-īde	
[1 linen	tunic (from) Arad]-Bunene	
	· 	
	ir, remnant 	
1 linen t	tunic before Aya	
<b>347. BN</b> 6.1 × 7.0	<b>4 65729</b> (82-9-18, 5719) 0 cm	
	(ca. month 8.[Dar] 20)	
	1'. 2 GADA <i>sa</i> [ <i>l-hu</i> ] 2'. 1 erased sign	
	3'. 2 GADA sal-ḫu	<sup>md</sup> UTU- <i>ir-il-la-a-a</i>
		<sup>m</sup> Su-qa-a-a
	5'. 3 GADA sal-ḫu 6 GADA su-ú-nu 6'. šá <sup>d</sup> UTU <sup>md</sup> UTU-a-na-ki-tu <sub>4</sub>	
Rev.	7'. ½ GÚ.UN 5 ½ ma-na <sup>síg</sup> ta-bar-ri 8'. KI.LAL 2 GADA <i>šid-du</i> <sup>m[eš]</sup> 9'. [ <i>šá</i> <sup>? m</sup> ] <i>Za-bi-nu</i> <sup>l[ú</sup> ] 10'. [x x] <sup>r</sup> x x <sup>1</sup> [] 1'. nothing preserved	

2'. 「1 <sup>1</sup> GADA sal-[ḫu] 3'. <sup>m</sup> Za-bi-nu []
4'. 1 GADA <i>ḫu-la-an-[na]</i> 5'. <i>šá</i> MU.20.KAM <i>a-na</i> <sup>rm</sup> x x <sup>1</sup> 6'. <sup>cm&gt;</sup> EN-bu-na-ku <sup>m</sup> Ni-din-tu <sub>4</sub>
7'. 1 GADA <i>sal-ḫu šá</i> ITI.APIN U <sub>4</sub> .15.KAM 8'. 1 GADA <i>ḫu-la-an-na šá</i> <sup>d</sup> ḤAR 9'. <sup>md</sup> EN-M[U]

## Rest lost

It seems that the text should be recognised as a list of iškāru obligations, similar to the two texts presented above. The measure of the text and writing of the division of the last syllable (hu-la-an-na, instead of hu-la-nu/na) suggest that the text was written later, probably in 20th year of Darius I.

L. 3' and 6'. According to my knowledge both names are mentioned here for the first time. In 1. 6' the writing <sup>md</sup>UTU-a-na-ki-tu<sub>4</sub> is for <sup>md</sup>UTU-a-na-<É-a>-ki-tu<sub>4</sub>
L. 9'. Zabīnu, maybe identical with *išpar kitê/puṣaya*, see Bongenaar, *Ebabbar*, p. 353 (ac-

tive in the time of Darius I' rule).

Rev. 6'. Bēl-bunaku, cf. the name Bunakka known in the Neo-Assyrian period, see PNAE, vol. 1, part II, p. 352 ("probably Elamite" according to M. Caprano).

L. 8'. Concerning of *šiddu*, see also in BM 65976 (= 414): 7.

2 linen tunics (from?) [PN]
2 linen tunics (from?) Šamaš-irillaya
2 linen tunics (from?) Suqāya
3 linen tunics, 6 linen <i>sūnu</i> -belts for Šamaš (from?) Šamaš-ana-akītu
35 ½ mina of red wool, the weight of 2 linen <i>šiddu</i> curtain [from <sup>?</sup> ] Zabīnu, the []
1 linen tunic, [] (from <sup>?</sup> ) Zabīnu,
1 linen <i>ḫullānu</i> -cloak, [] for the 20 <sup>th</sup> year for [PN] Bēl-bunaku and Nidintu
1 linen <i>salḫu</i> for the 15 <sup>th</sup> day of the month Araḫsamna 1 linen <i>ḫullānu</i> for Bunene (from²) Bēl-id[din].

# XIV. Diverse texts concerning manufacture of garments

PLATE 79

```
6.8 \times 4.4 cm
                   1. [x ma-n]a 1/3 4 GÍN šá 1 mut-ta-tu<sub>4</sub> šá <sup>d</sup>U[TU]
                  2. [x x x] <sup>7</sup> GÍN šá 1 ma-na ta-bar-ru šá 2 TÚG.BAR.DUL<sub>8</sub>
                              1 GÚ.UD.DU
                  3. [šá {}^{\rm d}\!A-a 1]-{}^{\rm r}en{}^{\rm ?!}{}^{\rm l}ni-bi-ḫu šá {}^{\rm d}\!Bu-ne-ne
                  4. [PAP<sup>?</sup> ½<sup>?</sup>] GÚ.UN 6 ½ ma-na
                  5. [x GÚ.ÚN] ^{\lceil 3 \rceil 8} ma-na 12 GÍN SÍG.ḤI.A šá ^{\rm m}Du-muq ina
                             MU.AN.NA
                  6. [ina lìb-b]i 2 GÚ.UN 15 ma-na šá ta-hap-šú
                  7. [x x]-bi 11 GÚ.UN 29 ma-na ih-ti-it šá ^{\Gamma}1^{et_{\gamma}} mut-ta-tú šá
                             MU.AN.NA
                  8. [x \ x \ x]^{\lceil 6 \rceil \frac{1}{2}} [ma]-na a \ [x]^{\lceil 9 \rceil} \check{s} \acute{a}^{\lceil m} Du^{?}-muq^{?} \ x^{\rceil} [(x)]
                  9. [x x] 26 <sup>r</sup>ma<sup>1</sup>-na SÍG.HI.A šá 13 GÍN KÚ.[BABBAR]
                                                                           aná muḥ-ḥi <sup>md</sup>EN-ú-[....]
                 11. [x \ x]^{\lceil 5/6 \rceil} ma - na \{ [x]^{\lceil x]^{?} \} SÍG.HI.A \check{s} \acute{a}^{m} D[u - .... ]
Edge
                 12. [x x] MU.<sup>r</sup>9<sup>1</sup>.KAM e-tir
                13. [x \ x]^{-1}<sup>2</sup> 4 ½ ma<sup>1</sup>-na<sup>1</sup> ina muḥ-ḥi-šú
Rev.
                 13a.
                                                                                         8 30 SUR
                 14. [x x] ma-na LAL {UD} <sup>m</sup>BA<sup>šá</sup>-a šá MU.9.<KAM>
                 15. [x GÚ.U]N 34 ma-na <sup>m</sup>BA<sup>šá</sup>-a ina MU.9.<KAM> iḥ-ti-iṭ
16. [x x] 30 ma-na SÍG.ḤI.A šá <sup>m</sup>BA<sup>šá</sup>-a MU.10.KAM
                 17. [x G]Ú.UN <sup>m</sup>TIN 30 ma-na <sup>md</sup>EN-PAP mi-ta-tú šá
                             MU.10.KAM 「DÙ/ni
                                                          {}^{\mathrm{m}}\mathrm{BA}^{\check{s}\acute{a}}-a ul-te-{}^{\mathsf{r}}nu{}^{?}-\acute{u}^{?}
                 17a.
                 18. [x GÚ.U]N<sup>?</sup> 14 ma-<na> ha-a-tu <sup>m</sup>BA<sup>šá</sup>-a šá MU (sic) 19. [x m]a-na SÍG.ḤI.A <sup>m</sup>BA<sup>šá</sup>-a <sup>r</sup>šá MU.9 U<sub>4</sub><sup>?</sup> 8<sup>1</sup>
```

- L. 2. The reading  $\lceil 7 \rceil$  instead of 6 is also not excluded.
- L. 7. šá MU.AN.NA is written over erasure.
- L. 8 looks like intentionally erased.

**348. BM 49757** (82-3-23, 748)

I decided to present here the transliteration and copy of the text with only a relatively preliminary translation although its sense is not clear to me. It might be a type of document concerning the redistribution of wool for the manufacture of the types of garments mentioned. The act of weighing the wool might suggest the role of Dummuqu as the person responsible for the distribution of wool in the  $9^{th}$  and  $10^{th}$  year, but this is not certain.

[x] minas 24 shekels, (the weight of<sup>2</sup>) 1 *muttatu*-headdress for Ša[maš] [x]+ <sup>r</sup>7<sup>1</sup> shekels, <the price<sup>2</sup>> of 1 mina of red wool for 2 robes, 1 *naḥlaptu*-cloak [for Aya]; <sup>r</sup>1<sup>1</sup> *nēbeḥu*-belt for Bunene, [total<sup>2</sup> 3<sup>2</sup>]6 ½ minas (of wool)

[x talents] 38 minas 12 shekels of wool yearly for/from? Dummuqu, [includi]ng 2 talents 15 minas for covers

[...] 11 talents 29 minas he has weighed. For 1 muttatu-headdress yearly

[....] + 6 ½ mina .... Dummuqu;

[x] +26 minas wool for 13 shekels of silver on account of Bēl-u[...]; [x] + 5/6 mina  $[x \ x]$  wool, which D[ummuqu] [...] has paid in the  $9^{th}$  year.

[...] + 14 ½ mina on his account

8 30 ....... [x] minas is missing? (for?) Iqīša, 9<sup>th</sup> year

[x talen]t(s) 34 minas Iqīša has weighed in the 9<sup>th</sup> year

[x]+30 minas of wool – Iqīša, 10<sup>th</sup> year [x ta]lent(s) – Balāţu; 30 minas – Bēl-nāṣir, shortage for the 10th year ... Iqīša changed?!

[x talen]ts 14 minas, the supply (for) Iqīša, yearly

[x mi]nas of wool – Iqīša, 9<sup>th</sup> years, 8<sup>th</sup> day

#### **349. BM 60968** (82-9-18, 944)

 $4.8 \times 5.8$  cm

1'. [....]  $^{r}hi^{?_{1}}$  [x x]

2'. [x x] <sup>r</sup> x x<sup>1</sup> 4 GADA sal-<sup>r</sup> hu<sup>1</sup>

3'. [1 G]ADA *hu-ul-la-nu* 

4'. 1<sup>et</sup> TÚG.GÚ.UD.DU bir-mu

5'. 1<sup>et</sup> TÚG.BAR.DUL<sub>8</sub> 4 TÚG.GÚ.UD.DU.MEŠ

SÍG.HÉ.ME.DA

7'. 2 GADA sal-hi 2-ta TÚG.BAR. [DUL<sub>8</sub>]. [MEŠ]

8'. 4 TÚG.GÚ.UD.DU.MEŠ šá <sup>d</sup>[DUMU.MÍ].MEŠ *E-babbar-ra* 

9'. ina IGI  ${}^{m_{\Gamma}}$ Ṣi $l^{1}$ -la-a  ${}^{1\acute{u}}$ [TÚG.BABBA]R

10'. ITI.GU<sub>4</sub> U<sub>4</sub>.3.KAM MU.23.「KAM<sup>1</sup>

11'. <sup>md</sup>AG-NÍG.DU-ÙRU LUGAL E.[KI]

#### Rev. uninscribed

- Ll. 1'-6' comprise most probably the list of garments for Aya.
- L. 2. Two badly preserved signs are similar to 「BAR.DUL8¬, but such reading is rather improbable because this garment appears in 1.5'.

Rev. 9'. Şillā, ašlāku, see Bongenaar, Ebabbar, pp. 341-42 and Zawadzki, Garments of the Gods, Vol. I, p. 225.

[....], 4 linen tuncis, [1 li]nen hullānu-cloak, 1 multicoloured nahlaptu-cloak, 1 robe, 4 red nahlaptu-cloaks

2 linen tunics, 2 robes, 4 nahlaptu-cloaks for [the Daughte]rs of the Ebabbar at disposal of Šulā, the [ašlā]ku.

Month of Ayaru, 3<sup>rd</sup> day, 23<sup>rd</sup> year of Nebuchadnezzar, king of Babylon.

# **350. BM 76963** (83-18, 2335)

1'. [....] 「x¬ [....]

2'. [.... <sup>d</sup>]DUMU.MÍ.<MEŠ> *É-babbar-*<sup>-</sup>*ra*<sup>1</sup>

 $5.1 \times 5.0$  cm

# [x.x].Nbn 10

```
1. [....] x [....]
            2. [.... <sup>md</sup>AG]-up-ni-ja <sup>lú?</sup>[UŠ]. 「BAR<sup>1</sup>
3. [.... MU]. 「10<sup>?</sup>1. KAM <sup>md</sup>AG-I LUGAL E<sup>ki</sup>
            _____
            4. [... K]I.LAL ku-si-tu4 š\acute{a} {}^dΓA1-a
            5. [....] GÍN šá a-di-la-nu
            6. [.... TÚG.ḤI.A] me-ṭu TÚG.ḤI.A ku-lu-lu
            _____
            7. [.... K]I.LAL 2 par-ši-gu [....]
            8. [....] x e x [....]
Rev.
            1'. [....] TÚG.ḤI.A me-ṭu
            2'. [... šá] <sup>d</sup>IM
            3'. [....]-tu<sub>4</sub> TÚG.ḤI.A me-ṭu TÚG.ḤI.A
            4'. [ku-lu-lu šá <sup>d</sup>A-nu-n]i-tu<sub>4</sub>
            5'. [....] x x x a-a-ri pa-ni
            6'. [....]-ni
[.... Nabû]-upnīya, the [wea]ver [....] 10^{\rm th} [year] of Nabonidus, king of Babylon
[...., the we]ight of (one) robe of Aya
[....] shekels for tassel?
[...., the lubār] mēṭu (and) lubār kulūlu-headbands
[...., the we]ight of 2 paršīgu-headdresses [....]
[....] lubār mēţu [....<sup>?</sup> for] Adad
[.... the] lubār mēṭu (and) lubār [kulūlu-headbands for Anun]ītu
[.... the] front rosette [....].
351. BM 70885 (82-9-18, 10886)
6.7 \times 2.7 cm
```

```
3'. [.... par]-ši-hu a-na {}^{d}Bu-ne-ne 4'. [....] {}^{f}a^{1}-na {}^{d}GAŠAN UD.KIB.NUN{}^{ki}
                5'. [.... <sup>d</sup>A]-nu-ni-tu<sub>4</sub>
6'. [.... <sup>d</sup>G]u-la
                 7'. [.... <sup>d</sup>]UTU [....]
Rest of Obv. lost
Rev.
                 1'. [....] a-na <sup>d</sup>[UT]U
                 2'. [....] [x \times x^1 [....]
                 3'. [....]-ši
                4'. [.... <sup>d</sup>Bu-ne]-ne
5'. [.... <sup>d</sup>GAŠAN] Sip-par<sup>ki</sup>
6'. [.... <sup>d</sup>A]-nu-ni-tu<sub>4</sub>
                 7'. [....].ÚR
                8'. [.... <sup>d</sup>]Gu-la
                 9'. [....] [x] (erased?)
               10'. [....].ÚR
               11'. [....] U<sub>4</sub><sup>?</sup> KAM<sup>?</sup> [....]
L. 1'. Only two vertical wedge are preserved.
[....] the Daughters of the Ebabbar
[.... par]šīgu-headdress for Bunene
[....] for the Queen of Sippar
[.... for A]nunītu
[.... for G]ula
[.... for] Šamaš[....]
[....] for Šamaš [....]
[.... for Bune]ne
[.... for the Queen of] Sippar
[.... for A]nunītu
[....] sūnu-belt
[.... for] Gula
.....
[....] sūnu-belt [....].
352. BM 73703 (82-9-18, 13714)
3.9 \times 3.5 cm
                 1. [.... KI].LAL 10 <sup>túg</sup>hu-ṣa-ni-e
                2. [....] <sup>d</sup>Ša-la
```

```
3. [....] ^{\text{túg}}hu-şa-ni-e
4. [....] ^{\text{f5/6}} ma-na 6 GÍ[N
                 5. [....] ÚR.MEŠ
                 6. [....] u <sup>d</sup>ME.ME
                 7. [....] [x][x][x]
Rev.
                 8. [....] 「KI.LAL¹ [x x] a-[....]
                 9 . [....]-la [x x] du bu<sup>?</sup>
                10. [....] [x] it-ta-[din]
                11. [ITI.x U<sub>4</sub>.x].KAM MU.10.KAM
                12. [KN LUG]AL E.「KIT
[.... the we]ight of 10 sashes
[....] Šala
[....] sash(es)
[....] 56 shekels [...
[....] sūnu-belts
[....] and Gula
[....] the weight [....]
[....] has given
[N<sup>th</sup> month, n<sup>th</sup>] day, 10<sup>th</sup> year [of KN, ki]ng of Babylon.
353. BM 66232 (82-9-18, 6223)
                                                                                                                 PLATE 80
5.5 \times 6.9 cm
                 1. [x ma-na KI.LAL TÚG.ḤI]. 「A¬ šá dUTU ina lìb-bi
                 2. [½ ma-na ta-ki]l¹-tu4 2 ma-na KI.LAL [...]
                 3. [....] <sup>túg</sup>hu-ṣa-ni-e šá <sup>d</sup>UTU
                 4. [\dots]^g su-ni-e šá <sup>d</sup>UTU
                 5. [1 ma-na KI.LAL ^{t\acute{u}]g!}hu-sa-ni-e s\acute{a} ^dA-a 6. [1/3 ma-na KI.LA]L ^{t\acute{u}]g}su-ni-e s\acute{a} ^dA-a
                 7. [1 1/3 ma-na KI.LA]L TÚG.ḤI.A šá <sup>d</sup>Bu-ne-ne ina <sup>r</sup>lìb¹-[bi
                            6 GÍN]
                 8. [SÍG.ZA.GÌN.KUR].RA 2/3 ma-na KI.LAL túg șib-tu4 [šá
                            dHAR]
                 9. [1 ma-na KI.LAL 10 <sup>túg</sup>]ḫu-ṣa-ni-e šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
               10. [1 ma-na KI.LAL 10 <sup>túg</sup>]ħu-ṣa-ni-e šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
11. [1/3 ma-na KI.LAL <sup>túg</sup>]su-ú-nu šá [<sup>d</sup>DN]
12. [.... KI.LAL] <sup>síg</sup>ħu-<sup>[</sup>ṣa-ni<sup>]</sup>-e <sup>[</sup>šá<sup>]</sup> [<sup>d</sup>DN]
13. [.... KI.LAL <sup>túg</sup>]su-[nu-ú šá <sup>d</sup>DN]
Edge
Rev.
```

```
14. [50 GÍN KI.LAL 10 ^{\text{síg}}]hu-sa-[ni-e] šá [^{\text{d}}I]M u ^{\text{d}}[\check{S}a-la]
           15. [\dots su]-ú-nu [x \ x] [x^1] [ma]-na dul-lu BABBAR-ú
           _____
           16. [....] <sup>r</sup>x<sup>1</sup> [....] šá ITI.DU<sub>6</sub>
           17. [....] \lceil x \rceil [....] \lceil^{m_1}Na-sir
           18. [....] <sup>r</sup>x<sup>1</sup> [x ITI.x U<sub>4</sub>.x.].KAM MU.[x.KAM]
           19. [KN LUGAL] E<sup>ki</sup>
[x mina(s), the weight of the lubār]u-garment for Šamaš with addition [of 30 shek-
els of the blue-pur]ple wool
2 minas, the weight of [..., the] sahses for Šamaš, [..., the] sūnu-belts for Šamaš
[1 mina, the we]ight of 10] sahses for Aya
[20 shekels, the we]ight of the sūnu-belts for Aya
[1 mina 20 shekels, the we]ight of the lubāru-garment for Bunene inc[luding
6 shekels of the blue-purple wool]
40 shekels, the weight of the sibtu-garment [for Bunene]
[1 mina, the weight of 10] the sahses for the Queen of Sippar
[1 mina, the weight of 10] the sahses for Anunītu
[20 shekels, the weight of] the sūnu-belt for [DN]
[...., the weight of] the sahs[es for DN]
[...., the weight of] the sūnu-belt for [DN]
[50 shekels, the weight of] the sahs[es for Adad and Šala
[\dots s\bar{u}]nu-belt [\dots mi]na(s) for white work
[....] month Tašrītu
[....] Nāṣir
[N<sup>th</sup> month, n<sup>th</sup> day, n<sup>th</sup>] year, [KN, king of] Babylon.
354. BM 99462 (83-1-21, 1824)
3.1 \times 3.8 cm
```

# 22.1.Cam [x]

1. [....]  $^{\Gamma}$ X¹.LÁ 2 ku-si-tu4
2. [....]  $^{meš}$   $\check{s}\check{a}$   $^{d}$ DUMU.MÍ  $\acute{E}$ -babbar- $^{\Gamma}$ ra $^{1}$ 

3. [....] *ku-lu-lu* ù <sup>túg</sup>*e-ir* 

4. [....] 「x <sup>1</sup> ½ ma-na KI.LAL

5. [.... hu-ṣ]a-an-ni a-na 6. [....] <sup>r</sup>x<sup>1</sup> a-na <sup>m</sup>Gi-mil-lu

7. [.... I]TI.BÁR U<sub>4</sub>.22.KAM

8. [MU.x.KAM] <sup>m</sup>Kam-bu-zi-ja

9. [LUGAL TIN.TIR<sup>ki</sup>] LUGAL KUR.KUR Rev.

[], 2 robes [] for the Daughters of the Ebabbar [, the lubār] kulūlu and erru-headbands [] [x1 30 shekels, the weight [] [ sas]hes for [] for Gimillu [ m]onth Nisannu, 22 <sup>nd</sup> day [n <sup>th</sup> year] of Cambyses, [king of Babylon], king o Lands.				
<b>355. BM 70309</b> (82-9-18, 10310) 4.8 × 5.5 cm	PLATE 81			
1. [ MU.SAG.NAM].LUGAL.LA [x x x x] TIN.TIR <sup>ki</sup> 2. [ eš-šu]-tu 3. [] <sup>r</sup> x¹ la-bir-ri 4. [] <sup>r</sup> x¹ PAP 9 GADA ina IGI <sup>m</sup> IGI- <sup>d</sup> EN-a- <sup>r</sup> dag-gal¹ 5. [] <sup>r</sup> šá¹ <sup>d</sup> A-nu-ni-tu <sub>4</sub> 6. [] šá <sup>d</sup> UTU 7. [] šá <sup>d</sup> Nin-ŠA 8. [] <sup>r</sup> šá¹ <sup>d</sup> IM 9. [] <sup>r</sup> šá¹ <sup>d</sup> Ša-la 10. [šá] <sup>rd</sup> ¹Bu-ne-ne				
Edge 11. [] <sup>rd</sup> Gu- <sup>r</sup> la¹ Rev. 12. [ <sup>d</sup> ] DUMU.MÍ. <meš> É-babbar-ra 13. [ ḥu-ul]-la-nu-ú 14. [ G] ADA ina IGI <sup>m</sup>Pa-ni- <sup>d</sup>EN-a-d[ag-gal]</meš>				
L. 1. TIN.TIR <sup>ki</sup> is written over an reverse				
[], the ac]cession year [of KN, king] of Babylon. [ ne]w [] used [], total 9 linen cloths at disposal of Pāni-Bēl-adaggal [] for Anunītu [] for Šamaš [] for Nin-ŠA [] for Adad [] for Šala [] for Bunene [] for J Gula [] for] the Daughters of the Ebabbar [] hullā]nu-cloaks				
[ li]nen cloths at disposal of Pāni-Bēl-adaggal.				

# 356. BM 49913 (82-3-23, 904) cf. Lorenz, No. 9

PLATE 82

 $2.8 \times 5.1$  cm

#### 14.6.Nbk 0

Up.edge Obv.

- 1. *mu-ṣi-*[*pi-ti* <sup>meš</sup>]
- Dbv. 2. 1 GADA *sal-hu* 3. 6 <sup>túg</sup>tu-<sup>Γ</sup>un-*š*ú<sup>1</sup>
  - 4. 2 TÚG.HI.A 「x¹-šú
  - 5. 1 IGI mu-și-e
  - 6. 3 *mu-ri-si*
  - 7. 1 *sib-tu*₄
  - 8. 1 TÚG.GÚ.UD.DU bir-mu
  - 9. 3 TÚG.BAR.SI
  - 10. [x] TÚG.ŠU<sup>ii</sup>
  - 11. [PAP x *mu-ṣ*]*i-pi-ti* г<sup>meš</sup>¬

Rev. Beginning uninscribed (ca. 2 lines)

- 12. [ITI].KIN U<sub>4</sub>.14.KAM
- 13. MU.SAG.NAM.LUGAL.「LAT
- 14. <sup>md</sup>AG-NÍG.DU-ÙRU
- 15. LUGAL ŠÚ

Note that the first line is written on the top edge enabling quick identification of the tablet.

L. 3. My copy of the line follows the reading by Lorenz 2009, No. 3.

L. 5. Cf Index s.v. pan muṣê. In BM 63922 (= 553): 2 (Nbn 15), CT 55, 528 (= 552): 2 (Nbn 15), BM 64099 (= 554): 3 (Dar 29) and maybe in BM 65133 (= 619): (Dar 31) it was destined for Šamaš. Nbn 664: 9-10 suggests that the pan muṣê could have been used as a cover for (Šamaš') parade wagon (½ ma-na 4 GÍN ¹par¹-[su šá] IGI mu-ṣe-e šá GIŠ.GIGIR, "34 shekels of the choice wool for ša pan muṣê for the wagon". Salonen, NUVI 3, p. 62 translates ša pan muṣê as "die Vorderseite des muṣû-Gewänder", which in light of other texts and especially the one published here cannot be accepted, i.e. (ša) pan is part of the full name ša pan muṣê. The presence of a naḥlaptu-cloak, a female garment, suggests that the text enumerated items both for male and female (gods or goddesses). According to VS 6, 16 the paršīgus were re-used for manufacturing a <pan> muṣê.

L. 6. This type of garment appears here for the first time.

L. 10. Such writing is not noted before. Probably ša qātē, cf. CAD Q 200 "hand towel"?

Garments: 1 linen tunics, 6 *tunšu*-covers, 2 *lubār* [x], 1 *pan muṣê*, 3 *murisus*, 1 *ṣibtu*-garment, 1 multicoloured *naḫlaptu*-cloak, 3 *paršīgu*-headdresses, [x] *ša qātē*, (total) [x gar]ments.

Month of Ulūlu, 14<sup>th</sup> day, the accession year of Nebuchadnezzar, king of the universe.

### 357. BM 60579 (82-9-18, 554)

 $3.9 \times 4.0$  cm

- 1. 1 GADA hu-ul-la-nu
- 2. 5 GADA kib-su

- 3. 6 GADA sal-hu
- 4. PAP 12 GADA [x] [*a-na*]
- 5. *pu-su-*Γ*ú*<sup>1</sup>
- 6. <sup>m</sup>ÌR-ja [<sup>lú</sup>mu-pa-ṣu-ú]
- 7.  $SUM^{in}IT[I.x]$
- 8. U<sub>4</sub>.10.KAM [MU.x.KAM]
- 9. dAG-I LUGAL TIN. TIR1. [KI]
- L. 4. The GADA is followed with a broken sign, which might be identified as n[ak, k[a or similar.

1 linen *hullānu-*cloak, 5 linen *kibsu-*fabrics, 6 linen tunics, total 12 linen garments were given [for] cleaning to Ardīya, [the cleaner?]. Month [of x], 10<sup>th</sup> day, [n<sup>th</sup> year] of Nabonidus, king of Babylon.

## 358. BM 101286 (83-1-21, 2947)

PLATE 82

 $5.0 \times 3.2$  cm

<sup>7</sup>4<sup>7</sup>.2.Nbn 9

- 1. 9 GÍN KI.LAL pa-tin-nu šá <sup>d</sup>UTU
- 2. 7 GÍN KI.LAL pa-tin-nu
- šá <sup>d</sup>Bu-ne-ne
- 4. [x GÍN] KI.LAL [pa-tin-nu]

Rest lost

Rev.

1'.[....] <sup>[</sup>ki<sup>?</sup>]

- 2'. [....] 「GÍN<sup>?</sup> x x x <sup>¬</sup> ina lìb-bi
- 3'. ½ GÍN KÚ.BABBAR *m*[*a-h*]*ir*
- 4'. ITI.GU $_4$  U $_4$ . $^{\rm r}$ 4'.KAM MU.9.KAM 5'.  $^{\rm md}$ AG-I LUGAL E $^{\rm ki}$

- 9 shekels, the weight of *patinnu*-belt for Šamaš 7 shekels, the weight of *patinnu*-belt for Bunene [x shekels], the weight of *patinnu*-belt [....]
- [....] including ½ shekel of silver was received. Month of Ayaru, 4<sup>th</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon.

# **359. BM 50282** (82-3-23, 1273)

PLATE 83

 $3.9 \times 6.0$  cm

- 1. GADA *šá dul-lu*
- 2. 5 GADA sal-ḥa šá <sup>d</sup>[UTU u <sup>d</sup>]<sup>r</sup>A¹-a
- 3. 4 KI.MIN *šá* <sup>d</sup>*Bu-n*[*e-ne*]

- 4.  $u^{d}$ DUMU.MÍ.ME  $\acute{E}$ -bab[bar-ra]
- 5. 3 gú-hal-șa 2 pa-tin-nu
- 6. 2 *ni-bi-hu*
- 7. 5 TÚG.GÚ.UD.DU.ME
- 8. 2 GADA kib-si
- 9. 2 TÚG.GÚ.UD.DU.<ME> šá $^{\rm d}$ GAŠAN  $\it Sip\mbox{-}[\it par\mbox{}^{\rm ki}]$

#### Rev. uninscribed

Cf. the similar texts ZA 4, No. 4 (= 176); BM 82581 (= 180); CT 55, 811 (= 182); BM 68361 (= 277).

The atypical numbers of garments for particular gods and goddesses should be noted: 5 *salhus* for Šamaš and Aya instead of 4; 4 for Bunene and the Daughters of the Ebabbar instead of one for each, i.e. a total 3 (one for Bunene, two for two Daughters). It is hardly possible to recognize in lines 5–6 the garments for the Queen of Sippar, because in the light of other texts such garments do not belong to her attire. The text is similar to the texts assigned to the group of the early *mihṣu tenû* texts, i.e. it should be dated to the end of Nabopolassar or early years of Nebuchadnezzar.

#### Knock-about cloths:

- 5 linen tunics for Šamaš and Aya
- 4 ditto for Bunene and the Daughters of Ebabbar
- 3 scarves, 2 patinnu-belts, 2 nēbeļu-belts, 5 naļlaptu-cloaks, 2 kibsu-fabrics (and)
- 2 nahlaptu-cloaks for the Queen of Sippar.

#### **360. BM 84149** (83-1-21, 1312)

PLATE 83

 $3.7 \times 2.9$  cm

<sup>[15]</sup>.[x].Nrg [x]

- 1.4 sal-h[u]
- 2. 8 *kib*-<sup>Γ</sup>*su*<sup>1</sup>
- 3. *a-na zi-ku-t*[ú]
- 4. a-na <sup>m</sup>Šu-la-a
- 5. <sup>lú</sup>pu-ṣa-a-a

Edge

6.  $SUM^{na}$ 

Rev.

- 7. IT[I.x] <sup>r</sup>U<sub>4</sub>. 15<sup>1</sup>.KAM
- 8. MU.[x. KAM]
- 9. <sup>md</sup>U+GUR-LU[GAL-ÙRU]
- 10. LUGAL [TIN.TIR<sup>ki</sup>]

Šulā, *pūṣaya* is identical with Šulā/Šamaš-šum-iddin, see Bongenaar, *Ebabbar Temple*, p. 351 and Zawadzki, *Garments of the Gods*, Vol. I, p. 231. Note that in result of new collation I suggest to read the date as <sup>1</sup>15<sup>1</sup>.

4 tunics, 8 *kibsu*-fabrics were given to Šulā, the washerman for cleaning. Month [x],  $15^{th}$  day,  $[n^{th}]$  year of Neriglis[sar], king [of Babylon].

# **361. BM 101467** (83-1-21, 3128)

 $3.5 \times 3.6$  cm

- 1. 1 *hu-la-*[*nu*]
- 2. 1 sal- $hi \lceil x \rceil [(x)]$
- 3. 1 sal-hi[(x x)]
- 4. GADA e-ri [(x)]
- 5. PAP 3 *ki*-[....]

Rev. 6. *ina* IGI <sup>md</sup> [HAR<sup>?</sup>]-[*ši-man*<sup>an</sup>-ni]

- 7. lúTÚG.KAL.KAL [SUM<sup>na</sup>]
- 8. ITI.BÁR U<sub>4</sub>.3.[KAM]
- 9. MU.42.KA[M]
- 10. rdAG¹-NÍG.DU-Ù[RU]

Edge 11. LUGAL TIN.TIR.[KI]

The total in l. 5 suggests that one of the garments mentioned before was not included to the total

1 *ḥullā*[nu]-cloak, 1 tunic, 1 [...] tunic, 1 linen *erru*-headband, total 3 .... at disposal of Bunene-[šimanni], the mender.

Month of Nisannu, 3<sup>rd</sup> day, 42<sup>nd</sup> year of Nebuchadnezzar, king of Babylon.

# **362. BM 73254** (82-9-18, 13265)

PLATE 84

 $5.8 \times 4.4$  cm

## 1.2.Nbn [7<sup>?</sup>]

- 1. 2 GADA sal-hi  $^{5}$ ? x x $^{1}$  [x x x]
- 2. šá <sup>d</sup>A-a 2-ta [GADA sal-hi 6]
- 3. na-hal-pa-a-tu4 2-ra1
- 4. ku-sa-tu<sub>4</sub> šá <sup>d</sup>GAŠAN.MEŠ
- 5. ina ŠU<sup>ii m</sup>It-ti-en-šú-<sup>d</sup>AG
- 6. 「a¹-na UD.<KIB>.NUN<sup>ki</sup>

Edge 7.  $[\check{s}]u$ -bu-ul

Rev. 8. ITI.GU<sub>4</sub> U<sub>4</sub>.1.KAM MU.6+ $^{1}$ <sup>?</sup><sub>1</sub>.KAM

9. <sup>md</sup>AG-I LUGAL <sup>r</sup>E<sup>1</sup>.[KI]

- L. 1. Probably  $\lceil 5$ -ta  $na^{\gamma}$ -[hal-pa-a- $tu_4$ ].
- L 3. Clearly *na-hal-pa-a-tu*<sub>4</sub> instead of *na-hal-lap-tu*<sub>4</sub>.
- 2 linen tunics, <sup>75<sup>?1</sup></sup> [*naḥlaptu*-cloaks] for Aya; 2 li[nen tunics, 6] *naḥlaptu* cloaks (and) 2 robes for the Ladies were brought to Sippar by Itti-enšu-Nabû. Month of Ayaru, 1<sup>st</sup> day, <sup>77<sup>?</sup>1th</sup> year of Nabonidus, king of Babylon.

# 363. BM 84500 (83-1-21, 1663)

PLATE 84

 $3.0 \times 3.3$  cm

$$13+x.[x x]$$

1'. 1 kib-su a-na

2'. dA-nu-ni-tu4

3'. 1 kib-su a-na

4'. dGu-la

Rev.

5'. PAP 4 kib-su 6'. a-[na] <sup>md</sup>UTU-NUMUN-GÁL<sup>ši</sup> 7'. <sup>lú</sup>rTÚG¹.BABBAR SUM<sup>in</sup>

8'. ITI.[x] <sup>[</sup>U<sub>4</sub>.13+x<sup>2</sup>KAM<sup>1</sup>

The presence of Šamaš-zēr-ušabši makes it possible to date the text to the time of Nabonidus, see Bongenaar, Ebabbar, p. 349 and Zawadzki, Garments of the Gods, Vol. I, p. 229.

[....], 1 kibsu-fabric for Anunītu, 1 kibsu-fabric for Gula, total 4 kibsu-fabrics were given to Šamaš-zēr-ušabši, the ašlāku. Month of [x], day  $13^{th} + [x ....]$ .

# 364. BM 84140 (83-1-21, 1303)

PLATE 85

 $3.8 \times 3.2$  cm

- 1. 40 ma-na KI.L[AL]
- 2. 9 *su-ba-*[*a-ti*]
- 3. šá ta-bar-ri  $[(\check{s}\acute{a}^?)]$
- 4. <sup>m</sup>DUB-NUMUN
- 5. a-na É-[babbar-ra]

Rev.

- 6. *it-ta-*[*din*]
- 7. *șu-ba-a-[ti šá]* 8. <sup>m</sup>Á*r-ra-b[i* <sup>lú</sup>TÚG.KAL.KAL SUM<sup>na</sup>] 9. ITI.GU<sub>4</sub> <sup>r</sup>U<sub>4</sub>.15<sup>?</sup> <sup>1</sup>.K[AM] 10. MU.6.KAM <sup>md</sup>AG-[I]

- 11. LUGAL T[IN.TIR]. 「KIT

40 minas of <wool>, the weight of 9 red şubātu-cloths, [(which)] Šāpik-zēri has delivered to the E[babbar] temple; the *ṣubātu-*cloths [were given to] Arrabi, [the mender]. Month of Ayaru, 15<sup>?th</sup> day, 6<sup>th</sup> year of Nabo[nidus], king of Ba[bylon].

**365. BM 63909** (82-9-18, 3877) = Bertin 1292

 $4.8 \times 3.7$  cm

#### 12.6.Nbn 5

- 1. 1 GADA sal-hi ir-bi šá ina UGU
- 2. KI.ZÁLAG.GA i-ru-bu

- 3. ku-mu sal-hi šá GIŠ.GU.ZA
- 4. šá a-na ki-ba-su SUM<sup>na</sup>
- 5. a-na <sup>m</sup>Ar-ra-bi
- 6. lúTÚG.KAL.KAL a-na
- 7. GIŠ.GU.ZA SUM $^{in}$

Rev.

- 8. ITI.KIN U<sub>4</sub>.12.KAM MU.5.KAM 9.  $^{\rm md}$ AG-I LUGAL TIN.TIR $^{\rm ki}$

The Akkadian equivalent of KI.ZALÁG.GA is not known to me, maybe a part of temple or storehouse. The kibāsu is treated as a broken Plural of kibsu (kind suggestion of John Mac-Ginnis).

1 linen tunic (from) the *irbu*-income which entered KI.ZALÁG.GA, (and) instead of tunic (used as cover) for throne was given to Arrabi, the mender, (to make) kibsu fabrics for the throne?.

Month Ulūlu, 12<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, king of Babylon.

### **366. BM 66582** (82-9-18, 6575)

 $5.6 \times 2.3$  cm

- 1. GADA *šá a-na bat-qa a-na* <sup>m</sup>*Ar-rab* <sup>lú</sup>TÚG.KAL.KAL
- 2. SUM<sup>na</sup> ITI.GU<sub>4</sub> U<sub>4</sub>.21.KAM MU.3.K[AM ....]
- -----
- 3.  $\lceil 9^{?_1} \text{ GADA } sal\text{-}hu 9 \text{ GADA } \lceil na^{?}\text{-}x^{1}\text{-}[...]$
- 4. [a]-[na] bat-[a] [...]

Rest lost

L. 3. At the beginning of line the numeral 6 is preserved, but most probably there was an additional row, now broken. The partly preserved na is followed with a horizontal wedge in the upper part of the line.

Linen garments, which were given for repair to Arrabi, the mender. Month of Ayaru, 21<sup>st</sup> day, 3<sup>rd</sup> year [....]

<sup>1</sup> linen tunics, 9 linen [....] for repair [....].

# **367. BM 61942** (82-0-18, 1911)

PLATE 85

 $5.4 \times 8.05 \text{ cm}$ 

4.2.Dar [x]

- 1. 12 *ka-b*[*a-ri* ....]
- 2. [šá <sup>md</sup>H]AR-ši-man-a[n-ni SUM<sup>na</sup>]
- 3. [ITI.GU]<sub>4</sub> UD.4.KAM [MU.x.KAM]
- 4.  $[^{m}Da]$ -ri- $[\check{s}\check{u}]$  LUG[AL KUR.KUR]

-----

5. [1 GAD] A hu-la-nu šá  $^{\rm d}$ UTU

Rev.

```
6. [\dot{u}] 1 GADA hu-la-nu <ina> ITI.[x]
  7. it-ta-din <sup>m</sup>Ki-na-a <sup>1</sup>[<sup>ú</sup>x]
  8. PAP 2 GADA hu-la-nu id-din-nu
  9. 7 GADA sal-hu šá <sup>d</sup>UTU
10. 1 GADA ḫu-la-nu šá <sup>d</sup>ḤAR
11. <sup>r</sup>2 <sup>1</sup> GADA sal-ḫu šá <sup>d</sup>G[u-la]
12. [^{md}H]AR-\check{s}i-man^{an}-n[i]
13. [i]t-ta-din
14. <sup>[2]</sup>4 GADA ka-ba-r[i]
15. KI.LAL 1^{en} \check{s}id-d[u]
```

Rest uninscribed

16. it-ta-din

- Ll. 6-7. There is no space for a personal name in line 6. It seems that in 1. 7 the scribe wrote the words in wrong sequence.
- L. 8 and 15. There is no place for the personal names there. In l. 16 most probably Bunenešimanni is meant, but who in 1. 8
- L. 11 The reading of the god's name is highly uncertain.
- 12 (minas?) of thi[ck] (linen) [Bu]nene-šiman[ni has given?. Month Ayar]u, 4th day, [n<sup>th</sup> year of Da]rius, kin[g of Lands].

[1 line]n hullānu-cloak for Šamaš

and 1 linen *hullānu*-cloak in/from the month [x] Kinā, the [...] has given.

-----

Total 2 linen *hullānu*-cloaks he has given

- 7 linen tunics for Šamaš
- 1 linen *hullānu*-cloak for Bunene
- 2 linen tunics for G[ula<sup>?</sup>] [Bu]nene-šimanni has given.
- 24 thick linen skeins, the weight of šiddu-curtain he has given.

# **368. BM 53001** (82-3-23, 4035)

 $3.2 \times 2.2 \text{ cm}$ 

```
1'. TÚG.HI.「A ku-lu-lu šá¹ [....]
```

2'. šá <sup>d</sup>Bu-ne-ne [....]

3°. TÚG.ḤI.A me-ta TÚG.ḤI.A [ku-lu-lu]4°. šá  ${}^{\dot{a}}$ IM

5'. [x x x x x]. MEŠ

Rest lost

Rev.

1'. TÚG.BAR.DUL TÚG.NÍG.Í[B.LÁ.(MEŠ)]

2'. 3 TÚG.BAR.SI [....]

3'. TÚG.HI.A *ku-lu-lu* [....]

4'. *šá* <sup>d</sup>[DN]

Rest lost

[....], the  $lub\bar{a}r\ kul\bar{u}lu$ -headband of [....] for Bunene [....], the  $lub\bar{a}r\ m\bar{e}tu$  (and)  $lub\bar{a}r\ [kul\bar{u}lu]$ -headbands for Adad

[....] robe, the sas[h(es)], 3  $par\check{s}\bar{t}gu$ -headdresses [....], the  $lub\bar{a}r$   $kul\bar{u}lu$  [(and)  $lub\bar{a}r$   $m\bar{e}tu$ ]-headbands for [DN].

### 369. BM 68902 (82-9-18, 8901)

 $6.4 \times 5.2 \text{ cm}$ 

# 8.<sup>7</sup>2<sup>?</sup>1.Nbn 12

- 1. [TÚG.ḤI.A šá] lúUŠ.BAR GADA id-di-nu
- 2. [ITI.GU]<sub>4</sub> U<sub>4</sub>.8.KAM MU.12.KAM <sup>d</sup>AG-I [LUGAL *Bābilî*<sup>ki</sup>]

3.	[ḫ]u-la-nu	sal-ḫi	kib-su		
4.			<sup>md</sup> ḤAR-DÙ a-na za-ki-ú		
5.	1		<sup>m</sup> Ba-zu-zu		
6.	1		$^{\text{md}}$ UTU-SIPA-[ $u$ ]- $a$		
7.	1		<sup>md</sup> AG-DA		
8.	1		<sup>md</sup> EN-MU A <sup>m</sup> TIN		
9.	1		<sup>md</sup> UTU-ŠEŠ-MU		
10.	3	1	A <sup>md</sup> ḤAR-DÙ		
11. [.	11. [] 1 <sup>m</sup> La-ba-ši				
12.			A <sup>m</sup> Šu-la-a		
13.			<sup>md</sup> UTU-KAM		
14.			<sup>r</sup> x x x <sup>1</sup> din (erased <sup>?</sup> )		
15. [] <sup>r</sup> x x <sup>1</sup> .MEŠ 1 GADA <i>ḫu-ul-la-nu</i> <sup>m</sup> Lib-luṭ					
16. [U]D (or $n$ ] $a$ ) $\lceil 2 \rceil$ $\lceil GADA \rceil$ $sal-hi$ $A^{!m}U\check{s}-\check{s}a-a-a$					
17. [.	] <i>šá</i> <sup>d</sup> ḤAR		mdUTU-SIPA!-u-a		
18. [] <sup>[9]</sup> GADA <sup>lú</sup> qal-la šá <sup>m</sup> KAR- <sup>d</sup> EN					
19. [.	]		「x <sup>1</sup> din PAP <sup>?</sup> x		
20. [.	]		ina lìb-bi		
21. []- <i>nu</i> 4 GADA <i>sal-hi</i> 「x ¬					
22. [.	<sup>m</sup> ] <sup>d</sup> ḤAR- <i>ši-ma</i>	n-ni []			

- Ll. 9–10. Šamaš-aḥ-iddin/Bunene-ibni, most probably identical with Šamaš-aḥḥē-[iddin]/Bunene-ibni, the linen weaver known from three previously published texts (Bongenaar, *Ebabbar*, p. 343). The question is why the information about 2 *salḥus* is divided into two lines. The same situation concerns Liblut/Uššaya (Il. 15–16). All persons mentioned in the texts, except for Mušēzib-Bēl (l. 18) are well known linen weavers, see Bongenaar, *Ebabbar*, chap. IV.2
- L. 14 looks like consciously erased.
- L. 17. The second sign of the name is atypical and I decided to emend it to SIPA.

[The garments, which] the linen weavers have delivered. [Month of Aya]ru², 8<sup>th</sup> day, 12<sup>th</sup> year of Nabonidus, [king of Babylon].

```
[h]ullānu-cloaks tunics kibsu-fabrics
                               Bunene-ibni, for cleaning
                1
                               Bazuzu
                               Šamaš-rē'ua
                               Nabû-ile'i
                               Bēl-iddin, son of Balāţu
                               Šamaš-ah-iddin,
                 1
                               son of Bunene-ibni
                 1
                               Labāši,
           [....]
                         1
                               son of Šūla
                               Šamaš-ēreš
[....], 1 linen hullānu-cloak (from) Liblut,
[....], 2 tunics
                               son of Uššaya
[....] for Bunene (from) Šamaš-rē'ua
[....] 9 linen (garments) (for?) the slave of Mušēzib-Bēl [....]
[.... in addition to [....] 4 tunics [....] (to) Bunene-šimanni.
370. BM 61364 (82-9-18, 1338)
                                                                                     PLATE 86
6.3 \times 4.3 \text{ cm}
             1. 19 hu-ul-la-nu ina lìb-bi 5 eš-šú
             2. ina 1<sup>en</sup> na-ak-ma-ru
             3. 20 sal-hi eš-šu 2-ú na-ak-ma-ru
             _____
             4. 3 sal-hi eš-šú 3-šú na-ak-ma-<sup>r</sup>ru<sup>1</sup>
             _____
             5. [x GADA sal-h]i pe-tu-ú šal-šú na-a[k-ma-ru]
Rest lost
Rev.
             1'. [x GADA sa]l-ḥi <sup>r</sup>šá x<sup>1</sup> [....]
             2'. [x GADA s]al-hi šá bat-「qu¹ [....]
             3'. [x x] ħu-ul-la(T: 1)-nu šá <sup>d</sup>[x (x)]

4'. [4 GADA] sal-ḥi šá <sup>d</sup>UTU u <sup>d</sup>A-a

5'. <sup>[2]</sup> GADA sal-ḥi šá <sup>d</sup>Gu-la

6'. [1]<sup>en</sup> ħu-ul-la-nu šá <sup>d</sup>Bu-ne-<sup>[ne]</sup>
             7'. PAP 14 GADA ina IGI <sup>md</sup>UTU-it-ti-iá
L. 5. šal-šu is probably a scribe's mistake for 4-šú "fourth".
```

L. 7'. Šamaš-ittīya is noted here for the first time and because he co-operates with Arrabi, the mender, he belonged most probably to the same professional group. The presence of Arrabi makes it possible to suggest that the text was composed in the period between the beginning of Nabonidus' reign and the 4<sup>th</sup> year of Cambyses, see Bongenaar, *Ebabbar*, *p*. 317.

19 *hullānu*-cloaks, among them 5 new (placed) in the first basket.

20 new tunics in the second basket.

-----

3 new tunics in the third basket.

\_\_\_\_\_

[x] open [linen tun]ic in the third basket.

[x linen tu]nic [....]

[x linen] repaired [tu]nic [....]

[x] *hullānu*-cloak for [....]

[4 linen] tunics for Šamaš and Aya

<sup>7</sup>2<sup>1</sup> linen tunics for Gula

1 hullānu-cloak for Bunene,

total 14 linen tunics at disposal of Šamaš-ittīya and Arrabi.

### 371. BM 65259 (82-918, 5244)

PLATE 86

 $4.7 \times 3.1$  cm

- 1. <sup>r</sup>i¹-na 11 GADA *hu-la-nu*
- 2. šá ina nak-ma-ri šak-nu ina lìb-bi
- 3. 2 GADA hu-la-nu [x] [IGI] mu-și-e
- 4. SUM<sup>in</sup> 2 šá bat-qa šá ú-ri-du
- 5. ina IGI <sup>md</sup>ḤAR-ši-man-ni <sup>lú</sup>T[ÚG.KAL.KAL]
- 6. a-na bat-qa ITI.ŠU U<sub>4</sub>. [6].KAM<sup>1</sup>
- 7. MU.15.KAM <sup>md</sup>AG-I
- 8. LUGAL E<sup>ki</sup>

Rev. uninscribed

- L. 3. Or: 2 GADA *ḥu-la-nu* [šá] IGI *mu-ṣi-e*, "2 *hullānu-*cloaks [for] *pan muṣê-*cover."
  L. 5. *uridu*, see p. 433 s.v. (*w*)*arādu*, meaning 2. "of parts of the body, clothing "hang down,
- L. 5. *uridu*, see p. 433 s.v. (*w*)*arādu*, meaning 2. "of parts of the body, clothing "hang down, droop".
- L. 7. The second element of the king's name is written over erasure.

Out of 11 linen  $hull\bar{a}nu$ -cloaks which were placed in the basket, 2  $hull\bar{a}nu$ -cloaks (and) [x]  $pan m\bar{u}s\hat{e}$ -cover were given. 2 with damaged uridu are at disposal of Bunene-simanni, the m[ender] for repair.

Month of Du'ūzu, 6<sup>th?</sup> day, 15<sup>th</sup> year of Nabonidus, king of Babylon.

## **372. BM 66445** (82-9-18, 6438)

 $4.4 \times 2.6$  cm

- 1. <sup>[5]</sup> GADA sal-hu 1 GADA hu-la-nu
- 2. [x+] 4 GADA  $e\check{s}$ - $\check{s}\acute{u}$  x (er.)  $\check{s}\acute{a}$  du [x] [....]

- 3.  $\begin{bmatrix} {}^{m} \hat{\mathbf{I}} \end{bmatrix} \mathbf{R} ja \stackrel{\langle 1\acute{u} \rangle}{} mu pa şu u$
- 4. [n]a- $\check{s}\acute{a}$ - $\dot{i}$  [x] [...]
- 5.  $[x \ x] [x] [...]$

Rest lost

Rev. 1'. ITI.SIG<sub>4</sub> U<sub>4</sub>.25.KAM MU 10+[x<sup>?</sup>.KAM]

2'. [md] AG-I LUGAL TIN.TIRki

5 linen tunics, 1 linen hullanu-cloak, [x]+4 new linen [..., Ardīya, the cleaner has brought [....].

Month of Simanu, 25<sup>th</sup> day, year 10+[x] of Nabonidus, king of Babylon.

## 373. BM 61459 (82-9-18, 1433)

PLATE 87

 $5.6 \times 4.6$  cm

#### 25.2.Dar 18

- 1. 5 GADA sal-hu 14 GADA ki[b-su]
- 2. [šá] <sup>md</sup>UTU-MU-MU <sup>lú</sup>TÚG.BABBAR *it-[ta-din]*
- 3. ina lìb-bi 1 GADA sal-ḫu 「a-na¹ ÚR.[MEŠ]
- 4. šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> SUM<sup>nu</sup>
- 5. [1] GADA sal-hu 6 kib-su i-na
- 6.  $[x(x)]^{\lceil lu^2 \rceil}$ -ba-ru 2 GADA sal-hu
- 7. [x x x] [x] a-na bat-qa
- 8. [x x x x ki]b-su 5-ta

Edge 9.  $[\mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x}]^{\mathsf{T}} \mathbf{x}^{\mathsf{T}} \mathbf{2}^{\mathsf{T}} kib^{\mathsf{T}} - [su]$ 

Rev.

- 10. [x x x] <sup>[</sup>x<sup>]</sup> qa a-na
- 11. [x lúTÚG]. KAL KAL MEŠ SUM [na]
- 12. [PAP x GADA ki]b-su šá MU.17.<KAM> 1 GADA kib-su
- 13. [šá] MU.18.<KAM> i-na IGI <sup>md</sup>UTU-MU-M[U]

Blank space for one line

- 14. ITI.GU<sub>4</sub> U<sub>4</sub>.25.KAM
- 15. MU.18.<KAM> <sup>m</sup>Da-ri-uš-šú
- 16. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.K[UR]
- L. 3. Compare Nbk 312 (= 312): 24 and Cam 148 (= 315): 8–10: 1 GADA  $kib\text{-}su\ \check{s}\acute{a}$  ÚR.(MEŠ).
- 5 linen tunics, 14 linen ki[bsu]-fabrics, [which] Šamaš-šum-iddin, the  $a\bar{s}l\bar{a}ku$  has delivered, including 1 tunic for  $s\bar{u}nu$ -belt[s] for the Queen of Sippar was given.
- [1] linen tunic, 6 kibsu-fabrics [....]
- 2 linen tunics, [....] for the repair of [.... ki]bsu-fabric, 5 [....], 2 kib[su]-fabrics [.... for x] menders were given, [total x linen ki]bsu-fabrics for 17<sup>th</sup> and 1 linen kibsu-fabric for 18<sup>th</sup> [ye]ar at disposal of Šamaš-šum-id[din].

Month of Ayaru, 25<sup>th</sup> day, 18<sup>th</sup> year of Darius, king of Babylon, king of the Lands.

### 374. BM 64903 (82-9-18, 4884)

 $2.8 \times 4.5$  cm

# [x].1.Cyr 4

- 1. mu-sip-tu<sub>4</sub> šá a-na
- 2. su-ni-e na-šá-a
- 3. ITI.[B]ÁR [U<sub>4</sub>.x.K]AM MU.4.KAM
- 4. <sup>m</sup>Ku-raš LUGAL E<sup>ki</sup>
- u KUR.KUR

- 6. 2 ma-na <sup>m</sup>[Ba]-<sup>r</sup>la<sup>1</sup>-ṭu 7. 4 ma-na <sup>m</sup><sup>r</sup>Na<sup>1</sup>-din

L. 6. It is impossible to identify Balātu with Balātu, son of Nabû-bēl-šumāti, išparu (see Bongenaar, Ebabbar, p. 320f), because he disappears in the 4th year of Nabonidus. Maybe we can recognize in him Balāṭu (written regularly TIN-su) the išpar kitê, known from the texts dated to the time of Nebuchadnezzar, see Bongenaar, Ebabbar, p. 320. L.7. Nādin, maybe Nādin, the išpar kitê, see Bongenaar, Ebabbar, p. 338.

Piece of cloth which was withdrawn for (making) the *sūnu*-belts. Month of [Nisa]nnu, [n<sup>th</sup> da]y, 4<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

2 minas (for?) Balāţu

4 minas (for?) Nādin.

#### 375. BM 77920 (85-4-30, 113)

 $5.5 \times 4.2$  cm

#### 9.[x.x]

- 1. [x ma]-na 5 GÍN KI.LAL TÚG. [BAR.x]
- 2. [x x d]ul-lu-šú šá <sup>md</sup>UTU-MU-MU 3. [x x] 1/3 GÍN KI.LAL <sup>túg</sup>par-ši-gu
- 4.  $[x x x] \lceil x \rceil u ku-lu-lu \check{s} \acute{a}^{d} \lceil A-a \rceil$
- 5.  $[x \times x \times x]^{-1}MU^{1}$  it-ta-din
- 6. [ITI.x U<sub>4</sub>]. [9]. KAM
- 7. [MU.x.KAM KN]

8. [LUGAL E<sup>ki</sup> LUGAL KUR].KUR Rev.

- L. 1. At the end of the line the remains of vertical and horizontal strokes are preserved, which makes it possible to recognise here SI or DUL<sub>8</sub>.
- L. 4. The first preserved sign might be  $\delta u$  or the remains of another sign, e.g. r]i. DINGIR is followed with the upper parts of two vertical strokes in a small distance, most probably  $\lceil A-a \rceil$ . L. 7. I suggest reconstructing this line because there is not enough space for the king's name in the last line.

[x mi]na(s) 5 shekels (of wool), the weight of [..., the w]ork of Šamaš-šum-iddin;

[x mina(s)] 20 shekels (of wool), the weight of  $par \tilde{s} \bar{t} g u$ -headdress(es) [....] and  $(lub \bar{a} r) ku l \bar{u} l u$ -headband for Aya [were given to x]-iddin. [Month of x],  $9^{th}$  [day, year x of KN, king of Babylon, king of La]nds.

#### 376. BM 79711 (89-10-14, 260)

 $5.8 \times 3.8$  cm

#### 13.8.Dar 28

- 1. 1 GADA hu-la-nu eš-šú
- 2. a-na ITI.APIN MU.28.KAM
- 3. <sup>m</sup>Za-bi-ni it-ta-din
- 4. 1 GADA sal-<hi> eš-šú šá a-na
- 5. pi-su-i <sup>r</sup>x<sup>1</sup> ina ITI.GU<sub>4</sub>
- 6. MU.28.KAM šá ina IGI
- 7. <sup>md</sup>EN-it-tan!-nu ù

Rev.

- 8. 1 GADA sal-hu eš-šú TA
- 9. šad-da PAP 2 GADA sal-hu
- 10. a-na te-nu-ú a-na
- 11. dGAŠAN UD.KIB.NUN<sup>ki</sup> SUM<sup>na</sup>
- 12. 「GADA<sup>1</sup> hu-la-nu te-nu-ú
- 13. ina šad-da šá <sup>d</sup>AG i-kal-la
- 14. U<sub>4</sub>.13.KAM MU.28.KAM
- 15. <sup>m</sup>Da-ri-mu-šú LUGAL KUR.KUR

1 new *hullānu*-cloak for the month of Arahsamna, 28<sup>th</sup> year, Zabīnu has delivered; 1 new tunic for cleaning? for the month of Ayaru, 28<sup>th</sup> year, which is at disposal of Bēl-ittannu and 1 new tunic from the chest, total 2 linen tunics for the change for the Queen of Sippar were given.

The linen *ḫullānu*-cloak (for) the change is *deposited*? in the chest of Nabû?. 13<sup>th</sup> day, 28<sup>th</sup> year of Darius, king of Lands.

#### **377. BM 99535** (83-1-21, 1897)

 $4.3 \times 2.8$  cm

- 1'. 'x GÍN a-na ta\-hap-šú
- 2'. [<sup>m</sup>R]i-ḫi-tu u <sup>lú</sup>ERÍN.MEŠ-šú SUM<sup>in</sup>
- 3'. [x GÍN] SÍG.ZA.GÌN.KUR.RA 2 ma-<sup>r</sup>na<sup>1</sup> [<sup>na4</sup>gab]-<sup>r</sup>bu<sup>1</sup>-ú
- 4'. [a-na] dul-lu šá ni-bi- $\lceil hu$  $\rceil$ [(meš)]

Rev.

- 5'. [šá] <sup>d</sup>UTU u <sup>d</sup>ḤAR
  - 6'. [m] Ri-hi-e-tu u [úER[ÍN.MEŠ-šú]
  - 7'.  $[SUM^i]^n$

Free space

8'. [x x] [....]

```
L. 2' and 6'. Rēḥētu, see Bongenaar, Ebabbar, p. 340 f. L. 8'. Maybe 'ITI.ŠE'.
```

x shekels (of wool<sup>?</sup>) for the *taḥapšu* (to) Rēḫētu and his workers were given; [x shekels] of blue-purple wool, 2 minas of alum for manufacturing of *nēbeḥu*-belt [for] Šamaš and Bunene [were giv]en to Rēḫētu and [his wor]kers. [....].

```
378. BM 66459 (82-9-18, 6452)
```

 $4.9 \times 3.6$  cm

```
1'. 1/3 4 GÍN 「KI」.[LAL ....]
```

2'. 8 GÍN KI.LAL [....]

3'. TÚG.SÍG.ZA.GÌN.<KUR>.RA šá [....]

4'. 57 GÍN KI.LAL 3 <sup>túg</sup>par-si-g[u<sup>meš</sup>....]

5'. 1<sup>en</sup> TÚG.HI.A ku-lu-lu TÚG.SÍG.ZA.GÌN.[<KUR>.RA šá ....]

6'. 57 GÍN KI.LAL 2-ta TÚG.BAR.DUL<sub>8</sub>.ME[Š (x x x)]

7'. 「TÚG¹.SÍG.HÉ.ME.DA šá <sup>d</sup>DUMU.MÍ.M[EŠ É-babbar-ra]

Rev. 8'. 17 GÍN KI.LAL TÚG.ḤI.A ku-lu-[lu x x x x])

9'. TÚG.SÍG.ZA.GÌN.<KUR>.RA šá <sup>d</sup>IM [(x x)]

10'. ½ ma-na 2 GÍN KI.LAL TÚG.ḤI.A [ku-lu-lu]

11'. 3 túg par-si-gu meš [TÚG].SÍG.ḤĚ.M[E.DA]

12'. šá <sup>d</sup>Ša-la

13'. PAP [x] ma-na [....]

14'. [x x]  $u/10^{\lceil x \rceil}$  [....]

#### Rest lost

24 shekels, the wei[ght of ....]

8 shekels, the weight [....] of blue-purple wool ....]

57 shekels, the weight of 3 *paršīgu*-headdresses, [....], 1 *lubār kulūlu*-headband of blue-purple wool [....]

57 shekels, the weight of 2 robes [(....)] of red wool for the Daughters of [Ebabbar];

17 shekels (of wool), the weight of  $lub\bar{a}r\ kul\bar{u}lu$ -headdress, [....] of blue-purple wool for Adad

32 shekels of wool, the weight of  $lub\bar{a}r$  [ $kul\bar{u}lu$ ]-headdress, 3 red  $par s \bar{i} gu$ -headdresses for S ala,

total [x] minas [....

# XV. Issue of (white) wool for the manufacture of the garments for the gods

379. VS 6, 8; cf. NUVI 3, No. 236

15.7.Nbp 9

- 1. 2 GÚ.UN SÍG.ḤI.A  ${}^{\rm m}$ BA  ${}^{\check s\acute a}$  a  ${}^{\rm l\acute u}$ UŠ.BAR 2. 2 GÚ.UN 40 ma-na  ${}^{\rm m}$ Du-muq
- 3. 10 ma-na <sup>m</sup>NUMUN-ú-tu
- 4. lúṣa-pu-ú a-na
- 5. șu-bi-ti

2 talents of wool (for) Iqīša, the weaver; 2 talents 40 minas (for) Dummuqu;

10 minas (for) Zērūtu, the dyer for dying.

**380. BM 50293** (82-3-23, 1284)

 $6.5 \times 4.2 \text{ cm}$ 

15.5.Nbp 11

1. 3 GÚ.UN SÍG.ḤI.A <sup>m</sup>Du-m[uq] Obv.

2. ina ha-a-ṭu šá MU.11.KAM

a lot of free space

3. ITI.NE  $U_4.1^{\dagger}9^{\dagger}$ .KAM MU.11. $^{\dagger}$ KAM $^{\dagger}$ Rev.

4. mdAG-A-ÙRU

E. Leichty in Catalogue of the Babylonian Tablets in the British Museum, vol. VI: Tablets from Sippar 1, p. 30 suggests to read "year 10", however, 11 is certain.

3 talents of wool (for?) Dumuqu, from the supply of the eleventh year. Month of Abu, 19<sup>th</sup> day, 11<sup>th</sup> year of Nabopolassar.

381. BM 49669 (82-3-23, 660)

PLATE 87

 $4.5 \times 2.2$  cm

7.9.<Nbp> 11

- 1. 4 GÚ.UN 56 2/3 ma-na
- 2. a-di ta-kil-tu
- 3. gi-nu-ú šá  ${}^{\mathrm{m}}\mathrm{BA}^{\check{s}\acute{a}}$ -a

4. ITI.GAN U<sub>4</sub>.7.KAM MU.11.KAM Rev.

Iqīša,  $išp\bar{a}ru$  was active between Šši 0 and Nbp 11, see Bongenaar, p. 322. The dating to the time of Nabopolassar supports also the use of the term  $gin\hat{u}$ , replaced from the beginning of Nebuchadnezzar by the term sattukku.

4 talents, 56 minas 40 shekels, including blue-purple wool, the regular offering of Iqīša.

Month of Kislīmu, 7<sup>th</sup> day, 11<sup>th</sup> year.

#### **382. BM 50623** (82-3-23, 1614)

PLATE 88

 $6.1 \times 3.8$  cm

<->.3.<Nbp> 13

- 1. 1 GÚ.UN 45 ma-na SÍG.HI.A <sup>md</sup>AG-[x x]
- 2. *šá* ITI.ŠE *ih-ti-it*
- 3. *šá* 2/3 *ma-na* <sup>[4]</sup> [GÍN] SÍG.ḤI.A *e-ṭir*

.\_\_\_\_\_

- 4. 1 GÚ.UN [31 ma-na SÍG.Ḥ]I.A 「šá¹ ITI.「BÁR¹
- 5. 2 GÚ.UN <sup>[6]</sup> ma-[na x x] šá SÍG.HÉ.<ME>.DA
- 6. PAP 3 GÚ.UN 37 ma-na SÍG.[HI.A]
- 7.  $^{\text{md}}$ AG-NUMUN-DÙ A- $\check{s}\acute{u}$   $<\check{s}\acute{a}$   $^{\text{m}}>$ Pu-uh-hu-ru

Edge 8. ITI.SIG<sub>4</sub> MU.13.<KAM>

8a. 4 ½ MA AN.BAR <sup>md</sup>AG-「A¹-PAP

8b. 32 *ma-na* 

Rev. 9. PAP 5 GÚ.UN 14 ma-na SÍG.HI.A <sup>m</sup>Du-muq

10. *gi-nu-*Γ*ú*<sup>1</sup>

11. 2 GÚ.UN 17 ma-na šá KÙ.BABBAR <sup>m</sup>Du-muq U<sub>4</sub>.<sup>[2]</sup>.KAM

12. 1 GÚ.UN <sup>m</sup>Du-muq šá KÙ.BABBAR U<sub>4</sub>.3.KAM

13. PAP 8 GÚ.UN 31 ma-na <sup>m</sup>Du-muq

L. e. 14. 1 GÚ 53 ½ 4 [....]

15. 3 GÚ 58 [x] 50

L. 5. The gap between ma- and SÍG is large and has to be filled with [na] and at least two additional signs.

Lines 8a and 8b and 14–15 were written later, and the signs are very small.

The total sum mentioned in 1. 9 has to result from the addition of 1. 6 and 8 and 8b, however, it gives only 4 talents and 13 minas. The second total (1. 13) includes the sum of lines 9, 11 and 12.

The sense of lines 14 and 15 is not clear for me.

1 talent 45 minas of wool Nabû-[xx] has weighed in the month of Addaru; for it  $4^{7}4^{7}$  shekels of wool is paid.

<sup>1</sup> talent [31 minas of wo]ol of the month Nisannu;

<sup>2</sup> talents 6 minas [....] of red wool, total 3 talents 37 minas of wo[ol] (from) Nabû-zēr-ibni, son of Puḥḥuru; month of Simanu, 13<sup>th</sup> year.

<sup>4</sup> ½ minas of iron? (from) Nabû-apal-uşur

32 minas

total 5 talents 14 minas of wool (for) Dummuqu (as) regular offering 2 talents 17 minas (bought for?) silver (for) Dummuqu (on) the 2<sup>nd</sup> day 1 talents (for) Dummuqu (bought for) silver (on) the 3<sup>rd</sup> day, total 8 talents 31 minas (for) Dummuqu 1 talents 53 (minas) 34 [shekels<sup>?</sup>] 3 talents 58 (minas) [x] 50 (shekels).

The logic of the text is difficult to understand, mostly because of the bureaucratic character of this report, written in a department where the obligations of persons mentioned in the text were well known. For this reason not all the numerals can be explained, i.e. we do not know how the accountant reached the sum of 5 talents 14 minas of wool in line 9. It is certain at least that the sum is not the result of adding the data from 1. 1 with the figures from line 6. The interpretation of lines 8a and 8b added between previously written lines and lines 14 and 15 is also unclear.

The presence of Dummuqu, the person responsible for the manufacture of the garments for Šamaš and some items for other gods in the time of Nabopolassar's, and the beginning of Nebuchadnezzar's, rule helps to understand the text. His activity as a prebendary weaver is supported by the use of the term ginû, describing the wool at the disposal of the prebendary weaver destined for manufacturing sacred garments for the gods. The amount enumerated in Il. 11–12 and described with the ambiguous expression ša kaspi is also destined for fulfilment of Dummuqu's prebendary obligation because they are subsumed in line 13 together with the wool described with the term ginû. The description ša kaspi probably means that this wool comes not from the temple's herds but that it was bought at the market. 8 talents 31 minas wool would be obtained from ca. 340 adult sheep (90 shekels of wool from each adult sheep).

# 383. BM 50963 (82-3-23, 1958)

PLATE 89

 $3.7 \times 4.1 \text{ cm}$ 

2.3.[Nbp] 1[6<sup>?</sup>]

```
1. SÍG.ḤI.A ha-a-tu ^{l\acute{u}} [BAR.MEŠ SUM^{na}]
```

- 2. 7 GÚ.UN 35 ma-[na SÍG.ḤI.A]
- 3. *šá* TÚG.MÁŠ.MEŠ *šá* <sup>d</sup>UTU [*ù*]
- 4. *šá* <sup>d</sup>*Bu-ne-ne* TÚG.[....]
- 5. TÚG SIG<sub>5</sub>.MEŠ *šá* <sup>d</sup>UTU <sup>d</sup>[DN]
- 6. [TÚG m]e-e<sup>1</sup> SAG šá <sup>d</sup>UTU [x][...] 7. [x x x]. [MEŠ TÚG x][....]

Rest lost

Rev.

- 1'. [....]「UD<sup>?</sup>.A¹ [....] 2'. 「šá <sup>d</sup>¹UTU u <sup>d</sup>A-「a¹
- 3'. *šá* MU.15.KAM MU.1[6<sup>?</sup>.KAM]
- 4'. PAP 18 GÚ.UN 5 [ma-na SÍG.HI.A]

- 5'. <sup>túg</sup>ni-bi-ḥu šá iz-<sup>r</sup>ḥi<sup>¬</sup> šá <sup>rd¬</sup> [UTU<sup>?</sup>]
- 6'. TÚG.BAR.SI šá dGAŠAN Sip-pa[rki]

7'. ITI.SIG<sub>4</sub> U<sub>4</sub>.2.KAM MU.[16.KAM  $^{\rm d}$ AG-A-PAP] 8'. LUGAL [TIN.TIR $^{\rm ki}$ ] 9'. TÚ[G.ḤI.A] $^{\rm ?}$  TÚG.GÚ.UD.DU  $^{\rm r}$ ta¹-[bar-ri]

10'.  $\check{s}\check{a}^{\mathrm{m}}Du\text{-}um\text{-}mu\text{-}q[u \dots]$ 

Obv. 7. Or  $\lceil 30 \ ma^{1} - n[a]$ .

Rev. 5', cf. above BM 50209+ (= 171): 8 and BBSt 36 (= 175): 6.

Rev. 9'. Or  $\lceil ku \rceil - \lfloor um \rfloor$  "instead of"

The  $16^{th}$  year of Nabopolassar is suggested because Dummuqu, the weaver, was active in the period between Kan 15 (BM 50209+ (= 171)) and Nbp 17 (BM 49268 = 3) and the second date is more probable because of the shape and colour of the tablet, similar to the tablets from the time of Nabopolassar and the early years of Nebuchadnezzar.

Wool, the supply, (which) [was given for] the we[avers].

7 talents 35 mi[nas of wool] for the  $\dot{s}ibtu$ -garments for Šamaš [and] for Bunene, [....], the  $lub\bar{a}r\ damqi$ -garment for Šamaš (and) the god(dess) [....], the  $[lub\bar{a}r]\ m\bar{e}\ qaqqadi$ -headdress for Šamaš, [....]

[....] for Šamaš and Aya for  $15^{th}$  (and)  $1[6]^{th}$  year, total 18 talents 5 [minas of wool for] tied  $n\bar{e}behu$ -belt for [Šamaš] (and)  $parš\bar{i}gu$ -headdress for the Queen of Sippar.

-----

Month of Simanu,  $2^{nd}$  day,  $[16^{th}]$  year [of Nabopolassar], king of [Babylon]. The  $lu[b\bar{a}ru]$ -garment? (and) red *nahlaptu*-cloak, which Dummuqu [has delivered].

384. VS 6, 24; cf. NUVI 3, No. 241

8.3.Nbk 3

- 1. SÍG.[ḤI.A] *ḫa-a-ṭu* <sup>lú</sup>UŠ.BAR.MEŠ
- 2. ITI.SIG4 U4.8.KAM MU.3.KAM  $^{\rm md}$ AG-NÍG.DU-ÙRU LUGAL TIN.TIR $^{\rm ki}$

\_\_\_\_\_

- 3. 11 GÚ.UN SÍG.HI.A <sup>md</sup>AG-EN-MU.MEŠ
- 4. 1 GÚ.UN 10 ma-na a-na SÍG.HÉ.<ME>.DA
- 5. ina IGI <sup>md</sup>UTU-ŠEŠ-MU <sup>lú</sup>ṣa-pu-ú
- 6. 4 GÚ.UN a-na É.GUR7.MEŠ
- 7. a-di gi-ni-e šá ITI.KIN
- 8. 1 me GÚ.UN [.....] 7 30<sup>?!</sup>

A few additional signs, probably without connection with the main text.

Wool, the supply for the weavers. Month Simanu, 8<sup>th</sup> day, 3<sup>rd</sup> year of Nebuchadnezzar, king of Babylon

<sup>11</sup> talents of wool (for) Nabû-bēl-šumāti;

<sup>1</sup> talent 10 minas for red wool at disposal of Šamaš-aḥ-iddin, the dyer;

<sup>4</sup> talents (are stored) in the  $b\bar{\imath}t$ - $k\bar{a}re$ -storehouse, including (for) the reguar offering for the month Ulūlu.

<sup>100</sup> talents [....] 7 30<sup>?!</sup>

# 385. BM 83316 (83-1-21, 479)

PLATE 89

 $3.0 \times 3.0 \text{ cm}$ 

#### 19.6.Nbk 23

- 1. 11 GÚ.UN 15 *m*[*a-na* SÍG.HI.A]
- 2. a-di SÍG.HI.A šá ina [....]
- 3. šá ITI.BÁR u I[TU.GU<sub>4</sub>]
- 4.  $^{\text{md}}$ AG-EN-MU.M[EŠ u]
- 5. mdAG-NUMUN-GÁL rši 1

Edge

- 6. [I]TI.KIN  $\check{s}\acute{u}$ - $\lceil ni \rceil$ [....]
- Rev. 7. U<sub>4</sub>. [20] 1.LAL.KAM
  - 8. MU.23.[KAM] 9. <sup>md</sup>AG-NÍG.DU-ÙRU
  - 10. LUGAL KÁ.DIN[GIR.RA<sup>ki</sup>]
- L. 6. The sense of  $\check{su}^{-1}ni^{-1}$  is not clear, however, it cannot be the designation of the intercalary month because it was a year with the intercalary Addaru, see Parker-Dubberstein,  $Babylonian\ Chronology$ , p. 5.
- 11 talents 15 [minas of wool], including wool which [....] of the month Nisannu and [Ayaru] Nabû-bēl-šum[āti and²] Nabû-zēr-ušabši (have received²). Month of Ulūlu ...., 19<sup>th</sup> day, 23<sup>rd</sup> year of Nebuchadnezzar, king of Babylon.

### **386. BM 76362** (83-1-18, 1730)

 $3.3 \times 3.2 \text{ cm}$ 

# 28.3<sup>?</sup>.Nbk [x]

- 1. 1 GÚ.UN S[ÍG.HI.A]
- 2. a-na <sup>m</sup>DUB-NU[MUN]
- 3.  $^{l\acute{u}}$ UŠ.BAR *bir-m*[*u*]
- 4. SUM<sup>na</sup> ITI.S[IG<sub>4</sub><sup>?</sup>]

Rev.

- 5. U<sub>4</sub>.28.KAM MU.[x.KAM]
- 6. dAG-NÍG.DU-ú-[sur]
- 7. LUGAL TIN.TIR.[KI]

Šāpik-zēri, see Bongenaar, *Ebabbar*, p. 349f. and Zawadzki, *Garments of the Gods*, Vol. I, p. 230f.

E. Leichty in Catalogue of the Babylonian Tablets in the British Museum, vol. VIII: Tablets from Sippar 3, p. 60 reads day date as 8.

1 talent of w[ool] was given to Šāpik-zēri, the multicoloured weaver. Month of Si[manu],  $28^{th}$  day, [ $n^{th}$ ] year of Nebuchadnezzar, king of Babylon.

### **387. BM 59660** (82-7-14, 4070)

PLATE 90

 $4.0 \times 3.3$  cm

#### 17.2.Nbn 6

- 1. 11 ½ GÍN *ha\*-tu*
- 2. KI.LAL 9\*-ta síg gú\*-hal\*-su\*
- 3. šá sa-am-mu-ú
- 4. [ina Š]U<sup>ii md</sup>30-DINGIR A-šú šá
- 5. [m]dUTU-MU *a-na*
- 6.  $\lceil \acute{E} \rceil$ -babbar-ra  $\mathrm{SUM}^{nu}$

Edge Rev.

- 7. [ITI].GU<sub>4</sub> U<sub>4</sub>.17.KAM
- 8. MU.6\*.KAM\*  $^{\rm d}$ AG-I 9. [LUG]AL TIN.TIR<sup>ki</sup>

Bongenaar, Ebabbar, p. 254 reads hulālu (NÍR = ZA.GÍN, according to CAD H 226a "precious stone") in l. 1, and sikkatu (pegs or sticks) in line 2. However, the new readings in ll. 1–2 are beyond question. For the description of the colour of *guḥaṣṣu* (given very seldom), the word tabarri is used. It seems that the text concerns the surplus of wool left after finishing 9 guhaşşus scarves.

The accession year suggested by Leichty, p. 290, and accepted by Bongenaar can hardly be true. There are only two signs between MU and <sup>d</sup>AG, the second one is definitely KAM. The year is written with horizontal wedges, i.e.  $3+ \lceil 3 \rceil$ .

11 ½ shekels of silver, the supply, the weight of 9 red scarves, delivered by Sin-ilī, son of Šamaš-iddin to the Ebabbar temple. Month of Ayaru, 17<sup>th</sup> day, 6<sup>th</sup> year of Nabonidus, king of Babylon.

# 388. BM 84214 (83-1-21, 1377)

PLATE 90

 $4.1 \times 3.2$  cm

#### 3.5.Nbn 1

- 1. 1 GÚ.UN SÍG.HI.A *ba-ab-t*[*u*<sub>4</sub>]

- 2. 4 ½ GÚ.UN 5 ma-na 3. a-na <sup>md</sup>AG-KAM <sup>md</sup>AG-muq-e-a 4. 「u¹ <sup>md</sup>AG-ú-pi-ni-ja 5. 「lú¹ qal-「la¹ šá <sup>md</sup>AG-EN-[MU.MEŠ]
- 6. <sup>rlú</sup>ŪŠ¹.BAR SUM<sup>in</sup>

7. 3 BÁN ŠE.BAR <sup>md</sup>AG-*ú-pi-*<sup>r</sup>*ni*<sup>1</sup>-[*ja* SUM] Edge

8. [IT]I.NE <sup>[</sup>U<sub>4</sub>].3.KAM Rev.

- 9. [M]U.1.KAM <sup>m</sup> [<sup>d</sup>AG]-I
- 10. LUGAL TIN.T[IR.K]I
- 11. 3 ma-na SÍG.HI.「А а<sup>¬</sup>-na
- 12. <sup>túg</sup>ú-za-ri šá an-dul-lum
- 13. 3 ma-na a-na tum-bi
- 14. ù ți-ma-a-ta šá pi-<šá>-an-nu
- 15. a-na <sup>md</sup>UTU-TIN<sup>it</sup> SUM<sup>[na]</sup> L. e.

L. 13. Although the identification of the signs is beyond question the sense of tumbu is not clear to me. This word, in a context connected with wool, appears here for the first time. Šamaš-uballit, see Bongenaar, Ebabbar, p. 348. Add BM 62100 (= 343): 9 ( $i\bar{s}k\bar{a}ru$  text dated 2.[x].Dar 20).

1 talent of wool, the outstanding amount from 4 talents 35 minas (of wool) was given to Nabû-ereš, Nabû-muqēa and Nabû-upnīya, the slave of Nabû-bēl-šumāti, the weaver:

3 sūtu of barley [was given] (to) Nabû-upnīya.

Month of Abu, 3<sup>rd</sup> day, 1<sup>st</sup> year of [Nabo]nidus, king of Baby[lon].

3 minas of wool for the *uzāru*-cover of the canopy;

3 minas(of wool) for *tumbu* and yarn for the *pišannu*-bag was given to Šamaš-uballiţ.

#### 389. BM 84470 (83-1-21, 1633)

PLATE 91

 $4.3 \times 3.2$  cm

#### 9.4.Nbn 4

- 1. ½ GÚ.UN SÍG.HI.A
- 2. a-na lu-bu-uš-tu<sub>4</sub>
- 3. šá ITI.DU<sub>6</sub> MU.4.KAM a-na
- 4. <sup>m</sup>Ba-ku-ú-a ù
- 5. <sup>md</sup>AG-*up-ni-ja*

Edge Rev. 6. <sup>[lú</sup>]*la-mu-ta-nu* 

7. [šá <sup>md</sup>A]G-EN-MU.MEŠ <sup>lú</sup>UŠ.[BAR]

- 8. SUM<sup>in</sup> e-lat SÍG.HI.A
- 9. maḥ-ri-e-tu<sub>4</sub> šá TA É ŠU<sup>ii</sup> šá KÁ
- 10. ITI.ŠU U<sub>4</sub>.<sup>r</sup>9<sup>1</sup>.KAM MU.4.KAM
- 11. md AG-I LUGAL TIN.TIRki

 $\frac{1}{2}$  mina of wool for the *lubuštu* ceremony for the month of Tašrītu,  $4^{th}$  year, for Bakûa and Nabû-upnīya, the servant of Nabû-bēl-šumāti, the weaver was given. Except for an earlier (delivery) of wool from the  $b\bar{t}t$   $q\bar{a}ti$ -storehouse at the gate. Month of Du'ūzu,  $9^{th}$  day,  $4^{th}$  year of Nabonidus, king of Babylon.

### 390. BM 99937 (83-1-21, 2299)

PLATE 91

 $3.5 \times 3.7 \text{ cm}$ 

### [x].3.Nb[n] 5

- 1. 5 ma-na SÍG.ḤI.「A¹ [šá]
- 2. a-na <sup>túg</sup>lu-bu-uš-tu<sub>4</sub> [šá ITI.KIN]
- 3. a-na <sup>m</sup>Ba-ku-ú-a <sup>l</sup>[<sup>ú</sup>qal-la šá]
- 4. <sup>md</sup>AG-*na-şir*-IBILA [lúUŠ.BAR]
- 5. na-din ITI.SIG<sub>4</sub> U<sub>4</sub>.[x.KAM]

# 6. MU.5.KAM <sup>md</sup>AG-[I]

7. LUGAL TIN.TIR.K[I] Edge

Rev. uninscribed

L. 2. Because the nearest *lubuštu* ceremony was in the month Ulūlu, we might fill the gap with [šá ITI.KIN].

5 minas of wool, for the (garment) for the *lubuštu* ceremony [of the month Ulūlu] was given to Bakûa, [the slave of] Nabû-nāṣir-apli, [the weaver]. Month of Simanu,  $[n^{th}]$  day,  $5^{th}$  year of Nabo[nidus], king of Babylon.

### **391. CT 55, 842** = BM 56405

#### 29.5.Nbn 5

- 1. 1 *ma-na* 15 GÍN 「KI ].[LAL]
- 2.  $^{\text{túg}}$ *mut-ta-tu*<sub>4</sub>
- 3. 1 ma-na 10 GÍN KI.LAL 10 hu-sa-ni-e 1<sup>en</sup> su-ú-nu
- 4. šá <sup>d</sup>IM u <sup>d</sup>Šá-la
- 5. [1/2] ma-na 5 GÍN

- 6. [KI].LAL 5 *ḫu-ṣa-ni-e*7. [*u* 1]<sup>ren</sup> su-ú-nu
  8. šá <sup>d</sup>Gu-la <sup>m</sup>Ba-ku-ú-a
  9. <sup>lú</sup>qal-la šá <sup>md</sup>AG-na-ṣir-A
- 10. it-ta-din ITI.NE
- 11. U<sub>4</sub>.29. KAM MU.5.KAM 12.  $^{\rm md}$ AG-I LUGAL  $E^{\rm ki}$
- L. 5. The reconstruction of the numeral is certain, because 5 huşannu-sashes for Gula weighed 15 shekels, while 1 sūnu-belt weighed 20 shekels.

1 mina 15 shekels, the weight of *muttatu*-headdress

1 mina 10 shekels, the weight of 10 sashes and 1 sūnu-belt for Adad and Šala [3]5 shekels, the weight of 5 sashes [and] [1] sūnu-belt for Gula, Bakûa, the slave of Nabû-nāṣir-apli has delivered.

Month of Abu, 29<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, king of Babylon.

# **392. BM 60445** (82-9-18, 413) = Str. II 351/4

 $5.0 \times 3.8$  cm

#### 10.5.Nbn 7

- 1. ½ GÚ.UN 5 ma-na
- 2. SÍG.ḤI.A e-rlat sat-tuk IGI-tu<sub>4</sub>
- 3. a-na dul-lu šá ITI.DU<sub>6</sub>
- 4. md AG-PAP mBa-ku-ú-a

- 5. <sup>m</sup>A-na-<sup>d</sup>AG-up-ni-ja
- 6.  $\lceil \text{SUM} \rceil^{[i]n}$

Rev.

7. ITI.NE U<sub>4</sub>.10.KAM

- 8. MU.7.KAM <sup>md</sup>AG-I 9. LUGAL TIN.TIR<sup>ki</sup>

35 minas of wool except for the earlier regular offering for the work for the month of Tašrītu was given to Nabû-nāsir, Bakûa (and) Ana-Nabû-upnīya. Month of Abu, 10<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

#### 393. BM 65047 (82-9-18, 5028)

PLATE 92

 $5.7 \times 4.3$  cm

#### 20+x.8.Nbn 7

- 1. 2 GÚ.UN SÍG.HI.A *a-na lu-bu-u*[*š-tu*<sub>4</sub>]
- 2. *šá* ITI.ŠE MU.7.KAM *u* ITI.BÁR M[U.8.KAM]
- 3. 22 ma-na SÍG.HI.A a-na dul-lu
- 4. ta-bar-ri šá ITI.GU<sub>4</sub> MU.8.KAM
- 5. PAP 2 GÚ.UN 22 ma-na SÍG.HI.A
- 6. *a-na* <sup>m</sup>*Ba-ku-ú-a* <sup>lí</sup>*qal-la* 7. [*šá*] <sup>md</sup>AG-EN-MU.MEŠ *u* <sup>md</sup>UTU-NUMUN-「GÁL」<sup>*ši*</sup>
- 8. [DUM]U <sup>m</sup>Ṣil-la-a [SUM<sup>na</sup>]
- 9. [ITI].APIN U<sub>4</sub>.20[+x<sup>2</sup>.KAM] 10. [MU].<sup>1</sup>7<sup>1</sup>.KAM [<sup>md</sup>AG-I] 11. LUGAL TIN.TI[R]<sup>ki</sup>

Rev.

- Ll. 1–2, compare with BM 76590+ (= 163), col. I 8–12.
- L. 10. Only Nabonidus' reign is possible, because Nabû-bēl-šumāti is not known after Nbn 9; also all texts of Šamaš-zēr-ušabši are dated to Nabonidus' time. Month Arahsamna is clear (contra Catalogue).
- 2 talents of wool for the *lubuštu* ceremony for the month Addaru, 7<sup>th</sup> year and the month Nisannu, [8th yea]r;
- 22 minas of wool for work with red wool for the month Ayaru, 8<sup>th</sup> year, total 2 talents 22 minas of wool [was given] to Bakûa, the slave [of] Nabû-bēl-šumāti, and Šamaš-zēr-ušabši, son of Sillā.

[Month] of Arahsamna,  $20^{th}/20+[x^{?}]$  day,  $7^{th}$  [year of Nabonidus], king of Babylon.

#### 394. BM 64937 (82-9-18, 4918)

 $5.4 \times 4.1$  cm

## 12.11.Nbn 8

- 1. [x G]Ú.UN SÍG.ḤI.A [šá a-na]
- 2. [muh]-hi dul-lu šá ITI.ŠE
- 3. [M]U.8.KAM <sup>r</sup>u ITI<sup>1</sup>.BÁR MU.9.KAM

- 4. a-na <sup>m</sup>Ba-ku-ú-a
- SUM<sup>in</sup>

6. [x] ma-na SÍG.ḤI.A ina [SÍG.ḤI.A] Edge

Rev.

- 7.  $[\check{s}\check{a}^{1\acute{u}}]U\check{S}.BAR-u-tu\ u\ [x\ x\ x]$
- 8.  $^{\text{lú}}\check{\text{SID}}$  SUM $^{in}$ 9.  $^{\text{md}}\text{AG}$ -di-<ni>- $D\grave{\text{U}}^{u\check{s}}$   $^{\text{lú}}\text{U}\check{\text{S}}^!$ .[BAR ....]
- 10. ITI.ZÍZ U<sub>4</sub>.12.KAM MU.8.KAM
- 11. [mdA]G-I LUGAL TIN.TIRki
- L. 9. The sign reconstructed as UŠ looks exactly like ni, however, because Nabû-dīni-ēpuš, the weaver is known (see Bongenaar, Ebabbar, p. 334), the reconstruction seems certain. It is completely unclear how he is connected with the main subject of the text.
- [x] talent(s) of wool for the work of the month Addaru,  $8^{th}$  year, and month Nisannu,  $9^{th}$  year, was given to Bakûa
- [x] minas of wool from the wool of the weaver's prebend and [for PN], the scribe was given. Nabû-dīni-ēpuš, the weaver...

Month of Šabātu, 12<sup>th</sup> day, 8<sup>th</sup> year of Nabonidus, king of Babylon.

## **395. BM 60933** (82-9-18, 909)

PLATE 93

 $4.5 \times 3.5$  cm

#### 21.8.Nbn 13

- 1. 10 GÚ.UN SÍG.HI.A *a-n*[*a*]
- 2. dul-la šá ITI.ŠE MU.1[3.KAM]
- 3. ½ GÚ.UN SÍG.ḤI.A *a-n*[*a* x x]
- 4. ni-bi-hu ku-si-tu<sub>4</sub> <sup>r</sup>pa-tin-ni<sup>7</sup>
- 5. šá M[U.13.KA]M MU.14.KAM
- 6. [a-na] <sup>md</sup>AG-na-şir-A 7. [u] <sup>m</sup>Ba-a-ku-ú-a 8. <sup><lú></sup>qal-li-šú SUM<sup>nu</sup>

Edge

- Rev.
  - 9. ITI.APIN U<sub>4</sub>.21.KAM MU.13.KAM
  - 10. dAG-I LUGAL TIN.TIR. KI

10 talents of wool for the work for the month of Addaru, 1[3<sup>th</sup>] year;  $\frac{1}{2}$  talent of wool for [...], the *nēbehu*-belt, the robe, the *patinnu*-belt for  $\frac{1}{3}$ <sup>th</sup> ye]ar (and) 14<sup>th</sup> year was given [to] Nabû-nāṣir-apli [and] Bakûa, his slave. Month of Araḥsamna, 21<sup>st</sup> day, 13<sup>th</sup> year of Nabonidus, king of Babylon.

## **396. BM 62178** (82-9-18, 2147)

PLATE 93

 $4.2 \times 3.5$  cm

13.4.Nbn <sup>[3?]</sup>

- 1. [x *ma-na*] SÍG.H[I.A]
- 2. [a]-na lu-bu- $u[\check{s}$ - $tu_4]$

- 3. [*šá* IT]I.DU<sub>6</sub> <sup>[</sup>*a*<sup>1</sup>-*na*
- 4.  $[^{m}B]a-ku-\acute{u}-a\grave{u}$
- 5. [mdAG]-up-ni-ja

6.  $[SUM^i]^n$ Edge

7. [I]TI.ŠU U<sub>4</sub>.13.KAM Rev.

- 8. [M]U.<sup>73</sup><sup>?</sup>.KAM<sup>7</sup> <sup>md</sup>AG-I
- 9. [LUG]AL TIN. [TIR][ki]

[x minas] of wool for the lubuštu ceremony of the month Tašrītu was given to Bakûa and [Nabû]-upnīya.

Month of Du'ūzu, 13<sup>th</sup> day, <sup>[3rd?</sup> year<sup>1</sup> of Nabonidus, king of Babylon.

## **397. Nbn 785** = BM 60611; cf. NUVI 3, No. 72 Collated

- 1. 2 ma-na 1/3 GÍN SÍG.HI.A
- 2. TA É ŠU<sup>ii</sup> a-na
- 3. 1 ma-na 12 GÍN ta\*-bar-ri
- 4. a-na şib-tu šá <sup>d\*</sup>A\*-[nu]-ni\*-tu<sub>4</sub>\*
- 5.  $[x \times x^{1}]$ ....]

Rev.

- 6. ITI.KIN U<sub>4</sub>.13.KAM MU.14.KAM
- 7. md AG-I LUGAL Eki

2 minas 20 shekels of wool from the bīt qāti storehouse for 1 mina 12 shekels of red wool for the sibtu-garment of Anunītu [....].

Month of Ulūlu, 13<sup>th</sup> day, 14<sup>th</sup> year of Nabonidus, king of Babylon.

## **398. BM 101416** (83-1-21, 3077)

PLATE 94

 $4.3 \times 4.0$  cm

#### 29.10.Nbn 15

- 1. [x GÚ.UN x] ma-na SÍG.HI.A
- 2. [a-na] <sup>[</sup>lu-bu-uš<sup>]</sup>-tu<sub>4</sub> šá ITI.BÁR
- 3. [a-na <sup>md</sup>AG]-PAP-A u <sup>m</sup>Ba-ku-ú-a <sup>lú</sup>UŠ.BAR.<MEŠ>
- 4. [SUM<sup>na</sup>] ITI.AB U<sub>4</sub>.29.KAM MU.15.KAM
- 5. [mdAG]-I LUGAL TIN.TIRki
- 6. [ina lìb-b]i 12 ma-na SÍG.ḤI.A šá a-na 「UGU」
- 7. [mdAG]-PAP-A ina ŠUKU.ḤI.A lúUйBAR¹-ú-tu 8. [....]- $^{\Gamma}$ zib²¹ SUM

## Rev uninscribed

L. 7. In the text there is in fact  ${}^{1\acute{u}}T\acute{U}G.U\r{S}-\acute{u}-tu$ , with  $U\r{S}$  written over another character. The emendation is justified by the position of Nabû-nāṣir-apli, a well-known prebendary and the owner of Bakûa. The kurummat išparūti means probably here the rations given for Nabûnāṣir-apli's weavers.

L. 8. Instead of  $\lceil zib \rceil$  a it is possible also to read [M]U.

[x talent(s) x] mina(s) of wool [for] the *lubuštu* ceremony for the month of Nisannu [was given to Nabû]-nāṣir-apli and Bakûa, the weaver(s). Month of Ṭebētu, 29<sup>th</sup> day, 15<sup>th</sup> year of [Nabo]nidus, king of Babylon.

[Out of i]t 12 minas of wool for [Nabû]-nāṣir-apli as the weavers prebendary rations were given [to ....]-zib<sup>7</sup>.

## **399. BM 66810** (82-9-18, 6803)

 $2.8 \times 3.9 \text{ cm}$ 

## 20+x.5.Nbn [x]

- 1. 1 GÚ.UN SÍG.ḤI.[A ....]
- 2. NÍG.GA <sup>d</sup>UTU *šá* [....]
- 3. A-*šú šá* <sup>md</sup>UTU-「LUGAL¹-[x]
- 4. <sup>lú</sup>qal-la šá <sup>m</sup>[....]
- 5.  $\lceil a \rceil$ -na É-babbar- $r[a \text{ SUM}^{in}]$
- 6. [ina] 'lìb¹-bi ½ 'GÚ¹.[UN UN SÍG.ḤI.A]
- 7. *ina sat-tuk šá* É [....]

Rev.

- 8. a-na <sup>m</sup>(erased space) [.... u?]
- 9. <sup>m</sup>*Ba-ku-ú-*[*a* SUM<sup>in</sup>]
- 10. ITI.NE  $U_4.20[+x^?.KAM\ MU.x.KAM]$
- 11. dAG-I LU[GAL TIN.TIR<sup>ki</sup>]

1 talent of wool [....], the property of Šamaš, which [PN<sub>1</sub>], son of Šamaš-šar-[x], the slave of [PN<sub>2</sub> has delivered] to the Ebabbar temple, including ½ ta[lent of wool from the sattukku-offernig of the temple [....] was given to PN<sub>3</sub> and] Bakûa. Month of Abu, day 20+[x<sup>?</sup>, n<sup>th</sup> year] of Nabonidus, ki[ng of Babylon].

#### **400. BM 99850** (83-1-21, 2212)

 $4.0 \times 3.5$  cm

#### 22.2.[Nb]n 10

- 1. [x *ma-na*] SÍG.HI.A
- 2. [a-na lu-bu-uš-t]u<sub>4</sub> šá ITI.BÁR
- 3.  $[u \text{ ITI.GU}_4]^{\mathsf{r}} x^{\mathsf{r}} \check{s} \check{a}^{\mathsf{md}} \mathsf{AG-A-MU}$
- 4.  $\lceil a-na \rceil^{m} \lceil Ba-la \rceil tu < A-\check{s}\check{u} \check{s}\check{a} >$
- 5. md AG-ŠEŠ.MEŠ-bul-lit
- 6. ma-hi-ir

Rev.

- 7. ITI.GU<sub>4</sub> U<sub>4</sub>.22.KAM
- 8. MU.10.[KAM <sup>md</sup>AG]-I 9. [LUGAL] TIN.「TIR」<sup>ki</sup>

If the wool was really destined for the *lubuštu* ceremony, it would be the first delivery of wool after the ceremony, i.e. Balāṭu had to use his own wool to perform his task.

[x mina(s)] of wool [for the *lubuš*]tu ceremony of the month Nisannu [and Ayaru] which Nabû-apal-iddin has delivered to Balāṭu, son of Nabû-aḥḥē-bulliṭ. Month of Ayaru, 22<sup>nd</sup> day, 10<sup>th</sup> year of [Nabo]nidus, [king] of Babylon.

## **401. BM 63006** (82-9-18, 2975)

 $5.1 \times 3.9$  cm

## 10.3.Cam [x]

- 1. [x+<sup>?</sup>]10 ma-na SÍG.ḤI.A ina dul-lu
- 2. lu-bu-uš-tu<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 3. *šá* UD.KIB.NUN<sup>ki d</sup>A-nu-ni-tu<sub>4</sub>
- 4. šá ITI.ŠU a-na <sup>m</sup>ŠEŠ.M[EŠ-MU-<sup>d</sup>AMAR.UTU A-šú šá]
- 5. [<sup>m</sup>SU]- <sup>d</sup>AMAR.UTU SUM<sup>[na]</sup>
- 6. [ITI.SI]G<sub>4</sub> U<sub>4</sub>.10.KAM M[U.x.KAM]
- 7.  $[^mKam-bu-z]i-ja$

Edge 8. [LUGAL TIN.TIR]<sup>ki</sup> LUGAL KU[R.KUR]

[x+<sup>?</sup>] 10 minas of wool for the manufacturing (garments) for *lubuštu* ceremony for Anunītu-of-Sippar-Anunītu for the month of Du'ūzu was given to Aḫḫē-[iddin-Marduk, son of Erība]-Marduk.

Month of [Sima]nu<sup>?</sup>, 10<sup>th</sup> day, [n<sup>th</sup> ye]ar of Cambyses, [king of Babyl]on, king of Lands.

## **402. BM 64577** (82-9-18, 4557)

PLATE 94

 $6.2 \times 4.3$  cm

### 5.5.Dar 18

- 1. 2 m[a-n]a SÍG.ḤI.A [a]-na
- 2. TÚG.ÚR šá me-e-ŠU<sup>ii</sup>
- 3. <sup>r</sup>šá<sup>1</sup> <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup> a-na
- 4. <sup>m</sup>ÌR-ja <sup>lú</sup>UŠ.BAR bir-mu 「SUM<sup>¬</sup>
- 5. [x ma]-na SÍG.HI.A  $[i^2]$  [x x]
- 6. [x SÍG.H]É.ME.DA šá [x] [....]

Edge

7. [a]- $\lceil na \rceil$   $\lceil m \lceil x \rceil$  [....]

Rev.

- 8. ITI.NE U<sub>4</sub>.5.KAM
- 9. MU.18.KAM <sup>m</sup>Da-ri-uš-šú
- 10. LUGAL TIN.TIR<sup>ki</sup> 'LUGAL KUR.KUR'

L. 4. Ardīya, see Bongenaar, *Ebabbar*, p. 316 f. and Zawadzki, *Garments of the Gods*, Vol. I, p. 210.

The sūnu šá mē-qātê appears here for the first time.

2 minas of wool for the  $s\bar{u}nu$ -belts of the  $m\bar{e}$ - $q\bar{a}te$  for the Queen of Sippar <sup>r</sup>was given <sup>1</sup> to Ardīya, the multicoloured weaver.

[x mi]na of wool ..... red wool [... was given] to [PN].

Month of Abu, 5<sup>th</sup> day, 18<sup>th</sup> year of Darius, king of Babylon, king of Lands.

## **403. BM 61228** (82-9-18, 1204)

PLATE 95

 $4.7 \times 3.8$  cm

## 6.5.Dar 21

- 1. [x] GÚ.UN 2 ma-na SÍG.HI.A
- 2. ina lu-<sup>r</sup>bu<sup>¬</sup>-uš-tu<sub>4</sub> šá
- 3. ITI.<sup>r</sup>KIN<sup>1</sup> MU.21.KAM
- 4. *a-na* <sup>md</sup>UTU-MU-MU
- 5. SUM<sup>na</sup> ITI.NE U<sub>4</sub>.6.KAM
- 6. MU.21.KAM <sup>m</sup>Da-ri-mu-šú

Rev. 7. LUGAL TIN.TIR<sup>ki</sup>

8. LUGAL KUR.KUR

[x] talent(s) 2 minas of wool for the *lubuštu* ceremony of the month Ulūlu of the 21<sup>st</sup> year was given to Šamaš-šum-iddin.

Month of Abu, 6<sup>th</sup> day, 21<sup>st</sup> year of Darius, king of Babylon, king of Lands.

## **404. BM 83877** (83-1-21, 1040)

 $4.2 \times 3.5 \text{ cm}$ 

#### 26.11.Dar 23

- 1. 1 GÚ.UN SÍG.ḤI.A a-na [lu-bu-uš-tu<sub>4</sub>]
- 2. šá ITI.GU<sub>4</sub> MU.24.KAM [<sup>m</sup>Da-ri-'-muš a-na]
- 3.  $^{\text{md}}$ UTU-MU-MU  $^{\text{lú}}$ UŠ.<BAR> SU[M $^{na}$ ]
- 4. [x *ma-n*]*a* SÍG.ḤI.A IGI-[*tu*<sub>4</sub>]
- 5. [10<sup>?</sup>] [ma-na SÍG.Ḥ]I.A i-na [....]
- 6.  $[x \times x \times x \times u^{\text{lú}}U]$ Š.BAR [....]

#### Rest lost

Rev.

- 1'.  $\lceil x \rceil \lceil x \rceil \lceil x \text{ SUM} \rceil^{nu}$
- 2'. 1 ma-na SÍG.ḤI.A ina ŠUKU.[ḤI.A]
- 3'.  $^{\text{lú}}$ UŠ.BAR *bir-ri a-*[na (x x)]
- 4'. <sup>md</sup>UTU-MU-MU SUM<sup>[na]</sup>
- 5'. 2 ma-na SÍG.ḤI.A ina ŠUKU.[ḤI.A ....]
- 6'. a-na <sup>m</sup>La-qip-pi <sup>lú</sup>[....]
- 7'. ITI.ZÍZ U<sub>4</sub>.26.KAM MU.<sup>1</sup>20<sup>1</sup>+[3.KAM]
- 8'. <sup>m</sup>Da-ri-'-muš LUG[AL TIN.TIR<sup>ki</sup>]
- 9'.  $u \text{ KUR.KUR}^{\text{me}[\S]}$

Rev. 6'. Presumably Lāqīpu, the *išpar birme*, known from the document from the 24<sup>th</sup> year of Darius (Bongenaar, *Ebabbar*, p. 330), but probably active already in the time of Cyrus, see Zawadzki, *Garments of the Gods*, Vol. I, p. 218.

1 talent of wool for (garments) for [the *lubuštu* ceremony] of the month Ayaru, 24<sup>th</sup> year [of Darius] was given [to] Šamaš-šum-iddin, the weaver;

[x min]as of wool of an earlier (issue), [10] minas of wool from [...., the we]aver [....]

#### [....] was given;

1 mina of wool from the rations of the multicoloured weaver t[o(x x)] Šamaš-šumiddin was given

2 minas of wool as the ratio[ns ....] to Lāqīpu, the [.... was given].

Month of Šabaţu, 26<sup>th</sup> day, 2[4]<sup>th</sup> year of Darius, king of Babylon, king of Lands.

## **405. BM 60427** (82-9-18, 395)

PLATE 95

 $3.9 \times 3.0$  cm

## 1.11.Nrg 1

- 1. 5 5/6 ma-na 5 GÍN
- 2. KI.LAL 1<sup>en túg</sup>sib-tu<sub>4</sub>
- 3. a-na GIŠ.NÁ šá <sup>d</sup>UTU
- 4. <sup>m</sup>Ba-ku-ú-a
- 5. it-ta-din šá ITI.ZÍZ

Rev.

- 6. U<sub>4</sub>.1.KAM MU.3.KAM
- 7. dU+GUR-LUGAL-ÙRU
- 8. LUGAL TIN.TIR<sup>ki</sup>

The text was earlier edited by Watanabe, ASJ 10 (1988) 229. BM 67080, edited below, supports Watanabe' supposition that in Šabaţu was a special festival in honour of Šamaš, most probably close to the 20<sup>th</sup> day of the month, see BM 64557, edited by Zawadzki, NA-BU 2005, No. 9, according to which Šamaš came back from Babylon to Sippar some time before the 20<sup>th</sup> of Šabaţu.

Note the atypical weight of the *şibtu* of Šamaš here, which suggests that it was specially manufactured as the cover of a bed, not as an item of the god's clothes.

5 minas 50 shekels, the weight of 1 *şibtu* for the bed of Šamaš, which Bakûa has delivered. Month of Šabaţu, 1<sup>st</sup> day, 3<sup>rd</sup> year of Neriglissar, king of Babylon.

## **406. BM 67080** (82-9-18, 7075)

PLATE 96

 $4.3 \times 3.6$  cm

22.10.Dar 24

- 1. 15 ma-na SÍG.HI.A
- 2. ina SÍG.HI.A šá șib-tu4 šá
- 3. GIŠ.NÁ *šá* <sup>d</sup>UTU

- 4. šá ITI.ZÍZ MU.24.KAM
- 5. a-na <sup>m</sup>Su-qa-a-a
- 6. 「it-ta-din<sup>1</sup>

7. ITI.AB U<sub>4</sub>.22.KAM

- 8. MU.24.KAM
- 9. <sup>m</sup>Da-ri-mu-šú
- 10. LUGAL TIN.TIR<sup>ki</sup>
- 11. LUGAL KUR. 「KUR」
- L. 5. Sūqaya, see Bongenaar, Ebabbar, p. 341 and Zawadzki, Garments of the Gods, Vol. I, p. 225.

15 minas of wool from the wool for the *şibtu* for the bed of Šamaš for the month of Šabatu,  $24^{th}$  year, was given to Sūqaya. Month of Tebētu,  $22^{nd}$  day,  $24^{th}$  year of Darius, king of Babylon, king of Lands.

### **407. BM 61011** (82-9-18, 987)

PLATE 96

 $5.0 \times 4.0$  cm

Rev.

#### 21.12.Dar 33

- 1. [2] GÚ.UN SÍG.ḤI.A a-na ṣib-ti<sup>m[eš]</sup>
- 2. *šá* <sup>d</sup>UTU *šá* ITI.ŠE MU.33.KAM
- 3. ù ITI.BAR MU.34 KAM
- 4. a-na <sup>m</sup>Lib-luṭ e-piš-an-nu
- 5. [šá <sup>m</sup>]EN-bul-liṭ-su SUM<sup>na</sup>
- 6. [x] ma-na SÍG.HI.A a-na šuq-lu
- 7. [šá e-piš]-šá-an-nu a-na
- 8.  $[^{m}x x (x)]-a SUM^{na}$ Rev.
  - 9. [ITI.ŠE U<sub>4</sub>].21.KAM MU.33.KAM
  - 10. [<sup>m</sup>Da-r]i-ja-muš LUGAL KUR.KUR
- L. 1. The numeral at the beginning is written over erasure.
- 2 talents of wool for the sibtu-garments for Šamaš for the month of Addaru, 33<sup>rd</sup> year, and (for) the month of Nisannu, 34<sup>th</sup> year for Liblut, the performer of Bēlbullissu was given.

[x] mina(s) of wool for paying of the performer was given to [PN]-a.

[Month of Addaru], 21<sup>st</sup> [day], 33<sup>rd</sup> year of [Da]rius, king of Lands.

## 408. BM 61598 (82-9-18, 1570)

 $4.9 \times 3.1 \text{ cm}$ 

Dar 16

- 1. 1 GÚ.UN SÍG.HI.A ina [lu-bu-uš-tu<sub>4</sub>]
- 2. šá ITI.ŠU šá  ${}^{d}A$ -nu- ${}^{r}ni$ - $[tu_4]$

3. a-na  $^{m}$  $\acute{U}$ -bal-lit-su- $^{d}$ Gu-la [SU] $M^{nu}$ 

4. ½ GÚ.UN 1 [*ma-na šá*?] <sup>md</sup>UTU-MU-[MU]

5.  $\lceil a - na \rceil^{m} \lceil x \rceil \lceil x \rceil \lceil x \rceil$  SUM

Rest lost

1'.  $[x \times x \times (x)] \lceil lib^{?} \rceil [....]$ Rev.

2'. [x x (x)] *şib-ba-tu*<sub>4</sub>

3'. [x x x x] <sup>md</sup>EN-ri-man-ni

4'. [x GÚ]. [UN<sup>?</sup>] [x *ma-n*]*a* SÍG. ḤI. A

5'. [*a-na*] <sup>[</sup>*lu*]-*bu-u*[*š-t*]*ú šá* ITI. <sup>[</sup>ŠE]

6'. I[TU.B]ÁR u ITI.GU<sub>4</sub>

7' *šá* MU.16. KAM [x x x]

8'. it-ti-su-nu- $t[u_4 \times \times (x)]$ 

9'. <sup>m</sup>Da-ri-[ja-muš LUGAL ....] L. h.e.

L. 4. The order of line 7'-9' is completely unclear to me.

1 talent of wool for [the *lubuštu* ceremony] of the month Du'ūzu for Anunītu was given to Uballissu-Gula

31 minas of wool, [which?] Šamaš-šum-[iddin] has given t[o ....\

[....] *şibtu*-garments [.... to] Bēl-rēmanni;

[x tale]nt(s) [x mina(s)] of wool [for] the *lubuštu* ceremony of the month Addaru, Nisannu and Ayaru, the 16<sup>th</sup> year [....] with them [...], Dari[us, king ....].

#### **408a. BM 83650** (83-1-21, 813)

PLATE 97

11.7.Dar 23

1'. [x GÚ.UN] <sup>7</sup>3 ½ ma-na SÍG.HI.A<sup>1</sup>

2'. [a-na l]u- ${}^{r}bu$ }-u $\check{s}$ -tu4  $\check{s}$  $\acute{a}$  ITI.DU $_6$  a-na

3'. TIN-su-dGu-la SUM ITI.DU<sub>6</sub> U<sub>4</sub>.11.KÁM

4'. MU.23.KAM <sup>m</sup>Da-ri-ia-muš LUGAL

5'. 5 ma-na 「SÍG.HI.A a¹-na ŠUKU.HI.A

6'. <sup>rm</sup>ıÌR-ja šá É.ŠU<sup>ii</sup> SUM Edge

7'. ½ GÚ.UN 3 ma-na 10 GÍN SÍG.HI.A a-na Rev.

8'. lu-bu!(T: bar)-uš-tu<sub>4</sub> šá <sup>d</sup>UTU u <sup>d</sup>A-a

9. šá ITI.APIN šá MU.23.KAM

10.  $[x \ x \ x \ x \ x \ x]$ 

L. 2'. Note that the lubuštu ceremony took place on the  $7^{th}$  day of Tašrītu.

[x] 3 ½ minas of wool [for] the *lubuštu* ceremony for the month Tašrītu was given to Uballissu-Gula. Month of Tašrītu, 11<sup>th</sup> day, 23<sup>rd</sup> year of Darius, king. 5 minas of wool for the ration for Ardīya of the *bīt qāti*-storehause.

33 minas 10 shekels of wool for the *lubuštu* ceremony for Šamaš and Aya for the month Arahsamna, 23<sup>rd</sup> year [....].

## **409. BM 62170** (82-9-18, 2139)

PLATE 97

 $5.4 \times 3.8$  cm

#### 21.2.Dar 27

- 1. 4 ½ ma-na SÍG.HI.A i-na
- 2. lu-bu-uš-tu<sub>4</sub> šá ITI.ŠU šá <sup>d</sup>A-[nu-ni]-tu<sub>4</sub>
- 3. a-na <sup>m</sup>TIN-su-<sup>d</sup>Gu-la
- 4. SUM<sup>na</sup> ITI.「GU<sub>4</sub>」 U<sub>4</sub>.21.[KAM]
- 5. 「MU¹.[27.KAM <sup>m</sup>Da-ri-ia-muš]

Rest lost

Rev.

- 1'. 「1 *ma*<sup>?</sup>¬-[*na* SÍG.ḤI.A]
- 2'. a-na <sup>m</sup>[TIN-su]- <sup>d</sup>Gu-[la]
- 3'. SUM $^{na}$  ITI.GU $_4$  U $_4$ .21. [KAM]
- 4'. MU.27.KAM <sup>m</sup>Da-ri-iá-a-muš
- 5'. LUGAL E<sup>ki</sup> u KUR.KUR<sup>meš</sup>

4 minas 30 shekels of wool for! the (garments) for the *lubuštu* ceremony of the month Du'ūzu for Anunītu was given to Uballissu-Gula. Month of Ayaru, 21<sup>st</sup> day, [27<sup>th</sup> year of Darius].

......

1 mi[na of wool] was given to [Uballissu-Gu]la.

Month of Ayaru, 21st day, 27th year of Darius, king of Babylon, king of Lands.

### **410. BM 99474** (83-1-21, 1836)

 $2.8 \times 4.2 \text{ cm}$ 

## 5.[x].Dar [x]

- 1. 1 ½ ma-na [SÍG.HI.A  $\dot{u}^2$ ]
- 2. 3 ma-na S[ÍG<sup>?</sup> ....]
- 3. *a-na lu-bu-u*[*š-tu*<sub>4</sub> *šá* ITI.ŠU *šá*]
- 4. <sup>d</sup>*A-nu-ni-t*[*u*<sub>4</sub> *šá* UD.KIB.NUN<sup>ki</sup> <sup>d</sup>*A-nu-ni-tu*<sub>4</sub>]
- 5. a-na <sup>m</sup>TIN-s[u-<sup>d</sup>Gu-la SUM<sup>na</sup>]
- 6. 5/6 ma-na pap-[pa-su ....]
- 7. 1 *ma-na* [....]
- 8. *a-na* [....]
- 9. <sup>túg</sup>ku-[....]
- 10. *šá* <sup>d</sup>HAR [....]
- 11. ana ŠU<sup>ii</sup> [PN SUM<sup>na</sup> ITI.x]
- 12. U<sub>4</sub>.5.KAM [MU.x.KAM]
- 13. <sup>m</sup>Da-ri-mu[š LUGAL TIN.TIR<sup>ki</sup>]
- 14. LUGAL KUR.[KUR]
- L. 1–2 Most probably wool of two different type or colour was counted there.

1 mina 30 shekels [of .... wool] (and 3 minas of .... wo]ol for the (manufacturing the garments) for the *lubu*[stu] ceremony [of the month of Du'ūzu for] Anunīt[u-of Sippar-Anunītu] for Uballis[su-Gula was given].

50 shekels, the preben[dary income ....]; 1 mina [....] for [...] ku-[....]-garment [.... for Bunene by the hand of [PN was given].

Mont of [x], 5<sup>th</sup> day, [n<sup>th</sup> year] of Darius, [king of Babylon], king of Lan[ds].

## **411. BM 76347** (83-1-18, 1715)

PLATE 98

 $5.2 \times 2.9 \text{ cm}$ 

#### 7.10.Dar 27

- 1. 1 ½ GÚ.UN SÍG.HI.A šá a-na
- 2. lu-bu-uš-tu<sub>4</sub> šá ITI.ŠE a-na
- 3. <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>
- 4. [ITI.A]B U<sub>4</sub>.7.KAM MU.27.KAM
- 5. [<sup>m</sup>Da-r]i-ja-a-muš

-----

6. [....] 「*a-na* <sup>d</sup>UTU<sup>1</sup>

Rest lost

Rev.

1'. [....] <sup>r</sup>x x<sup>1</sup> [....]

2'. šá <sup>m</sup>x-nu-ba-nu 3'. šá <sup>m</sup>Ši-rik-tu<sub>4</sub>

4'. ITI.AB U<sub>4</sub>.7.KAM

L. 4. The numeral 7 is written over erasure. The remnants of numeral 10 are still recognizable in front of numeral 7.

Rev. 2'. I cannot identify the sign.

1 talent 30 minas of wool for (the garments) for the *lubuštu* ceremony of the month of Addaru, was given to Šamaš-šum-iddin, the weaver.

[Month of Te]betu, 7<sup>th</sup> day, 28<sup>th</sup> year of Darius.

[.... for Šamaš?

[(....)] (for?) x-nu-banu?

Širiktu

Month of Ţebētu, 7<sup>th</sup> day.

## **412. BM 101678** (83-1-21, 3339)

PLATE 98

 $4.2 \times 3.7 \text{ cm}$ 

[Nbk] 34

- 1. [x G]Ú.UN SÍG.ḤI.A pap-pa-su
- 2. [šá É] <sup>d</sup>IM u É <sup>d</sup>Gu-la
- 3. [TA<sup>?</sup> (x)] SÍG.HI.A MU.34.KAM
- 4. [a-na] <sup>m</sup>Mu-šal-lim-<sup>d</sup>[AMAR.UTU] [SUM<sup>na</sup>]

\_\_\_\_\_

5. [x *m*]*a-na* SÍG.ḤI.A *a-*[*na* ....] 6. [x x (x)]-*rik-tu*<sub>4</sub> <sup>r</sup>x<sup>1</sup>[....] 7. [x x] *na* [x x (x)]

Rest lost

Rev.

1'. [....] <sup>[</sup>x<sup>1</sup>[....]

2'. [LUG]AL TIN.TI[R<sup>ki</sup>]

L. 4. Mušallim-Marduk is most probably identical with Mušallim-Marduk/Šamaš-šum-ukīn//*šangû* Sippar known from the 33<sup>rd</sup> year of Nebuchadnezzar till the 3<sup>rd</sup> year of Neriglissar, see MacGinnis 2000, p. 63.

x talent(s) of wool, the prebendary income [of the chapel] of Adad and the chapel of Gula [from $^{?}$ ] the wool for  $34^{th}$  year, [was given to] Mušallim-Marduk.

\_\_\_\_\_\_

[x m]inas of wool for [....] [..., ki]ng of Babylon.

#### **413. BM 61726** (82-9-18, 1696)

 $5.3 \times 3.7$  cm

1. 6 GÚ.UN <sup>[6]</sup>				<sup>md</sup> EN-MU
2. ina lìb-bi 2 ½				sat-tuk
3. 4	1 me 80	blank	blank	<sup>md</sup> EN-MU

Rev. uninscribed

The tablet has been re-used. On the reverse the traces of erased signs are still visible, and the numeral 6 in l. 1 looks also like intentionally erased. Leichty suggested in the *Catalogue* that the tablet was a "wool ledger", but this opinion can be supported only by the high quantity in first line. If we accept the possibility that 6 talents means the total amount due from Bēliddin, the second line might include the quantity of wool destined for the *sattukku* offering, while l. 3 sheep: 4 (rams) and 180 (ewes). The proposal seems to be uncertain because of high productivity: ca. 1 mina 57.4 shekels of wool per one sheep.

6 talents 6 (minas of wool from?) Bēl-iddin including 2 talents 2 ½ (minas of wool for) regular offering

4 (rams?) 180 (sheep) (at disposal of?) Bēl-iddin.

## **414. BM 65976** (82-9-18, 5968)

 $4.7 \times 5.3$  cm

(3.3).[Nbk] 19

1'. [x x] <sup>[1]</sup> 5 GÚ.UN SÍG.ḤI.[A] 2'. [(x x)] <sup>síg</sup>ta-bar-ri u ta-k[il-ti]

- 3'. [šá M]U.19.KAM 9 GÚ.UN 50 [ma-na] 4'. [SÍG]. HI.A šá sat-tuk  $^{md}$ AG-EN-MU.M[EŠ]
- 5'. lúUŠ.BAR <SUM<sup>na</sup>> ITI.SIG<sub>4</sub> U<sub>4</sub>.3.[KAM]

6'. [PAP x+] 5 GÚ.UN 38 ½ ma-na SÍ[G.HI.A]

7'. [a]-na dul-lu šá šid-du šá É-babbar-r[a]

\_\_\_\_\_

- 8'. [x] GÚ.UN a-na 2 ma-na KÙ.BAB[BAR]
- 9'. [x x]  $^{r}x^{1}$  [x] ITI.  $^{r}SIG_{4}^{?!}$ [....] 10'. [x x x]  $^{r}x^{1}$  [x]  $^{r}ITI.SIG_{4}^{?!}$

Rest of Obv. lost

In the middle of rev. on the very left side of preserved part, a fragment of one sign, most probably lu is preserved, followed by free space for ca. 4 lines and the next two lines written in the opposite direction (from the bottom to the upper of the "width" of the tablet).

- 1'. [PAP<sup>?</sup>] 42 GÚ.UN 「55<sup>†</sup> *m*[*a-na*] 2'. SÍG.HI.A
- L. 7'. Note that the *šiddu* is not destined for the gods or to the performer of the service but for the Ebabbar temple, i.e. it was an elaborate curtain (note the high weight) in the (main) part of the temple of Šamaš. The *šiddu* is also mentioned in BM 65729: 8'.
- [...] 15 talents of red and blue-purple wool for the 19<sup>th</sup> [ye]ar; 9 talents 50 [minas of wo]ol, of regular offering, Nabû-bēl-šūmāti, the weaver <has delivered>. Month of Simanu, 3<sup>rd</sup> day

[Total x+]5 talents 38 ½ minas of wo[ol f]or manufacture of the šiddu-curtain of the Ebabbar temple.

[x] talents (of wool) for 2 minas of silver [....], [total<sup>?</sup>] 42 talents 55 mi[nas] of wool.

**415. BM 65050** (82-9-18, 5031)

 $4.3 \times 3.0$  cm

11.6b.<Cam 3>

- 1. 5 ma-na SÍG.HI.A
- 2. <sup>m</sup>Lib-lut
- 3. lúTÚG.KAL.KAL
- 4. ITI.KIN 2-na.KAM
- 5. U<sub>4</sub>.11.KAM MU.3.KAM
- L. 3. Liblut was active in the time of Cyrus and Cambyses (Bongenaar, Ebabbar, p. 330, and Zawadzki, Garments of the Gods, Vol. I, p. 218), but only during the third year of the second king there was an intercalary Ulūlu month, described here in a slightly atypical way.

5 minas of wool (for) Liblut, the mender. Month of Ulūlu II, 11th day, 3rd year.

## **416. BM 60900** (82-9-18, 876)

PLATE 99

 $7.5 \times 6.0$  cm

#### 3.1.Dar 29

- 1. 1 GÚ.UN 40 ma-na SÍG.HI.A TA 'É' SÍG.HI.A
- 2. a-na lu-bu-uš-tu<sub>4</sub> šá <sup>d</sup>UTU šá U<sub>4</sub>.10.KAM šá ITI.GU<sub>4</sub>
- 3. šá MU.29.KAM a-na <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>
- 4. EN SÍG.ḤI.A šá a-na <sup>m</sup>TIN<sup>su</sup>- <sup>d</sup>AMAR.UTU SUM<sup>na</sup> -----
- 5. [x] 「GÚ¹.UN SÍG.HI.A a-na sib-ti<sup>meš</sup> šá U<sub>4</sub>.10.KAM
- 6. [šá I]TI.GU<sub>4</sub> MU.29.KAM *a-na* <sup>md</sup>AMAR.UTU-*ri-man* <sup>an</sup>-ni  $SUM^{r^{na}}$

- 7. [x m]a-na SÍG.HI.A a-na ta-ḥap-šú šá ITI.GU<sub>4</sub>
- 8.  $[x \times a-n]a^{r^m}AD^1-\dot{U}RU^{l\acute{u}}U\check{S}.BAR SUM^{na}$

\_\_\_\_\_

- 9. [x x x x] 「šá $^{?}$ 1 ina SÍG.ḤI.A šá ITI.GU4 MU.[2]9.KAM
- 10.  $[x \times x \times x]^{\mathsf{r}^d} IM^{\mathsf{q}} a$ -na  $^{\mathsf{m}^d} UTU$ -MU-<MU>
- 11. [x x x x  $^{m}$ *Ha*]-ba-ṣi-ru SUM $^{na}$

\_\_\_\_\_

12. [x ma-na] SÍG.HI.A 「a¹-na 4 GÍN KÙ.BABBAR BABBAR-ú Rev.

- 13. [a-n]a <sup>md</sup>AG-bul-liṭ-su A <sup>m</sup>Lu-UD.DU-a-na-ZÁLAG SUM<sup>na</sup>
- 14. [x ma-n]a a-na šam-ni šá U<sub>4</sub>.17.KAM šá ITI.[x]
- 15. r<sup>md</sup>EN-lu¹-da-ri šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> SUM<sup>na</sup>
- 16. ITI.BÁR U<sub>4</sub>.3.KAM MU.29.KAM 17. <sup>m</sup>Da-ri-ja-muš LUGAL 「TIN.TIR<sup>1ki</sup> LUGAL KUR.KUR
- L. 8. Abu-uşur = Abu-šar-uşur, see Zawadzki, Garments of the Gods, Vol. I, p. 208.

1 talent 40 minas of wool from the wool-house for the *lubuštu* ceremony of the god Šamaš for the 10<sup>th</sup> day of the month of Ayaru of the 29<sup>th</sup> year was given to Šamaššum-iddin, the weaver, including the wool which was given to Uballissu-Marduk. -----

[x] talent(s) of wool for the *sibtu*-garments for the 10<sup>th</sup> day of the month of Ayaru of the 29<sup>th</sup> year was given to Marduk-rēmanni

[x mi]nas of wool for the tahapšu-blanket for the month of Ayaru was given to Abu-usur, the weaver

[x minas of wool] from wool for the month of Ayaru, [2]9<sup>th</sup> year [....] of Adad was given to Šamaš-šum-<iddin> [....] (and) Ḥabaṣiru

[x minas] of wool for 4 shekels of white silver was given to Nabû-bullissu, son of Lūṣi-ana-nūr

[x min]a(s) (of silver) for the oil for the 17<sup>th</sup> day of the month A[yaru<sup>?</sup>] was given (to) Bēl-lū-dāri of the Queen of Sippar.

Month of Nisannu, 3<sup>rd</sup> day, 29<sup>th</sup> year of Darius, king of Babylon, king of Lands.

#### 417. BM 60553 (82-9-18, 528)

PLATE 100

 $7.9 \times 6.2 \text{ cm}$ 

#### 26.2.Dar 30

- 1. [2<sup>?</sup> GÚ.U]N 22 ma-na 50 GÍN SÍG.HI.A
- 2. 「gi-zi<sup>¬meš</sup> šá 1 me 15 și-e-ni
- 3. [šá] <sup>m</sup>Ši-rik-tu<sub>4</sub> A <sup>m</sup>KI-<sup>d</sup>UTU-TIN ina ITI.GU<sub>4</sub> it-<sup>r</sup>ta<sup>1</sup>-[din]
- 4. [ina lì]b-bi 1 GÚ.UN SÍG.HI.A a-na lu-bu-uš-<sup>r</sup>tu<sub>4</sub><sup>1</sup>
- 5. šá ITI.KIN šá MU.30.KAM a-na <sup>m</sup>ÌR-<sup>d</sup>U+GUR
- 6. A <sup>md</sup>EN-KÁD *ina qí-bi šá* <sup>m</sup>Še-<sup>r</sup>x¹-[x x (x)]
- 7. A-šú šá  ${}^{m}Mu$ -ra-šu-ú {a-[na] [ ${}^{m}$ ]R- ${}^{d}$ U+GUR]
- 8. [A]- $^{\Gamma}$ šú šá $^{\Pi}$  EN-KÁD SUM $^{na}$ }

Rev.

- 9. ITI.GU<sub>4</sub> U<sub>4</sub>.26.KAM MU.30.KAM
- 10.  $^{\rm m}Da$ -ri-ja-muš [LUGAL TIN.TI]R.[KI LUGAL]  $^{\rm r}$ KUR $^{\rm l}$ .KUR
- L. 7. The text which follows the name of Murašu and l. 8 should be recognized as a scribal error

[2<sup>?</sup> talen]ts 22 minas 50 shekels of wool from the shearing of 115 sheep [which] Širikti, son of Itti-Šamaš-balāṭu has delivered in the month of Ayaru; out of it 1 talent of wool for the *lubuš*tu ceremony of the month Ulūlu, 30<sup>th</sup> year, was given to Arad-Nergal, son of Bēl-kāṣir at the order of Še-x x, son of Murašû. Month of Ayaru, 26<sup>th</sup> day, 30<sup>th</sup> year of Darius, [king of Baby]lon, [king] of Lands.

## **418. BM 64600** (82-9-18, 4580)

PLATE 100

 $5.5 \times 4.2$  cm

- 1. 20 ma-n[a SÍG.HI.A] KI.LAL 「TÚG.HI.A]
- 2.  $\dot{u}^{\text{túg}}$ şib-[t]i šá  $^{\text{d}}$ IM
- 3. 3 ma-[na < KI.LAL > ni]-[bi]-hu
- 4. ½ ma-na SÍG.ZA.GÌN.KUR.RA
- 5. KI.LAL TÚG.UD.A ku-lu-lu
- 6. *šá* <sup>d</sup>UTU {*an*} (er.)
- 7. <sup>[3]</sup> ma-na KI.LAL 1 TÚG.SAG<sup>?</sup>

Edge 8. *šá* <sup>d</sup>UTU

L. 1. 15 minas of *lubāru* for Adad and 5 minas of *şibtu* for Adad gives exactly 20 minas, as stated in the texts.

L. 2. The broken space is too small to place there KI.LAL. The suggested reading is based on the fact that the weight of  $n\bar{e}behu$  is about 3 minas, see Zawadzki, *Garments of the Gods*, Vol. I, p. 188ff.

L. 7. The reading TÚG.SAG is highly uncertain, cf. the copy and commentary to 1. 4 of Cyr 241 (= 229).

20 mina[s of wool], the weight of the *lubāru* and *şibtu*-garments for Adad;

3 minas, <the weight> of the *nebēhu*-belt

½ mina of blue-purple wool, the weight of the *lubār kulūlu*-headband for Šamaš 3 minas, the weight of the TÚG.SAG²-headdress for Šamaš.

### **419. BM 66852** (82-9-18, 6846)

PLATE 101

 $4.9 \times 3.5$  cm

#### [x].6.Cam 1

- 1. 「16 ma-na SÍG¹.ḤI.A [a]-「na¹
- 2. 16 ma-ši-hu šá sat-tuk <sup>[</sup>x<sup>]</sup>
- 3. ina pap-pa-su šá É <sup>d</sup>Gu-<sup>r</sup>la<sup>1</sup>
- 4. ù bi-ta-nu šá <sup>d</sup>G[AŠAN Sip-par<sup>ki</sup>]
- 5. mdEN-MU ITI.KIN U[4.x.KAM]
- 6. MU.1.KAM <sup>m</sup>*Ka*[*m-bu-zi-ja*]
- 7. LUGAL E.[KI LUGAL KUR.KUR]

### Rev. uninscribed

- L. 1–2. If our reading is correct, it means that one *sattukku*-measure is equivalent to 1 mina of wool
- L. 4. There is no enough space for *Sip-par*<sup>ki</sup> to be written.
- L. 5. The expected verb after the name is missing. Bēl-iddin, see Bongenaar, *Ebabbar*, pp. 71, 244f.

16 minas of wool for 16 *sattukku*-measures ... from the prebendary income of the Gula temple and the inner quarter of the Queen of <Sippar>, Bēl-iddin (has received).

Month of Ulūlu, [n<sup>th</sup> d]ay, 1<sup>st</sup> year of Cam[byses], king of Ba[bylon, king of Lands].

## **420. BM 60784** (82-9-18, 759)

PLATE 101

 $4.6 \times 3.4$  cm

## 9.4.[Nbn] 16

- 1. 「9<sup>?</sup>」 5/6 *ma-na* 「SÍG¹.HI.A
- 2. 「a¹-na 2 GÍN gír-ú.LAL KÙ.BABBAR
- 3. ŠÁM TÚG.BAR.SI.MEŠ
- 4. md AG-MU-MU KAR
- 5. ITI.ŠU U<sub>4</sub>.9.KAM

Rev. 6. MU.16.KAM [<sup>md</sup>AG-I] 7. LUGAL TIN.TIR.<sup>r</sup>KI<sup>1</sup>

L. 6. The gap was filled with the name of Nabonidus, because there is not enough place for a longer name.

 $\lceil 9^{?_1} \rceil$  minas 50 shekels of wool for 1 23/24 shekels of silver, the price of the *paršīgu*-headdress, Nabû-šum-iddin has paid.

Month of Du'ūzu, 9<sup>th</sup> day, 16<sup>th</sup> year [of Nabonidus], king of Babylon.

## **421. BM 66698** (82-9-18, 6692)

 $3.1 \times 3.6$  cm

Rev.

#### 21.7.Cam [x]

- 1. 6 ma-na SÍG.Ḥ[I.A a-na]
- 2. TÚG.ÍB.LÁ *šá* <sup>d</sup>UT[U]
- 3. a-na <sup>m</sup>Ri-ḥi-tú [SUM<sup>na</sup>]
- 4. 40 ma-na SÍG.HI.[A a-na]
- 5. <sup>lú</sup>UŠ.BAR-*ú-tu* [....]
- 6. e-lat 10 GÍN KÙ.BABBAR [a-na]?

Edge 7.  $^{\text{md}}$ UTU-MU-MU  $^{1}$ [ $^{\acute{\text{u}}}$  ....]

8. ITI.DU<sub>6</sub> U<sub>4</sub>.21.KAM [MU.x.KAM]

9. "Kam-bu-zi-ja L[UGAL TIN.TIR<sup>ki</sup>]

10. LUGAL KUR.KUR

L. 7. It is impossible to say which of the two titles of Šamaš-šum-iddin was written in the text. Concerning him, see Bongenaar, *Ebabbar*, pp. 347f. and Zawadzki, *Garments of the Gods*, Vol. I, p. 227ff.

6 minas of wool for the *nēbehu*-belt for Šamaš [was given] to Rēhētu.

40 minas of wool as the weaver's prebend [was given']; except for 10 shekels of silver [which was given to] Šamaš-šum-iddin, the [weaver/bleacher].

Month of Tašrītu, 21st day, [nth year] of Cambyses [king of Babylon], king of Lands.

## **422. BM 66202** (82-9-18, 6193)

 $6.4 \times 5.0$  cm

#### 12.[x.Dar] 18

- 1. [x ma-na x GÍN] SÍG.HI.A ina lu-bu-uš-tu<sub>4</sub>
- 2. [šá ITI.x U<sub>4</sub>.x.KAM MU].18.KAM a-na
- 3. [<sup>md</sup>UTU]-MU-MU <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>
- 4. [x ma-n]a SÍG.ḤI.A ina ṣi-ba-tu4 šá <sup>d</sup>UTU
- 5. [....] a-na <sup>md</sup>AMAR.UTU-ri-man<sup>an</sup>-ni SUM<sup>na</sup>

Two lines completely erased.

Rev. Beginning uninscribed

- 1'. ITI.[API]N<sup>?</sup> U<sub>4</sub>.12.KAM MU.18 KAM
- 2'. [mDa-ri-ja-muš LUG]AL TIN.TIRki

L. 3. The presence of Šamaš-šum-ukīn and Marduk-rēmanni makes the dating of the text to the time of Darius certain, but the lack of LUGAL KUR.KUR is strange. Possibly it was written in the missing left hand edge of the tablet.

Rev. 1'. From the name of the month only one vertical wedge is preserved, but because the *lubuštu* ceremony is mentioned, the only possibility seems to be the month of Arahsamna.

[x mina(s) x shekels] of wool for! the lubuštu ceremony for the [nth day of the month x], 18<sup>th</sup> [year] was given to [Šamaš]-šum-iddin, the weaver. [x min]as of wool for! the *şibtu*-garments for Šamaš [....] was given to Marduk-

rēmanni.

Month [Araḥsam]na<sup>?</sup>, 12<sup>th</sup> day, 18<sup>th</sup> year of [Darius, ki]ng of Babylon.

## **423. BM 70592** (82-9-18, 10593)

 $5.3 \times 3.5$  cm

#### 28.2. [Dar] 17

- 1'. *lu-bu-uš-tu*<sub>4</sub> *šá* 「U<sub>4</sub>¹.[10.KAM]
- 2'. šá ITI.GU<sub>4</sub> MU.17.KAM
- 3'. a-na  $^{m}$  $\acute{U}$ -bal-lit-su- $^{d}$ Gu-la 4'.  $SUM^{na}$
- 5'. 「9<sup>?</sup>¬ *ma-na* SÍG.ḤI.A
- 6'. [a]-na ta-hap-šú šá ITI.GU<sub>4</sub>
- 7'. 「MU¹.17.KAM [*a-na*]
- 8'. [m]ÎR-*ja* l<sup>lí</sup>[Uй.[BAR] SUM<sup>na</sup> 9'. ITI.GU<sub>4</sub> U<sub>4</sub>.28.KAM
- 10'. [MU.1]<sup>[7]</sup>.KAM <sup>m</sup>Da-r[i-ja-muš]

Rest lost

L. 5'. The numeral might be also 8 or even x+8/9.

[.... for] the *lubuštu* ceremony of the 10<sup>th</sup> day of the month Ayaru, 17<sup>th</sup> year, was given to Uballissu-Gula

 $\tilde{9}^{?}$  minas of wool for the *taḥapšu* of the month Ayaru, 17<sup>th</sup> year, was given [to] Ardīya, [the wea]ver. Month of Ayaru, 28<sup>th</sup> day, [1]7<sup>th</sup> [year] of Dar[ius, ....].

## **424. BM 66777** (82-9-18, 6770)

 $5.2 \times 3.9 \text{ cm}$ 

## [x].8.<KN>31

- 1. [x ma-na S]ÍG.ḤI.A [a-na] lu-[bu-uš]-tu<sub>4</sub>
- 2. [šá U]<sub>4</sub>.15.KAM [šá] ITI.ŠE

- 3. a-na <sup>m</sup>EN- $\check{s}\acute{u}$ -nu <sup>lú</sup>e- $pi\check{s}$ - $<\check{s}\acute{a}>$ -nu
- 4. [šá <sup>md</sup>EN-bu]l-liṭ-su SUM<sup>na</sup>
- 5. [x ma-na SÍ]G.HI.A ri-hi SÍG.HI.A
- 6. [šá IT]U.APIN MU.31.KAM
- 7.  $[x \times x \times x]$   $[x \times TIN.TIR^{ki_1}]$

#### Rest lost

L. 3. Bēlšunu, the *ēpišānu* is not known before and the identification of his master is also problematic (most probably Bēl-bullissu, cf. BM 61011 (= 407): 5).

[x minas of w]ool [for] the  $lu[bu\check{s}]tu$  ceremony of the 15<sup>th</sup> day of Addaru was given to Bēlšunu, the performer of [Bēl-bu]llissu.

[x minas of w]ool, the rest of wool [for the month] of Araḥsamna, 31<sup>st</sup> year [of KN, king] of Babylon.

## **425. BM 63992** = Bertin 1868 Collated

 $4.3 \times 3.7 \text{ cm}$ 

#### 20.2.Cam 6

Obv. 1. 6 ma-na SÍG.HI.A

2. a-na ú-za-ri šá an-dul-lum

3. šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> a-na

4. <sup>md</sup>30-DINGIR A-*šú šá* <sup>md</sup>UTU-MU SUM<sup>na</sup>

5. ITI.GU<sub>4</sub> U<sub>4</sub>.20.KAM MU.6.KAM

6. <sup>m</sup>Kam-bu-zi-ja

Edge 7. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

Rev. 8. 5 ma-na SÍG.ḤI.A

9. *ina* SÍG.HI.A *šá* <sup>md</sup>AG-SUR

10. e-lat IGI-tu<sub>4</sub> a-na

11. md AG-SUR 1 GÚ.UN 43 ma-na

12. SÍG.ḤI.A šá <sup>md</sup>AG\*-SUR\*

13. ina É-babbar-ra <SUM<sup>na</sup>> ITI.GU<sub>4</sub>

14. U<sub>4</sub>.20.KAM MU.6.KAM

L.e. 15. <sup>m</sup>Kam-bu-zi-iá

Lh.e. 16. LUGAL TIN.TIR<sup>ki</sup>

17. LUGAL KUR.KUR

6 minas of wool for the cover of the canopy of the Queen of Sippar were given to Sin-ilī, son of Šamaš-iddin. Month of Ayaru, 20<sup>th</sup> day, 6<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

5 minas of wool from the wool of Nabû-ēṭir, except for an earlier (issue) for Nabû-ēṭir, (total) 1 talent 43 minas of wool, which Nabû-ēṭir <has received> from the Ebabbar temple. Month of Ayaru, 20<sup>th</sup> day, 6<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

## **426. BM 73825** (82-9-18, 13836)

4.2 x 2.7 cm

- 1. [x ma-na SÍG.HI.A] KI.LAL <sup>túg</sup>ú-za-ri
- 2. *šá an-dul-lu šá* <sup>d</sup>A-*nu-ni-tu*<sub>4</sub> 3. <sup>rmd</sup>ḤAR-DÙ¹ <sup>lú</sup>UŠ.BAR *it-ta-din*
- 4. [....] <sup>r</sup>x<sup>1</sup> *ri-hi*
- 5. [....] <sup>r</sup>x x<sup>1</sup>
- L. 3. Bunene-ibni is most probably the person identical with Bunen-ibni <*ša bīt Anunnītu*>, see Bongenaar, Ebabbar, p. 247, however here he is mentioned for the first time with the

[x mina(s) of wool], the weight for the cover of the canopy of Anunītu, Buneneibni, the weaver has delivered [....], the rest [....].

## **427. BM 72999** (82-9-18, 13008)

PLATE 102

 $8.3 \times 5.4$  cm

```
1'. [.... M]U<sup>?</sup>.3<sup>?</sup>.KAM <sup>m</sup>ÌR<sup>?</sup>-[....]
                       _____
                      2'. [x ma-na] a-na 	ilde{s}ib-tu_4 	ilde{s}\acute{a} ^{\rm d}UTU 	ilde{s}\acute{a} ITI. ^{\Gamma} 	ilde{S}U^{
m l}
                       3'. [x] ma-na a-na lu-bu-uš-tu<sub>4</sub> šá
                       4'. [ITI].ŠU šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> a-na
5'. [<sup>m</sup>TIN]-su-<sup>d</sup>Gu-la SUM<sup>na</sup>
                      6'. [x m]a-na a-na ^{\text{túg}}ú-za-ri šá an-dul-lu 7'. [šá] ^{\text{d}}GAŠAN UD.KIB.NUN^{\text{ki}} a-na
Edge
Rev.
                       8'. mdEN-ŠEŠ-it-tan-nu 「SUM<sup>na</sup>1
                      9'. [x m]a-na! šá <sup>túg</sup>ú-za-ri šá an-dul-lu šá
                    10'. [<sup>d</sup> A-nu]-<sup>r</sup>ni]-tu<sub>4</sub> x 5 ½ ma-na šá
11'. [x x] x 1 ḫu-ṣa-nu<sup>meš</sup> šá <sup>d</sup>Dumu-zi
12'. [x] a-na <sup>m</sup>TIN-su-<sup>d</sup>Gu-la SUM<sup>[na]</sup>
```

L. 10' na is written over erasure.

[....] 3<sup>rd?</sup> year<sup>?</sup> Ardi-[....]

13'. [x ma-na a-na s]ib-tu4 sá [x][....]

[x mina(s)] for the *şibtu*-garment for Šamaš for month Du'ūzu

[x] mina(s) for the *lubuštu* ceremony of the [month] Du'ūzu for Anunītu was given to [Ubal]lissu-Gula

-----

 $[x]\mbox{ mina}(s)$  for the cover for the canopy of the Queen of Sippar was given to Bēlah-iddina

•

[x] mina(s) for the cover for the canopy of [Anu]nītu; 5 ½ mina for [the ....], 1 sash for Dumuzi [was given] to Uballissu-Gula.

-----

[x mina(s) for the *şib*]tu for [....].

## **428. BM 101063** (83-1-21, 2724)

 $5.3 \times 2.6$  cm

- 1. 1 GÚ.UN 1 ma-<na> ri-ḥi lu-bu-uš-tu<sub>4</sub>
- 2. U<sub>4</sub>.15.KAM ITI.ŠE MU.11.KAM ½ GÚ.UN
- 3. SÍG.ḤI.A 「EN 111 ma-na IGI-「tu41
- 4. *a-na ku-si-tu*<sub>4</sub> [šá <sup>d</sup>DN]
- 5. <sup>[</sup>x x x<sup>]</sup> [....]

Rest lost

Rev.

- 1'.  $\lceil x \ x \rceil \ tin \ [....]$
- 2'. 1 「GÍN 4-tú KÙ.BABBAR a-na 5 ma-na SÍG.HI.A
- 3'. a-na [ $^{m}(x)$ ]Muq-qí-e-lip SUM $^{na}$
- 4'. 1 「KÙR ZÚ.LUM.MA<sup>1</sup> ri-hi ma-la-tu<sub>4</sub>

Edge 5'. "MU-dAG A "Na-şir SUR

L. 3'. The *muq* might be preceded with one small sign (e.g. EN).

1 talent, 1 mina, the rest (of wool for) the  $lubu\check{s}tu$  ceremony for the  $15^{th}$  day of the month Addaru,  $11^{th}$  year

½ talent of wool, together with 11 minas an earlier (issue) for robe [for DN ....]

11/4 shekels of silver for 5 minas of wool for Muqqe<a>-elīp was given

1 kurru of dates, the rest of the  $mal\bar{a}tu$ -payment is paid (to) Iddin-Nabû, son/descendant of Nāṣir.

## **429. BM 83281** (83-1-21, 444)

PLATE 103

 $3.8 \times 3.3$  cm

13.6.Nbn [8]

- 1. 1 GÚ.UN 40 ma-na [SÍG.HI.A]
- 2. a-na dul-lu šá ITI.[x]
- 3. MU.8.KAM *a-na*
- 4.  ${}^{\rm m}Ba$ -ku- ${}^{\rm \Gamma}\acute{u}$ -[a]

- 5. lúla-[mu-ta-nu šá]
- 6. md[AG-ŠEŠ-A lúUŠ.BAR SUM<sup>na</sup>]

7. ITI.KIN U<sub>4</sub>.13.KAM M[U.8.KAM] Rev.

8. mdAG-I LUGAL TIN.T[IRki]

The data from this text are included to the yearly account concerning wool and garments in BM 76590+ (= 163), rev. col. I 7'-8'.

1 talent 40 minas [of wool] for the work of the month [x], the 8<sup>th</sup> year, [was given] to Bakûa, the ser[vant of Nabû-nāṣir-apli, the weaver]. Month of Ulūlu, 13<sup>th</sup> day, [8<sup>th</sup> year] of Nabonidus, king of Baby[lon].

## **430. BM 67252** (82-9-18, 7248)

**PLATE 103** 

6.  $3 \times 4.3$  cm

#### 19.7.Nbn 10

- 1. 「SÍG.HI.A<sup>†</sup> šá {ina} ul-tu É šu-tum LUGAL
- 2. *a-na dul-lu* SUM<sup>nu</sup> ITI.DU<sub>6</sub> U<sub>4</sub>.20.1.LAL.KAM 3. MU.10.KAM <sup>md</sup>AG-I LUGAL TIN.TIR<sup>ki</sup>

- 4. [x G]Ú.UN a-na dul-lu šá ITI.ŠE <sup>m</sup>Ba-ku-ú-a
- 5. [x ma]-na a-na lu-bu-šú-si-tu<sub>4</sub> ù dul-lu ta-bar-ri
- 6.  $[x \times x \times \dot{U}R]U^{?_1}{}^m Ba-ku-\acute{u}-a$
- 7. [x x x x] <sup>r</sup>TÚG<sup>1</sup>.ÍB.LÁ *šá* <sup>d</sup>UTU
- 8.  $[x \times x \times x]^{\lceil a \rceil}$ -di-la-nu

Edge

- 9.  $[\mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x}] \check{s} \acute{a}^{\mathbf{d}} \mathbf{A} a^{\mathsf{T}}$
- 10. [x x x x IT]U.GU<sub>4</sub> MU.11.KAM

Rev.

- 11.  $[x \times x \times x]$  [dul]-lu ta-bar-ri
- 12.  $[x x x x x]^{-r} \check{s}i^{\gamma}$
- 13. [x x x x] *ta-kil-ti*!
- 14.  $[x \times x \times ^mD]UB^?$ -NUMUN
- 15. [PAP<sup>?</sup>] + <sup>1</sup>31 ½ GÚ.UN 5 ma-na SÍG.HI.A

L. 5. *lu-bu-šú-si-tu*<sub>4</sub> is a strange form and it is not excluded that it is a scribal error.

Wool, which from the king's storehouse for work was given Month of Tašrītu, 19<sup>th</sup> day, 10<sup>th</sup> year of Nabonidus, king of Babylon

[x tale]nts for the work for the month of Addaru (for) Bakûa

[x mi]nas for the *lubuštu*<sup>?</sup> ceremony and for manufacturing red wool [.... for ....] uşur (and) Bakûa.

- [....] the *nēbehu*-belt for Šamaš
- [....] *adilānu*-tassel<sup>?</sup> [...] for Aya [....], month Ayaru, 11<sup>th</sup> year [....] (for) work with red wool
- [....] blue-purple wool [....] (for) Šāpik-zēri,

[total x+] 3 talents 35 minas of wool.

## **431. BM 63919** = Bertin 1526 Collated

## 21.5.Nbn 13

- 1. 3 ma-na SÍG.HI.A
- 2. a-na dul-lu šá ITI.KIN
- 3. *a-na* <sup>m</sup>*Ba-ku-ú-a* 4. SUM<sup>na</sup>

Rev.

- 5. ITI.NE U<sub>4</sub>.21.KAM
- 6. MU.13.KAM
- 7.  $^{d}$ AG-I LUGAL  $E^{ki}$

3 minas of wool for the work of the month of Ulūlu was given to Bakûa. Month of Abu, 21<sup>st</sup> day, 13<sup>th</sup> year of Nabonidus, king of Babylon.

## **432. BM 74431** = Bertin 1510 Collated

#### 9.6.Nbn 13

- 1. [x *m*]*a-na* SÍG.HI.A
- 2. [a]-na dul-lu a-na
- 3. [<sup>m</sup>Ba]-ku-ú-a <sup>lú</sup>qal-la 4. šá <sup>md</sup>AG-ŠEŠ-A SUM<sup>in</sup>
- 5. ITI.KIN U<sub>4</sub>.9.KAM
- 6. MU.13.KAM

Rev.

7. md AG-I LUGAL NUNki

[x mi]nas of wool for the work was given to Bakûa, the slave of Nabû-naşir-apli. Month of Ulūlu, 9<sup>th</sup> day, 13<sup>th</sup> year of Nabonidus, king of Babylon.

## **433. BM 100960** (83-1-21, 2621)

 $4.5 \times 2.7$  cm

## [Nbn] 3

- 1'. [....]-tú
- 2'. u <sup>m</sup>[Ba]-[ku-ú-a ....] šá
- 3'. [....] 4'. [md AG-EN-MU.MEŠ]
- 5'. lúUŠ.BAR SUM<sup>in</sup>
- Rev.
- 1'. 14 ma-na ŠUKU.HI.A
- 2'. lúŠID šá MU.3.KAM a-na
- 3'. UGU <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>UŠ.BAR SUM<sup>[in/na]</sup>
- 4'. 10 ma-na a-na mu-sib-tu4
- 5'. *šá* <sup>md</sup>AG-ú-pi-ni-e <sup>[</sup>ù<sup>]</sup>
- 6'. Γ<sup>m</sup>*Ba*<sup>¬</sup>-[*ku-ú-a* ....]

Obv. is heavily eroded. Rev. 2'. The  $3^{rd}$  year has to be identified with the  $3^{rd}$  year of Neriglissar or more probably with the  $3^{rd}$  year of Nabonidus.

[.... and Ba[kûa ....] Nabû-bēl-šumāti, the weaver was given.

14 minas (of wool), the ration of the scribe for the 3<sup>rd</sup> year on account of Nabû-bēl-šumāte, the weaver was given.

10 minas for the garments for Nabû-upnīya and Ba[kûa ....].

## **434. BM 71878** (82-9-18, 11881)

PLATE 104

 $3.7 \times 2.9$  cm

24.[6<sup>?</sup>].Nbn 0

- 1. [x] ma-na SÍG.HI.A a-na
- 2. [dul-lu] šá ITI.DU<sub>6</sub>
- 3.  $[a-na^{m}Ba]^{-1}ku^{1}-\acute{u}-a$
- 4. [lúqal-la šá md]AG-EN-MU.MEŠ
- 5.  $[^{\text{lú}}\text{U}]$ Š.BAR SUM<sup>in</sup>

- 6. [ITI.KIN<sup>2</sup> U] <sub>4.2</sub>5.KAM 7. [MU.SAG.NA]M.LUGAL.LA 8. [<sup>md</sup>A]G-<sup>[I]</sup> LUGAL TIN.TIR<sup>ki</sup>

[x] minas of wool for [the work] of the month Tašrītu was given [to Ba]kûa, [the slave] of Nabû-bēl-šumāti, the weaver.

[Month of Ulūlu<sup>2</sup>], 25<sup>th</sup> da[y, the acces]sion year of Nabonidus, king of Babylon.

## **435. BM 101488** (83-1-21, 3149)

PLATE 104

 $4.2 \times 3.9 \text{ cm}$ 

Dar 20+x

- 1. 12 *ma-na* SÍG.Ḥ[I.A *a-na*]

- 2. *lu-bu-uš*-<*tu*<sub>4</sub>> *a-na* <sup>m</sup>[PN] 3. <sup>lú</sup>2-*ú šá* <sup>md</sup>UTU-*a*-[*a*] 4. <sup>lú</sup>TIL.LA.GÍD.DA 「ɹ-[babbar-ra]
- 5. SUM<sup>na</sup> ITI.  $\lceil x \rceil \lceil U_4.x.KAM \rceil$

Rev.

- 6. [MU].20+[x.KAM]
- 7. [<sup>m</sup>Da]-ri-[ja-muš LUGAL E<sup>ki</sup> LUGAL KUR.KUR]

Rest lost

- L. 3. Šamšaya, the qīpu, see Bongenaar, Ebabbar, p. 50. This is the first attestation of the engagement of a person of such high status in the preparation of the *lubuštu* ceremony.
- 12 minas of wool [for] the lubuštu ceremony to [PN], the deputy of Šamšaya, the qīpu of Ebabbar was given.

Month of [x, day x], 20+[x] year of [Da]ri[us], [king of Babylon, king of Lands].

## **436. BM 64072** = Bertin 2593

#### 26.9.Dar 28

- 1. 5 ma-na SÍG.HI.A sat-tuk
- 3. mi-ih-şu <sup>d!</sup>GAŠAN
- 4. šá U<sub>4</sub>.28.KAM šá ITI.GAN
- 5. a-na <sup>md</sup>AMAR.UTU-ri-man-ni</sup>

Edge

- 6. u <sup>m</sup>Ap-la-a
- 7. e-piš-nu šá Rev.
  - 8. lúTÚG.BABBAR SUM<sup>na</sup>
  - 9. ITI.AB U<sub>4</sub>.26.KAM
  - 10. MU.26.KAM
  - 11. <sup>m</sup>Da-ri-mu-šú
  - 12. LUGAL KUR.KUR

In Bongenaar, Ebabbar, p. 316 and 331 (under Aplā and Marduk-rēmanni) change "dates" to "wool".

5 minas of wool, the regular offering, for woven textile of the Queen of <Sippar> for the 28th Kislīmu, was given to Marduk-rēmanni and Aplā, the performer of the

Month of Tebētu, 26<sup>th</sup> day, 26<sup>th</sup> year of Darius, king of Lands.

#### **437. BM 75530** (83-118, 877) = Str II 155/1

#### 25.8.Dar 35

- 1. 1 ½ GÚ.UN S[ÍG.HI.A] a-na lu-bu-uš-tu<sub>4</sub>
- 2. šá <sup>d</sup>UTU šá ITI. [ŠE U<sub>4</sub>.15.KAM M]U.35.KAM
- 3. ½ GÚ.UN SÍG.H[I.A KI.LAL]  $^{\text{rtúg}}$ ku-si $^{1}$ -tu $_{4}$  ù
- 4. <sup>r</sup>na-ah-la-ap-tu<sub>4</sub><sup>1</sup> šá <sup>d</sup>A-a ITI.GU<sub>4</sub> MU.36.KAM
- 5. PAP 2 GÚ.UN SÍG.ḤI.A a-na pi 「ra² tu4¹
- 6.  $\dot{u}^{T}x x x^{T} \dot{s} \dot{u}^{hi}U\dot{S}.BAR SUM^{na}$ 7. pu-ut dul- $lu^{m}A$ -a DUMU- $\dot{s} \dot{u}^{l}$ 8.  $^{m}Mu$ - $\dot{s} e$ -zib- $^{d}AMAR.UTU na$ - $\dot{s} i$

#### Edge erased

Rev.

- 9. 1/2 GÚ.UN SÍG.HI.A a-na ŠUKU.HI.A
- 10. lúTIL.GÍD.DA a-na <sup>m</sup>Ú-bar lúTIL.GÍD.DA
- 11. SUM<sup>na</sup> ITI.APIN U<sub>4</sub>.25.KAM
- 12. MU.35.KAM <sup>m</sup>Da-<ri-ja-muš> (sic<sup>!</sup>)

1 ½ talent of w[ool] for the *lubuštu* ceremony of Šamaš of [the 15<sup>th</sup> day] of the month [Addaru] 35<sup>th</sup> ye[ar].

 $\frac{1}{2}$  talent of woo[l, the weight] of robe and *naḥlaptu*-cloak for Aya; month of Ayaru,  $36^{th}$  year, total 2 talents of wool for [....] and [....], the weaver was given. For the work Aplā, son of Mušēzib-Marduk is responsible.

½ talent of wool for the rations of the  $q\bar{t}pu$  for Ubar, the  $q\bar{t}pu$  has been given. Month of Arahsamna, 25<sup>th</sup> day, 35<sup>th</sup> year of Da<ri>vis>.

#### **438. BM 64113** = Bertin 2933 Collated

- 1'. É  $\lceil x \times x \times x \times x \rceil$  ina lìb-bi
- 2'. 1 GÚN SÍG.HI.<A > a-na 10 GÍN KÙ.BABBAR ina gi-iz-zi
- 3'. šá AMA.MEŠ šá UDU.NÍTA pu-ha-di-e
- 4'. *šá* ITI.GU<sub>4</sub> *šá* <sup>md</sup>UTU-S[U] A <sup>md</sup>AG-NUMUN-DÙ
- 5'. ul-tu  $KUR^{i}$  i-bu-ku a-na
- 6'. "Bul-lu-ṭa-a SUM"

Rev.

- 7'. 24 ma-na SÍG.ḤI.A-šú ina E.GUR<sub>7</sub> ri-ḫi
- 8'. 8 ma-na ina É.ŠU<sup>ii</sup> 1<sup>r</sup>6<sup>r</sup> ma-na a-na
- 9'. lu-bu-uš-tu4 šá ITI.APIN a-na
- 10'. <sup>md</sup>U+GUR-MU A <sup>md</sup>UTU-SUR *e*-<sup>r</sup>*piš*<sup>-</sup>-*an-ni*
- 11'. 1 GÚ.UN 24 ma-na [x] [....]
- L. 3' Concerning puhadu, cf. van Driel, BSA 7, p. 233.

[....] including 1 talent of wool for 10 shekels of silver from the shearing of mothers of *puḥādu*-sheep in the month Ayaru, which Šamaš-er[ība], son of Nabû-zēr-ibni has brought from the mountain (and) gave to Bulṭa;

24 minas of wool (is) in  $b\bar{\imath}t$   $kar\hat{e}$  storehouse; the rest – 8 minas in  $b\bar{\imath}t$   $q\bar{a}ti$  storehouse;

16 minas for the *lubuštu* ceremony of the month Araḥsamna (was given) to Nergaliddin, son of Šamaš-ēṭir, the *epišānu*;

1 talent 24 minas [....].

## **439. BM 61311** (82-9-18,1286)

 $3.6 \times 3.5$  cm

- 1. [x x x] SÍG.HI.A ina lu-bu-uš-tu4
- 2. [šá ITI.ŠU šá] <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 3. [a-na <sup>m</sup>ŠEŠ].MEŠ-MU-<sup>d</sup>AMAR.UTU SUM<sup>na</sup>
- 4. [x x x] SÍG.ḤI.A ina pap-pa-su
- 5.  $[x \ x \ x \ x] \ ^{\lceil}x^{\rceil} [....]$

Rest of Obv. lost

Rev. 1'. [LUGAL *Bābili*]<sup>rki</sup> LUGAL KUR.KUR<sup>1</sup>

[....] of wool for the *lubuštu* ceremony [for the month Du'ūzu for] Anunītu, was given [to Aḫ]ḫē-iddin-Marduk. [...] of wool for the prebendary income [....] [king of Babylon], king of Lands.

## **440. BM 74459** = Bertin 1808 Collated

 $6.8 \times 5.8$  cm

## 10.5<sup>?</sup>.Cam 1

- 1. [x+<sup>?</sup>] <sup>1</sup> <sup>1</sup> GÚ.UN <sup>5</sup> 6 ma-na SÍG.ḤI.A
- 2.  $[x m]a^{-1}na^{?}$  6  $[GÍN^{?}]$  SÍG.ZA.GÍN.KUR.RA
- 3. [ŠÁM<sup>?</sup> x ma-n]a 3 ri-bat mi-šil bit-qa KÙ.BABBAR pap\*-<sup>[</sup>pa\*<sup>1</sup>-su\*
- 4. [šá a-na l]u-bu-uš-tu<sub>4</sub> šá U<sub>4</sub>.3.KAM
- 5. [šá IT]I.KIN a-na <sup>m</sup>Kal-ba-a
- 6. [A-šú šá <sup>m</sup>]Kab-ti-ja SUM<sup>na</sup>
- 7. [x x] [a-na] SÍG.HI.A a-na TÚG.GÚ.UD.DU.[A] [bir\*]-mu
- 8. [a-na <sup>d</sup>GAŠAN Sip]-par<sup>ki</sup> 2 <sup>túg</sup>su-nu-ni-e</sup>

Edge Rev. erasure

9. [.... n]a ți-im šá

10. [....]-nu a-na <sup>m</sup>Gi-mil-lu

11. [....] SUM<sup>na</sup>

- 12. [....] {「SÍG\*¹.HI\*.A\*} SÍG.HI.A *a-na*
- 13. [TÚG.NÍG.Í]B.LÁ.MEŠ u mu-ta-ta
- 14. [šá U<sub>4</sub>.3].KAM ITI.KIN a-na
- 15. [mdUTU]-MU-MU
- 16. ITI.NE<sup>?</sup>1 U<sub>4</sub>.10.KAM *šá* MU.1.KAM
- 17. "Kam-bu\*-zi-ja LUGAL E<sup>ki</sup>
- 18. LUGAL\* KUR.KUR
- L. 16. Bongenaar, *Ebabbar*, p. 328, suggests Du'ūzu (ŠU), however, the traces of sign suggest rather Abu (NE).
- [x+<sup>?</sup>] 1 talent 56 minas of wool [x] <sup>rminas</sup> 6 [shekels?] of blue-purple wool, [worth x mi]na ¾ (minus) 1/8 shekels of silver, the prebendary income, which was given to Kalbā, [son of] Kabtīya [for the *l*]*ubuštu* ceremony of the third day [of the mon]th of Ulūlu.
- [...] for wool for the multicoloured *naḥlaptu*-cloak [for the Queen of Sip]par; 2 *sūnu*-belts [....] (and) yarn [....] was given to Gimillu.
- [....] wool for sash]es and *muttatu*-headdress for the [3<sup>rd</sup> da]y of the month of Ulūlu was given to [Šamaš]-šum-iddin, the *epišānu*.

Month of [Abu], 10<sup>th</sup> day, 1<sup>st</sup> year of Cambyses, king of Babylon, king of Lands.

### **441. BM 74479** = Bertin 1396 Collated

#### 20.8.Nbn 10

- 1. 1 GÚ.UN 15 ma-na SÍG.HI.A 「ù¹
- 2. 2 ½ GÚ.UN *pap-pa-su*
- 3. PAP 3 GÚ.UN 45 ma-na SÍG.HI.A

- 4. a-na dul-lu šá ITI.GU<sub>4</sub> MU.11.KAM
- 5. a-na <sup>md</sup>U+GUR-MU A-šú šá <sup>md</sup>UTU-SUR
- 6. e-piš-a-nu SUM<sup>in</sup>

Rev. 7. ½ ma-na KÙ.BABBAR ir-bi a-na

- 7. /2 ma-na KO.DADDAK ir-ot u-na
- 8. 7 ½ ma-na dul-lu ta-bar-ri
- 9. šá ITI. 「GU<sub>4</sub>1 MU.11.KAM *a-na* <sup>md</sup>U+GUR-MU
- 10. SUM<sup>in</sup> [ina lìb]-bi 2 GÍN 2 -ta ŠU<sup>ii meš</sup> KÙ.BABBAR
- 11. ri-hi [TÚG]. HI .A MURUB<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 12. ITI.APIN U<sub>4</sub>.20.KAM MU.10.KAM
- 13. md AG-I LUGAL Eki
- L. 5. Nergal-iddin/Šamaš-ēţir, *išparu* and *ēpišānu* from Kutha, see Bongenaar, *Ebabbar*, p. 338.

Concerning the interpretation of lines 1–3, see Zawadzki, *Garments of the* Gods, Vol. I, p. 51, note 119.

1 talent, 15 minas of wool and 2  $\frac{1}{2}$  talents (as) the prebendary income, total 3 talents 45 minas of wool for the work of the month Ayaru,  $11^{th}$  year was given to Nergal-iddin, son of Šamaš-ēţir, the *epišānu*.

 $\frac{1}{2}$  mina of silver, the *irbu*-income for 7  $\frac{1}{2}$  minas (for) work with red wool in the month of Ayaru,  $11^{th}$  year, was given to Nergal-iddin, including 2 and  $\frac{2}{3}$  shekels of silver, the rest (for) the *lubār qabli*-belt for Anunītu.

Month of Arahsamna, 20<sup>th</sup> day, 10<sup>th</sup> year of Nabonidus, king of Babylon.

#### **442. BM 99578** (83-1-21, 1940)

PLATE 105

 $3.4 \times 2.8$  cm

## 19.6<sup>?</sup>.Nbn [x]

- 1. [x] GÚ.UN 2 ma-na SÍG.HI.A
- 2. [a-na<sup>? d</sup>]A-nu-ni-tu<sub>4</sub> <sup>m</sup>DUB-NUMUN
- 3. [SUM<sup>na</sup> ITI.K]IN U<sub>4</sub>.20.1.LAL.KAM
- 4. [MU.x].KAM <sup>d</sup>AG-I
- 5. [LUGAL TI]N.TIR<sup>ki</sup>

[x] talents 2 minas of wool [for] Anunītu, Šāpik-zēri [has delivered]. [Month of Ulū]lu, 19<sup>th</sup> day, [n<sup>th</sup> yea]r of Nabonidus, [king of Ba]bylon.

### 443. BM 62718 (82-9-18, 2687)

 $4.1 \times 2.6$  cm

#### 2.1.Nbk 36

- 1. [x m]a-na 10 GÍN SÍG.ḤI.A
- 2. mdEN-NUMUN a-na UGU
- 3. <sup>m</sup>Sil-la-a <sup>lú</sup>TÚG.BABBAR

it-ta-ši

5. ITI.BÁR U<sub>4</sub>.2.KAM Rev.

6. MU.36.KAM

7. dAG-NÍG.DU-ÙRU

8. LUGAL TIN.TIR<sup>ki</sup>

Bēl-zēri is not noted in Bongenaar's book.

[x] minas 10 shekels of wool, was withdrawn by Bēl-zēri on account of Şillāya, the

Month of Nisannu, 2<sup>nd</sup> day, 36<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

### **444. BM 67125** (82-9-18, 7120)

PLATE 105

 $5.8 \times 3.8$  cm

#### 20.5.Cam 7

- 1. 2 GÚ.UN SÍG.HI.A sat-tuk u pap-pa-su
- 2.  $[a]^{-1}di^{-1}SIG'(T: ŠUKU).HI.A$  šá lu-bu-uš-tu<sub>4</sub> U<sub>4</sub>.7.KAM
- 3. [šá IT]I.DU<sub>6</sub> MU.7.KAM a-na <sup>m</sup>ÌR-<sup>d</sup>EN
- 4. [A-*šú šá*  $^{\text{md}}$ AG-n]a-*şir*-IBILA u  $^{\text{md}}$ UTU-「NUMUN」 5. [A-*šú šá*  $^{\text{md}}$ x x-GÁ]L $^{?\$i \ \text{lú}}$ UŠ.BAR.MEŠ SUM $^{na}$

6. [x ma-na<sup>?</sup> SÍG.HI.A] ri-hi pap-<sup>[</sup>pa-su<sup>]</sup>

#### Rest lost

Rev.

1'. [.... U]<sub>4</sub>. [21.KAM]

- 2'. [x m]a-na SÍG.ḤI.A ina ŠUKU.ḤI.A
- 3'. [lúERÍN.MEŠ] 「šál ŠUKU.HI.A LUGAL a-na

- $^{\mathrm{md}}$ AG-bul-liṭ-an-ni $^{!}$  (T: Gu-la) 4'. [ $^{\mathrm{l\acute{u}}}$ šá m]uḥ-ḥi qu-up-pu u  $^{\mathrm{l\acute{u}}}$ ERÍN.MEŠ šá ŠUKU.ḤI.A LUGAL
- 5'. a-di-i 10 ma-na SÍG.ḤI.A IGI-tú {「x¹}
- 6'. ITI.NE U<sub>4</sub>.20.KAM MU.7.KAM
- 7'. <sup>m</sup>Kám-bu-zi-ja LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

It seems that the text consists of two different parts; the first one concerns the issue of wool for the weaver for the manufacture of the garments for the *lubu*štu ceremony, and the second, the issue of wool as rations for the workers receiving king's rations.

- L. 1–2. [a]-<sup>r</sup>di<sup>1</sup> SÍG.HI.A *šá lu-bu-uš-tu*<sub>4</sub> makes no sense because *sattukku* denotes wool destined for the manufacture of garments for the gods. The scribe wished to stress that the wool was destined not only for the month of Ulūlu, but also for Tašrītu.
- L. 4. My reconstruction of lines 5 and 6 suggests that the names of two weavers were written there, but a different possibility is also acceptable, i.e. that three persons, i.e. Arad-Bēl, [Nabû]-nāṣir-apli and Šamaš-zēri, son of [--- ušabš]i were mentioned. I prefer the first possibility because there is quite a large space at the beginning of l. 4, appropriate for the suggested reconstruction. If the suggested filiation is correct, the question arises of whether this

Arad-Bēl, son of [Nabû]-nāṣir-apli, is the son of the well-known weaver and the grandgrandson of Nabû-bēl-šumāti and whether he is identical with the Arad-Bēl of the texts cited by Bongenaar, Ebabbar, p. 316. Although these questions cannot be resolved, it seems that Arad-Bēl/[Nabû]-nāṣir-apli is more probably the person different from the Arad-Bēl of Cam 326:1 (dated to the 6<sup>th</sup> year of Cambyses) because the latter one has run away without ful-

filling his obligations. Rev. 3'. "AG-bul-liṭ-an-Gu-<sup>1</sup>la¹ is evidently a scribe's mistake for <sup>md</sup> AG-bul-liṭ-an-ni!, the person active in the period Cyr 4-Bar 1, see Bongenaar, *Ebabbar*, p. 110.

Rev. 5'. At the end of the line the rest of two signs are visible, maybe intentionally erased.

2 talents of wool, the regular offering and the prebendary income, together with wool for the *lubuštu* ceremony of the 7th day of the [month] of Tašrītu, 7th year, was given to Arad-Bēl, [son of Nabû-n]āşir-apli and Šamaš-zēri, [son of DN-Xušab]ši, the weavers.

[x minas of wool], the rest of the prebendary income ....

[....], 21<sup>st</sup> day

[x mina]s of wool for the rations of the workers receiving the king's rations was given to Nabû-bulliţanni, the supervisor of the box and (for) the workers receiving the king's rations, including 10 minas of wool of an earlier (issue).

Month of Abu, 20<sup>th</sup> day, 7<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

**445. BM 83377** (83-1-21, 540)

PLATE 106

 $3.2 \times 2.3$  cm

5.12.Nbn 2

- 1. 1 GÚ.UN SÍG.HI.A
- 2. a-na 1 GÚ.UN
- 3. hu-ra-tu<sub>4</sub> a-na
- 4. <sup>m</sup>EN-KAR-<sup>d</sup>AG

Edge

5. SUM<sup>in</sup> ITI.ŠE

Rev.

6. U<sub>4</sub>.5.KAM MU.2.KAM 7.  $^{\rm d}$ AG-I

8. LUGAL TIN.TIR<sup>ki</sup>

The person with the name of Bēl-ēţir-Nabû appears in a few texts from the time of Cyrus and Cambyses, but only in Cyr 291: 12 as a širku. There is reason to identify him with the same person from the text published here.

1 mina of wool = 1 mina of  $hur\bar{a}tu$ , see also the text below.

1 talent of wool for 1 talent of *hurātu*-dye was given to Bēl-ētir-Nabû. Month of Addaru, 5<sup>th</sup> day, 2<sup>nd</sup> year of Nabonidus, king of Babylon.

## **446. BM 72330** (82-9-18, 12336)

 $4.0 \times 2.4 \text{ cm}$ 

- 1. 22 *ma-na* SÍG.ḤI.A. <sup>гm?</sup> [....]
- 2. [2]2 *ma-na hu-r*[*a-tu*]
- 3. [x (x)] 「ši¬ šá GADA/GIŠ
- 4.  $[x \ x \ x] \lceil x \rceil$

Rest lost

Rev. 1'.  $rina^{?1}$  [....]

2'. [bi<sup>?</sup>] [....]

3'. SÍG.ḤI.A [....]

4'. *e-lat* 2 [....]

Edge 5'.  $\check{s}\acute{a}$  a-na  ${}^{\mathrm{m}}R[i$ -....]

22 minas of wool [for] 22 minas of *hurātu*-dye [....] fro [....] wool [...], except for 2 [....] which for Rē[mūt? ....].

## **447. BM 79695** (89-10-14, 244)

PLATE 106

 $5.35 \times 4.3$  cm

Dar 29

- 1. ½ ma-na KI.LAL TÚG.ḤA.A ku-lul-lu
- 2. ù TÚG.ḤA.A me-ți šá <sup>d</sup>UTU
- 3. šá U<sub>4</sub>.15.KAM šá ITI.APIN <šá> šá-lam <É>
- 4. 1 1/3 ma-na 4 GÍN KI.LAL
- 5. TÚG.ḤA.A šá <sup>d</sup>Bu-ne-ne
- 6. šá U<sub>4</sub>.15.KAM šá ITI.APIN

Edge 7. MU.29.KAM Rev. 8. <sup>m</sup>Da-ri-ja-muš

9. LUGAL E<sup>ki</sup> LUGAL KUR.KUR

TÚG.ḤA.A, a by-form of TÚG.ḤI.A, cf. TÚG.ḤA.A  $kul\bar{u}lu~\hat{u}$  TÚG.ḤA.A  $m\bar{e}ti~\hat{s}\acute{a}$   $^{d}$ UTU in this text with TÚG.ḤI.A  $kul\bar{u}lu$  TÚG.ḤI. A  $m\bar{e}tu$  in Cyr 202 (= 485): 7–8 and in many other texts

L. 4. The typical weight of the *lubāru*-garment of Bunene is 1 mina 20 shekels.

½ mina (of wool), the weight of the *lubār kulūlu* and *lubār mēṭu*-headbands for Šamaš for 15<sup>th</sup> of Araḥsamna (for) *šalām <bīti>* ceremony and 1 mina 24 shekels, the weight of the *lubāru*-garment for Bunene for 15<sup>th</sup> of Araḥsamna, 29<sup>th</sup> year of Darius, king of Babylon, king of Lands.

## **448. BM 55011** (82-5-22, 1342)

 $6.8 \times 4.9$  cm

## Cyr 0

- 1. [SÍG.ḤI.A šá a-na] lúUN.MEŠ šá dul-lu ip-pu-uš SUM
- 2. [ITI.x.] MU.SAG.NAM.LUGAL.LA  $^{\rm m}$  Ku-ra-áš LUGAL KUR.KUR

<sup>md</sup> ḤAR-DÙ <sup>lú</sup> UŠ.BAR GADA
$^{\mathrm{md}}\mathrm{D}\grave{\mathrm{U}}^{t\acute{u}} ext{-}\mathrm{KAM}$
<sup>md</sup> EN-MU A <sup>m</sup> Šul-lu-mu
<sup>m</sup> ZÁLAG- <sup>d</sup> UTU <sup>lú</sup> Γx¹ []
<sup>md</sup> EN-「x x x <sup>1</sup>
[]

Rev. uninscribed

L. 1. [SÍG.ḤI.A] against Bongenaar, *Ebabbar*, p. 324: [ŠUK].ḤI.A because the counting is in minas. Bongenaar reads also [ $\check{s}\check{a}$ ]...  $ippu\check{s}\bar{u}$ 

L. 4. Bānītu-ēreš might be identical with the *širku* mentioned in CT 56, 474: 10 who received a TÚG.KUR.RA garment.

L. 6. Concerning the possible reading of the TÚG.KUR.RA as *suḥattu*, see CAD S 346b and Zawadzki 2009; cf. Jursa 2006, p. 203, No. 9: 3.

[Wool, which] was given [for] people, who made the work. [Month x], the accession year of Cyrus, king of Lands.

.....

[10] minas (for) Bunene-ibni, the multicoloured weaver

10 minas (for) Bānītu-ēreš

10 minas (for) Bēl-iddin, son of Šullumu

one earlier (issued) TÚG.KUR.RA-garment (for) Nūr-Šamaš, the [...

10 minas (for) Bēl-<sup>r</sup>x x x

10 minas (for) [....]

10 mi[nas (for) [....].

#### **449. BM 83918** (83-1-21, 1081)

 $4.2 \times 2.3$  cm

- 1. 15 ma-na SÍG.HI.A a-na
- 2. <sup>m</sup>DUB-NUMUN <sup>1ú</sup>UŠ.BAR
- 3.  $10 \, ma$ - $na \, ^{md}$ EN-MU
- 4. A-šú šá  ${}^{\rm m}$ Šá-du-nu
- 5. [10 *ma-na*] <sup>rmd</sup>UTU<sup>¬</sup>-[....]

Rest lost

Rev.

1'. [ $10 \ ma$ ]- $^{\Gamma}na^{\Gamma} \ ^{m}Ki/KI$ -[....] 2'.  $10 \ ma$ - $na \ ^{md}UTU$ - $DU^{u\check{s}}$ 

3'. lúSIMUG AN.BAR

4'. 10 ma-na <sup>md</sup>ḤAR-ši-man-ni

5'. lúTÚG.KAL. KAL

Because the three persons named here were active in the time of Nabonidus and at the very beginnings of Persian rule, it seems that the text may be dated safely to the time of Nabonidus.

15 minas of wool for Šāpik-zēri, the weaver 10 minas (of wool for) Bēl-iddin, son of Šadūnu [10 minas (of wool for)] Šamaš-[....]

[10 mi]nas (of wool for)] Ki-[...] / Itti-[....] [10 mi]nas (of wool for)] Šamaš-ēpuš, the ironsmith 10 minas (of wool for) Bunene-šimanni, the mender.

## **450. BM 61597** (82-9-18, 1569)

PLATE 107

 $4.7 \times 6.1$  cm

## 12.[x].[Cam] 5

- 1. SÍG.HI.A šá É-[babbar-ra ....]
- 2. U<sub>4</sub>.12.KAM MU.5.[KAM ....]
- 3. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

- 4. 10 <ma-na> SÍG.HI.A ina SÍG.HI.A šá É-babbar-ra
- 5. <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR

\_\_\_\_\_\_

- 6. 20 ma-na SÍG.HI.A <sup>m</sup>DUB-NUMUN
- 7.  $\dot{u}^{\rm m}U$ š-šá-a-a šá [x<sup>?</sup>] [x]
- 8. [x ma-n]a <sup>m</sup>Te-rik-LUGAL-u[t-su <sup>lú</sup>SAG LUGAL] Rev.
  - 9.  $[(\mathbf{x} \ \mathbf{x})] \mathbf{x} \mathbf{I} \mathbf{G} \mathbf{I} t u_4$
  - 10. [1 ma] -na <sup>m</sup>Ni-din-it <sup>1ú</sup>TÚG.BABBAR [TA<sup>?</sup>]
  - 11. ŠÁM ŠE.BAR-šú šá ina É-babbar-ra
  - 12. 15 ma-na ÌR 「É.GAL¹.MEŠ
  - 13. 10 ma-na <sup>m</sup>ŠU <sup>r</sup>A- $š\acute{u}$  <sup>?</sup> [ $š\acute{a}$  <sup>?</sup> x] <sup>r</sup>x x<sup>7</sup>
  - 14. <sup>md</sup>ḤAR-DÙ *u* [....]
  - 15. PAP 5 lú[UŠ.BAR GADA ....]
- L. 5. Three different titles of Šamaš-šum-iddin are known: ašlāku, išpāru, and ēpišānu, but he is attested for the first time as išpāru only in the time of Cambyses, which makes it possible to suggest the dating of the text to his fifth year (instead to [Ach(emenid period)] as was given in Zawadzki, Garments of the Gods, Vol. I. Such a dating is enhanced by the presence of Tērik-šarussu, active from Cam 1 till Dar 15 (Bongenaar, Ebabbar, p. 112), and Nidintu, the išpar kitė/puṣaya, known from one text dated to Cyr 8 (Bongenaar, Ebabbar, p. 339). Gimillu and Bunene-ibni belonged most probably to the group of 5 išpar kitê

(Bongenaar, *Ebabbar*, p. 327 and pp. 323 f. accordingly). There is some problem with the identification of Šāpik-zēri and Uššaya. The first is known as an *išpar birme/ṣāpû* (Bongenaar, *Ebabbar*, p. 349 ff), the second only with the title *išpar kitê/mukabbû* (Bongenaar, *Ebabbar*, p. 352). Because they appear together and as a group separate from Gimillu, Bunene-ibni and their three colleagues, most probably the *išpar kitê*, it is possible that Uššaya is not identical with *išpar kitê/mukabbû* but with a hitherto unknown *išpar birme/sāpû*.

L. 9. Before IGI- $tu_4$  the tiny remains of Winkelhaken is preserved; maybe of E]N.

Wool from the E[babbar temple ...., 12<sup>th</sup> day, 5<sup>th</sup> year of [Cambyses<sup>?</sup>], king of Babylon, king of Lands

-----

10 <minas> of wool from wool of the Ebabbar temple (for) Šamaš-šum-iddin, the weaver

20 minas of wool (for) Šāpik-zēri and Uššaya [....]

[x min]a(s for) Terik-šarussu, [the royal official, ....wi]th? previous issue

 $\lceil 1 \rceil$  mina  $\lceil (\text{for}) \rceil$  Nidintu, the *ašlāku* from the price of his barley, which (is) in the Ebabbar temple

15 minas (for) the builders

10 minas (for) Gimillu, son? of [....], Bunene-ibni and [....], total 5 [linen weavers? ....].

# XVI. Issue of the coloured wool for manufacture of the garments for the gods

**451. BM 49883** (82-3-23, 874)

**PLATE 107** 

 $5.5 \times 2.5$  cm

## 9.2.Nbp 3

- 1. 5 GÍ[N] SÍG.ZA.GÌN.<KUR>.RA KI.LAL
- 2. 10 TÚG.ḤI.A [ku]-lu-lu TÚG.ḤI.A me-ṭu
- 3. [x] 「x¹ 「i-na UGU<sup>?</sup>」 <sup>m</sup>Du-muq it-ta-din

Rest of Obv. lost

Rev.

- 1'. 'x x DA x x x x (traces of bottom part of signs)
- 2'. <sup>m</sup>BA<sup>šá</sup>-a it-ta-din
- 3'. ITI.GU $_4$  U $_4$ .9.KAM MU.3.KAM
- 4'. md AG-A-PAP LUGAL TIN.TIR ki

Dummuqu, see Bongenaar, Ebabbar, p. 326 and Zawadzki, Garments of the Gods, Vol. I, p. 216.

5 shekels of blue-purple wool, the weight of 10 lubār kulūlu (and) lubār mēţuheadbands [....] to Dummuqu was delivered.

[.... Iqīša has delivered. Month of Ayaru,  $9^{th}$  day,  $3^{rd}$  year of Nabopolassar, king of Babylon.

## 452. VS 6, 23; cf. NUVI 3, No. 240

#### 25.6b.Nbk 2

- 1. 11 5/6 ma-na SÍG.ZA.GÌN.KUR.[RA]
- 2. a-na <sup>túg</sup>ku-si-ti TÚG.ḤI.A  $\lceil pa^*$ -ni- $e^{\rceil}$  3. ša <sup>d</sup>GAŠAN UD.KIB.NUN<sup>ki</sup>
- 4. a-na <sup>md</sup>AG-EN-MU.MEŠ
- 5. na-din ITI.KIN U<sub>4</sub>.2-na.KAM U<sub>4</sub>.25.KAM 6. MU.2.KAM  $^{\rm md}$ AG-NÍG.DU-ÙRU
- 7. LUGAL TIN.TIR<sup>ki</sup>

11 minas 50 shekels of blue-purple wool for the robe (and) the *lubār pāni*-veil for the Queen of Sippar was given to Nabû-bēl-šumāti.

Month Ulūlu II, 25<sup>th</sup> day, 2<sup>nd</sup> year of Nebuchadnezzar, king of Babylon.

## **453. BM 64798** (82-9-18, 4779)

 $4.3 \times 3.2$  cm

## [x].8.[Nr]g 3

- 1. 「1/3¬ ma-na <sup>síg</sup>ta-bar-ri
- 2. 5/6 ma-na <sup>síg</sup>ta-kil-tu<sub>4</sub> 3. <sup>1</sup>1 ma-na <sup>na4</sup>gab-bu-ú
- 4. [1 ma]-na GIŠ.ḤAŠḤUR a-na
- 5. [*și*]-*bu-tu*<sub>4</sub> *šá* 2-[*ta*]
- 6. [<sup>túg</sup>*g*]*a-mi-da-*[*tu*<sub>4</sub>] 7. [*a-na*<sup>? m</sup>]DUB-NUMUN

Rev.

- 8. [A-šú šá <sup>md</sup>]UTU-ŠEŠ-MU
- 9. [SUM<sup>na</sup>] ITI.APIN
- 10. [U<sub>4</sub>.x].KAM MU.3.KAM
- 11. [<sup>md</sup>U+GUR-LUGAL]-ÙRU
- 12. [LUGAL] TIN.TIR<sup>ki</sup>

The text was already edited with copy in Zawadzki 2010, No 3.

L. 5. Concerning sibûtu, see CAD \$ 171b "dyed fabric", but another meaning "need, demand" or similar is also not excluded.

20 shekels of red wool, 50 shekels of blue-purple wool, 1 mina of alum [1? mi]na of apple-colour-dye for dyed fabric for two gamidātu-garments were given [to] Šāpik-zēri, son of Šamaš-aḥ-iddin. Month of Araḥsamna, [n<sup>th</sup>] day, 3<sup>rd</sup> year of [Neriglis]sar, [king] of Babylon.

## **454. CT 55, 859** = BM 56438

### 27.12.Nbn 1

- 1. ½ ma-na 「6 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. a-na TÚG.HI.A šá <sup>d</sup>UTU ù
- 3. <sup>d</sup>Bu-ne-ne a-na
- 4. <sup>md</sup>AG-PAP u <sup>m</sup>Ba-ku-ú-a 5. <sup>lú</sup>A šip-ri-šú šá [<sup>m</sup>Ba-la-ṭu]
- 6. [A  $^{\text{md}}$ AG-EN-MU.MEŠ] 7.[it]- $^{\text{f}}ta^{?_{1}}$ -[din]
- 8. ITI.ŠE U<sub>4</sub>.27.[KAM]
- 9. MU.1.KAM <sup>md</sup>AG-IM.TUKU 10. LUGAL TIN.TIR<sup>ki</sup>

36 shekels of blue-purple wool for the *lubāru*-garments of Šamaš and Bunene was given to Nabû-nāṣir and Bakûa, the messenger of [Balāṭu, son of Nabû-bēl-šumāti]. Month Addaru, 27<sup>th</sup> day, 1<sup>st</sup> year of Nabonidus, king of Babylon.

# **455. BM 59621** (8-2-7-14, 4031)

PLATE 108

 $4.4 \times 3.4$  cm

#### 18.7.Nbn 2

- 1. ½ ma-na SÍG.ZA.GÌN.KUR. [RA] [a-na]
- 2. TÚG.KUR.RA GIŠ.TUKUL DINGIR TÚG.KUR.RA
- 3. šá <sup>d</sup>UTU ½ ma-na SÍG.ZA.GÌN.<KUR>.RA
- 4. a-na TÚG.KUR.RA šá Γ<sup>d</sup>

  1
  UTU
- 5. 6 GÍN a-na TÚG.KUR.RA

Edge

- 6. šá <sup>d</sup>Bu-ne-ne
- 7. a-na lu-bu-uš-tu<sub>4</sub>

Rev.

- 8. šá ITI.APIN <sup>m</sup>Ba-la-ṭu
- 9. lúUŠ.BAR ma-hir
- 10. ITI.DU<sub>6</sub> U<sub>4</sub>.18.KAM
- 11. MU.2.<KAM> dAG-I
- 12. LUGAL TIN.TIR<sup>ki</sup>

I owe the reading of GIŠ.TUKUL DINGIR to M. Jursa. The phrase  $\frac{1}{2}$  ma-na SÍG.ZA.GÌN.<KUR>.RA a-na TÚG.KUR.RA šá  $\frac{[d]}{[d]}$ UTU is parallel to  $\frac{1}{2}$  ma-na SÍG.ZA.GÌN.KUR.RA a-na TÚG.ḤI.A šá dUTU and 6 GÍN a-na TÚG.KUR.RA šá dBu-ne-ne to 6 GÍN a-na TÚG.HI.A šá dBu-ne-ne, which suggests that at least here TÚG.KUR.RA was used instead of the *lubāru*.

30 shekels of blue-purple wool [for] the TÚG.KUR.RA garment for the symbol of the god (i.e.) for the TÚG.KUR.RA of Šamaš (and) 30 shekels of blue-purple wool for the TÚG.KUR.RA-garment of Šamaš; 6 shekels (of blue-purple wool) for TÚG.KUR.RA-garment for Bunene for the lubuštu ceremony of the month of Araḥsamna, Balāṭu, the weaver has received. Month of Tašrītu, 18<sup>th</sup> day, 2<sup>nd</sup> year of Nabonidus, king of Babylon.

### **456. BM 64996** (82-9-18, 4977)

 $3.4 \times 3.3 \text{ cm}$ 

### 10.2.Nbn 4

- 1. [x GÍN] SÍG.ZA.GÌN.KUR.RA
- 2. [a-na p]i-šá-nu šá
- 3. [dGAŠAN] Sip-parki a-na
- 4.  $\begin{bmatrix} {}^{m}x \ x \end{bmatrix}$ - $\begin{bmatrix} {}^{r}x \end{bmatrix}$ -e- $ti \ SUM^{na}$
- 5. [ITI].GU<sub>4</sub> U<sub>4</sub>.10.KAM
- 6. [MU].4.KAM <sup>md</sup>AG-I

7. LUGAL E ki Edge

L. 4. One can try to identify the person mentioned in the line as Rēhētu only if we emend the rest of the sign preceding e to hi (in fact it looks like me or like the end of GAL).

[x shekels] of blue-purple wool [for a b]ag of the [Queen] of Sippar was given to [PN] [Month] of Ayaru,  $10^{th}$  day,  $4^{th}$  [year] of Nabonidus, king of Babylon.

### **457. BM 59488** (82-7-14, 3897)

PLATE 108

 $4.2 \times 3.3$  cm

# 30.12.Nb[n] 4

- 1. [1]+1 ma-na 13 GÍN is- ${}^{\dagger}ha^{?}$ - $x^{1}[x]$
- 2. 5 GÍN SÍG.ZA.GÌN.KUR.R[A]
- 3. 2 GÍN ta-bar-ri
- 4. *a-na gu-ḫal-*「ṣ*a-a*¬-[*tu*<sub>4</sub>]
- 5. šá ITI.BÁR a-na
- 6.  $^{\text{md}}$ AG-PAP  $u^{\text{md}}$  [AG<sup>1</sup>-u[p-ni-ja]

Edge 7. SUM<sup>na</sup>

Rev. 8. ITI.ŠE U<sub>4</sub>.30.KAM

- 9. MU.4.KAM <sup>md</sup>AG-[I]
- 10. LUGAL TIN.TI
- L. 4. The reading is very difficult because all signs are atypical: gu has an additional small wedge and it looks like sal+din; hal looks like an and the broken a is similar to ha.
- L. 6. The reconstruction is justified by the fact that if they appear together Nabû-upn $\bar{\text{y}}$  always follows Nabû-nāṣir.
- L. 9. I read Nabû-[nā'id] because the small space excludes other longer names of the Neo-Babylonian kings.
- $^{721}$  minas 13 shekels of linen  $ishu^{?}$ ; 5 shekels of blue-purple wool, 2 shekels of red wood for the *guhalṣu* for the month of Nisannu was given to Nabû-naṣir and Nabû-up[nīya].

Month of Addaru, 30<sup>th</sup> day, 4<sup>th</sup> year of Nabo[nidus], king of Babylon.

# **458. BM 79222** (89-4-26, 519)

PLATE 109

 $5.5 \times 4.1$  cm

#### 4.<sup>[5]</sup>.Nbn 5

- 1. 2 ma-na 15 GÍN S[ÍG.ZA.GÌN.KUR.RA]
- 2.  $4 \frac{1}{2}$  ma-na in-za-hu-ri- $\lceil e \rceil$ - $\lceil t \hat{u} \rceil$
- 3. ina lìb-bi mi-šil pi-lu-ú
- 4. a-na ku-lu-lu<sup>meš</sup>
- 5. ù par-ši-ga-nu
- 6. [a-n]a <sup>m</sup>DUB-NUMUN {MU} (er.)

Edge

- 7. A-*šú šá* <sup>md</sup>UTU-ŠEŠ-MU
- Rev. 8. SUM<sup>in</sup> ITI. [NE]
  - 9. U<sub>4</sub>.4.KAM MU.5.「KAM<sup>1</sup>
  - 10. md AG-I LUG[AL TIN].TIRki

- L. 3. The word  $pel\hat{u}$  ("to be red") appears in such a context for the first time. It suggests that  $inzahur\bar{e}tu$  wool has a red tinge different from  $pil\hat{u}$ .
- 2 minas 15 shekels of bl[ue-purple] wool (and) 4 ½ minas of *inzaḫurētu* wool, including half (mina of wool) of *pelû* colour was given to Šāpik-zēri, son of Šamaš-aḫ-iddin for (manufacturing) *kulūlu* and *paršigānu* headdresses. Month of 「Abu¹, 4<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, kin[g of Baby]lon.

# **459. Nbn 217** = BM 75480 Collated

 $4.8 \times 3.7$  cm

### 28.12.Nbn <sup>5</sup>1

- 1. ½ ma-na 5 GÍN SÍG.ZA.GÌN.[KUR.RA]
- 2. TA <É>.ŠU<sup>ii</sup> a-na TÚG\*.ḤI.A\* šá <sup>d</sup>[UTU]
- 3. *ù* <sup>d</sup>HAR *a-na lu-* <sup>r</sup>*bu\*-uš\*-tu*<sub>4</sub>\*1
- 4. šá ITI.BÁR MU.10. KAM
- 5. a- $na^{m_{\lceil}}Ba$ - $ku^{\rceil}$ - $[\acute{u}$ -a]
- 6.  $\dot{u}^{\text{md}} [AG^{\dagger} [\dot{u} pi ni ja]]$
- 7. <sup>lú</sup>la\*-mu\*-[ta-nu šá]
- 8. <sup>md</sup>AG-na-sir-A\* <sup>lú</sup>ΓUŠ<sup>1</sup>.[BAR]
- 9. SUM<sup>in</sup> ITI.ŠE U<sub>4</sub>.28.KAM
- 10. MU.<sup>1</sup>9\*1.KAM <sup>md</sup>AG-I
- 11. LUGAL TIN.TIR<sup>ki</sup>
- 35 shekels of blue-purple wool from the  $b\bar{t}t$   $q\bar{a}t\bar{t}$ -storehouse for the  $lub\bar{a}ru$ -garments [of Šamaš] and Bunene for the  $lubu\bar{s}tu$  ceremony of the month Nisannu,  $10^{th}$  year, was given to Bakûa and Nabû-[upnīya], the serv[ants of] Nabû-nāṣir-apli, the wea[ver].

Month of Addaru, 28<sup>th</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon.

# 460. BM 79134 (Bu 89-4-26, 431)

PLATE 110

 $6.4 \times 4.6$  cm

### 7.1.Nbn 6

- 1. 1 ma-na 1/3 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. ba-ab-tu<sub>4</sub> 4 ma-na SÍG.ZA.GÌN.KUR.RA
- 3. ½ ma-na SÍG.ZA.GÌN.KUR.RA a-na TÚG.ḤI.A
- 4. me-e-tu TÚG.HI.A ku-lu-lu šá <sup>d</sup>UTU
- 5. PAP 4 ½ ma-na SÍG.ZA.GÌN.KUR.RA a-di
- 6. SÍG.ZA.GÌN.KUR.RA mah-ri-tu4 a-na
- 7. dul-<sup>r</sup>lu<sup>1</sup> šá ITI.GU<sub>4</sub> MU.6.KAM

Edge 8. *a-na* <sup>md</sup>[AG-PAP] <sup>m</sup>*Ba-ku-ú-a* 

9.  $u^{\text{md}}[AG-up-ni-ja] \text{ SUM}^{[i]n}$ Rev.

10. ½ ma-na [SÍG.ZAGÌN.KUR.R]A a-na

11. 「TÚG.HI.A šá <sup>d</sup>¹UTU 6 GÍN a-[na]TÚG.HI.A

12. <sup>r</sup>šá <sup>d</sup>HAR¹ 1/3 GÍN *a-na* [TÚG].HI.A šá <sup>d</sup>IM

13. PAP 56 GÍN SÍG.ZA.GÌN.KUR.RA e-lat IGI-tu<sub>4</sub>

14. a-na TÚG.HI.A.MEŠ a-na <sup>md</sup>AG-PAP <sup>m</sup>Ba-ku-ú-a

15. *u* <sup>md</sup>AG-*up-ni-ja* SUM<sup>in</sup> ITI. 「BÁR <sup>¬</sup>

16. U<sub>4</sub>.7.KAM 「MU<sup>1</sup>.6.KAM <sup>md</sup>AG-I

17. LUGAL TIN.TIRki L. e.

18. [x] GÍN KÙ.BABBAR a-na dul-lu šá ITI.GU<sub>4</sub> L. h. e.

19. šá <sup>md</sup>AG-PAP

1 mina 20 shekels of blue-purple wool, the outstanding amount of 4 minas bluepurple wool; 30 shekels of blue-purple wool for the *lubār mētu* and *lubār kulūlu*headbands for Šamaš, total 4 ½ minas of blue-purple wool including an earlier blue-purple wool-(delivery) for the work of the month of Ayaru, 6<sup>th</sup> year, was given to [Nabû-nāṣir], Bakûa and [Nabû-upnīya].

30 shekels of blue-purple wool for the *lubāru*-garment of Šamaš; 6 shekels for lubāru-garment of [Bunene]; 20 shekels for lubāru-garment Adad; total 56 shekels of blue-purple wool except for an earlier (issue) for the *lubāru*-garments was given to Nabû-nāṣir, Bakûa and Nabû-upnīya. Month of Nisannu, 7<sup>th</sup> day, 6<sup>th</sup> year of Nabonidus, king of Babylon.

[x] shekels of silver for the work of the month Ayaru <was given> to Nabû-nāṣir.

# **461. CT 55, 865** = BM 56017

#### [x x].Nbn 6

- 1. [x] GÍN SÍG.ZA.GÌN.KUR.RA ul-tu
- 2. SÍG.ZA.GÌN.KUR.RA šá LUGAL a-na
- 3. mu-ut-ta-tu<sub>4</sub> šá ITI.KIN a-na
- 4.  $^{\text{md}}AG\text{-PAP} < u > {}^{\text{m}}Ba\text{-}ku\text{-}ú\text{-}a \text{ SUM}^{in}$
- 5. 1 ma-na <sup>na4</sup>gab-bu-ú
- 6. a-na mu-ut-ta-tu<sub>4</sub>
- 7. <sup>md</sup>AG-PAP *u* <sup>m</sup>*Ba-ku-ú-a*
- 8. 1 ma-na in-za-hu<sup>!</sup>(T: ki)-[ri-e-tu<sub>4</sub>]
- 9. [x x] É [....][x]
- 10. 「x x <sup>↑</sup> [....]-din
- 11. I[TI.x U<sub>4</sub>.x.KA]M MU.6. KAM
- 12. [md AG-I LUG]AL Eki

[x] shekels of blue-purple wool from the king's blue-purple wool for muttatuheaddress for the month Ulūlu was given to Nabû-nāsir <and> Bakûa.

1 mina of alum for the *muttatu*-headdress <was given to> Nabû-nāṣir and Bakûa.

1 mina of inzahurītu [....]. M[onth x, n<sup>th</sup> day], 6<sup>th</sup> year of [Nabonidus, ki]ng of Babylon.

### **462. BM 83708** (83-1-21, 871)

PLATE 111

 $3.3 \times 3.4$  cm

### 8.1.Nbn 7

- 1. 10 GÍN SÍG.ZA.GÌN.[KUR.RA]
- 2. *šá ḫi-il-ṣu* [.....]
- 3. *šá* <sup>d</sup>GAŠAN *Sip-par*<sup>k[i]</sup>
  4. <sup>md</sup>30-DINGIR SU[M<sup>na</sup>]
- 5. e-lat 10 GÍN SÍG.Z[A.GÌN.KUR.RA]
- 6. šá ina ITI.ZÍZ SUM<sup>i[n]</sup>
- 7. ITI.BÁR U<sub>4</sub>.8.KAM
- 8. MU.7.KAM <sup>md</sup>AG-<sup>Γ</sup>I<sup>¬</sup>
- 9. LUGAL TIN.TIR<sup>[ki]</sup>
- L. 2. *filsu*, see Bongenaar, *Ebabbar*, p. 267: "a perfume or incense, or the ceremony for which that incense/perfume was used". If the ceremony is meant a possible reconstruction of 1. 2 might be [ $\delta \acute{a}$  U<sub>4</sub>.x.KAM]. It should be stressed that as in all other texts known hitherto, here, too, *hilsu* is connected with the Queen of Sippar, but wool is mentioned for the first time. For hilşu wool, see CAD H 187 ("combed wool"); cf. halşu CAD H 50 ("combed (said of flax))".

Sîn-ilī, Bongenaar, Ebabbar, p. 254f.

10 shekels of blue-pu[rple] wool for the *hilşu* ceremony? [of n<sup>th</sup> day?] for the Queen of Sippar was given (to) Sîn-ilī; except for 10 shekels of blu[e-purple] wool, which was given in the month of Šabatu. Month of Nisannu, 8<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

# **463. CT 55, 867** = BM 56586

# 4.2.Nbn 7

- 1. 10 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. a-na pi-šá-an-nu a-na
- 3. MÍ.<GAL>MEŠ šu-bu-ul
- 4. ITI.GU<sub>4</sub> U<sub>4</sub>.4.KAM
- 5. MU.7.KAM
- 6. <sup>md</sup>AG-I LUGAL E<sup>ki</sup>
- L. 3. For reading MÍ.<GAL>MEŠ, see Bongenaar, Ebabbar, p. 249.

10 shekels of blue-purple wool for the *pišannu*-bag was brought to female chief? Month Ayaru, 4<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

# **464. BM 83511** (83-1-21, 674)

 $3.7 \times 3.2$  cm

#### 30.7.Nbn 7

- 1. [½ ma-na] SÍG.ZA.GÌN.KUR.RA
- 2. [a-na TÚG].HI.A me-tu ù
- 3. [TÚG].ḤI.A ku-lu-lu šá <sup>d</sup>UTU
- 4.  $[\check{s}\acute{a}]$   $\lceil lu \rceil$ -bu-u $\check{s}$ -< $tu_4$ >  $\check{s}\acute{a}$  ITI.APIN
- 5. [MU].7.KAM a-na 6. [ $^{\mathrm{md}}$ AG-PA] $\mathrm{P}^{2}$  $^{\mathrm{m}}$ Ba-ku- $\acute{u}$ -a
- 7.  $\left[u^{\mathrm{m}}\right]^{\mathrm{d}}$ AG-*up-ni-ja*
- [SUM]<sup>in</sup>
- 9. ITI.DU<sub>6</sub> U<sub>4</sub>.30.KAM
- 10. MU.7.KAM <sup>md</sup>AG-I

[½ mina] of blue-purple wool [for the  $lub\bar{a}$ ]r  $m\bar{e}tu$  and  $lub\bar{a}$ ]r  $kul\bar{u}lu$ -headbands for Šamaš [for] the  $lubu\check{s}tu$  ceremony of the month of Araḥsamna,  $7^{th}$  [year, was give]n to [Nabû-nāṣi]r, Bakûa [and] Nabû-upnīya. Month of Tašrītu, 30<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

# 465. BM 79383 (Bu 89-4-26, 680)

PLATE 111

 $4.2 \times 3.1$  cm

#### 2.8.Nbn 7

- 1. 5 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. a-na su-ú-nu

- 3. šá É <sup>d</sup>A-nu-ni-tu<sub>4</sub> 4. a-na <sup>md</sup>AG-A-MU 5. [u] <sup>m</sup>Ri-ḫi-tu<sub>4</sub> na-<sup>r</sup>din<sup>1</sup>

- 6. ITI.APIN U<sub>4</sub>.2.KAM
- 7. MU.7.KAM <sup>md</sup>AG-I
- 8. LUGAL E<sup>ki</sup>
- L. 4. For Rēhētu, išpar birmi, see Bongenaar, Ebabbar, pp. 340f. and Zawadzki, Garments of the Gods, Vol. I, 224f.
- L. 5. For Nabû-apal-iddin, *išpar kitê*, see Bongenaar, *Ebabbar*, pp. 332. This is the first text attesting the cooperation of both weavers, belonging to two different professional subgroups. Note, however, that the title of Nabû-apal-iddin appears only in CT 56, 230, r. 2 where the theophoric element is badly preserved.
- 5 shekels of blue-purple-wool for the sūnu-belt for the temple of Anunītu was given to Nabû-apal-iddin [and] Rēḥētu. Month of Araḥsamna, 2<sup>nd</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

# 466. BM 62259 (82-9-18, 2228)

 $3.7 \times 3.1$  cm

### 2.3.Nbn 8

- 1. [x GÍN S]ÍG.ZA.GÌN.KUR.RA
- 2. [a-na] su-ú-nu šá
- 3. [<sup>d</sup>x] <sup>m</sup>DUB-NUMUN <sup>lú</sup>UŠ.[BAR *bir*]-*ri*
- 4. [SUM]<sup>in</sup> ITI.SIG<sub>4</sub>
- 5.  $[U_4]$ .2.KAM MU.8.KAM 6.  $^{[md]}$ AG-I LUGAL  $E^{ki}$

Rev. uninscribed

For Šāpik-zēri/Šamaš-aḥ-iddin, išpar birmi and ṣāpû and head of the išparātu birmi, see Bongenaar, Ebabbar, pp. 349ff and Zawadzki, Garments of the Gods, Vol. I, p. 230f.

[x shekels of] blue-purple wool [for] the sūnu-belt of the [god(dess) x was give]n (to) Šāpik-zēri, the multico[loured wea]ver.

Month of Simanu, 2<sup>nd</sup> day, 8<sup>th</sup> year of Nabonidus, king of Babylon.

### **467. BM 63962** (82-9-18, 3931) = Bertin 1374

 $4.2 \times 3.3$  cm

### 1.8.Nbn 9

- 1. 5 ma-na 10 GÍN SÍG.SAG.HÉ.<ME>.DA
- 2. a-na TÚG.BAR.DUL<sub>5</sub> šá <sup>d</sup>A-a
- 3. a-na <sup>lú</sup>la-mu-ta-nu 4. šá <sup>md</sup>AG-na-şir-IBILA <sup>lú</sup>UŠ.BAR
- 6. ITI.APIN U<sub>4</sub>.1.KAM
- Rev.
- 7. MU.9.KAM md AG-I
- 8. LUGAL TIN.TIRki
- L. 1. Cf. however, Nbn 415: 12 SÍG.SAG.ME.HÉ.DU (collated).

5 minas 10 shekels of first quality red wool for the robe of Aya was given to the servant of Nabû-nāsir-apli, the weaver.

Month of Arahsamna, 1<sup>st</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon.

# **468. BM 101726** (83-1-21, 3387)

PLATE 112

 $4.5 \times 4.1$  cm

# 20.8.[Nb]n 9

- 1. [x GÍN KÙ.BABBAR] *ul-tu* KÙ.BABBAR 「šá¹ [*ir-bi*]
- 2.  $[x \ x]$   $[u \ 17]$  GÍN KÙ.BABBAR [x]
- 3. [x x x].MEŠ *šá* MU.9.K[AM]

- 4. [x x x] *a-na* 10 *ma-na* 10 「GÍN<sup>1</sup>
- 5.  $[\mathbf{x} \mathbf{x} \mathbf{x}]^{\mathsf{T}} \check{\mathbf{s}} \check{a}^{?} \mathbf{a}$ -na
- 6.  $[^{md}$ U+GUR-MU A]-*šú šá*  $^{md}$ UTU-KAR $^{ir}$
- 7. [lúUŠ.BAR] *šá* ITI.GU<sub>4</sub> MU.9.「KAM<sup>1</sup>
- [SU]M<sup>in</sup>

9. [x GÍ]N SÍG.ZA.GÌN.<KUR>.RA a-na dul-lu<sub>4</sub> Rev.

- 10. [šá ITI.G]U<sub>4</sub> a-na <sup>túg</sup>na-ḥal-lap-tu<sub>4</sub> šá <sup>d</sup>A-a 11. <sup>[m]d</sup>U+GUR-MU SUM<sup>in</sup>

Blank space for one line

- 12. [ITI.API]N U<sub>4</sub>.20.KAM MU.9.KAM
- 13. [mdAG]-II LUGAL TIN.TIRki

For Nergal-iddin/Šamaš-ēţir, an išpāru and ēpišānu from Cutha, see Bongenaar, Ebabbar, p. 338 and Zawadzki, Garments of the Gods, Vol. I, p. 224. Note the long distance between the date when the text was written (month of Arahsamna) and the destination of wool for the work (month of Ayaru).

[x shekels of silver] from the silver, [the income ...] (and) 17 shekels of silver [....], 9th year [....] for 10 minas 10 shekels [....] to [Nergal-iddin, son] of Šamaš-ēṭir, [the weaver] for the month of Ayaru, 9th year, was given.

[x shek]els of blue-purple wool for the work [of the month Aya]ru for the nahlaptu-cloak of Aya was given to Nergal-iddin.

[Month of Arah]samna<sup>?</sup>, 20<sup>th</sup> day, 9<sup>th</sup> year of [Nabo]nidus, king of Babylon.

# **469. CT 55, 870** = BM 56892

10.[x].Nbn [x]

- 1. 1/3 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. *a-na* <sup>túg</sup>na-hal-ap-tu<sub>4</sub>
- 3. šá <sup>d</sup>A-a a-na <sup>m</sup>DUB-NUMUN
- 4. A-*šú šá* <sup>md</sup>UTU-ŠEŠ-[MU]
- 5. SUM<sup>in</sup> ITI.[x]
- 6. U<sub>4</sub>.10.KAM MU.[x.KAM]

7. <sup>d</sup>AG-I LUGAL Rev.

8. TIN.TIR<sup>ki</sup>

20 shekels of blue-purple wool for the *naḥlaptu-*cloak for Aya was given to Šāpik-zēri, son of Šamaš-aḥ-[iddin].

Month [x],  $10^{th}$  day, [n<sup>th</sup>] year of Nabonidus, king of Babylon.

### **470. BM 101193** (83-1-21, 2854)

 $4.7 \times 3.5$  cm

12.9.Nbn 8

- 1. 5 ½ ma-na [SÍG.HÉ.ME.DA]
- 2.  $\delta \dot{a} ku-si-[tu_4 \delta \dot{a}^{d}x]$

- 3. <sup>m</sup>DUB-NUMUN A <sup>md</sup>UTU-ŠEŠ-[MU]
- 4. it-ta-din SÍG.HÉ.ME.DA
- 5. ina É.ŠU<sup>ii</sup>

Rev.

6. ITI.GAN U<sub>4</sub>.12.KAM

- 7. MU.8.KAM <sup>d</sup>AG-<sup>r</sup>I<sup>1</sup>
- 8. LU[GAL TIN.TIR<sup>ki</sup>]

5 ½ minas of [red wool] for the rob[e of the goddess x] Šāpik-zēri, son of Šamašaḫ-[iddin] has delivered. The red wool (is placed) in the *bīt qāti*- storehouse. Month of Kislīmu, 12<sup>th</sup> day, 8<sup>th</sup> year of Nabonidus, ki[ng of Babylon].

# **471. VS 6, 77**; cf. NUVI 3, No. 245

#### 1.2.Nbn 9

- 1. 10 GÍN SÍG.[ZA.GÌN].KUR.RA a-na
- 2. dul-lu šá [pi]-ſšá¬-an-nu šá
- 3. dGAŠAN *Sip-par*<sup>ki</sup> u dA-nu-ni-tu<sub>4</sub> 4. 4 ½ GÍN SÍG.ZA.GÌN.KUR.RA {*a-na*}
- 5. a-na ki-li-lu šá <sup>d</sup>Aḥ-la-mi-tu<sub>4</sub>
- 6. šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> 2 BÁN uh-hu-lu
- 7. 1 BÁN bu-ra-šú 1 BÁN ŠE.GIŠ.Ì

Edge

8. a-na ha-pa-ap-šá NA<sub>4</sub>

Rev.

- 9. a-na MÍ.GAL.MEŠ SUM<sup>in</sup>
- 10. ITI.GU<sub>4</sub> U<sub>4</sub>.1.KAM MU.9.KAM
- 11. dAG-I LUGAL E. [ki]
- 12. 15 GÍN GAB *diš-pi*

10 shekels of bl[ue-pur]ple wool for manufacturing of the [pi]šannu-bag(s) for the Queen of Sippar and Anunītu.

4 ½ shekels of blue-purple wool (for manufacturing) of a wreath for Aramean Anunītu; 2 sūtu of alkali, 1 sūtu of juniper oil, 1 sūtu of sesame oil for cleaning of the stone were given to the female chiefs?. Month Ayaru, 1<sup>st</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon.

15 shekels of the beewax.

#### **472. BM 75767** = Bertin 1399 Collated

# 6.7.Nbn 10

- 1. 1 ma-na 19 GÍN ta-bar-ri
- 2. KI.LAL TÚG.ḤI.A MURUB<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 3. ina ŠU<sup>ii md</sup>U+GUR-MU <sup>lú</sup>UŠ.BAR
- 4. šá GU.DU<sub>8</sub>.A<sup>ki</sup> ½ ma-na ta-bar-ri
- 5. KI.LAL gú-hal-su hi-il-lat

6. ina ŠU<sup>ii m</sup>Ḥi-ri-e-tú

7. 2 GÍN ta-kil-tu₄

Edge 8. a-na ți-me-tu<sub>4</sub> a-na

9. šá-pi-e TÚG.ḤI.A me-ṭu Rev.

10. ù TÚG.HI.A ku-lu-lu šá dA-nu-ni-tu4

11. šá ½ GÍN ta-kil-tu4 a-na

12. li-ib-bu šá hu-ṣa-an-na

13. 10 GÍN ta-bar-ri ha-a-țu

14. šá hu-ṣa-an-nu šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>

15. ITI.DU<sub>6</sub> U<sub>4</sub>.6.KAM MU.10.KAM 16. <sup>md</sup>AG-I LUGAL E<sup>ki</sup>

17. [x]+2 GÍN ta-bar-< ri> a- $n[a^?]$ L. h. e.

18. *hu-ṣa-*<sup>г</sup>ni<sup>!</sup>-e<sup>¬ т</sup>Ва-ки-ú-а

L. 5. hillātu, Pl. of hillu, cf. CAD H 186 b (a type of wool). Although the coloured wool was precious, hillātu described also in some way its quality.

L. 12. libbu means here probably the middle part of a sash made of the blue-purple wool, while outer parts might have been made of white (or natural) wool.

1 mina 19 shekels of red wool, the weight of the *lubār qabli*-belt of Anunītu from the hands of Šamaš-iddin, the weaver from Cutha.

30 shekels of red wool, the weight of scarf of the hillātu type from the hands of Rēhētu!

2 shekels of blue-purple wool for yarn for weaving? of the lubār mēṭu and lubār kulūlu-headbands for Anunītu; of it ½ shekel of the blue-purple wool for the libbu of the sash of Anunītu.

10 shekels of red wool, the supply for sash(es) of Anunītu. Month of Tašrītu,  $6^{th}$  day,  $10^{th}$  year of Nabonidus, king of Babylon.

[x]+2 shekels of red wool for sashes (for) Bakûa.

#### **473. BM 63928** = Bertin 1437

### 4.2.Nbn 11

- 1. 7 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. 7 GÍN ta-bar-ri
- 3. ul-tu ta-bar-ri
- 4. šá pi-šá-nu [x]
- 5. [x +] 2 GÍN ki-tu [x]
- 6. [x] 「GÍN<sup>1</sup> KÙ.BABBR a-[n]a

7.  $[x x x] \check{s} \acute{a} [x x]$ Edge

8. <sup>r</sup>x x x<sup>1</sup>-*šú šá* Rev.

9. gu-[hal-ṣa]-tu4 šá 2-ta

10.  $sa^{-1}am^{-1}-ma-tu_4$  SUM<sup>in</sup>

11. ITI.GU<sub>4</sub> U<sub>4</sub>.4.KAM MU.11.KAM

12. [m]dAG-I LUGAL Eki

It is worth noting the secondary use of red wool and the equal quantity of blue-purple and red wool for manufacturing the pišannu-bag. The meaning of sammatu is unknown.

7 shekels of blue wool, 7 shekels of red wool from the red wool of *pišannu*-bag, [x]+2 shekels fo[r .... x] shekels of silver for [....] of scarf for 2 *sammatu* was given. Month of Ayaru,  $4^{th}$  day,  $11^{th}$  year of Nabonidus, king of Babylon.

### **474. BM 69122** (82-9-18, 9121)

 $2.6 \times 3.7$  cm

# [x].12b.[Nbn] 12

- 1. 1 ma-na SÍG.[ZA.GÌN.KUR.RA]
- 2. *šá ni-bi-hi* [*šá* <sup>d</sup>UTU]
- 3. <sup>m</sup>DUB-NUMUN [....]
- 4. 1 ma-na 10 G[ÍN SÍG.ZA.GÌN.KUR.RA a-na]
- 5. *lu-ba-ri* [....]
- 6. <sup>rd</sup><sup>1</sup>[.... *šá* U<sub>4</sub>.15.KAM]
- 7. *šá* ITI.ŠE [....]
- 8.  $\lceil a \rceil$ -na  $^{m}Ba$ -k[u-u-a SUM $^{na}$ ]
- 9. ITI.DIRIG.ŠE.KIN.KU[D U<sub>4</sub>.x.KAM]
- 10. MU.12.KAM <sup>md</sup>[AG-I LUGAL E<sup>ki</sup>]

The text is parralel to BM 60320 (see above).

1 mina of [the blue-purp]le wool for the nēbehu-belt [for Šamaš was given to] Šāpik-zēri.

1 minas 10 she[kels of the blue-purple wool for] the *lubāru*-garment [for ...., 15<sup>th</sup> day] of the month Addaru [.... was given] to Bak[ûa].

Month of Addaru II, [n<sup>th</sup> day], 12<sup>th</sup> year of [Nabonidus, king of Babylon].

# 475. BM 61218 (82-9-18, 1194)

**PLATE 112** 

 $3.8 \times 2.75 \text{ cm}$ 

### 28.2.Nbn 15

- 1. 1/3 8 GÍN *pi*-<sup>Γ</sup>x<sup>¬</sup>-*si*
- 2. šá ta-bar-ri {x} (erased)
- 3. 12 GÍN 'SÍG'.ZA.GÌN.KUR.RA
- 4. a-na 2-<sup>r</sup>ta¹ TÚG.BAR.DUL<sub>8</sub>² 5. a-na <sup>md</sup>ḤAR-ši-man-ni

Edge

6. SUM<sup>in</sup> ITI.GU<sub>4</sub>

- 7.  $\rm U_4.2^{\rm F}8^{\rm J}.KAM~MU.15.KAM$  8.  $\rm ^{md}AG\text{-}I~LUGAL~E^{ki}$
- L. 4. The last sign in the line is written over erasure and the reading BAR.SI is also possible.

28 shekels .... of red wool, 12 shekels of blue-purple wool for 2 robes? was given to Bunene-šimanni.

Month of Ayaru, 2<sup>r</sup>8<sup>1th</sup> day, 15<sup>th</sup> year of Nabonidus, king of Babylon.

### **476. BM 64811** (82-9-18, 4792)

**PLATE 113** 

 $4.5 \times 3.1$  cm

# 2.4. [Nbn] 16

- 1. 'x' GÍN SÍG.'ZA'.[GÌN.KUR.RA]
- 2. KI.LAL 1<sup>en</sup> ku-si-<sup>[tu4]</sup>
- 3. <sup>r</sup>x¹ GÍN SÍG.HÉ.ME.DA
- 4. KI.LAL 1<sup>en</sup> TÚG.BAR.SI
- 5. PAP 5/6 ma-na
- 6. <sup>m</sup>*Mu-šib-ši-*<sup>d</sup>AMAR.UTU
- 7. [a]- $[na \acute{E}-babbar]$ -ra
- 8. [i]t-ta-din KÙ.BABBAR NU SUR
- 9. [IT]I.ŠU U<sub>4</sub>.2.KAM
- 10. [MU].16.KAM [<sup>d</sup>AG-I]
- 11. LUGAL [TIN.TIR<sup>ki</sup>]
- L. 6. Mušibši-Marduk has to be identical with Mušibši-Marduk/Bēl-nādin-apli(/Šangû Sippar) <*ša bīt Adad u Šala>*, see Bongenaar, *Ebabbar* p. 251 or (less probably) with Mušibši-Marduk/Šamaš-zēr-ibni/Šangû Ištar Bābili <*ša bīt Anunnītu* + <*ša bīt Gula>* see Bongenaar, *Ebabbar* p. 252. Our text suggests for the first time the connection of Mušibši-Marduk with the weaver's prebend or at least with the temple's textile industry.
- [x] shekels of blue-purple wool, the weight of 1 robe
- [x] shekels of red wool, the weight of 1 *paršīgu*-headdress, total 50 shekels, Mušibši-Marduk has delivered to the Ebabbar-temple. Siver is not paid Month of Du'ūzu, 2<sup>nd</sup> day, 16<sup>th</sup> [year] of [Nabonidus], king [of Babylon].

### **477. BM 101687** (83-1-21, 3348)

 $3.6 \times 3.1$  cm

# 5.[6].Nbn 17

- 1. [½ m]a-na 6 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. [a-na TÚ]G.HI.A šá <sup>d</sup>UTU u <sup>d</sup>HAR
- 3. [a-na lu-bu-u]š-tu<sub>4</sub> šá ITI.DU<sub>6</sub>
- 4.  $[a-na^{m}Ba]-ku-\acute{u}-a^{1\acute{u}}U\check{S}.BAR SUM^{in}$
- 5. [x ma-na] in-za-ḫu-ri-e-tu<sub>4</sub>
- 6. [x *ma-na* <sup>na4</sup>]*gab-bu-ú*

Edge 7. [a-na] TÚG.NÍG.ÍB.LÁ

Rev. 8.  $[x \times x]^{\text{túg síg}} g \hat{u}$ -hal-şu

9. [x x x x x]-*tu*<sub>4</sub> *a*-*na* 

- 10. [PN] SUM<sup>in</sup>
- 11. [ITI.KIN U<sub>4</sub>]. $^{1}$ 5 $^{1}$ .KAM MU.17.KAM 12. [ $^{md}$ AG-I LUGAL]  $E^{ki}$

36 shekels of blue-purple wool for the *lubāru*-garments for Šamaš and Bunene for the *lubuštu* ceremony of the month Tašrītu was given to Bakûa, the weaver. [x mina(s)] of inzahurītu-dye, [x mina(s)] of alum [for] the sashes, [....], the scarf, the .... for [PN] was given.

### **478. BM 60320** = Str. II 339/3

 $4.8 \times 3.7$  cm

### 3.12.Nbn [x]

- 1. 1 ma-na SÍG.ZA.GÌN.KUR.RA
- 2. a-na ni-bi-hu šá <sup>d</sup>UTU
- 3. a-na <sup>m</sup>Ri-hi-tu<sub>4</sub> SUM<sup>in</sup>
- 4. ½ ma-na 6 GÍN SÍG.ZA.GÌN.KUR.[RA]
- 5. a-na TÚG.HI.A.[MEŠ<sup>?</sup>] šá ITI.<sup>r</sup>ŠE<sup>1</sup>
- 6. <sup>m</sup>*Ba-ku-ú-*[*a* SUM<sup>in</sup>]

Edge Rev.

- 7. [.... T] $\acute{\mathbf{U}}$ G<sup>?</sup> 1 na-[x] [....]
- 7. [.... T]UG 1  $n\omega$   $\kappa$  [.... ni]-bi-hu  ${}^{m_{\Gamma}d?}x^{1}$ -[x]  ${}^{lu}$ TUG.KAL.KAL
- 10. [SUM<sup>in</sup>]
- 11. 「ITI.ŠE¹ U₄.3.KAM MU.[x.KAM] 12. [dAG]-I LUGAL TIN.TIR<sup>ki</sup>

1 mina of blue-purple wool for the *nēbehu*-belt of Šamaš was given to Rēhētu. 36 shekels of blue-purple wool for the *lubāru*-garments for the month of Addaru was given to Bakûa.

[.... the  $n\bar{e}$ ] behu was given] (to) PN, the mender. Month of Addaru,  $3^{rd}$  day,  $[n^{th}]$  year of [Nabo]nidus, king of Babylon.

# **479. BM 62980** (82-9-18, 2949)

 $4.3 \times 3.2$  cm

# [x.x.].Nbn[x]

- 1. 1 ma-na SÍG.ZA.GÌN.KUR.RA
- 2. gu-ru-ub-tu₄ a-na
- 3. TÚG.ÍB.LÁ šá <sup>d</sup>UTU
- 4. a-na <sup>m</sup>DUB-NUMUN A-šú šá
- 5. Γ<sup>md</sup>¹UTU-ŠEŠ-MU SUM<sup>na</sup>

- 6. [ITI.x U<sub>4</sub>.x].KAM
- 7.  $[MU.x.KAM ^{md}A]G-I$
- 8. L[UGAL TIN.TIR<sup>k</sup>]<sup>i</sup>

L. 2. The word *gurrubtu* is known otherwise only from Nbn 637, where it appear in similar context.

1 mina of blue-purple wool of *gurrubtu* quality? for the  $n\bar{e}behu$ -belt for Šamaš was given to Šāpik-zēri, son of Šamaš-ah-iddin.

Month of [x, n<sup>th</sup> day, n<sup>th</sup> year of Na]bonidus, k[ing of Babylo]n.

### **480. BM 59423** (82-7-14, 3832)

**PLATE 113** 

 $4.0 \times 3.5$  cm

# 9.5.Nbn [x]

- 1. 2/3 GÍN SÍG.ZA.GÌN.K[UR.RA]
- 2. a-na mu-ut- $\lceil ta \rceil$ - $\lceil tu_4 \rceil$
- 3. *šá* IT[I.AP]IN <sup>m</sup>[<sup>d</sup>AG-PAP]
- 4. <sup>m</sup>Ba-[ku-ú-a]
- 5.  $u^{\text{md}}[AG-up-ni-ja]$

Edge 6. S

Rev.

6.  $SUM^{[na]}$ 

7. 1 KÙR 1 (PI) 4 BÁN ŠE.BAR [a-na]

- 8.  $^{\text{md}}$ AG-PAP  $^{\text{m}}$ Ba-ku- $^{\text{r}}$ ú $^{\text{l}}$ -[a]
- 9. *u* <sup>md</sup>AG-*up-ni-ja* [SUM<sup>na</sup>]
- 10. ITI.NE U<sub>4</sub>.9.KAM M[U.x.KAM]
- 11. <sup>m</sup>[<sup>d</sup>A]G-I LUGAL T[IN.TIR<sup>ki</sup>]

a-na in 1. 7 and SUM<sup>na</sup> in 1. 9 have been written on the very end of the line or on the right edge of the tablet.

40 shekels of blue-purple wool for the *muttatu*-headdress for the mon[th of Araḫsa]mna was given to [Nabû-nāṣir], Ba[kûa] and [Nabû-upnīya].

1 *kurru* 1 *pān* 4 *sūtu* of barley [was given to] Nabû-nāṣir, Bakû[a] and Nabû-upnīya. Month of Abu, 9<sup>th</sup> day, [n<sup>th</sup> ye]ar of [Nab]onidus, king of Ba[bylon].

### **481. BM 84300** (83-1-21, 1463)

 $2.8 \times 4.0$  cm

# 10+[x].7.Nbn[x]

- 1. 56 GÍN S[ÍG ZA.GÌN.KUR.RA]
- 2. TA SÍG.ZA.GÌN.K[UR.RA ....]
- 3. <sup>1ú</sup>DAM.GÀR [....]
- 4. šá ITI.APIN [....]
- 5. <sup>m</sup>Na-șir 5 [....]
- 6. [x x] x *du* [....]

- 7. 1 *ma*-[*na* ....]
- 8. GÍN KÙ.BABBAR
- 9. *ina pap-pa-su* <sup>lú</sup>[....]

10. e-lat 3 GÍN KÙ.[BABBAR ...]

11. <sup>m</sup>NÍG.DU SUM [....]

12. ITI.DU $_6$  U $_4$ .10[+ $x^?$ .KAM MU.x.KAM] 13.  $^{md}$ AG-I [LUGAL TIN.TIR $^{ki}$ ]

56 shekels of bl[ue-purple wool] from the blue-purp[le wool ....] the merchant [.....] of the month of Araḥsamna [.....] Nāṣir, 5 [....], 1 mi[na x] shekels of silver from the prebendary income of the [....], except for 3 shekels of sil[ver ....] Kudurru was given [....].

Month of Tašrītu, 10+[x] day, [n<sup>th</sup> year] of Nabonidus, [king of Babylon].

# **482. BM 67525** (82-9-18, 7523)

 $4.8 \times 3.6$  cm

### 12.8.Nbn [x]

- 1. 5 GÍN SÍG.[ZA].GÌN.[KUR]. TRA ina rpap-pa -su
- 2.  $^{\text{l\'u}}$ UŠ.BAR- $^{\text{r\'u}}$ - $^{\text{m}}$ r $^{\text{d}}$ l[AG-PAP]-A u  $^{\text{m}}$ Ba-ku- $\acute{u}$ -a
- 3. ITI.APIN U<sub>4</sub>.12.KAM MU.[x.KAM]
- 4. md AG-I LUGAL Eki

Rev. uninscribed

5 shekels of the 'blue-purple wool' from the prebendary income of the weaver's prebend (for) [Nabû-nāṣir]-apli and Bakûa. Month of Araḫsamna, 12<sup>th</sup> day, [n<sup>th</sup>] year of Nabonidus, king of Babylon.

# **483. BM 101776** (83-1-21, 3437)

 $3.3 \times 3.2 \text{ cm}$ 

# 24.8.Nbn [x]

- 1. [x ma-n]a 「SÍG¹.ZA.GÌN.KUR.RA
- 2.  $[x ma]^{-1}$  [na]  $[hi-il-la-tu_4]$
- 3. [a-na s]u-ú-nu šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 4. [a-n]a <sup>m</sup>Ri-hi-<sup>Γ</sup>tú<sup>7</sup>
- 5. SUM<sup>in</sup>

- 6. [ITI.A]PIN U<sub>4</sub>.24.KAM
- 7. [MU.x].KAM <sup>md</sup>AG-I
- 8. LUGAL E<sup>ki</sup>
- L. 2. Before *hillātu* (Plural from *hillu*, a type of wool, see CAD H 186) only one horizontal stroke is preserved. I filled the gap using the parallel from Nbn 664: 5: ina lìb-bi 4 ma-na hiil-la-tu<sub>4</sub> The activity of Rēḥētu lasted from the Nbn 7 till Darius I (Bongenaar, Ebabbar, pp. 340-341 and Zawadzki, Garments of the Gods, Vol. I, pp. 224-225.

[x min]a of blue-purple wool, [(and) x mi]na(s) of hillu wool [the s] $\bar{u}nu$ -belt for Anunītu was given to Rēhēţu.

[Month of A]raḥsamna, 24<sup>th</sup> day, [n<sup>th</sup> year] of Nabonidus, king of Babylon.

# 484. BM 101301 (83-1-21, 2962)

PLATE 114

 $4.5 \times 3.6$  cm

#### 4.12.Nbn [x]

- 1. ½ ma-na 6 [GÍN SÍG.ZA.GÌN.KUR.RA]
- 2. a-na TÚG.ḤI.A [šá dUTU u dBu-ne-ne]
- 3. 15 GÍN SÍG. ZA.GÍN [KUR.RA a-na]
- 4. 1 ku-si-tu šá  ${}^{d}$ [A]-[a]
- 5. TA É ŠU<sup>ii</sup> a-na [<sup>m</sup>Ba-ku-ú-a] 6. <sup>lú</sup>qal-la šá <sup>md</sup> Gl-[PAP-A] 7. <sup>lú</sup>UŠ.BAR SUM<sup>in</sup>

8. ITI.ŠE U<sub>4</sub>.4.KAM M[U.x.KAM] Rev.

9.  $^{md}$ AG-I LUGAL  $^{\Gamma}$ E $^{1[ki]}$ 

L. 4. There is enough space to reconstruct  ${}^{d_{\Gamma}}A^{1}$ -[nu-ni-tu<sub>4</sub>], however,  ${}^{d_{\Gamma}}A^{1}$ -a is preferred because according to Nbn 547 and Nbn 751 robes for Aya were manufactured by Bakûa, while his engagement in manufacturing of the robes for Anunītu is not attested.

36 shekels [of blue-purple wool] for the *lubāru*-garments [for Šamaš and Bunene] 15 shekels of blue purr[plea wool] from bīt qāti-storehouse [for 1 robe for A[ya]] was given to [Bakûa], the slave of Nabû-[nāṣir-apli], the weaver. Month of Addaru, 4<sup>th</sup> day, [n<sup>th</sup> ye]ar of Nabonidus, king of Babylon.

# **484a. BM 79560** (89-10, 14, 110)

**PLATE 115** 

 $5.3 \times 7.1$  cm

# Cyr/Cam 1 Corregency

- 1. SÍG.ZA.GÌN.KUR.RA šá a-na dul-lu šá ITI. KIN<sup>?</sup>1
- 2. MU.1.KAM <sup>m</sup>Ku-ra-áš LUGAL KUR.KUR
- 3. ù <sup>m</sup>Ka-am-bu-zi-ja LUGAL E<sup>ki</sup>
- 4. ½ ma-na <KI.LAL> TÚG.ḤI.A me-ṭu u TÚG.ḤI.A kù-lu-lu šá <sup>d</sup>UTU
- 5. ½ ma-na a-na TÚG.ḤI.A šá <sup>d</sup>UTU
- 6. 1 ma-na a-na ni-bi-hi šá <sup>d</sup>UTU
- 7. 10 GÍN *a-na mu-ut-ta-tu*<sub>4</sub> šá <sup>d</sup>UTU
- 8. 6 GÍN *a-na* TÚG.HI.A *šá* <sup>d</sup>HAR
- 9. [x] [GÍN] [a-na] TÚG.HI.A me-tu
- 10. [*u* TÚG.HI.A *kù-lu-lu*] *šá* <sup>d</sup>HAR
- 11. [....] šá ku-si-tu<sub>4</sub>
- 12. [....] $^{\text{rd}}A$ -[*a*]
- 13. [....] <sup>r</sup>x x<sup>7</sup>

```
14. [....]^{r}lu^{?_{1}}
Rev.
             15. [....]šá <sup>d</sup>IM
             16. [....] šá kù-lu-lu<sup>meš</sup>
             17. PAP 5 ma-na 57 GÍN SÍG.ZA.GÌN.KUR.RA {x}
             18. a-na <sup>md</sup>AG-PAP-A ù <sup>m</sup>Ba-ku-ú-a SUM<sup>nu</sup>
```

The text was published previously in RA 90 (1981), p. 181.

Blue-purple wool for the work of the month [Ulūlu] of the 1st year of Cyrus, king of Lands and Cambyses, king of Babylon.

½ mina, <the weight> of the *lubār mēṭu* (and) *lubār kūlulu*-headbands for Šamaš

½ mina for the *lubāru* garment for Šamaš

1 mina for the *nēbeḥu*-belt for Šamaš

10 shekels for muttattu-headdress for Šamaš

6 shekels for the *lubāru* garment for Bunene

[x shekels] the *lubār mēṭu* [(and) *lubār kūlulu*-headbands] for Bunene

[x shekels for adilānu<sup>?</sup>] of the robe [.... for] Aya

[....] for Adad

[....] for  $\langle lub\bar{a}r \rangle k\bar{u}lulu$ -headbands,

total 5 minas 57 shekels of blue-purple wool was given to Nabû-nāşir-apli and Bakûa.

# **485.** Cyr **202** = BM 75802; Salonen, NUVI 3,

No. 119; Giovinazzo 1981, No. 11 Collated

- 1. 「SÍG¹.ZA.GÌN.KUR.RA šá a-na¹ lu-「bu¹-[uš-tu4]
- 2. *šá* ITI.APIN *a-na* <sup>lú</sup>UŠ.BAR [SUM<sup>na</sup>]
- 3. ITI.DU<sub>6</sub> U<sub>4</sub>.6.KAM MU.5.KAM  ${}^{m_{\Gamma}}Ku^{1}$ -[ $ra\check{s}$ ]
- 4. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.「KUR<sup>1</sup>
- 5. ½ \* ma-na a-na TUG\*.HI<sup>!</sup>.A<sup>!</sup> šá <sup>d</sup>UTU
- 6. [6] GÍN a-na KI.MIN šá <sup>d</sup>Bu-ne-ne
- 7. ½ \* ma-na a-na TUG.HI.A me\*-tu TUG.HI.A ku-lu-lu

<sup>d</sup>UTU 8. šá

Rev.

9. [1/3 ma]-na a-na TUG.HI.A

šá

- 11. PAP 1 1/3 ma-na 6 GÍN SÍG.ZA.GÌN.KUR.RA
- 12. 1 GÚ.UN 50 ma-na SÍG.HI.A šá lu-bu-uš-tu<sub>4</sub>
- 13. U<sub>4</sub>.15.KAM šá ITI.APIN MU.5.KAM
- 14. *a-na* <sup>m</sup>*Ba-ku-ú-a* <sup>lú</sup> *qal-la šá* <sup>md</sup>AG-PAP-A 15. <sup>lú</sup>UŠ.BAR SUM<sup>na</sup> ITI.DU<sub>6</sub> U<sub>4</sub>.6.KAM
- 16. MU.5.KAM <sup>m</sup>*Ku-raš* LUGAL TIN.TIR<sup>ki</sup>
- 17. LUGAL KUR.KUR

Blue-purple wool for the *lubuštu* ceremony of the month Araḥsamna [was given] to the weaver. Month of Tašrītu, 6<sup>th</sup> day, 5<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

½ mina for the *lubāru*-garment for Šamaš

[6] shekels for ditto for Bunene

½ mina for the *lubār mēṭu* (and) *lubār kulūlu*-headbands for Šamaš

[20] shekels for the lubāru-garment for Adad, total 1 mina 26 shekels of bluepurple wool (and) 1 talent 50 minas of wool for the *lubuštu* ceremony of the 15<sup>th</sup> day of Araḫsamna, 5<sup>th</sup> year was given to Bakûa, the slave of Nabû-nāṣir-apli, the

Month of Tašrītu, 6<sup>th</sup> day, 5<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

# **486. BM 84391** (83-118, 1544)

 $4.8 \times 3.3 \text{ cm}$ 

### 18.12b.Cyr 6

- 1. 4 ma-na in-za-hur-e-tú a-na
- 2. 2 ma-na 10 GÍN KI.LAL ku-lu-la-a-nu
- 3. ù 2 par-ši-ga-nu šá <sup>d</sup>A-a
- 4. dDUMU.MÍ.MEŠ É-babbar-ra
- 5.  $\lceil {}^{\rm d}Gu \rceil$ -la u  ${}^{\rm d}\check{S}a$ -la
- 6.  $[x \ x] \lceil x \rceil a-na^{m} \lceil x \ x \ x \rceil -tu$
- 7. [....] <sup>r</sup>x<sup>1</sup>

Rest lost

Rev.

- 1'. [....]  $\lceil x \rceil$ -tas
- 2'. a-na <sup>m</sup>[DUB]-N[UMUN<sup>?</sup> SUM]<sup>in</sup>
- 3'. ITI.GU<sub>4</sub> U<sub>4</sub>.3.[KAM M]U.11.KAM
- 4'. md AG-I LUGAL [TI]N.[T]IR ki
- L. 3. 2 paršigānu šá Aya mārāt Ebabbar Gula u Šala means probably 2 headdresses each.
- L. 6. The first two signs in the name are so badly preserved that I cannot identify them; the partly preserved sign before tu looks exactly like síg.
- Rev. 1'. The last sign is preceded by  $\check{s}\check{u}$ , probably the remains of another sign.
- Rev. 2'. After DUB only a fragment of horizontal stroke is preserved.

4 minas of inzahurētu-wool for 2 minas, 10 shekels the weight of kulūlu-headbands and 2 paršīgu-headdresses for Aya, the Daughters of Ebabbar, Gula and Šala [... was given] to [xx]-tu.

[.... was given] to <sup>r</sup>Šāpik¹-z[ēri]. Month of Ayaru, 3<sup>rd</sup> day, 11<sup>th</sup> [ye]ar of Nabonidus, king of Babylon.

# **487. BM 64919** (82-9-18, 4900)

PLATE 116

 $3.9 \times 3.0$  cm

10.2.Cyr 8

- 1. 18 GÍN SÍG.ZA.GÌN.KUR.RA
- 2.  $^{\text{túg}}l[u\text{-}ba\text{-}r]i\ ku\text{-}[lu]\text{-}^{\Gamma}lu^{\Gamma}$ 3.  $^{\text{túg}}lu\text{-}^{\Gamma}ba^{\Gamma}\text{-}ri\ me\text{-}tu$
- 4. šá <sup>d</sup>IM šu-qul-tu<sub>4</sub>-šú

Rev. 5. ITI.GU<sub>4</sub> U<sub>4</sub>.10.KAM 6. MU.8.KAM <sup>m</sup>*Kur-raš* 

L. 5. The day date is written over one vertical wedges.

18 shekels of blue-purple wool, the *lubār kulūlu* and *lubār mēṭu*-headbands for Adad, is their! weight.

Month of Ayaru,  $10^{th}$  day,  $8^{th}$  year of Cyrus.

# **488.** Cam **39** = BM 60039; cf. NUVI 3, No. 134 Collated

<->. 2.Cam 1 (538 BC)

- 1. [x] [x x x] [GÍN] KI.[LAL
- 2.  $[x^1 [x x x] \hat{u}^* 2-ta^* [...]]$
- 3. [2] TÚG [x] x [x] [x x x] [DA/ta]
- 4.  $[\check{s}\acute{a}]^{\mathsf{r}^{\mathsf{d}}}$ \*DUMU\*.MÍ\*1.ME\*  $\acute{E}$ -babbar-[ra]
- 5. <sup>[6]</sup> GÍN KI.LAL TÚG.HI.A <sup>[me\*-tu\*]</sup>
- 6. ù TÚG.HI.A ku\*-lu\*-lu\* šá SÍG.ZA\*.[GÌN.KUR.RA]
- 7. ½ ma-na 3\* GÍ[N] SÍG.BAR.DUL<sub>5</sub> šá TÚG [....]
- 8. 7 GÍN 'KI.LAL' [ $x \times (x) \check{s} \acute{a}$ ' TÚG.ÍB.LÁ x (er?)
- 9. *šá* <sup>d</sup>*Bu*-[*ne-n*]*e*

Rev. 10. ½ ma-na SÍG.ḤÉ.ME.DA [....]

- 11. [x] TÚG.ÍB.LÁ *šá* <sup>d</sup>*Bu*-[*ne*]-*n*[*e*]
- 12. dul-lu SÍG.HÉ.ME.DA ù [SÍG.ZA.GÍN.KUR.RA]
- 13. *šá* ITI.GU<sub>4</sub> <sup>r</sup>x<sup>1</sup> [MU].1.KAM
- 14. <sup>m</sup>Ka-am-bu-zi-ja LUGAL TIN.TIR<sup>ki</sup>

In NUVI 3, No. 134, it is edited with wrong number as Cam 36. It seems that at the beginning no line is missing.

[...] shekels, the weight of [....] and 2 [...., 2 [.... for] the Daughters of the Ebabbar 6 shekels of blu[e-purple] wool, the weight of the  $lub\bar{a}r$   $m\bar{e}tu$  and  $lub\bar{a}r$   $kul\bar{u}lu$ -headbands

33 she[kels], <the weight of> the robe?! [....]

7 shekels, the weight of [x] sashes for Bunene

½ mina of red wool [for ....] (and) sashes for Bu[nen]e.

(This is) the blue-purple (and) [red] work of the month Ayaru, 1<sup>st</sup> year of Cambyses, king of Babylon.

### 489. VS 6, 107; cf. NUVI 3, No. 246

25.11.Cam 0

- 1. 「1/3」 <GÍN> SÍG.ZA.GÍN.KUR.RA a-na [bat-qa]
- 2. šá hu-ub-bu-ut-tu<sub>4</sub> šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 3. 5 GÍN SÍG.ZA.GÍN.KUR.RA 10 GÍN

- 4. SÍG.HÉ.ME.DA a-na bat-ga
- 5. <*šá*> *pi-šá-an-nu*
- 6. a-na <sup>md</sup>30-DINGIR
- 7.  $SUM^{nu}$
- 8. ITI.ZÍZ U<sub>4</sub>.25.KAM
- 9. MU.SAG.NAM.LUGAL.LA
- 10. <sup>m</sup>Kám-bu-zi-ja LUGAL TIN.TIR<sup>ki</sup>
- 11. LUGAL KUR.KUR
- L. 2, cf. BM 65127 (= 495): 2.
- 20 <shekels> of blue-purple wool for [repair] of the *hubbutu*-garment for the Queen of Sippar;

5 shekels of blue-purple wool (and) 10 shekels of red wool for repair <of> pišan-nu-bag(s) was given to Sîn-ilī.

Month Šabatu, 25<sup>th</sup> day, the accession year of Cambyses, king of Babylon, king of Lands.

# 489a. BM 63011 (82-9-18, 2980)

PLATE 116

3.7 x 2.7 cm

- 1. 10 GÍN <sup>síg</sup>ta-kil-tu<sub>4</sub>
- 2. a-na bat-qa šá
- 3. ku-si-tu<sub>4</sub> šá
- 4. dGAŠAN<sup>rat</sup> [Sip-par<sup>ki</sup>]

Edge 5.  $3 < GÍN > a-na ku-[si-tu_4]$ Rev. 6.  $sá^{d}A-nu-ni-tu_A$ 

- L. 4. The writing  $GAŠAN^{rat}$  supports the reading Šarrat suggested by Bongenaar, *Ebabbar*, p. 229.
- 10 shekels of blue-purple wool for repair of the robe of the Queen of [Sippar]; 3 <shekels> for (repairing of) the ro[be] of Anunītu.

# **490.** Cam **158** = BM 60433; cf. NUVI 3, No. 143 Collated

7.2.Cam 3

- 1. 5 GÍN SÍG.ZA.GÍN.KUR.RA a-na ți-mu
- 2. šá TÚG.HI.A me-e-tu\* TÚG.HI.A ku-[lu]
- 3. ù e-ri šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 4. a-na ŠEŠ.MEŠ-MU-[d]AMAR.UTU SUMin
- 5. 10 <GÍN> SÍG.ZA.GÍN.KUR.RA a-na ti!-mu
- 6. šá pi-ša-an-ni [a-na] MÍ.GAL.MEŠ
- 7. 5 GÍN SÍG.ZA.GÍN.KUR.RA *a-n*[*a*]

- 8.  $g\dot{u}^*$ - $\dot{h}al$ - $\dot{s}u^{\text{meš}}$   $\dot{s}\dot{a}$   $[x^{\dagger}]$  [....] 9.  $\dot{s}\dot{a}$  [DN ....]
- 10. *a-na* [....]
- 11. 11 GÍN SÍG.ZA.GÍN.KUR.RA [a-na]
- 12. gu-ḥal-ṣu<sup>meš</sup> šá [<sup>d</sup>GAŠAN Sip-par<sup>ki</sup>] 13. a-na <sup>md</sup>30-DINGIR SUM<sup>[in</sup>]
- 14. ITI.GU<sub>4</sub> U<sub>4</sub>.7.KAM MU.3.KAM
- 15. <sup>m</sup>Kam-bu-zi-ja LUGAL E<sup>ki</sup> LUGAL KUR.KUR
- L. 6. Concerning rabītu, see Bongenaar, Ebabbar, p. 249.
- L. 12. The gap was already filled by Bongenaar, Ebabbar, p. 225.
- 5 shekels of blue-purple wool for the yarn for the lubār mētu, lubār kulūlu and lubār erru-headbands of Anunītu was given to Ahhē-iddin-Marduk;
- 10 <shekels> of blue-purple wool for the varn for the pišannu-bag <was given to> the female chiefs?;
- 5 shekels of blue-purple wool for the scarf for [....] for the [god(dess) x was given] to [PN];
- 11 shekels of blue-purple wool [for] the scarf for [the Queen of Sippar] was given

Month of Ayaru, 7<sup>th</sup> day, 3<sup>rd</sup> year of Cambyses, king of Babylon, king of Lands.

### **491. BM 84034** (83-1-21, 1197)

**PLATE 117** 

 $5.0 \times 3.8$  cm

### 14.5.Cam 3

- 1'. [x GÍN SÍG.ZA.GÌ]N.KUR.R[A]
- 2'. [a-na mu]-<sup>r</sup>ta<sup>¬</sup>-ta šá <sup>d</sup>U[TU]
- 3'. [a-na lu-b]u-uš-tu<sub>4</sub> šá ITI. 「KIN<sup>¬</sup>
- 4'. a-na <sup>md</sup>UTU-MU-MU SUM<sup>na</sup>
- 5'. 7 GÍN SÍG.ZA.GÌN.KUR.RA
- 6'. ina lu-bu-uš-tu4 šá ITI.DU<sub>6</sub>

Edge

7'. a-na <sup>md</sup>UTU-MU-MU

- 8'. SUM<sup>na</sup>
- 9'. ITI.NE U<sub>4</sub>.14.KAM
- 10'. [MU].3.KAM $^{\rm m}$ Kam-bu-zi-iá 11'. [LUGAL E] $^{\rm ki}$  LUGAL KUR.KUR
- L. 3'. The partly preserved month's name might be read also  $DU_6$ , but because the blue-purple wool for this month given to Šamaš-šum-iddin appears in ll. 5-7, I prefer the reading KIN.
- [x shekels of blue]-purple wool for the muttatu-headdress for Šamaš [for the *lub*]*uštu* ceremony of the month 「Ulūlu」 was given to Šamaš-šum-iddin;
- 7 shekels of blue-purple wool for the *lubuštu* ceremony of the month Tašrītu was given to Šamaš-šum-iddin.
- Month of Abu, 14<sup>th</sup> day, the 3<sup>rd</sup> [year] of Cambyses, [king of Babylon], king of Lands.

# **492. BM 66823** (82-9-18, 6816)

PLATE 117

 $3.9 \times 2.8$  cm

### 19.12.Cam 4

- 1. 2/3<sup>?</sup> GÍN SÍG.ZA.GÌN.KUR.RA
- 2. a-na TÚG.ÍB.LÁ
- 3. *šá* <sup>d</sup>UTU *u* <sup>d</sup>HAR
- 4. a-na <sup>m</sup>Gi-mil-lu
- 5. SUM<sup>nu</sup> ITI.ŠE
- 6. U<sub>4</sub>.[20].1.LAL.KAM
- 7. MU.4.KAM <sup>m</sup>*Kam-bu-zi-iá* 8. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
- L. 1. Because u looks like written over erasure, it is not excluded that the numeral might be read as 12.
- $40^{?}$  shekels of blue-purple wool for  $n\bar{e}behu$ -belt of Šamaš and Bunene was given to

Month of Addaru, 19<sup>th</sup> day, 4<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

# **493.** Cam 382 = BM 60614; cf. NUVI 3, No. 162 Collated

### 21.6.Cam 7

- 1. ½\* ma-na SÍG.ZA.GÌN.KUR.RA
- 2. a-na ku-lu-lu šá <sup>d</sup>UTU
- 3. ½\* ma-na 6 KI.MIN šá
- 4. TÚG.UD. A šá $^{\rm d}$ UTU <br/> u  $^{\rm d}$ HAR\*
- 5. 1/3\* ma-na KI.MIN šá TÚG.UD.A
- 6. *šá* <sup>d</sup>IM PAP 1 1/3 *ma-na* 6 <sup>!</sup> [GÍN]
- 7. SÍG.ZA.GÌN.KUR.RA {x x}
- 8. a-na <sup>md</sup>UTU-MU-MU SUM<sup>!</sup>[<sup>nu</sup>]
- 9. SÍG.ZA.GÌN.KUR.RA šá a-na
- 10. *lu-bu-uš-tu*<sub>4</sub> *šá* U<sub>4</sub>.15.KAM
- 11. ITI.APIN *a-na* <sup>md</sup>UTU-MU-MU

- 12. SUM<sup>nu</sup> ITI.DU<sub>6</sub> U<sub>4</sub>.21.<sup>r</sup>KAM<sup>1</sup> 13. MU.7.KAM <sup>m</sup>Kam-bu-zi-iá 14. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
- L. 6. The numeral 5 is clear which means that the scribe made a mistake here.
- L. 7. SÍG.ZA.GÌN.KUR.RA is followed with two additional unidentified signs (not erased, as suggested by Strassmaier).

½ mina of blue-purple wool for the (lubār) kulūlu-headband for Šamaš 36 shekels ditto for the lubāru-garments for Šamaš and Bunene

20 shekels ditto for the lubāru-garment for Adad

1 mina 26<sup>th</sup> [shekels] of blue-purple wool was given to Šamaš-šum-iddin. (This is) wool, which was given to Šamaš-šum-iddin for the *lubuštu* ceremony on the 15<sup>th</sup> day of month Arahsamna.

Month of Tašrītu, 21<sup>st</sup> day, 7<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

# **494. BM 69225** (82-9-18, 9224 A)

**PLATE 118** 

 $5.1 \times 3.3$  cm

<->.8.Dar 1

- 1. ½ ma-na 6 ½ GÍN
- 2. SÍG.ZA.GÌN.<KUR>.RA a-na lu-bu-uš-tu<sub>4</sub>
- 3. *šá* ITI.APIN <sup>f</sup>*Ú-bar-*<sup>r</sup>*tu*<sub>4</sub><sup>1</sup>
- 4. šá É a-si-i SUM<sup>na</sup>
- 5. ITI.APIN MU.1.KAM
- 6. <sup>[m]</sup> [Da-', -ri] -[muš

The text is cited in Altavilla – Walker 2009, p. 109, No. 508.

Ubartu is, except for Murānātu, (Bongenaar, *Ebabbar*, pp. 331–32 and Zawadzki, *Garments of the Gods*, Vol. I, p. 219) and Ri'du (BM 66172: 4, mentioned as one out of fives weavers) the only woman involved in the manufacturing of garments for the gods.

Ll. 3–4, cf.  $^{\rm m}Ba$ -ku- $\acute{u}$ -a  $\acute{s}\acute{a}$   $\acute{E}$  a-si-i (CT 56, 618: 4–5).  $as\^{u}$  can be translated as "physician" (hence Bongenaar, Ebabbar, p. 135), but the lack of determinative  $l \acute{u}$  makes such an interpretation unlikely. As the term  $as\^{u}$  denotes a wooden part of a loom and the general term for a loom is not known, it seems to me that at least in the first millennium BC, the  $b \bar{t} t as\^{t}$  denoted the house, or its part, where looms were placed and where garments and clothes were manufactured. Presumably rab  $as\^{t}$  mentioned in Coll. Smit 110: 26 (unpublished, cited by Bongenaar, Ebabbar, p. 135) should be translated not as "chief physician" but "chief of the weaver's shop", or similar.

36 ½ shekels of blue-purple wool for *lubuštu* ceremony for the month of Araḫsamna was given to Ubartu of the weaver's shop. Month Araḫsamna, 1<sup>st</sup> year of Dar[ius, king of ......].

**494a. BM 69226** (82-9-18, 9224 B)

 $4.7 \times 3.55 \text{ cm}$ 

[(x)] GÍD.DA SÍG.ZA.GÌN.[<KUR>.RA]

The text is cited in Altavilla – Walker 2009, p. 109, No. 508 with photo of a seal on diskette (B 29)

Tablet concerning of blue-purple wool.

# **495. BM 65127** (82-9-18, 5108)

PLATE 118

 $4.0 \times 2.9$  cm

#### 17.11.Dar 1

- 1. 2/3 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. a-na TÚG.HI.A hu-ub-bi-tu<sub>4</sub>
- 3. šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 4. ina lìb-bi 8 GÍN
- 5. ina É.GUR7.MEŠ
- 6. [x] GÍN *a-na*
- Edge
- 7.  $[^m x]$ - $[^n x]$ -a

Rev.

- 8. [SU]M<sup>nu</sup> ITI.ZÍZ
- 9. U<sub>4</sub>.17.KAM MU.1.KAM
- 10. <sup>m</sup>Da-ri-šú
- 11. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
- 12. 1 ma-na SÍG.HI.A
- L. e. 13. *a-na* 1<sup>*en*</sup> TÚG.ÚR
  - 14. *a-na* ra qa e
  - 15. SUM<sup>nu</sup>
- L. 2. Cf. *hubbutu* in VS 6, 107 (= 489): 2.
- L. 7. The possible reading is  $[{}^{m}\check{S}]u$ -[m]a-a.
- L. 14. The reading of the signs is certain but the sense is obscure; a name is expected here.

40 shekels of blue-purple wool for the  $lub\bar{a}r$  hubbitu garment for the Queen of Sippar, including 8 shekels from the  $b\bar{\imath}t$   $kar\hat{e}$  storehouse (and) [x] shekels [was gi]ven to [PN]-a.

Month of Šabaṭu, 17<sup>th</sup> day, 1<sup>st</sup> year of Darius, king of Babylon, king of Lands. 1 mina of wool for 1 *sūnu*-belt for [....] was given.

#### **496. BM 55775** = Bertin 2113 Collated

# 2.[x].Dar 7

- 1. 5 GÍN SÍG.ZA.GÍN.KUR.RA a-na
- 2. UGU <sup>md</sup>UTU-MU-MU *a-na*
- 3.  $\check{s}ul$ -lu-mu KÁ-tu<sub>4</sub> ½\* ma\*-na\*
- 4. SÍG.ZA.GÍN.KUR.RA HA.LA LUGAL
- 5. lúGAL ka-ṣir šu-bu-lu

- 6. [ITI.x] U<sub>4</sub>.2.KAM MU.7.KAM
- 7. <sup>m</sup>Da-ri-šú LUGAL TIN.TIR<sup>ki</sup>
- 8. LUGAL KUR.KUR
- L. 1. The *šūlum bābti* ceremony is not known from other texts.

5 shekels of blue-purple wool on account of Šamaš-šum-iddin for the šūlum bābti

 $\frac{1}{2}$  mina of blue-purple wool, the king's share, has been brought by *rab*  $k\bar{a}$ *șir*. [Month of x],  $2^{nd}$  day,  $7^{th}$  year of Darius, king of Babylon, king of Lands.

### **497. BM 64563** (82-9-18, 4534)

 $6.0 \times 5.0$  cm

#### 22.4.Dar 17

- 1. [1<sup>?</sup> GÚ.U]N 55 ma-na SÍG.HI.A
- 2. [(u) ½ ma-na] <sup>6</sup> GÍN SÍG.ZA.GÌN.<KUR>.RA
- 3. [a-na lu]-bu-uš-tu 4 šá U4.3.KAM
- 4. [šá ITI].KIN MU.17.KAM a-na
- 5.  $\lceil^{\text{md}} A \rceil G^? it \lceil tan \rceil nu \ e pi [\check{s} \check{s}\acute{a} nu]$
- 6. [x]-DÙ-A DUMU šá <sup>m</sup>Mu-r[a-nu SUM]
- 7. [x x] SÍG.ZA.GÌN.<KUR>.RA *a-*[na] Rev.
  - 8. [*lu*]-*bu*(T: *mu*)-*uš*-*tu*<sub>4</sub> *šá* <sup>d</sup>UTU
  - 9. [šá] U<sub>4</sub>.3.KAM šá ITI.KIN MU.17.KAM
  - 10. [a]-na <sup>md</sup>UTU-MU-MU SUM<sup>na</sup>
  - 11. [x G]ÍN 4-tú LAL KÙ.BABBAR a-na
  - 12. [<sup>md</sup>A]G-it-tan-nu <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>
  - 13. [ITI].ŠU U<sub>4</sub>.22.KAM MU.1<sup>r</sup>7<sup>1</sup>.KAM
  - 14. [<sup>m</sup>Da-r]i-mu-šú LUGAL E<sup>ki</sup>
- L. e. 15. [LU]GAL KUR.KUR
- L. 12. Nabû-ittannu appears also in BM 82568 (= 624): 4 (5.1.Dar 28) as išpar birmi, where he received silver for buying blue-purple wool for adilānu ša kusītu of the Queen of Sippar. The sign UŠ resembles more KIN than UŠ.

[1 tale]nt 55 minas of wool, [(and) 3]6 shekels of blue-purple wool for the *lubuštu* ceremony of the 3<sup>rd</sup> day [of the month] Ulūlu, 17<sup>th</sup> year, [was given] to [Nab]û-ittannu, the perfor[mer of x]-bān-apli, son² of Murā[nu]. [x mina] of blue-purple wool for the [*lu]buštu* ceremony of Šamaš, the 3<sup>rd</sup> day of the month Ulūlu, 17<sup>th</sup> year, was given to Šamaš-šum-iddin. [x she]kels minus ¼ shekel of silver was given to [Nab]û-ittannu. [Month] of Du'ūzu, 22<sup>nd</sup> day, 17<sup>th</sup> year of [Dar]ius, king of Babylon, [ki]ng of Lands

Lands.

498. BM 61970 (82-9-18, 1939)

PLATE 119

 $4.7 \times 5.8$  cm

15.1.Dar 18

- 1. <sup>[1/3]</sup> GÍN SÍG.ZA.GÌN.<KUR>.RA [*a-na*<sup>?</sup>]
- 2. 「TÚG¹.ÍB.LÁ {ÍB} šá dUTU 「x x¹

- 3. [a]- $na^{\text{m}}$ ÌR-ja SUM $^{ra}$
- 4. <sup>[1/3]</sup> ma-na 1 GÍN SÍG. <sup>[ZA]</sup>. [GÌN. <KUR>. RA]
- 5. a-na dul-lu šá IT[I.GU<sub>4</sub>]
- 6. MU.18.KAM *a-*<sup>г</sup>*na*<sup>1</sup>
- 7.  $[^{md}UTU-MU-MU ^{l\acute{u}}x x]$

Edge 8.  $\{[a]^{-1}na^{-1} dul - lu \check{s}\acute{a} IT[I.GU_4 MU.18.KAM]$ 

Rev.

- 9. a-na  $^{\text{md}}$ UTU-MU-MU $^{\text{l}}[^{\text{u}}x x]$ }
- 10. ITI.BÁR U<sub>4</sub>.15.KAM
- 11. MU.18.KAM <sup>m</sup>Da-ri-mu-[šú]
- 12. LUGAL KUR.KUR
- Ll. 8–9 repeat ll. 5–7. It is impossible to say which of the two titles of Šamaš-šum-iddin was written in the text. Concerning him, see Bongenaar, *Ebabbar*, pp. 347f and Zawadzki, *Garments of the Gods*, Vol. I, p. 227ff.
- 20 shekels of blue-purple wool [for] *nēbeḥu*-belt (and) sashes? for Šamaš was given to Ardīya.
- 21 shekels of blu[e-purple] wool for the work for the month of [Ayaru], 18<sup>th</sup> year, was given to Šamaš-šum-iddin, the [weaver/bleacher].

Month of Nisannu, 15<sup>th</sup> day, 18<sup>th</sup> year of Darius, king of Lands.

# **499. BM 65114** (82-9-18, 5095)

 $4.5 \times 3.1$  cm

#### 27.10.Dar 25

- 1. 1 5/6 ma-na SÍG.ZA.GÌN.<KUR>.RA
- 2. šá ina IGI <sup>md</sup>EN-it-tan-nu
- 3. lúUŠ.BAR bir-ri ina lìb-bi
- 4. [x m]a-[na ....]

# Rest lost

Rev.

- 1'.  $\lceil x \rceil \times \times \times \lceil ma-na \rceil [....]$
- 2'. mdEN-it-tan-nu <SUM> ITI. 「AB」
- 3'. U<sub>4</sub>.27.KAM MU.25.KAM
- 4'. <sup>m</sup>Da-ri-'-muš-šú
- 5'. LUGAL TIN.TIR<sup>ki</sup> u KUR.KUR

Bēl-ittannu, *išpar birmu*, was not known till now but he might be identical with the *ašlāku/mukabbû*, cf. Bongenaar, *Ebabbar*, p. 32 and Zawadzki, *Garments of the Gods*, Vol. I, p. 214.

1 mina 50 shekels of blue-purple wool <was given> at disposal of Bēl-ittannu, the multicoloured weaver; out of it [...]

...] was given to Bēl-ittannu.

Month of Ţebētu, 27<sup>th</sup> day, 25<sup>th</sup> year of Darius, king of Babylon, king of Lands.

# **500. BM 60847** (82-9-18, 823)

**PLATE 120** 

 $5.8 \times 4.3$  cm

#### 3.10.Dar 26

- 1. 1 1/3 ma-na 7 GÍN 「SÍG¹.ZA.GÌN.<KUR>.RA
- 2. 3 1/2 GÍN KÙ.BABBAR BABBAR-ú a-na
- 3. 1/3 1 GÍN SÍG.ZA.GÌN. $\langle KUR \rangle$ .RA  $\{a^{-1}na^{-1}\}$  (na erased)
- 4. PAP 1 <sup>7</sup>2/3 <sup>1</sup> ma-na 8 GÍN SÍG.ZA.GÌN.<KUR>.RA
- 5. *šá lu-*<sup>r</sup>*ba*<sup>1</sup>*-ri šá* <sup>d</sup>UTU *šá* ITI.ŠE
- 6. 「ITI.BÁR u ITI.GU<sub>4</sub>¹ šá

7. MU.[27.KAM šá <sup>m</sup>D]a-ri-'-muš Rev.

- 8. LUGAL [E<sup>!</sup>][<sup>ki</sup> a-na] <sup>md</sup>UTU-MU-MU
- 9. <sup>lú</sup>UŠ.BAR SUM<sup>na</sup> ITI.AB
- 10. U<sub>4</sub>.3.KAM MU.26.KAM
- 11. <sup>m</sup>Da-ri-'-muš-šú LUGAL E<sup>ki</sup>
- 12. u KUR.KUR
- L. 4. The numeral recognized as 2/3 is written over an erasure and resembles more 5/6, however I decided to read it as 2/3! because 1 mina 27 shekels (l. 1) + 21 shekels (l. 3) gives exactly 1 minas 48 shekels.

1 mina 27 shekels of blue-purple wool (and) 3 ½ shekels of white silver for 21 shekels of blue-purple wool, total 1 mina 48 shekels of blue-purple wool for the *lubāru*-garment of Šamaš for the month of Addaru, Nisannu and Ayaru, [27<sup>th</sup> year of Da]rius, king of Babylon, was given to Šamaš-šum-iddin, the weaver. Month of Ţebētu, 3<sup>rd</sup> day, 26<sup>th</sup> year of Darius, king of Babylon and Lands.

### **501. BM** 61317 (82-9-18, 1292)

 $4.1 \times 2.8$  cm

# 25. [x]. Dar 26

- 1. 1/3 ma-na SÍG.ZA.GÌN.<KUR>.RA
- 2. eš-ru-ú šá <sup>m</sup>DUB-NUMUN
- 3. 「A<sup>¹ lú</sup>NAGAR<sup>?</sup> ina ŠU<sup>ii</sup>
- 4.  $[m]^d$ UTU-TIN $^{it}$  a-na
- 5. É-babbar-ra SUM

Rev.

- 6. ITI.[x] U<sub>4</sub>.26.<KAM>
- 7. MU.2<sup>r</sup>6<sup>r</sup>.KAM <sup>m</sup>Da-ri-šú 8. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.<KUR>

20 shekels of blue-purple wool, the tithe which Šāpik-zēri, the ... has given to the Ebabbar temple by Šamaš-uballit. Month of [x],  $26^{th}$  day,  $26^{2th}$  year of Darius, king of Babylon, king of Lands.

# **502. BM 60976** (82-9-18, 952)

 $5.4 \times 4.2$  cm

#### 8.4.Dar 28

- 1. 5 GÍN SÍG.ZA.GÌN.KUR.RA a-na
- 2. ki-ri-ki šá hu-sa-an-ni-e
- 3. šá lu-bu-uš-tu<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 4. šá U<sub>4</sub>.17.KAM šá ITI.ŠU
- 5. 6 GÍN SÍG.ZA.GÌN.KUR.RA a-na
- 6. ki-ri-ki šá hu-ṣa-an-ni-e
- 7.  $\check{s}\check{a}^{\lceil x \rceil}[x]^{\lceil x \rceil}in[x]$

Edge Rev

- 8. šá <sup>d</sup>GA[ŠAN UD.KI]B.「NUN<sup>1ki</sup>
- 9. 「PAP1 11 GÍN SÍG.ZA.GÌN.KUR.RA
- 10. <sup>r</sup>a-na<sup>1</sup> ki-ri-ki šá hu-ṣa-an-ni-e
- 11. a-na <sup>m</sup>TIN-su-<sup>d</sup>Gu-la
- 12. SUM<sup>na</sup> IT[U].ŠU U<sub>4</sub>.8.KAM
- 13. MU.28.KAM <sup>m</sup>Da-ri-'-muš 14. LUGAL E<sup>ki</sup> u KUR.KUR<sup>meš</sup>
- L. 2, 6 and 10: ki-ri-ki, not known till now, maybe from Hebrew k-r-k "to bind" (courtesy R. Zadok).
- L. 7 and 8 are heavily broken and the reading is very uncertain. 6 shekels of blue-purple wool was usually given for garments for Bunene.
- 5 shekels of blue-purple wool for kiriku of sashes for the lubuštu ceremony of Anunītu, the 17<sup>th</sup> day of the month Du'ūzu.
- 6 shekels of blue-purple wool for kiriku of sashes [....] of the Queen of Sippar, total 11 shekels of blue-purple wool for kiriku of sashes was given to Uballissu-

Month of Du'ūzu, 8<sup>th</sup> day, 28<sup>th</sup> year of Darius, king of Babylon, king of Lands.

### **503. BM 65841** (82-9-18, 5832)

PLATE 120

# 21.7.Dar 29

- 1. [x GÍN SÍ]G.ZA.GÌN. $\langle$ KUR $\rangle$ .R[A  $u^2$ ]
- 2. [x GÍN SÍ]G.ZA.GÌN.<KUR>.RA <sup>r</sup>x¹ [..]
- 3. [*a-n*]*a pa-ni mu-și-*[*e*]
- 4. [*a*]-*na* <sup>m</sup>AD-ÙRU
- 5.  $[SU]M^{na} e-lat! [IGI-tu_4]$

- 6. [IT]I.DU<sub>6</sub> U<sub>4</sub>.21.KAM
- 7. [M]U.29.KAM <sup>m</sup>Da-ri<sup>!</sup>-iá-mu[š] 8. LUGAL E<sup>ki</sup> u KUR.KUR<sup>meš</sup>
- L. 5. The sign following e looks like ud. At the end we might expect IGI-tu<sub>4</sub>. The ri in l. 7 looks like written over an erasure.

[x shekels of bl]ue-purple wool [and? x shekels of] blue-purple wool [f]or (manufac]ture of] the *pan muṣê*-cover? was given to Abu-uṣur; (this is) except for an earlier issue.

[Mont]h Tašrītu, 21<sup>st</sup> day, 29<sup>th</sup> year of Darius, king of Babylon and Lands.

# **504. BM 60341** (82-9-18, 309)

PLATE 121

 $5.2 \times 4.3 \text{ cm}$ 

4.[x].Dar 30

- 1. 1/3 GÍN SÍG.ZA.GÌN.<KUR>.RA
- 2. 2 ma-na in-za-hu-hur-e-ti
- 3. a-na mut-ta-tu<sub>4</sub>
- 4. [šá] <sup>rd</sup>¹UTU šá ITI.KIN
- 5. [x x x] <sup>[10.KAM]</sup>
- 6. [x x x x x x]-*tu*<sub>4</sub>
- 7.  $[x \times x \times SUM]^{\lceil na \rceil}$

Rev.

- 8. [ITI.x] U<sub>4</sub>.4.KAM
- 9. [M]U.30.KAM <sup>m</sup>Da-ri-iá-a-muš
- 10. LUGAL

20 shekels of blue-purple wool, 2 minas of *inzaḥurētu*-dye for the *muttatu*-headband [for] Šamaš for the month of Ulūlu [....], 10<sup>th</sup> day [.... was giv]en. Month of [x], 4<sup>th</sup> day, 30<sup>th</sup> year of Darius, king.

# **505. BM 67854** (82-9-18, 7852)

PLATE 121

 $5.1 \times 3.2$  cm

3.12.Dar 32

- 1'. [x] GÍN SÍG.ZA.G[ÌN.KUR.RA ù]
- 2'. [x GÍN] SÍG.ZA.GÌN.<KUR>.RA *ir-bi šá* É <sup>d</sup>GAŠAN <sup>r</sup>Sip-par<sup>ki</sup><sup>1</sup>
- 3'. [a-na T]ÚG.UD.A šá <sup>d</sup>UTU u <sup>d</sup>Bu-ne-n[e]
- 4'. mìR-ja lúUŠ.BAR SUM
- 5'. [IT]I.ŠE U<sub>4</sub>.3.KAM MU.32.KAM
- 6'. [mD]a-a-ri-iá-muš LUGAL E<sup>ki</sup>
- 7'.  $u \text{ KUR.KUR}^{\text{meš}}$

[x] shekels of blue-p[urple] wool [and x shekels] of blue-purple wool from the income of the temple of the Queen of Sippar [for the  $lu]b\bar{a}ru$ -garments for Šamaš and Bunene was given to Ardīya, the weaver.

[Mont]h of Addaru, 3<sup>rd</sup> day, 32<sup>nd</sup> year of [Da]rius, king of Babylon and Lands.

# **506. BM 75379** (83-1-18, 714) = Str. II 264/3

 $4.0 \times 4.3 \text{ cm}$ 

#### 9.12.Dar 33

- 1. ½ ma-na SÍG.ZA.G[ÌN.<KUR>.RA]
- 2. šá 15 GÍN <sup>síg</sup>[ta¹-[bar-ri a-na]
- 3. <sup>md</sup>EN-ŠEŠ.MEŠ-*it-tan-nu* [A-*šú šá* <sup>md</sup>30-DINGIR SUM<sup>na</sup>]
- 4. 4 GÍN SÍG.ZA.GÌN.<KUR>.RA [(x x)]
- 5. *šá* 2 GÍN <sup>síg</sup>[x¹-[....]
- 6. <sup>m</sup>Ap-la-a 「DUMU「[....]
- 7. [PAP<sup>?</sup>] ½ *ma-n*[*a* 4 GÍN SÍG.ZA.GÌN.<KUR>.RA]

Edge

- 8. [*a*]-*na*<sup>túg</sup>[....<sup>d</sup>UTU]
- 9.  $u^{d}Bu^*$ -[ne-ne ....]

Rev. 10. [*šá*] ITI.GU<sub>4</sub> MU.33.[KAM]

- 11. a-na <sup>m</sup>AD-ÙRU <sup>lú</sup>U[Š.BAR bir-mu SUM<sup>na</sup>]
- 12. ITI.ŠE U<sub>4</sub>.9.KAM [MU.33. KAM]
- 13. <sup>m</sup>Da-ri-iá-[muš LUGAL E<sup>ki</sup> LUGAL KUR.KUR]
- L. 3. Cf. Bēl-aḥ-ittannu/Sîn-ilī, see Bongenaar, *Ebabbar*, p. 245 and Zawadzki, *Garments of the Gods*, Vol. I, p. 213.
- L. 5. The broken sign following síg is similar to *lu*.
- L. 6. Aplā, see Bongenaar, Ebabbar p. 316.
- L. 9. Bongenaar, *Ebabbar*, p. 260, suggests to reconstruct there the name of Uballissu-Gula (probably TI[N-su-....]), but the sign is preceded only by the god's determinative and is very similar to *bu*.
- L. 11. Abu-uşur, the full name is Abu-šar-uşur (BM 61135: 22 (12.9. <Dar> 30).

½ mina of blue-pu[rple wool] for? 15 shekels of re[d] wool was given [to] Bēl-ahhē-iddin, [son of Sîn-ilī].

4 shekels of blue-purple wool for 2 shekels of [....-wool], [total] 34 shekels of blue-pur[ple wool] for [....]- garment of [Šamaš] and Bu[nene ..] of the month Ayaru, 33<sup>rd</sup> [year, was given] to Abu-uṣur, [the multicoloured weave]r. Month of Addaru, 9<sup>th</sup> day, [33<sup>rd</sup> year] of Dari[us, king of Babylon, king of Lands].

### **507. BM 64093** = Bertin 2732 Collated

### 26.12. Dar 34

- 1. ½ ma-na 6 GÍN SÍG.ZA.GÌN.[KUR.RA]
- 2. a-na TUG.UD.A šá <sup>d</sup>UTU ù
- 3. *hu-ṣa-ni-*<sup>r</sup>*e*<sup>¬</sup> *šá* <sup>d</sup>UTU *ù*
- 4. TÚG.UD.A šá <sup>d</sup>HAR a-na
- 5. <sup>m</sup>ÌR-*ja* <sup>lú</sup>UŠ.BAR SUM
- 6. ITI.ŠE U<sub>4</sub>.26.KAM
- 7. MU.34.KAM  $^{\rm m}Da$ -ri- $^{\rm \Gamma}mu\check{s}^{\rm T}$
- 8. LUGAL E<sup>ki</sup> u LUGAL KUR.KUR

Note that usually the sum of 36 shekels of blue-purple wool was given for the lubāru of Šamaš and Bunene.

36 shekels of blue-purple wool for the *lubāru*-garment for Šamaš and the sashes for Šamaš and for *lubāru*-garment for Bunene was given to Ardīya, the weaver. Month of Addaru, 26<sup>th</sup> day, 34<sup>th</sup> year of Darius, king of Babylon and king of Lands.

### **508. BM 75676** (83-1-18, 1026) = Str. II 243/4

3.[x].Dar 34

- 1. 3 1/2 < GÍN> KÙ.BABBAR a-na 15 GÍN
- 2. SÍG.ZA.GÌN.<KUR.RA a-na
- 3. <sup>m</sup>Ki-din-nu SUM<sup>na</sup>
- 4. SÍG.ZA.GÌN.<KUR>.RA a-na
- 5. su-ḥa-a šá <sup>d</sup>UTU
- 6. [šá U<sub>4</sub>.x+]2.KAM a-na <sup>m</sup>ÌR-<sup>r</sup>ja<sup>1</sup>
- lúU]Š.BAR SUM<sup>na</sup>

8. [ITI.x] U<sub>4</sub>.<sup>[3]</sup>.KAM Rev.

- 9. MU.34.KAM 10. <sup>m</sup>Da-ri-a'-<sup>[</sup>muš] LUGAL E<sup>ki</sup>
- L. 5. The term su-ha-a is known only from this text. The context suggests that the term described an unknown type of garment of Šamaš for festival or cultic performance on the x+2 day of unknown month.
- L. 6. For the reading of the name, see already Bongenaar, *Ebabbar*, p. 316.
- 3 ½ <shekels> of silver for 15 shekels of blue-purple wool was given to Kidinnu; the blue-purple wool for the  $suh\hat{u}$  for Šamaš [for the x+]2 day, was given to Ardīya, the [we]aver.

[Month of x], 3<sup>rd</sup> day, 34<sup>th</sup> year of Darius, king of Babylon.

# **509. CT 55, 866** = BM 56870

# 7.4.Dar 35

- 1. 13 SÍG.ZA.GÌN.<KUR>.RA
- 2. a-na lu-bu-u $\check{s}$ -t[u<sub>4</sub>]
- 3. šá ITI.KIN šá MU.3<sup>r</sup>5<sup>1</sup>.[KAM]
- 4. a-na <sup>m</sup>Ni-din-tu<sub>4</sub> [u]
- 5. <sup>m</sup>Su-qa-a-a SUM<sup>na</sup>
- 6. ITI.ŠU U<sub>4</sub>.7.KAM
- 7. MU.35.KAM
- 8. <sup>m</sup>Da-ri-iá-muš
- 9. LUGAL KUR.KUR<sup>meš</sup>

13 shekels of blue-purple wool for the *lubuštu* ceremony of the month Ulūlu for the 35<sup>th</sup> year was given to Nidintu [and] Sūqaya. Month Du'ūzu, 7<sup>th</sup> day, 35<sup>th</sup> year of Darius, king of Lands.

### **510. BM 66041** (82-9-18, 6032)

 $3.6 \times 4.0 \text{ cm}$ 

16.[11<sup>?</sup>.Dar x]

- 1. [x] [1/3] GÍN SÍG.HI.A
- 2.  $\lceil a-na \rceil < in > -za-hu-\acute{a}r-e-ti \ \grave{u}$
- 3. [x x (x)] 17 *šá* ITI.ZÍZ
- 4. [a-n]a <sup>md</sup>EN-ŠEŠ.MEŠ-it-tan-nu 5. [A-šú šá <sup>md</sup>]30-DINGIR 6. [SUM<sup>na</sup> ITI. ZÍZ<sup>?</sup> U<sub>4</sub>].16.KAM

Rev.

- 7. [MU.x.]KAM

Rest lost

L. 4. Bēl-aḥhē-ittannu/Sîn-ilī, see Bongenaar, Ebabbar, p. 245 and Zawadzki, Garments of the Gods, Vol. I, p. 213. His activity in the time of Darius was the basis for the suggested dating of the text.

[x]+ 20 shekels of wool for *inzahurētu*-dye and [....]  $17^{th?}$  of the month Šabaţu [was given t]o Bēl-aḥḥē-ittannu, [son of] Sîn-ilī. [Month of Šabaţu²,  $16^{th}$  day [year  $x^{th}$  of Darius, king of Babylon, king of Lands].

# **511. BM 75289** (83-1-18, 621) = Str. II 274/2

 $4.3 \times 3.4 \text{ cm}$ 

21.9.Dar [x]

- 1. [x ma-na x G]ÍN KÙ.BABBAR BABBAR-ú
- 2. [ŠÁM x G]ÍN SÍG.ZA.GÌN.<KUR>.RA
- 3.  $[a-n]a^{md}$ EN-ŠEŠ.MEŠ-it-tan- $^{\Gamma}nu^{\dagger}$ 4.  $[A-\check{s}\check{u}\ \check{s}\check{a}^{md}]$ 30-DINGIR SUM $^{na}$  SÍG.ZA.GÌN.<KUR>.RA
- 5. [a-n]a  $iz-hu-\hat{u}^{me\S}$

Edge Rev.

6. *šá an ú* 「x<sup>1</sup> *la-nu* 

7.  $\lceil \check{s} \acute{a} \rceil$  dGAŠAN Sip- $[par^{ki} u]$ 

- 8.  ${}^{d}A$ -nu-ni- ${}^{\dagger}tu_4$  SUM $^{na_1}$
- 9. ITI.GAN U<sub>4</sub>.<sup>r</sup>21.KAM MU.x.KAM<sup>1</sup>
- 10. <sup>[m]</sup>Da-ri-[ja-muš x x x]
- 11. 「x x<sup>1</sup>
- L. 3. Bēl-ahhē-ittannu/Sîn-ilī, see Bongenaar, Ebabbar, p. 245 and Zawadzki, Garments of the Gods, Vol. I, p. 213.

[x mina(s) x shek]els of white silver, [the price of x she]kels of the blue-purple wool was given t[o Bēl-aḥhē-ittannu, [son of] Sîn-ilī. The blue-purple wool was given for the izhu-belts? of [....] for the Queen of Sip[par and] Anunītu. Month of Kislīmu, 21<sup>st</sup> day, [n<sup>th</sup>] year of Darius [....].

# **512. BM 83706** (83-1-21, 869)

PLATE 122

 $3.6 \times 3.3$  cm

[x].10.[Nbk<sup>?</sup>] 30

- 1. 2 GÍN KÙ.BABBAR a-na 2 m[a-na]
- 2. SÍG.ZA.GÌN.KUR.RA *a-[na]*
- 3.  $^{\text{md}}$ U+GUR-TIN $^{i}[^{t}$  A-šú šá]
- 4. <sup>m</sup>*It-ti-ma*-[*ku*-DINGIR]
- 5. lúUŠ.BAR *bir*-[*mu* SUM<sup>in</sup>]

Rev.

6. ITI.AB U[4.KAM]

MU.30.KA[M ....] 7.

Rest lost

Ll. 3-4. Both persons were already known as išpar birme (see Bongenaar, Ebabbar, p. 328

2 shekels of silver for 2 mi[nas] of blue-purple wool was given to Nergal-uballi[t, son of] Itti-ma[kû-ilī], the multicol[oured] weaver. Month of Ṭebētu, [n<sup>th</sup> day], 30<sup>th</sup> year [of Nebuchadnezzar<sup>?</sup> ....].

and 339), but our text makes it possible to establish their family connection.

# **513. BM 62420** (82-9-18, 2389)

 $5.4 \times 3.8$  cm

#### Achemenid

- 1. 1/3 ma-na 8 GÍN SÍG.ZA.GÌN.<KUR>.RA
- 2. a-na ku-lu-lu šá <sup>d</sup>UTU
- 3. ù <sup>d</sup>Bu-ne-ne šá ITI.APIN
- 4. 6 GÍN 4-tú SÍG.ZA.GÌN.<KUR>.RA
- 5. a-na lu-bar-ri šá <sup>d</sup>UTU
- 6.  $[x x x]^{\lceil x \rceil} ^d UTU$

Rest lost

1'. LUGAL E<sup>ki</sup> LUGAL KUR.KUR<sup>meš</sup> Rev.

28 shekels of blue-purple wool for the (lubār) kulūlu-headbands for Šamaš and Bunene for the month of Arahsamna;

6 ¼ shekels of blue-purple wool for the *lubāru*-garment for Šamaš.

[....] Šamaš

[....], king of Babylon, king of Lands.

# **514. BM 62213** (82-9-18, 2182)

PLATE 122

 $3.8 \times 4.0 \text{ cm}$ 

- 1. [x G]ÍN SÍG.ZA.GÌN.KUR.RA šá LUGAL
- 2. [a-na TÚG.ḤI.A k]u-lu-lu šá <sup>d</sup>UTU
- 3. [x GÍN] a-na TÚG.HI.A ku-lu-lu
- 4. [šá <sup>d</sup>GAŠAN] UD.KIB.NUN<sup>ki</sup>
- 5. [6 GÍN SÍ]G.ZA.GÌN.KUR.RA <<br/>a-na> TÚG. 「ḤI¹.A ku-lu-lu
- 6.  $\lceil \check{s} \acute{a} \rceil$  <sup>d</sup>Bu- $\lceil ne \rceil$ - $\lceil ne \rceil$
- 7. [x *ma-n*]*a*<sup>?</sup> 6 [GÍN SÍG.ZA.GÌN.KUR.RA *a-na* ....]

Edge 8. [šá <sup>d</sup>GAŠA]N Sip-par<sup>k[i]</sup>

Rev. uninscribed

- L. 1. takiltu ša šarri "royal blue-purple wool" is mentioned here for the first time. It is difficult to say if it describes a high quality of wool, or simply that king delivered wool for the garments of the chief god of Sippar.
- L. 7. The numeral 6 is preceded with one vertical stroke. The Queen of Sippar is mentioned two times probably because wool was delivered separately for manufacturing two different garments.

[x shek]els of royal blue-purple wool [for the *lubār k*]*ūlulu*-headband for Šamaš.

[x shekels] for the *lubār kulūlu*-headband for the [Queen] of Sippar.

[6 shekels] of blue-purple wool for the *lubār kulūlu*-headband for Bune[ne].

[x min]a<sup>?</sup> 6 [shekels blue-purple wool for [....] for Que]en of Sippar.

# **515. BM 73113** (82-9-8, 13123)

 $6.1 \times 3.9$  cm

Obv<sup>?</sup> 1'. [x] <sup>r</sup>ma-na<sup>1</sup> [SÍG.ZA]. <sup>r</sup>GÌN.KUR.RA KI<sup>2</sup><sup>1</sup>. [LAL ....]

2'. 5 2/3 ma-na ta-bar-r[i] [x] [...]

3'. [5] ma-na 15 GÍN ta-[kil-ti

4'. 59 GÍN *ta-bar-ri* [....]

5'. [x] <sup>r</sup>ma-na<sup>1</sup> KI.LAL TÚG.BAR.DUL<sub>8</sub> S[ÍG.ḤÉ.ME.DA]

6'. [x] GÍN SÍG.ZA.GÌN.KUR.R[A ....]

### Rest lost

Rev.

- 1'. [....]  $^{\text{rd}}$ GAŠAN UD.K[IB $^{?}$ .NUN $^{\text{ki}}$
- 2'. [x] GÍN SÍG.ZA.GÌN.KUR.RA KI.LAL 'TÚG.ḤI'.[A
- 3'. 12 GÍN ta-bar-ri KI.LAL TÚG.HI.A ku-lu-lu [
- 4'. 1/3 7 GÍN SÍG.ZA.GÌN.KUR.RA KI.LAL TÚG.ḤI.A me-ṭ[u
- 5'. 1 ma-na 4 GÍN ta-bar-ri KI.LAL TÚG.ḤI.A [
- 6'. [....] <sup>[</sup>x<sup>]</sup> *ri* <sup>[</sup>x<sup>]</sup> *šá* <sup>d</sup>*Ša-la*
- 7'. [.... GÍ]N KI.LAL TÚG.ÍB.LÁ.M[EŠ?

### Rest lost

[x] mina(s) of [bl]ue-purple wool, the wei[ght of ....] 5 minas 40 shekels of red wool [....]

```
5 minas 15 shekels of blu[e-purple wool ....]
59 shekels of red wool [....]
[x] minas, the weight of the r[ed] kusītu-robe (and) [x] shekels of blue-purple wool
[....] of the Queen of Sip[par ....]
[x] shekels of blue-purple wool, the weight of the lub\bar{a}[r...]
12 shekels of red wool, the weight of the lubār kulūlu-headband [....]
27 shekels of blue-purple wool, the weight of the lubār mēt[u-headband ....]
1 mina 4 shekels of red wool, the weight of the lubār [....]
[....] for Šala
[x minas x sh]ekels, the weight of sashes [....].
```

# **516. BM 62003** (82-9-18, 1972)

 $3.9 \times 2.8$  cm

# [x].12b.[KN x]

- 1. 1/3 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. *a-na* <sup>túg</sup>na-ḫal-ap-tu<sub>4</sub> bir-[mu] 3. šá <sup>d</sup>A-a a-na <sup>m</sup> DUB¹-[NUMUN A-šú] 4. 「šá¹ <sup>md</sup>UTU-ŠEŠ-MU [....]
- 5. *šá* ITI.ŠE.KIN.KUD [....]

### Rest lost

A very thin fragment broken off from the larger tablet.

Šāpik-zēri/Šamaš-aḥ-iddin, the *išpar birmi* and the *ṣāpû*, see Bongenaar, *Ebabbar*, pp. 349f. and Zawadzki, Garments of the Gods, Vol. I, p. 230f.

20 shekels of blue-purple wool for the multico[loured] nahlaptu-cloak for Aya, [was given to] Šāpik-zēri, son of Šamaš-aḥ-iddin [....] of the month Addaru II [....].

# XVII. Texts concerning dying and dying materials

**517. BM 59990** (82-7-14, 4400)

 $4.5 \times 2.8$  cm

27.12.Nbn 2+

- 1. 1 *ma-na* <sup>г na4</sup>gab-ú<sup>1</sup>
- 2. a-na a-di-la-nu šá
- 3. ku-si-tu4  $š\acute{a}$  <sup>d</sup>A-a
- 4. a-na <sup>m</sup>DUB-NUMUN A-šú [šá]
- 5. [<sup>md</sup>]'[UTU]-[ŠEŠ-MU] [SUM]<sup>in</sup>
  6. ITI.ŠE U<sub>4</sub>.27.KAM MU.'<sup>2</sup>]+[x.KAM]

Rev.

- 7. [md][AG-I] [LUGAL TIN.TIRki]

The rest of the tablet is lost, but most probably it was uninscribed.

1 talent of alum for 2 adilānu-tassel? for the robe for Aya was given to Šāpik-zēri, son [of] Šamaš-[aḥ-iddin].

Month of Addaru, 27<sup>th</sup> day of the 2+[x] year of Nabonidus, [king of Babylon].

### **518. BM 66460** (82-9-18,6453)

PLATE 123

 $3.7 \times 2.7$  cm

# 10.7.Nb[n] 3

- 1. 1 GÚ.[U]N SÍG.ḤI.A i-na
- 2. sat-tuk <sup>r</sup>šá¹ ITI.APIN MU.2.KAM
- 3. <sup>m</sup>Ba-la-ṭu A <sup>md</sup>AG-EN-MU.MEŠ
- 4. lúUŠ.BAR SUM<sup>in</sup>
- 5. 5 ma-na SÍG.HI.A a-na
- 6. şi-i-pu šá TÚG. GÚ UD. DU

Edge

7. šá <sup>d</sup>A-a a-na

- 8.  $^{\rm m}$ DUB-NUMUN A-šú šá
- 9. <sup>md</sup>UTU-ŠEŠ-MU
- 10. [SU]M<sup>in</sup> ITI.DU<sub>6</sub>
- 11. 「U<sub>4</sub><sup>1</sup>.10.KAM MU.3.KAM
- 12. <sup>m</sup><sup>rd</sup>AG¹-[I LUGAL] 「E¹<sup>ki</sup>
- L. 6. For *ṣīpu*, see Tawil 2009, p. 317.

1 talent of wool from the regular offering of the month Arahsamna of the 2<sup>nd</sup> year, was given (to) Balāṭu, son of Nabû-bēl-šumāti, the weaver.

5 minas of wool for dying for *nahlaptu*-cloak of Aya, was given to Šāpik-zēri, son of Šamaš-aḥ-iddin.

Month of Tašrītu, 10<sup>th</sup> day, 3<sup>rd</sup> year of Nabo[nidus, king of] Babylon.

## **519. BM 79352** (Bu. 89-4-26, 649)

**PLATE 123** 

 $4.3 \times 3.2$  cm

#### 16.1.Nbn 4

- 1. 7 ma-na 1/3 GÍN
- 2. in-za-hu-ri-e-tu<sub>4</sub>
- 3. a-na 3 5/6 ma-na
- 4. ta-bar-ri a-na
- 5. TÚG.ÍB.LÁ.<MEŠ> šá <sup>d</sup>UTU
- 6.  $[u]^{d}Bu$ -ne-ne

Rev.

- 7. [a]-na <sup>m</sup>DUB-NUMUN
- 8. SUM<sup>in</sup> ITI.BÁR
- 9.  $\mathrm{U}_4.16.\mathrm{KAM}$  MU.4. $\mathrm{KAM}$  10.  $^{\mathrm{md}}$  AG-I LUGAL TIN.TIR $^{\mathrm{ki}}$

#### L. 3. na is written over KÙ.BABBAR.

7 minas 20 shekels of inzahurētu-dye for 3 minas 50 shekels of red wool for the *nēbeḥu*-belts of Šamaš [and] Bunene was given to Šāpik-zēri. Month of Nisannu, 16<sup>th</sup> day, 4<sup>th</sup> year of Nabonidus, king of Babylon.

## **520. BM 73111** (82-9-18, 13121)

PLATE 124

 $3.9 \times 5.4$  cm

### 28.4.Nbn 4

- 1. 2 ma-na <sup>[</sup>10 x x x x <sup>]</sup>
- 2. a-na 1 GÚ.UN 5/6 ma-na <sup>[5]</sup> [GÍN]
- 3. in-za-hu-ri-e-tu4 a-na
- 4. <sup>m</sup>EN-KAR-<sup>d</sup>AG S[UM<sup>in</sup>]
- 5. 15 ma-na 1/3 5 GÍN in-za-h[u-ri-e-tu<sub>4</sub>]
- 6. [ina] IGI-šú ri-hi 5/6 ma-na [in-za-hu-ri-e-tu4]
- 7. [ina] É.ŠU<sup>ii</sup> šá-kin

Edge

8. 4 ½ GÍN [KÙ].BABBAR [ir]-[bi]

9. šá É <sup>d</sup>Gu-la Rev.

- 10. ITI.ŠU U<sub>4</sub>.28.KAM MU.4.KAM
- 11. md AG-IM.TUKU LUGAL TIN.TIR ki
- L. 1. The most probable filling of the gap would be 10[+x<sup>?</sup> GÍN KÙ.BABBAR].

Although lines 1–7 probably concern the same case, the text is incoherent. Probably after ri-hi the scribe forgot to write 45 ma-na, however, 1 talent 55 shekels minus 15 minas 25 shekels gives 45 minas 30 shekels, not <45 minas> 50 shekels.

2 minas 10 [shekels of silver<sup>?</sup>] for 1 talent 5<sup>f</sup>9<sup>1</sup> [shekels] of *inzaḥurētu*-dye was given to Bēl-ēţir-Nabû.

15 minas 25 shekels of inzahurētu-dye was in his disposal; the remnant 50 shekels [of inzahurētu-dye] was placed in the storehouse.

4 ½ shekels of silver (is) the ir[bu]-income of the temple of Gula. Month of Du'ūzu,  $28^{th}$  day,  $4^{th}$  year of Nabonidus, king of Babylon.

### **521. CT 55, 348** = BM 56518

### 25.1.Nbn <sup>[5]</sup>

- 1. 18 ma-na in-za-hu-<sup>r</sup>ri-tu<sub>4</sub><sup>1</sup>
- 2. a-na sa-pi-e
- 3. šá na-ah-lap-tu<sub>4</sub> a-na
- 4. <sup>m</sup>DUB-NUMUN <sup>lú</sup>UŠ.BAR
- 5. na-din ITI.BÁR

Rev.

6. U<sub>4</sub>.25.KAM MU.<sup>r</sup>5<sup>1</sup>.KAM 7. <sup>md</sup>AG-IM.TUKU LUGAL E<sup>ki</sup>

18 minas of inzahurītu-dye for dying of the nahlaptu-cloak was given to Šāpik-zēri, the weaver.

Month of Nisannu, 25<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, king of Babylon.

#### **522. CT 55, 356** = BM 56347

# [x.x].Nbn[x]

- 1. [x ma]-na in-za-hu- $\Gamma ri$ -tu<sub>4</sub>
- 2. [a-na] ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a
- 3. [a-na] <sup>m</sup>DUB-NUMUN A-šú šá 4. [<sup>md</sup>UTU-ŠEŠ-MU <sup>lú</sup>UŠ.BAR bir-mu
- 5.  $[SUM^i]^{n?}$

Rest of Obv. Lost

Rev.

- 1'. [ITI.x U<sub>4</sub>]. [x]. [KA]M
- 2. [MU.x].KAM <sup>md</sup>AG-I 3. [LUGAL TI]N.TIR<sup>ki</sup>

[x mi]na(s) of inzahurītu-dye [for] (dying) the robe of Aya [was give]n [to] Šāpik-zēri, son of Šamaš-aḥ-iddin, the multicoloured weaver. [....]

[Month x, n<sup>th</sup> day, n<sup>th</sup> year] of Nabonidus, [king of B]abylon.

### **523. CT 55, 357** = BM 56173

#### 6.[x].Nbn [x]

- 1. [x m]a-na in-za-hu-ri-tú
- 2. [a-na ku]-si-tu<sub>4</sub> SÍG.HÉ.ME.DA
- 3. [šá <sup>d</sup>A]-a a-na <sup>m</sup>DUB-NUMUN 4. [A-šú šá <sup>md</sup>]UTU-ŠEŠ-MU SUM<sup>in</sup>
- 5. [ITI.x] U<sub>4</sub>.6.KAM
- 6. [MU.x.KAM <sup>m</sup>]<sup>d</sup>AG-I 7. [LUGAL TI]N.TIR<sup>ki</sup>

[x mi]na(s) of inzahurītu-dye [for] red robe of Aya was given to Šāpik-zēri, [son of] Šamaš-aḥ-iddin.

[Month x], 6<sup>th</sup> day, [n<sup>th</sup> year of] Nabonidus, [king of] Babylon.

#### **524. BM 59642** (82-7-14, 4052)

PLATE 124

 $4.2 \times 3.8$  cm

#### 20.1.Nbn 7

- 1. [x] *ma-na* 10 GÍN
- 2. [in]-[za]-hu-ri-e- $t\acute{u}$
- 3. [a]-na dul-lu šá ITI.GU<sub>4</sub>
- 4. [a]-na a-da-la-nu
- 5.  $\check{s}\acute{a}$  ku-si-tu<sub>4</sub>  $\check{s}\acute{a}$   ${}^dA$ -a  $\{x\}$
- 6. *a-na* <sup>m</sup>DUB-NUMUN SUM<sup>in</sup>

Edge

7. erased

Rev.

- 8. [a]-na <sup>m</sup>DUB-NUMUN SUM<sup>in</sup>(sic!)
- 9. [IT]I.BÁR U<sub>4</sub>.20.KAM
- 10. MU.7.KAM <sup>md</sup>AG-I
- 11. LUGAL TIN.TIR<sup>ki</sup>
- L. 6. Šāpik-zēri/Šamaš-aḥ-iddin, see Bongenaar, Ebabbar, pp. 301f. and 349ff. and Zawadzki, Garments of the Gods, Vol. I, p. 230f.
- L. 8, just like l. 7, was written by mistake, but is not erased.

x mina(s) 10 shekels of inzahurētu-dye for the work of the month of Ayaru for *adilānu*-tassel<sup>?</sup> of the robe of Aya was given to Šāpik-zēri. Month of Nisannu, 20<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

# **525. CT 55, 353** = BM 56205

### 15.1.Nbn 7

- 1. [x ma]-na in-za-hu-ri- $t[u_4]$
- 2. [x m]a-na <sup>na4</sup>gab-bu-ú
- 3. a-na pa-tin-na-a-tu<sub>4</sub>

- 4. *a-na* <sup>m</sup>*Mu-šal-li-[mu]* 「SUM<sup>in</sup>
- 5. 20 GÍN KÙ.BABBAR [x] [x] [x]

6. a-na <sup>m</sup>Mu-šal-li-mu 7. [SUM<sup>in?</sup> x ma-na <sup>na4</sup>ga]b-bu-ú Rev.

8. 4 ma-na in-za-hu-ri-tu<sub>4</sub>

9. a-na 2 ma-na ṭì-mi-tu<sub>4</sub> 10. šá É <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

11. <sup>m</sup>DUB-NUMUN [A-šú šá <sup>md</sup>]UTU-ŠEŠ-MU

12. [ITI].BÁR [U<sub>4</sub>].15.KAM MU.7.KAM

13. [mdAG]-I LUGAL Eki

[x mi]na(s) of inzahurētu-dye, [x mi]na(s) of alum for (dying?) of the patinnu-belts was given to Mušalli[mu].

20 shekels of silver [.... was given] to Mušallimu

[x minas of a]lum (and) 4 minas of inzahurētu-dye for (dying?) of 2 minas of thread for (the garments) for the chapel of the Queen of Sippar (was given to) Šāpik-zēri, [son of] Šamaš-aḥ-iddin. [Month] of Nisannu, 15<sup>th</sup> [day], 7<sup>th</sup> year of [Nabo]nidus, king of Babylon.

### **526. BM 63522** (82-9-18, 3489)

#### [x].8.[Nbn] 8

- 1. 6 ma-na in-za-hu-ri-[e-tu4] 2. 3 ma-na  $^{na4}g[ab$ -bu- $\acute{u}]$
- 3. *a-na și-pi* [*šá* .... *a-na*]
- 4. <sup>m</sup>*Ri-ḥi-*[*e-tú* ....]
- 5. 「SUM¬[<sup>in</sup>]
- Rev.
- 6. ITI.APIN U<sub>4</sub>.[x.KAM] 7. MU 8.KAM $^{\text{m}^{\text{rd}}}$ [AG-I]
  - 8. LUGAL E<sup>ki</sup>
- L. 7. Rēhētu, the išpar birme and ēpišānu of Aḥḥē-iddin-Marduk, see Bongenaar, Ebabbar, p. 340f. and Zawadzki, Garments of the Gods, Vol. I, p. 224, active from Nbn 7 till Cam 4.

6 minas of inzahur[ētu]-dye, 3 minas of a[lum] for the dyeing [of ....] was given [to] Rēhē[tu, the ....].

Month of Arahsamnu, [n<sup>th</sup>] day, 6<sup>th</sup> year of [Nabonidus], king of Babylon.

# **527. BM 62962** (82-9-18, 2931)

**PLATE 125** 

 $4.0 \times 3.0$  cm

### 20.5.Nbn 9

- 1. 1/3 GÍN SÍG.ZA.GÌN.KU[R.RA]
- 2. *a-na* <sup>m</sup>*Ri-mut-* <sup>d</sup>E[N SUM<sup>na</sup>]
- 3.2 ma-na in-za-hu-[ri-e-tu4]

4. a-na si-pi

Edge

5. šá SÍG.ÙZ!

Rev.

6. a-na <sup>m</sup>Ba-ku-ú-a 7. qal-la <sup>md</sup>AG-EN-MU.M[EŠ]

8. UŠ.BAR SUM<sup>in</sup>

9. ITI.NE U<sub>4</sub>.20.K[AM]

10. MU.<sup>r</sup>9<sup>1</sup>.[KA]M] <sup>md</sup>AG-[I]

11. LUGAL TIN.T[IR<sup>ki</sup>]

L. 2. After mut only a tiny fragment of a sign is preserved, however any other reading seems unlikely; additionally Rēmūt-Bēl, the išpar kitê was active in time of Cyrus and maybe earlier, in time of Nabonidus, see Bongenaar, Ebabbar, p. 341.

20 shekels of blue-purple wool [was given] to Rēmūt-B[ēl].

2 minas of inzahu[rētu-dye] for dying of the goat hair? was given to Bakûa, the slave of Nabû-bēl-šumāti, the weaver. Month of Abu, 20<sup>th</sup> day, 9<sup>th</sup> year of Nabo[nidus], king of Babylon.

#### **528. CT 55, 362** = BM 56390

#### 12.9.Nbn 9

- 1. 4 ½ ma-na <sup>na4</sup>gab-bu-ú
- 2. 9 ma-na in-za-hu-ri-tu<sub>4</sub>
- 3. a-na ni-bi-hu šá <sup>d</sup>UTU
- 4. ina ITI.GU<sub>4</sub> MU.10.KAM
- 5. a-na <sup>m</sup>DUB-NUMUN A-šú šá
- 6. <sup>md</sup>UTU-ŠEŠ-MU *na-<din>*

Rev.

- 7. ITI.GAN U<sub>4</sub>.12.KAM
- 8. MU.9.KAM <sup>md</sup>AG-I
- 9. LUGAL TIN.TIR<sup>ki</sup>
- 4 ½ minas of alum, 9 minas of *inzaḫurītu*-dye for (dying) the  $n\bar{e}behu$ -belt of Šamaš for the month Ayaru,  $10^{th}$  year, given to Šāpik-zēri, son of Šamaš-aḫ-iddin. Month of Kislīmu,  $12^{th}$  day,  $9^{th}$  year of Nabonidus, king of Babylon.

### **529. CT 55, 363** = BM 56854

1<sup>7</sup>4/5<sup>7</sup>.12.Dar 26

- 1. 3 ma-na <sup>na4</sup>gab-ú
- 2. šá Mi-sir
- 3. 9 ma-na  $[in-za-hu^!-ri^!]-e-t[u]^!$
- 4. a-na TÚG.ÍB.LÁ šá <sup>d</sup>UTU
- 5.  $u^{d}$ HAR  $\check{s}\acute{a}$  ITI.GU<sub>4</sub>
- 6. MU.2[7.KAM a-na]

- 7. <sup>m</sup>AD-Š[EŠ <sup>lú</sup>UŠ.BAR GADA]
- 8. SUM<sup>na</sup> ITI.ŠE U<sub>4</sub>.1<sup>r</sup>4/5<sup>1</sup>.KAM
- 9. MU.26.KAM
- 10. <sup>m</sup>Da-ri-mu-šú
- 11. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

3 minas of the Egyptian alum, 9 minas of inzahurītu-dye for (dying) the nēbehubelts of Šamaš and Bunene for the month Ayaru, the 2[7<sup>th</sup>] year, were given to Abu-u[sur, the linen weaver].

Month of Addaru, 14/15<sup>th</sup> day, 26<sup>th</sup> year of Darius, king of Babylon, king of Lands.

### **530. BM 63048** (82-9-18, 3017)

**PLATE 125** 

 $4.3 \times 3.0$  cm

#### [x].10.Nbn 12

- 1. 「8 *ma-na* <sup>na4</sup>¬*gab-ú*
- 2. a-na 8 ma-na SÍG.HI.A
- 3. <sup>r</sup>a-na<sup>1</sup> și-pi šá ku-si-tu<sub>4</sub>
- 4.  $[\check{s}\check{a}]^{\text{rd}}A$ -a a-na
- 5. [<sup>m</sup>DUB]-<sup>r</sup>NUMUN<sup>1</sup> A <sup>md</sup>UTU-ŠEŠ-[MU]

Rev.

 $SUM^{nu}$ 

- 7. ITI.AB [U<sub>4</sub>.x.KAM] MU.12.<KAM>
- 8. dAG-I LUGAL [TIN.TIR]ki

8 minas of alum for 8 minas of wool for the dyeing of the robe [of] Aya was given to [Šāpik]-zēri, son of Šamaš-ah-[iddin].

Month of Tebētu, [x<sup>th</sup> day], 12<sup>th</sup> year of Nabonidus, king of Babylon.

# **531. BM 72840** (82-9-18, 12848)

PLATE 126

 $4.0 \times 3.1$  cm

### 14.12b.Nbn 12

- 1. 3 ma-na <sup>na4</sup>gab-bu-ú
- 2. šá Mi-sir a-na
- 3. dul-lu šá ni-bi-hu
- 4. šá <sup>d</sup>UTU a-na
- 5. <sup>m</sup>DUB-NUMUN A <sup>md</sup>UTU-ŠEŠ-MU
- $SUM^{na}$

Rev.

- 7. ITI.DIRIG.ŠE.KIN.[KUD]
- 8.  $U_4.14.KAM MU.12.KAM$ 9.  $^{md}AG-I LUGAL TIN.TIR^{ki}$

3 minas of Egyptian alum for manufacturing of the nēbehu-belt of Šamaš, was given to Šāpik-zēri, son of Šamaš-aḥ-iddin.

Month of Addaru II, 14<sup>th</sup> day, 12<sup>th</sup> year of Nabonidus, king of Babylon.

#### **532. CT 55, 367** = BM 56464

- 1. 2 *ma-na* <sup>na4!</sup> *gab-bu-* <sup>г</sup>*ú* <sup>1</sup>
- 2. a-na și-i-pu
- 3. <sup>m</sup>DUB-NUMUN ITI.BÁR
- 4. U<sub>4</sub>.24.KAM MU.3.KAM
- 5. <sup>md</sup>AG-I LUGAL
- 6. LUGALTIN.[TIR<sup>ki</sup>]

2 minas of alum for dying (was given to) Šāpik-zēri. Month of Nisannu, 24<sup>th</sup> day, 3<sup>rd</sup> year of Nabonidus, king of Ba[bylon].

#### **533. BM 83479** (83-1-21, 642)

PLATE 126

 $4.2 \times 4.4 \text{ cm}$ 

#### Nbn

- 1. [x x x] <sup>r</sup>x¹ NÍG.GA <sup>d</sup>UTU
- 2. [ina IGI<sup>? m</sup>R]i-mut-<sup>d</sup>EN DUMU-šú šá
- 3.  $[^{m}NUMUN-\dot{u}]^{-1}tu^{1}A^{m}MU^{-d}U+GUR$
- 4. [ina lìb-bi] <sup>[20]</sup> ma-na <SÍG>.ZA.GÌN.KUR.RA
- 5. [x hu-ra-t]u<sub>4</sub> 1 GÚ.UN in-za-hur-ri-e-<sup>Γ</sup>tú<sup>7</sup>
- 6. [a-na É-babbar]-<sup>r</sup>ra<sup>¬</sup> i-nam-din
- 7. [ina GUB-zu md]EN-ŠEŠ.MEŠ-BAšá Rev.
  - 8. [lúTIL.LA.GÍD].DA É-babbar-ra

  - 9. [<sup>m</sup>Mu-še-zib-<sup>d</sup>ŠÚ] <sup>lú</sup>SANGA Sip-par<sup>ki</sup> 10. [<sup>lú</sup>mu-kin-nu <sup>m</sup>]<sup>d</sup>AG-MU-SI.SÁ A-šú šá 11. [<sup>m</sup>TIN-su A <sup>l</sup>]<sup>ú</sup>SANGA <sup>d</sup>Ištar TIN.TIR<sup>ki</sup>

  - 16. [ITI.x U<sub>4</sub>.x].KAM MU.12.KAM
- 17. [mdAG-IM.TUK]U LUGAL TIN.TIRki L. e.
- L. 3. The reconstruction of the name of Zērūtu was based on the comparison with BM 64895: 2-3. Concerning the other persons, cf. index of personal names in Bongenaar, Ebabbar.

[x minas of silver]?, the property of Šamaš, [at disposal? of Rē]mūt-Bēl, son of [Zērū]tu, descendant of Iddin-Nergal. [Of these] 20 minas of blue-purple wool, [x (minas) of \( \bar{y}\tilde{u}ra\)]tu-dye, 1 talent of \( inza\bar{y}ur\tilde{e}tu\)-dye he will deliver [to the Ebabb]ar temple.

[In the presence of] Bēl-ahhē-iqīša, [the  $q\bar{t}$ ]pu of the Ebabbar (and) [Mušēzib-Marduk], the *šangû* of Sippar.

[Witnesses are]: Nabû-šum-līšir, son of [Balassu, descendant] of the šangû Ištar-

[Bēl-apal-id]din, son of Balīhu, descendant of the šangû of Sippar

[Bēl-uballit], son of Kiribtu, descendant of the šangû of Sippar;

[and the scribe Šamaš-tab]ni-uşur, son of Erība-Marduk, [descendant of the šangû Ištar-Bāb]ili.

Sippar, [month x], 12<sup>th</sup> year of [Nabo]nidus, king of Babylon.

### **534. BM 63899** = Bertin 1552 Collated

#### 22.5.Nbn 14

- 1. 1 ma-na KÙ.BABBAR <sup>m</sup>DUB-NUMUN
- 2. A-*šú šá* <sup>md</sup>UTU-ŠEŠ-MU *a-na*
- 3. 2 ½ GÚ.UN *hu-ra-tu*<sub>4</sub>
- 4. a-na ṣa-pi-e šá TÚG.KUR.RA.MEŠ
- 5. SUM<sup>in</sup> ITI.NE

6. U<sub>4</sub>.22.KAM MU.14.[KAM] 7.  $^{\rm md}$ AG-I LUGAL TIN.TIR $^{\rm ki}$ Edge Rev.

It seems that the scribe wrote the text in the wrong order, i. e. the personal name should be placed at the beginning of l. 5.

1 mina of silver for 2 ½ talents of hūratu-dye for dyeing of TÚG.KUR.RAgarments was given to Šāpik-zēri, son of Šamaš-aḫ-iddin. Month of Abu,  $22^{nd}$  day,  $14^{th}$  year of Nabonidus, king of Babylon.

#### **535. BM 63912** = Bertin 1584 Collated

 $5.4 \times 4.1$  cm

#### 16.5.Nbn 15

- 1. 「1 ½ ma-na in-za-hu-ri-e-tu4
- 2. a-na 1 ma-na <sup>síg</sup>ta-bar-ri
- 3. šá SAG<sup>?</sup> šá ITI.KIN ù
- 4. 5/6 ma-na 5 GÍN ți-me-tu<sub>4</sub>
- 5. šá <sup>gada</sup>pi-šá-an-ni <a-na> <sup>m</sup>Ba-ku-ú-a {x} (expected: SUM)
- 6. 52 GÍN in-za-hu-ri-e-tu<sub>4</sub>
- 7. 1/3 ma-na 2 GÍN <sup>na4</sup>ga-bu-u 8. a-na TÚG SAG<sup>?</sup> šá <sup>d</sup>UTU a-na

Rev.

- 9. <sup>md</sup>HAR-*ši-man-ni* SUM<sup>na</sup>
- 10. ITI.NE U<sub>4</sub>.16.KAM MU.15.KAM
- 11. [m]dAG-I LUGAL TIN.TIRki

- L. 1. The numeral is partly broken and it seems that the amount of inzahurētu dye is really too much for dyeing only 2 ½ mina of wool (about 1,25 kg).
- L. 3 and 8. The suggested reading is unsure, however TÚG.SAG in l. 8 could be compared with lubuštu SAG of VS 6, 16 (= 15): 4, 8 and with TÚG SAG (cf. the list in commentary to 1. 4 of Cyr 241 (= 229).
- 1 ½ minas of inzahurētu-dye for (dying of) 1 mina of red wool of SAG garment? for the month of Ulūlu and 55 shekels of yarn for the bag (was given to) Bakûa. 52 shekels of inzahurētu-dye, 22 shekels of alum for (dyeing) of SAG-garment for Šamaš was given to Bunene-šimanni. Month of Abu, 16<sup>th</sup> day, 15<sup>th</sup> year of Nabonidus, king of Babylon.

#### **536. BM 63941** = Bertin 1593 Collated

#### 13.8.Nbn 15

- 1. 2 ma-na in-za-ḫu-ri-e-tú
- 2. 1 ma-na <sup>na4</sup>gab-bu-ú
- 3. 1 ma-na SÍG.HI.A a-na
- 4. *și-i-pi šá* GADA ḤU.PAP<sup>meš</sup>
- 5. [šá] ú-ri-gal-la šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>
- 6.  $\Gamma^{d_{1}}A$ -nu-ni-tu<sub>4</sub>

Rev.

- 7. *a-na* <sup>m</sup>DUB-NUMUN <sup>lú</sup>UŠ.BAR
- 8. SUM ITI.APIN U<sub>4</sub>.13.KAM
- 9. MU.15.KAM <sup>d</sup>AG-I
- 10. LUGAL TIN.TIR<sup>ki</sup>
- L. 4. The Akkadian reading of the HU.PAP is not known. Prof. E. Leichty kindly inform me that the same logogram appears also in other texts mentioned in A.L. Oppenheim' unpublished compendium concerning the material culture of the Neo-Babylonian time.
- L. 5. Concerning the urigallu in the Neo-Babylonian Uruk, see Beaulieu, The Pantheon of Uruk, p. 353f.
- 2 minas of inzahurētu-dye, 1 mina of alum, 1 mina of wool for the dyeing of the linen HU.PAP [of] the urigallu-standard of the Queen of-Sippar-(of) Anunītu-(ša-Sippar-Anunītu) were given to Šāpik-zēri, the weaver. Month of Araḥsamna, 13<sup>th</sup> day, 15<sup>th</sup> year of Nabonidus, king of Babylon.

**537. BM 79348** (Bu 89-4-26, 645)

PLATE 127

 $4.3 \times 2.9$  cm

#### 27.[x].Nbn [x]

- 1. [2] ma-na in-za-hur-ru-tu4
- 2. 1 ma-na <sup>na4</sup>gab-bu-ú
- 3. [x ma-na] ta-bar-ri a-na
- 4. na-hal-lap-tu<sub>4</sub> šá <sup>d</sup>A-a

- 5. *a-na* <sup>m</sup>DUB-NUMUN <sup>lú</sup>UŠ.BAR
- 6. bir-ri SUM<sup>na</sup>

- 7. 「ITI.x.<sup>1</sup> U<sub>4</sub>.27.KAM
- 8. M[U.x.KAM] <sup>d</sup>AG-I 9. LUGAL <sup>r</sup>TIN.TIR<sup>1ki</sup>

2 minas of inzaḥurētu-dye, 1 mina of alum, [x mina(s)] of red (wool) for (dying of) the nahlaptu-cloak of Aya were given to Šāpik-zēri, the multicoloured weaver. Month of [x1, 27<sup>th</sup> day, [n<sup>th</sup>] year of Nabonidus, king of Babylon.

#### **538.** Nbn **1061** = BM 60351; cf. NUVI 3, No. 98 Collated

#### 18.1.Nbn [x]

- 1. 7 GÍN KÙ.BABBAR er-bi a-na [...
- 2.  $^{\text{na4}}gab$ -bu-u  $^{\text{r}}\dot{u}$  [x GÍN KÙ.BABBAR a-na x x x] 3.  $^{\text{na4}}gab$ -bu-u a-na [si-pi]

- 4. šá TÚG.ḤI.A šá <sup>d</sup>A-<sup>r</sup>nu<sup>1</sup>-ni-t[u<sub>4</sub>] 5. ku\*-sa\*-a\*-tú\* ù\* <sup>túg</sup>\*na-[aḥ-lap-tu<sub>4</sub>]
- 6. šá <sup>d</sup>MÍ:DUMU.MEŠ *É-babbar*!(T: kur)-[*ra*]
- 7. a-na <sup>m</sup>DUB-NUMUN SUM<sup>in</sup>

Rev.

- 8. ITI.BÁR U<sub>4</sub>.18.KAM MU[.x.KAM]
- md AG-I LUGAL TIN.TIR<sup>k[i]</sup>

7 shekels of silver, the income for [....] alum and [x shekels of silver for ....] alum for [dying] of the *lubāru*-garment of Anunītu, the robes and the *na*[*hlaptu*]-cloaks for the Daughters of the Ebabbar, was given to Šāpik-zēri. Month of Nisannu, 18<sup>th</sup> day, [n<sup>th</sup>] year of Nabonidus, king of Babylon.

### **539. BM 54922** (82-5-22, 1252)

 $3.1 \times 3.1 \text{ cm}$ 

# 10+x.8.[Nbn x]

- 1. [x *m*]*a-na* <sup>na4</sup>*gab-bu-ú*
- 2. [x ma]-na in-zah-hu-ri-e-tú
- 3. [a-na] si-pi šá ta-bar-ri
- 4. [šá ku-s]i-tu<sub>4</sub> šá <sup>d</sup>A-a 5. [a-na] <sup>md</sup>AG-NUMUN A-šú šá
- 6. [mdA]G-ŠEŠ-MU SUM<sup>[na]</sup>

Rev.

- 7. [ITI.AP]IN  $U_4.10+[x.KAM]$
- 8. [MU.x.KAM KN]
- 9. [LUGAL] TIN.TIR<sup>ki</sup>
- L. 5. Nabû-zēri/Nabû-ah-iddin is attested here for the first time.
- L. 7. The month APIN is suggested because two vertical wedges are preserved.

[x mi]nas of alum, [x mi]nas of inzahurētu-dye were given to Nabû-zēri, son of [Na]bû-aḥḥē-iddin for dying of red wool for the robe of Aya. Month of Araḥsamna, day 10+[x, n<sup>th</sup> year of KN, king of] Babylon.

```
540. BM 83668 (83-1-21, 831)
3.3 \times 3.5 cm
                         24.[x].Nbn 14
              1. [x ma-na] SÍG.HI.A
             2. [x ma-na] in-za-hu-ri-tu
             3. [x ma-na] <sup>na4</sup>gab-bu-u
             4. [a-na TÚG.NÍG.Í]B.LÁ šá
             5. [{}^{d}A-nu]-ni-tu_4 šá
             6. [a-na lu-bu]-uš-tu<sub>4</sub> šá
             7. [U<sub>4</sub>.3.KAM šá IT]I.KIN
             8. [(x x x)^m]Ba-ku-\acute{u}-a
Rev.
             9. [<sup>lú</sup>UŠ.BAR SUM]<sup>Γna</sup>]
```

12. [md AG-I LUG]AL Eki

[x minas] of wool, [x minas] of  $inzahur\bar{e}tu$ -dye, [x minas] of alum [for sash]es of [Anu]nītu [for the lubu] $\check{s}tu$  ceremony [of the  $3^{rd}$  day of the mon]th Ulūlu [were giv]en [to ....] Bakûa, [the weaver ....]. [Month of x], 24<sup>th</sup> day, 14<sup>th</sup> year of [Nabonidus, ki]ng of Babylon.

**541. BM 62149** (82-9-18, 2118)

PLATE 127

 $4.1 \times 4.2 \text{ cm}$ 

### [time of Nbn]

11. [ITI.x U<sub>4</sub>].2<sup>r</sup>4<sup>1</sup>.KAM MU.14.KAM

- 1.  $[x]+ 5/6 \ ma-na \ ^{rna4} gab-ú^1 [a-na ....]$
- 2. šá <sup>d</sup>UTU u <sup>d</sup>ḤAR <sup>m</sup>DUB-NUMUN <sup>l</sup>[<sup>ú</sup>ṣa-pu-ú ....]
- 3. [x+] 1 ma-na in-za- ${}^{\Gamma}hu$ -ri-tu4 ${}^{\Gamma}[....]$
- 4. šá <sup>d</sup>A-a <sup>m</sup>DUB-NUM[UN ....]
- 5. [x m]a-na <sup>na4</sup>gab-bu-ú [....] 6. a-na ku-si-tu<sub>4</sub> šá <sup>d</sup>A-<sup>r</sup>a<sup>1</sup> [....]
- 7.  $[x(x)]^{na4}gab-\acute{u} a-na\{1\}$  si-pu[...]
- 8. [x(x)] in-za-hu-ri-tu<sub>4</sub> a-na [x] [....]
- 9. [šá] <sup>d</sup>GAŠAN Sip-par<sup>ki</sup>

Rev. completely eroded

[x]+50 shekels of alum [for ....] of Šamaš and Bunene, Šāpik-zēri, the [dyer<sup>?</sup>] [x]+1 mina of inzahurētu-dye [....] of Aya, Šāpik-zē[ri

[x m]ina(s) of alum [....] for the robe of Aya [....] [...] of alum for dying [....] inzahurētu-dye for [.... of] the Queen of Sippar.

#### **542. BM 61805** (82-9-18, 1774)

 $3.8 \times 4.6$  cm

#### Nbn

- 1. [x] GÍN KÙ.BABBAR ir-bi
- 2. [dul]-lu ta-bar-ri
- 3.  $[\check{s}\check{a}^? na-h]al-lap-tu_4 \check{s}\check{a}^dA-a$
- 4. [šá U<sub>4</sub>.x+]2.KAM (one sign erased)
- 5. [x (x)] *ta-kil-tu*<sub>4</sub>
- 6.  $[x(x)]^{md}AG-PAP$

Rest lost

Rev.

The preserved beginning is uniscribed

- 1'. 「U<sub>4</sub>?.10<sup>?</sup>1.KAM
- 2'. 「MU<sup>?</sup>.x.KAM<sup>1</sup> dAG-I
- 3'. LUGAL E<sup>ki</sup>
- [x] shekels of silver, the irbu-income (for) [the wor]k with red wool [for the nah]laptu-cloak for Aya [for the x]+2 [day] [....] of the blue-purple [....] Nabû-nāṣir [....]
- [....] 10<sup>th</sup> day, [n<sup>th</sup>] year of Nabonidus, king of Babylon.

### **543. BM 65341** (82-9-18, 5326)

PLATE 128

 $5.2 \times 3.9$  cm

# (Time of Nabonidus?)

- 1. [....]
- 2. [....]  $\check{s}\check{a}^{\mathsf{d}}[A]$ - $\lceil a^{\dagger} \mid \grave{u} \rceil$ 3.  $\lceil {}^{\mathsf{d}}B \rceil u$ -ne-ne
- 4. [x m]a-na a-na a-di-la-[nu]
- 5. [šá] ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a
- 6. PAP 1 ma-na 5 GÍN SÍG.ZA.GÌN.KUR.RA

Rev.

- 7. [a]-<sup>r</sup>na<sup>1 m</sup>Ba-ku-ú-a 8. <sup>lú</sup>qal-la šá <sup>md</sup>AG-PAP-A SUM<sup>nu</sup>
- 9. [1/2] *ma-na* SÍG.[HI.A] *a-na*

- 10. [x x x] šá <sup>d</sup>[UTU] 11. [a- na <sup>md</sup> x x]-MU 12. [SUM<sup>in</sup>] [x x] <sup>r</sup>x x]
- 13. broken.

[....] for 「Aya [and] Bunene

[x] mina for tassel? of the robe of Aya, total 1 mina 5 shekels of blue-purple wool was given to Bakûa, the slave of Nabû-nāṣir-apli.

½ mina of wool for [....] of Šamaš was given to [x x]-iddin [....].

#### **544. BM 60803** (82-9-18, 779) = Str. II 387/3 Collated

 $5.1 \times 3.8$  cm

#### 18.1.4

- 1. 1 ma-na 18 GÍN <sup>síg</sup>ți-me
- 2. šá pi-šá-an-ni a-na si\*-pi
- 3. ina IGI <sup>m</sup>Gi-mil-lu 15 GÍN KÙ.BABBAR
- 4. *a-na in-za-ḥur-ri-tu*<sub>4</sub> <sup>na4</sup> *gab-bu-ú*
- 5. a-na dul-lu šá ITI.GU₄ ina ŠU<sup>ii</sup>
- 6.  $[^mG]i$ -mil-lu  $\check{s}u$ -bu-lu
- 7. [PAP 2<sup>?</sup> ma-na] ½ 6 GÍN
- 8. [in-za-hu-ri-tú] 1 ma-na 18 GÍN

Rev.

- 9.  $\lceil^{\text{na4}}*\rceil$  [gab-bu]-ú a-na
- 10. și-pi šá ți\*-me šá
- 11. pi-šá-Гап<sup>¬</sup>-ni SUM<sup>na</sup>
- 12. ITI.BÁR U<sub>4</sub>.18.KAM
- 13. MU.4.KAM (one sign erased)

Cf. Bongenaar, Ebabbar, p. 327, who suggested dating the text to the time Cyrus' or Cambyses' reign.

The reconstruction of 11. 7–8 is based on the observation that the proportion between inzahurētu and alum is usually 2:1.

L. 6. In Strassmaier' copy the beginning of the line is still preserved.

1 mina 18 shekels of yarn for dyeing of the pišannu-bag (given) at disposal of Gimillu.

15 shekels of silver for inzahurētu-dye (and) alum for the work of the month Ayaru was sent through Gimillu, [total 2 minas] 36 shekels [of inzahurētu-dye] (and) 1 mina 18 shekels of alum for dyeing of yarn for the bag was given. Month of Nisannu,  $18^{\rm th}$  day,  $4^{\rm th}$  year.

## **545. BM 83408** (83-1-21, 571)

1'. [....]  $^{r}ir^{?}$ Obv.

2'. [....].RA 3'. [....]

4'. [....] GÍN *in-za-*[*hu*]-[*ri-tú*]

Rest lost

- 1. [a]-na <sup>m</sup>DUB-NUMUN A <sup>md</sup>UTU-[ŠEŠ-MU]
- 2. [SUM]<sup>in</sup> 3 ma-na SÍG.HI.A
- 3. [a]-na și-pi šá GIŠ.GU.ZA
- 4. [a]-na <sup>m</sup>DUB-NUMUN SUM<sup>in</sup>
- 5. [IT]I.DU<sub>6</sub> U<sub>4</sub>.28.KAM MU.<sup>7</sup>5<sup>7</sup>.KA[M]

#### Rest lost

- [....] shekels of inzahurētu-dye [....]
- [....] was given to Šāpik-zēri, son of Šamaš-[ah-iddin].

3 minas of wool for the dying of the throne cloths was given to Šāpik-zēri. [Mon]th of Tašrītu, 28<sup>th</sup> day, 5<sup>th?</sup> year [...

### **546. BM 84381** (83-1-21, 1544)

 $3.8 \times 3.5$  cm

### 18.12b.Cyr 6

- 1. 3 *ma-na* KI.LAL *t*[*i-mu*]
- 2. *šá* TÚG.ÍB.LÁ *šá* <sup>rd</sup><sup>1</sup>[DN]
- 3. 8 ma-na SÍG.HI.A hal-și [....]
- 4. *šá* <sup>rtúg</sup>*ṣib*<sup>1</sup>-*tu*<sub>4</sub> *šá* <sup>d</sup>[DN]
- 5. a-na <sup>r</sup>ṣi<sup>¬</sup>-pi ina IGI [<sup>m</sup>Gi-mil-lu]
- 6. A- $\lceil \check{s}\check{u}^{?_1} \rceil \check{s}\check{a}^{m}$ DU]B-NUMUN  $\langle SUM^{in} \rangle$

Edge Rev.

- 7. ITI.DIRIG.[ŠE.K]IN.KUD
- 8. U<sub>4</sub>.18.[KAM] MU.6.[KAM]
  - 9. <sup>m</sup>Kur-raš LUGAL E.[KI]
  - 10. LUGAL KUR.KUR

3 minas, the weight of y[arn] for  $n\bar{e}behu$ -belt of the god [x],

8 minas of combed wool for the sibtu-garment of the god [x] for dyeing <was given> at disposal of [Gimillu<sup>?</sup>], son of [Sāp]ik-zēri. Month Addaru II, 18<sup>th</sup> day, 6<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

### **547. BM 64013** = Bertin 1884

### 23.11.Cam 0

- 1. 19 ma-na dul-lu KI.LAL
- 2. is-hu-un-ni-e 17 ma-na
- 3. dul-lu KI.LAL şu-ub-ba-as
- 4. <sup>m</sup>Gi-mil-lu <sup>lú</sup>UŠ.BAR bir-mu
- 5. it-ta-din ITI.ZÍZ
- 6. U<sub>4</sub>.23.KAM MU.SAG.

Edge

- 7. NAM.LUGAL.LÁ <sup>m</sup>Kam-bu-zi-iá
- 8. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

- 9. 20 ma-na in-za-hu-ri-tu<sub>4</sub>
- 10. 8 ma-na <sup>na4</sup>ga-bu-ú
- 11. a-na și-pi šá ku-si-tu<sub>4</sub>
- 12. a-na <sup>m</sup>Gi-mil-lu SUM<sup>na</sup>

19 minas (of wool for) work, the weight of ishunnūs

17 minas (of wool for) work, the weight of the textile, Gimillu, the multicoloured weaver has delivered.

Month of Šabatu, 23<sup>rd</sup> day, the accession year of Cambyses, king of Babylon, king

20 minas of inzahurētu-dye, 8 minas of alum for the dying of the robe were given to Gimillu.

### **548. BM 59003** (82-7-14, 3412)

 $4.9 \times 3.4$  cm

#### 1<sup>r</sup>2<sup>7</sup>.12.Cam 1

- 1. [x] ma-na [SÍG.ḤI.A]
- 2. *a-na și-i-pi šá* [*lu*]-*bu-*[*uš-tu*<sub>4</sub>]
- 3. šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> a-na
- 4. <sup>m</sup>Ri-hi-<sup>r</sup>e<sup>1</sup>-tú e-pi-šá-nu šá
- 5. <sup>m</sup>ŠEŠ.MEŠ-MŪ-<sup>d</sup>AMAR.UTU [SUM<sup>na</sup>]
- 6. *šá e-lat* [....]

Rev.

- 7. ITI.ŠE U<sub>4</sub>.1<sup>r</sup>2<sup>1</sup>.KAM MU.<sup>r</sup>1<sup>1</sup>.KAM
- 8. <sup>m</sup>Kám-bu-zi-ja LUGAL E<sup>ki</sup>
- 9. LUGAL KUR.KUR
- L. 2. lubuštu might also be understood not as a ceremony, but as a general description of the goddess's attire.
- L. 4. Bongenaar, Ebabbar, p. 243, where this line is cited.
- [x] mina(s) [of wool] for dying (the garments) for the [lu]bu[štu] ceremony of Anunītu [was given] to Rēhētu, the performer of Ahhē-iddin-Marduk. Except

Month of Addaru, 12<sup>th</sup> day, 1<sup>st</sup> year of Cambyses, king of Babylon, king of Lands.

### **549. BM 74484** = Bertin 1817 Collated

#### 3.1.Cam 4

- 1. in-za- $\hbar u$ - $^{\Gamma}ri$ 1-tu4  $^{na4}gab$ -bu- $\acute{u}$ 2.  $\check{s}\acute{a}$   $\check{s}i$ -pi SUM $^{nu}$  ITI.BÁR U<sub>4</sub>.3.<KAM>
- 3. MU.4.KAM <sup>m</sup>Kam-bu-zi-iá LUGAL TIN.TIR<sup>ki</sup>
- LUGAL KUR.KUR

- 5. 20 ma-na in-za-hu-ri-tu<sub>4</sub>
- 6.  $8 < ma-na > {}^{na4}gab-bu-\acute{u}$  EN IGI- $\acute{u}$
- 7. a-na și-pi šá ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a SUM
- 8. 5 ma-na in-za-hu-ri-tu<sub>4</sub>
- 9. 2 ½ ma-na <sup>na4</sup>gab-bu-ú

10. a-di IGI-ú a-na a-di-lu meš

- 11. šá ku-si-tu<sub>4</sub> šá <sup>d</sup>A-a
- 12. mGi-mil-lu SUMnu
- 13. ina lìb-bi 1 ma-na in-za-hu-ri-tu<sub>4</sub>
  - 4. *ri-i*

The *inzaḥurētu*-dye (and) alum for dying are delivered. Month of Nisannu, 3<sup>rd</sup> day, 4<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

20 minas of *inzaḥurētu*-dye (and) 8 (minas) of alum, including the previous (issue) for the dying of the robe of Aya was given.

5 minas of *inzahurētu*-dye (and) 2 ½ minas of alum, including the previous (issue) for the dying of tassel? of the robe of Aya were given to Gimillu; including 1 mina of *inzahurētu*-dye, the rest.

**550. BM 69003** (82-9-18, 9002) cf. Lorenz No. 51 5.7 × 4.0 cm

PLATE 129

# 19.7. Nbk 0 (522 B.C.)

- 1. <sup>[2/3]</sup> 6 ½ GÍN KÙ.BABBAR *a-na*
- 2. [x +]1 ma-na in-za-hu-ri-tu<sub>4</sub>
- 3. [a-n]a <sup>md</sup>AG-KAR-<sup>r</sup>ZI<sup>1</sup>.MEŠ
- 4. [A-šú šá <sup>m</sup>]Ni-qu-du SUM
- 5. [x G]ÍN KÙ.BÂBBAR 4-tú a-na
- 6. [x ma-n]a <sup>na4</sup>gab-bu-ú šá 「Mi-ṣir<sup>¬</sup>
- 7.  $[a-na^{? m}]^d$ AG-MU-Ù[RU]

#### Rest lost

Rev.

- 1'.  $[x (x)] ^{\mathsf{T}} x x^{\mathsf{T}} [....]$
- 2'.  $[SUM]^{r^{nu_1}}$  ITI.DU $_6$  U $_4$ .20.1.LAL.KAM
- 3'. [MU.SA]G.NAM.LUGAL.LA
- 4'. [ $^{d}$ AG-NÍ]G.DU-ÙRU LUGAL TIN.TIR $^{ki}$  LUGAL KUR.KUR
- 5'. [1/3] GÍN KÙ.BABBAR a-na 1 ga-an-du
- 6'. ha-[ru]-tú KÙ a-na md AG-MU-PAP SUM
- 7'. 「½」 ma-na KÙ.BABBAR a-na 12 ½ ma-na {「KÙ.BABBAR」} in-za-ḥu-ri-tú
- L. e. 8'. *a-na* <sup>m</sup>*Gi-mil-lu* 
  - 9'. A <sup>m</sup>DUB-NUMUN SUM

Many signs are written over erasures, i.e. *an* in the word *ga-an-du* (rev. 5'), *na* in rev. 6' and ½ *ma-na* in rev. 8' (followed by the erased KÙ.BABBAR). The mistakes in simple signs suggest that the text might be a copy by a young apprentice.

Rev. 5'. gandu may be a by-form of kandu (kind suggestion of M. Jursa).

Rev. 9'-10'. For Gimillu, son of Šāpik-zēri, see Bongenaar, *Ebabbar*, pp. 326–327. Add to the list also Nbn 1: 12, 22 (18.3. Nbn 0). In the light of the previously known texts the activity of Gimillu lasted between 556–526 BC; for this reason BM 69003 has to be dated to the time of Nebuchadnezzar IV, i.e. 521 BC and such dating was already established by Lorenz.

46 ½ shekels of silver for [x]+ 1 minas of *inzahurētu*-dye, was given to Nabû-ēţirnapšāti, [son of]? Niqūdu

[x+] ¼ shekels of silver for [x minas] of Egyptian alum was given [to] Nabû-šum-uṣ[ur].

[....] was given. Month of Tašrītu, 19<sup>th</sup> day, [the ac]cession year of Nebuchadnezzar, king of Babylon, king of Lands.

[x]+ 1/3 shekel of silver for 1 *kandu*-jar (and?) pure *ḫarūtu*? was given to Nabû-šum-uşur;

½ mina of silver for 12 ½ minas of *inzaḫurētu*-dye was delivered to Gimillu, son of Šāpik-zēri.

#### **551. BM 66061** (82-9-18, 6052)

PLATE 130

 $4.8 \times 4.0$  cm

```
19.3.Dar (5<sup>?</sup>)
```

- 1'. [....]-<sup>r</sup>na<sup>1</sup> ITI.GU<sub>4</sub> [....]
- 2'. ½ ma-na 6 GÍN KÙ.BABBAR a-na h[u-rat?!]
- 3'. a-na și-pi šá gab-bu-šú
- 4'. a-na  $\stackrel{\text{r}}{\sim}$  Ri-hi- $tu_4$   $SUM^{na}$
- 5'. e-lat 1 GÚ.UN 5 ma-na hu-rat
- 6'. maḥ-ri-tú šá a-na <sup>m</sup>Ri-ḥi-tu<sub>4</sub> SUM<sup>[na]</sup>
- 7'. ITI. GU<sub>4</sub> MU.5.KAM
- 8'. [x] GÍN KÙ.BABBAR 3 (PI) 2 BÁN 「ŠE.BAR」 [....]
- 9'. [*a-n*]*a* <sup>md</sup>[UTU-MU]-[MU<sup>?</sup>]

Rest of obv. lost

Rev.

- 1'. [....] sib- $t[u_4$  ....]
- 2'. [....] [x] a-na ni-[....]
- 3'.  $\lceil x x x^{1} ki \text{ SUM } \lceil .... \rceil$
- 4'. ITI. SIG<sub>4</sub> U<sub>4</sub>.20.1.LAL.KAM M[U].<sup>75</sup><sup>?1</sup>.[KAM]
- 5'. <sup>rm</sup>Da-ri<sup>¬</sup>-mu-šú LUGAL KUR.KUR
- L. 3'. The sequence of words and the lack of determinative before *gabbu* seem to exclude the possibility that alum is meant here.

Rev. 3'. The first sign in the line seems to be LUGAL, but such a reading does not help to reconstruct this fragment.

#### [.... f]or the month Ayaru [.....]

36 shekels of silver for  $h[\bar{u}ratu$ -dye<sup>?</sup>] for dying of all his (garments<sup>?</sup>) was given to Rēhētu; (this is) except for 1 talent 5 minas of  $h\bar{u}ratu$ -dye of earlier issue, which

was given to Rēhētu; month Ayaru, 5<sup>th</sup> year.

[x] shekels of silver (and) 3 (pi) 2 sūtu of barley [was given t]o Šamaš-šum-[iddin<sup>?</sup>....]

[...] sibtu-garment<sup>?</sup> [....] for  $n\bar{e}[behu^2]$  ....] was given. Month Simanu,  $19^{th}$  day,  $r_5^{th?_1}$  ye[ar] of Darius, king of Lands.

#### **552. CT 55, 828** = BM 55727

#### 8.2.Nbn 12

- 1. 10 GÍN SÍG.ZA.GÍN.KUR.RA
- 2. *a-na pa-ni* [*m*]*u-și-e*
- 3. šá <sup>d</sup>UTU a-na <sup>m</sup>Ri-hi-tu<sub>4</sub>
- 4. na-din

Edge 5. ITI.GU<sub>4</sub> U<sub>4</sub>.8.KAM

Rev. 6. MU.12.KAM <sup>d</sup>AG-I

7. LUGAL E<sup>ki</sup>

L. 2. The *pan muṣê* appears also in Nbn 664:4 (11.11.Nbn 12).

10 shekels of blue-purple wool for pan muṣê-cover? of Šamaš was given

Month of Kislīmu, 8<sup>th</sup> day, 12<sup>th</sup> year of Nabonidus, king of Babylon.

# **553. BM 63922** = Bertin 1490 Collated

### 29.5.Nbn 12

- 1. 1/3 GÍN <sup>síg</sup>ta-kil-tu<sub>4</sub>
- 2. šá a-na pa-ni mu-uṣ-ṣi-e
- 3. šá <sup>d</sup>UTU a-na <sup>m</sup>Ri-hi-e-ti
- 4. lúUŠ.BAR bir-mu SUM<sup>na</sup>
- 5. ITI.NE U<sub>4</sub>.29.KAM

6. MU.12.KAM [<sup>md</sup>A]G-I] Edge

LUGAL TIN.TIR<sup>ki</sup> Rev.

20 shekels of blue-purple wool for pan muşê-cover? of Šamaš was given to Rēhētu, the multicoloured weaver. Month of Abu, 29<sup>th</sup> day, 12<sup>th</sup> year of Nabonidus, king of Babylon.

# **554. BM 64099** (82-9-18, 4068) = Bertin 2665 Collated

# 5.5 Dar 29

- 1. 1 ma-na 10 GÍN in-šá-hur-ri-tu<sub>4</sub>
- 2. ½ ma-na <sup>na4</sup>gab-bu-ú

- 3. a-na dul-lu šá pa-ni mu-și-e
- 4. šá <sup>d</sup>UTU a-na <sup>m</sup>AD-ÙRU
- 5. lúUŠ.BAR *bir-ri* SUM<sup>na</sup>
- 6. ITI.NE U<sub>4</sub>.5.KAM
- 7. MU.29. KAM

8. <sup>m</sup>Da-ri-muš

9. LUGAL E<sup>ki</sup> LUGAL KUR.KUR<sup>meš</sup>

Abu-uşur, full name Abu-šar-uşur, see Zawadzki, Garments of the Gods, Vol. I, p. 208.

1 mina 10 shekels of *inzahurētu*-dye,  $\frac{1}{2}$  mina of alum for the work (of dyeing) of *pan muṣê*-cover<sup>?</sup> of Šamaš were given to Abu-uṣur, the multicoloured weaver. Month of Abu,  $5^{th}$  day,  $29^{th}$  year of Darius, king of Babylon, king of Lands.

### **555. BM 65772** (82-9-18, 5762)

 $7.5 \times 4.5$  cm

- 1'. [....] 「NE<sup>1</sup>
- 2'. [.... S]ÍG.ZA.GÌN.<KUR>.RA pap-pa-su-šú
- 3'. PAP x] *ma-na* 3 GÍN SÍG.ḤÉ.ME.DA *ù* SÍG.ZA.GÌN.<KUR>.RA
- 4'. [....] 4 GÍN SÍG.ZA.GÌN.<KUR>.RA ina lìb-bi $^{\rm md}$ AG-EN-MU.MEŠ ma-hir
- 5'. [....] <sup>r</sup>a¹-na 10 ma-na SÍG.ḤÉ.ME.DA ù SÍG.ZA.GÌN.<KUR>.RA
- 6'. [....] <sup>1</sup>10 GÍN<sup>1</sup> ina lìb-bi (erasured signs)
- 7'. [....] <sup>r</sup>e-piš šá <sup>r</sup>nam<sup>?!</sup>¹
- 8'. [.... md AG]-EN-MU.MEŠ
- 9'. [....] A-*šú šá* <sup>m</sup>Sag-gil-<sup>[</sup>lu<sup>]</sup>
- 10'. [....] <sup>[2</sup> ma-na<sup>[]</sup> [x x]

#### Rest lost

[....] Abu
[....] of blue-purple wool, his prebendary income
[total x mina(s) 3 shekels of red and blue-purple wool, [....] 4 shekels of bluepurple wool except for (that) it was received from Nabû-bēl-šumāti.
[....] for 10 minas of red and blue-purple wool ..... [10 shekels]; out of it [....]
[....] Nabû-bēl-šumāti, [PN], son of Saggilu [....] 2 minas [....].

# XVIII. Texts concerning kitinnû

556. BM 49188; cf. M. Falkner, AfO 16, p. 307, No. 2 and Pl. XV

22.8. Sši 0

- 1. 38 ma-na
- 2. ki-tin-ni-e
- 3. a-na șib-ba-ta
- 4. ina IGI <sup>m</sup>BA<sup>šá</sup>

Rev.

- 5. ITI.APIN U<sub>4</sub>.22.KAM
- 6. MU.SAG.NAM.LUGAL.LA
- 7.  $^{\text{md}}$ 30-LUGAL- $i\check{s}$ -kun
- 8. LUGAL kiš-šat

Here most probably two 2 *şibtus* for Anunītu are meant.

38 minas of *cotton*? for the *sibtu*-garments at disposal of Iqišā. Month of Araḥsamna, 22<sup>nd</sup> day, the accession year of Sîn-šar-iškun, king of the universe.

**557. CT 56, 6** = BM 56240

14.8.<Nbk>30

- 1. 15 ma-na ki-tin-ni-[e]
- 2. a-na  $^{m}Ri-mut-{}^{d}EN$
- 3. A-šú šá  $^{\text{md}}$ EN-TIN $^{it}$  SUM $^{nu}$
- 4. ITI.APIN U<sub>4</sub>.14.KAM
- 5. MU.30.KAM

Rev. uninscribed

Concerning Rēmūt-Bēl/Bēl-uballit, see Bongenaar, Ebabbar, p. 196.

15 minas of  $cotton^?$  was given to Rēmūt-Bēl, son of Bēl-uballiţ. Month of Araḫsamna,  $14^{\rm th}$  day,  $30^{\rm th}$  year.

**558. CT 55, 831** = BM 56765

3.6.<Nbp/Nbk> 14

- 1. 16 ½ ma-na [....]
- 2. ki-tin-ni-e KI.LÁ

- 3. BABBAR.HI.A šá <sup>d</sup>UTU
- 4. šá ina ITI.KIN U<sub>4</sub>.3.[KAM]
- 5. MU.14.KAM

- 6. ul-tu muh-hi
- 7. <sup>d</sup>UTU ú-ri-du

16 ½ minas [(x x)] of  $cotton^{?}$ , the weight of  $lub\bar{a}ru$ -garment for Šamaš, which in the month of Ulūlu,  $3^{rd}$  day,  $14^{th}$  year was taken from Šamaš.

#### **559. BM 79359** (Bu 89-4-26, 656)

PLATE 130

 $4.4 \times 3.4$  cm

#### 11.5.Nbn [x]

- 1. [x] ma-na ki-tin-ni-e
- 2. [a-na] mdEN-LUGAL-bul-lit
- 3. [šá] ŠUKU.HI.A LUGAL SUM<sup>in</sup>
- 4. [I]TI.NE U<sub>4</sub>.11.KAM

Rev.

- 5. [MU.x].KAM 6. [<sup>d</sup>AG-I LUGAL] E<sup>ki</sup>
- L. 3. On ša kurummati šarri see J. MacGinnis 1994, pp. 203f. and Kleber 2008, pp. 295f. For Bēl-šar-bullit, see Appendix A, p. 215, and note 85 in the cited article by MacGinnis. Additional texts are Nbn 401: 7 (9.1.Nbn 10) and maybe Nbn 1043: 4 (5.4.Nbn 17), both cited by Ólafsson and Pedersén 2001, but in the last one the reading of the last element of the name is uncertain. Add GAM 21859 (Ólafsson and O. Pedersén, 2001, No. 13: 3, 14 (18.8.Nbn 7), BM 73296: 5 (14.1.Cyr 3) and BM 100942, rev<sup>2</sup> 5'. Add kitinnû to the list of different commodities issued to peoples receiving ša kurummati šarri composed by MacGinnis 1994, p. 203, Note 32.
- [x] minas of cotton? for Bēl-šar-bullit, in charge of the rations of the king, was

Month of Abu, 11<sup>th</sup> day, [n<sup>th</sup> year of Nabonidus, king] of Babylon.

### **560. BM 64991** (82-9-18, 4972)

**PLATE 131** 

 $4.0 \times 3.1$  cm

# 1.3.Nbn 1

- 1. 3 ma-na ki-tin-ni-e
- 2. *a-na* <sup>md</sup>EN-LUGAL-ŠEŠ
- 3. *šá* ŠUKU.ḤI.A LUGAL SUM<sup>in</sup>
- 4. 2 ma-na 「SÍG¹.HI.A
- 5. ŠUKU.ḤI.A lú qí-i-rpi¹

Edge

- 6. a-na <sup>lú</sup>qí-i-pi

8. ITI.SIG<sub>4</sub> U<sub>4</sub>.1.KAM

9. MU.1.KAM <sup>d</sup>rAG-I<sup>7</sup>

10. LUGAL TIN.TIR<sup>ki</sup>

Except for the texts mentioned by J. MacGinnis 1994, p. 215, Bēl-šar-uşur appears also in GAM 21885 (Ólafsson and O. Pedersén, 2001, No11: 13' (Nbn 1)).

3 minas of *cotton*? for Bēl-šar-uṣur, in charge of the rations of the king 2 minas of wool, the ration of the king's resident was given to the king's resident. Month of Simanu, 1<sup>st</sup> day, 1<sup>st</sup> year of Nabonidus, king of Babylon.

# **561. BM 65041** (82-9-18, 5022)

PLATE 131

 $3.6 \times 2.4$  cm

#### 24.2.Nbn 2

- 1.  $\lceil 5 \rceil$  ma-na ki- $\lceil tin \rceil$ -ni-e
- 2. [K]I.LAL 1<sup>en túg</sup>sib-tu<sub>4</sub>
- 3. *šá la*-IGI <sup>m</sup>TIN <sup>lú</sup>UŠ.BAR
- 4. na-šá-<sup>Γ</sup>a' ina IGI
- 5. <sup>m</sup>Ar-rab-bi <sup>lú</sup>T[ÚG.KAL.KA]L

Edge 6. pa

6. paq-qid ITI.ŠU

Rev.

7. U<sub>4</sub>.24.KAM MU.2.KAM

8. <sup>d</sup>AG-I LUGAL E<sup>ki</sup>

Balāṭu, *išpāru*, see Bongenaar, *Ebabbar*, pp. 320f. Arrabi, *mukabbû*, see Bongenaar, *Ebabbar*, p. 317.

5 minas of *cotton*<sup>2</sup>, the weight of 1 *şibtu*-garment, which was withdrawn from Balāṭu, the weaver (and) entrusted to Arrabi, the m[ender]. Month of Du'ūzu, 24<sup>th</sup> day, 2<sup>nd</sup> year of Nabonidus, king of Babylon.

## **562. BM 67964** (82-9-18, 7962)

**PLATE 132** 

 $3.8 \times 2.8$  cm

#### 5.7.Nbn 3

- 1. [1/3 5 [GÍN x x]-nu
- 2. a-na gú-ḥal-ṣi-e-ti
- 3. šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 4. *a-na* <sup>m</sup>*Ba-la-*<sup>[</sup>*tu*]
- 5. lúUŠ.BAR SUM<sup>[in</sup>]

Edge Rev. 6. ITI.DU<sub>6</sub> U<sub>4</sub>.5.KAM

7. MU.3.KAM <sup>d</sup>AG-I

8. LUGAL TIN.TIR<sup>ki</sup>

L. 1. Only tiny badly preserved remnants of two signs before nu are preserved, rather not ki-tin, maybe tu and ma.

25 shekels of [....] for guḥaṣṣu-thread for (the garments) of Anunītu was given to Balāţu, the weaver.

Month of Tašrītu, 5<sup>th</sup> day, 3<sup>rd</sup> year of Nabonidus, king of Babylon.

#### **563. BM 60842** (82-9-18, 818)

**PLATE 132** 

 $4.3 \times 3.2$  cm

[x]+4.5.Nbn 7

- 1. 2 ma-na ki-tin-ni-e
- 2. e-lat 1 ma-na IGI-ú-tú
- 3. *a-na* <sup>md</sup>AG-ŠEŠ.MEŠ-GI
- 4. A-šú šá <sup>m</sup>Ap-la-a
- 5. ina pap-pa-[s]i-šú SUM<sup>in</sup>

Rev.

- 6. ITI.<sup>r</sup>NE<sup>1</sup> [U<sub>4</sub>.x+] 4.KAM 7. MU.7.KAM <sup>md</sup>AG-I 8. LUGAL TIN.TIR<sup>ki</sup>

Nabû-ahhē-šullim/Apla, the brewer, see Bongenaar, Ebabbar, p. 221.

2 minas of cotton?, except for 1 mina of an earlier (issue) was given to Nabû-aḥhēšullim, son of Aplā from his prebendary income. Month of Abu, day [x]+4, 7<sup>th</sup> year of Nabonidus, king of Babylon.

#### **564. BM 100893** (83-1-21, 2554)

 $4.0 \times 3.4 \text{ cm}$ 

8.[x].Nbn[x]

- 1. [x ma-na x] GÍN ki-tin-ni-e
- 2. [šá <sup>md</sup>AG-ŠE]Š.MEŠ-GI
- 3. [A-šú šá  $^{\rm m}$ ]  $^{\rm l}Ap^{\rm l}$ -la-a ina pap-pa-su-šú 4. [a]-na  $^{\rm md}$ EN-TIN $^{it}$
- 5. [A-šú šá <sup>m</sup>K]i-rib-tu<sub>4</sub>

Rest lost

Rev.

- 1'. [x  ${}^{m}Ni$ ]- ${}^{r}din^{\gamma}-tu_4$
- 2'.  $[x \times x]^{\lceil x]}^{md}UTU-DA$
- 3'. [ITI.x U<sub>4</sub>]. [8]. KAM
- 4'. [MU.x.KAM] <sup>md</sup>AG-I
- 5'. [LUGAL TIN.TIR]<sup>ki</sup>

Nabû-aḥḥē-šullim/Aplā, the brewer, see Bongenaar, Ebabbar, p. 221.

[x mina(s) x] shekels of cotton?, which [Nabû-aḥh]ē-šullim, [son of] Aplā, from his prebendary income [has given t]o Bēl-uballit, [son of K]iribtu. [.... Ni]dintu [....] Šamaš-ile'i. [Month x,] 8<sup>th</sup> [day, n<sup>th</sup> year of] Nabonidus, [king of Babyl]on.

### **564a. BM 60937** (82-9-18, 913)

 $4.1 \times 3.0$  cm

#### 26.1.Nbn 5

- 1. 5 GÍN KÙ.BABBAR TA ir-bi šá KÁ
- 2. 10 GÚ.UN [SÍG].ḤI.A TA É ŠU<sup>ii</sup>
- 3.  $[x \times x \ ki]$ -tin-ni-e
- 4. [x x x G]I i-di a-na
- 5.  $[x \times x]^{-1}ja^{1}$  GAL bat-qa
- 6.  $[x \times x]^m Kal-ba-a$
- 7. [x x x se]-pi-ri SUM $^{in}$

Kalbā, the sēpiru appears in BM 79670: 9.

5 shekels of silver, the income of the gate (and) 10 talents of wool from the  $b\bar{t}t$ qāti-storehouse, [x x x of] cotton? [....-ušall]im, the payment for [.....]-ja, the rab batqa [....] Kalbā [...., the alp]habetic scribe was given.

#### **565. Nbn 291** = BM 75683

### 1.3.Nbn 8

- 1. 5 ma-na ki-tin-ni-e
- 2. a-na 1 GÍN KÙ.BABBAR
- 3. mdUTU-NUMUN-GÁLši
- 4. ITI.SIG<sub>4</sub> U<sub>4</sub>.1.KAM
- 5. MU.8.KAM <sup>md</sup>AG-I 6. LUGAL TIN.TIR<sup>ki</sup>

Rev.

5 minas of *cotton*? for 1 shekel of silver (for?) Šamaš-zēr-ušabši. Month of Simanu, 1<sup>st</sup> day, 8<sup>th</sup> year of Nabonidus, king of Babylon.

# **566. BM 69861** (82-9-18, 9861)

 $3.9 \times 3.1$  cm

**PLATE 133** 

- 18.9.Nbn 8
- 1. 1 ma-na 50 GÍN
- 2. <sup>r</sup>ki<sup>¬</sup>-tin-ni-e ina pa-ni
- 3. [mdA]G-ŠEŠ.MEŠ-GI

4. ma-hi-ir ITI.GAN

5. U<sub>4</sub>.18.KAM MU.8.KAM

6. md AG-I Rev.

7. [LUGAL TIN].TIR<sup>ki</sup>

1 mina 50 shekels of *cotton*? was received by Nabû-aḫḫē-šullim. Month of Kislīmu, 18<sup>th</sup> day, 8<sup>th</sup> year of Nabonidus, king of Babylon.

### **567. CT 56, 3** = BM 56833

## 9.2.Nbn 8

- 1. 1 5/6 ma-na ki-tin-ni-e
- 2. ŠÁM 1<sup>en</sup> UDU.NÍTA
- 3. šá a-na <sup>lú</sup>um-man-nu
- 4. SUM<sup>na</sup> a-na
- 5. md UTU-DU-IBILA

Edge

6. SUM<sup>na</sup> ITI.GU<sub>4</sub>

Rev.

7.  $U_4$ .9.KAM MU.8.KAM 8.  $^d$ AG-I LUGAL TIN.TIR $^{ki}$ 

1 mina 50 shekels of cotton?, the price of one sheep, which is given for the craftsmen, was handed over to Šamaš-mukīn-apli. Month of Ayaru, 9<sup>th</sup> day, 8<sup>th</sup> year of Nabonidus, king of Babylon.

### **568. BM 79346** (Bu 89-4-26, 643)

PLATE 133

 $4.2 \times 2.9$  cm

#### 17.4.Nbn 10

- 1. 5 ma-na 1/3 GÍN ki-tin-ni-e
- 2. TA É.ŠU<sup>ii</sup> ina pap-pa-su
- 3. lúBAPPIR-ú-tu a-na
- 4. <sup>m</sup>*Mu-še-zib-* AMAR.UTU
- 5. A <sup>md</sup>AG-*ni-ip-šá-ri*

SUM<sup>in</sup> Edge

Rev.

7. ITI.ŠU U<sub>4</sub>.17.KAM MU.10.KAM

8. md AG-IM.TUKU LUGAL Eki

L. 4. Mušēzib-Marduk/Nabû-nipšāri, < sirāšu ša Šamaš>, cf. Bongenaar, Ebabbar,

5 minas 20 shekels of cotton? from the bīt qāti-storehouse from the prebendary income of the brewer's prebend was given to Mušēzib-Marduk, son of Nabû-

Month of Du'ūzu, 17<sup>th</sup> day, 10<sup>th</sup> year of Nabonidus, king of Babylon.

## **569. CT 55, 871** = BM 56399 Collated

#### 14.6.Nbn 10

- 1. 1/3 6 ½ 「GÍN¹ [SÍG.HÉ.ME.DA]
- 2. *u* SÍG.ZA.GÌN.KUR.R[A]
- 3. 3 ma-na  $\lceil ki \rceil$ -tin-ni- $\lceil e \rceil$
- 4. [x +] 3 GÍN bit-qa KÙ\*.BABBAR\*
- 5.  $[a-n]a^{\text{md}}\text{EN-}^{\text{\Gamma}}\text{LUGAL}^{1*}-[bul^*]-lit^*$

6. [šá ŠUKU.Ḥ]I\*.A\* LUGAL SUM\*<sup>in\*</sup> Edge

Rev. 7. ITI.KIN U<sub>4</sub>.14.KAM

8. MU.10.KAM <sup>md</sup>AG-I

 $LUGAL \: E^{k[i]}$ 

26 ½ [shekels of red] and blue-purple wool, 3 minas of cotton?, [x]+3 shekels plus 1/8 shekel of silver were given to Bēl-šar-[bul]lit, in charge of the rations of the

Month of Ulūlu, 14<sup>th</sup> day, 10<sup>th</sup> year of Nabonidus, king of Babylon.

#### **570. Nbn 439** = BM 75584

### 20.6b.Nbn 10

- 1. 1 GÚ.UN 9 ma-na ki-<sup>r</sup>tin<sup>?</sup>¹-[ni-e]
- 2. a-na 7 GÍN KÙ.BABBAR ina i-di É.MEŠ
- 3. <sup>m</sup>Na-ṣir u <sup>m</sup>Šu-la-a
- 4. it-tan-nu
- 5. ITI.KIN.2.KAM
- 6. U<sub>4</sub>.20.KAM MU.10.KAM Rev.
  - 7. md AG-I LUGAL Eki

The reading kitinnû was suggested by Bongenaar, Ebabbar, p. 285, who recognized Nāṣir and Šulā as the traders. Here the temple accepted *kitinnû* instead of the due silver for houses rented by Nāṣir and Šulā. Note that the price of kitinnû is here extremely low (more than 9 minas for 1 shekel of silver). Probably both traders needed money and they were persuaded to pay in cotton, although on very hard conditions.

1 talent 9 minas of *cot*[ton]<sup>?</sup> for 7 shekels of silver as the rental of the houses, Nāṣir and Šulā have delivered. Month of Ulūlu II,  $20^{th}$  day,  $10^{th}$  year of Nabonidus, king of Babylon.

#### **571. Nbn 460** = BM 77860 Collated

#### 1.10.Nbn 10

- 1. 4 ma-na ki-tin-ni-e
- 2. a-na muḥ-hi <sup>md</sup>UTU-DÙ

- 3. *u* <sup>m</sup>*fṢil-la-a* A <sup>md</sup>UTU-SU
- 4. 8 ma-na ki-tin-ni-e
- 5. "GI-dAMAR.UTU A "La\*-ba\*-a-ši\*

Edge 6. ina lìb-bi 2 ma-na

7. mdUTU-SU

Rev. 8. ITI.AB U<sub>4</sub>.1.KAM

9. MU.10.KAM <sup>d</sup>AG-I

10. LUGAL E<sup>ki</sup>

Šamaš-ibni and Şillā, see Bongenaar, *Ebabbar*, pp. 176–177, who identified them as the overseers of the bakers in the period Nbn 9-Nbn 15.

Mušallim-Marduk/Lābāši, see Bongenaar, *Ebabbar*, p. 207–208 (the prebendary brewer and the overseer of the brewers together with Sūqaya, active probably from Nbn 6 till Cyr-Cam coregency).

4 minas of cotton? on account of Šamaš-ibni and Sillā, son of Šamaš-erība

8 minas of *cotton*? on account of Mušallim-Marduk, son of Lābāši; out of it 2 minas (for) Šamaš-erība.

Month of Ţebētu, 1<sup>st</sup> day, 10<sup>th</sup> year of Nabonidus, king of Babylon.

# **572. BM 79669** (89-10-14, 218)

PLATE 134

 $4.15 \times 3.2$  cm

#### 18.9.Nbn 10

- 1. 5 ma-na ki-tin-ni-e
- 2. a-na <sup>m</sup>A-zi-ja
- 3. a-na gi-i-di
- 4. SUM<sup>in</sup> ITI.GAN
- $5. U_4.18.KAM MU.10.KAM$

Rev. 6. dAG-I LUGAL TIN.TIR<sup>[ki]</sup>

 $g\bar{\imath}du$  CAD G 66 "sinew of animal" gives no good sense in the content of this text. We expect here a name of a garment or some different product made of  $kitinn\hat{u}$ .

5 minas of  $cotton^{?}$  was given to Aziya for a  $g\bar{\imath}du$ . Month of Kislīmu,  $18^{th}$  day,  $10^{th}$  year of Nabnidus, king of Babylon.

### **573. Nbn 879** = BM 75270

# 11.6.Nbn 15

- 1. 13 ma-na ki-tin-ni-e
- 2. 1 ma-na ta-bar-ri
- 3. a-na șib-tu<sub>4</sub> šá <sup>d</sup>[A-nu-ni-tu<sub>4</sub>]
- 4. šá lu-bu-uš-tu<sub>4</sub> [šá ITI.DU<sub>6</sub>]
- 5. *a-na* <sup>m</sup>*Ba-k*[*u-ú-a* SUM<sup>in</sup>]

# 6. ITI.KIN U4.11.KAM MU.15.KAM 7. $^{md}$ AG-I LUGAL TIN.TIR $^{ki}$ Rev.

L. 3. The reading *şibtu* was established by Bongenaar, *Ebabbar*, p. 319. I suggest to read here Anunītu, because total weight of her kitinnû and tabarri is close to the weight of her şibtu.

13 minas of cotton?, 1 minas of red wool for the *sibtu* garment [of Anunītu] for the lubuštu ceremony [of the month Tašrītu were given] to Bak[ûa]. Month of Ulūlu, 11<sup>th</sup> day, 15<sup>th</sup> year of Nabonidus, king of Babylon.

### **574. Nbn 929** = BM 60767

### 14.11.Nbn 15

- 1. *hi-ši-ih-tu*<sub>4</sub> *šá* <sup>d</sup>*Ištar* GIŠ.TUK
- 2. 2 mi-šil šá TÚG.ḤI.A ki-tin-ni-e
- 3. 1 PI ŠIM šá na-pi-šú
- 4. 10 GÍN KÙ.BABBAR *a-na ḥi-ši-iḥ-tu*<sub>4</sub> 5. *ina* ŠU<sup>ii md</sup>EN-ŠEŠ.MEŠ-BA<sup>šá</sup>
- 6. a-na É <sup>d</sup>Ištar GIŠ.TUK
- 7.  $\it \check{su}$ - $\it bul$  ITI.ZÍZ U $\it _4$ .14.KAM 8. MU.15.KAM  $\it ^{md}$ AG-I LUGAL TIN.TIR $\it ^{ki}$
- L. 5. Bēl-aḥḥē-iqīša, obviously the then *qīpu* of Ebabbar.

Supplies for the temple of Ištar-tašme: 2 ½ lubāru-garment made of cotton?, 1 pānu of aromatics for censer (and) 10 shekels of silver for the needed materials (taken) from Bēl-aḥḥē-iqīša were sent to the temple of Ištar-tašme. Month of Šabatu, 14<sup>th</sup> day, 15<sup>th</sup> year of Nabonidus, king of Babylon.

### **575. CT 56, 5** = BM 57801

(Time of Nabonidus)

Obv. lost

Rev.

- 1. ½ GÚ.UN ki-ti-ni-e
- 2. *šá* 2 *și-ba-tu*<sub>4</sub>
- 3. [šá] <sup>d</sup>A-<nu>-ni-tu<sub>4</sub> 2 ma-na ta-bar-ri
- 4. TA É.ŠU<sup>ii</sup> a-na
- 5. {*a-na*} <sup>m</sup>*Ba-ku-ú-a* 6. *u* <sup>md</sup>AG-*ú-pa-ni-ja* 7. SUM<sup>nu</sup>

½ talent of cotton? for 2 sibtu-garments of Anunītu (and) 2 minas of red wool from the bīt qāti-storehouse was given to Bakûa and Nabû-upnīya.

## **576. CT 55, 798** = **BM** 58186

#### 1.2.Cyr 5

- 1. [x GÍN] KÙ.BABBAR a-na [x x x]
- 2.  $[ki-ti]n-ni-e\ ma-\lceil x\rceil$
- 3. 16 *ma-na ki-tin-*[*ni-e*]
- 4. *a-na* <sup>túg</sup>ṣib-tu<sub>4</sub> šá <sup>d</sup>A-[nu-ni-tu<sub>4</sub>] 5. *a-na* <sup>md</sup>ḤAR-ši-man-ni 6. SUM<sup>in</sup> 4-tú K[Ù.BAB]BAR<sup>?</sup>

Edge

7. [x x] *šá* ŠUKU.ḤI.A [x x]

8.  $\lceil x \rceil \lceil x \rceil \lceil x \rceil - MU \lceil \dots \rceil$ 

Rev.

- 9. ITI.GU<sub>4</sub> U<sub>4</sub>.1.KAM MU.5.KAM
- 10. <sup>m</sup>Ku-ra-áš LUGAL 「E<sup>ki</sup>」

[*u* KUR.KUR<sup>?</sup>]

L. 4. According to Bongenaar, Ebabbar, p. 325 "sibtu for Aya" was mentioned here, but the reading A[nunītu] is justified by the weight of her sibtu (16 minas; see Zawadzki, Garments of the Gods, Vol. I, p. 92).

[x shekels] of silver for [x minas?] of *cotton*? [....]

16 minas of cotton? for the sibtu-garment of A[nunītu] was given to Bunene-

<sup>1</sup>/<sub>4</sub> shekels of silver<sup>?</sup> [....], the ration of [....]-iddin [....]

Month of Ayaru, 1<sup>st</sup> day, 5<sup>th</sup> year of Cyrus, king of Babylon [and Lands].

### **577. BM 79603** (82-9-18, 153)

PLATE 134

 $9.3 \times 5.9$  cm

(27.2.Cam 6)

- 1. ki-tin-ni-e šá i-na MU.6.KAM <sup>m</sup>Kam-bu-zi-ja
- 2. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR *a-na* KÙ.BABBAR
- 3. 41 ma-na ki-tin-ni-e a-na 13 GÍN šu[l-l]u-tu 1 GÍN KÙ.BABBAR
- 4. a-na  $^{md}$ EN-MU A  $^{m}$ TIN SUM $^{na}$  ITI.GU $_4$  U $_4$ .27.KAM
- 5. 20 ma-na ki-tin-ni-e a-na 10 GÍN KÙ.BABBAR a-na
- 6. [mdE]N-it-tan-nu A mNUMUN-a-a SUMna 2/3 ma-na ki-tin-ni-<sup>Γ</sup>e<sup>¬</sup>

- 7. [x ma-na ki]-tin-ni-e a-na 2 PI 3 qa ŠE.GIŠ.Ì  $\lceil x \rceil \lceil x \rceil$
- 8.  $[x \times x \times A]^{m}$ ÎR- $^{d}$ EN SUM $^{na}$  ITI. $[x \times x \times x]$

L. 6. 2/3 ma-na ki-tin-ni-<sup>r</sup>e<sup>1</sup> makes no sense, probably something is missing, i.e. [LAL], "missing" (= not given to the buyer?).

Cotton?, which was sold in the 6th year of Cambyses, king of Babylon, king of

41 minas of  $cotton^{?}$  was sold to Bēl-iddin, son of Balassu for 13 1/3 shekels of silver. Month Ayaru,  $27^{th}$  day.

20 minas of cotton? was sold to Bēl-ittannu, son of Zēriya for 10 shekels;

40 shekels of *cotton*? [....]

[x minas of cot]ton? for 2 pānu 3 qa of sesame [was sold to PN], son of Arad-Bēl. Month [....].

### **577a. CT 56, 4** = BM 56882

#### 19.7.Cam 1 (538 BC)

- 1.  $[x m]a-na^{sig}ki-tin^{1}-ni-e$
- 2.  $[a-n]a^{?}$  7 ma-ši-hu ina ki-is-ki-ri
- 3.  $^{\text{l\'u}}man^{-\text{r}}di\text{-}di\text{ x }\check{s}\check{a}^{?_{1}}\text{ MU.1.KAM}$ 4.  $^{\text{md}}_{\Gamma}\text{x }\text{x }^{\gamma}$   $^{\text{l\'u}}man\text{-}di\text{-}di$
- 5. ITI.DU<sub>6</sub> U<sub>4</sub>.20.1.LAL.KAM

6. MU.1.KAM Edge

7. <sup>m</sup>Kam-bu-zi-ja Rev.

8. LUGAL TIN.TIR<sup>ki</sup>

L. 4. Bongenaar, Ebabbar, p. 292 suggests "with some imagination" the reading Ea-iddin.

[x min]as of cotton? [fo]r? 7 measures as the kiskirru payment of the measurers for the 1<sup>st</sup> year (was given to) [PN], the measurer. Month of Tašrītu, 19<sup>th</sup> day, 1<sup>st</sup> year of Cambyses, king of Babylon.

#### **578.** Cam **30** = BM 60067

#### 4.1.Cam 1

- 1. 1 ma-na ki-tin-ni-e a-<sup>r</sup>na<sup>¬</sup>
- 2. md30-DINGIR A mdUTU-MU
- 3. ina bu-ru-ra-nu šá <sup>[x]</sup>
- 4. SUM<sup>na</sup>
- 5. ITI.BÁR U<sub>4</sub>.4.[KAM]

6. MU.1.KAM Rev.

- 7. <sup>m</sup>Kam-bu-zi-ja
- 8. LUGAL KUR.KUR

1mina of  $cotton^?$  was given to Sîn-ilī, son of Šamaš-iddin ..... Month of Nisannu,  $4^{th}$  day,  $1^{st}$  year of Cambyses, king of Lands.

### **579.** Cam **191** = BM 75968

#### 26.7.Cam 3

- 1. 13 ½ ma-na ki-tin-ni-e
- 2. ina ŠÁM as-ni-e
- 3. a-na <sup>md</sup>EN-KAM <sup>lú</sup>man-d[i-di]
- 4. šá É-sag-íla SUM<sup>na</sup>
- 5. ITI.DU<sub>6</sub> U<sub>4</sub>.26.KAM
- 6. MU.3.KAM

Rev.

7. <sup>m</sup>Kam-bu-zi-ja

8. LUGAL E<sup>ki</sup> LUGAL KUR.KUR

13 ½ minas of cotton? as the price of Dilmun-dates was given to Bēl-ēreš, the measurer of the Esagila temple.

Month of Tašrītu, 26<sup>th</sup> day, 3<sup>rd</sup> day of Cambyses, king of Babylon, king of Lands.

#### **580.** Cam **250** = BM 74875

### 4.8.Cam 4

- 1. 15 2/3 ma-na ki-tin-ni-e
- 2. a-na 5 GÍN šul-lul-ţu KÙ.BABBAR
- 3. *a-na* <sup>m</sup>*Ina-*GIŠ.MI-<sup>d</sup>EN
- 4. ri-hi-tú GU<sub>4</sub> SUR
- 5. ITI.APIN U<sub>4</sub>.4.KAM

#### Rev.

- 6. MU.4.KAM
- 7. <sup>m</sup>Kam-bu-zi-ja
- 8. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

15 minas 40 shekels of cotton? for 5 1/3 shekels of silver is paid to Ina-şilli-Bēl, the

rest (of the price) of cow. Month of Araḥsamna, 4<sup>th</sup> day, 4<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

### **581. BM 64060** = Bertin 2354

 $4.8 \times 3.9$  cm

### 11.6.Dar 16

- 1. <sup>Γ1</sup>⁄<sub>2</sub><sup>?</sup> ma-na ki-tin-ni-e
- 2. KI.LAL 1  $^{en}$  şib-tu $_4$  a-na 3. GIŠ.NÁ šá  $^{d}$ IM a-na

- 4. <sup>m</sup>Eri<sub>4</sub>-ba-a A <sup>m</sup>Lib-<lut> SUM
- 5. ITI.KIN U<sub>4</sub>.11.KAM
- 6. MU.16.KAM <sup>m</sup>Da-ri-muš

7. LUGAL TIN.TIR<sup>ki</sup> Rev.

8. LUGAL KUR.KUR

<sup>1</sup>/<sub>2</sub> mina of cotton<sup>2</sup>, the weight of 1 sibtu-cover for the bed of Adad, was given to Erība, son of Lib<lut>.

Month of Ulūlu, 11<sup>th</sup> day, 16<sup>th</sup> year of Darius, king of Babylon, king of Lands.

#### **582. CT 55, 834** = BM 56864

#### 1.9.Dar 20

- 1. 10 ma-na <sup>síg</sup>ki-tin-nu
- 2. *ul-tu lu-bar-ri šá* <sup>d</sup>UTU
- 3. a-na sib-tu<sub>4</sub> šá GIŠ.NÁ
- 4. šá <sup>d</sup>UTU šá ITI.ZÍZ
- 5. ku-mu SÍG.HI.A a-na
- 6. <sup>m</sup>Su-qa-a-a SUM

Rev.

- 7. ITI.ZÍZ U<sub>4</sub>.1.KAM
- 8. MU.20.KAM <sup>m</sup>Da-ri-ja-muš
- 9. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR<sup>meš</sup>
- L. 1. Note the same writing <sup>síg</sup>ki-tin-nu in CT 55, 753: 3 (2<sup>nd</sup> year of Amēl-Marduk).

10 minas of cotton? from the lubāru-garment of Šamaš for (manufacturing) of the şibtu-cover for the bed of Šamaš was given to Sūqaya instead of wool.

Month of Šabatu, 1<sup>st</sup> day, 20<sup>th</sup> year of Darius, king of Babylon, king of Lands.

### **583. BM 83271** (83-1-21, 434)

**PLATE 135** 

 $4.2 \times 3.1 \text{ cm}$ 

### <->.2. [Nbk] [33]

- 1'. [x ma-n]a ki-tin-ni-e
- 2'. <sup>1</sup>2<sup>1</sup> GÍN SÍG.ZA.GÍN.KUR.RA
- 3'. ina pap-pa-su šá  $^{\rm m}$ TIN-<su> A-šú 4'.  $^{\rm r}$ šá  $^{\rm md}$ AG-EN-MU.MEŠ
- 5'. [SUM]<sup>in</sup> ITI.GU<sub>4</sub>

6'. [U<sub>4</sub>.x.KAM MU].「331.KAM Edge

7'. [dAG-NÍG.DU-ÙRU LUGAL TIN].TIR.K[I] Rev.

- 8'. [2<sup>?</sup>] [....] [x ad<sup>?</sup>]
- 9'. [....] <sup>[</sup>*x*<sup>]</sup> *a-na*
- 10'. [....] 'x' NUN' x KÁ

Rest lost

[x min]a(s) of *cotton*?, 2 shekels of blue-purple wool as the prebendary income of Balas<su>, son of Nabû-bēl-šumāti [was giv]en².

Month Ayaru, [n<sup>th</sup> da]y, <sup>[33] rd</sup> year [of Nebuchadnezzar, king of Bab[ylon ....].

#### **583a. BM 61150** (82-9-18, 1126)

PLATE 136

 $5.0 \times 3.8$  cm

#### 23.2.Dar 25

- 1.  $[x+] 6^{\lceil 1/2 \rceil} [ma]$ -na ki-tin-nu
- 2. [a]-<sup>r</sup>na<sup>1</sup> TÚG.UD.A šá <sup>d</sup>UTU šá ITI.BÁR
- 3. MU.2<sup>5</sup>1.KAM *a-na* <sup>1</sup>12 GÍN 4-tú [*bi*]t-qa
- 4. KÙ.BABBAR BABBAR-ú a-na <sup>m</sup>Ni-din-tu<sub>4</sub>
- 5.  $u^{\text{md}}$ EN-[it-ta]n-nu [SUM $^{na}$ ]
- 6. [x x x] <sup>m</sup>[*Kal-ba*]

Edge

7.  $[x x x x]^{-d}$ AMAR.UTU

Rev.

- 8. A-šú šá <sup>m</sup>Kal-ba-a SUM<sup>na</sup>
- 9. ITI.GU<sub>4</sub> U<sub>4</sub>.23.KAM
- 10. MU.25.KAM
- 11. <sup>m</sup>Da-ri-mu-šú
- 12. LUGAL E<sup>ki</sup> LUGAL KUR.KUR
- L. 1. Maybe [1]6 [1/2].
- L. 4. Nidintu might be identical with one of two Nidintu from the list of textile craftsmen cited in Bongenaar, *Ebabbar*, p. 339 or with one of Nidintu from the list from Zawadzki, *Garments of the Gods*, Vol. I, p. 221.
- L. 5. Bēl-ittannu might be identical with Bēl-ittannu known from the documents cited in Bongenaar, *Ebabbar*, p. 322 or with Bēl-ittannu mentioned in the texts cited in Zawadzki, *Garments of the Gods*, Vol. I, p. 214.
- [x+] 6  $\frac{1}{2}$  minas of  $cotton^{?}$  for the  $lub\bar{a}ru$  garment of Šamaš for the month of Nisannu, 25<sup>th</sup> year for 12  $\frac{3}{8}$  shekels of white silver [was so]ld to Nidintu and Bēl-[ittanu].
- [....], Kalbā [....]-Marduk, son of Kalbā was given.

Month of Ayaru, 23<sup>rd</sup> day, 25<sup>th</sup> year of Darius, king of Babylon, king of Lands.

### **584. BM 71174** (82-9-18, 11176)

PLATE 136

 $3.3 \times 1.8 \text{ cm}$ 

2<sup>r</sup>7.[x].Dar [x]

- 1. [x *ma*]-*na* SÍG.HI.A x x
- 2. [x ma]-na ki-tin-nu a-na

Lost

Rev.

- 1'.[ITI.x] U<sub>4</sub>.2<sup>r</sup>7<sup>1</sup>.K[AM MU.x.KAM]
- 2'. <sup>m</sup>Da-ri-ja-muš
- 3'. LUGAL KUR<sup>meš</sup>

Note that Rev. 3' is written on top obverse.

[x mi]na(s) of wool, [x mi]na(s) of  $cotton^{?}$  for [....] [Month x],  $27^{th}$  day, [n<sup>th</sup> year] of Darius, king of Lands.

## **585. BM 60955** (82-9-18, 931)

PLATE 137

 $4.1 \times 3.1$  cm

#### 21.3.<KN>2

- 1.  $10 \ ma-na^{\text{túg}} ki-tin-ni-\lceil e \rceil$
- 2. *a-na* UGU <sup>m</sup>Sil-la-<sup>r</sup>a<sup>1</sup> [....]
- 3. <sup>m</sup>ŠEŠ.MEŠ-MU ITI.SIG<sub>4</sub>
- 4. U<sub>4</sub>.21.KAM MU.2.KA[M]

-----

Rev. uninscribed

L. 2. At the end of this line a reconstruction  $[A-\check{su}\ \check{sa}]$  or  $[\check{u}]$  is possible. Because Sillāya is a common Babylonian name, the identification of person is impossible. Note that Sil is written over erasure.

10 minas of  $cotton^?$  on account of Şillāya [and/son of] Aḫḫē-iddin. Month Simanu,  $21^{st}$  day,  $2^{nd}$  year.

#### **586. BM 60719** (82-9-18, 692)

PLATE 137

 $7.65 \times 5.7$  cm

- 1. 2 ma-na 50 GÍN ki-tin-ni-e
- 2. 「a¹-na dul-lu šá <sup>d</sup>IM a-na
- 3. [m] Mu-še-zib SUM<sup>na</sup>
- 4. [x ma-n]a KI.LAL BAR.SI
- 5. [.....]

Free space for ca. 2 lines

Rev. 6. [x ma-na SÍG.HÉ].ME.DA KI.LAL 2 <sup>r</sup>ku-lu-lu<sup>1</sup>

- 7.  $[x \ x] \lceil x \rceil [x \ x \ x] \lceil x \rceil$
- 8. 4<sup>r</sup>8<sup>r</sup> GÍN <sup>r</sup>SÍG.HÉ.ME<sup>r</sup>.DA KI.LAL *e-ri*
- 9.  $[\mathbf{x} \mathbf{x} \mathbf{x}]^{-1} \mathbf{u} \mathbf{TUG.BAR.} [\mathbf{SI}^{?}] \check{s} \acute{a} \dot{S} [a^{?} la^{?}]$
- 10. [x] LAL [x x] BABBAR<sup>u</sup> KI [x x] dŠ[a?-la?]
- 11.  $\lceil 1/3^{?_1}$  GÍN KI.LAL [x x x šá  $^{d}$ ] $\lceil IM^{1}$
- 12. 1/3 5 GÍN SÍG.HÉ.ME.DA KI.LAL
- 13. 「TÚG¹.ḤI.A ku-[lu-lu] e-ri u BAR.SI
- L.e. 14. šá <sup>d</sup>Gu-la

It is not certain if l. 4 was followed with l. 5; the only argument for such reconstruction is that the name of god is expected.

L. 3. If Muēzib is identical with Mušēzib/Balāţu, an *išparu* known from Cam 367: 12, our text might be written about the same time.

L. 10. LAL should be preceded with KI, but the preserved part of the sign looks different; additionally the numerals should be at the end of previous line.

L. 11. The first sign looks like written over an erasure.

2 minas 50 shekels of cotton? for the work for Adad was given to Mušēzib.

[x min]a, the weight of paršīgu-headdress

[x] mina of red wool, the weight of 2 < lubār> kulūlu-headbands [for the god ...]

48 shekels of red wool, the weight of the *<lubār> erru*-headbands, [the ....] and  $par[\check{s}\bar{\imath}gu]$ -headdress? for  $\check{S}[ala^?]$ 

[....] of white [...], the we[ight of] x x [for] Š[ala?]

20? shekels, the weight of [.... for] [Adad]

25 shekels of red wool, the weight of the  $lub\bar{a}r$   $kul\bar{u}lu$  (and)  $< lub\bar{a}r> erruheadband$  and  $parš\bar{t}gu$ -headdress for Gula.

# XIX. Silver paid for materials or as payment for the prebendaries

**587. BM 61611** (82-9-18, 1583)

PLATE 138

 $4.2 \times 3.3 \text{ cm}$ 

16.12.<Nbk>41

- 1. 3 GÍN KÙ.BABBAR *ir-[bi]*
- 2. ina ŠU<sup>ii md</sup>EN-tuk-e-<sup>[</sup>tir-ri]
- 3. lú qal-la šá 4. md AG-EN-MU.MEŠ

Rev.

- 5. *a-na* <sup>m</sup>Ba-la-ṭu 6. A <sup>md</sup>AG-EN-MU.MEŠ
- 7. šu-bu-ul
- 8. ITI.ŠE U<sub>4</sub>.16.KAM
- 9. MU.41.KAM

This is the earliest text mentioning Balāṭu/Nabû-bēl-šumāti, see Bongenaar, Ebabbar,

L. 2. mdEN-tuk-e-tir-ri, obviously for Bēl-tuktē-tirri. It is the only mention of this slave of Nabû-bēl-šumāti.

3 shekels of silver, the income, which was brought to Balāţu, son of Nabû-bēlšumāti by Nabû-tuktē-tirri, the slave of Nabû-bēl-šumāti. Month of Addaru, 16<sup>th</sup> day, 41<sup>st</sup> year.

# **588. BM 67013** (82-9-18,7008)

PLATE 138

 $4.6 \times 3.1$  cm

2.10.<Nbk> $^{7}39^{?}_{1}$ 

- 1. [4<sup>?</sup>] GÍN KÙ.BABBAR *a-na* [UGU]
- 2. md AMAR.UTU-KAM lúNAGAR
- 3. ina i-di-šú SUM<sup>na</sup>
- 4. 1/2 GÍN KÙ.BABBAR a-na 3 BÁN ŠE.GIŠ.Ì
- 5. ina pap-pa-su <sup>r</sup>šá<sup>?</sup>¹ a-na

Edge Rev.

- 6.  ${}^{m} \Gamma R i^{?} \Gamma [mut \text{ A-} \check{s} \check{u} \check{s} \check{a}^{m}] \text{BA-} \check{s} \check{a} a \text{ SUM} \Gamma^{nu} \Gamma$
- 7. 1 1/2 GÍN KÙ.BABBAR ir-bi
- 8. a-na  $^{m}Na$ -din  $^{\Gamma}A^{1}$ - $\check{s}\check{u}$ 9.  $\check{s}\check{a}$   $^{md}AG$ -EN-MU.MEŠ SUM $^{nu}$ 1
- 10. ITI.「AB<sup>1</sup> U<sub>4</sub>.2.KAM
- 11. MU.<sup>7</sup>39<sup>?</sup>1.KAM

- L. 2. For Marduk-ēreš, the carpenter, see Bongenaar, *Ebabbar*, p. 402 (active from Nbk 36 till Nbk 39).
- L. 6. Probably Rēmūt/Iqīšā//ṣāḫitu (Bongenaar, *Ebabbar*, p. 281) is mentioned here. For Nādin/Nabû-bēl-šumāti, see Zawadzki, *Garments of the Gods*, Vol. I, p. 223. In light of new collation year 39 seems more probably.
- <sup>7</sup>4<sup>?</sup>1 shekels of silver on [account] of Marduk-ēreš, the carpenter, as his rent was given (to him).

 $\frac{1}{2}$  shekel of silver for 3  $s\bar{u}tu$  of sesame as his? prebendary income was given to Rī[mūt, son of] Iqīšā.

1½ shekel of silver, the income was given to Nādin, son of Nabû-bēl-šumāti. Month Ṭebētu,  $2^{nd}$  day,  $\lceil 39^{?_1}$  year.

### **588a. BM 66096** (82-9-18, 6087)

**PLATE 139** 

 $4.2 \times 3.2 \text{ cm}$ 

6.2.Nbk 42

- 1. [x] 「GÍN¹ KÙ.BABBAR ir-bi
- 2. a-na <sup>m</sup>Na-din A-šú šá
- 3. <sup>md</sup>AG-EN-MU.MEŠ
- 4. SUM<sup>na</sup> ITI.GU<sub>4</sub>
- 5. U<sub>4</sub>.<sup>1</sup>6<sup>1</sup>.KAM MU.42.KAM

Rev.

- 6. dAG-NÍG.DU-ÙRU
- 7. LUGAL TIN.TIR<sup>ki</sup>

[x] shekels of silver, the income was given to Nādin, son of Nabû-bēl-šumāte. Month of Ayaru,  $6^{th}$  day,  $42^{nd}$  year of Nebuchadnezzar, king of Babylon.

**589. BM 75322** (83-1-18, 655) = Str. II 229/2

 $4.0 \times 3.2$  cm

20.5.AmM 0

- 1. 15 GÍN KÙ.BABBAR ŠÁM
- 2. hur-ra-tu šá ITI.GU<sub>4</sub>
- 3. MU.2.KAM a-na ta-bar-ri
- 4. šá ta-hap-taš-šú a-na
- 5. <sup>m</sup>DUB-NUMUN 15 GÍN KÙ.BABBAR
- 6. <sup>m</sup>EN-SUR <sup>I</sup>I NI

Edge Rev.

- 7.  $[(x)^{?}] \frac{1}{2} ma$ -na a-na
- 8. <sup>md</sup>AG-BÀD-IGI-*iá* SUM<sup>na</sup>
- 9. ITI.NE U<sub>4</sub>.20.KAM
- 10. MU.SAG.NAM.LUGAL.LA
- 11. LÚ-<sup>d</sup>AMAR.UTU LUGAL TIN.TIR<sup>ki</sup>

This text was used by Bongenaar, Ebabbar, p. 349.

L. 6. The reading [1] and NI seems certain, but the sense is unclear.

15 shekels of silver, the price of the  $h\bar{u}ratu$ -dye for the month of Ayaru,  $2^{nd}$  year, for a blanket was given to Šāpik-zēri.

15 shekels of silver Bēl-ēţir ....

 $[(x^{?})]$ ½ mina for Nabû-dūr-īnīya was given. Month of Abu,  $20^{th}$  day, the accession year of Amēl-Marduk, king of Babylon.

### **590. BM 67472** (82-9-18, 7469)

**PLATE 139** 

11.9.Nrg 2

- 1. [x *ma-na*] <sup>[2]</sup> GÍN ŠÁM 1 <sup>[x]</sup>
- 2. [x] <sup>r</sup>x<sup>1</sup> ri 1/3 GÍN KÙ. <sup>r</sup>BABBAR<sup>1</sup>
- 3. a-na SÍG.ZA.GÌN.KUR.RA
- 4. 15 GÍN KÙ.BABBAR a-na
- 5. mu-sib-tu PAP 5/6 ma-na
- 6. 「šá¬ ina ŠU<sup>ii m</sup>Mu-še-zib-<sup>d</sup>[DN]

7. [šá UG]U eš-ru-ú Edge

8.  $a^{-\lceil na \rceil}$  É-babbar-ra it- $\lceil ta \rceil$ -[din] Rev.

- 9. ITI.GAN U<sub>4</sub>.11.KAM MU.2.K[AM]
- 10. dU+GUR-LUGAL-ÙRU LUGAL TIN.TIRki

L. 6. The last partly preserved sign could also be the remains of bi, however, neither Mušēzib-d[x], nor Mušēzibu, the šā muḥḥi ešrî is known from the previously published texts, see the list of ša muḥḥi ešrî in Jursa 1988, p. VIIf.

[x mina] 2 shekels (of wool?), the price of [.....]

[....] 20 shekels of silver for the blue-purple wool,

15 shekels of silver for the *muşibtu* garment, total 50 shekels Mušēzib-<sup>d</sup>[DN], the tithe collector, has given to the Ebabbar temple. Month of Kisl $\bar{l}$ mu,  $11^{th}$  day,  $2^{nd}$  year of Neriglisar, king of Babylon.

# **591. BM 65913** (82-9-18, 5905)

PLATE 140

 $6.4 \times 5.3$  cm

Nbn 3

- 1. 1 GÚ.UN 56 ma-na SÍG.HI.A
- 2. ½ ma-na 6 GÍN SÍG,ZA,GÌN,KUR,RA
- 3. a-na lu-bu-uš-tu<sub>4</sub> šá ITI.KIN
- 4. U<sub>4</sub>.3.KAM MU.3.KAM <sup>d</sup>AG-IM.TUKU 5. LUGAL TIN.TIR<sup>ki</sup> *a-na* <sup>m</sup>Ba-lat-su A-[šú]
- 6.  $\check{s}\check{a}^{\mathrm{md}}AG\text{-PAP}\ u^{\mathrm{m}}Kab\text{-}ti\text{-}i\check{a}\ [A\text{-}\check{s}\check{u}]$ 7.  $\check{s}\check{a}^{\mathrm{md}}U\text{+}GUR\text{-}^{\Gamma}D\grave{U}^{u\check{s}^{\mathrm{m}}}\Gamma x\ x^{1}\ [....]$
- 8. A-*šú šá* <sup>m</sup>*Ap-la-a* [....]

9. [*i*]*d*-*di*-*in* [....]

Rev.

- 10. [x x] [....]
- 11. md<sub>[</sub>AG<sup>?</sup>]-[....]
- 12. 1/3 GÍN [SÍG.ZA.GÍN.KUR.RA a-na]
- 13. *mu-ut-ta-*[*tu*<sub>4</sub> *šá* <sup>d</sup>UTU]
- 14. a-na  ${}^{m}Ba$ -ku-u- $[a\ u$   ${}^{md}AG$ -up-ni-ja] 15.  ${}^{l\acute{u}}la$ -a'-ta-nu[  ${}^{mes}$   $\check{s}\acute{a}$   ${}^{md}AG$ -EN-MU.MEŠ]
- 16.  $^{\text{l\'u}}$ UŠ.BAR SUM $^{\text{r}^{in}}$ 1 [ITI.x U<sub>4</sub>.x.KAM]
- 17. MU. $^{r}$ 31.KAM AG-[IM.TUKU LU] $^{r}$ GAL  $^{r}$ E $^{k[i]}$
- 18. 2 GÍN KÙ.BABBAR ŠÁ[M x ma-na x G]ÍN SÍG.ZA.GÌN.KUR.R[A]

L.e.

- 19. pap-pa-as-su [a]-[na lú]UŠ.BAR meš a-na
- 20. <sup>m</sup>Ba-[lat]-su u <sup>m</sup>Kab-ti-ja [SUM<sup>na</sup>]

L. 14. I fill the gap with the name of <sup>md</sup>AG-up-ni-ja because in other texts he follows Bakûa, while Nabû-nāşir, another slave of Nabû-bēl-šumāti precedes Bakûa.

1 talent 56 minas of wool (and) 36 shekels of blue-purple wool for the *lubuštu* ceremony on the 3<sup>rd</sup> day of the month of Ulūlu, the 3<sup>rd</sup> year of Nabonidus, king of Babylon was given to Balāssu, son of Nabû-nāsir, and Kabtīva, [son of] Nergalēpuš, [PN], son of Aplā.

20 shekels of [blue-purple wool for] muttat[u-headdress for Šamaš] was given to Bakûa [and Nabû-upnīya], the slaves of [Nabû-bēl-šumāti], the weaver. [Month of x, n<sup>th</sup> day], 3<sup>rd</sup> year of Nabo[nidus], king of Babylon.

2 shekels of silver, the price of [x mina(s) x] shekels of blue-purple wool, the prebendary income of the weavers [was given] to Balassu and Kabtīya.

### **592. BM 61749** (82-9-18, 1719)

PLATE 141

 $4.7 \times 3.6$  cm

# 23.12.Nbn 4

- 1. 10 GÍN KÙ.BABBAR a-na dul-lu
- 2. 6 GÍN *a-na* lúUŠ.BAR
- 3. šá ni-bi-hu
- 4. PAP 16 GÍN KÙ.BABBAR ina pap-pa-su
- 5.  $[\check{s}\check{a}]^{\mathrm{md}}\mathrm{AG}$ -na-sir-IBILA  $^{\mathrm{l\acute{u}}}\mathrm{U\check{S}}.\mathrm{BAR}$  6. [a-na)  $^{\mathrm{rmd}}\mathrm{AG}$ -na-sir

Edge

7.[<sup>m</sup>Ba-ku-ú-a] ù

Rev.

- 8.  $\lceil^{\text{md}} AG-up-ni-ja \text{ SUM} \rceil^{\lceil in \rceil}$
- 9. [ul]-tu [ir-bi] šá KÁ
- 10. a-na dul-lu šá ITI.GU<sub>4</sub> ina GUB-zu
- 11. šá <sup>m</sup>DUB-NUMUN A-šú šá <sup>md</sup>UTU-ŠEŠ-MU
- 12. SUM<sup>in</sup> ITI.ŠE U<sub>4</sub>.23.KAM
- 13. MU.4.KAM  $^{md}$  AG-I LUGAL  $E^{ki}$

10 shekels of silver for the work (and) 6 shekels for the weaver (manufacturing) the nēbehu-belt, total 16 shekels of silver from the prebendary income of Nabûnāṣir-apli, the weaver [was giv]en to Nabû-nāsir-apli, [Bakûa] and [Nabû-upnīya]. (This is silver) from the income of the gate for the work of the month Ayaru given in the presence of Šāpik-zēri, son of Šamaš-aḥ-iddin. Month of Addaru, 23<sup>rd</sup> day, 4<sup>th</sup> year of Nabonidus, king of Babylon.

#### **593. BM 67934** (82-9-18, 7932)

PLATE 141

 $4.0 \times 3.3$  cm

# 4.<sup>[8]</sup> Nbn 5

- 1. 「3」 GÍN KÙ.BABBAR ina pap-pa-su šá [lúUŠ.BAR-ú-tu]

- 2.  $^{\text{md}}$ AG-EN-MU.MEŠ  $^{\text{m}}B[a-ku-\dot{u}-a]$ 3.  $^{\text{md}}$ AG-PAP  $^{\text{md}}$ UTU-ri- $s[u-\dot{u}-a]$ 4.  $^{\text{ru}}$   $^{\text{md}}$ AG-up-ni-ja  $^{\text{ru}}$   $^{\text{ru}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$   $^{\text{li}}$
- 5. [ $\check{s}\check{a}$ ] <sup>m</sup>DUB-NUMUN SUM<sup>i[n?]</sup>
- 6. [x+]1 KÙ.BABBAR  $[BABBAR]^2$
- 7. [i]- $\lceil si^{?} \rceil$ -man-nu- $\lceil \acute{u} \rceil$

8. [šá <sup>lú</sup>]UŠ.BAR GAD[A *a-na*?] Edge

9. [<sup>m</sup>x]-*la-a* <sup>1</sup>[<sup>ú?</sup>..... Rev.

- 10.  $[SUM]^{in}$  ITI.AP $[IN]^{?}$
- 11. [U] 4.4.KAM MU.5.KAM 12.  $^{md}$ AG-I LUGAL TIN.TIR $^{[ki]}$
- L. 2. The determinative before the name of Bakûa is written over an erasure.
- L. 6. BABBAR is written over an erasure.

3 shekels of silver from the prebendary income [of the weavers, which] Šāpik-zēri has given to Nabû-bēl-šumāti (and) B[akûa], Nabû-nāṣir, Šamaš-riṣ[ûa] and Nabûupnīya, [his slaves].

[x]+1 shekels of white silver [....], the ration of the linen weaver was given to [x]-1]lā, the [....].

Month of Arahsamna<sup>?</sup>, 4<sup>th</sup> day, 5<sup>th</sup> year of Nabonidus, king of Babylon.

#### 593a. BM 66993 (82-9-18, 6988)

**PLATE 142** 

 $3.55 \times 3.1 \text{ cm}$ 

### 16.2.Nbn 6

- 1'. [....] <sup>r</sup>ma<sup>?</sup>¹-na 1<sup>r</sup>1¹ GÍN [K]Ù.BABBAR
- 2'. [ki]-<sup>r</sup>i<sup>1</sup> pi-i 15 GÍN <SÍG>.ZA.GÌN.KUR.RA
- 3'. a-na 1 GÍN KÙ.BABBAR ina KÙ.BABBAR šá ina pa-ni
- 4'. <sup>md</sup>EN-NUMUN-DÙ A-šú šá <sup>md</sup>30-kit-ri
- 5'. <sup>m</sup><Za>-ab-bi-na-a' A-šú šá

6'. md AMAR.UTU-「DA」 a-na Rev.

- 7'. É-kur-ra it-ta-din
- 8'. ITI.GU4 U4.16.KAM
- 9'. 「MU¹.6.KAM <sup>md</sup>AG-I
- 10'. [LUGAL] 「E<sup>1ki</sup>

Note that the rate of 15 shekels of takiltu wool for one shekel of silver is the lowest of all known till now texts., cf. Zawadzki, Garments of the Gods, Vol. I, p. 47. Bēl-zēr-ibni/Sîn-kitri and <Za>bina'/Marduk-ilē'i appear here for the first time.

[.... x] minas 11 shekels of silver at the rate of 15 shekels of blue-purple wool for one shekel of silver, from silver, which is at disposal of Bēl-zēr-ibni, son of Sîn-kitri, Zabina', son of Marduk-ilē'i has delivered to the small sanctuaries. Month of Ayaru, 16<sup>th</sup> day, 6<sup>th</sup> year of Nabonidus, [king] of Babylon.

# **594. BM 60866** (82-9-18, 842)

PLATE 142

 $4.8 \times 3.5$  cm

#### 19.9.Nbn 6

- 1. 1 ma-na KÙ.BABBAR ir-bi a-na
- 2. SÍG.ZA.GÌN.KUR.RA a-na
- 3.  $^{\rm m}{}_{\rm f} Kal\text{-}ba\text{-}a$  A-šú šá  $^{\rm md}$ x-x¹-šú 4.  $u^{\rm md}$ UTU-SIG $_5{}^{iq}$  A-šú šá
- 5. <sup>m!</sup>Šu-zu-bu SUM<sup>in</sup>
- 6. ITI.GAN U<sub>4</sub>.20.1.LAL.KAM
- 7. 「MU¹.6.KAM <sup>md</sup>AG-I

Edge

- 8. LUGAL TIN.TIR<sup>ki</sup>
- Rev.
- 9. 「KÙ¹.BABBAR šá TA É.ŠU<sup>ii</sup>
- 10.  $SUM^{nu}$
- L. 1. a-na is written over an erasure.
- L. 3 looks like intentionally erased, but note *u* at the beginning of l. 4.

1 mina of silver, the income, (which) for blue-purple wool was given to Kalbā, son of [PN]-šu and Šamaš-udammiq, son of Šūzubu.

Month of Kislīmu, 19<sup>th</sup> day, 6<sup>th</sup> year of Nabonidus, king of Babylon.

Silver was taken from *bīt gāti*-storehouse.

### **595. BM 61211** (82-90-18, 1187)

**PLATE 143** 

 $4.2 \times 3.3$  cm

#### 5.2.Nbn 7

- 1. [x G]ÍN KÙ.BABBAR a-na
- 2. hal-lu-ru a-na
- 3. și-pi a-na

- 4. <sup>m</sup>DUB-NUMUN A-šú šá
- 5. <sup>rm</sup><sup>ηd</sup>UTU-ŠEŠ-MU

Edge 6.  $SUM^{in}$ 

7. ITI.GU<sub>4</sub> U<sub>4</sub>.5.KAM Rev.

8. MU.7.KAM <sup>md</sup>AG-[I]

9. LUGAL E<sup>ki</sup>

- L. 2. According to my knowledge this is the first attestation of chick-pea used for dying.
- [x] shekels of silver for chick-pea for dyeing was given to Šāpik-zēri, son of Šamaš-ah-iddin.

Month of Ayaru, 5<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

#### **596. CT 55, 868** = BM 56885

20.6.Nbn 7

- 1. <sup>[9]</sup> ma-na 10 GÍN SÍG.ZA.GÌN.KUR.RA
- 2. a-na 57 GÍN KÙ.BABBAR
- 3. <sup>md</sup>UTU-LUGAL-ÙRU *a-na É-babbar-ra*
- 4. it-ta-din ITI.KIN U<sub>4</sub>.20.KAM
- 5. MU.7.KAM <sup>md</sup>AG-I LUGAL E<sup>ki</sup>

9 minas 10 shekels of blue-purple wool for 57 shekels of silver, (which) Šamaššar-uşur has sold to the Ebabbar. Month of Ulūlu, 20<sup>th</sup> day, 7<sup>th</sup> year of Nabonidus, king of Babylon.

## **597. BM 62479** (82-9-18, 2448)

**PLATE 143** 

 $4.1 \times 3.4$  cm

10.2.Nbn 8

- 1. 2 GÍN KÙ.BABBAR ŠÁM {KÙ.BABBAR}
- 2. *šá* TÚG. MURUB<sub>4</sub> · .ÍB.LÁ. [MEŠ]
- 3.  $\check{s}\acute{a}^{d} \Gamma U T U^{\dagger} u^{d} B u \Gamma n e n e^{\dagger}$
- 4. a-na <sup>md</sup>EN-GI <sup>lú</sup>UŠ.[BAR šá <sup>d</sup>U+GUR]
- 5. [SU]M<sup>in</sup> ITI.GU<sub>4</sub>
- 6. [U<sub>4</sub>].10.KAM MU.8.KAM

7. dAG-I LUGAL INUNkij Edge

Rev. uninscribed

Bēl-ušallim is certainly identical with Bēl-ušallim/Bāniya, the išpāru ša Nergal known from Nbn 410: 9, written about two years later (15.2.Nbn 10). The new texts supports the interpretation of Nbn 410 by Bongenaar (Bongenaar, Ebabbar, p. 323) and shows that the Ebabbar temple had some problem with the manufacturing of the garments for the gods and needed some extra support from outside, e. g. from Cutha.

2 shekels of silver, the price of the patinnu-belts for Šamaš and Bunene was given to Bēl-ušallim, the wea[ver of Nergal]. Month of Ayaru, 10<sup>th</sup> day, 8<sup>th</sup> year of Nabonidus, king of Babylon.

### **598. BM 63866** = Bertin 1436 Collated

#### 8.11.Nbn 11

- 1. 2 GÍN KÙ.BABBAR TA ir-bi
- 2. a-na lu-bu-uš-tu<sub>4</sub>
- 3. šá ITI.ŠE u ITI.BÁR
- 4. a-na <sup>md</sup>AG-na-ṣir-A
- 5. ù <sup>m</sup>Ba-kú-ú-a 6. <sup>lú</sup>qal-la-šú 7. SUM<sup>in</sup>

Edge Rev.

- 8. ITI.ZÍZ U<sub>4</sub>.8.KAM
- 9. MU.11. KAM  $^{\rm d}$ AG-I
- 10. LUGAL TIN.TIR<sup>ki</sup>

2 shekels of silver from the irbu-income for the lubuštu ceremony of the month Addaru and Nisannu was given to Nabû-nāṣir-apli and Bakûa, his slave. Month of Šabāṭu, 8<sup>th</sup> day, 11<sup>th</sup> year of Nabonidus, king of Babylon.

# 599. BM 62415 (82-9-18, 2384)

PLATE 144

 $4.5 \times 3.5$  cm

# 24.8.Nbn 12

- 1. 1 GÍN KÙ.BABBAR ina pa-pa-s[u]
- $2.\ ^{l\acute{u}}U\check{S}.BAR-\acute{u}\text{-}tu$
- 3. md AG-na-sir-DUMU. UŠ
- 4. ina ŠU<sup>ii m</sup>Ba-ku-ú-a
- $\mathsf{SUM}^{na}$

Rev.

6. ITI.APIN U<sub>4</sub>.24.KAM

- 7. MU.12.KAM <sup>md</sup> AG-I
- 8. LUGAL.TIN.TIR.K[I]

1 shekel of silver from the prebendary income of the weaver's prebend was given to Nabû-nāṣir-apli by the hand of Bakûa. Month of Araḫsamna, 24<sup>th</sup> day, 12<sup>th</sup> year of Nabonidus, king of Babylon.

**599a. BM 59009** (82-7-14, 3418)

PLATE 144

 $4.3 \times 3.5 \text{ cm}$ 

[x].7.[Nb]n 7

- 1. [x GÍN] KÙ.BABBAR TA ir-bi
- 2. [š]á ina pap-pa-[su]

- 3.  $^{[1]\acute{u}}$ UŠ.BAR- $\acute{u}$ - $^{\Gamma}tu$
- 4. a-na <sup>m</sup>Ki-sir-iá
- 5. <sup>™</sup>*Ba-*「*ku*¹-*ú*-*a*

6. u <sup>md</sup> [AG<sup>¬</sup>-up-ni-iá Edge Rev.

7. [SU]M<sup>in</sup> ITI.DU<sub>6</sub>

8.  $[U_4.x.K]AM MU.^77^1.KAM$ 

9. [mdAG]- I LUGAL.Elki

Three almost unreadable lines, see copy of the text.

[x shekels] of silver, from the prebendary income as the prebendary income of the weavers was given to Kişiria, Bakûa and Nabû-upnīya.

Month of Tašrītu, [n<sup>th</sup> d]ay, 7<sup>th</sup> year of [Nabo]nidus, king of Babylon.

# **600. BM 64920** (82-9-18, 4901)

**PLATE 145** 

 $5.1 \times 3.4$  cm

# 27.[x].Nbn 13

- 1. 1 GÍN KÙ.BABBAR KÁ- $tu_4$  [ $sa^{?}$ ] [x x]
- 2. ina pap-pa-su <sup>lú</sup>UŠ.BAR-<sup>Γ</sup>ú<sup>η</sup>-tu
- 3. ana dul-lu šá ITI.DU<sub>6</sub>
- 4. *a-na* <sup>md</sup>AG-*na-ṣir*-A
- 5. u <sup>m</sup>Ba-ku-ú-a
- 6. SUM<sup>na</sup>

Edge 7. 4-tú a-na GI.MEŠ

Rev. 8. [a]-na šu-ut-tu-um šá É

- 9. *şa-lam* LUGAL.MEŠ [*šá* <sup>m</sup>]<sup>d</sup>UTU-NUMUN-DÙ
- 10. ½ GÍN KÙ.BABBAR 「ri¹-hi ŠUKU.ḤI.A-šú
- 11. šá ITI.NE ITI.KIN u ITI.DU<sub>6</sub>
- 12. ri-hi-tu<sub>4</sub> šá KÁ.GAL-ú SUR
- 13. [x G]ÍN 4-tú a-na 60 šil-ta-h[u]
- 14. kuš til-la šá LUGAL a-na

15.  ${}^{m}$  $\lceil A-nu \rceil - i-ba-a \text{ SUM}^{na}$ L.e.

16. [ITI.x] <sup>r</sup>U<sub>4</sub><sup>1</sup>.27.KAM MU.13.K[AM]

17. [mdAG-I LUG]AL E<sup>ki</sup> L. h. e.

#### L. 8. The word *šuttumu* is not noted till now.

1 shekel of silver, the outstanding amount of [....] from the prebendary income of the prebendary weaver for the work of the month Tašrītu was given to Nabû-nāṣirapli and Bakûa;

 $\frac{1}{4}$  shekel for reed for the  $\check{s}ut(t)umu$  of the chapel with the kings' statues (was given) [to] Šamaš-zēr-ibni;

½ shekel of silver, the remaining of his ration of the month of Abu, Ulūlu and Tašrītu, the remaining of the gate is paid;

[x shek]els (and) 1/4 (of shekel) for 60 arrows for the king's quiver was given to Anu-ibā.

[Month of x], 27<sup>th</sup> day, 13<sup>th</sup> year of [Nabonidus], king of Babylon.

### **601. BM 61828** (82-9-18, 1797)

PLATE 146

 $5.9 \times 4.7$  cm

# $22.7.\text{Nbn } 2[+x^?]$

- 1. 3 ½ ma-na KÙ.BABBAR ŠÁM
- 2. SÍG.HI.A 1 ½ ma-na KÙ.BABBAR šá ir-bi
- 3. PAP 5 ma-na KÙ.BABBAR a-na UD.KA.BAR
- 4. ù in-za-hur-ri-e-ti 「a-na T
- 5. <sup>m</sup>*A-tar-si-im-ki* <sup>r</sup>*A*<sup>1</sup>-[*šú*]
- 6. šá <sup>md</sup>30-ZÁLAG<sup>ir</sup> [SUM<sup>na</sup>] 7. ina GUB<sup>zu</sup> šá <sup>md</sup>U+G[UR-LUGAL-bul-liṭ]

Edge Rev.

8.  $^{\text{l\'u}}q\'i$ -i-pi šá  $^{\text{r\'E}}$ -[babbar-ra] 9.  $^{\text{m}}Mu$ -še-zib- $^{\text{d}}$ AMAR.UTU  $^{\text{l}}$ [ $^{\text{\'u}}$ SANGA Sip-pa $^{\text{k\'u}}$ ]

10. <sup>m</sup>NUMUN-TIN.TIR<sup>ki</sup> A <sup>m</sup><sup>r</sup>x<sup>1</sup>[....]

11. ITI.DU<sub>6</sub> U<sub>4</sub>.22.KAM MU. <sup>[2]</sup>+[1<sup>?</sup>.KAM]

12. dAG-I LUGAL TIN.TIRki

13. ½ ma-na ina KÙ.BABBAR ŠÁM SÍG.HI.A

14. *a-na ki-tu-ú a-na* <sup>m</sup>Š*u-la-a* 15. {*u*} <sup>lú</sup>*pu-ṣa-a-a* SUM<sup>in</sup>

- L. 1. kaspu ina kaspi šīm šipāti, verbatim "silver, from the silver the price of wool" means that the silver was yielded as a result of selling the wool, in contrast to the silver which was thrown into boxes at the entrance to the temple as small offerings.
- L. 10. Maybe it is Zēr-Bābili/Ina-tēšî-ēţir//Ēda-ēţir.
- L. 11. Because the year is written with vertical wedges the reading 2[+1] is also possible.
- L. 14. Šūla is most probably identical with the son of Ebabbar-lūmur, puṣāya, and probably the head of the team of išparātu kitê/puṣāya, see Bongenaar, Ebabbar, p. 351f. However, contrary to Bongenaar's proposal, CT 56, 777 should be shifted to the entry concerning Šūla/Šamaš-ah-[iddina'] išpar birmi.
- 3 ½ minas of silver from selling the wool (and) 1 ½ of minas from *irbu*-income, total 5 minas of silver was given to Atar-simki, son of Sîn-unammir for bronze and inzahurētu-dye.

In the presence of Ne[rgal-šar-bullit], the qīpu of Ebabbar (and) Mušēzib-Marduk, the  $\check{s}[ang\hat{u} \text{ of Sippar}]$  and  $Z\bar{e}r$ -Bābilî, descendant of [...].

Month of Tašrītu, 22<sup>nd</sup> day, 2+[1?] year of Nabonidus, king of Babylon.

½ mina (of silver) from selling of wool was given to Šūla, {and} the washerman for (buying) linen.

# **602. BM 75529** (83-1-18, 875)

 $4.2 \times 5.9$  cm

#### 7.10.Cam 2

- 1. [x] GÍN 3 ri-bat KÙ.BABBAR
- 2. a-na 1/2 GÚ.UN 5 ma-na
- 3. SÍG.ḤI.A a-na <sup>m</sup>Ri-ḥi-ti
- 4. lúA.MEŠ(sic!) šá <sup>m</sup>Kal-ba-a
- 5. mdUTU-SU mdUTU-DI.KU5\*-DÙuš
- 6. <sup>md</sup>ḤAR-LUGAL-ÙRU
- 7.  $^{\text{md}}$ UTU-PAP  $^{\text{m}}Lu$ - $\acute{u}$ -ŠEŠ- $^{\text{r}}\acute{u}$ <sup>1</sup>-[a]
- 8.  $SUM^{na}$
- 9. ITI. AB U<sub>4</sub>.7.KAM

Edge

10. MU.2.KAM

Rev.

11. <sup>m</sup>Kám-bu-zi-ja

12. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

Concerning this text, see Bongenaar, Ebabbar, p. 325.

[x]+ 3/8 shekels of silver for 35 minas of wool was given to Rēhēti, the son? of Kalbā (and) Šamaš-erība, Šamaš-dīni-ēpuš, Bunene-šar-uṣur, Šamaš-nāṣir, Lū-aḥū'a. Month of Ṭebētu, 7<sup>th</sup> day, 2<sup>nd</sup> year of Cambyses, king of Babylon, king of Lands.

# **603. BM 63590** (82-9-18, 3557)

PLATE 146

 $7.7 \times 3.9 \text{ cm}$ 

#### 13.11.Cam 5

- 1. [x ma-na x GÍ]N 4-tú bit-qa KÙ.BABBAR a-na 25 TÚG.KUR.RA.「MEŠ1
- 2. 「x¹ ku-satu túgšir-a-am <sup>m</sup>Ina-GIŠ.MI-<sup>d</sup>U+GUR a-na NÍG.GA
- 3. TÚG.KUR.RA.MEŠ u <sup>túg</sup>šir-a-am <sup>meš</sup> a-na <sup>m</sup>ÌR-<sup>d</sup>A-nu-ni-
- <tu<sub>4</sub>> lú GAL GIŠ.BAN

  4. SUM<sup>na.'</sup> ITI.ZÍZ U<sub>4</sub>.13.KAM MU.5.KAM <sup>m</sup>Kam-bu-zi-iá
  LUGAL E<sup>ki</sup> u KUR<sup>meš</sup>

- 5. 1 ma-na KÙ.BABBAR a-na 20 ni-sip šá šam-ni a-na
- l<sup>ú</sup>ERÍN.MEŠ šá <sup>lú</sup> qí-pi 6. a-na <sup>m</sup>Lib-luṭ <sup>m</sup>Šá-lam-ma-ri-e u <sup>md</sup>UTU-a-na-É-šú ina qí-bi 7. <sup>m</sup>LUGAL-lu-da-ri <sup>lú</sup>qí-pi šá É-babbar-ra SUM<sup>in md</sup>ḤAR-DÙ
- lúBAHAR
- 8. lúA.KIN ITI.ZÍZ U<sub>4</sub>.20.KAM M[U ....]
- 9. 1 GÍN *bit-q*[*a* KÙ.BABBAR] <sup>[x</sup> x x <sup>1</sup> [....]

10. SUM<sup>nu</sup> [....] 11. <sup>[</sup>x<sup>]</sup> [....]

Rev. uninscribed

L. 2. Ina-silli-Nergal is also present in BM 68423: 1 (Camb) and BM 55889: 1 (undated).

L. 3. Arad-Anunītu, the rab qašti, see Bongenaar, Ebabbar, p. 132. For Bunene-ibni, paḥāru, cf. Jursa 1995, p. 42. Add to his list BM 62349: 19 (16.8. Nbn 11); BM 74655: 1 (Nbn 16) and BM 72902: 18 (13.8.Cam 1). Until now he was known as potter active among the group of gardeners; here in his capacity as a messenger for the first time he is not performing the ordinary job of porter. Our text suggests that Bunene-ibni the potter and mār šipri ša qīpi (Bongenaar, Ebabbar, p. 51) is the same person. This means that his activity lasted at least from Nbk 30 to Cam 5 (575-524 BC). After A.KIN and before dating there is a blank space.

For Liblut, the mār šipri ša qīpi/rab širkī ša Šamaš, see Bongenaar, Ebabbar, p. 51 For Šalammarê, the sēpiru ša qīpi/ mār šipri ša qīpi, id., p. 52.

Šamaš-ana-bītišu is not known from other texts, however, because he appears together with the two above-mentioned persons, we can expect that his position was also similar.

[x minas x she]kels (and) 3/8 shekels of silver for 25 TÚG.KUR.RA, [x] robes (and) coats of armour Ina-silli-Nergal has given to the property of Šamaš. The TÚG.KUR.RA-garments, robes (and) coats of armour were given to Arad-Anunītu,

Month of Šabatu, 13<sup>th</sup> day, 5<sup>th</sup> year of Cambyses, king of Babylon, king of Lands.

1 mina of silver for 20 measures of oil for the workers of the king's resident on the orders of Šarru-lū-dāri, the king's resident of the Ebabbar temple was delivered to Liblut, Šalammarê and Šamaš-ana-bītišu. Bunene-ibni, the potter (was) the mes-

Month of Šabatu, 20<sup>th</sup> day, [year ....]

1 1/8 shekels [of silver ....] was given [....].

**604. BM 75186** (83-1-18, 512) = Str. II 300/2  $4.6 \times 4.0$  cm

PLATE 147

10.2.Dar 28

- 1. 2 ½ GÍN KÙ.BABBAR BABBAR-Γú¹
- 2. ТА qu-ир-ри а-па
- 3. pap\*-pa\*-su šá și-pu e-<sup>r</sup>lat<sup>1</sup> [SÍG.ḤI.A]
- 4. šá ITI.GU<sub>4</sub> šá lu-bu-u[š-tu<sub>4</sub>]
- 5.  $\check{s}a^{d}A$ -nu-ni- $tu_4$  a-n[a]
- 6.  $^{\text{md}}$ EN-a-su\*- $\acute{u}$ -[a]

7. SUM $^{rna}$ Edge

Rev.

8. ITI.GU<sub>4</sub> U<sub>4</sub>.10.K[AM]

9. MU.28.KAM <sup>m</sup>Da-ri-[muš] 10. LUGAL E<sup>ki</sup> LUGAL KUR.KUR

- L. 3. Or less probable  $e^{-t}lat^{-1}$  [KÙ.BABBAR].
- L. 6. It is not excluded that Bēl-asûa is identical with the oil-presser who was active at the same period, see Bongenaar, Ebabbar, p. 270 and p. 322.
- 1. 8. Contra Strassmaier's copy the reading of day date as 10 seems to me more probable.
- 2 ½ shekels of white silver, from the box for the prebendary income for dyeing; except for [wool] of the month Ayaru for the *lubuštu* ceremony of Anunītu was given to Bēl-asûa.

Month of Ayaru, 10<sup>th</sup> day, 28<sup>th</sup> year of Dari[us], king of Babylon, king of Lands.

### **605. BM 101312** (83-1-21, 2973)

 $3.9 \times 3.0$  cm

### 17.[x].Cyr [x]

- 1. 55 GÍN KI.LAL 2 <sup>r</sup>x x<sup>1</sup> (erased)
- 2. [t<sup>túg</sup>]par-ši-gu<sup>meš</sup> ta-bar-ra 3. [ši]-me<sup>?</sup> 3 GÍN 2-ta ŠU<sup>ii.meš</sup> KÙ.BABBAR
- 4.  $[^{md}UTU]$ -MU-MU  $u^{m_{\Gamma}}KAR^{?}$ - $^{d}AMAR.UTU^{?_{\Gamma}}$
- 5. [a-na] É-babbar-ra it-<sup>r</sup>tan<sup>¬</sup>-nu
- 6. [....] <sup>[</sup>x<sup>]</sup> *bi* <sup>[</sup>x<sup>]</sup> [....]
- 7. [.... *pa*]*r*-ši-gu<sup>meš</sup>
- Rev
- 8.  $\left[ .... \right]^{\frac{1}{M}} HAR \check{s}i man^{an} ni$
- 9. [SUM<sup>in</sup> ITI.x] U<sub>4</sub>.17.KAM 10. [MU.x].KAM <sup>m</sup>Ku-raš ĻUGAL E<sup>ki</sup>
- 11. [LUGAL] KUR.KUR<sup>meš</sup>
- 55 shekels, the weight of 2 red paršīgu-headdresses, [wor]th? of 3 2/3 shekels of silver, [Šamaš]-šum-iddin and Mušēzib-Marduk have given to the Ebabbar temple [.... x] paršīgu- headdresses [....] Bunene-šimanni [has given]. [Month of x], 17<sup>th</sup> day, [n<sup>th</sup> year] of Cyrus, king of Babylon, king of Lands.

# **606. BM 61107** (82-9-18, 1083)

PLATE 148

 $5.1 \times 4.0$  cm

#### 10.6.Cam 3

- 1. [x] 「GÍN¹ KÙ.BABBAR šá ir-bi
- 2. [a]-na 15 ma-na SÍG.HI.A
- 3. ina SÍG.HI.A IG[I-i]-tú!
- 4. u SÍG.HI.A šá <sup>lú</sup>ERÍN.MEŠ-šú
- 5. a-na <sup>m</sup>Ri-mut-DINGIR SUM<sup>[n]u</sup>
- 6.½ GÍN *šá ir-bi a-na* 7. <sup>m</sup>ÌR-<sup>d</sup>ḤAR <sup><lú></sup>[Uй.BAR *bi*[*r-m*]*u*

Edge Rev.

- 8. SUM<sup>in</sup> [x GÍN K]Ù.BABBAR
- 9. [a-na x m]a-na SÍG.HI.A-šú
- 10. ana [<sup>m</sup>Ri]-hi-tu<sub>4</sub> <sup>1</sup>[<sup>ú</sup>U]Š.BAR bir-<sup>r</sup>mu<sup>7</sup>

- 11. SUM<sup>nu</sup> 6 「GÍN」 [KÙ.BABBAR *šá ir*]-bi
- 12. a-na DUH.LÀL ina ŠU<sup>ii</sup>
- 13. <sup>md</sup>UTU-SU *šu-bu-lu*
- 14. ITI.KIN U<sub>4</sub>.10.KAM MU.3.<KAM>
- 15. <sup>m</sup> [Kam]-bu-zi-[iá LUGAL] TIN.TIR<sup>ki</sup>
- [LUGAL K]UR.KUR L.e.
- L. 3. What is preserved looks exactly like "11 blank space –na", which I might be interpreted as IG[I-i-t]ú.
- L. 12. The reading DUH.LAL I owe to M. Jursa.
- [x] shekels of silver from the irbu-income for 15 minas of wool from an earlier issue of wool and wool of his workers was given to Rēmūt-ilī.

½ shekel from the *irbu*-income was given to Arad-Bunene, the multi[colour]ed

[x shekels of si]lver [for x his min]a(s) of wool was given to Rēhētu, the multicoloured weaver.

6 shekels [of silver from the *ir*]bu-income for wax was brought by Šamaš-eriba. Month of Ulūlu, 10<sup>th</sup> day, 3<sup>rd</sup> year of Cambyses, king of Babylon, [king of L]ands.

### **607. BM 65104** (82-9-18, 5085)

**PLATE 148** 

 $5.1 \times 3.5$  cm

#### 21.6.Dar 2

- 1. [x ma-na] KÙ.BABBAR ina sat-tuk { \( \text{rsat} \) -tuk \}
- 2.  $^{\text{lú}}\text{MU}$ - $^{\text{r}}$ u-tu $^{\text{r}}$ u-na
- 3.  $^{md}$ AG- $^{\Gamma}$ x $^{1}$  [x (x) SUM] $^{na}$  5 GÍN  $^{\Gamma}$ KÙ.BABBAR $^{1}$
- 4. a-na 21 <sup>[</sup>ma-na<sup>]</sup> šá in-z[a-hu-ri-e]-tú
- 5. a-na lu-bu-uš-tu<sub>4</sub> šá IT[I.APIN]
- 6. *a-na* <sup>m</sup>[Ú-bal]-liṭ-su-dME.ME

Rev.

- 7.  $[x \times x \times a]$ -na gíd-li-e
- 8. <sup>r</sup>a-na <sup>m</sup>Ri<sup>1</sup>-mut <sup>lú</sup>SIMUG 9. SUM<sup>na</sup> ITI.KIN U4.21.KAM
- 10. 「MU.2.KAM<sup>¬ m</sup>Da-ri-mu-šú
- 11. [LUGAL TIN].TIR<sup>ki</sup> LUGAL KUR.KUR

For Uballissu-Gula, see Bongenaar, Ebabbar, p. 259f. and Zawadzki, Garments of the Gods, Vol. I, p. 231f. This is an additional text in which the price of inzahurītu-dye can be established; it is surprisingly low, i.e. 4 minas 12 shekels for one shekel of silver, cf. with the data in Vol. I, Table 1 on pp. 42-43.

[x mina/shekels] of silver as the baker's prebendary offering [was give]n to Nabû-

5 shekels of silver for 21 minas of inza[hurētu]-dye for the lubuštu ceremony of the month of [Araḥsamna<sup>?</sup>] was given to Uballissu-Gula.

[....] for the *gidlu*-torque was given [to Rē]mūt, the smith.

Month of Ulūlu, 21<sup>st</sup> day, 2<sup>nd</sup> year of Darius, [king of Ba]bylon, king of Lands.

### **608. BM 62654** (82-9-18, 2623)

PLATE 149

 $4.7 \times 3.2 \text{ cm}$ 

Dar 34

- 1. [....]
- 2.  $in^{-r}za^{\gamma}-[hu-ri]^{-r}e^{\gamma}-ta$
- $3. u^{\text{na4}} gab-bu-\acute{u}$
- 4. šá lu-bu-uš-tu<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub>
- 5. šá ITI.ŠU a-na <sup>m</sup>TIN-su-<sup>d</sup>[Gu-la SUM]
- 6. e-lat 3 GÍN KÙ. BABBAR¹

7. ITI.SIG<sub>4</sub> U<sub>4</sub>.[x.KAM] Edge

8. MU.34.K[AM]

9. 3 BÁN ŠE.GIŠ.Ì  $\lceil \acute{a}r \rceil - k [\acute{a}t^? (\mathbf{x} \ \mathbf{x})]$ Rev.

10. ri-hi sat-tuk šá U<sub>4</sub>.15.[KAM]

11. ár-kát-tu<sub>4</sub> šá ITI.SIG<sub>4</sub>

12. MU 30[+4.KAM] a-na

12.  $\lceil x \rceil \lceil x \times x \times x \rceil \lceil it^2 - ta^2 \rceil - \lceil din \rceil$ 

13. [....]

14. [m]Da-ri-iá-muš [LUGAL E<sup>ki</sup>] L. h. e.

LUGAL KUR.KUR

[....] inzahurētu-dye and alum for the lubuštu ceremony of Anunītu for the month

of Du'ūzu (were given) to Uballissu-[Gula]; except for 3 shekels of silver.

Month of Simānu, [x<sup>th</sup>] day, 34<sup>th</sup> year

3 sūtu of sesame of later [issue<sup>2</sup>], rest of sattukku-offering for the second part of the month Simānu, 3[4<sup>th</sup> year .... was given to [....]

[...], Darius, [king of Babylon], king of Lands.

# 609. BM 74670 (82-9-18A, 395)

**PLATE 149** 

 $4.6 \times 3.8$  cm

# 18.1.Cyr 8

- 1. 18 ma-na ki-tin-nu 1 ma-na GIŠ\*.LAGAB\*

- 2. 1 qa <sup>na4</sup>gab-ú a-na ti-mu-tu<sub>4</sub>
  3. šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> a-na <sup>md</sup>ḤAR-ši-man-ni
  4. [SU]M<sup>na</sup> 1 GÍN KÙ.BABBAR ina pap-pa-su šá
  5. [<sup>túg</sup>\*1sib\*-tu<sub>4</sub> šá <sup>d</sup>A-nu-ni-tu<sub>4</sub> a-na
- 6. [m]<sub>\(\Gamma\)</sub>HAR-\(\si\)-man-ni SUM

7. [x ma-n]a KÙ.BABBAR a-na GI.MEŠ

Rev. 8. a-na șa-pi-e šá a-di-la-nu

- 9. *šá ku-si-tu*<sub>4</sub> *šá* <sup>d</sup>*A-a* ù <sup>tág</sup>gu-ḫal-ṣi 10. *šá* <sup>d</sup>*A-nu-ni-tu*<sub>4</sub> *a-na* <sup>m</sup>*Gi-mil-lu* SUM<sup>na</sup>
- 11. 3 1/3 GÍN KÙ.BABBAR a-na šu-li-ja
- 12. 5 qu-up-pi-e šá E<sup>ki</sup> a-na

- 13. <sup>md</sup>UTU-KÁD SUM<sup>na</sup> ITI.BÁR
- 14. U<sub>4</sub>.18.KAM MU.8.KAM
- 15. <sup>m</sup>Ku-raš LUGAL E<sup>ki</sup> u 「KUR」.KUR
- L. 1. GIŠ.LAGAB contra "IS-SI [or GADA-SI]" (Bongenaar, *Ebabbar*, p. 325). L. 5. Bongenaar reads [fi-mu]-tu4, however,  $f^{tug}$ 1,fi1,fi2 clear.

18 minas of  $cotton^2$ , 1 mina of  $h\bar{u}ratu$ -dye, 1  $q\hat{u}$  of alum for thread of Anunītu [was gi]ven to Bunene-šimanni.

1 shekel of silver as his prebendary income for (manufacturing) the sibtu-garment for Anunītu was given to Bunene-šimanni.

[x min]a(s) of silver for reed for dyeing of the adilānu-tassel of the robe of Aya and the scarf of Anunītu was given to Gimillu.

3 1/3 shekels of silver for transporting five quppu-chests from Babylon was given to Šamaš-kāşir.

Month of Nisannu, 18<sup>th</sup> day, 8<sup>th</sup> year of Cyrus, king of Babylon and Lands.

### **610. BM 65377** (82-9-18, 5362)

 $5.4 \times 4.2$  cm

#### 17.5.Dar 2

- 1. [x ma-na KÙ.BABBAR a-n]a KI.LAM
- 2.  $[in-za-hu-ri-e-tu^2]$  [a-na] [uš]- $sa^4-a-au$  [uš]
- 3.  $[SUM^n]^a \frac{1}{2} ma-na KÙ.BABBAR$
- 4. 「a-na KI.LAM in-za-hu-ri-e-tú
- 5. a-na <sup>m</sup>Ú-bal-lit-su-<sup>d</sup>ME.ME
- $SUM^{na}$
- 7. ITI.NE U<sub>4</sub>.17.KAM
- 8. MU.2.KAM <sup>m</sup>Da-ri-mu-šú
- L. 2. The signs following *Uš* are written over an erasure.

[x shekels of silver a]s the price [of inzahurītu-dye was giv]en to Uššaya and Šellibi. 30 shekels of silver for the price of *inzaḥurītu*-dye was given to Uballissu-Gula. Month of Abu, 17<sup>th</sup> day, 2<sup>nd</sup> year of Darius.

### 610a. BM 62896 (82-9-18, 2865)

**PLATE 150** 

4.6 x 3.3 cm

#### 2.[x].Dar 3

- 1. 1 ma-na KÙ.BABBAR a-na
- 2. KI.LAM šá in-za-hur-ri-e-<tu<sub>4</sub>>
- 3. *a-na* <sup>md</sup>UTU-MU SUM<sup>na</sup>
- 4. [x] ma-na SÍG.ZA.GÍN.<KUR>.RA
- 5.  $[a-n]a \lceil lu \rceil bu u\check{s} tu_4$

6. [ $\check{sa}$  ITI.x] MU.3.KAM 7. [a-na]  $^{\mathrm{md}}$ UTU-MU 8. [ $\mathrm{SU}$ ]M $^{?}$ г $^{na?}$  $^{?}$ 1 Edge

9. 10 GÍN SÍG.ZA.GÍN.<KUR>.RA Rev.

10. a-na bat-qa šá dul-lu

11. 「šá¹ GIŠ.GIGIR *a-na* {1}

12. md[ĤA]R-*ši-man-an-ni* SUM<sup>na</sup>

13. ITI.[x] U<sub>4</sub>.2.KAM MU.3.KAM

14. <sup>m</sup>*Da-[r]i-mu-šú* 

(Nothing is missing)

- L. 11. Most probably the chariot of Šamaš, covered for the procession with luxurious cloth, is meant there.
- L. 12. Only one vertical wedge is preserved from the theophoric element, but the reconstruction seems certain as Bunene-šimanni was active at that time and he received coloured wool for repair of garments (cf. Camb 4; Dar 139; BM 66160).

1 mina of silver for the purchase of *inzaḥurētu*-dye was given to Šamaš-iddin;

[x] mina od blue-purple wool for the *lubuštu* ceremony [oft he month x], the 3<sup>rd</sup> year, was given to Šamaš-iddin;

10 shekels of blue-purple wool for repairing work on the chariot was given to Bunene-šimanni. Month [x],  $2^{nd}$  day,  $3^{rd}$  year of Darius.

#### **611. BM 61226** (82-9-18, 1202)

**PLATE 151** 

 $5.15 \times 3.9 \text{ cm}$ 

# $2+[x].^{1}^{?}$ .Dar [x]

- 1. 1/3 2 ½ GÍN KÙ.BABB[AR BABBAR-ú šá]
- 2. *a-na* 20 *ma-na in-za-hu-[ri-tu*<sub>4</sub>]
- 3. *a-na* <sup>md</sup>HAR-*ši-man* <sup>an</sup>-ni 4. SUM <sup>nu</sup>
- 5. 2 1/2 GÍN KÙ.BABBAR a-na
- 6. 2 PI ŠE.BAR a-na

7. ki-sat ANŠE.KUR.RA.MEŠ Rev.

- 8. šá <sup>d</sup>EN a-na <sup>md</sup>AG-it-tan-nu
- 9. 5 GÍN KÙ.BABBAR ina qí-bi šá <sup>md</sup>AG-PAP
- 10. a-na <sup>md</sup>ḤAR-[DÙ] <sup>lú</sup>DÚG.QA.BUR SUM
- 11. e-lat 10 [GÍN KÙ].BABBAR IGI-ú
- 12. ITI.B[ÁR U<sub>4</sub>.x].KAM [MU.x.K]AM
- 13. <sup>m</sup>Da-ri-<sup>r</sup>uš<sup>¬</sup>-šú LUGAL [KUR]. <sup>r</sup>KUR
- 14. 1 GÍN 'KÙ'.BABBAR *a-na* [UGU<sup>?</sup>]

15. 5 BÁN ZÍZ.A.AN *a-na* [PN] L.e.

16.  $[(x x)] SUM^{nu}$ 

17. 3 GÍN KÙ.BABBAR *šá* UGU L. h. e.

The scribe planned the tablet badly, writing only 6 lines on the obverse and 10 lines on the reverse; as a result he also used the left-hand edge. Line 15, apart from the last two signs is written over an erasure and is badly preserved; my reading is only tentative. Also the reading of line 18 is extremely difficult because it was written with a damaged stylus leaving many additional lines and, as is usual with text on the left-hand edge, the signs are very small.

- L. 1. Alternatively one can fill the gap with [šá gìn-nu].
- L. 5. Note the exceptionally high price of  $28 q\hat{u}$  of barley for 1 shekel of silver, while the typical price was ca. 1 kurru (180 qû) for 1 shekel of barley. Maybe the barley was of a special sort or it was in some way prepared for feeding the god's horses.
- L. 12. The collation suggests that instead of month the Du'ūzu the more probable reading is BÁ[R], because of the quite large space between the name of the month and KAM.
- L. 18. The sense of l. 18 is unclear to me.
- 22 ½ shekels of [white] silver for 20 minas of inzahurētu-dye was given to Bunene-šimanni.
- 2 ½ minas of silver for 2 pānu of barley for fodder for horses of Bēl was given to Nabû-ittannu.
- 5 shekels of silver was given to Bunene-[ibni], the potter, by the order of Nabû-

Except for 10 [shekels of sil]ver of the previous (issue).

Month of Du'ūzu, [x<sup>th</sup> day, year x+]2 of Darius, king [of the Lands].

1 shekels of silver on [account of] 5 sūtu of emmer [....] was given.

3 shekels of silver on account of regular offering [.... t]o Nabû-ittannu (was given).

#### 612. BM 101215 (83-1-21, 2876)

 $4.3 \times 3.1$  cm

```
1'. [...]-[nu]
```

2'. [....] <sup>r</sup>ma-na<sup>1</sup> 5 GÍN KÙ.BABBAR

3'. [.... *ul-tu*] ITI.NE MU.9.KAM

4'. [....] *a-di* ITI.NE MU.16.KAM *ina lìb-bi* 

5'. [....] 1/3 ma-na1 GÍN KÙ. BABBAR a-na<br/> $^{\mathrm{md}}\mathrm{U}\text{+}\mathrm{GUR}\text{-}\mathrm{MU}$ e-piš-an-na SUM

```
6'. [....] 「KÙ.BABBAR<sup>1</sup> šá a-na dul-lu a-na <sup>md</sup>AG-PAP-A
```

7'. [.... u]  $\int_{0}^{m} Ba^{1}-ku-u-a^{1u}U$ Š.BAR SUM

8'. [....] 'na' ITI.GU<sub>4</sub> 1 GÍN 'x' [....]

9'. [.... IT]I.DU<sub>6</sub> <U<sub>4</sub>>.15 K[AM]

10'. [....] [26] [....]

Rev.

1'. [....] <sup>[</sup>12.KAM<sup>[</sup> [....]

2'. [...-i]a (rest free)

3'. [....] 「x¹ šá ZÚ.LUM.MA

4'. [.... lú]UŠ.BAR

5'. [....].KAM

The comparison with the period of activity of Bakûa, Nabû-nāṣir-apli and Nergal-iddin (see Bongenaar, *Ebabbar*, pp. 317 ff., 337 ff. and 338, accordingly), makes it certain that the document was written in the time of Nabonidus and comprised the period from 9<sup>th</sup> till 16<sup>th</sup> year.

[.... x] mina(s) 5 shekels of silver . [.... from] the month of Abu,  $9^{th}$  year [KN?] until month of Abu,  $16^{th}$  year; including [....] 21 shekels of silver which was given to Nergal-iddin, the performer.

[....] of silver, which was given for the work to Nabû-nāṣir-apli [....] and Bakûa, the

[....], month of Ayaru, 1 shekel [....]

[....], month of Tašrītu, 15<sup>th</sup> day

[....], 12<sup>th</sup> [....]

[....] dates

[....], the weaver [....]

#### **613. BM 60783** (82-9-18, 758)

 $4.4 \times 3.7$  cm

#### 4.12.<KN->

- 1. [x] 「TÚG¹.KUR.RA.MEŠ 「a¹-[na]
- 2. [x] GÍN 3 ri-bat KÙ.BABBAR
- 3. <sup>m</sup>Na-din it-ta-din
- 4. 「KÙ.BABBAR」 NU SUM $^{na}$
- 5. [x] 「TÚG¹.KUR.RA.MEŠ ina 「ɹ [x x x]
- 6. [SUM<sup>*na*</sup>]

Rev. 7. [I]TI.ŠE  $U_4$ .4.KAM

Nothing is missing

Nādin, most probably the same person as in BM 73327, may be the son of Nabû-bēl-šumāti, see Bongenaar, *Ebabbar*, p. 338 and Zawadzki, *Garments of the Gods*, Vol. I, p. 223. For prices of TÚG.KUR.RA garments, see now Jursa 2010, pp. 620–623.

[x] TÚG.KUR.RA-garments Nādin has sold for [x] ¾ shekel of silver (but the silver is not paid. [x] TÚG.KUR.RA-garments are place in the [....]- storehouse. Month of Addaru, 4<sup>th</sup> day [....].

#### **614. BM 100874** (83-1-21, 2535)

 $4.2 \times 4.3$  cm

#### 7.3.Nbk 43

1'.[....] 'KÙ<sup>?</sup>¹.[....]

2'. [x x] KÙ.BABBAR šá TA [ir-bi]

3'. [x TÚG.K]UR.RA.MEŠ *a-na* [....]

- 4'. [x] TÚG.KUR.RA *a-na* 1<sup>?</sup> [....]
- 5'. 「x¹ TÚG.KUR.RA a-na 2 「x¹
- 6'. PAP 11 TÚG.KUR.RA  $\lceil x \rceil$  [....] 7'.  $\lceil K\grave{U}^{?}$ .BABBAR $^{?}_{1}$   $^{md}$ UTU-SIG $_{5}$ [ $^{iq}$  a-na]
- 8'. É-babbar-ra it-[ta-din]

9'. ITI.SIG<sub>4</sub> U<sub>4</sub>.7.[KAM] Edge

Rev.

- L. 5. At the end one vertical wedge is preserved.
- L. 6. RA is followed with two vertical wedge, or  $\lceil a \rceil^2$
- [....] of silver from the *irbu*-income,
- x KUR.RA-garments for [....]
- x KUR.RA-garments for 2 [....]
- x KUR.RA-garments for [....] of silver Šamaš-udammiq has gi[ven] to Ebabbar

Month of Simanu, 7<sup>th</sup> day, 43<sup>rd</sup> year of Nebuchadnezzar, king of Babylon.

### **615. BM 71100** (82-9-18, 11102)

 $4.7 \times 3.4$  cm

#### 6.6.[KN] 31

- 1. 40 *ma-na* SÍG.HI.[A]
- 2. a-na 10 GÍN KÙ.BABBAR šá ina [IGI]
- 3. <sup>m</sup>Ta-qiš-šú SUM<sup>na</sup>
- 4. ITI.KIN U<sub>4</sub>.6.KAM
- 5. MU.31.KAM
- 6. Lost

Rev. uninscribed

Because Taqiššu is not known from other documents, it is difficult to decide whether the document was written in the 31st year of Nebuchadnezzar or 31st year of Darius; both are possible, see Jursa 2010, pp. 616f, Table 96.

40 minas of wool for 10 shekels of silver which was given at disposal of Taqiššu. Month of Ulūlu, 6<sup>th</sup> day, 31<sup>st</sup> year [....]

#### **616. BM 63832** = Bertin 1140 Collated

26.1.Nbk 37

- 1. 6 TÚG.KUR.RA.MEŠ šá
- 2. <sup>md</sup>AG-NUMUN-DU A-šú šá
- 3. md AMAR.UTU-MU-DÙ

- 4. a-na 16 GÍN KÙ.BABBAR
- 5. a-na Ébabbar-ra
- 6. it-ta-din KÙ.「BABBAR<sup>1</sup>

Rev. 7. ul e-tir

- 8. ITI.BÁR U<sub>4</sub>.26.KAM
- 9. MU.37.KAM
- 10. dAG-NÍG.DU-ú-şur
- 11. LUGAL TIN.TIR<sup>ki</sup>

Nabû-zēr-ukīn/Marduk-šum-ibni, identical with nuhatimmu from Dannea family?, see Bongenaar, Ebabbar, p. 195.

6 TÚG.KUR.RA-garments, which Nabû-zēr-ukīn, son of Marduk-šum-ibni has sold to the Ebabbar temple for 16 shekels of silver. Silver has not been paid. Month of Nisannu, 26th day, 37<sup>th</sup> year of Nebuchadnezar, king of Babylon.

# **617. BM 83162** (83-1-21, 325)

**PLATE 151** 

 $4.6 \times 5.2$  cm

```
1'. [x] GÍN KÙ.BABBAR 「BABBAR^{\hat{u}_1} [....]
```

- 2'. [x]+1 ma-na 2-ta Š[U<sup>ii.meš</sup> KÙ.BABBAR]
- 3'. [ina lì]b-bi 1 ma-na 18 G[ÍN ....]
- 4'. [1<sup>en</sup>] TÚG.HI.A a-di pa-ni [x] [....]
- 5'. 2 ma-na KŬ.BABBAR šá <sup>m</sup>Ina-e-šá-bi<sup>?</sup> [....] 6'. ina ŠU<sup>ii md</sup>AG-KÁD a-na <sup>md</sup>AG-「x¹[....]
- 7'. 15 GÚ.UN SÍG.ḤI.A 1 ma-na KÙ.BABBAR šá i[na<sup>?</sup>....]
- 8'. 13 ma-na KI.LAL TÚG.BAR.DUL<sub>8</sub> a-di a-[di-la-nu]
- 9'. šá <sup>d</sup>GAŠAN Sip-par<sup>ki</sup> ITI.ŠE MU.<sup>[20]</sup>[....]
- 10'. ŠE.BAR šá a-na dul-lu šá É-bab[bar-ra]
- 11'. 1 me 20 KÙR ina ŠU<sup>ii md</sup>EN-「MU<sup>?</sup>」 [....]
- 12'.  $ina \check{S}U^{ii} {}^{m}KAL^{a} u {}^{md}U[TU-[....]$
- 13'. 2 me 10 KÙR šá TA [....]
- 14'. 16 KÙR *šá* MU [....]
- 15'. [....] 'KÙR x x' [....]

Rest lost

Rev. is completely effaced and it is not possible to say if it was inscribed.

[....] x shekels of white silver [....].

[x]+1 mina 40 shekels [of silver ....], including 1 mina 18 sh[ekels...] 1 lubārugarment together with pānu [....]

2 mina of silver, which Ina-ešabi?-[x has paid?] to Nabû-[xxx] by agency of Nabûkāsir.

15 talents of wool (for) 1 minas of silver [....], 13 minas, the weight of robe with ta[ssel]? for the Queen of Sippar. Month of Addaru, 20<sup>th</sup> year [....]. Barley for the work in the Ebab[bar] temple: 120 kurru from Bēl-<sup>r</sup>šum<sup>1</sup>-[x] [x kurru] by agency of Danna and Ša[maš -...]; 210 kurru that from [....] 16 kurru for the year? [....].

### **618. BM 49356** (82-3-23, 347)

**PLATE 152** 

4.6 x 2.7 cm

#### 11.11.8

- 1. 2 ma-na SÍG. 「ÙZ?」 a-na
- 2. 6-a' KÙ.BABBAR <sup>md</sup>AMAR.UTU-SUR
- 3. A-šú šá <sup>m</sup>Ri-mut KÙ.BABBAR *a-n*[*a*]
- 4. md[EN]-ka-ṣir na-[din SÍG.ḤI.A?]

Edge Rev.

- 5. [a-na] ni-is-h[a šá]
- 6. ITI.ZÍZ U<sub>4</sub>.11.KAM
  - 7. MU.8.KAM
  - 8. <sup>md</sup>EN-I ma-ak-ka-su-ú
  - 9. TÚG.KUR.RA <sup>m</sup>Ha-an-ba-tu-tú
  - 10. na-din  $\{\lceil e/kal^{?_1}\}$
- L. 9. The name Hanbatutu and its etymology are unknown to me.
- L. 10. The last sign is written after a small free space and its sense is unclear.

2 minas of goat hair? for 1/6 shekel of silver, Marduk-ēţir, son of Rēmūţ has given {the silver} to Nabû-kāṣir as the payment of the month Šabatu, 11<sup>th</sup> day, 8<sup>th</sup> year. The makkasu-dates<sup>?</sup> and TÚG.KUR.RA-garment are given to Hanbatutu by<sup>?</sup> Bēl-nā'id.

### 619. BM 65133 (82-9-18, 5114)

**PLATE 152** 

 $2.6 \times 2.1$  cm

Rev.

#### 22.2.Dar 31

- 1. 1/3 ma-na 5 GÍN
- 2. gada tu-ma-nu [a-na]
- 3. IGI *mu-ṣi-e šá* [<sup>d</sup>UTU]
- 4. a-na <sup>md</sup>AG-ŠEŠ-šú
- 5. lúUŠ.BAR SUM
- 6. ITI.GU<sub>4</sub> U<sub>4</sub>.22.KAM

- 7. MU.31.KAM
- 8. <sup>m</sup>Da-a-ri-ja-<sup>r</sup>muš<sup>7</sup>
- LUGAL (sic)

25 shekels of silver for the linen yarn [for the] pan muşê-cover? [of Šamaš] was given to Nabû-uşuršu, the weaver.

Month Ayaru, 22<sup>nd</sup> day, 31<sup>st</sup> year of Darius, king (sic!).

### **620. BM 74963** = Str. II 259/2

### 5.12.Nrg 3

- 1'. 1 1/3 ma-na KÙ.BABBAR šá a-na in-[za-ḫu-ri-e-tu<sub>4</sub>]?
- 2'. a-na <sup>m</sup>Ba-la-tu A-šú šá <sup>md</sup>AG-EN-MU.「MEŠ<sup>1</sup>
- 4'. <sup>md</sup>AG-MU-SI.SÁ *a-na É-babbar-ra* 「SUM<sup>nu</sup>」
- 5'. 10 GÍN KÙ.BABBAR a-na mu-šá-na-tu<sub>4</sub> [....]
- 6'. a-na <sup>md</sup>EN-GI A <sup>md</sup>UTU-[....]
- 7'. PAP 2 ma-na 10 GÍN <sup>md</sup>EN-G[I A <sup>md</sup>UTU-[....]
- 8'. a-na É-babbar-ra it-ta-din
- 9'. ITI.ŠE U<sub>4</sub>.15.KAM MU.3.KAM
- 10'.  $^{md}$ U+GUR-LUGAL-ÙRU LUGAL TIN.TIR $^{ki}$
- L. 5'. mušanātu is not known from other texts.
- 1 mina 20 shekels of silver for *in*[*zaḫurētu*-dye<sup>?</sup>] for Balā†u, son of Nabû-bēl-šumāti:
- 40 shekels of silver, the price of 2 oxen from the fattening house Nabû-šum-līšir has given to the Ebabbar temple:
- 10 shekels of silver for the mušanātu for Bēl-ušallim, son of Šamaš-[x x], total 2 minas 10 shekels Bēl-ušallim, son of Šamaš-[x x] has given to the Ebabbar temple. Month of Addaru,  $15^{th}$  day,  $3^{rd}$  year of Neriglissar, king of Babylon.

### **621. BM 62498** (82-9-18, 2467)

 $4.5 \times 3.5$  cm

### 3.3.Dar 1

- 1. 7 GÍN KÙ.BABBAR gìn-na a-[na]
- 2. SÍG.ZA.GÌN.KUR.RA a-<sup>r</sup>na<sup>1</sup>
- 3.  $[muh-hi^?]^m$ A-a SUM<sup>na</sup>
- 4. [IT]I.SIG<sub>4</sub> U<sub>4</sub>.3.KAM
- 5. [MU].1.KAM
- 6. <sup>m</sup>Da-ri-'-muš-šú
- 7. LUGAL E<sup>ki</sup> LUGAL KUR.KUR
- 8. a-di KÙ.BABBAR IGI-ú

Aplā, probably son of Mušēzib-Marduk, ēpišānu ša ašlaki, see Bongenaar, Ebabbar, p. 316.

7 shekels of silver with *ginnu*-mark for blue-purple wool was given [on account of]  $^{?}$  Apl $\bar{a}$ .

Month of Simanu, 3<sup>rd</sup> day, 1<sup>st</sup> [year] of Darius, king of Babylon, king of Lands. (This is) together with an earlier issue of silver.

# **622. BM 83474** (83-1-21, 637)

 $4.3 \times 3.1 \text{ cm}$ 

#### [x].7.Dar 3

- 1. 1/3 ma-na 5 「GÍN¹ [KÙ.BABBAR]
- 2. a-na KI.LAM šá S[ÍG.HÉ.MÉ.DA]
- 3. *u* SÍG.ZA.GÌN.K[UR.RA]
- 4.  $a^{-1}na^{-1}$  [....]

Rest lost

Rev.

- $1.\ ITI.DU_6\ U_4.[x.KAM]$
- 2. MU.3.KAM <sup>m</sup>Da-ri-[a-muš] 3. LUGAL TIN.TIR<sup>ki</sup> LUAL KUR.K[UR]

25 shekels of [silver] for the purchase of [red wool] and blue-purple wool for [....]. Month of Tašrītu, [n<sup>th</sup>] day, 3<sup>rd</sup> year of Dari[us], king of Babylon, king of Lan[ds].

### **623. BM 66981** (82-9-18, 6976)

**PLATE 153** 

 $5.8 \times 4.4$  cm

#### 22.12.Dar 15

- 1. [1<sup>?</sup>]+[x] [ma-na] 12 ½ [GÍN KÙ.BABBAR]
- 2. 5 「GÍN 4-tú¹.LAL 「gìn-nu¹
- 3. ir-bi šá U<sub>4</sub>.20.KAM šá ITI.<sup>r</sup>ŠE<sup>1</sup>
- 4. ina lìb-bi 2 ma-na gìn-nu a-na [KI.LAM]
- 5. šá in-za-hur-ri-tu<sub>4</sub> a-na
- 6. TIN.TIR<sup>ki</sup> šu-bul-lu<sub>4</sub>
- 7. 1 ma-na a-na KI.LAM [šá]
- 8. GU<sub>4</sub> a-na <sup>m</sup>ÌR-<sup>d</sup>EN 「SUM<sup>1</sup>
- 9. 1 ma-na 12 ½ GÍN gìn-nu 5 G[ÍN la gìn-nu a-na] Rev.
  - 10. KI.LAM šá MUŠEN.HI.A ina ŠU<sup>ii</sup>
  - 11. md UTU-SUR šu-bul-lu4
  - 11a. *šá* x [x]
  - 12. 11 ½ GÍN KÙ.BABBAR *a-na* <sup>[55]</sup> [GÍN]
  - 13. SÍG.ZA.GÌN.KUR.RA šá lu-bu-uš-<sup>r</sup>tu<sub>4</sub><sup>1</sup>
  - 14. *šá ina* ITI.DU<sub>6</sub> *u* ITI.APIN MU.[16.KAM]
  - 15. [I]TI.ŠE U<sub>4</sub>.22.KAM MU.15.KAM
  - 16. [<sup>m</sup>Da]-<sup>r</sup>ri<sup>¬</sup>-mu-šú LUGAL E<sup>rki</sup>¬
  - 17. [LUGAL] KUR.K[UR]
- L. 10. ina ŠU<sup>ii</sup> is written over an erasure.
- L. 12. [55] or [58].

Note the role of Babylon as a commercial center where, at least sometimes, the Ebabbar temple purchased imported commodities instead of organizing its own commercial longdistance enterprise.

 $1^{?}+[x]$  [minas]  $12\frac{1}{2}$  rshekels of silver (and) 5 shekels minus 1/4 (shekel) with the *ginnu*-mark, the *irbu*-income of the  $20^{th}$  day of month Addaru including 2 minas (of silver) with ginnu-mark that was sent to Babylon for [the purchase] of inzahurētu-dye:

1 mina (of silver) for the purchase of an ox was given to Arad-Bēl;

1 mina 12 ½ shekels of silver with ginnu-mark (and) 5 shek[els without ginnumark] was sent by Šamaš-ēţir [for] the purchase of birds;

11½ shekels of silver for (the purchase of) [55] s[hekels of] blue-purple wool for the *lubuštu* ceremony of the month of Tašrītu and Araḥsamna [of the 16<sup>th</sup>]? year. Month of Addaru, 22<sup>nd</sup> day, 15<sup>th</sup> year of Darius, king of Babylon, [king] of Lan[ds].

#### 624. BM 82568 (Bu 93-10-14, 20)

**PLATE 154** 

 $5.1 \times 4.1$  cm

#### 4.1.Dar 28

- 1. 5 GÍN bit-qa LAL KÙ.BABBAR
- 2. a-na KI.LAM šá SÍG.ZA.GÌN.KUR.RA
- 3. erased
- 4. <sup>md</sup>AG-it-tan-nu <sup>lú</sup>UŠ.BAR bir-mu
- 5. a-na <sup>túg</sup>a-di-la-nu šá <sup>túg</sup>ku-si-tu<sub>4</sub>
- 6. dGAŠAN UD.KIB.NUN<sup>ki</sup> šá ITI.GU<sub>4</sub>

Edge

- 7. MU.28.KAM SUM<sup>in</sup>
- Rev.
  - 8. ITI.BÁR U<sub>4</sub>.4.KAM MU.28.KAM
  - 9. <sup>m</sup>Da-ri-ja-muš LUGAL E<sup>ki</sup>
  - 10. LUGAL KUR.KUR

4 7/8 shekels of silver for the purchase of the blue-purple wool was given to Nabûittannu, the multicoloured weaver, for the *adilānu*-tassel of the robe for the Queen of Sippar for the month Ayaru, 28<sup>th</sup> year.

Month of Nisannu, 4<sup>th</sup> day, 28<sup>th</sup> year of Darius, king of Babylon, king of Lands.

### 625. BM 64564 (82-9-18, 4544)

**PLATE 155** 

 $5.7 \times 4.5$  cm

#### 26.1.Dar 28

- 1. 18 GÍ[N KÙ.BABBAR *ul-tu*]
- 2. *qu-up-pu* [x1 [....]
- 3. 50 GÍN in-za-h[ur-ri-tú a-na]
- 4. <sup>md</sup>EN-*it-tan-nu* A <sup>m</sup>[....]
- 5. SUM<sup>na</sup> in-za-hur-tu<sub>4</sub>  $\lceil x \rceil$  [....]
- 6. 50 GÍN *a-na* <sup>túg</sup>ku-si-tu<sub>4</sub>
- 7. ù TÚG.GÚ.UD.DU.A šá <sup>d</sup>A-a

8. šá ITI.GU<sub>4</sub> MU.28.KAM a-na Rev.

- 9. <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>
- 10. ITI.BÁR U<sub>4</sub>.26.KAM
- 11. MU.28.KAM <sup>m</sup>Da-ri-[a'-muš] 12. LUGAL E<sup>ki</sup> LUGAL KUR.K[UR]

Bēl-ittannu might be identical with Bēl-ittannu, the ašlāku and mukabbû, see Bongenaar, Ebabbar, p. 322. His second job suggests that here inzahurētu means wool rather than dye.

18 shek[els of silver from the cash box of [....]

50 shekels of *inzaḥurētu*-wool<sup>?</sup> was given to Bēl-ittannu, son of [....].

The inzahurētu – [x mina] 50 shekels was given to Šamaš-šum-iddin, the weaver, for (manufacturing of) robe and nahlaptu-cloak for Aya for the month Ayaru, 28th

Month of Nisannu, 26<sup>th</sup> day, 28<sup>th</sup> year of Dari[us], king of Babylon, king of Lands.

# **625a. BM 75708** (83-1-18, 1058)

**PLATE 155** 

 $3.9 \times 3.3$  cm

27.1.Dar 28

- 1. 2 ma-na BABBAR
- 2. TA É *ir-bi*
- 3. a-na m Za-bi-in 4. u pu-sa-a SUM u
- 5. ITI.BÁR U<sub>4</sub>.27.KAM
- 6. MU.28.KAM

Rev.

- 7. <sup>m</sup>Da-ri-mu-šú
- 8. LUGAL TIN.TIR<sup>ki</sup>
- 9. LUGAL KUR.KUR.MEŠ

The knowledge of this tablet I owe to R. Tarasewicz who gave me his own photo and transliteration. My own collation supported his reading.

The subject of the text is not fully clear, because issue of 2 minas of silver (<KÙ>. BABBAR) for launderer seems to be too high. The more probable possibility is that wool or a white cloth was delivered to Zabīnu for cleaning.

2 minas (of) white (wool/linen?) from the *irbu*-income was given to Zabīnu, the washerman.

Month of Nisannu, 27<sup>th</sup> day, 28<sup>th</sup> year of Darius, king of Babylon, king of Lands.

**626. BM 65741** (82-9-18, 5731)

**PLATE 156** 

 $5.9 \times 7.0 \text{ cm}$ 

20.5.Cam 1

1'. [....]  $^{\Gamma}x \times x^{\gamma}$  [....] 2'.  $[x \ \check{S}]U^{ii}$   $^{md}EN-MU^{l\acute{u}}SIPA^{\Gamma}x^{\gamma}$ [....]

```
3'. ITI.NE U<sub>4</sub>.20.KAM MU.1.KAM <sup>m</sup>Kam-b[u-zi-ja]
            4'. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
            5. ina lìb-bi 1 GÍN 4-tú KÙ.BABBAR a-na 5 ma-na SÍG.HI.A
            6. a-na <sup>m</sup>ÌR-ja <sup>lú</sup>mu-pa-ṣu SUM<sup>na</sup>
            7. 1 GÍN 4-tú KÙ.BABBAR a-na 5 ma-na <sup>m</sup>SILA-a-a <sup>lú</sup>KI.MIN
            8. 1 GÍN 4-tú KÙ.BABBAR a-na 5 ma-na <sup>m</sup>Ar-ra-bi
                    <sup>lú</sup>TÚG.KAL.KAL
            9. 1 GÍN 4-tú KÙ.BABBAR a-na 5 ma-na <sup>m</sup>BA<sup>šá</sup>-a-a <sup>lú</sup>KI.MIN
           10. 1 GÍN 4-tú KÙ.BABBAR a-na 5 ma-na <sup>md</sup>UTU-TIN<sup>i</sup>t u
                lúŠEŠ.MEŠ-šú
           11. 1 GÍN 4-<sup>r</sup>tú KÙ.BABBAR a-na 5 ma-na<sup>1 m</sup>Id-di-ja
           12. 1 GÍN [4-<sup>r</sup>tú KÙ.BABBAR a-na 5 ma-na <sup>m</sup>x x x]
           13. 2 G[ÍN
           1'. [1 GÍN 4]-tú a-na <sup>[5]</sup> [....]
Rev.
           3'. 1 GÍN 4-tú a-na 5 ma-na <sup>m</sup>ÌR-<sup>rd</sup> [....]
           4'. 1 GÍN 4-tú a-na 5 ma-na <sup>m</sup>Am-bu-ru [....]
5'. 1 GÍN 4-tú a-na 5 ma-na <sup>md</sup>UTU-TIN<sup>i</sup>
           6'. 1 GÍN 4-tú a-na 5 ma-na <sup>m</sup>ÌR-<sup>d</sup>ḤAR A <sup>m</sup>Ḥa-ri-ṣa-nu
           7'. 1 GÍN 4-tú a-na 5 ma-na <sup>md</sup>UTU-KÁD A-šú šá
           8'. 1 GÍN 4-tú a-[na\ 5\ m]a-na\ ^mHa-ri-sa-nu\ [(x\ x)]
           9'. [1] GÍN 4-tú a-na <sup>「5</sup> [ma-na] <sup>f</sup>Mu-ra-na-tu<sub>4</sub>
           _____
           10'. 1 GÍN 4-tú KÙ.BABBAR a-na 5 ma-na SÍG.HI.A
           14'. [1 GÍN 4]-^{\text{r}}t\acute{u} a-na 5 ma-na ^{\text{m}}Gi-m[il-lu-(^{\text{d}}UTU)]
                    lúAŠGAB/KI.MIN]
           15'. [1 GÍN 4-tú] <sup>[</sup>a<sup>1</sup>-na 5 ma-n[a ....]
           Rest of Rev. lost
          1. [....] 5/6 ma-na KÙ.BABBAR a-na 2+ [x] GÚ.U[N x m]a-na [....]
           2. [.... e]-lat 2 GÍN KÙ.BABBAR šá a-na tu-ma-nu [....]
```

Lines 5– rev. 9' includes issue of silver for the textile craftsmen, while rev. 10'–15' concern silver for the leather workers. More about the persons mentioned there, see Bongenaar, Ebabbar, chap. IV. 2 and IV par. 4c and an Appendix in Zawadzki, *Garments of the Gods*, Vol. I.

For fluctuation of prices in the time of Cambyses in Sippar, see Jursa 2010, p. 617 (one time 3.3 minas per shekels, two times 3.5, and two times 4 shekels. The document edited here with over 20 new attestations of price enlarges importantly the base date and suggests that most typical price in the time of Cambyses was 4 shekels.

- 2. [....] by the agency of Bēl-iddin, the herdsman [....].
  3. Month of Abu, 20<sup>th</sup> day, 1<sup>st</sup> year of Cambyses,
- 4. king of Babylon, king of Lands.
- 5. out of it 1 1/4 shekels of silver for 5 minas of wool
- 6. for Ardīya, the launderer was given.
- 7. 1 1/4 shekels of silver for 5 minas of wool (for) Sūqaya, ditto
- 8. 1 1/4 shekels of silver for 5 minas (of wool for) Arrabi, the mender
- 9. 1 1/4 shekels of silver for 5 minas (of wool for) Iqīša, ditto
- 10. 1 1/4 shekels of silver for 5 minas (of wool for) Šamaš-uballit and his brothers
- 11. 1 1/4 shekels of silver for 5 minas (of wool (for) Iddiya
- 12. 1 [1/4 shekels of silver for 5 minas (of wool for) [....]
- 13. 2 [shekels of silver for ....]

#### Rest lost Rev.

- 1'. [1 1/4 shek]els (of silver) for 5 [minas (of wool for) [....]
- 2'. 1 <sup>1</sup>/<sub>4</sub> shekels (of silver) for 5 minas (of wool for) [....]
- 3'. 1 \( \frac{1}{4} \) shekels (of silver) for 5 minas (of wool for) Arad-[....]
- 4'. 1 1/4 shekels (of silver) for 5 minas (of wool for) Amburu
- 5'. 1 1/4 shekels (of silver) for 5 minas (of wool for) Šamaš-uballit
- 6'. 1 1/4 shekels (of silver) for 5 minas (of wool for) Arad-Bunene, son of Harisānu
- 7'. 1 <sup>1</sup>/<sub>4</sub> shekels (of silver) for 5 minas (of wool for) Šamaš-kāsir, son of Lū-īdīa
- 8'. 1 1/4 shekels (of silver) for 5 minas (of wool for) Hariṣānu
- 9'. 1 <sup>1</sup>/<sub>4</sub> shekels (of silver) for 5 [minas] (of wool for) <sup>t</sup>Muranātu
- 10'. 1 1/4 shekels (of silver) for 5 minas of wool for Kinenaya, the leather worker was given
- 12'. 1 1/4 shekels (of silver) for 5 minas (of wool for) Šamaš-ah-id[din
- $(x \times x)$ 13'. 1 1/4 shekels (of silver) for 5 minas (of wool for) Murā[nu, the
- leather worker ....] 14'. [1] 1/4 shekels (of silver) for 5 minas (of wool for) Gim[il(lu)-(Šamaš)]
- 15'. [1 \( \frac{1}{4} \) shekels (of silver)] for 5 minas (of wool for) [....]
- 16'. [Total x] + 50 shekels of silver for 2 [+x] tal[ents x mi]nas [of wool]
- 17'. [except for x + ] 2 shekels of silver for the yarn [....]

# XX. Miscellanea

627. BM 66988 (82-9-18, 6983)

**PLATE 157** 

 $3.5 \times 2.6$  cm

#### 4.8.Nbn 6

- 1. 「1<sup>1</sup> ma-na SÍG.HI.A
- 2. 「ina<sup>¬</sup> pap-pa-su šá 「ITI<sup>¬</sup>.GAN
- 3. <sup>m</sup>Ba-la-ţu A-šú šá
- 4. Γ<sup>md</sup>AG¹-NUMUN-DÙ SUM<sup>na</sup>
- 5. [ITI].APIN U<sub>4</sub>.4.K[AM]

Edge 6. [MU].6.KAM

7. [md]AG-I LUGAL TIN.TIRki Rev.

Balātu/Nabû-zēr-ibni appears here most probably as the owner of the baker's or brewer's prebend (see Bongenaar, Ebabbar, pp. 176-177 and 213) receiving wool instead of cereals or dates.

1 mina of wool as the prebendary income of the month Kislīmu, Balāţu, son of Nabû-zēr-ibni was given. Month of Araḥsamna, 4<sup>th</sup> day, 6<sup>th</sup> year of Nabonidus, king of Babylon.

628. BM 79604 (89-10-14, 154)

 $4.25 \times 3.1 \text{ cm}$ 

#### [x].2.Nbk 8

- 1. [x] +1 GADA sal-hi <sup>md</sup>AG-DU-NUMUN
- 2. A-šú šá <sup>md</sup>AMAR.UTU-DUB-NUMUN
- 3. lúšà-tam šá É-sag-íla
- 4. 「a-na¬ É-babbar-ra
- 5. [it]-ta-din ITI.GU<sub>4</sub>

Edge

{*u*}

- 6. [U<sub>4</sub>.x.KAM M]U.<sup>[8]</sup>.KAM
- 7. dAG-NÍG.DU-ÙRU
- 8. LUGAL TIN.TIR<sup>ki</sup>

The text was published earlier in NABU 2001, No. 60, p. 58. The sign u on the edge is clear although from the point of view of content is fully superfluous.

Nabû-mukīn-zēri, son of Marduk-šāpik-zēri, the šatammu of the Esagila temple has given [x]+1 *salhu* to the Ebabbar temple. Month of Ayaru, [x day, ye]ar 8<sup>th</sup> of Nebuchadnezzar, king of Babylon.

# 628a. BM 61192 (82-9-18, 1168)

**PLATE 157** 

 $4.4 \times 3.4$  cm

8.2.Nbn 9

- 1. 1 KÙR 4 BÁN qé-me
- 2. <sup>md</sup>Bu-ne-ne-DÙ 3. <sup>lú</sup>pu-ṣa-a-a it-ta-din
- 4. ITI.GU<sub>4</sub> U<sub>4</sub>. 8.KAM
- 5. MU.9.KAM <sup>md</sup>AG-I

Edge

6. 「LUGAL<sup>1</sup> TIN.TIR<sup>ki</sup>

1 kurru 4 sūtu of flour has been given to Bunene-ibni, the washerman. Month Ayaru, 8<sup>th</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon.

# 628b. BM 65263 (82-9-18, 5248)

**PLATE 157** 

 $4.1 \times 3.4$  cm

26.12.Nbn 9

- 1. 2 KÙR 4 BÁN qé-me
- 2. <sup>m</sup>Šu-la-a <sup>lú</sup>pu-ṣa-a-a
- 3. it-ta-din
- $4.\ ITI.\check{S}E\ U_{4}.26.KAM$
- 5. MU.9.KAM <sup>md</sup>AG-<sup>[1]</sup> 6. LUGAL TIN.TIR<sup>[ki]</sup>

Edge

 $2 \, kurru \, 4 \, s\bar{u}tu$  of flour, has been given to Šulā, the washerman. Month Addaru,  $26^{th}$  day,  $9^{th}$  year of Nabonidus, king of Babylon.

### **628c. BM 60954** (82-9-18, 930)

PLATE 158

 $4.1 \times 2.8$  cm

29.12.Nbn 9

- 1. 3 (PI) 4 BÁN 3  $q\hat{u}$   $q\acute{e}$ -me 2.  $^{\rm m}Ar$ -ra-bi  $^{\rm l\acute{u}}$ TÚG.KAL.KAL
- 3. it-ta-din ITI.ŠE

4. U<sub>4</sub>.29.KAM MU.9.KÁM 5.  $^{\rm md}$ AG-I LUGAL TIN.TIR $^{\rm ki}$ Edge

3 ( $p\bar{a}nu$ ) 4  $s\bar{u}tu$  3  $q\hat{u}$  of flour has been given to Arrabi, the mender. Month Addaru, 29<sup>th</sup> day, 9<sup>th</sup> year of Nabonidus, king of Babylon.

521 XX. MISCELLANEA

# 629. BM 65007 (82-9-18, 4988)

**PLATE 158** 

 $4.8 \times 3.4$  cm

#### 30.7.<Nbk>38

- 1. 4 ma-<sup>r</sup>ši<sup>¬</sup>-hi <sup>r</sup>šá<sup>¬</sup> [ZÚ.LUM.MA]
- 2. ina ma-ši-hi šá sat-tuk
- 3. ina ki-is-ki-<sup>r</sup>ri<sup>7</sup> šá
- 4. ina maš-šar-tu<sub>4</sub> šá ITI.GAN
- 5. a-na <sup>m</sup>Ṣil-la-a

6. lúTÚG.BABBAR SUM<sup>na</sup> Rev.

- 7. 1 (PI) 5 BÁN ZÚ.LUM.MA
- 8. <sup>m</sup>Ri-mut i-di-šú
- 9. šá a-na UGU ZAG.LU
- 10.  $\lceil i^? li^? \rceil ki \text{ SUM}^{na}$
- 11. [IT]I.DU<sub>6</sub> U<sub>4</sub>.30.KAM
- 12. MU.38.KAM L.e.

The most important information which we gather from this text is that the kiskirru payment was used to pay maššartu for Şillāya, the ašlāku.

L. 7. Note that BÁN is written only with 2 horizontal wedges.

4 mašihu-measures of [dates] in the sattukku-measure from kiskirru-payment as the maššartu of the month Kislīmu was given to Şillāya, the bleacher.

1 (pānu) 5 sūtu of dates which were delivered on account of imittu-payment, are given to Rēmūt (as) his wage. Month of Tašrītu, 30<sup>th</sup> day, 38<sup>th</sup> year.

#### **630. BM 83699** (83-1-21, 862)

**PLATE 159** 

 $3.6 \times 2.9$  cm

#### 24.5.Nbn 2

- 1. 1 (PI) 4 BÁN ŠE.BAR 1 $^{en}$  dan-nu KAŠ.SAG DÙG.GA 2.  $^{m}$ Ba-la-ṭu A-šú šá  $^{md}$ AG-EN-MU.MEŠ 3.  $^{[1\acute{u}]}$ UŠ.BAR ina pap-pa-si-šú

- 4. [ma]-hir ITI.NE
- 5. U<sub>4</sub>.24.<KAM> MU.2.KAM

6. dAG-I Edge

7. LUGAL TIN.TIR<sup>ki</sup> Rev.

1 pānu 4 sūtu of barley, 1 jar of choicest strong beer, Balāṭu, son of Nabû-bēlšumāti, the weaver has received as his prebendary income. Month of Abu,  $24^{th}$  day,  $2^{nd}$  year of Nabonidus, king of Babylon.

**630a. BM 58976** (82-7-14, 3385)

**PLATE 159** 

 $3.8 \times 2.3$ 

#### 24.5.[Nbn 2]

- 1. 1<sup>en</sup> <sup>r</sup>dan¹-nu KAŠ.SAG DÙG.GA
- 2. a-na <sup>m</sup>Ba-la-ṭu A-šú šá
- 3. md AG-EN-MU.MEŠ lúUŠ. BAR
- 4. 「ITI.NE U<sub>4</sub>.24.KAM<sup>1</sup>

### Rest lost

Evidently the tablet concerns the issue of one of two commodities, which are the subject of tablet No. 630, as both texts were written on the same day. Because this document concerns only beer, it seems that it was written for the department or persons responsible for the manufacture and delivery of beer, while text No. 630 was intended for the general accounting office noting all the transactions of Balāţu/Nabû-bēl-šumāti.

1 jar of choicest strong beer to Balāţu, son of Nabû-bēl-šumāti, the weaver. Month Abu, 24<sup>th</sup> day [....].

630b. BM 78548 (Bu 88-5-12, 457)

PLATE 160

4.3 x 3.1 cm

#### 28.5.Nbn 2

- 1. 3 (PI) 2 BÁN ŠE.BAR ba-ab-tu<sub>4</sub>
- 2. 1 KÙR ŠE.BAR 1<sup>en</sup> dan-nu
- 3. KAŠ.SAG DÙG.GA a-na
- 4. <sup>m</sup>Ba-la-tu <sup>lú</sup>UŠ.BAR 5. SUM $^{in}$  2 (PI) 3 BÁN 3 qa
- 6. ŠE.GIŠ.Ì ina ŠU<sup>ii</sup>

Edge Rev.

- 7. <sup>m</sup>BE-*ja ina lìb-bi*
- 8. 2 ma-ši-ḫi [šá] sat-tuk
- 9. *a-na* <sup>m</sup>*Mu-* <sup>r</sup>*ra* <sup>1</sup>-*nu*
- 10.  $^{\text{lú}}$ Ì.SUR SUM $^{\text{r}^{in}}$
- 11. ITI.NE U<sub>4</sub>.28.KAM
- 12. MU.2.KAM <sup>d</sup>AG-I
- 13. LUGAL TIN.TIR<sup>ki</sup>

3 pānu 2 sūtu of barley, the outstanding amount from 1 kurru of barley (and) one jar of choicest strong beer were given to Balāţu, the weaver.

2 pānu 3 sūtu 3 qû of sesame from Kabtīya, in addition to 2 sattukku measure which were given to Murānu, the oil-presser.

Month of Abu, 28<sup>th</sup> day, 2<sup>nd</sup> year of Nabonidus, king of Babylon.

523 XX. MISCELLANEA

# **631. BM 83528** (83-1-21, 691)

 $4.0 \times 3.7$  cm

#### 1.6.[Nbn] 11

- 1.  $\frac{1}{2}$  GÚ.UN <sup>síg</sup>ti- $\frac{1}{2}$ ti- $\frac{1}{2}$ tu]
- 2. *ina pap-pa-su* <sup>lú</sup>MU-[ú-tu] 3. <sup>md</sup>UTU-DÙ u <sup>m</sup>Ṣi[l-la-a-a SUM]
- 4. [ITI].KIN  $U_4.11$ .[KAM] 5. MU.11.KAM  $^m[^dAG$ -I]
- 「LUGAL<sup>1</sup> [Bābilî]

The reconstruction of the year is based on the period of activity of both bakers, see Bongenaar, Ebabbar, p. 177f. However, it is strange that yarn was given as prebendary income to persons not connected with the textile industry department.

30 minas of yarn as the prebendary income of the baker's prebend (for) Šamaš-ibni and Ṣillāya [was given].

[Month] of Ulūlu, 11<sup>th</sup> day, 11<sup>th</sup> year of [Nabonidus], king of Babylon.

#### **632. BM 60135** = Str. II 302/2

PLATE 160

 $3.6 \times 3.0$  cm

#### 7.2.Nbn 4

- 1. 7 ½ GÍN ti-im 2.  $^{\rm m}$ Šu-la-a  $^{\rm l\acute{u}}$ rUй.BAR GADA
- 3. a-na É-babbar-ra
- 4. it-ta-din

Rev.

- 5. ITI.GU<sub>4</sub> U<sub>4</sub>.7.KAM
- 6. MU.4.KAM <sup>md</sup>AG-I 7. LUGAL TIN.TIR<sup>ki</sup>

Šulā, identical with Šulā/Ebabbar-lūmur, išpar kitê and pūṣaya as suggested by Bongenaar, Ebabbar, p. 351, who cites this text.

7 ½ shekels of yarn Šulā, the linen weaver has delivered to the Ebabbar temple. Month of Ayaru, 7<sup>th</sup> day, the 4<sup>th</sup> year of Nabonidus, king of Babylon.

# 633. BM 74663 (82-9-18A, 388)

18<sup>?</sup>.10.Cyr 5

- 1. 3 ½ ma-na SÍG.ḤI.A
- 2. TA É.ŠU<sup>ii</sup> KÁ-*tu*<sub>4</sub>
- 3. 7 ma-na SÍG.HI.A
- 4. ma-la-a-ta šá É <sup>d</sup>AMAR.UTU

- 5. šá MU.5.KAM a-na
- 6. [<sup>md</sup>AG]-ŠEŠ.MEŠ-GI Rev.
  - 7. [SUM<sup>na</sup>] ITI.AB U<sub>4</sub>.1<sup>r</sup>8<sup>1</sup>.KAM

  - 8. MU.5.KAM <sup>m</sup>Ku-ra-áš 9. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR
- L. 6. Most probably identical with Nabû-aḥḥē-šullim/Mušēzib-Marduk//Šangû-Ištar-Bābili, see Bongenaar, Ebabbar, p. 252 and p. 259.
- 3 ½ minas of wool from the  $b\bar{\imath}t$   $q\bar{a}ti$ -storehouse, the remaining from 7 minas of wool, the  $mal\bar{a}tu$  of the chapel of Marduk for the 5<sup>th</sup> year, (which) [was given to Nabû]-ahhē-šullim.

Month of Ţebētu, 18<sup>th</sup> day, 5<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

### 634. BM 101489 (83-1-21, 3150)

 $3.8 \times 3.1$  cm

15.7.Cyr 8

- 1. 4 (PI) 1 BÁN ŠE.BAR [pap-pa-su]
- 2.  $^{\text{lú}}$ UŠ.BAR- $\acute{u}$ -t[u (xxx)]
- 3. *a-na* <sup>md</sup>UTU-MU-MU S[UM<sup>na</sup>]
- 4. ITI.DU<sub>6</sub> U<sub>4</sub>.15.KAM MU.8.KAM
- 5. [<sup>m</sup>Ku]r-raš LUGAL E<sup>ki</sup> LUGAL KUR.KUR

 $4 p\bar{a}nu \ 1 s\bar{u}tu$  of barley, [the prebendary income] of the weaver's prebend [(x x x)] was given to Šamaš-šum-iddin. Month of Tašrītu, 15<sup>th</sup> day, 8<sup>th</sup> year of Cyrus, king of Babylon, king of Lands.

### **635. BM 63882** (82-9-18, 3850) = Bertin 1294

 $4.5 \times 3.4$  cm

### 3.5.Nbn [1]4

- 1. 1 KÙR 2 (PI) 3 BÁN ZÚ.LUM.MA
- 2. *ina pap-pa-su* <sup>lú</sup>UŠ.BAR-*ú-tu* 3. ŠUKU.ḤI.A ITI.SIG<sub>4</sub> ITI.ŠU *ù* ITI.NE
- 4. <sup>md</sup>AG-PAP-A u <sup>m</sup>Ba-ku-ú-a

5. [IT]U.NE U<sub>4</sub>.3.KAM Rev.

- 6. MU.[10+]4.KAM <sup>md</sup>AG-I
- 7. LUGAL TIN.TIR<sup>ki</sup>

1 kurru 2 pānu 3 sūtu of dates from the prebendary income of the weavers, the payment for the month of Simanu, Du'ūzu and Abu, Nabû-nāṣir-apli and Bakûa (have received).

Month of Abu, 3<sup>rd</sup> day, [1]4<sup>th</sup> year of Nabonidus, king of Babylon.

# **636. BM 65057** (82-9-18, 5038)

 $3.5 \times 5.1$  cm

- 1. <sup>m</sup>*Ba-zu-zu*
- 2.  $^{\mathrm{md}}Bu\text{-}ne\text{-}ne\text{-}\mathrm{D}\acute{\mathrm{U}}$
- 3. mdEN-ŠEŠ-GÁLši
- 4. mdAG-DA
- 5. <sup>m</sup>Ri-mut
- 6. md UTU-NUMUN-DÙ
- 7. <sup>m</sup>Su-qa-a-a

8.  $\lceil x \rceil [x] IGI^m Ba-zu-zu$ 

Rest lost

Rev.

- 1. [<sup>m</sup>Šu-la-a] 2. [<sup>md</sup>AMAR].UTU-ŠEŠ-MU 3. [<sup>md</sup>]UTU-tab-ni-ÙRU 4. [<sup>md</sup>]UTU-SIPA-ú-a

- 5. [m]*Ki-i-*dUTU
- 6. [m]LUGAL-dUTU-ja
- 7. mdEN-MU
- 8. <sup>f</sup>Mu-ra-na-tu<sub>4</sub>

- 9. PAP 8 UŠ.BAR GADA
- 10. [ina] IGI <sup>m</sup>Šu-la-a

L. 8. At the very beginning of the line tiny traces of a sign are preserved, which could be  $r^{l\acute{u}}$ or 'PAP'; however, there is no space to write the expected US.BAR GADA, because the comparison with other texts makes it certain that the first group supervised by Bazuzu also comprised linen weavers.

Bazuzu, Bunene-ibni, Bēl-aḥ-ušabši, Nabû-ile'i, Rēmūt, Šamaš-zēr-ibni, Sūqaya, <sup>r</sup>total<sup>1</sup> [7] < linen weavers> at disposal of Bazuzu.

[Šulā], [Mar]duk-ah-iddin, Šamaš-tabni-usur, Šamaš-rē'ûa. Kī-Šamaš, Šarrušamšaya, Bēl-iddin, <sup>1</sup>Murānātu, total 8 linen weavers [at] disposal of Šulā.

# **637. BM 62099** (82-9-18, 2068)

PLATE 161-162

 $9.8 \times 7.2$  cm

List of rations delivered to the various groups of the temple personnel, among them the weavers.

Obv. Col. I

Beginning lost

1'. [x x x x] [....]

<sup>md</sup>UTU-DU-ŠEŠ *šá* ŠUKU.ḤI.A LU[GAL] 2'. 1 KÙR

3'. 1 KÙR

 $^{md}UTU\text{-}\check{S}E\check{S}\text{-}MU$ 

```
^{\mathrm{md}}\mathrm{UTU\text{-}TIN}^{it}
               4'. 1 KÙR
                                                             <sup>md</sup>UTU-「SUḤUЬ-ja-DU
               5'. 1 KÙR
                                                             <sup>md</sup>UTU-ri-su-ú-a
               6'. 1 KÙR
                                                             ^{\rm m}Ki-i-^{\rm d}UTU
               7'. 1 KÙR
                                                             ^{\rm m} \check{S} E \check{S} \text{-} \check{s} \acute{u} \text{-} n u
               8'. 2 (PI) 3 BÁN
                                                             mdEN-at-ta-DA
               9'. 2 (PI) 3 BÁN
              10'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>ZÁLAG-<sup>d</sup>UTU
                                                              ^{\mathrm{md}}UTU-SUḤUŠ-DU 2^{\acute{u}}
              11'. 2 (PI) 3 BÁN
                                                             ^{md}UTU-AD-ÙRU
             12'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>Ina-GIŠ.MI-<sup>d</sup>U+GUR
             13'. 2 (PI) 3 BÁN
              14'. PAP 12 ERÍN.MEŠ šá ŠUKU.HI.A LUGAL
                                                             ^{\mathrm{m}}ÌR-a^{\mathrm{l}\acute{\mathrm{u}}}ÌR É.GAL
             15'. 1 KÙR
                                                 ^{\mathrm{md}}UTU-[x-x]-a/A
             16'.
                                                             md [....]
md UTU-[x1[....]
             17'. 1 KÙR
             18'. 1 KÙR
                                                              <sup>m</sup>ZÁLAG-[....]
             19'. 1 KÙR
                                                             ^{\mathrm{md}}AG-ÚŠ-TIN^{it_1}
             20'. 1 KÙR
                                                             ^{m}ÌR-^{d}AG
             21'. 1 KÙR
                                                             ^{md}D\grave{U}^{t\acute{u}}\text{-}KAM
             22'. 1 KÙR
                                                             m<sup>r</sup>d<sup>1</sup>[....]
             23'. 2 (PI) 3 BÁN
Rest lost
Col. II
Beginning lost
                                                              [^m....]
               1'. 1 KÙR
                                                             <sup>m</sup>[....]
               2'. 1 KÙR
                                                             <sup>md</sup>[....]
               3'. 1 KÙR
                                                              <sup>m</sup>Lib-[luṭ]
               4'. 1 KÙR
                                                             md A[G-....]
               5', 1 KÙR
                                                             <sup>m</sup>[....]
               6'. 1 KÙR
                                                             md AG-[....]
               7'. 1 KÙR
                                                             mdUTU-ši-[man-ni]
               8'. 1 KÙR
                                                             ^{\text{md}}AG-up-[ni-ja]
               9'. 1 KÙR
                                                              <sup>m</sup>NÍG.DU
              10'. 1 KÙR
              11'. PAP 11 <sup>lú</sup>UŠ.BA[R GADA]
                                                             ^{md}UTU\text{-}\check{S}E\check{S}\text{-}M[\overset{\circ}{U}^?]
             12'. 1 KÙR
                                                             ^{md}U+GUR-M[U^?]
             13'. 1 KÙR
                                                             m[d?] EN^{1}-I
             14'. 1 KÙR
             15'. [....]
                                                              \lceil_{X}\rceil_{X}
              16'. [....]
                                                             ^{\rm m}Ri-^{\rm \Gamma}mut<sup>?</sup>
             17'. 1 [KÙ]R
```

XX. MISCELLANEA 527

```
mdDI.[KUD?-...
             18'. 1 KÙR
                                                             ^{md}\Gamma x^{1} [....]
             19'. 1 KÙR
Rev. Col. I
Beginning lost
                                                            m[....] m\Gammad?\gamma[....]
               1'. erasure
               2'. 2 (PI) 3 BÁN
                                                             ^{\mathrm{md}_{\Gamma}}x^{\gamma}\left[ ....\right]
               3'. 2 (PI) 3 BÁN
                                                             mdUT[U- ....]
               4'.2 (PI) 3 BÁN
                                                             <sup>m</sup>ŠEŠ-[....]
               5'. erasure
                                                             <sup>md</sup>UT[U- ....]
               6'. 2 (PI) 3 BÁN
                                                             ^{md}A[G-....]
               7'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>ŠEŠ-[....]
               8'. 2 (PI) 3 BÁN
                                                             ^{m_{\Gamma}d}{}^{\eta}U[TU\;....]
               9'. erasure
                                                             <sup>md</sup>ΓUTU<sup>?</sup><sup>1</sup>-[....]
              10'. 2 (PI) 3 BÁN
                                                             ^{\text{md}}Bu-n[e-ne-x]
              11'. erasure
                                                             ^{\text{md}}UTU-B[A^{\check{s}\acute{a}}]
             12'. 2 (PI) 3 BÁN
                                                             ^{\mathrm{m}}\check{S}\acute{a}^{-\Gamma^{\mathrm{d}?}}[....]
             13'. rasure
                                                             14'. 2 (PI) 3 BÁN
             15. PAP 21 [^{l\acute{u}}....]
             _____
                                                             <sup>m</sup>[....]
             16'. 1 KÙR
                                                             [<sup>m</sup> ....]
              17'. 2 (PI) 3 BÁN
             18'. 1 'KÙR' [....]
Rev. Col. II
                                                             [^m....]
               1'. 2 (PI) 3 BÁN
               2'. 2 (PI) 3 BÁN
                                                             [....]
                                                             <sup>m</sup>La-qip
               3'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>Ḥa-an-ni-ja
               4'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>ZÁLAG-<sup>ď</sup>UTU šá É <sup>d</sup>GAŠAN Sip-
               5'. 2 (PI) 3 BÁN
                                                             par<<sup>ki</sup>>
                                                             <sup>m</sup>Ṣu-na-bu-na-aḥ
               6'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>Ina-pa-ṭar-da-nu
               7'. 2 (PI) 3 BÁN
                                                             ^{\mathrm{m}}UTU-ma-ti-i-ra-mu
               8'. 2 (PI) 3 BÁN
                                                             ^{\rm m}Ki-i-^{\rm d}AG
               9'. 2 (PI) 3 BÁN
                                                             ^{\mathrm{md}} [UTU]-TIN^{it}
              10'. 2 (PI) 3 BÁN
                                                             <sup>m</sup>Na-ni-ja
              11'. 2 (PI) 3 BÁN
                                                             ^{m}DU-A
             12'. 2 (PI) 3 BÁN
             13' 2 (PI) 3 BÁN
                                                             <sup>m</sup>EN-šú-nu
                                                             ^{\text{md}}AG-ja-a-^{\Gamma}nu^{?_{1}}
             14'. 2 (PI) 3 BÁN
                                                             ^{\mathrm{md}}UTÜ-ina-SÙḤ-ÙRU
              15'. erasure
             16'. PAP 15 <sup>lú</sup>NI.DU<sub>8</sub>.MEŠ
```

17'. 2 (PI) 3 BÁN	<sup>m</sup> ZÁLAG- <sup>d</sup> UTU <i>šá</i> UGU <i>qu-up-pu</i>
18'. 2 (PI) 3 BÁN	<sup>m</sup> AD-il-tam-meš
	d 1%
19'. 1 KÙR	<sup>md</sup> UTU-SU <sup>lú</sup> šá-qa-a-a
20'. erasure	<sup>m</sup> EN- <i>šú-nu</i>
<i>,</i>	
21'. 2 (PI) 3 BÁN	<sup>md</sup> UTU-ŠEŠ-MU
22'. 2 (PI) 3 BÁN	<sup>m</sup> Kal-ba-a
23'. erasure	<sup>m</sup> Šá- <sup>d</sup> AG-šu-ú
24'. 2 (PI) 3 BÁN	<sup>md</sup> DÙ <sup>tú</sup> -KAM
25'. 2 (PI) 3 BÁN	<sup>m</sup> Šá-du-ni-DINGIR
26'. 2 (PI) 3 BÁN	<sup>m</sup> Si-lim-[

Rev. II 14. The reading of the last sign is uncertain, maybe u not nu.

Obv. Col. I [Total x]----- workers

1 kurru	Šamaš-mukīn-aḫi of the king's ration
1 <i>kurru</i>	Yatıon Šamaš-aḫ-iddin
1 <i>kurru</i>	Šamaš-uballit
1 kurru	Šamaš-išdija-ukīn
1 kurru	Šamaš-rişûa
1 <i>kurru</i>	Kī-Šamaš
2 pānu 3 sūtu	Ahušunu
2 pānu 3 sūtu	Bēl-atta-tale'i
2 pānu 3 sūtu	Nūr-Šamaš
2 pānu 3 sūtu	Šamaš-išdi(ja)-ukīn, the second one <sup>4</sup>
2 pānu 3 sūtu	Šamaš-abu-uşur
2 pānu 3 sūtu	Ina-şilli-Nergal
Total 12 workers of the	king's ration
 1 <i>kurru</i>	Ardīya, the builder
	Šamaš-[]
1 kurru	[]
1 <i>kurru</i>	Šamaš-[]
1 kurru	Nūr-[]
1 kurru	Nabû-mīta-uballiţ
1 <i>kurru</i>	Arad-Nabû
1 <i>kurru</i>	Banitu-ēreš
1 10001 1 00	

<sup>&</sup>lt;sup>4</sup> 2- $\dot{u}$  means here not "second instalment", but "second (person of the same name").

XX. MISCELLANEA 529

```
Obv. Col. II
             1 kurru
                                                         [....]
             1 kurru
                                                         [....]
             1 kurru
                                                         [....]
                                                         Lib[lut]
             1 kurru
             1 kurru
                                                         Nabû-[....]
            [1 kurr]u
                                                         [....]
                                                         Nabû-[....]
             1 kurru
             1 kurru
                                                         Šamaš-ši[manni]
             1 kurru
                                                         Nabû-up[nīya]
                                                         Kudurru
             1 kurru
            Total 11 [linen] weavers
                                                         Šamaš-ah-i[ddin]
             1 kurru
             1 kurru
                                                         Nergal-i[ddin]
                                                         「Bēl<sup>1</sup>?-na'id
             1 kurru
                                                         \Gamma_{X \ X}
            [1 kurru]
            [1 kurru
                                                         x x
                                                         Rē[mūt]?
            \lceil 1 \ kurru \rceil
                                                         Ma[dānu<sup>?</sup>-....]
             1 kurru
             1 kurru
                                                         [....]
Rev. Col. I
             <sup>r</sup>2 pānu 3 sūtu<sup>1</sup> (erasure<sup>?</sup>)
                                                         [....]
            2 pānu 3 sūtu
                                                         [....]
            2 pānu 3 sūtu
                                                         [....]
                                                         Ša[maš?-....]
            2 pānu 3 sūtu
            <sup>[2]</sup> pānu 3 sūtu<sup>[]</sup> (erasure<sup>?</sup>)
                                                         Aḥu-[....]
                                                         Šamaš-[....]
            2 pānu 3 sūtu
            (erasure)
                                                         Ša[maš-....]
            <sup>r</sup>2 pānu 3 sūtu<sup>1</sup> (erasure<sup>?</sup>)
                                                                Nabû-[....]
            2 pānu 3 sūtu¹
                                                                Ahu-[....]
            <sup>[2]</sup> pānu 3 sūtu<sup>[1]</sup> (erasure<sup>?</sup>)
                                                                 Ša[maš ?-....]
            <sup>r</sup>2<sup>¬</sup> pānu 3 sūtu
                                                                Bun[ene-....]
            2 pānu 3 sūtu
                                                                Šamaš-iq[īša ...
            <sup>7</sup>2 pānu 3 sūtu<sup>1</sup> (erasure<sup>?</sup>)
                                                                Ša-[....]
            2 pānu 3 sūtu
                                                                [....]
            Total 21 [....]
            ----- [....]
             1 kurru
                                                                [....]
            2 pānu 3 sūtu
                                                                [....]
             -----
                                                                [....]
```

1 *kur*[*ru* ....]

# Rev. Col. II

••••		
<sup>r</sup> 2 pānu 3 sūtu <sup>1</sup>	[]	
2 pānu 3 sūtu	[]	
2 pānu 3 sūtu	Lāqīpu	
2 pānu 3 sūtu	Hanniya	
2 pānu 3 sūtu	Nūr-Šamaš of the Queen of	
	Sippar temple	
2 pānu 3 sūtu	Şunabunah	
2 pānu 3 sūtu	Ina-paṭar-danu	
2 pānu 3 sūtu	Šamaš-māti-irâmu	
2 pānu 3 sūtu	Kī-Nabû	
2 pānu 3 sūtu	Šamaš-uballiţ	
2 pānu 3 sūtu	Naniya	
2 pānu 3 sūtu	Mukīn-apli	
2 pānu 3 sūtu	Bēlšunu	
2 pānu 3 sūtu	Nabû-jānu?	
2 pānu 3 sūtu	Šamaš-ina-tēši-uşur	
Total 15 gatekeepers		
2 pānu 3 sūtu	Nūr-Šamaš in charge of the box	
2 pānu 3 sūtu	Abu-iltammeš	
1 7	· ·	
1 kurru	Šamaš-erība, the sack maker Bēlšunu	
2 = 2 =	Č d. :	
2 pānu 3 sūtu	Šamaš-aḫ-iddin	
2 pānu 3 sūtu	Kalbā	
	Ša-Nabû-šū	

Banītu-ēreš

Šadūni-ilī

Silim-[....]

# **638. BM 49607** (82-3-23, 598)

2 pānu 3 sūtu

2 pānu 3 sūtu

 $2\;p\bar{a}nu\;3\;s\bar{u}tu$ 

PLATE 163

 $5.5 \times 3.5$  cm

# 6.5.Nbp 16

1. [si]-di(!?)- $t\acute{u}$  š $\acute{a}$  ITI.NE MU.1 $^{\mathsf{f}}$ 6 $^{\mathsf{l}}$ .[KAM]

2. <sup>m</sup> A-ḫu-nu ŠUKU.ḤI. <a>- šú</a>	e-ţir
3. <sup>md</sup> AG-ŠEŠ.MEŠ- <i>šul-lum</i> KI.MIN	e-ṭir
4. <sup>m</sup> <i>I-di-</i> DINGIR <i>šá</i> É.GU <sub>4</sub> KI.MIN	e-tir

531 XX. MISCELLANEA

	5. <sup>m</sup> I-di-DINGIR šá KÁ	e-ṭir
	6. <sup>md</sup> UTU-SU <i>šá</i> KÁ	e-ṭir
	7. <sup>md</sup> UTU-ŠEŠ-MU <sup>lú</sup> UŠ.BAR <i>bir-ri</i>	e-ṭir
	8. <sup>md</sup> UTU-AŠ-PAP <sup>lú</sup> ṣ <i>a-pu-ú</i>	e-ṭir
Edge	9. <sup>m</sup> 「NUMUN¹-ja <sup>lú</sup> UŠ.BAR <i>bir-ri</i>	$e^{-\Gamma}tir^{\gamma}$
_	10. <sup>md</sup> U+GUR-TIN <sup>it lú</sup> UŠ.BAR <i>bir-ri</i>	e-[tir]
Rev.	11. <sup>md</sup> PA-ÚŠ-TIN <sup>iį lú</sup> [SIM]UG UD.KA.BAR	e-ṭir
	Free space of about 2 lines	
	12. ITI.NE U <sub>4</sub> .5.KAM MU.16.KAM	
	13. <sup>md</sup> AG-A-PAP LUGAL TIN.TIR <sup>ki</sup>	

# L. 1. The first partly preserved sign is similar to $\lceil li \rceil$ .

# [(Travel) pro]vison? for the month Abu, 1<sup>r</sup>6<sup>th¹</sup> [year]

Aḫunu, his ration	is paid
Nabû-aḥhē-šullum, ditto	is paid
Idi-ilī, of the cattle shed, ditto	is paid
Idi-ilī, of the gate, <i>ditto</i>	is paid
Šamaš-erība, of the gate, <i>ditto</i>	is paid
Šamaš-aḥ-iddin, the multicoloured weaver,	is paid
Šamaš-edu-uṣur, the dyer,	is paid
Zēriya, the multicoloured weaver,	is paid
Nergal-uballit, the multicoloured weaver,	is pa[id]
Nabû-mīṭa-uballiṭ, the bronze smith,	is paid
Month Abu, 5 <sup>th</sup> day, 16 <sup>th</sup> year of Nabopolass	ar, king of Babylon.

# **639. BM 66012** (82-9-18, 6004)

PLATE 164

 $6.5 \times 5.3$  cm

# $[(x^?)]+4.[Cyr] 4$

- 1. [.... TA ITI. x] *a-di qí-it*
- 2. [šá ITI.x MU.4.KÁM <sup>m</sup>Ku(r)-raš LUGAL TIN].「TIR<sup>1ki</sup> LUGAL KUR.KUR
- 3. [a-na lúUŠ.BAR GADA lúTÚG].KAL.KAL.MEŠ 4. [šá dul-lu ina UGU lúd Ku-raš li-pu-šu]-lxl ul-tu É-babbar-ra
- 5. [SUM<sup>*na*</sup>]

- 5. [SUM<sup>\*\*\*</sup>]
  6. [<sup>md</sup>HA]R-<sup>r</sup>DÙ¹ <sup>m</sup>Lib-luṭ <sup>md</sup><sup>r</sup>EN¹-MU <sup>md</sup>AG-DA
  7. [<sup>md</sup>UTU-SI]PA-ú-a <sup>m</sup>ÌR-<sup>d</sup><sub>r</sub>Bu¹-ne-ne (erasure) <sup>md</sup>UTU-MU
  8. [<sup>m</sup>Lu]-<sup>r</sup>ú¹-i-di-ja <sup>md</sup>UTU-ŠEŠ-MU <sup>md</sup>UTU-ŠEŠ.MEŠ-bul-liṭ
  9. [<sup>m</sup>Ba]-<sup>r</sup>zu¹-zu <sup>m</sup>LUGAL-<sup>d</sup>UTU-ja <sup>m</sup>AD-NU-ZU <sup>md</sup>AG-SIG<sub>5</sub><sup>iq</sup>
  10. [<sup>f</sup>M]u-ra-na-tu₄ PAP 15 <sup>lú</sup>UŠ.BAR GADA <sup>md</sup>HAR-ši-man-ni
  11. [x x x x] <sup>rm</sup>ìR-ja <sup>md</sup>rBu¹-ne-ne-LUGAL-ŠEŠ
  12. [<sup>m</sup>x x x] <sup>md</sup>UTU-TIN<sup>iṭ m</sup>ÌR-<sup>d</sup>A-nu-ni-tu₄

```
Rev. 13. [<sup>m</sup>x x x <sup>m</sup>]AG-si-in-qí-ja-pu-ṭur

14. [PAP 9<sup>?</sup>] <sup>1ú</sup>TÚG.KAL.KAL.ME[Š] 「šá¹ ŠU<sup>ii</sup>

15. [<sup>md</sup>ḤAR]-ši-man-ni ŠUKU.ḤI.A-šu-nu i-「na¹ ŠU<sup>ii</sup>

16. [<sup>md</sup>ḤA]R-ši-man-ni 「e-ṭir-u'¹

(free space for ca 2 lines)

17. [<sup>lú</sup>mu-kin-nu <sup>m</sup>]「x x¹ DU 「x ÙRU A-šú² šá²¹ <sup>m</sup>Ṣil-la-a

18. [x x x X A-šú] šá <sup>m</sup>DUB-NUMUN <sup>m</sup>MU- <sup>d</sup>AG A-šú šá <sup>m</sup>BA<sup>šá</sup>-a

19. [<sup>m</sup>x x A-šú šá <sup>m</sup>x x <sup>md</sup>]ḤAR-ŠEŠ-MU A-šú šá <sup>m</sup>ŠEŠ-šú-nu

20. [<sup>m</sup>x x x x x] A-šú šá <sup>m</sup>Ba-zu-zu

21. [(u) <sup>lú</sup>ŠID <sup>m</sup>ÌR- <sup>d</sup>EN A-šú] šá <sup>md</sup>EN-GI A <sup>md</sup>IM-šam-me-e

22. [UD.KIB.NUN<sup>ki</sup> ITI.x U4]. <sup>[41</sup>.KAM MU.4.KAM

23. [<sup>m</sup> Ku(r)-raš LUGAL TIN.TIR<sup>ki</sup>] u KUR.KUR
```

Reconstruction of the missing part of text in lines 1-4 is difficult, although it seems possible that there was information about a provision for linen weavers and cloth menders, treated as two separate, but in some way cooperating groups. The following reconstruction might be suggested:

1a. [x KÙR (x PI x  $q\hat{u}$ ) ZÚ.LUM.MA / ŠE.BAR/ $q\acute{e}$ -me (NÍG.GA  $^{\rm d}$ UTU) ŠUKU.ḤI.A šá TA ITI.x], or

lb. [<br/>  $[iup\text{-}pi\ š\acute{a}\ x\ K\`\text{U}R\ (x\ PI\ x\ q\^{u})\ Z\'\text{U}.\text{LUM.MA}$  / ŠE.BAR/ <br/>  $q\acute{e}\text{-}me\ (N\'\text{IG.GA}\ ^d\text{UTU})\ \text{ŠU-KU.HI.A}\ s\acute{a}\ \text{TA}\ \text{ITI.x}]$ 

The second reconstruction is more probable because that text cannot be treated as a typical administrative document, but rather as a contract with linen weavers and cloth menders who took the responsibility to complete some work. If our reconstruction of the king's name is correct, it is highly probable that they participated in the building of a new canal in the vicinity of Sippar named in a text dated to the 5<sup>th</sup> year as "Cyrus canal" (concerning this work, see MacGinnis, *Letter Orders*, p. 194 and Zawadzki, AOAT 252, pp. 599–602). They could have received dates, barley or flour, because it is highly improbable that they had mill stones for producing flour. This is supported by CT 56, 752 (9.9.Cyr 5), CT 55, 41 (10.9.Cyr 5), Cyr 209 (24.9.Cyr 5), Cyr 187 (9.-.Cyr 5), Cyr 207 (-.9.Cyr 5), BM 62430 = MacGinnis, *Letter Orders*, No. 11 (6.10.Cyr 5), BM 99540 = MacGinnis, *Letter Orders*, No. 10 (11.9. Cyr 5), CT 57, 807 (--. Cyr 6), CT 55, 23 (date broken, but time of Cyrus, not before Cyr 2 because of presence of Bunene-ibni, *rab bīt kīli*, active in this position from this year, see Bongenaar, *Ebabbar*, p. 114 and 124) and BM 84081 = MacGinnis, *Letter Orders*, No. 124 (12.10 <Cyr 5<sup>?</sup>>) where workers digging canal received flour.

The reconstruction of the king's name is based on the fact, that, out of 15 linen weavers, four (Bunene-ibni, Bazuzu, Šarru-šamšaja and Muranātu) are not active later than time of Cyrus. If our reconstruction is correct, it means that the building of the canal, named later as Nār Kuraš was already in progress in the fourth year of Cyrus and was continued in his 6<sup>th</sup> year.

Note that Šamaš-iddin (l. 7), the linen weaver, was not known before. Also Ardīya, *mukabbû* (l. 11), was not known before, although he might be identical with Ardīya, *mupaṣṣû* (Bongenaar, *Ebabbar*, p. 316 and Zawadzki, *Garments of the Gods*, Vol. I, p. 210). It is not impossible to identify Arad-Anunītu (l. 12) with Arad-Anunītu from BM 65592 (= 344): 12 (an *iškāru* document). The text makes possible to establish the proper reading of the name Nabû-sinqīja-puṭur, "O Nabû, release my distress", known till now from partly preserved name in BM 64007: 11 (cf. Bongenaar, *Ebabbar*, p. 338).

L. 18. There is a space for two short names, such as Balāṭu, written TIN, or Zikaru, written UŠ. L. 20. The scribe Arad-Bēl/Bēl-ušallim/Adad-šamme is one of most active scribe, writing mostly official, but also private documents, see Bongenaar, *Ebabbar*, pp. 481f.

533

[The document concerning x kurru (x  $p\bar{a}nu \times q\hat{u}$ ) of flour, the property of Šamaš, food allowance from the month x] till the end [of month x 4<sup>th</sup> year of Cyrus, king of Bablylon, king of Lands which was given to linen weavers and clothes menders [who are digging Cyrus<sup>?</sup> canal] from the Ebabbar temple.

[Bun]ene-ibni, Liblut, Bēl-iddin, Nabû-ile'i, [Šamaš]-re'ûa, Arad-Bunene, Šamašiddin, Lūidiya, Šamaš-ah-iddin, Šamaš-ahhē-bullit, [Ba]zuzu, Šarru-šamšaya, Abī-ulīde, Nabû-udammiq, [M]uranātu, total 15 linen weavers;

Bunene-šimanni, [NN<sub>1</sub>], Ardīya, Bunene-šar-uṣur, [NN<sub>2</sub>], Šamaš-uballit, Arad-Anunītu, [NN<sub>3</sub>], Nabû-sinqīja-puţur, [total 9?] menders under the authority of [Bunene]-šimanni, their provision is paid by [Bunen]e-šimanni.

[Witnesses are NN<sub>4</sub>], son of Şillā,

[NN<sub>5</sub>], son of Šāpik-zēri;

Iddin-Nabû, son of Iqīšā

[NN<sub>6</sub>, son of NN<sub>7</sub>]

Bunene-ah-iddin, son of Ahušunu

[NN<sub>8</sub>], son Bazuzu

[(and) scribe Arad-Bēl, s]on of Bēl-ušallim from the family of Adad-šammē.

[Sippar, month x, day  $(+^{?})$ ] 4, 4<sup>th</sup> year of [Cyrus, king of Babylon] and Lands.

### **640. BM 63054** (82-9-18, 3023)

PLATE 164

 $4.3 \times 2.9$  cm

#### 23.3.Nbk 27

- 1. 44  $\check{SU}^{ii}$   $\check{s}\acute{a}$  ki-te [(x)] 2. a-na  $^m$ TIN-su  $^{l\acute{u}}$ UŠ.[BAR]
- 3. SUM<sup>na</sup> ITI.SIG<sub>4</sub> U<sub>4</sub>.23. 「KAM<sup>1</sup>
- 4. MU.27.KAM <sup>d</sup>AG-NÍG.DU-ÙRU
- 5. LUGAL TIN.TIR<sup>ki</sup>

Rev. uninscribed

Concerning qātu, cf. Garments of the Gods, Vol. I, p. 108f.

44 skeins of linen [which] were given to Balassu, the weav[er]. Month Simanu, 23<sup>rd</sup> day, 27<sup>th</sup> year of Nebuchadnezzar, king of Babylon.

# **641. BM 65024** (82-9-18, 5005)

PLATE 165

4.7 x 3.1 cm

# 10.7.Camb [x]

- 1. 15 GÍN KÙ.BABBAR šá i-di É.MEŠ
- 2. ina pap-pa-su šá lúUŠ.BAR
- 3. *a-na* <sup>md</sup>UTU-MU-MU 4. A <sup>md</sup>UTU-NUMUN-GÁL <sup>ši</sup>
- 5. ITI.DU<sub>6</sub> [U<sub>4</sub>].10.KAM M[U.x.KA]M

# 

The text is of great importance because it contains the first attestation of the family relation between Šamaš-zēr-ušabši and Šamaš-šum-iddin. Taking into account earlier observation we know now four consecutive generations of the same family:

Ašlāku, known only as the father of Şillā

Şillā, son of Ašlāku, active from Nbp 11 till Nbk 40, i.e. 50 years (Bongenaar, Ebabbar, pp. 341f. and *Garments of the Gods*, Vol. I, p. 225) Šamaš-zēr-ušabši, son of Şillā, active from Nbn 4 till Nbn 12 (Bongenaar, *Ebabbar*, p. 349

and Zawadzki, Garments of the Gods, Vol. I, pp. 229f.)

Šamaš-šum-iddin, son of Šamaš-zēr-ibni, active from Nbn 12 till Dar 29, i.e. almost 50 years (Bongenaar, Ebabbar, p. 347f. and Garments of the Gods, Vol. I, pp. 227ff.)

15 shekels of silver from the rent of the houses from the prebendary weaver's income of Šamaš-šum-iddin, son of Šamaš-zēr-ušabši.

Month Tašrītu, 10<sup>th</sup> [day, n<sup>th</sup> ye]ar of [Cam]byzes, [king of Babylon] and Lan[ds].

# **642. BM 64998** (82-9-18, 4979)

4.3 x 3.4 cm

5.[x].Nbn 7

- 1. [x GÍ]N 「SÍG.ZA¹.GÌN.KUR.RA
- 2. 「*a*¬-*na su-ni-e*
- 3. [šá] <sup>d</sup>A-nu-ni-tu<sub>4</sub> 4. a-na <sup>m</sup>[R]i-ḫi-tu<sub>4</sub>
- 5. SUM<sup>in</sup>

Rev.

- 6. ITI.<sup>r</sup>x<sup>1</sup> U<sub>4</sub>.5.[KAM] 7. MU.7.KAM <sup>md</sup>AG-I
- 8. LUGAL Eki

Below last line a numeral 8 is written. Cf. the similar text BM 101776 (= 483).

[x] shekels of blue-purple wool for  $s\bar{u}nu$ -belt of Anunītu was given to Rēhētu. Month [x],  $5^{th}$  day,  $7^{th}$  year of Nabonidus, King of Babylon.

# **643. BM 64594** (82-9-18, 4574)

5.6 x 4.2 cm

(Darius 23<sup>?</sup>)

- 1. [x] ma-na SÍG.HI.A ina ˈlu-bu-uš-tu4¹
- 2. *šá* ITI.[KI]N<sup>?</sup> MU.23.KAM
- 3. 「a-na<sup>1 md</sup>AMAR.UTU-「ri<sup>1</sup>-man-an-ni SUM
- 4. 1 GÚ.UN <sup>[7]</sup> [*m*]*a-na* <sup>[</sup>SÍG.HI.A]
- 5. a-na ta-hap-šú a-na

535 XX. MISCELLANEA

6. <sup>m</sup>ÌR-*ja* <sup>lú</sup>UŠ.BAR SUM<sup>na</sup>

7. ½ GÚ.UN <sup>[3]</sup> 1/3<sup>1</sup> ma-na SÍG.HI.A

Edge Rev.

8. ina lu-bu-uš-tu<sub>4</sub> šá ITI.GU<sub>4</sub>

9. 「a¹-na <sup>m</sup>TIN-su-<sup>d</sup>Gu-la SUM 10. [x] 「GÚ.UN 2<sup>1</sup> ma-na SÍG.HI.A

12. a-na <sup>md</sup>UTU-「MU¬-MU SUM<sup>na</sup>

13. 「5」 ma-na SÍG.[HI].「A」 ina ŠUKU.H[I.A šá]

14. ITI.<sup>r</sup>DU<sub>6</sub><sup>1</sup> ITI.AP[IN ....]

15.  $^{\Gamma}$ MU $^{1}$ .22.KAM a-na  $^{m_{\Gamma}d_{1}}[...]$  16.  $^{[m]d}$ UTU-MU-MU a-na  $^{m_{\Gamma}x_{1}}[...]$ 

17.  $^{\Gamma}x \times x^{1} U_{4}.22+[....]$ 

Rest of three illegible lines on left hand edge

L. 16. The last preserved part might be a personal name or numeral.

[x] minas of wool for the *lubuštu* ceremony of the month [Ulū]lu<sup>2</sup>, 23<sup>rd</sup> year was given to Marduk-rēmanni.

One talent, 7 minas of wool for the tahapšu blanket was given to Ardīya, the

33 1/3 minas of wool for the *lubuštu* ceremony of the month Ayaru was given to Uballissu-Gula.

[x] talent(s) and 2 minas of wool for the *lubuštu* ceremony of the month Ayaru was given to Šamaš-šum-iddin.

5 minas of wool for the kurummatu-payment for the month Tašrītu and Arah[samna], 22<sup>nd</sup> year to [....] Šamaš-šum-iddin for [....].

# **644. BM 11475** (1920-12-13, 43)

PLATE 165

5.4 x 4.0 cm

# 4.1.Nbk 12

- 1. 31 ma-na dul-la gam-ru KI.LAL
- 2. TÚG.ḤI.A TÚG.MÁŠ TÚG.'ḤI.A¹ me-e SAG.DU
- 3. 7 TÚG.NÍG.ÍB.LÁ.[MEŠ 4] TÚG.ÚR.MEŠ šá <sup>d</sup>UTU
- 4. 10 TÚG.NÍG.ÍB.LÁ. MEŠ šá<sup>1 d</sup>A-a
- 5. 1 ma-na 55 GÍN KI.LAL TÚG.HI.A
- 6. TÚG.MÁŠ *šá* <sup>d</sup>*Bu-ne-ne*
- 7. 19 2/3 ma-na KI.LAL TÚG.HI.A TÚG.MÁŠ
- 8. šá <sup>d</sup>IM 1 ma-na 1/3 GÍN KI.LAL
- 9.  $1^{en}$  TÚG. ÚR 10 TÚG. NÍG. ÍB. LÁ. MEŠ

10. šá <sup>d</sup>IM u <sup>d</sup>Ša-la Edge

11. <sup>md</sup>AG-EN-MU.MEŠ <sup>lú</sup>UŠ.BAR Rev.

12. ma-hir ITI.BÁR U<sub>4</sub>.4.KAM

13. MU.12.KAM <sup>d</sup>AG-NÍG.DU-ÙRU LUGAL E<sup>ki</sup>

- 14. ½ ma-na TÚG.SÍG.ZA.GÌN.<KUR>.RA šá TÚG.HI.A šá <sup>d</sup>UTU
- 15. 「5 {GÍN} GÍN šá TÚG.HI.A šá dBu-ne-ne
- 16. 10 「GÍN¹ KI.MIN šá KI.MIN šá <sup>d</sup>IM
- 17. [TA TÚG.H]I.A.MEŠ na-si-ih

\_\_\_\_\_

- 18. [1<sup>en</sup> TÚG.ÚR 5] 'TÚG'.NÍG.ÍB.LÁ.[MEŠ]
- 19. 1<sup>en</sup> TÚG.BAR.SI BABBAR<sup>ú</sup> šá <sup>d</sup>Bu-ne-ne]
- 20. [8 TÚG.NÍG.ÍB.LÁ.MEŠ šá] <sup>d</sup>DUMU.MÍ.M[EŠ É]-babbar-ra
- 21. [mdAG-EN-MU.MEŠ] [(x x)] šá la ha-a-ṭu
- $22.\{\lceil ha^{\gamma}-a-tu\}\ [i]-nam-din$

In general the text is parallel to the documents Nos. 293–313, however, there is one notable difference, i.e. for the first time the wool is recovered not only from *lubāru*-garments of Šamaš and Bunene, but also from the *lubāru* of Adad. It is obvious that during these processes the old, used *lubāru*-garments were taken apart and replaced by new ones. The data preserved in some of these documents suggest that the process of replacement of old garments by new ones began in Sippar at the very beginning of Nebuchadnezzar II's reign and lasted until his second decade. The repetition of the information about the recovery of blue-purple wool from the old *lubāru*-garments of Šamaš and Bunene make it possible to state that each of them had at least a few *lubārus*. The important thing is that here we have the first information about the recovery of blue-purple wool from the *lubāru*-garment of Adad. The date of the text – 12<sup>th</sup> year of Nebuchadnezzar – suggests that although the process of exchange of *lubāru*-garments of Šamaš and Bunene did not end, the temple began the replacement of the old *lubāru*-garments of Adad about that time.

31 minas, the completed work, the weight of the *lubāru*, the *ṣibtu* and the *lubār mē qaqqadi*-garments, 7 sashes, [4] *sūnu*-belts for Šamaš, 10 sashes for Aya; 1 mina 55 shekels, the weight of the *lubāru* and *ṣibtu*-garments for Bunene; 19 mina 40 shekels, the weight of the *lubāru* and *ṣibtu*-garments for Adad; 1 mina 20 shekels, the weight of 1 *sūnu*-belt (and) 10 sashes for Adad and Šala were received from Nabû-bēl-šumāti, the weaver. Month Nisannu, 4<sup>th</sup> day, 12<sup>th</sup> year of Nebuchadnezzar, king of Babylon

-----

½ mina of blue-purple wool from the *lubāru*-garment for Šamaš 6 shekels of blue-purple wool from the *lubāru*-garment for Bunene, 10 shekels of ditto of ditto for Adad - [from (these) *lubā*]*ru*-garments (wool) was removed.

-----

[1 sūnu-belt, 5 s]ash[es, 1 white paršigu-headdresses for Bunene], [8 sash]es [fo]r the Daughters of the Ebabbar, [Nabû-bēl-šumā]ti whom no supply (is given except for these items), he delivers <to the temple> (of Šamaš).

**645. BM 114790** (1920-12-13, 82) 5.4 x 3.9 cm

PLATE 166

- 1. 6 GÍN KÙ.BABBAR *a-na* <sup>r</sup>*dul-lu* <sup>1</sup>
- 2. SÍG.ZA.GÌN.KUR.RA 2 G[ÍN KÙ.BA]BBAR

XX. MISCELLANEA 537

- 3. a-na pap-pa-su SÍG.ZA.GÌN.<KUR>.RA
- 4. PAP 8 GÍN KÙ.BABBAR *a-na*
- 5. <sup>md</sup>UTU-MU-MU <sup>lú</sup>UŠ.BAR SUM
- 6. e-lat 2 GÍN IGI-ú

Rev. 7. ITI.APIN U<sub>4</sub>.14.KAM

- 8. MU.7.KAM <sup>m</sup>Da-a-ru-muš
- 9. LUGAL TIN.TIR<sup>ki</sup> LUGAL KUR.KUR

6 shekels of silver for 'manufacturing' of blue-purple wool; 2 she[kels of si]lver for the prebendary income for blue-purple wool, total 8 shekels of silver was given to Šamaš-šum-iddin, the weaver. This is except for 2 shekels of an earlier (payment).

Month Arahsamna, 14<sup>th</sup> day, 7th year of Darius, king of Babylon, king of Lands.

This small administrative text is of great importance, because as was established in the first part of this book, the proportion between this parts of raw material issued to the prebendary weaver was about 2:1, i.e. 2/3 of the wool was destined for manufacturing the garments (*sattukku*) and 1/3 belonged to the weaver as his prebendary income (*pappassu*). Here the proportion is different, i.e. 3:1, i.e. 6 shekels for the manufacture of blue-purple wool and 2 shekels as the prebendary income. It seems that the difference is caused by the fact Šamaššum-iddin received silver, not wool, i.e. he did not need to sell wool to buy himself food, or other necessities.

# Additions and corrections to Garments of the Gods, Volume I

The most important study on similar subject is E. Payne, *The Craftsmen of the Neo-Babylonian Period: A Study of the Textile and Metal Workers of the Eanna Temple*, unp. dissertation, Yale University 2008, esp. pp. 86–201. Note also a good overview of the importance of textile industry in a broader perspective in L. Graslin-Thomé, *Les échanges à longue distance en Mesopotamie au I<sup>en</sup> millénaire. Une approache économique*, Paris 2009, esp. 189–213. New valuable observations on the textile industry in the Ancient Near East and Mycenaean word are in the volume cited in Zawadzki 2010 in the *Bibliography* at the beginning of this volume. Note also the recognition of proper reading of the garment *guzguzu* and its function as cover for cultic furniture in L. Quillien, "túg-LUM-LUM = túg-guzguz: a new interpretation of the «guzguzu» garment in first millennium BC Mesopotamia," NABU 2013/14 and S. Payne, "Two tablets from Yale Babylonian Collection mentioning *guzguzu*-garment," NABU 2013/15.

The informal discussions with the reader of my book inclined me to add a short additional explanation. The basis for my proposal is not the etymology of the word,<sup>5</sup> but mainly the fact that: (a). the material is used at the beginning only to manufacture gods' attire, thus, it was recognized as precious and was not commonly accessible (b) the price of  $kitinn\hat{u}$  was higher than price of linen ( $kit\hat{u}$ ) and wool. Alternatively we can accept the idea that  $kitinn\hat{u}$  dentoted a linen product with the use of a new technology, but the question is why that so long time would be needed to bring it into general use. I hope that the future discussion will clarify the question. Note new valuable arguments for the idea that  $kitinn\hat{u}$  is the word for cotton are given by K. Kleber in her review of my book in OLZ 106 (2011), pp. 88–90.

- p. 57 ff.: The term *išparu* has survived and is present in the Babylonian Talmud, however, with narrower meaning "mender of garments" (Sokoloff 2002, p. 147; kind communication of Nahum Ben Jehuda).
  - p. 65: pilaqqu, change "spindle whorls" to "spindle".
- p. 66: It was not my intention to suggest that *ašlākus* were the manufacturers of garments; quite opposite, they worked as intermediaries, i.e. they collected linen garments, sometimes also wool garments from the fullers as well as from the weavers and they were responsible for the preparation of garments for the cultic ceremonies, especially for their cleaning and repairing.
- p. 88, Table 20. The weight of the  $lub\bar{a}ru$  of Bunene should be corrected from 1 mina to 1 1/3 minas.

Some arguments concerning the function of the *lubāru* garment can now be presented. It is important to compare the items for Šamaš with the items for the

According to Sokoloff 2002, p. 579 kitan is the standard Aramaic and Syriac term for flax/linen (courtesy of Nahum Ben Jehuda).

goddesses in the *miḥṣu tenû* lists. The lists of items for Šamaš comprises a *salḥu*, a tunic placed on the "naked" body of the statue, and next a *ḥullānu*-coat, *guḥaṣṣu*-scarf, two types of belts (*patinnu* and *nēbeḥu*), and headdresses of different types. The lists of goddesses items comprise one element, which is missing in the list of Šamaš items, i. e. an outer overcoat, a *kusītu*, a long coat decorated with hundreds of sequins. The comparable item in Šamaš's list must be searched for in the *dullu peṣû* lists. The only item which can be compared to the *kusītu* is *lubāru*, which has to be recognized as the gods' overcoat. The idea is strengthened by the fact that in the list of items of Anunītu the *kusītu* is replaced by a *lubāru*. Additionally in two texts in the place where the *kusītu* is expected the scribe wrote *lubāru*. Such a mistake is possible if both items have a similar function, i.e. they were overcoats. The overcoats differed probably in colour; the gods' ones were most probably always white the goddesses' overcoats were made with coloured thread. Additionally the overcoats of the goddesses were decorated with sequins, while the god's ones were not. Cf. also Zawadzki 2010, p. 411.

- p. 92: *Şibtu*: The idea that the weight of the *şibtu* of Anunītu was 16 minas plus additional coloured yarn is probably not entirely correct, although in BM 67848: 2, the weight of one *şibtu* is 16 ½, presumably 16 minas of *kitinnû* and 1½ mina of red wool. Sometimes the weight of the main yarn was lower, cf. CT 56, 5 (= 575): 2, where for two *şibtus* 30 minas of *kitinnû* and 2 minas of red wool was used, i.e. accordingly 15 minas *kitinnû* and one minas of red wool for each *şibtu*. Lastly BM 49188 (= 556) suggests that one *ṣibtu* weighted 18 minas; the possibility that the *ṣibtu* Anunītu was meant there is based only on the weight, close to the weight of her *şibtu*.
  - p. 96: CT 56, 5 delete from the list of *şibtu* used as cover.
- p. 212: In BM 67525, No. 482 in the edition, read [Nabû-nāṣir]-apli, not [Bal-as]su. Delete the second data from the list of attestation under Balassu, *išpar kitê*.
  - p. 219: BM 51148, No. 177 in the edition, is dated in fact [x].2. Nb[k] 11.
  - p. 227: BM 67149, No. 242; only year Cyr 7 is preserved.
- p. 229: In BM 59963, No. 271 in the edition, read now rather Šamaš-zēr-ušabši instead of Šamaš-zēr-ibni.
- p. 247: BM 50449. The tablet is partly miscopied. For this reason new copy is published here (see Plate 167). In transliteration (Part I, p. 53) at the end of l. 10' delete exclamation mark and add *ina lib-bi*. Note that translation is correct.

# Postscript

An additional lastly recognized fragment of early *dullu peşû* text is BM 44751 ([x].7.Nbk 3) mentioning Nabû-bēl-šumāti.

# **Indexes**

#### Personal names

**Fat** – active in the textile industry, but previously not noted.

\* Person known before, but his presence in the given text was not mentioned, or the text is not noted in Vol. I.

[x (x)]-iddin 322: 1'.
[GN-aḥ-iddin 322: 2'.
[GN]-bān-apli/Murā[nu] 497: 6.
[x]-Marduk/Kalbā 538a: 7.
[NN] *šanû ša* Šamšaya, *qīpu Ebabbar* 435: 3.
NN/Bazuzu 639: 20 (6<sup>th</sup> witness).
[NN]/Saggilu 555: 9'.
[NN]/Şillā 639: 17 (1<sup>st</sup> witness).
[NN]/Šamaš-šar-[x], slave 399: [2].
NN/Sāpik-zēri 639: 18 (2<sup>nd</sup> witness).
Abu-iltammeš *ša muḥḥi quppi* 637 rev. II
18' (one out of two *ša muḥḥi quppi* in the rations' list).

\*Abī-ul-īde 639: 9 (one out of 15 lúUŠ.BAR GADA).

Aḫu/Aḫh[ē.....] 637 rev. I 5', 8' (out of 21 members of an unidentified professional group; the rations' list).

Ahhē-iddin 585: 3.

Aḥūnu 638: 2 (first position in the list of persons receiving travel provision (*sidītu*)).

Aḥušunu *ša kurummāti šarri* 637 obv. I 8' (one out of 12 members of the group; the rations' list).

Anu-ibā 600: 15.

\*(**Ana)-Nabû-upnīya** 174: 2; 457: <sup>[6]</sup>; 591: [14]; 592: [8]; 593: 4; 599a: 6.

Aplā 621: 3.

Aplā 313, rev. 4'.

Arad-Bēl/Bēl-ušallim//Adad-ušamme 639: 21 (scribe).

Arad-Bēl BM 623: 8.

\*Arad-Anunītu 639: 12 (one out of 9? húmukabbû).

Arad-Anunītu rab qašti 603: 3.

\*Arad-Bunene 348: '\(^8\)'; BM 62063: 9' (one out of seven(?)\(^\text{MUŠ.BAR GADA.}\)

Arad-Nabû *arad ekalli* 637 obv. I 21' (the rations' list).

Ardīya *arad ekalli* 637 obv. I 15' (the rations' list).

**Ardīya** *mukabbû* 639: 11 (one out of 9? *mukabbû*s).

\***Ardīya** [*mupaṣṣû*] 357: 6.

Ardīya išparu 643: 6.

Ardīya ša bīt qātê 408a: 6'.

\***Arrabi**, <sup>lú</sup>*mukabbû* 628c: 2; BM 59010, rev. 7'.

Atar-simki/Sîn-unammir 601: 5.

Aziya 572: 2.

\*Bakûa 174: 「2」; 389: 4; 405: 4; 474: 「8¹; 484a: 18; 592: [7]; 599: 4; 599a: 5; BM 61848: 9 (4/2/Cyr 3).

Balāṭu/Nabû-aḫḫē-bulliṭ 400: 4.

Balātu/Nabû-zēr-ibni 627: 3.

\*Balāṭu/Nabû-bēl-šumāti lúUŠ.BAR 630a: 2.

\*Balāṭu <sup>lú</sup>UŠ.BAR 1: 6; 561: 3; 640: 2. Banitu-ēreš *arad ekalli* 637, obv. I 22' (the rations' list).

Bānītu-ēreš 637, rev. II 24' (the rations' list; member of an unidentified professional group).

Bānītu-ēreš 448: 4.

\*Bazuzu 639: 9 (one of 15 lúUŠ.BAR GADA).

Bēl-[...] 637 obv. II 14' (the rations' list; member of an unidentified professional group).

Bēl-[...] 448: 7.

Bēl-ahhē-iqīša, qīpu Ebabbar 553: 7.

Bēl-ahhē-ittannu/Sîn-ilī 510: 4.

[Bēl-apal-iddin]/Balīḥu//*šangû* of Sippar 553: [12].

Bēl-atta-ilē'i *ša kurummāti šarri* 637 obv. I 9' (one out of 12 members of the group; the rations' list).

Bēl-bullissu 407: 5; 424: [5].

Bēl-ēreš mandidi ša Esagila 579: 3.

Bēl-ētir 589: 6.

Bēl-ētir-Nabû 445: 4.

\***Bēl-iddin** 346: 3'; 639: 6 (one out of 15 lúUŠ.BAR GADA).

Bēl-iddin/Šadūnu 449: 3.

Bēl-iddin/Šullumu 448: 5.

Bēl-iddin 419: 5.

Bēl-iddin 617: 11'.

Bēl-iddin 413: 1, 3.

Bēl-ittannu 583a: 5.

Bēl-ittannu 376: 7.

Bēl-lūdāri ša Šarrat Sippar 416: 15.

Bēl-na'id 618: 8.

Bēl-nāsir 348: 17.

Bēl-rēmanni 408, rev. 3'.

Bēl-šar-bulliţ *ša kurummāti šarri* 559: 2; 569: 5.

Bēl-šar-uşur ša kurummāti šarri 560: 2.

Bēlšunu  $at\hat{u}$  637 rev. II 13' (one out of 15  $at\hat{u}$ s; the rations' list).

Bēl-u[...] 348: 10.

Bēl-uballit/Kiribtu//šangû Sippar 553: [13].

Bēl-uballiţ/Kiribtu 564: 4.

Bēl-ušallim/Šamaš-[...] 620: 6', 7'.

Bēl-zēr-ibni/Sîn-kitri 593a: 4'.

Bulta 438: 6'.

Bun[ene ...] 637 rev. I 11' (one out of 21 members of unidentified professional group; the rations' list).

Bunene-aḥ-iddin/Aḥḥēšunu 639: 19 (5<sup>th</sup> witness).

Bunene-ibni 450: 14 (?); 639: 6 (one out of 15 lúUŠ.BAR GADA); BM 60908: 16'

Bunene-ibni *paḥāru*, *mār šipri* 603: 7; 611: 10.

- \*Bunene-ibni puşaya 628a: 2; BM 61148: 8 (issue of 1 (PI) 4 BÁN of flour for HAR-DÙ u lúpu-şa-a-a; 11. 8. Nbn 9).
- \*Bunene-šar-uşur 639: 11 (one out of  $9?^{16}mukabb\hat{u}$ ).
- **1.\*Bunene-šimanni** 639: 10 (one out of 9? <sup>1ú</sup>mukabbû); BM 114821: 12 (28. 12.Nbn 2) mukabbû, received 1 shekel of silver because of his illness (mar-şa-')
- 2. (= 1?) Bunene-šimanni 605: 8.

Danna 617: 12'.

**Dummuqu,** BM 50934, rev. 2 (wool ledger; *Du-muq* <sup>lú</sup>UŠ.BAR)

Erība/Lib-<lut > 581: 4.

**Eulm[aš-x x]** BM 66172: 2' (<sup>5</sup>'PAP 5 LÚ.MEŠ <sup>lú</sup>UŠ.BAR.MEŠ)).

\*Gimillu/Šapik-zēri 546: [5].

Gimillu 450: 13.

Habasiru 416: 11.

. Hanbatutu 618: 9.

Hanniya *atû* 637 rev. II 4' (one out of 15 *atû*s; the rations' list).

Ina-e-šá-bi 617: 5'.

Ibnā *atû* 637 rev. II 12' (one out of 15 *atûs*; the rations' list).

Idi-ilī ša bīt alpē 638: 4 (third in the list of persons receiving travel provision (*sidītu*)).

Idi-ilī ša bābi 638: 5 (fourth in the list of persons receiving travel provision (*sidītu*)).

Iddin-Nabû/Iqīša 639: 18 (3<sup>rd</sup> witness).

Iddin-Nabû/Nāşir 428, rev. 5.

Ina-silli-Bēl 580: 3.

Ina-patar-dana *atû* 637 rev. II 7' (one out of 15 *atû*s; the rations' list).

Ina-şilli-Nergal *ša kurummāti šarri* 637 obv. I 13' (one out of 12 members of the group; the rations' list).

Ina-şilli-Nergal 603: 2.

Iqīša 381: 3\*.

Itti-makû-ilāni BM 61905 II 7' (one out of five lúUŠ.BAR *bir-mu*).

Kabtīya 630b: 7.

Kalbā/[xx]šu 594: 3.

Kalbā 564a: 6.

Kalbā 637, rev. II 22' (the rations' list; member of an unidentified professsional group).

Kidinnu 508: 3.

Kinā 367: 7.

Kī-Nabû *atû* 637 rev. II 9' (one out of 15 *atû*s; the rations' list).

Kī-Šamaš ša kurummāti šarri 637 obv. I 7' (one out of 12 members of the group; the rations' list).

**Kişiria** <UŠ.BAR> 599a: 4.

Kudurru 481: 11.

Lāqīpu *atû* 637 rev. II 3' (one out of 15 *atûs*; the rations' list).

\*Libluţ ēpišānu of Bēl-bulliţsu 407: 4.

\*Liblut/[x] 637 obv. II 4' (one out of 11 llúUŠ.BAR GADA; the rations' list); 639: 6 (one out of 15 llúUŠ.BAR GADA); BM 62063: 6'(one out of seven(?) llúUŠ.BAR GADA).

\*Libluţ mukabbû BM 61486: 7 (lúTÚG.KAL.KAL); BM 72824: 5 (lúTÚG.KAL.KAL).

Liblut 603: 6.

\***Lūidiya** 639: 8 (one out of 15 lúUŠ.BAR GADA).

Lūși-ana-nūr 416: 13.

Mad[ānu ...] 637 obv. II 18' (the rations' list; member of an unidentified professional group).

Marduk-ēreš naggāru 588: 2.

Marduk-ēţir/Rēmūt 618: 2.

Mugge<a>-līp 428, rev. 3'.

Murānu 630b: 9.

\*<sup>f</sup>Murānātu 639: 10 (one out of 15 l<sup>ú</sup>UŠ.BAR GADA); BM 62063: 10' (one out of seven(?) l<sup>ú</sup>UŠ.BAR GADA).

Mušallim-Marduk 412: 4.

Mušēzib 586: 3.

Mušēzib-<sup>d</sup>[x] *ša muhhi ešri* 590: 6.

Mušēzib-Marduk/Nabû-nipšāri 568: 4.

Mušēzib-Marduk *šangû* Sippar 553: [9]; 601: 9.

Mušēzib?-Marduk 605: 4.

Mušibši-Marduk 476: 6.

Nab[û ....] 637 rev. I 7' (the rations' list; one out of 21 members of unidentified professional group).

Nabû-<sup>r</sup>x<sup>1</sup> 617: 6'.

Nabû-aḥḥē-šullim/Aplā 563: 3; 564: 2.

2. (= 1?) Nabû-ahhē-šullim 566: 3.

3. Nabû-ahhē-šullim 633: <sup>[6]</sup>.

4. Nabû-aḥḥē-šullum 638: 3 (second in the list of persons receiving the travel provision (*şidītu*)).

Nabû-apal-iddin 400: 3

Nabû-apal-uşur 382: 8a.

\*Nabû-bēl-šumāti 12: 6; 39: 6 (l<sup>ú</sup>UŠ. BAR GADA); 42: 10; 303, col. II [9'] ([l<sup>ú</sup>U] Š.BAR); 304, rev. 2'; 307: 8'; 312: <sup>[</sup>12']; 591: [15] (l<sup>ú</sup>UŠ.BAR); 644: 11, [21].

Nabû-bulliţanni *ša muḥḥi quppi* 444, rev. 3'.

Nabû-bullissu 416: 13.

Nabû-dūr-īnīya 589: 8.

Nabû-ēţir 425: 9, 12.

Nabû-ēţir-napšāti/?Niqūdu 550: 3.

\*Nabû-ile'i 639: 6 (one out of 15 lúUŠ.BAR GADA).

\* [Na]bû-ittannu ēpi[šānu] (?) 497: 5.

Nabû-ittannu 611: 8, 19.

Nabû-jānu (?) *atû* 637 rev. II 14' (one out of 15 *atû*s; the rations' list)

Nabû-kāşir 617: 6'; 618: 4.

Nabû-mīţa-uballiţ *nappaḫ siparri* 638: 11 (the last in the list of ten persons receiving travel provision (*sidītu*)).

Nabû-mīṭa-uballiṭ *arad ekalli* 637 obv. II 20' (the rations' list).

Nabû-mukīn-zēri/Marduk-šāpik-zēri, the *šatammu* of Esagila 628: 1.

\*Nabû-nāṣir 457: 6; 542: 6; 592: 6; BM 61905 II 6' (one out of five lúUŠ.BAR bir-mu).

Nabû-nāşir 611: 9.

\***Nabû-nāşir-apli** 125: 2; 482: <sup>[2]</sup>; 484: <sup>[6]</sup>; 484a: 18; 599: 3; BM 66807, rev. 4.

\*Nabû-sinqija-puţur 639: 13 (one out of 9? lúmukabbû).

Nabû-šum-iddin 420: 4.

Nabû-šum-līšir/[Balassu]//*šangû* Ištar-Bābili 533: 10.

Nabû-šum-līšir 620: 4'.

Nabû-šum-uşur 550: 7, rev. 6'.

\*Nabû-uballiţ UŠ.BAR GADA 343: 9.

\*Nabû-udammiq 639: 9 (one out of 15 lúUŠ.BAR GADA).

Nabû-zēri/Nabû-ahhē-iddin 539: 5.

\***Nabû-zēr-ibni** 46: 3; BM 49500: 5 (2 *ta* SU<sup>ii</sup>.MEŠ <sup>md</sup>AG-NUMUN-DÙ <sup>lú</sup>UŠ.BAR; dated [x].7. 9 <Nbp?>).

Nabû-zēr-ukīn/Marduk-šum-ibni 616: 2.

Nabû-zēr-ušabši 385: 5.

Nādin 613: 3.

Naniya *atû* 637 rev. II 11' (one out of 15 *atûs*; the rations' list).

Nāṣir 481: 5.

Nāṣir 353: 17.

\*Nergal-iddin ēpišānu 173: 2.

Nergal-id[din] 637 obv. II 13' the rations' list; member of an unidenti-fied professional group).

Ne[rgal-šar-bullit], the  $q\bar{t}pu$  of Ebabbar 601: 7.

Nergal-uballiţ 638: 10.

Nergal-ušēzib/Nabū-zēr-ibni//Ḥammaya 5: 6.

\*[Nergal]-ušēzib lúUŠ.BAR 12: 19.

Nidintu 564, rev. <sup>[1]</sup>.

Nidintu 583a: 4.

\*Nidi[ntu] <sup>lú</sup>UŠ.BAR GADA 343: 8.

Nūr-[....] *arad ekalli* 637 obv. I 19' (the rations' list).

Nūr-Šamaš *atû ša bīt Šarrat Sippar 637* rev. II 5' (one out of 15 *atû*s; the rations' list).

Nūr-Šamaš *ša muḥḥi quppi* 637 rev. II 17' (one out of two *ša muḥḥi quppi* in the rations' list).

Nūr-Šamaš 448: 6.

Pāni-Bēl-adaggal 355: 4, 14.

Rēhētu 483: 4; 642: 4.

Rēmūt/Iaīšā 588: 6.

Rēmūt, nappahu 607: 8.

Rēm[ūt] (?) 637, obv. II 17' (the rations' list; member of an unidentified professional group).

Rēmūt 629: 8.

 [Rē]mūt-Bēl/[Zērū]tu//Iddin-Nergal 553: 2<sup>6</sup>.

2. (= 1?) \*Rēmūt-B[ēl] 527: 2.

Rēmūt-ilī 606: 5

**fRi'du** BM 66172: 4'(<sup>f</sup>Ri-'-i-<sup>r</sup>du<sup>1 5</sup>'PAP 5 LÚ.MEŠ <sup>lú</sup>UŠ.BAR.MEŠ)

Silim-[....] 637 rev. II 26' (the rations' list; member of an unidentified professional group).

Sîn-ilī BM 462: 4.

**Suqāya/**<sup>r</sup>*Kal*<sup>r</sup>-[...] <sup>lú</sup>UŠ.BAR BM 66172: 3' (<sup>S</sup> PAP 5 LÚ.MEŠ <sup>lú</sup>UŠ.BAR.MEŠ).

Şillā nuhatimmu 631: 3.

**Sillā** 317, rev. <sup>[6</sup>?]; 324: 1; 585: 2.

Şunabunah *atû* 637 rev. II 6' (one out of 15 *atûs*; the rations' list).

Šadūni-ilī 637 rev. II 25' (the rations' list; memeber of an unidentified professional group).

Šalammarê 603: 6

Šam[aš-....] 320, rev. 8'

Šamaš-[x]-<sup>r</sup>x<sup>1</sup>-a/A arad ekalli 637 obv. II 16' (the rations' list).

Šamaš-[...] *arad ekalli* 637 obv. II 18' (the rations' list).

Šamaš-[...] 637 rev. I 6', 12' (one out of 21 members of unidentified professional group; the rations' list).

Šamaš-abu-uşur *ša kurummāti šarri* 637 obv. I 12' (one out of 12 members of the group; the rations' list).

\*Šamaš-aḥ-iddin 639: 8 (one of 15 lúUŠ.BAR GADA); BM 62063: 7'(one out of seven(?) lúUŠ.BAR GADA).

\*Šamaš-aḥ-iddin 638: 7 (lúUŠ.BAR birri; sixth in the list of persons receiving travel provision (sidītu)).

Šamaš-aḥ-iddin *ša kurummāti šarri* 637, obv. I 3' (one out of 12 members of the group; the rations' list).

Šamaš-aḥ-id[din] 637, obv. II 12' (the rations' list; member of unidentified professional group).

Šamaš-aḫ-iddin 637, rev. II 21' (the rations' list; member of unidentified professional group).

Šamaš-ana-bītišu 603: 6.

\*Šamaš-aḥḥē-bulliṭ 639: 8 (one of 15 l<sup>ú</sup>UŠ.BAR GADA); BM 62063: 8'(one out of seven(?) l<sup>ú</sup>UŠ.BAR GADA).

Šamaš-ēpuš *nappah parzilli* 449, rev. 2'. Šamaš-erība/Nabû-zēr-ibni 438: 4'.

Šamaš-erība *ša bābi* 638: 6 (fifth in the list of persons receiving travel provision (*şidītu*)).

\*Šamaš-erība saqqaya 637 rev. II 19' (one out of two saqqaya in the rations' list).

Šamaš-erība 606: 13.

Šamaš-ēţir BM 623: 11.

Šamaš-ibni nuhatimmu 631: 3.

Šamaš-iddin 639: 7 (one out of 15 lúUŠ.BAR GADA).

Šamaš-ile'i 564, rev. 2'.

Šamaš-ina-tēši-uṣur atû 637 rev. II 15' (one out of 15 atûs; the rations' list).

Šamaš-išdija-ukīn *ša kurummāti šarri* 637 obv. I 5', 11' (one out of 12 members of the group; the rations' list).

Šamaš-kāşir 609: 13.

Šamaš-māti-iramu *atû* 637 rev. II (one out of 15 *atûs*; the rations' list).

Šamaš-mukīn-aḥi *ša kurummāti šarri* 637 obv. I 2' (one out of 12 members of the group; the rations' list).

\*Šamaš-nāṣir BM 61905 II 8' (one out of five <sup>lú</sup>UŠ.BAR *bir-mu*; one out of 15 *atû*s; the rations' list).

\*[Šamaš]-rē'ua) 639: 7 (one out of 15 lúUŠ.BAR GADA) BM 62063: 4'(one out of seven(?) lúUŠ.BAR GADA).

Šamaš-rişûa *ša kurummāti* š*arri* 637 obv. I 6' (one out of 12 members of the group; the rations' list).

Šamaš-šar-uşur 596: 3.

Presumably it is the same person as Rēmūt-Bēl/Šamaš-zēr-ibni.

\*Šamaš-šum-iddin/Šamaš-zēr-ibni 61: 
[4?1; 107: [2?] (UŠ.BAR); 128: [5?] (UŠ.BAR); 408: 4; 450: 5 (UŠ.BAR); 500: 8 (UŠ.BAR); 551: 9'(?); 641: 3; 643: 12, 16; 645: 5 (UŠ.BAR).

[Šamaš-tab]ni-uşur/Erība-

Marduk//[šangû Ištar-Bāb]ili 553: 14.

**Šamaš-uballiţ** *ašlaku* 315: 3.

Šamaš-uballit 388: 15.

\*Šamaš-uballiţ 639: 12 (one out of 9? <sup>lú</sup>mukabbû).

Šamaš-uballit *ša kurummāti šarri* 637 obv. I 4' (one out of 12 members of the group; the rations' list).

Šamaš-uballiţ  $at\hat{u}$  637 rev. II 10' (one out of 15  $at\hat{u}$ s; the rations' list).

Šamaš-uballit 501: 4.

Šamaš-udammiq/Šūzubu 594: 4.

Šamaš-udammiq 614: 7'.

Šamaš-zēr-ibni 600: 9.

Šamšaya, qīpu Ebabbar 435: 3.

Ša- [....] 637, rev. I 13' (one out of 21 members of an unidentified professional group; the rations' list).

Ša-Nabū-šū 637, rev. II 23' (the rations' list; member of an unidentified professional group).

Šāpik-zēri/?Naggāru 501: 2.

\*Šāpik-zēri/Šamaš-aḥ-iddin 470: 3; 486, rev. 2'(?); 516: <sup>r</sup>3<sup>1</sup>; 592: 11; 595: 4; 645: 5; BM 114784: 11 (21.8.Nbk 41; wool <sup>9</sup>a-na <sup>sig</sup>ta-kil-tu<sub>4</sub> u [ta-barri] <sup>10</sup>SÍG.ḤI.A ana şu-pa-a-ta).

Šarru-lū-dāri, *qīpu Ebabbar* 603: 7.

Šarru-Šamšaya 639: 9 (one out of 15 lúUŠ.BAR GADA).

Še-<sup>[</sup>x<sup>1</sup>-[x]/Murašû 417: 6.

Širiktu/Itti-Šamaš-balāţu 417: 3.

Širiktu 411, rev. 3'

\*Šulā lúUŠ.BAR 12: 20 (?).

\*Šulā puşaya 628b: 2.

Terik-šarussu [rēš šarri] 450: 8.

*Tuq*?-*nu-ba-nu* 411, rev. 2'.

\*Uballissu-Gula 168: 2; 408: 3; 408a: 3'; 423: 3'; 502: 11; 611: 15; 643: 9.

Uballissu-Marduk 416: 4.

<sup>f</sup>Ubartu ša bīt asî 494: 3.

<Za>bīnu/Marduk-ile'i 593a: 5'.

\*Zabīnu pusava 625a: 3.

Zēr-Bābili 601: 10.

Zēriya 638: 9 (lúŪŠ.BAR *bir*-ri; eighth in the list of persons receiving travel provision (*şidītu*)).

Zerūtu 24: <sup>[9]</sup>.

### Divine names

# Adad

11: 11; 12: [5]; 16: 8; 17: [7]; 18: 9; 19: 9; 25, rev. 4'; 26: [7]; 27: [7]; 34: 7'; 35: 5'; 36: 5; 47, rev. [7']; 48, rev. 5'; 49: [8']; 50: 10–11; 52: 12; 54: 13; 56: 10-11; 57: 11; 58: 12; 59: 16, 18; 62: 10, [11]; 63, rev.1', 6'; 66: 15, 17-18; 67: 16–17, 25, 29; 68, rev. 4'; 69: 15-16, 18-19; 73: [5, rev. 2']; 76, rev. 2', 4', 8'; 77: [10, 19]; 78, [rev. 2', 4']; 79: [14]; 81: 10, 12, 14; 82: 16, [17, 20], 22; 83: 11, 13; 84: [16–18]; 85: 12, [13], 14, [15–16]; 86: 15; 87: 17; 90, rev. 1'-2'; 91: 13, 15; 97: 11', 13'; 100: 9'; 101, rev. 5'; 102: 14; 104: 17; 106: 16; 108: [16]; 110, rev. 5'; 111: 12; 112: 16; 116: [17], [18]; 118: [14–15]; 122: [13, 16]; 123: 12; 124: [12]; 131: 13'; 132: [13']; 136: 8'; 138: 6'; 140: [8']; 144: 11-12; 146: [7'], 10'; 147: [8–9], 11, 13; 148: 8'-9'; 150: 9'-11'; 157: 「5?, 7¹; 158:

<sup>[77]</sup>; 160, rev. 3'; 161: 10; 170: 19; 172: 12; 177: [10']; 178: 19; 179: [17']; 181, rev. 6'; 184: 13; 185, rev. 1'; 188, rev. 9; 189, rev. [4']; 190, rev. 4'; 193: 20; 195: 「141; 196: 24; 197, rev. 3'; 198, rev. 8'; 200: 16; 202: 12; 203: 18; 204: 9'; 205: [16']; 206: [14']; 208: 19'; 210: 23; 212: 19; 214: 12'; 216: [14']; 220: [16]; 221: 18; 222, rev. 9'; 225, rev. [6']; 228: 17; 229: 19; 231: [21]; 232: 16; 233: 15'; 239, rev. 2'; 242, rev. [6']; 243, rev. 1'; 244, rev. [8']; 246: 8'; 248: 10'; 251: 13'; 253, rev. 7'; 254: [1']; 256: 「10'1; 257: [4']; 259: 15; 261: [13']; 263: [15']; 265: 10'; 268: 14'; 269: [3']; 275: [16], <sup>1</sup>18<sup>1</sup>; 277, rev. 3', 5a'; 278, rev. [3]; 280: 8; 281: [14]; 283: [12']; 286a, rev. 2'; 286b, rev. 4'; 287: 8, 17; 288: 5; 290: [28]; 291: 15; 292: 24; 293, obv. col. I 10'; 294, rev. col. II 10'; 296, col. II 6'; 297, obv. col. I

15', rev. col. I 11', rev. col. II 21'; 298: '5'1; 305: 8; 306: [10]; 307: '5'1; 308: '10'; 314: '15'1; 315, rev. 2', 5'; 316: 12'; 319: [8']; 320, rev. 3'; 325: 22; 326: 26; 328: 21; 329: 19, 30; 333, rev. 2'; 335: 17'; 337, rev. 6'; 339, rev. 5'; 344, rev. 9', 18'; 345: 20'; 353: '14';355: 8; 391: 4; 460: 12; 484a: 15; 487: 4; 493: 6; 586: 2, '10'; 644: 10, 16; VS 6, 4: 6.

#### Ahlamītu ša Anunītu

471: 5-6

# Anunītu

67: 10–12, 24, 26; 69: 13–14; 111: 11; 112: 13-14; 113, rev. 5'; 116: [12]; 117: 15, 17; 134: 9'; 163, rev. col. I 26', rev. col. II 15'; 165: 2; 166: 2, 6; 167: [2]; 168: 4; 172: 14, 18; 189, rev. <2'?>; 190, rev. 9'; 221: 15; 222, rev. 6'; 225: [5']; 232: 14; 237, rev. 7'; 245: 3; 253, rev. [3']; 254: [10']; 263: 13'; 267: 11'; 274: [7']; 275: 14; 280: 6'; 281: [12]; 284: [10']; 290: 11, 26; 291: 14, 26; 292: [23?]; 314: 13'; 315, rev. 4'; 319: 6'; 320, rev. 2'; 321, rev. 6'; 6; 322, rev. [7']; 323: 8'; 325: 14, 18, 26; 326: 17, 22; 327: 24; 329: 18; 333, rev. 6'; 337, rev. <sup>[5]</sup>; 339, rev. 3'; 344, rev. 6'; 350: <sup>[12]</sup>; 351: 5'; 353: 10; 355: 5; 363: 2'; 397: 4; 401: 3; 408: 2': 409: [2]: 410: 4: 426: 2: 427: 4'; 439: 2; 441: 11; 442: 2; 465: 3; 471: 3, 6; 472: 2, 10, 14; 483: 3; 489a: 6; 490: 3; 502: 3; 511: 8; 536: 6; 538: 4; 540: 5; 548: 3; 562: 3; 573: [3]; 575: 3; 576: <sup>[41]</sup>; 604: 5; 608: <sup>[41]</sup>; 609: 3, 5, 10; 642: 3; BM 83328: <sup>[12]</sup>; BM 83776: 7'.

# Aya

1: 4; 2: [4]; 3: 7; 4: 3; 5: 4; 6: 2, 8; 7: [1], 8; 8: 5; 9: 4; 11: 6; 16: 5; 17: 3; 18: 5; 21: 5, rev. 5'; 23: 3; 24: [4]; 26: [4]; 27: [4]; 28: [6]; 29: [4]; 32: [5]; 34: 4; 48: 6; 49: 6'; 50: [7], 9; 52: 6, 8; 56: 9; 57: 8–9; 58: 8; 59: 12; 60: [7]; 62: [6–7]; 64: [5]; 66: 8; 67: 6, 20–22; 68: 6, rev. 3'; 69: 8; 71: 8; 72: [8]; 74: 8; 77: 6, [8]; 79: [12]; 82: [9]; 83: 7; 84: [9]; 85: [6], 22; 86: 7!; 87: [10]; 88: 9; 89: [6']; 90: [6'?]; 91: 8; 93:

[6']; 94: [5'?, 7']; 95: [7?]; 97: [6']; 98: [5']; 100: 7'; 101: <sup>[6]</sup>; 102: [6]; 103: 「10'」; 104: 10; 106: [10]; 107: [10?]; 108: [7]; 111: 8; 112: 8–9; 113: [7]; 114: [8]; 116: 9; 117: 11; 118: [9]; 119: 8; 120: 6'; 121: 5, [13?]; 122: 7-8; 123: 8–9; 124: [10]; 125: [8]; 126: [7]; 131: [7']; 132: 4', 6'; 133: [7']; 134: [5'?, 6]; 135: [6]; 137: [3']; 138: 3'; 139: 「3'1; 140: 4'; 141: 13; 143: 4; 144: 8; 145: 7-8; 148: 3-5'; 149: [6]; 150: 3'; 151: [3']; 152: 3'; 156: 7'; 160: [1']; 161: 5, 7; 163, rev. col. I 10', 12'; rev. col. II 9', 11'; 172: 8; 173: 5; 174: [4-5]; 176: 2, 10, 18; 178: 4-5, 8; 180: 2; 181: 5, rev. 2'; 184: 7; 185: 6; 187: [7]; 189: 6; 190: 9; 192: 3; 193: [7]; 194: 7; 195: 6; 197: [8]; 198: 6; 200: [6]; 201: 6; 202: 6; 203: 6; 204: 5'; 205: 4'; 206: 5; 207: 7'; 208: [7']; 209: [7]; 210: 10; 211: [6']; 212: 7; 213: [7']; 214: 5'; 215: [4']; 216: [7']; 217: [7]; 218: 6; 220: [7]; 221: 6; 222: [7–9]; 223: [5]; 226: [6]; 228: 7; 229: 7; 229a: [6]; 231: 6; 232: 6; 233: 5'; 234: [3']; 235: 7'; 236: [3']; 237: 8, 11; 238: 6; 239: [7]; 240: [6]; 242: 7; 243:  $\lceil 7 \rceil$ ; 246: [2']; 247: 3'; 251: 5'; 254: 1'; 255: 6'; 256: [1']; 260: [3']; 261: [3']; 263: 3'; 264: 7; 268: 2'; 270: [3']; 271: [6]; 273: [6]; 275: [7]; 277: 6; 279: 1'; 281: [6]; 287: 3, 15; 288: [3], [10]; 289: [5]; 290: 9, 18; 291: 6, 22; 292: 9, 19; 293, obv. col. I <sup>6</sup>7, rev. col. I 8; 294, obv. col. I [17'], rev. col. II [7']; 295 col. II [7']; 297, obv. col. I 13', rev. col. I [7'], col. II 18'; 299: 18'; 301: 4; 305: [4]; 306: 6; 307: [2']; 308: 5; 22: [4]; 309: 6; 310: 4', 10'; 312: [3']; 314: [3']; 315: 6; 316: 6; 317: [2']; 321: 4, 6, 10; 322: [4']; 323: 4'; 324: [16], 26; 325: 5, 7, [10]; 326: 6, 8, 11; 327: 9, 11; 328: 5, 9; 329: 6– 7, 23; 332: 5; 333: 1', 5'; 334: 1'; 335: 4'; 336: 2'; 340: [7]; 344, rev. 13'; 346, rev. 3'; 348: [3]; 350: 4; 353: 5; 359: <sup>[2]</sup>; 370, rev. 4'; 375: <sup>[4]</sup>; 430: 9; 437: 4; 467: 2; 469: 3; 484: <sup>[4]</sup>; 484a: 12; 486: 3; 517: 3; 518: 7; 523: 3'; 524: 2; 530: 4; 537: 4; 539: 4; 541: 4, 6; 542: 3; 543: 5; 549: 11; 609: 9; 625: 7; 644: 4.

Published in NABU 2001, No 60, p. 59.

Bēl

611: 8.

#### Bēlete

181: 7; 195: 7; 232: <sup>[9]</sup>; 234: [4']; 259: 13; 271: 7; 314: [16']; 362: 4.

#### Bēltija (GAŠAN-ja) or Şarpanītu) marked (G) and (S)

314: [16'] (G?); 320, rev. 5' (\$); 323: 10' (\$); 328: 12 (G); 329: 13 (G); 333: 8' (G); 335: 14' (\$); 336, rev. [3'] (G).

#### Bunene

1: 5; 2: 4; 3: 6; 4: 4; 5: 5; 6: 2, 10; 7: 2, 9, 13; 8: 7; 9: [5]; 12: 12, 15; 16: 6, 17; 17: 4; 18: 6; 19: 5; 21, rev. 7', 9', 13'; 22: [6]; 23: 6; 24: 8, 14; 25, rev. 1'; 27: 「51; 28: 4; 30: 4; 34: 5; 35: [6']-7'; 37: 2, rev. 1'; 39: 5; 44: [3]; 47, rev. 5'; 48, rev. 3; 49: 8'-9'; 50: 8; 52: 9; 53: [9]; 54: 11–12; 57: 10; 58: 9-10; 59: 13, 16; 61: 9; 62: [8]; 64: [6], 17; 66: 9, 19; 67: 19; 69: [9]; 71: 9; 76, rev. 3'; 77: [9]; 79: [10-11]; 84: [12]; 85: 7–<sup>[8]</sup>; 89: [7']; 91: 11; 98: [6']; 100: 11'; 102: 11; 103: 14'; 104: 11; 106: 11; 108: 10, 12; 111: 9; 112: 11; 114: [9]; 116: [10]; 117: 13; 118: 10–11; 120: 10'; 121: 10, 12; 122: 10, 12; 123: 14, 16; 124: [8]; 125: [9]; 126: [8]; 127: 8; 132: 7'; 134: [7']; 136: [4']; 137: 6'-7'; 139, rev. 3'; 140: 6'; 141: 7; 143: 6, 8; 144: 9–11; 146: 10', 11'; 151: 5'; 152: 7'; 153: 2; 163, rev. col. I [15], rev. col. II 17; 170: 9, 11; 171: 5; 176: 3, 7; 177: [7'-8']; 178: 13, 16; 179: 13'-14'; 180: 5, 7, 14; 181, rev. 4'; 182: 12; 183: 16'; 184: 9; 189: <sup>[8]</sup>; 192: 4, rev. 3'; 193: [9]; 195: 9; 196: 16; 198: [7]; 201: 8'; 202: [8]; 203; <sup>[8]</sup>; 204: 7a'; 205: <sup>[8]</sup>; 206: [9']; 207: [11']; 208: 12'; 210: <sup>[15]</sup>; 211: [9'?]; 212: 9; 213: 12'; 214: 10'; 216: [10']; 217: [11]; 218: [10]; 220: [11]; 221: 8; 222, rev. [1']; 224: [8]; 228: 9; 229: 11; 231: 9; 232: 8; 233: 9'; 236: 7'; 237, rev. [1']; 239: [11]; 240: 10; 246: 6'; 249: 5'; 251: [7']; 256: 5'; 261: [7']; 262: 2'; 263: [7']; 264: 12; 266: 4'; 267: [2']; 268: 6'; 274: [2'1]; 275: [9]; 276: [6']; 279: [6']; 280: 1'; 281: [9]; 283: [5]; 284: [4']; 286: 4'; 286a: [4?]'; 287: 4, 19; 288: 14; 290: 12, 22; 291: 9, 23; 292: <sup>1</sup>10<sup>1</sup>, 21; 293, obv. col. I 8', rev. col. II

[2'], 5'; 294, obv. col. I 7'; 295, col. I 5'; 297, obv. col. I [2'], 14, rev. col. I [9', 16'], rev. col. II 2', 19', [25']; 298: 9'; 299: 6', [11']; 301: 5, 14; 303, col. I 「1'1; 304: 5; 306: 7, 16; 307: [11']; 308: 7, [15]; 309, rev. <sup>[4']</sup>; 310: 11'; 312: 7'; 314: 4'; 11'; 316: [8], rev. 7'; 317: 4'; 319: 4'; 321: 12, rev. [9']; 323: 6'; 324: 8, 10, [13], 19; 325: 12, 16; 326: 13, 19; 327: 13, 17, 20; 328: 15, 23; 329: 10, 16, 25; 333: 11', rev. 4'; 334: [5'?]; 335: 6'; 336: 5'; 339, rev. 1'; 344, rev. 4', [14']; 348: 3; 351: 3', rev. <sup>[4']</sup>; 353: 7'; 355: 10; 358: 3; 359: 3; 367: 10; 368: 2'; 369: 17; 377: 5'; 383: 4; 447: 5; 459: 3; 460: [12]; 477: 2; 484: [2]; 484a: 8, 10; 485: 6; 488: [10-11]; 492: 3; 493: 4; 505: 3'; 506: <sup>[9]</sup>; 507: 4; 513: 3; 514: [6]; 519: 6; 529: 5; 597: 3; 644: 6, 15, 19.

#### Dumuzi

427: 11'.

#### Gula

54: [15]; 64: [15]; 67: 18; 68, rev. 11', 13'; 69: 18; 73: 2; 76: 4'; 78, rev. [5']; 79: [15–16]; 83: 15; 84: [13–15]; 85: <sup>1</sup>7<sup>1</sup>, 18, 19; 86: 11–13; 91: 16–17; 97: 14'-[15?]; 104: 15; 108: [17]; 112: 17; 113, rev. 4'; 115: 3'; 116: [15–16]; 118: [16-17]; 122: [15, 17]; 123: 13, 15; 124: [13]; 132: 10'-11'; 136: 5'; 138: 「81; 148: 9'; 150: 12'-13'; 152: 9'; 157: 6; 158: [5']; 161: 11; 162: [7']; 164: 12; 170: 1; 182: 16; 189, rev. 3'; 190, rev. 2'; 193: 18; 195: [13]; 196: 28; 197, rev. 1'; 198, rev. 6'; 200: [14]; 203: 16; 205: [14]; 206: [13']; 207: 17'; 210: 21; 212: 18; 213: 9'; 220: [14]; 221: 16; 222, rev. 7'; 228: 15; 229: 17; 231: 18; 232: [15]; 233: 13'; 242, rev. [4']; 244, rev. [7']; 251: 11'; 253, rev. [5']; 255: 8'; 256: 8'; 257: [3']; 259: 19; 260: 5'; 261: [11']; 263: [14']; 265: 9'; 268: 12'; 286b, rev. 2'; 271, rev. 1'; 275 [15]; 277, rev. 3'; 280: 7'; 283, rev. [10']; 290: 27; 292: 23; 313, rev. [1']; 314: 14'; 316: 10, rev. 10'; 319: [7']; 320: 10; 321, rev. 10'; 323: 9'; 324: 12, 19; 325: 15, 19; 326: 18, 23; 327: 16, 26; 328: 20, 26; 329: 26; 333, rev. [1], 7; 334: 11'; 335: 16'; 339, rev. 4'; 342:

12; 344, rev. 8', 17'; 345: 9'; 351: 6', rev. 8'; 352: 6; 355: 11; 363: 4'; 367: ¹11¹; 370, rev. 5'; 391: 8; 412: 2; 419: 3; 486: 5; 520: 9; 586: 14.

#### Immertu

321: 11; 323: 5'; 325: <sup>[11]</sup>; 326: 12; 327: 12; 329: 22; 333: 6'; 335: 5'.

#### Ištar-šamê

574: 1, 6.

#### mārāt Ebabbar

16: 16; 21, rev. 11'; 101: <sup>[1']</sup>; 143: <sup>[9]</sup>; 163, rev. col. I 17'; 164: 9; 170: 15; 177: [3']; 178: 11, 30; 180: 4, 19; 181, rev. 10'; 182: 14-15; 183: 13'; 184: 11; 193: 11; 194: [9]; 196: 13; 198: 8; 201: [9]; 202: [10]; 203: 10; 204: 6'; 205: 6'; 206: [7']; 207: [9']; 208: 9'; 210: 12; 211: [8']; 212: 11; 213: 9'; 214: 7'; 215: 「6'<sup>1</sup>; 216: 12'; 217: 9; 218: [8]; 220: 9; 222, rev. [2']; 228: 11; 229: 9; 229a: [7]; 231: 12; 233: 7'; 239: 9; 240: <sup>[8]</sup>: 242: 9: 246: 4': 248: 8': 249: 7: 252: 6'; 253: 「3'1; 261: 7'; 262: 「4'1; 263: 5'; 264: 9; 265: 5'; 267: [4']; 268: 4'; 270: [4']; 272: [5']; 275: [8]; 276: [4']; 279: [3']; 281: [7?]; 284: [2']; 286: <sup>[2]</sup>; 286a: 2'; 287: 21; 288: 12; 289, rev. <sup>5</sup>?, 7'?, 8a'<sup>1</sup>; 290: 20; 291: 7; 292: 20; 293, rev. col. I [1'], rev. col. II 6; 294, obv. col. I [11]; 295: 8; 297, obv. col I 6'1, rev. col. II 6'1; 298: 10'; 299: 7'; 300: 2'; 301: 15; 302: 53'; 304: [6]; 306: 17; 309, rev. <sup>[5]</sup>; 310: 6'; 312: 「9'-10'1; 644: 20.

#### Marduk

314: 16'; 316, rev. 4'; 320, rev. 5'; 323: <sup>[10]</sup>; 324: 20; 325: 21; 326: 25; 328: 12; 329: 13; 333: 8'; 335: 14'; 336, rev. 3'; 633: 4.

#### Nabû

376: 13.

#### Nergal

597: [4].

**Nin**- [x]

320: [8-9]

# Nin-[ŠA]

260, rev. 2'; 329: 11, 17; 355: 6.

# Şalam šamê

597: 9.

### Šala

11: 12; 12: 5; 16: 8; 17: [7]; 18: 9; 25, rev. 4'; 26: [7]; 27: [7]; 36: 5; 47, rev. 8'; 49: [7']; 50: 10; 52: 13; 54: 14; 56:

10-11; 58: 12; 59: 18; 62: <10>; 63, rev. 3', 6'; 64: 11; 66: [18]; 67: 27!; 68, rev. 8'; 69: 15; 76, rev. <2'>; 77: [19]; 78, [4']; 83: 11, 13; 84: [19]; 85: [13–15]; 90, rev. 2'; 91: 15; 100: 9'; 101, rev. 5'; 102: 14; 104: 17; 106: 17; 108: [16]; 110, rev. [5']; 111: <12>; 112: 16; 116: [17]; 118: [14]; 122: [13]; 123: 12; 124: [12]; 131: [13]; 132: [14']; 136: 8'; 138: 6'; 140: [8']; 143: 7; 144: 13; 146: 8'; 147: 11; 148: 8'; 150: 9'; 154, rev. 7'; 158: [7]; 170: 21; 173: [23]; 177: [12]; 178: 22; 179: [17']; 181, rev. [8!]; 184: [15]; 185, rev. 3'; 188, rev. 9; 189, rev. [5']; 190, rev. 6'; 193: [22]; 194, rev. 3'; 195: 15; 196: 26; 197, rev. 5'; 198, rev. 10'; 200: 18; 202: 14; 203: 19; 204: 10'; 205: [18']; 206: [15']; 208: [22]; 210: 25; 212: [20]; 214: [14]; 220: [18]; 221: 20; 222, rev. [10]; 225, rev. [8']; 228: 18; 229: 21; 231: [24]; 232: 17; 233: [17']; 239, rev. 4'; 242, rev. [8']; 243, rev. 3'; 244, rev. 10'; 246: <sup>[10']</sup>; 251: <sup>[15']</sup>; 255, rev. 2'; 256: 12'; 257: [5']; 259: 17; 261: [14']; 263: [16']; 265: 11'; 268: 16'; 269: [5']; 271, rev. 4'; 275: [17]; 277, rev. 9'; 278, rev. [5']; 281: [16]; 283: [13']; 286a, rev. 3'; 287: 8, 23; 288: [15]; 290: 29; 291: 16; 292: 25; 293, obv. col. I 10'; 294, rev. col. II [10']; 296, col. II [6']; 297, obv. col. I [16'], rev. col. I [11'], rev. col. II 21'; 298: <sup>[6]</sup>; 305: <8>; 306: <sup>[10]</sup>; 307: <sup>[6]</sup>; 308: [11]; 314: 「20']; 316: 12'; 319: [10]; 320, rev. 4'; 325: 23; 326: 27; 328: 22; 329: 19; 333, rev. 3'; 335: 17'; 337, rev. [7']; 339, rev. 6'; 344, rev. 10', [18']; 352: 2; 353: 14; 355: 9; 378: 12'; 391: 4; 486: 5; 515, rev. 6'; 586: [10?]; 644: 10.

#### Šamaš

1: 4; 2: 「4¹; 3: 4; 5: 3, 10; 6: 1, 8; 7: [1], 7, 12; 8: 4; 9: 4; 11: 6; 13: 3; 14: 3; 16: 4; 17: 2, 5; 18: 5; 19: 2; 21: 5; 22: 4; 23: 3; 24: [3]; 25: 5; 26: [3]; 27: [4]; 28: 2–3, 6; 29: 4; 30: 3; 32: [4]; 34: 1, <4>; 35: 1', 4'; 37: 1, rev. 2'; 38: 3'; 44: [2]; 47, rev. 8'; 48: 4–5, [6], rev. [1']; 49: 1'–2', 4'; 50: [3–6], 9; 51: 3, [5–8]; 52: 3–7; 53: 6, 8; 54: 4–5, 8; 55: 5, 8, [9–11]; 56: 4–8; 57: 3–7; 58: 3–7; 59: 4–6,

8, [10]; 60: [3-6]; 61: 6-8; 62: [3-6], 13; 63: 5, 8, 11; 64: 2, [3], 5; 65: [4]; 66: 3-7; 67: 3-5, 18-19; 69: 4-5, [6], 7; 70: [4]; 71: 4–7, 20; 72: [3–7]; 74: 4– 7, 9; 75: 4, [5–8]; 76: 4, [5–8], rev. 6'; 77: 3-7, 22; 79: [4-9]; 81: 6; 82: 5, [8, 10], 14; 83: [4–5], 7; 84: [4–8]; 85: 1, [2–3], 4, [5], 22; 86: 3–6; 87: [4–9]; 88: 5-6, 8; 89: [1'-5']; 90: 2'-5', [6']; 91: 4; 92: [2-4']; 93: 2', [3'-5']; 94: 2'-6'; 95: [4-7]; 96: [2'-5']; 97: [1'-5']; 98: [1'-4']; 99: [2'-5']; 100: [2'], 4', [5']; 101: [4], 5; 102: 3–8; 103: [4'], 6', [7'– 8', 10'; 104: 4-9; 105: [4-5]; 106: 5-7, [8–9]; 107: 5–6, [7, 9]; 108: 4–6, [8]; 109: [4-5]; 110: [4]; 111: 4-7; 112: 4-8; 113: [4–7]; 114: 3?, [4–7]; 116: 4–8; 117: 6; 118: [4–8]; 119: [4], 5–7; 120: [1'-4'], 5'; 121: [1-3, 7]; 122: 3-7; 123: 4–8; 124: 4–7, [9]; 125: [4–7]; 126: 4–5, [6]; 127: [5]; 128: [2], 7–8, 10; 129: [4–5]; 130: 4, [5–7]; 131: [2'– 6']; 132: 1'-2', [3'], 4'-5'; 133: [2'-6']; 134: [1'-5']; 135: [1, 3-5]; 136: [1'-3']; 137: [1'-2'], 4'; 138: [2']; 139: [1'-2']; 140: [1'], 2-3; 141: [4], 5, [9], 11; 143: 1, 3; 144: 3-7; 145: [3], 4-7; 146: [4', 6']; 148: 1'-3'; 149: 3-4, [5-7]; 150: 「2' ]; 152: 2'; 155: 4; 156: 3'-4', 6'; 159: [5–6]; 161: 2; 170: 4–5; 171: [5], 8; 172: 6; 174: 6, rev. 5'; 176: 2, 5, 17; 177: 4', 6'; 178: 2-3; 179: [2']; 180: 2, 6, 13; 181: 10; 183: [1'], 2'-4', 6'; 184: 5; 185: 4; 186: [6]; 187: [5]; 189: [4]; 190: 6, rev. 7'; 191: [3]; 193: [5]; 195: 4; 196: 8; 197: 6; 198: [4]; 200: 4; 201: [4]; 202: 4; 203: [4]; 204: 3; 205: [2']; 206: [3']; 207: 4'; 208: [4']; 209: [5]; 210: 7; 211: [4']; 212: [5]; 213: [5']; 214: 2'; 215: 2'; 216: [4']; 217: 5; 218: 4; 219: 7; 220: [5]; 221: 4; 222: 4–6; 223: [4]; 224: [4]; 225: [5]; 226: 3; 227: [5]; 228: 5; 229: 5; 229a: [4]; 230: 2; 231: 3; 232: 4; 233: 3'; 234: [1']; 235: 4'; 237: [3], 4, 7; 238: 4; 239: 5; 240: [4]; 242: [5]; 243: 5; 248: 4'; 250: [4]; 251: [2']; 255: 4'; 264: [3]; 265: 1'; 266: [1?]; 271: 4; 272 : 9; 273: [4], rev. 8'; 275: [5]; 277: 1, 4; 281: [4]; 287: 3, [11]; 288: 3, [8]; 290: 4–8, 16; 291: 4, 19, [20]–21; 292: 4-8, [17]; 293, obv. col. I [2'-3', 5'], rev. col. I [4'-5', 7'], rev. col. II [1'];

294, obv. col. I 6', 13'-14', [16'], rev. col. II 3'-4', 6'; 295, col. I 3', col. II [3'-4', 6']; 296, col II [9'-10']; 297, obv. col. I [1'], 9'-10', 12'; obv. col. II [10']; rev. col. I [3'-4', 6', 15'], rev. col. II [1'], 14'-15', 17', [24']; 299: [10', 13'-14']; 301: [4], 9; 302: [9'-10']; 303, col. II [2', 4']; 304: [1]; 305: [1–2]; 306: 5; 307: [1', 10']; 308: [14]; 309: 1-2, 4-5; 310: 10'; 312: [2, 9]; 313: [3], 6; 314: 5'; 315: 1, [5, 7], rev. 3'; 316: 5, 11, 13–14; 319: [1'], [3']; 321: 3, 7, 9, rev. 9', 11'; 322: [3', 6']; 323: 3'; 324: 4, 6-7, [15], 23; 325: [4], 8; 326: 5, 9, 327: 5-7, 10; 328: [2, 4], 6, 8; 329: 2, 4–5, 8–9, 23–24; 332: 1, [4], rev. [3']; 333: 2', 4', 12'; 334: 2'; 335: [1']-3'; 338: 3; 339: [1], rev. 7'; 340: 2, 6; 341: [1], <sup>5</sup>1; 342: 4; 344, rev. 11'-12'; 345: 14', 18'; 347: 6'; 348: [1]; 353: 1, 3–4; 355: 6; 358: 1; 359: [2]; 367: 5: 370. rev. 4': 377: 5': 383. rev. 2'; 399: 2; 405: 3; 406: 3; 407: 2; 416: 2; 418: 6, 8; 421: [2]; 422: 4; 430: 7; 437: 2; 447: 2; 454: 2; 455: 3-4; 459: [2]; 460: 4, 11; 23: 3; 464: 3; 474: [2]; 477: 2; 478: 2; 479: 2; 484: [2]; 484a: 4-7; 485: 5, 8; 491: [2]; 492: 3; 493: 2, 4; 497: 8; 498: 2; 500: 5; 504: 4; 505: 3'; 506: [8]; 507: 2–3; 508: 5; 513: 2; 514: 2; 519: 5; 524: 5; 528: 3; 529: 4; 533: 1; 535: 8; 552: 3; 553: 3; 554: 4; 556: 4-8; 558: 3, 7; 582: 2, 4; 591: [13]; 597: 3; 603: 2; 644: 3, 14.

# Šarrat Sippar

1: 5; 5: 4; 11: 7; 15: 19; 22: [5]; 23: 3; 24: 16; 26: [5]; 29: [5]; 37, rev. 4'; 38: 4'; 39: 5; 40: 7; 42: 9; 43: 6; 47: 4; 52: 11; 66: [11]; 67: 7–9, 23; 69: 11–12; 71: 14–16; 76: 7'; 77: [11]; 79: [13]; 83: 9; 84: [10]; 85: [9, 11], 22; 86: 8-10; 87: [13], 16, 19; 88: 10; 89: [8], 10; 101: 7; 102: 12; 103: 17'; 104: 13; 106: [12]; 108: [13]; 111: 10; 112: 10; 116: [11]; 118: [12–13]; 121: 5; 122: 9; 123: 10; 124: [11]; 128: 12; 132: 9'; 137: 5'; 134: 8'; 138: 4'; 139: 4'; 140: 5'; 143: 5; 145: 9–11; 147: [2], 3–4; 148: 6; 150: 6-8'; 152: 5'; 154: 4'; 163, rev. col. I [23'], rev. col. II 13'; 170: 13; 171: 5–6; 172: 10; 174: 8, rev. 7'; 179: 19'; 181, rev. 12'; 192: [7]; 193: 16; 195: [12]; 196: 22; 198, rev. 4'; 200,

```
rev. [13]; 203: 14; 205: 12'; 206: [12'];
207: 15'; 208: 16'; 210: 19; 211: [15'];
212: 17; 220: 13; 221: [11]; 228: 14;
229: 15; 231: 16; 232: 10; 233: 11';
237, rev. 7'; 239: [14]; 242, rev. 2';
249: 12'; 252: 13'; 254: 8'; 256: 6';
257: 2'; 261: [10']; 262: [7']; 263: [8'];
266: [8']; 267: 7'; 268: [10']; 274: [4'];
275: [11]; 277, rev. 2'; 280: [3']; 281:
[10]; 286: [6']; 286a: 6'; 283: [8']; 284:
<sup>[7]</sup>; 289: [6]; 290: 10, 23; 291: 10, 24;
292: [12], 22; 297, rev. col. I [8'], col.
II 10'; 299: 19'-20'; 300: 6'; 306: [8];
309: 7; 312: 5'; 314: 12'; 316: 9, rev.
8'; 319: 5'; 321: 2-3 ; 323: 7'; 324:
11, [14], 18; 325: 13, 17; 326: 15, 21;
```

327: 「141; 22; 328: 16, 18, 24; 333: 12', [14'], rev. 5'; 334: 8'; 335: 7', 13'; 338: 13; 339, rev. 2'; 344, rev. 5', [15']; 351: 4', rev. <sup>[5']</sup>; 353: 9; 359: 9; 373: 11; 383, rev. 6'; 416: 15; 419: <sup>1</sup>4<sup>1</sup>(?); 425: 3; 436: 3 (GAŠAN); 440: <sup>[8]</sup>; 456: <sup>[3]</sup>; 462: 3; 471: 3; 489: 2; 489a: 4; 490: [12]; 493: 3; 495: 3; 505: 2'; 511: 7; 514: <sup>[4]</sup>, 8<sup>1</sup>; 515, rev. 1'; 525: 10; 536: 5; 541: 9; 617: 9'; 624: 6; 637, rev. col. I 5.

#### Ziqqurat

314: 17'; 316, rev. 6'; 320, rev. 6'; 323: 「11」; 324: 22; 325: 20; 326: 24; 328: 13; 329: 14; 333: 9'; 336, rev. 4'; 344, rev. <sup>[3]</sup>.

# Terms of garments and fabrics

Note that in the Index data from texts not published here are sometimes also included. It is easy to recognize such a text because after the signature there is no number for the text in this volume.

```
adīlu
written regularly in plural:
  a-di-la-nu BM 65211: 9'
  a-di-lu<sup>meš</sup> 173: 11; 350: 5; 517: 2; 524:
    4; 549: 10; 609: 8; 617: 8; 624: 5;
    Cam 230: 2; Nbn 751: 2.
adīlānu of kusītu of:
  Aya 517: 2; 524: 4; 549: 10; 609: 8;
    Cam 230: 2; Nbn 751: 2.
  Sarrat Sippar 624: 5
  Unidentified BM 65211: 9'.
Colour
  takiltu: 624: 5; Cam 230: 2; Nbn 751:
ayāri pāni 42: 4; 170: 8, 21; 174: 7; 177:
  13; 200: 12; 214: 5 (pa-ni <sup>[a]</sup>-[a-ri];
  350: rev. 5'; BM 68164: <sup>[10]</sup>.
ayari pāni of:
  Aya: 170: 8; 214: 5
  Šala: 170: 21
  Šarrat Sippar: 174: 7; 200: 12.
andullu 425: 2; 426: 2; 427: 6', 9'; CT
```

56, 425: 3; CT 56, 426: 3; CT 56, 427:

3; Nbn 514: 3; Nrg 19: 3.

```
andullu of:
 Anunītu 426: 2
 GAŠAN-AN.NA Nrg 19: 3
 Šarrat Sippar: 425: 3; 427: 6'.
```

# gamidatu 453: 6.

```
guḥaṣṣu
regular writing: gú-hal-şu, usually pre-
  ceded with determinative:
atypical writing:
  gu-ḥa-aṣ 237: 5.
  gú-ḥaṣ-ṣa 176: 5–6.
  gú-hal-și 189: <sup>[3]</sup>; 227: 4 ([gú]-hal-
    \lceil si \rceil); 609: 9.
preceded with GADA 114 attestations.
followed with GADA 196: 6.
preceded with túg 181: 6'; 208: 11',
  <sup>1</sup>18?<sup>1</sup>; 216: 9'; 236: 7; 237: 5; 239: 4;
  251: 12'; 275: 5; 609: 9.
preceded with sig: 387: 2.
not preceded with determinative: 32 at-
```

testations. preceding sign cannot be reconstructed: 256: 4'; 264: 11; 286: 3'.

<sup>síg!</sup>h[a-á]š-hu-ri 13: 9

#### guhalşu/guhaşşu of: hullānu Typical writing: hu-ul-la-nu and hu-la-nu Adad 184: 12; 189, rev. [4']; 190, rev. 3'; 193: 19; 195: 14; 196: 23; 197, Rare writings: rev. 2'; 200: 15; 203: 17; 206: 14'; hu-la-na 226: 8 hu-la-an-na 237: 4, rev. 9' 210: 22; 212: 19; 214: 11'; 216: 13'; 220: 15; 221: 17; 222, rev. 8'; 228: hu-la-an-nu BM 51467: 3 hu-ul-la-an-nu BM 51467: 9 16; 229: 18; 232: [16]; 233: 14'; 239, preceded with GADA: 130 attestations. rev, 2'; 242, rev. 6'; 246: 7'; 248: 9'; with reconstructed GADA: 204: [2]; 225: 251: 12'; 257: 4'(?); 259: 14; 261: 4; 238: [3]; 240: [3, 9]; 248: [2', 9']; 「12'¹(?)'; 263: 15'; 265: 10; 268: 276: 「5'1; 281: 「3, 81. 13'; 269: [2]; 275: 16; 278: 2'; 281: followed with GADA: 277: [1]. <sup>[</sup>13]; 290: [28]; 291: 15; 292: 24. preceded with túg 222, rev. 24'; 236: 6'; Anunītu 167: 8, 11; 263: <sup>[9']</sup>, and 263: 10'; 267: 8'; 280: 4'; 290: 24. probably 472: 5. preceded with sig 237: 4, rev. 9. **Bunene** 176: 6; 184: 8; 185: <sup>7</sup>7; 189: without determinative 186: 4; 196: 5, 14; 7; 192: 4; 193: [8]; 195: 8; 196: 14; 221: 12; 250: 3; 281: [11]; 321: 3; 370: 197: 9; 201: 7; 202: [7]; 203: [7]; 1, rev. 6'; Cyr 109: 4, 10; Nbn 164: 14. 206: [8']; 207: 10'; 208: 11'; 210: Quality/Shape 13; 212: 8; 213: 11'; 214: 8'; 216: new (eššu): 320: 3; 324: 4, 8; 325: 4; [10']; 217: 10; 218: [9]; 220: [10]; 326: 5' 376: 1; Nbn 137: 1, 8; Nbn 221: 7; 228: 8; 229: 11; 232: 7; 233: 143: 1. 8'; 236: 7; 239: 11; 240: 9; 246: 5'; old (labīru): Nbn 252: 5. 249: [4]; 252: 7'; 254: 3'; 256: 4'; open (petû): Nbn 115: 5. 261: [6']: 262: 1': 263: [6']: 264: 11: hullānu of 265: 10; 272: 7'; 274: 1'; 286: 3'; Anunītu 222, rev. 4'; 232: 11; 254: 290: 21; 292: 21. [10]; 263: 10'; 267: 8'; 221: [12]; **Šamaš** 176: 5; 183: 4'; 184: 3; 185: 3; 275: 12; 280: 4'; 290: 24; 291: 12. 186: 4; 187: 4; 189: [3]; 190: 5; 191: **Bunene** 184: 8; 185: <sup>7</sup>7; 189: <sup>7</sup>7; 195: <sup>[3]</sup>; 193: [3]; 195: 3; 196: 6; 197: 5; 8; 196: 14; 197: [9]; 201: 7; 202: [7]; 200: 3; 201: 3; 202: 3; 203: [3]; 204: 203: 7; 206: 8'; 208: [10]; 210: 13; 2'; 206: 2'; 210: [4]; 212: 4; 213: 4'; 211: 「9'1; 212: 「81; 213: 10'; 214: 8'; 217: 4; 219: [5]; 220: 4; 221: 3; 225: 217: [10]; 221: 7; 228: 8; 231: [7]; 5; 227: 4; 228: 4; 229: 5; 229a: [3]; 232: 7; 233: 8'; 239: 10; 240: [9]; 231: 2; 232: 3; 233: 2'; 237: 5; 238: 246: 5'; 247: 4'; 249: 3; 251: 6'; 252: 3; 239: 「41; 240: 3; 242: 「41; 243: 4; 7'; 254: 「2'1; 261: 6'; 263: 6'; 265: 248: 2'; 250: <sup>[4]</sup>; 271: 3; 275: 5; 281: [6']; 266: [2']; 272: [6']; 274: 1'; 4: 290: 16: 291: 3; 292: 16; BM 275: 9; 276: 「5'1; 281: 「81; 290: 21; 83534: <sup>[3]</sup>; Cam 414: 3. 291: 8; 321: 3, rev. 9; 324: 8; 367: Unidentified 181: 6; 209: 9; 211: 10'; 10; 370, rev. 6'; Cyr 109: 10 (?); Cyr 225, rev. 6'; 231: 19; 262: 8'; 270: 241: 10; Dar 62: 8. 5'; 490: 8, 12; Cyr 109: 14. Šamaš 184: 3; 186: 4; 187: 4; 189: 3; Colour 190: 4; 191: 2; 195: 3; 196: 5; 197: 5; peşû: 167: 8; 169: 6. 200: 3; 201: 「3」; 202: 3; 203: 3; 204: tabarri: 169: 8. [2]; 206: 2'; 207: 1'; 209: 4; 210: 4; guhassātu: 211: 「2'」; 212: 4; 217: 4; 219: 5; 220: 359: 4 $(gu-hal!-\lceil sa-a\rceil-\lceil tu_4\rceil)$ and gú-4; 221: 3; 222: 5; 223: 3; 225: 4; 226: haş-şu<sup>meš</sup> 490: 8, 12. 1'; 227: 3; 228: 4; 229: 4; 229a: 3; 231: 1; 232: 3; 233: 2'; 237: 4; 238: hašhuru HAŠHUR 14: 5; 453: 4. 「3<sup>1</sup>; 239: 4; 240: [3]; 242: 4; 243: 「4<sup>1</sup>; 248: [2']; 250: 3; 251: 1'; 255: 2'; <sup><síg></sup>haš-hu-ru 13: 5; 15: 3, 13.

271: 「3'」; 277: 「1¹; 281: 「3¹; 290: 15;

291: 3; 315: 5; 321: 3, rev. 9'; 322: 「3'1; 324: 4; 325: 4; 326: 5; 340: 5; 367: 5; BM 61601: [3']; Cyr 109: 4; Dar 62: 4; 193): 3; Nbn 115: 5.

Unidentified 181: 3; 182: 5; 226: 8; 237: rev. 9'; 242: 10; 281: <sup>[11]</sup>; 349: 3'; 367: 6, 8.

#### Colour

tabarri (all Anunītu) 263: 10; 267: [9']; 290: 24; 291: 12.

#### huşannu (TÚG.NÍG.ÍB.LÁ)

TÚG.NÍG.ÍB.LÁ: 136 attestations TÚG.NÍG.UB.BAL 86: 6-7, 9, 13.

syllabically and not preceded with determinative:

hu-şa-an-na 472: 12; 7: 6

hu-şa-an-ni 57: 5, 8; 88: 8-10.

hu-şa-an-ni-e 30: 1; 134: 4', 6', 8'-9'; 502: 2, 6, 10.

hu-şa-an-nu 472: 12

*hu-şa-ni-e* 7: 7; 102: 7, 9, 13, 16; 134: 4', 6', 8'-9'; 391: 3, 6; 472: 16.

preceded with determinative:

túghu-șa-an-ni-e 34: 3-4

túghu-ṣa-ni-e 7: 11; 48: 5; 50: 6, 7, 10; 102: 16; 143: 8–9; 352: 1, 3.

túghu-ṣa-nu-ni-e 143: 3, [4–5](?) túghu-şa-nu<sup>meš</sup> 35: 4'-5'; 427: 11.

Total of 36 syllabic writings.

# huşannu of

**Adad and Šala**: 49: 7'; 50: 10; 58: 11; 62: [9']; 76, rev. 2; 78, rev. [4']; 85: 14; 91: 15; 100: 9'; 101, rev. 5'; 102: 13; 108: 16; 118: 14; 131: 12'; 132: 12'; 136: 7'; 140: [8]; 143: 7; 147: 10; 148: 7'; 150: 9'; 288: 5; 293 I 9'-10'; 294 I 1'-2'; rev. II 9'-10'; 297 I 116', rev. II 20'-21'; 301: 6; 305: 7; 307: 4'-6'.

Anunītu: 111: 11; 134: 9'.

Aya: 34: 4; 49: 6'; 50: 7; 57: 8; 58: 8; 62: [7]; 71: 8; 72: 8; 82: 9; 83: [6??]; 84: [9]; 85: 6; 86: 7 (TÚG.NÍG.UB. BAL); 87: 10; 88: 9; 91: 8; 94: [7']; 97: 6'; 100: 6'; 101: 6; 102: 9; 103: 11'; 108: 7; 111: 8; 118: 9; 125: 8; 126: [7]; 131: 「7'¹; 132: 6'; 133: 「7'¹; 134: 6'; 136: 6'; 137: 3'; 139: 3'; 140: 4; 141: 12; 143: [4]; 148: 5'; 150: 3'; 151: [3']; 152: 3'; 160: 1'; 293 I 6', rev. I 8'; 294 I [17'], rev. II 7'; 297 I 13', rev. I 7', col. II 18'; 301: 4; 303 II [5]; 305: [4]; 306: 5; BM 73909: <sup>[6']</sup>.

Bunene: 143: 8; 293 rev. II 4'; 294 I 9'; 297 rev. II 4', [25']; 300: <sup>[1]</sup>; 30): 15; 301: 13.

Dumuzi: 427: 11'.

Gula: 84: 15; 85: 18; 86: 13
(TÚG.NÍG.UB.BAL); 91: 17; 102: 16; 115: 2; 118: 16; 132: 10'; 136: 5'; 138: 7'; 150: 13.

mārāt Ebabbar: 143: 9; 293 rev. II 6'; 294 I 10'; 295: 7'; 297 I 5', rev. II 5'; 298: [10']; 299: [7']; 301: 15; 300: 2'; 302: [3']; 304: [6]; 306: 16.

**Šamaš**: 30: 3; 49: 4'; 50: 6; 51: <sup>[6]</sup>; 57: 6; 58: 7; 60: 5; 62: [5]; 71: 7; 72: 7; 75: 7; 76: 7; 83: 5; 85: 5; 86: 6 (TÚG.NÍG.UB.BAL); 88: 8; 89: [3']; 90: 4'; 91: 6'; 92: [2]; 94: 6'; 96: 4'; 97: 4'; 98: 4'; 100: 3; 101: 57; 102: 7; 103: 7'; 107: 8; 108: 6; 111: 7; 118: 7; 125: 6; 126: [6]; 128: 9; 130: [7]; 131: 6'; 132: 5'; 133: 「5']; 134: 4'; 135: [5]; 136: 3'; 137: 2'; 139: 2'; 140: 2'; 141: [9]; 143: 3; 148: 2'; 150: <sup>[2]</sup>; 152: 2'; 156: 3'; 288: 3; 293 I 5', rev. I 7'; 294 I 16'; rev. II 6'; 295 II 5'; 297 I 12', rev. I 6', II 17'; 299: 16'; 301: 3; 303 II 4'; 305: 4: 306: 4.

**Šarrat Sippar**: 71: 15; 85: 9; 86: 9 (TÚG.NÎG.UB.BAL); 88: 10; 89: 8'; 91: 9; 102: 12; 103: 16'; 108: 13; 111: 10; 118: [12]; 128: 12; 132: 8'; 134: 8'; 137: 5'; 139: 4'; 140: 5'; 143: 5; 147: 1; 150: 6'; 152: 「4']; 303 II [6'].

Unidentified 115: 5; 125, rev. 4'; 126: 12; 142: 4'; 157, rev. 8; 160, rev. 1'; 169: 4; 297 rev. II 12'; 300: 8'.

#### izhu 511: 5; 547: 2.

kibsu 314: 14'-25'; 316, rev. 3'-13'; 317: 5'; 322: 8'-12', rev. 1'-5', 7'; 326: 9, 29, 32; 328: 23-26; 330: 4'; 331, rev. 1'; 333, rev. 4'-7'; 334: 9', 11'-12'; 335: 7'-9'; 336, rev. 2'-6' (or GADA kibsu); 337, rev. 5'-6'; 338: 10; 344, rev. 1'-6', 8'-10', 17'-18'; 360: 2; 363: 1', 3', 5'; 369: 3; 373: [8]-9.

# kibsu for

Adad 316, rev. 12'; 337, rev. 6'; 344, rev. 9', 18'.

Anunītu 316, rev. 10'; 334: 9'; 337, rev. 5'; 344, rev. 6'; 363: 1'.

Bunene 316, rev. 8'; 336, rev. 5'; 344,

```
rev. 4'.
                                                     rev. 1'-3', 7'; 324: 10-12; 326: 20, 30;
                                                     327;\ 13{-}14;\ 328;\ 6{-}7,\ 11,\ 14,\ 17;\ 329;
 Gula 316, rev. 11'; 334: 12'; 344, rev.
                                                     8, 12, 14–19; 333: 7'; 334: 6'–7', 10'.
   8', 17'; 363: 3'.
                                                   (GADA) kibsu eššu for
 mārāt Ebabbar 316, rev. 6'; 336, rev.
                                                     Adad 320, rev. 3'; 329: 19; 337, rev.
 Šala 316, rev. 3', 13'; 344, rev. 10',
   18'.
                                                     Anunītu 320, rev. 2'; 329: 18; 337,
 Šamaš 326: 32.
 Šarrat Sippar 316, rev. 9'; 344, rev.
                                                     Bunene 319: 4'; 324: 10; 325: 16; 326:
                                                       19; 327: 13; 328: 14; 329: 16; 333:
                                                       10'.
 šubat Marduk u Bēltiya 314: 16'; (cf.
   kibsu eššu ...); 336, rev. 3'.
                                                     Gula 324: 12.
 ana tabê for [DN] 314: 19', 21'.
                                                     mārāt Ebabbar 321: 7'; 328: 11; 329:
 for Ša[la] 314: 20'.
                                                       15.
 ana ziqqurat 316, rev. 7'; 336, rev.
                                                     eli šubtu Marduk u Bēltiya 329: 12'
   4'(bīt ziqqurat); 344, rev. 3'.
                                                     Nin-ŠA 329: 17.
 for PN 338: 10; 363: 5'.
                                                     Nin-[x] 320: 9.
for kibsu ana tahapšu, see under tahapšu
                                                     Šala 329: 19.
                                                     Šamaš 328: 6'; 329: 8.
                                                     Šarrat Sippar 324: 11; 326: 20; 327:
(GADA) kibsu made of salhu eššu 321:
 7: 325: 8: 326: 9. 19: 329: 8: 333: 2'.
                                                       14; 328: 17; 334: 7'.
(GADA) kibsu made of salhu eššu for
                                                     talukatu 328: 7.
                                                     ziqqurat 329: 14.
 Bunene 326: 19.
  Šamaš 325: 8; 326: 19; 333: 2'
GADA ki-ib-su 339, rev. 4'-6', 8'.
                                                   (GADA) kibsu petû eššu 321: 6; 325: 7,
GADA kib-su 314: 19'-21'; 316, rev.
                                                     16-17; 326: 8, 19
 1'-2', 5'; 318: 3-4; 319: 14'; 320, rev. 4'-6'; 322, rev. 1'-5'; 325: 8; 328: 7; 329: 29-30; 335: 12', 14'-17'; 337,
                                                   (GADA) kibsu petû eššu for:
                                                     Bunene 325: 16; 326: 19.
                                                     Sarrat Sippar 325: 17.
 rev. 5'-6'; 338: 5; 340, rev. 1'-2'; 357:
                                                     šubtu ša Aya 321: 6; 325: 7; 326: 8.
 2; 359: 8 (-si); 373: <sup>[1]</sup>, 12.
cf. kibsu GADA 317, rev. 1'-3', 5'.
                                                   (GADA) kibsu labiri 314: 17'-18'(?);
(GADA) kibsu
                                                     319: 5'-9'; 321: 12-13, rev. 2'; 324:
 ana Adad 329: 30; 335: 17'; 339, rev.
                                                     13-14, 19; 325: 12-15, 18-23; 326:
                                                     13-16, 18, 23-27; 327: 20-21, 23, 25;
 eli paššuri hurași ša Šamaš 324: 23.
                                                     328: 12-14, 17, 19-22; 333: 8'-10',
 eli šubtu ana Marduk 324: 20.
                                                     13', rev. 1'-3'; 334: 5'-7'.
 ana šubat Marduk 316, rev. 5'.
                                                   (GADA) kibsu labiri for
                                                     (ana eli) šubtu Anunītu 325: 18; 326:
 (ana) Marduk and Şarpanītu 320: 5;
   335: 14'.
                                                       22;328: 19.
 eli šubtu ana Marduk and Bēltiya
                                                     Adad 325: 22; 326: 26; 328: 21; 333,
   329: 12.
                                                       rev. 2'.
 ana Gula 335: 16'; 339, rev. 4'.
                                                     Bunene 324: 13; 328: 14; 333: 10';
 eli šubtu ana ziggurrat 324: 21.
                                                       334: 5'.
 ana ziqqurrat 316, rev. 7'; 335: 15'
                                                     Gula 324: 19; 325: 19; 326: 23; 328:
 ana Šala 320, rev. 4'; 335: 17'.
                                                       20; 333, rev. 1'.
 339, rev. 6'.
                                                     (bīt) Marduk 325: 21; 326: 25.
 ana Šamaš 329: 29.
                                                     Marduk and Bēltiya 328: 12; 333: 8'.
 ana Šarrat Sippar (?) 359: 8.
                                                     mārāt Ebabbar 324: 13; 333: 7'.
 ana tabê 314: 19'-20' (unid.), 21'
                                                     Šala 325: 23; 326: 27; 328: 22; 333,
   (Šala).
                                                       rev. 3'.
 ana PN 373: 12.
```

(GADA) kibsu eššu/e 319: 4'; 320: 9,

```
Šarrat Sippar 324: 14; 328: 17; 333:
    13'; 334: 7'
  for ziqqurat 325: 20; 326: 22; 328:
    13; 333: 9'.
  for šubat ša ziqqurat 314: 17'.
Cf. also kibsu labiri ana tahapšu under
  tahapšu
kibsu petû 324: 25; 328: 16 (for Šarrat
  Sippar).
kibsu GADA qalla 317, rev. 1'-3', 5'.
(GADA) kibsu ša/ana sūni (ÚR) 314:
  10', 22'-23'; 315, rev. 3'-5'; 316, rev.
  4'; 321, rev. 5'; 322, rev. 7'; 324: 24;
  325: 25; 327: 18; 337, rev. 4'; 344, rev.
(GADA) kibsu ša sūni for:
  Adad 315, rev. 4'; 337, rev. 4'.
  Anunītu 315, rev. 4'; 321, rev. 5';
    322, rev. 7'; 325: 25.
  Šamaš 314: 10'; 315, rev. 3'.
  PN: 327: 18.
kusītu
TÚG.BAR.DUL<sub>5</sub>: 170: 6; 180: 10, 17;
  181: 5, 7; 467: 2.
TÚG.BAR.DUL<sub>8</sub>: 170: 16; 176: 8; 178:
  4; 179: 4'; 192: 2; 249: 1', [7']; 262:
  3'; 277, rev. 4'; 288: 9; 289, rev. 6'.
SÍG. BAR.DUL<sub>8</sub>: 277, rev. 6'.
written syllabically:
  ku-sa-a-ta 256: 2'.
  ku-sa-a-tu4 195: 7; 214: 7'; 254: 1'
    (ku-sa-[a-tu_4].
  ku-sa-tu4: 242: 8; 362: 4.
  ku-satu(SAT) 603: 2.
  ku-sa-tu 242: 8.
  [ku-si-t]i 237: 11.
  [ku-s]i-tì 203: 6.
  ku-si-tu<sub>4</sub> 79 attestations.
  ku-si-tu_4^{\text{meš}} 220: 9.
  ku-si-i-tu4 196: 11, 19, 25, 28; 210: 9,
    11; 221: 6, 11, 16, 19.
  ^{\text{síg}}ku-si-tu<sub>4</sub> 228: 7, 10.
  túgku-sa-a-tú 231: 11.
  <sup>túg</sup>ku-si-ti 452: 2.
  ^{\text{túg}}ku-si-tu<sub>4</sub> 87: 「11?<sup>1</sup>; 231: 6, 14, 18;
    292: 25; 625: 6.
kusītu of
  Aya 67: 20, 22; 178: 4'; 187: [7']; 190:
```

[9]; 191: 4; 195: 6; 196: 11; 200: <sup>6</sup>; 201: <sup>6</sup>; 203: 6; 210: 9; 214: 4'; 220:

[7]; 221: 6; 228: 7; 229a: [6]; 231: 6;

```
237: 11; 238: [6]; 239: 7; 240: [6];
   242: 7; 243: [7]; 246: 2'; 247: 「3'];
   249: 「1'1; 254: 「1'1; 255: 「6'1; 350:
   4; 484: 4; 539: <sup>[4]</sup>; 609: 9; 625: 6;
   Cam 230: 2 (her adilānu ša kusītu
   made of takiltu).
 Bēlete (GAŠAN.MEŠ) 195: 7; 362: 4.
 Gula 190, rev. <sup>[2]</sup>; 195: [13]; 196:
   28; 200: 14; 203: 15; 210: 20; 220:
   [14]; 221: 16; 228: 15.
 mārāt Ebabbar 180: 17; 196: 13; 201:
   9; 202: [10]; 203: [9]; 210: [11]; 214:
   7'; 218: 7; 220: 9; 228: 10; 240: [8];
   242: 8; 246: 3'; 249: 7; 255: [7'];
   256: 2'; Cam 414: 8.
 Šala 190, rev. 6'; 195: 15; 196: 26;
   200: 17; 202: [14]; 203: 19; 210: 24;
   214: 14'; 220: 18; 221: [19]; 228: 18;
   242, rev. [7']; 243, rev. [2']; 246:
   10'; 251: <sup>[15]</sup>; 255, rev. 2'; 256:
   [12].
 Šarrat Sippar 195: [11]; 196: 19; 200:
   13; 203: 14; 210: [18]; 221: [11];
   237, rev. [7']; 239: [14]; 254: 8';
   452: 2; Cam 229: 1; Dar 322: 2.
 Unidentified 180: 10; 199, rev. 3';
   251: 4'- 5'; 252: 11'; 484a: 11; BM
   65211: 9'.
kusītu nabāsu: 178: 4'; 180: 10, 17; 195:
 6; 202: [10]; 203: [9]; 210: 9, 24; 218:
 7; 240: <sup>[6]</sup>.
kusītu tabarri of
  Aya 178: 4'; 195: 11; 196: 11; 210: 9;
   214: 4'; 240: 6.
 Bēlete 195: 7.
 mārāt Ebabbar 180: 17; 195: 7; 202:
   [10]; 203: [9]; 218: 7.
  Šala 210: 24; 214: 14'; 246: 10'.
 kusītu takilti of
 Šarrat Sippar 195: 11; 210: <sup>[</sup>18]; 452:
lubāru (TÚG.HA.A, TÚG.HI.A, TÚG.
 UD.A, TÚG.UD.HI.A)
TÚG.HA.A 447: 5.
TÚG.HI.A ca. 100 attestations
TÚG.UD.A 52: 9; 57: 3, 5; 59, rev.13;
 79: 5; 81: 6, rev. 12; 82: 5; 86: 3, 15;
 92: 2; 106: 5, 11; 179: 6; 245, rev. 12;
 292: 4, 22, 24;<sup>8</sup> 507: 2, 4.
```

<sup>8</sup> L. 22 and 24, see the commentary to the text.

<sup>12</sup> Most probably *lubār* <*kulūlu*>.

```
Anunnītu 490: 3; Cam 277: 11
TÚG.UD.HI.A 22: 2 (?); 54: 10; 69: 4, 6,
                                                         Gula 68 rev. 9'.
                                                         Šala 67: 27!; 68, rev. 7'.
lu-ba-ri 30: 1, 4, 5; 68, rev. 7' (-[ri])^9;
  500: 5.
                                                         Šarrat Sippar 67: 23; 87: 15; 163 rev.
lu-bar-ri 582: 2.
                                                           I 13' and rev. II 23' 195: 12; 196: 21;
<sup>túg</sup>lu-ba-ra 134: 1', 7'.
                                                           229: 14; Cyr 253: 9.
túglu-ba-ri 34: 1, 5; 68, rev. 10<sup>10</sup>.
                                                       Colour
túglu-ba-ru 68, rev. 4'.
                                                         tabarri: 68 rev. 7' (Šala), rev. 9'
lubāru of
                                                           (Gula).
  Adad 68, rev. 4'; 288: 4.
                                                         takiltu: 67: 23 (Šarrat Sippar); 229: 14
  Anunītu BM 83776: 6'; Nbn 415: 5.
                                                           (Šarrat Sippar); 490: 3 (Anunītu);
  Bunene 30: 4; 34: 5; 52: [9]; 53: 9; 54:
                                                           Cam 277: 11 (Anunītu).
    10; 64: 6; 69: 9; 76: [10]; 103: 13';
    112: 11; 114: [9]; 116: [10]; 123: 16;
                                                      lubār hubbitu (exclusively for Šarrat
    126: 8; 132: 7'; 134: 7'; 293 I 7', rev.
                                                         Sippar):
    I 9', II 2'; 294 I 7'; 295 I 4'; 297 I 2,
                                                       TÚG.HI.A hu-ub-bi-tu4 495: 2; VS 6,
    14', rev. I [3'], 9', 16', II 2', 19';
                                                         107: 2 (-ub-bu-).
    298: 2'(?); 299: 11'; 301: [5]; 305: 5;
    307: 11'; 308: 5; 309: 6'; 312: 6';
                                                       lubār kulūlu
    484a: 8; 507: 4.
                                                       ku-lu-lu (without determinative or pre-
  Gula 68, rev. 10<sup>11</sup>
                                                         ceding word is broken): 67: 27-28; 82:
  Šala 68, rev. 7<sup>12</sup>
                                                         12: 106: 13: 173: 21: 287: 18: 296: 6':
  Šamaš 30: 1; 34: 1; 51: 3; 52: 3; 53: 6;
                                                         354: 3; 493: 2; 513: 2; Cam 414: 5;
                                                         Cyr 253: 6, 8.
    64: [1]; 69: 4; 75: 4; 76: 4; 77: 5; 82:
    5; 90: 2'; 102: [3]; 103: [4']; 108: 4;
                                                       lu-bar ku-lu-lu 37, rev. 3'; 195: 12; 196:
    111:\ 4;\ 112:\ 4;\ 114:\ 3;\ 116:\ 4;\ 123:
                                                         7.
    4; 126: 4; 132: 1'; 134: 1'; 135:
                                                       lu-bar ku-lu<sub>4</sub>-lu<sub>4</sub> 196: 21.
    1;149: 3; 293 I [2']; rev. I [4'], II 1';
                                                       lu-bar ku<sub>14</sub>-lu-lu Cam 277: 11.
    294 I 6', 13', rev. II 3'; 295 I 3' II 3';
                                                       lu-bar kul-lu-lu 40: 2.
    296 II <sup>[9]</sup>; 297 I [1], 9, 14; rev. I
                                                       lu-ba-ri ku-lu-lu 91: 7; 174, rev. 4'; 186:
    [3'], 15', II [1'], 14'; 298: 1'(?)';
    299: 10', 13'; 301: 9; 302: 9'; 305: 1;
                                                       lu-bar-ru ku-lu-lu: 163, rev. II 14'.
                                                       TÚG ku-lu-lu 67: 23; 173: 16, 22; 288:
    307: 10'; 308: [1]; 313: 4; 484: 2;
    484a: 5; 500: 5; 507: 2; 582: 2.
                                                       <sup>túg</sup>lu-bar ku-lu-lu 195: 4; 15: 17, 19,
  Unidentified 30: 5; 64: 9; 106: 1; 293,
                                                       túglu-ba-ri ku-lu-lu BM 50392: 2, 5<sup>13</sup>.
    rev. II 3'; 294 I 6', 7', [8'], rev. II 8';
                                                       <sup>túg</sup>lu-bar-ru ku-lu-lu 209: 5.
    295 I 5'; 296 II 1'; 299: 22'; 300: 5';
    313: 7; BM 101133: 8.
                                                       TÚG.HA.A ku-lu-lu 447: 1.
                                                       TÚG.HI.A kul-lu-lu 42: 2; 163, rev. I 8',
                                                         15', [18'].
lubār erru
e-ri 67: 23; 68 rev. 9; 87: 15 (e-r[i]);
                                                       TÚG.HI.A ku-lu-lu: 96 attestations
  163, rev. I 11', 13', rev. II 19', 23';
                                                       TÚG.HI.A túgkul-lu-lu 289, rev. 5'.
  195: 12; 196: 21; 490: 3.
                                                       TÚG.HI.A ku-lu<sub>4</sub>-lu<sub>4</sub> 185: 4; 193: 4
ir-ri Cam 277: 11. <sup>túg</sup>e-ir 229: 14 (e<sup>!</sup>-ir); 354: 3.
                                                       TÚG.HI.A kù-lu-lu 484a: 4.
                                                       [TÚG.HI.A] šá kù-lu-lu 484a: 16.
túge-ri CT 55, 846: 1; Cyr 253: 9
                                                       TÚG.UD.A ku-lu-lu 67: 18, 21, 24, 25;
lubār erru of
                                                         71: 13; 210: 6.
  Aya 163, rev. I 11' and rev. II 19'.
                                                       TÚG.UD.ḤI.A ku-lu-lu: Cam 66: 4.
                                                       lubār kulūlu of
                                                         Adad 63, rev. 6' (or Šala); 67: 25; 170:
   Most probably lubār <kulūlu>.
                                                           19; 172: 12; 177: 9; 178: 17; 179:
   Most probably lubār <kulūlu>.
   Most probably lubār <kulūlu>.
```

<sup>&</sup>lt;sup>13</sup> Part I, p. 55.

15' (or Šala); 181, rev. 5'; 287: 16; 378: 8'; BM 62915, rev. 1'; BM 66394: 8'.

Aya 67: 21; 91: 7; 163, rev. I 10' and rev. II 19'; 178: 6; 179: 8'; 183: 5'; 287: 14; BM 50392: 5<sup>14</sup>

Anunītu 67: 24; 163, rev. I 15 and col. II 22'; 172: 14; 179: 8; 221: <sup>[14]</sup>; 222, rev. 6'; 225, rev. 4'; 232: [13]; 291: [14]; 350, rev. 3'-4'; 472: 10; Cam 277: 11.

Bunene 163, rev. II 14'; 177: 8'; 178: 15; 181, rev. <4'>; 284a: 6'; 287: 18; 288: 13; 484a: [10]; 514: 5; BM 51422: 8'; BM 101133: [5]; Cam 66:

**Gula** 67: 28; 68, rev. 10' (<*ku-lu-lu*>); 170: 17; Cyr 253: 6(?).

mārāt Ebabbar 289, rev. 8'; 378:5'. Šala 63, rev. 6' (or Adad); 67: 27!; 68, rev. 7'; 173: 22; 177: 11'; 178: 20; 179: 15' (or Adad): 181, rev. 8': 277, rev. 4'; 284a: 9'; 287: 22; 288: [15]; 378: [10]; BM 51422: 5'.

**Šamaš** 43: 1 (?); 63: 10; 67: 18; 71: 13; 76, rev. 6'; 82: 12; 163, rev. I 8'; 170: 5; 172: 5; 177: 5; 178: 6; 185: 4; 186: 「51; 187: 5; 190: 6; 191: 「31; 193: 4; 195: 4; 196: 7; 200: 4; 201: 4; 203: 4; 204: 3'; 206: 3'; 207: 3'; 209: 5; 210: 6; 211: 4'; 213: 5'; 215: 2'; 216: 4'; 287: 11; 288: 8; 447: 1; 460: 4; 464: 3; 484a: 4; 493: 2; 513: 2; 514: 2; BM 50392: 2<sup>15</sup>; BM 51685: 6'; Cam 414: 5; Cyr 202: 7.

**Šarrat Sippar** 20: 12; 37, rev. 3'; 40: 2; 42: 2; 67: 23; 87: 14; 91: 7; 163, rev. I 12' and rev. 22'; 172: 9; 179: 19'1; 181, rev. 11'; 195: 12; 196: 21; 203: 14; 211: 15'; 212: 16; BM 62213: 3; Cyr 253: 8; 15: 19.

Unidentified 106: 13; 163, rev. I 18'; 173: 16, 21, 25; 174, rev. 4'; 289, rev. 5'; 296: 6'; 350: 6; 354: 3; 15: 17; 451: 2; 484a: 16; 515, rev. 3'; BM 51685: 7'-8'; BM 52018 II 10'; BM 62915: 3'; BM 67458: [2'], 5', 8'.

#### lubār damqi TÚG.HI.A SAG<sup>qa</sup> 143: 2.

TÚG SIG<sub>5</sub> 6: 6; 383: 5. TÚG.HI.A SIG<sub>5</sub> 3: 3; 7: 7; 11: 4; 18: 4; 19: 3; 23: 2; 26: 2; 27: 2; 29: [3]; 63: 8; TÚG.HI.A SIG<sub>5</sub><sup>qa</sup> 28: 3; cf. below, *lubar* mē damai. TÚG.UD.A SIG<sub>5</sub> 117: 8.

#### lubar mē qaqqadi

lu-bar S[AG] 311: 2.

TÚG.HI.A SAG.DU 56: 6; 104: 6; 105: 7; 120: 4'; 121: 7; 124: 7; 306: 2; túg309: 3. lu-ba-ra me SAG.[(DU)] 134: 3'.

TÚG me SAG 50: 5.

TÚG me SAG.DU 75: 6; 111: 6.

TÚG me-e SAG 64: <sup>[4]</sup>(?).

TÚG me-e SAG.DU 155: 3 (?).

TÚG.ḤI.A me SAG.([DU]) 42: 「7」; 51: [71; 52: 5; 55: 9; 58: 5; 60: [61; 62: [41; 66: 5; 72: 5; 77: 5; 88: 7; 90: 5'; 91: 5; 94: 「4'1: 95: 「61: 98: 2': 102: 「51: 103: 8'; 113: [6]; 114: [5]; 116: 6; 122: [6]; 123: 6; 126: [5]; 131: 4'; 132: 3'; 133: <sup>[4]</sup>; 135: [4]; 136: <sup>[1]</sup>; 144: 6; 145: <sup>[6]</sup>; 149: 5; 307: <sup>[3]</sup>.

TÚG.ḤI.A me-e SAG.([DU]) 10: <sup>[2]</sup>; 16: 3; 43: 「41; 49: 「31; 89: 「51]; 112: 6; 139: 「1'1; 140: 3'; 146: 「4'1(?); 293, obv. col.I [4'], rev. col. I [6']; 294, obv. col. I 15', rev. col. II 5'; 295, col. II 5'; 297, col. I 11', rev. col. I [5'], col. II 16'; 299: [15']; 301: 2; 302: 5'; 303, col. II [3']; 644: 2.

<TÚG>.UD.HI.[A me SAG.(DU)] 69: 6. TÚG.HI.A me SIG 97: 1'.

TÚG.UD.A me SAG 57: 5; 67: 4; 79: 8; 106: 8.

TÚG.UD.A me SIG 61: 7; 93: 3'; 292: 6. TÚG.UD.A me S[IG<sup>qá</sup>/.GA] 118: <sup>[6]</sup>.

TÚG.UD.A me-si-iq 107: 7.

TÚG.UD.A me-e šá SIG/zíq? 82: 7.

TÚG.UD.A me SIG<sub>5</sub> 59: 6.

TÚG.UD. [HI.A] [me-e] šá SIG<sub>5</sub> 54: 6.

#### lubar mē damqi, or lubar siqqu/ziqqu/ mesiau

TÚG.ḤI.A SIG<sub>5</sub> 310: 9'.

TÚG me SIG<sub>5</sub> BM 83776: 6'.

TÚG.ḤI.A me SIG<sup>qá</sup>/.GA 108: 8; 290: 7; 291: 20.

TÚG.HI.A me-e SIG<sub>5</sub> 38: 2'; 127: 10; 156: 「4"1.

<sup>&</sup>lt;sup>14</sup> Part I, p. 55.

<sup>&</sup>lt;sup>15</sup> Part I, p. 55.

TÚG.ḤI.A me-e  ${
m SIG_5}^{qd}$ .GA 12: 18.  ${
m I}^{t\psi^1g}$ lu-ba-ri me-si-qu 34: 2; 35:  ${
m I}^{21}$ . lu-ba-ri-e zíq-qu 30: 2. lu-bar zíq- ${
m qu}$  > 1: 3. TÚG.ḤI.A ziq-tu<sub>4</sub> 2: 2.

#### lubār mēţu

*lu-bar me-ţù* Cam 277: 10. *lu-ba-ri me-ţu* 91: 7; 186: <sup>r</sup>6<sup>1</sup>; BM 50392: 2<sup>16</sup>.

*lu-bar-ru me-țu* 163, rev. II 13'.

lu-bar me-țu 196: 7.

túglu-bar me-ţu 195: 4; 15: 18; BM 50342, rev. 6'.

<sup>túg</sup>lu-bar-ru me-ṭu 209: 5.

TÚG.ḤA.A me-ti 91: 7; 447: 2.

TÚG.HI.A me-e-ti Cam 158: 2.

TÚG.HI.A *me-e-ţu* 170: 5, 10, 18; 460: 3-4.

TÚG.HI.A me-ta BM 101133: 5.

TÚG.HI.A me-ți 174: 9.

TÚG.HI.A *me-tu*: 58 attestations

TÚG. ÚD. A *me-tu* 67: 24, 25; 71: 12; 210: 6; 245, rev. 2'.

Cf. also țimītu ša me-țu Cyr 190: 16.

#### lubār mēţu of

**Adad** 67: 25; 170: 18; 172: 11; 178: 18; 277, rev. 3'; 284a: 8'; 287: 16; 350, rev. 1'; BM 62915, rev. 2; CT 55, 808, rev. 5'.

**Anunītu** 67: 24; 163, rev. I 14', II [24]; 172: 13; 221: 15; 232: 13; 350, rev. 3'; 472: 9; Cam 158: 2 Cam 277: 10

**Bunene** 163, rev. II 13'; 170: 10; 178: 14; 181, rev. 4'; 284: 4'; 284a: 7'; 287: 19; 288: 14; 484a: 9; BM 50342, rev. 6'; BM 51422: 8; BM 101133: 8; Cyr 259: 3.

Šamaš 72: 12; 77: 22; 82: [12](?); 163, rev. I 7'; 170: 5; 172: 5; 178: 1; 183: 6'; 185: 4; 186: ¹6¹; 187: 5; 189: 4; 190: 6; 191: 3; 195: 4; 196: 7; 200: 4; 201: [4]; 202: 4; 203: [4]; 204: 5'; 206: 3'; 207: 3; 208: ¹3'¹; 209: 5; 210: 6; 211: [4']; 212: [5]; 213: 5'; 215: [1']; 216: ¹3'¹; 287: [11]; 288: 8; 447: 2; 464: 2; 484a: 4; BM 50392: 2; ¹7 BM 51685: 5'(?).

Unidentified 91: 7; 163, rev. I 7'; 173: <sup>†</sup>21<sup>†</sup>; 174: 9; 245, rev. 2'; 350: 6; 451: 2; BM 52018 II 12'; BM 67458: 2', [8']; Cam 66: 4; Cyr 190: 16; Nbn 723: 2; 15: 18.

#### Colour

Tabarri (SÍG.ḤE.ME.DA) 183: 6' (Šamaš).

takiltu of

**Adad** 67: 25; 170: 18; 178: 18; BM 62915, rev. 2; CT 55, 808, rev. 5'.

**Anunītu** 67: 24; Cam 158: 2; Cam 277: 10.

**Bunene**178: 14; 287: 19; BM 51422: 8'; Cam 259: 3; Cyr 259: 5.

**Šamaš** 71: 12; 77: 22; 82: [12](?); 178: 1; 210: 6; 464: 2; 484a: 4; BM 50392: 2

Unidentified Cam 66: 4; Nbn 723: 2.

# *lubār pāni* (exclusively for Šarrat Sippar)

lu-bar pa-ni 196: 20; 198: [3']; 262: 6' ([lu]-bar).

*lu-ba-*<sup>r</sup>*ri*<sup>1</sup> *pa-*<sup>r</sup>*ni*<sup>?</sup> 237, rev. 6'; 284a: 4' ([*lu-ba*]-*ri*).

<sup>túg</sup>lu-bar pa-ni 195: 11.

<sup>túg</sup>lu-ba-ri pa-ni 231: 15.

TÚG.HI.A *pa-ni* 200: 11; 203: 13; 205: 11'; 212: 14; 254, rev. 8; 274: 4'; 452: 2 (*pa\*-ni\*-e*).

TÚG.HI.A IGI 193: 15.

TÚG.UD.A pa-ni 210: 17; 228: 13.

#### Colour

takiltu (SÍG.ZA.G[ÌN.KUR.RA]) 195: 11; 210: 17.

# lubār qabli (exclusively for Anunītu)

TÚG.ḤI.A *qab-lu* 165, rev. 4'; 167: 13. TÚG.ŪD.A *qáb-lu* 67: 26.

TÚG.HI.A MURUB<sub>4</sub> 221: 13; 222, rev. 5'; 225, rev. 2'; 280: 5'; 290: 25; 291: 13; 441: 11; 472: 2.

### Colour

tabarri (SÍG.HÉ.ME.D) 67: 26; 167: 13; 472: 1.

# lubār (ša) šammamu (exclusively for Anunītu)

[lu-ba]-ru šá šam-[ma-mu] 275: 14. [TÚG.ḤI]. A¹ šam-ma-ma 253, rev. 3'. [TÚG.ḤI]. A¹ šam-ma-mu 284: 10'.

<sup>&</sup>lt;sup>16</sup> Part I, p. 55.

<sup>&</sup>lt;sup>17</sup> Part I, p. 55.

TÚG.ḤI.A šá šam-ma-mu 221: 14; 284: 11'.

TÚG.ḤI.「A¹ šam-ma-mu 222, rev. 6'.

# lubār ša qabli<sup>18</sup>

TÚG šá MURUB<sub>4</sub> Nbk 183: 7, 9, 14; Camb 321: 13; CT 56, 382: 8 cf. GADA ša MURUB<sub>4</sub> in BM 60071: 4.

murisu 356: 6. muşibtu 590: 5.

muttatu (only syllabical writing):

mu-ta-ta 220: 5; 440: 13

*mu-ut-ta-tu*<sub>4</sub> 180: 9; 182: 10; 229a: 4; 232: 4; 234: 1'; 461: 3; 484a: 7; 591: 13; CT 55, 857: 5, 8; Nbn 284: 10; Nbn 349: 2.

*mut-ta-tu*<sub>4</sub> 226: 3; 348: 1; 504: 3.

mut-ta-tú 348: 7.

<sup>túg</sup>mu-ta-tú CT 55, 827: 2.

 $^{\text{túg}}mu$ -ú-ta-tu<sub>4</sub> BM 64129: 2.

túg*mut-ta-tu*<sub>4</sub> 231: 2; 391: 2.

 $[^{\text{túg}}]mu\text{-}ut\text{-}ta\text{-}ti$  5: 9; 36: 2.

#### muttatu of

Šamaš: 5: 9; 220: 5; 226: [3]; 229a: 4; 231: 2; 232: 4; 234: 1'; 348: 1; 484a: 7; 504: 3; 591: 13; BM 64129: 2.

#### Colour

takiltu 5: 9; 461: 3; 484a: 7; 504: 3; 591: 12; BM 64129: 2; Nbn 349: 2. tabarri u takiltu (?) Nbn 284: 10.

**Weight** 5: 9; 391: 1; 484a: 7; BM 64129: 1; Nbn 349: 1.

# naḥlaptu

*na-aḥ-la-ap-tu*<sub>4</sub> 237, rev. 3'–5', 8' (<*ap>*).

na-ah-lap-tu<sub>4</sub> 186: 7; 196: 10, 12, 17–19, 25, 27; 200: 5, 11, 14, 17; 209: 6, 8; 220: 6–7, 14, <sup>1</sup>17<sup>1</sup>; 223: 5; 227: 7, rev. <sup>1</sup>2'<sup>1</sup>, 7'; 235: 5'–6'; 257: 3'; 263: 2', 4', 8', 12', 14', 16'; 281: <sup>1</sup>5<sup>1</sup>, 7, 10, 15.

*na-ḥal-lap-tú* 212: 6, 10, 12–13, 18, 20; 221: 5–6; 254: 5–7'.

na-hal-lap-tu<sub>4</sub> 185: 5; 189: 5, rev. [5']; 190: 7, rev. 5'; 198: 5, 7, rev. 1'-2, 5', 9'; 201: 5, 9; 202: 5, <sup>[9]</sup>, 13; 203: 5, 9, 11-13, 15, 18; 211: 5'; 7', 12'-13'; 213: 6'-7', 8', rev. <sup>[8']</sup>; 215: 3'; 221:

12, 16; 224: [5], rev. <sup>[4]</sup>, 6<sup>[1]</sup>; 225: [6, rev. 1<sup>[1]</sup>]; 229a: 5–6, <sup>[7]</sup>; 232: 5–6, 9, 10, 12, 15, [17]; 234: 2<sup>[1]</sup>, 4<sup>[1]</sup>; 238: 5–6; 244: [2<sup>[1]</sup>]–4<sup>[1]</sup>, 7<sup>[1]</sup>, 9<sup>[1]</sup>; 247: 2<sup>[1]</sup>; 251: 3<sup>[1]</sup>–5<sup>[1]</sup>, 8<sup>[1]</sup>, 10<sup>[1]</sup>, 14<sup>[1]</sup>; 254: 5<sup>[1]</sup>–7<sup>[1]</sup>, 9<sup>[1]</sup>; 257: 5<sup>[1]</sup>; 259: 12, 16; 269: <sup>[4]</sup>; 271: 5–6, [7], rev. 1<sup>[1]</sup>, 4<sup>[1]</sup>; 273: 5, 7, rev. 5.

na-hal-pa-a-tu<sub>4</sub> 362: 3.

<sup>túg</sup>*na-aḥ-lap-tú* 231: 4–5, 10, 17; 264: 5–6, 9, 13–14; 266: 5–7; 272: 4'; 275: <sup>τ</sup>6¹, [8], 10–11, [12], 15, 17.

<sup>túg</sup>na-aḥ-lap-tu<sub>4</sub> 196: 9; 220: 8, 13; 231: 13; 289, rev. 4', 7'.

t<sup>tig</sup>na-hal-ap-tu<sub>4</sub> 184: 6, 10, <sup>[</sup>14<sup>]</sup>; 193: 6, 10, 12–14, 17.

túgna-ḥal-lap-tu<sub>4</sub> 185, rev. 2'; 216: 5'-6', [11']; 225, rev. [7']; 236: 4', 8'; 252: <sup>[3']</sup>, 5', 10'.

GÚ.UD.DU(=È) 176: 8; 177: 3'; 181: 4, 7; 187: 6; 192: 2, 5–6; 195: 7, 10–11, 13, 15; 210: 8, 11, 16, 20, 24; 225: [6]; 228: 6, 12–13, 15, 18; 239: 6; 242: rev. 7'; 253: 4'; 259: 18; 268: 「1'」, 3', 8'; 288: 9; 348: 2.

GÚ.UD.DU.A 192, rev. 2'; 242: <6,> 8, rev. [3']: 249: 6'.

GADA.GÚ.UD.DU.A 242, rev. 7'.

SÍG.GÚ.UD.DU 228: 10.

TÚG.GÚ.UD.DU: 139 attestations.

TÚG.GÚ.UD.DU.A 170: 7, [15], 16; 207: 5'-8', 12'-13', 16'; 226: 5; 267: 5'-6', 8'; 230: 3; 243: [6], <sup>1</sup>8¹, rev. 2'; 249: 8'-9', 13'; 292: 18, 20, 22–23, 25; 625: 7.

# nahlaptu of

**Anunītu** 221: 12; 222, rev. 3'; 225: [rev. 1']; 232: 12; 254: 9'; 267: 8'; 274: 5'; 275: [12]; 280: 4'; 284: 9; 291: 12.

Aya 163, rev. II 12'; 170: 7; 176: 8; 178: 5; 179: 6'; 180: 11–12(?); 182: 7–8 (?); 183: 9'–10'; 187: 6; 211: 5; 212: 6; 213: 6'-7'; 214: 3'; 215: 3'; 216: 5'–6'; 217: 6; 218: 「5¹; 219: 8-[9]; 220: 8; 221: 5–6; 223: 5; 224: [5]; 226: 5; 227: 7; 228: 6; 229: 6; 229a: 5–6; 231: 4–5; 232: 5–6; 233: 4'–5'; 234: 2'; 235: 5'–6'; 236: 「2'–3'¹; 238: 5–6; 239: 6; 240: 5–6; 242: <6>; 243: 6; 246: 1'; 247: 2'; 251: 3'–「5'¹; 252: 「3'¹; 255: 5'; 261: 2'; 263: 2'; 264: 5–6; 265: 2'; 268: 「1'¹; 270: 2'; 271: 5–6; 273: 5; 275: 「6¹; 277: 5; 281: 「5¹;

Different from the above item, probably did not belong to the gods' attire.

287: 13; 288: 9; 289, rev. 4'(?); 291: 5; 292: 18; 310: 3'; 348: 2; 349: 4'-5'(?); 518: 6; 625: 7.

**Bēlete** 232: 9; 234: 4'; 236: 8'; 259: 12; 271: [7].

Gula 170: 16; 186: 7; 212: 18; 213, rev. [8'1; 220: 13; 221: 16; 222, rev. 7'; 227, rev. [2'1; 228: 15; 231: 17; 232: 15; 233: 12'; 242, rev. [3'1; 244: 7'; 251: 10'; 253: 4'; 257: 3'; 259: 18; 265: 8'; 271, rev. 1'; 275: 15; 280: 7'; 291: 10; 292: 23.

mārāt Ebabbar 163, rev. II 17'; 170: [15]; 177: 3'; 178: 10; 180: 18; 182: 13; 183: 12'; 211: 7'; 212: 10; 213: 8'; 214: 6'; 216: [11']; 217: 8; 220: 8; 225: [6]; 228: 10; 229: 8; 229a: <sup>[71]</sup>; 231: 10; 233: 6'; 236: 4'; 239: 8; 240: 7; 242: 8; 243: 8; 246: 3'; 248: <sup>[71]</sup>; 249: 6'; 252: 5'; 255: 7'; 260: 2'-4'; 261: 4'; 263: 4'; 264: 9; 265: 4'; 268: 3'; 270: 6'; 272: 4'; 273: 7; 275: [8]; 276: <sup>[31]</sup>; 279: 2'; 281: 7; 287: 21; 288: 11; 289, rev. 7'; 291: 7; 292: 20; 349: 8'.

**Šala** 212: 20; 221: 19; 222, rev. 10'; 225, rev. [7']; 227, rev. 7'; 228: 18; 229: 20; 232: [17]; 233: 16'; 239, rev. 3'; 243, rev. 2'; 246: 9'; 251: 14'; 255, rev. 1'; 257: 5'; 259: 16; 261: 14'; 263: 16'; 265: 11'; 269: <sup>[4]</sup>; 271, rev. 4'; 278: 4'; 281: 15; 291: 16; 292: 25; 359: 7, 9.

Šarrat Sippar 211: 12'-13'; 220: 13; 221: 9-[10]; 231: 13; 233: 10'; 237, rev. 3'-5'; 239: 12-13; 240: 11; 242, rev. 7'; 244: [2']-4'; 249: 8'-10'; 254: 5'-7'; 261: 8'; 263: 12'; 266: 5-7; 267: 5'-6'; 268: 8'; 274: 3'-4; 275: 10-11; 280: 2'-3'; 281: 10; 284: <sup>1</sup>6'-7'<sup>1</sup>; 291: 9; 292: 22; 440: 7.

Unidentified 92, rev. 3'; 212: 12– 13; 224, rev. <sup>[4]</sup>, 6']; 225: [6, rev. 1']; 230: 3; 237, rev. 8'; 244: 9'; 248: 11'–12'; 249: 13'; 251: 8'; 252: 10'; 264: 13–14; 270: 7'; 273, rev. 5; 277, rev. 6'; 356: 8; 383, rev. 9'.

#### nēbeḥu

*ni-bi-ih-hu* 288: 7, 13. *ni-bi-hu* 59 attestations. <sup>túg</sup>*ni-bi-ha* BM 83776: 4'. <sup>túg</sup>*ni-bi-ḥu* 193: 20; 195: 4; 202: [11]; 216: 10', 14'; 231: 20; 236: 7'; 249: 4'; 278: 3'; 292: 21.

 $[^{\text{túg}}n]i-bi-ih\ 237:\ 7.$ 

túg*ni-bi-hu ša izhi* 171: 8'; 175: 6; 383, rev. 5'.

TÚG.ÍB.LÁ 88 attestations

#### nēbeļu of

Adad 184: 13; 190, rev. 3'; 193: 20; 195: 14; 196: 24; 197, rev. [3']; 198, rev. 8'; 200: 16; 203: 17; 204: 8!; 205: 15'; 208: 19'; 209: 「11¹; 210: 23; 212: 19; 214: [12']; 216: 14'; 221: 18; 222, rev. 8'; 228: 16; 229: 18; 231: 20; 232: 16; 233: 14'; 244, rev. 8; 246: 7'; 248: [10']; 251: 12'; 255: 2'; 259: 15; 265: [10']; 275: [16]; 278: 3'; 280: 8'; 290: 28; 291: 15.

**Anunītu** 222, rev. 4'; 225, rev. 3'232: 13; 291: 13.

#### Bunene

170: 9; 177: 7'; 178: 12; 180: 15; 184: <sup>[9]</sup>; 189: 8; 193: 9; 195: 9; 196: 15!; 202: [11]; 203: 8; 204: 7!; 205: [7]; 206: 9'; 207: [11']; 210: [14]; 211: [10']; 213: 11'; 214: 9'; 216: 10'; 217: 11; 218: [10]; 220: [11]; 221: [8]; 224: 8; 228: 9; 229: 10; 231: [8]; 233: [9']; 236: 7'; 239: [10]; 240: [10]; 246: [5']; 249: 4; 251: <sup>[6']</sup>; 252: [8']; 254: 4'; 261: 7'; 265: [7']; 268: 5'; 275: [9]; 276: 6'; 277: 2'; 279: 6'; 280: 1'; 281: 「91; 285: 5; 287: 18; 288: 13; 290: 22; 291: <sup>[9]</sup>; 292: 21; 348: 3 (and Šamaš); 377: 4'(and Šamaš); 488: 8, 11; 492: 2 (and Šamaš); 519: 5 (and Šamaš).

Šamaš 63: 「9¹; 170: 4; 171: 8'; 175: 6; 177: 4'; 178: 3; 183: 2'; 184: 4; 189: 4; 190: 5; 193: 5; 195: 4; 196: 7!; 197: [6]; 198: 4; 200: 4; 201: 「3¹; 203: 4; 204: [3']; 205: [1']; 208: 3'; 209: 4; 210: 6; 211: [3']; 216: 3'; 217: [4]; 218: [4]; 219: [6]; 221: 「4¹; 224: [4]; 227: 「5¹; 237: 7; 238: [4]; 239: 5; 240: [4]; 241: 5; 255: 2'; 287: 「10¹; 288: 7; 291: 3; 348: 3; 377: 4' (and Bunene)'; 383, rev. 5'; 421: 2; 430: 7; 478: 2; 479: 3; 484a: 6; 492: 2 (and Bunene); 498: 2; 519: 5 (and Bunene); 528: 3; 529: 4.

Unidentified 190, rev. 7'; 192: 1; 213, rev. 3', 11'; 252: \(^10)^1\); 258: 4'; 273, rev. 7'; 286: 8'; 311, rev. 1'; 359: 6; 478: 8; 515, rev. 7'; 546: 2; BM 65211: 8; BM 83776: 4'.

#### Colour

tabarri (SÍG.HÉ.ME.DA)

Adad 244, rev. 8.

Bunene 195: 9; 519: 5.

Šamaš 255: 2'; 291: 3; 519: 5.

Unidentified 286: 8'.

takiltu (SÌG.ZA.GIN.KUR.RA)

**Bunene** 484a: 6.

Šamaš 479; 3; 498: 2.

Šamaš and Bunene 377: 4'; 492: 2.

# nebettu (TÚG.ÍB.BAL) 275: 18-19.

**pan muşê** (IGI/pa-ni mu-şi-e/mu-uş-şi-e) 15: 6, 10; 503: 3; 552: 2; 553: 2; 554: 3; 619: 3.

# paširu

<sup>1úg</sup>pa-ši-r[i] 82: 22 (for Adad) <pa>-ši-ir 181, rev. 2(?) (for Aya) pa-ši-ir! (T: ni) 179: 8(?) (for Aya)

# patinnu (TÚG.MURUB<sub>4</sub>.ÍB.LA)

TÚG.MURUB<sub>4.</sub>ÍB.LÁ 59: 7; 67: 19; 187: 5; 196: 6, 15, 23; 199, rev. 5'; 207: 11'; 210: 「5, 14', 22; 214: 「9'',11'; 217: 10; 218: 3, 9; 220: 「11'; 228: 5, 8, 16; 231: 8; 239: 5; 246: 6', 8'; 248: [4']; 249: 4'; 253: 6'; 255: 3'; 256: 4', 9'; 261: 7'; 265: [7'], 10'; 268: 5', 13'; 272: [7']; 274: [2'], 6'; 277: 2; 279: 8'; 280: [1', 5'], 「8''; 284: 4'; 287: 10; 290: 21, 28; 291: [4], 8, 12, 16, 21, 24; 292: 5, 14, 22; 597: 2; Nbn 410: 5, 6.

SÍG.TÚG.MURUB<sub>4</sub>. ÍB.LÁ: 219: 6.

pa-tin-na-a-tu<sub>4</sub> 232: 12; 525: 3.

pa-tin-nu/i 180: 13, 14; 183: 3'; 185: 4; 190: 5, rev. [4']; 195: 3, 8; 200: 4, 15; 201: [4]; 203: [4], 8; 221: 4, [8], 17; 229a: 4; 247: 1'; 250: 4; 254: 3'; 257: 4'; 258: 4'; BM 60071: 2.

[p]a-te-en 242: 5, rev. 5'.

pat-ti-in 285: 5.

<sup>túg</sup>pa-ti-in 237: 6.

túgpa-ti-in-nu 193: 4, 9, 19.

túg<sup>†</sup>pa-tin-nu 202: 12.

#### patinnu of

Adad 190: rev. [4']; 193: 19; 196: 23; 200: 15; 210: 22; 214: 11'; 221: 17; 228: 16; 239, rev. 1'; 246: 8'; 253: 6'; 256: 9'; 257: 4'; 258: 4'(Adad²); 265: 10'; 268: 13'; 280: <sup>[8']</sup>; 290: 28; 292: 24.

**Anunnītu** 222, rev. 5'; 232: 12; 274: 6'; 275: 13; 291: 12; 597: 2; BM 67859: [5'].

Bunene 67: 19; 180: 14; 193: 9; 195: 8; 196: 15; 203: 8; 207: 11'; 210: 

[14]; 214: [9]; 217: 10; 218: 9; 220: 

[11]; 221: [8]; 228: 8; 231: 8; 246: 6'; 249: 4'; 254: 3'; 256: 4'; 258: 4'; 261: 7'; 265: [7']; 268: 5'; 272: [7']; 274: [2']; 280: [1']; 284: 4'; 287: 18; 290: 21; 291: 8; 292: 21; Nbn 410: 6.

Šamaš 67: 19; 180: 13; 187: 5; 190: 5; 193: 4; 196: 6; 200: 4; 203: [4]; 210: <sup>1</sup>5<sup>1</sup>; 217: 5; 218: 3; 219: 6; 221: 4; 228: 5; 229a: 4; 237: 6; 239: 5; 242: 5; 247: 1'; 248: <sup>1</sup>4'<sup>1</sup>; 250: 4; 255: 3'; 285: 5; 287: 10; 292: 16; 597: 2; Nbn 410: 5.

#### Colour

SÍG.HÉ.ME.DA = nabāsu/tabarru 183: 3'; 195: 8; 199, rev. 5'; 207: 11'; 210: 5, '14'; 214: 9', 11'; 219: 6; 239: 5', rev. 1'; 248: 4'; 256: 4', 9'; 290: 21, '25'; 292: 16; Nbn 410: 5-6.

**Adad** 214: 11'; 239, rev. 1'; 256: 9'.

Anunītu 290: [25].

**Bunene** 195: 8; 207: 11'; 210: <sup>1</sup>4<sup>1</sup>; 214: 9'; 218: 9; 256: 4'; 290: 21; Nbn 410: 6

**Šamaš** 183: 3'; 210: 5; 218: 3; 219: 6; 239: 5(?); 248: 4'; Nbn 410: 5.

Unidentified 199, rev. 5'; 292: 16.

# Weight

5 shekels for *patinnu* of Bunene: Nbn 410: 6.

12 shekels for *patinnu* of Šamaš: Nbn 410: 5.

4 minas of Šamaš and Bunene 67: 19.

# Number

always one piece for Adad, Bunene and Šamaš

2 pieces for Anunītu: 232: 12.

#### paršīgu (= BAR.SI)

BAR.SI 69: 12; 181, rev. 9'; 580: 4, <sup>1</sup>10<sup>1</sup>, 14; BM 101551, rev. <sup>1</sup>3<sup>1</sup> (BAR.[SI.MEŠ].

**Šarrat Sippar** 42: 3; 67: 23; 71: 14; 83: 8; 85: 11; 91: 10; 147: 3; 150:

[8']; 152: 4'; 163, rev. I 12'; rev. II

22'; 170: 12; 171: 6; 172: 10; 174: 7,

```
TÚG.BAR.SI 93 attestations including
                                                             rev. 7'; 179: 18'; 181: 12'; 196: 20;
  data from a few texts not published
                                                             200: <sup>[12]</sup>; 210: 18; 262: 6'; 297 rev. I
                                                             10; 383, rev. 6'; BM 52018 II 14';
SÍG.BAR.SI 15: 5, 9; 228: 5; Cam 156: 3.
                                                             Cam 413: 12; Cyr 253: 8; Nbk 87: 4;
TÚG.BAR.SIG 310: 4'.
                                                             VS 6,16: 19!
par-ši-ga-ni 270: 3'.
                                                         Colour
par-ši-ga-nu 288: 10, 15.
                                                        peşû (exclusively Bunene) 87: 12; 293
pár-ši-gu<sup>meš</sup> 196: 20.
                                                           rev. II 5'; 294 I 9'; (two); 295: 6'; 297
par-si-hu 351: 3.
                                                           I 4', rev. II 4'; 299: 5.
par-si-hu<sup>meš</sup> 196: 10.
                                                         takiltu (exclusively Šarrat Sippar): 43: 3;
par-ši-gu 77: 20; 163, rev. I 21'; 174: 7,
                                                           47: 2; 67: 23; 170: 12.
  rev. 4',7'; 203: 13; 214: 5'; BM 62915:
                                                         tabarru
                                                           Aya 170: 8 (tabarru and/or takiltu); 19
^{\mathrm{túg}}p\acute{a}r\text{-}si\text{-}gu BM 51025: 10; Nbk 87: 4.
                                                             178: 7; 229: 7; 291: 6.
t^{\text{túg}}par-ši-ga^{\text{<meš>}} BM 50392: 5; BM
                                                           mārāt Ebabbar 170: 14; 178: 29; 210:
  101133: 3.
                                                             9; 214: 5.
túgpar-ši-gu<sup>meš</sup> 41: 2; 47: 2; 85: 11; 163,
                                                           Šamaš 290: 15.
  rev. I 11', 12' and rev. II 22'; 174: 10';
                                                           Šala 178: 21; 170: 20.
  177: 12'; 178: 7, 21 200: 12; 203: 13;
                                                           Unidentified 245, rev. 4; 270: 3'; 475:
                                                             28 (tabarri and takiltu for 2 paršī-
^{\text{túg}}pa-< ar >-\check{s}i-^{\Gamma}gu^{1 < \text{meš} >} 40: 3.
                                                             gus); 605: 2; Cyr 4: 1.
túg par-ši-gu 91: 10, 14; 299: 5.
t^{tig}par-\Gamma \check{s}i^{7}-ir 23: 8.
                                                        pišannu
                                                         <sup>gada</sup>pišannu 535: 5.
paršīgu of
  Adad 67: 17; 76, rev. 8'; 85: 15; 91:
                                                         salhu
    14; 147: 12; 150: 10'; 188: 8; 287: 7;
                                                         sa-al-hu 196: 5, 9, 12, 14, 17, 23, 25, 27;
                                                           BM 84827: 4.
    Cam 413: 16.
                                                        sa-al-ah 237: 3, 8, rev. 2', 7'.

[sa-al]-la-a[h²] 197, rev. 2'.

sal-hi: 369: 3, 16, 21; BM 60071: 2.
  Aya 21, rev. 4'; 67: 21; 68, rev. I 11',
    rev. II 20'; 170: 8; 178: 7; 179: 7; 181, rev. 7'; 183: 8'; 195: 6; 196: 10;
                                                         <sup>gada</sup>sal-ḥa 359: 2.
    204: 「5'1; 210: 9; 220: 7; 242: 7; 270:
                                                         gada sal-hi 180: 1, 3, [5]; 200: 3, 5, 11, 14,
    3'; 275: 7; 287: 14; 288: 10; 290: 18;
    292: 19; 310: 4'; 486: 3; Cam 414: 7;
                                                           15–16; 203: 3, [5–7, 9], [11], [15], 17–
                                                           18; 221: 3, 5, 7, 9, 16-17, 19; 229a: 2,
    Cyr 190: 14; Cyr 241: 7.
  Anunnītu 165, rev. 6'; 232: 13; 263:
                                                           5, 7-8, rev. 2'-4'; 254: 2' 5', 9'; 257:
    11'; 274: [6']; 280: 5'; 290: 26.
                                                           3'-5'; 332, rev. 1'; 362: 1-2; 365: 1;
  Bunene 87: [12]; 293 rev. II 5'; 294 I
                                                           628: 1.
                                                         gada sal-hu: 187: 4, 6; 191: 2; 195: 3, 5,7-
    9'; 295: 6'; 297 I 4', rev. II 4'; 298,
    rev. [9']; 299: 5; 304: 5; 351: 3';
                                                           8,10, 13–15; 210: 4, 8, 11, 13, 16, 20,
                                                           22, 24; 219: 5, 8; 225: 4, 6, rev. 1', 6'-
    Cam 156: 3(?).
  Gula 67: 28; 68, rev. 10'; 164: 11;
                                                           7'; 242: 4, [6, 8, 10, rev. 5', 7']; 243: 4,
    170: [17?]; 181: 9'; 306: 15; 586: 14;
                                                           6, rev. 2'; 283: 2', 4', 6', 9', 11', 13';
                                                           292: 15-[16], 18, 20-25; 332: 4-6, rev.
    Cyr 253: 7.
  mārāt Ebabbar 170: 14; 178: 9, 29;
                                                           1', 3'; 333: 2'-6', rev. 9'-11'; 356: 2;
    183: 11; 287: 20; 288: 11.
                                                           BM 84072: 2.
                                                         sal-hu GADA BM 63009: 8–11<sup>20</sup>.
  Šala 67: 27; 68, rev. 7'; 170: 20; 178:
    21; 287: 23; 378: 11; 586: 9.
                                                         túgsal((!)-hi 292: 17 (?).
  Šamaš 195: 4; 203: 13; 210: [5]; 228:
```

Colour of wool is given only in heading: tabarru u talkiltu.

Published in RA 90 (1996), No 4.

#### salhu of

**Adad** 42, rev. [5']; 195: 14; 200: 15; 203: 17; 210: 22; 221: 17; 225, rev. 6'; 257: 4'; 292: [24].

**Anunītu** 221: [12]; 225, rev. 1'; 254: 9'.

**Aya** 180: 1; 187: 6; 195: 5; 200: 5; 203: [5]; 210: 8; 219: 5; 221: 5; 225: [6]; 229a: 5; 242: [6]; 243: [6]; 251: 3'; 283: 2'; 292: [18]; 332: 5; 359: 2; 362: 1.

**Bēlete** 195: 7; 362: 2.

**Bunene** 180: [5]; 195: 8; 203: 7; 210: 13; 221: 7; 242: [10]; 254: 2'; 283: 5'; 292: [21]; 359: 3.

Dar 62: 8; Nbn 252: 1.

**Gula** 195: 13; 200: 14; 203: 15; 210: <sup>†</sup>20<sup>†</sup>; 221: 16; 242, rev. [3']; 251: [10']; 257: 3'; 283: 9'; 292: [23].

**mārāt Ebabbar** 180: 3; 203: 8; 210: 11; 229a: 7; 242: [8]; 243: [8]; 332: 6; 359: 4.

Šala 195: 15; 200: 17; 203: 18; 210: 24; 221: 19; 225, rev. 7'; 242, rev. '7'; 243, rev. [2']; 251: 14'; 257: 5'; 292: [25].

Šamaš 180: 1; 187: 4; 191: 2; 195: 3; 200: 3; 203: 3; 210: 4; 219: 5; 221: 3; 225: 4; 242: 4; 243: 4; 257: 5'; 292: 15-17(?); 332: 4, rev. 3'; 359: 2; CT 55. 823: 1.

**Šarrat Sippar** 195: 10; 200: 11; 203: <sup>1</sup>11<sup>1</sup>; 210: 16; 221: [9]; 254: 5'; 283: 6'; 292: [22].

**Unidentified** 251: 8'; 254: 9'; 283: 11', 13'.

#### รนิทม

*su-ni-e* 30: 2; 44: 4; 85: 4; 108: 9; 161: 4; 321, rev. 5'; 325: 26; 642: 2.

su-ú-ni 85: 19.

su-ú-nu 52: 12; 160, rev 3'; 391: 3, 5.

<sup>túg</sup>su-ni-e 1: 3; 16: 4; 86: 5; 99: <sup>[4']</sup>; 134: 5', 10'; 142: 3'; 353: 4, 6, 13.

<sup>túg</sup>su-nu-ni-e 50: 9; 440: 8.

 $t^{t\acute{u}g}su$ - $\acute{u}$ -ni 85: 16.

<sup>túg</sup>su-ú-nu 50: 11; 85: 10; 86: 8, 12; 353: 11.

TÚG.ÚR 243 attestations.

<TÚG>ÚR 30 attestations.

sūnu ša mē-qātê (TÚG.ÚR šá <sup>r</sup>me<sup>1</sup>-e-ŠU<sup>ii</sup>) 402: 2.

#### sūnu of

Adad 4: 5; 11: 9; 12: 4; 16: 8; 17: 6; 18: 8; 19: 8; 25, rev. 3'; 26: 7; 34: 7; 36: [4]; 47, rev. 7'; 49: [5']; 50: 11; 52: 12; 56: [11]; 57: [11]; 58: 12; 59: 15; 62: [11]; 66: <sup>[</sup>17]; 67: 17; 76, rev. 3'; 77: 10; 78, rev. 3'(?); 79: 14; 82: <sup>[21]</sup>; 83: 10; 84: 18; 85: 16; 100: 8'; 101, rev. <sup>[4]</sup>; 102: 13; 104: 16; 112: 16; 116: 18; 118: 15; 122: 16; 123: 12; 131: 12'; 132: [12]; 136: 7'; 137: 4'; 138: 6'; 140: 7'; 143: 7; 146: 9'; 147: 12; 150: 10; 152: 11(?); 160, rev 3'; 179: 17; 287: 6; 288: 5; 293, col I 9'; 294 I 1', rev. II [9']; 296 II [5']; 297 I 15', rev. I [10'], rev. II 20'; 301: [6]; 305: 7; 306: [9]; 307: 5'; 308: 9; 312: 14'; 315, rev. 3'; 344: 12, rev. 9'; 391: 3.

Aya 161: 4; 353: 6.

**Anunītu** 67: 12; 117: 16; 165: <sup>[9]</sup>; 167: 7; 168: 5; 291: 25; 315, rev. 4'; 321, rev. 5'; 322, rev. 7'; 325: 26; 642: 2.

Bunene 1: 5; 16: 15(!); 19: 3; 24: 13; 49: [8']; 54: 12; 59: 15; 66: [19]; 76, rev. 3'; 98: [6]; 118: 11; 123: 14; 139, rev. 2' (?); 146: 9'; 293, rev. II 4'; 294 I 9'; 297 I <sup>[4']</sup>, rev. II <sup>[4']</sup>; 298: [9']; 299: 5'; 301: 13; 304: 4; 306: 15; 308: 6.

**Gula** 54: 15; 76, rev. 3'; 83: 14; 84: 14; 85: 19; 86: 12; 102: 15; 104: 14; 112: 15; 113, rev. 3; 115: 1'; 116: 15; 118: 17; 122: 17; 123: 15; 132: 11; 138: 7'; 312: 16'; 391: 5.

**Šala** 52: 12.

Šamaš 353: 4.

Šamaš (and Aya) 1: 3; 2: 3; 3: 3; 5: 3; 6: 7; 7: 9(?); 8: 8(?); 9: 3; 11: 3; 17: [5]; 18: 4; 21: 3; 22: 3; 23: 2; 26: 3; 27: [3]; 28: 5; 29: 3; 30: 2; 31: 2(?); 32: [3]; 33: 3(?); 34: 3; 35: [3']; 48: 6; 50: 9; 51: [8]; 52: 6; 54: 7; 55: 10; 56: 8; 57: 7; 58: 6; 59: 9; 60: 7; 61: 8; 62: [6]; 63: 7; 64: 4; 66: 6; 67: 4; 71: ¹6¹; 72: 6; 74: 9; 75: [9]; 76: [8]; 77: 6; 79: 9; 82: [10]; 83: 6; 84: 7; 85: 4; 86: 5; 87: 8; 89: 4'; 90: 6'; 91: 6; 92: 3'; 93: 4'; 94: [5']; 95: 7; 97: 3'; 98: 3'; 99: ¹4'¹; 100: 5'; 101: 4; 102: 6; 103: [9']; 104: 7; 106: 9; 107: 9; 112: 8; 113: [7]; 114: 7; 116: 8; 118:

8; 119: [6]; 120: 5'; 121: 13; 122: 7; 123: 8; 124: 6; 125: 7; 126: 6; 131: 5'; 132: 4'; 134: 5'; 136: 2'; 140: 2'; 141: [10]; 142: 3'; 143: 7; 144: 「7¹; 145: 「7¹; 146: 6'; 149: 6; 156: 6'; 171: 「4¹; 287: 2; 288: 2; 290: 8; 291: [21]; 292: 8; 293, col I 5', rev. I 7'; 297 I [12'], rev. I 6', rev. II 17'; 301: 3; 303 II 4'; 305: 3; 306: 3; 308: 4; 309: 4'; 310: 「3'?¹; 311: 3; 312: 2'; 314: 10'; 315, rev. 3'; 440: 8.

Šarrat Sippar 1: 3; 3: 3; 5: 3; 39: [4]; 40: 5; 42: 6; 43: 3; 47: 3; 59: 15; 67: 9; 69: 17; 71: 16; 76, rev. 3'; 85: 10; 86: 8; 118: 13; 132: 9'; 147: 4; 150: '7''; 299: 20'; 373: 3; 402: 2

Unidentified 12: 17; 20: 3; 44: 4; 64: <sup>[8]</sup>; 84: 11; 116: [14?]; 125, rev. 3'; 131: 11'; 134: 5', 10'; 147: 7; 153: 4; 157, rev. 1'–2'; 161: 4; 162: 6', rev. 3'; 165: <sup>[9]</sup>; 169: 5; 226: 7; 297, rev. II 11'; 302: 6', 12'; 303 I 2'; 308: 11, 18; 311: 3; 313, rev. 2'; 314: 22', 23'; 319: 11'; 324: 24; 326: 33; 327: 18; 334: 3'; 337, rev. 4'; 351, rev. 7'; 352: 5; 353: 11, 13; 440: 8; 495: 13.

#### șibtu

MÁŠ 10: 2; 11: 2; 52: 4; 77: 4.

TÚG.MÁŠ 1: 2, 5; 2: 2; 18: 3'19: 2, 5; 23: 2, 5; 24: 2, [8]; 25, rev. [1]; 27: 2, 4; 28: 2, 4; 63: 6, rev. 5'; 66: 15; 87: [5]; 116: 5, [10]; 124: 5, 8; 127: [7]; 290: 4, 12, 16; 295: 4'; 301: 9; 644: 2, 5.

și-ba-tu, 57: 4; 575: 2.

 $sib-ba-tu_{4}^{4}$  59: 5; 117: 5; 196: 8.

<sup>túg</sup>ṣi-ba-ta 12: 14.

túg si-bat-tu<sub>4</sub> 248: 3'.

 $t^{túg}sib-ba-tu_4^4$  50: 4; 66: 4; 79: 6.

 $t^{tig}$ *șib-bá-tu* $_{4}$  64: 3; 242: 5.

şib-ti 30: 1, 4, 5.

sib-ti<sup>meš</sup> 407: 1; 416: 5.

*şib-tu*<sub>4</sub> 6: 6; 34: 1, 5; 50: 8; 52: 9; 77: 9; 103: 6', 15'; 105: 6; 112: 11; 117: 14; 122: [4], 12; 134: 7'; 161: 11; 356: 7; 406: 2; 573: 3; 581: 2; 582: 6; BM 67848: 2<sup>21</sup>.

<sup>túg</sup>ṣ*i-ba-a-ta* 97: 2.

ti<sup>1</sup>gib-tu<sub>4</sub> 3: 2, 5; 6: 9; 54: 5, 10; 59: 13; 64: 14; 66: 9; 67: 3, 10, 13; 79: 11; 81, rev. 14; 82: [13], 17; 102: <sup>[4]</sup>, 10; 106:

6, 11; 108: 5, 12; 112: 5; 113: 5, rev. 5'; 114: 4, 9; 117: 12, 14; 123: 5, 16; 134: 2'; 146: 12'; 149: 4 (?); 150: 4', 12'; 161: 9; 167: 6; 209: 4; 292: 5, 10, 17; 576: 4; 609: 5; BM 61883: 5; BM 65041: 2; CT 57, 255: 6.

#### *șibtu* of

**Adad** 63, rev. 5'; 66: 15; 81, rev. 14; 82: 17; 161: 9; 581: 2.

**Anunītu** 67: 10; 69: 14; 113, rev. 5'; 117: 14; 167: 6; 573: 3; 575: 2; 576: 4; 609: 5; BM 67848: 2<sup>22</sup>; CT 57, 255: 6.

Bunene 1: 5; 3: 5; 6: 9; 12: 14; 18: 6; 19: 5; 23: 5; 24: [8]; 25, rev. <sup>1</sup>1<sup>3</sup>; 27: 4; 28: 4; 30: 4; 34: 5; 50: 8; 52: 9; 54: 10; 58: [10]; 66: 9; 77: 9; 79: 11; 102: 10; 103: 15'; 106: 6; 108: 5; 112: 11; 114: 9; 116: [10]; 117: 12; 122: 12; 123: 16; 124: 8; 127: [7]; 134: 7'; 146: 12'; 150: 4'; 290: 12; 292: 17.

**Gula** 64: 14; 67: 13; 86: 11; 108: 12; 150: 12'; 161: 11.

Šamaš 1: 2; 2: 2; 3: 2; 6: 6; 10: 2; 11: 2; 12: 14; 18: 3; 19: 2; 23: 2; 24: 2; 27: 2; 28: 2; 30: 1; 34: 1; 50: 4; 52: 4; 54: 5; 57: 4; 63: 6; 64: 3; 66: 4; 67: 3; 77: 4; 79: 6; 82: [13]; 87: 5; 97: 2; 102: <sup>1</sup>4¹; 103: 6'; 105: 6; 106: 6; 112: 5; 113: 5; 114: 4; 116: 5; 117: 4; 123: 5; 124: 5; 134: 2'; 149: 4; 196: 8; 209: 4; 220: 5; 242: 5; 248: 3'; 290: 4, 16; 292: 5, 10; 295: 4'; 301: 9; 406: 2; 407: 1 (2 talents for XII 33 and I 34 Dar); 582: 6.

**Unidentified** 30: 5; 416: 5; 561: 2.

**şibtu šá erši** of Šamaš: 406: 2–3; 582: 6; BM 61883: 5–6.

șibtu šá erši of Adad 581: 2.

<sup>(gada)</sup>šiddu 347: 8'; 367: 15; cf. dullu ša šiddu 414: 7.

#### taḥapšu

*ta-ḥap-šú* 275: 2; 314: 7'-9', 11'-15'; 316: 14–16; 319: [5'-9'], 「15'¹; 321: 9–12; 322: 6'-12'; 323: 3'-9'; 324: 15–17; 325: 9–15; 326: 10–16, 18; 327: 10–12, 20–21, 23, 25; 328: 8–10,

<sup>&</sup>lt;sup>21</sup> RA 90 (1996), no 2.

<sup>&</sup>lt;sup>22</sup> RA 90 (1996), no 2.

```
23-26; 329: 5, 7, 10-11, 22; 331: 4-6;
                                                  tahapšu made of salhu labiri for
 333: 4'-5', rev. 4'-7'; 335: 3'-9'; 348:
                                                    Aya 321: 10; 322: [6']; 323: 4'; 325:
 6; 423: 6'; 643: 5.
                                                      10; 326: 11; 327: 11; 328: 9; 333: 5'.
ta-hap-šú<sup>meš</sup> 344, rev. 11'.
                                                    Anunītu 323: 8'.
ta-hap-ta-šú 311, rev. 4'.
                                                    Bunene 321: 12; 323: 6'.
                                                    Gula 323: 9 (?).
ta-hap-taš-šú 589: 4.
ta-hap-ti 327: 20.
                                                    Immertu 321: 11; 323: 5'; 325: 11;
                                                      326: 12; 327: 12; 328: 10; 333: 6'.
GADA ta-hap-šú 181: 10; 320: 4-5, 7,
                                                    Šamaš 321: 9; 323: 3'; 325: 9; 326:
<sup>túg</sup>ta-ḥap-šú 171: 15 (and only partly
                                                      10; 327: 10; 328: 8; 333: 4'.
 preserved in 344, rev. 12'-16').
                                                    Šarrat Sippar 323: 7'.
tahapšu made of kibsu (without ad-
                                                  tahapšu made of salhu (quality not
 ditional qualification) 181: 9; 314:
                                                    stated) for
  14'-15'; 322: 6'-12'; 328: 23-26; 331:
                                                    Anunītu 314: 13'.
 4-6; 333, rev. 4'-7'; 335: 7'-9'.
                                                    Aya 324: 16; 335: 4'.
tahapšu made of kibsu (without ad-
                                                    Bunene 314: 11'; 324: 17; 335: 6'.
 ditional qualification) for
                                                    Immertu 335: 5'
 Adad 314: 15'.
                                                    Šamaš 314: 12'; 335: 3'.
                                                    Šarrat Sippar 324: 17.
 Anunītu 328: 25; 333, rev. 6'.
 Bunene 328: 23; 333, rev. 4.
                                                  tahapšu made of GADA (kītu) without
 Gula 314: 14'; 328: 26; 333, rev. 7'.
                                                    any additional qualification 181: 10;
 Šamaš 181: 9; 322: [6'].
                                                    320: 4-5, 7, 10: 329: 10-11, 22.
 Šarrat Sippar 328: 24; 333, rev. 5';
                                                  tahapšu made of GADA (kītu) without
                                                    any additional qualification for
   335: 7'
tahapšu made of kibsu labiri 319: 5'-9';
                                                    Bunene 329: 10.
 321: 12-13; 325: 12-15; 326: 13-16,
                                                    Gula 320: 10.
  18; 327: 20-21, 23, 25.
                                                    Immertu 329: 22.
tahapšu made of kibsu labiri for:
                                                    Nin-ŠA 329: 11.
  Adad 319: 8'.
                                                    Nin-[x] 320: 8.
                                                    Šamaš 181: 10.
  Anunītu 319: 6'; 325: 14; 326: 16; 327:
   23.
                                                  <sup>túg</sup>tunšu13: 2 (tunšu ša eli ešri); 15: 5, 9;
 Bunene 321: 12; 325: 12; 326: 13; 327:
                                                    356: 3; Cam 4: 4, 8; Nbn 329: 4; Nbn
   20.
  Gula 319: 7'; 325: 15; 326: 18; 327: 25;
                                                    415: 4; Nbn 467: 5.
   328: 26.
  Šala 319: 9'.
                                                  ţīmētu 67: 22; 175: 16; 277, rev. 8'; 346:
 Šarrat Sippar 319: 5'; 325: 13; 326:
                                                    2; 388: 14; 472: 8; 525: 9; 535: 4; BM
   14; 327: 21.
                                                    83776: 3'.
tahapšu made of salhu labiri 321: 9-12;
                                                  cf. ţīmutu
                                                  (síg) tīmu 164: 「10<sup>1</sup>; 165: 4'; 167: 13; 440:
 322: 6'-7'; 323: 3'-9'; 325: 9-11; 326:
  10-12; 327: 10-12; 328: 8-10; 333:
                                                    9; 490: 1, 5; 544: 1,10; 546: [1]; 632:
 4'-5'
                                                    1
                                                  (síg) ţīmutu 609: 2; 631: 1.
tahapšu made of salhu (quality not
                                                  gada<sup>t</sup>tumanu 343: 17; 345: 16'; 619: 2;
 stated) 314: 7'-9', 11'-13'; 316: 14-
 16; 319: 「15'1; 324: 15–17; 329: 5, 7;
                                                    626, l. h. e. 2; Nbn 164 : 21.
 335: 3'-6'.
```

564 INDEXES

#### Terms written ideographically

HU.PAP.MEŠ 536: 4. SÍG.IR.Ú.MA.MI.IŠ 13: 6; 14: 5; 15: 3, 13. SÍG.ÙZ 527: 5?; 618: 1?.

TÚG.KUR.RA 448: 6; 455: 2, 4–5; 534: 4; 603: 1, 3; 614: 3'–6'; 616: 1; 618: 9. TÚG SAG 104: 9; 106: 15; 229: 4; 242: 5; 418: 7; 535: 8; cf. *lubuštu* SAG in 15: 4, 8.

#### Other terms

(w)atāru 148: 9'. bīt alpê 638: 4. bīt asû 494: 4. bīt ili (É DINGIR) 15: 22; 24: [17]; 29, rev. 2'; 101, rev. 2'; 171: 24; 177: 14'; 178: 26; 293, col. I 12', rev. I 3', rev. col. II 8'; 294, col. I 4', [12'], rev. col. I [2'], [12']; 295: 9'; 297, col. I 7', rev. col. I [2', 13'], rev. col. II 7', 13', 23'; 298: [13']; 299: 2, [8']; 300: 4', 9'; 301: 10; 302: [4', 7']; 303, col. II [9']; 305: [10]; 306: [18]; 307: [8']; 313, rev. 5'. bīt irbi 625a: 2. bīt kārê (É. GUR<sub>7</sub>.MEŠ) 495: 5; 613: 4'. bīt qātê 348: 9; 459: 2; 470: 5; 484: 5; 520: 7'; 564a: 2; 568: 2; 575: 4; 594: 9; 633: 2. bīt quppu 625: 1-2. bīt şalam šarri 609: 8-9. bīt šipāti (É SÍG.ḤI.A) 416: 1. bīt urû 620: 3'. bururānu 578: 3. dullu 52: 13: 54: 16: 61: 10: 67: 18. 30: 86: 14; 104: 18; 116: 19; 117: 7, 11; 118: 18; 120, rev. 2'; 128: 13; 159, rev. 5'; 163, col. I 3, 13, 19, col. II <sup>7</sup>3, 15<sup>1</sup>; rev. col. I <sup>5</sup>7, col. II 4'; 172: 16; 277: 4; 292: 13; 401: 1; 429: 2; 432: 2; 437: 7; 586: 2; 612: 6'; 639: [4]; 645: 1. dullu in: şabê ša dullu ippuš 448: 1. dullu ša Ebab[barra] 617: 10'. dullu ša ITI.GU<sub>4</sub> 441: 4, rev. 8; 460: 7, 18; 468: 9; 498: 5, 8; 524: 3; 544: 5; 547: 1, 3; 592: 1, 10 ; 604: 3-4; BM 83946: 2. dullu ša ITI.ŠU 401: 1; 484a: 1. dullu ša ITI.KIN 431: 2; 460: 7, rev.18. dullu ša ITI.DU<sub>6</sub> 392: 3; 434: [2]; 600: 3. dullu ša ITI.ŠE 394: 2; 395: 2; 430: 2.

dullu ša ITI.[x] 429: 2.

dullu gamru/gamra/gammar/TIL 1: 1: 2: 1; 3: 1; 4: 1; 7: 5; 8: 2; 9: 1–2; 10: 1; 11: 16; 12: 1, 10–11; 15: 2; 16: 2; 18: 1; 20: 1-2; 22: [1]; 23: 1; 24: [1]; 25: 1, rev. 2'; 26: 1; 27: <sup>[1]</sup>; 28: 1; 31: 1; 32: 1–2; 33: 1–[2]; 36: 1; 39: 1–2; 41: 1; 44: 2; 45: 1-2; 46: 2; 48, rev. 7'; 76, rev. [9']; 85: 20; 103: 19 (?); 108: 14; 137: 「8'1; 293, col. I 11'; 294, col. I [3'], rev. col. II 11'; 297, col. II 9', rev. col. I [12'], rev. col. II 22'; 298: 7'; 301: 1; 303: 8'; 305: 9; 306: 8'; 307: [7']; 310: 8'; 311: 1; 313, rev. 4'; 644: 1; BM 101551: 4'. dullu peşû (BABBAR-ú/ pi-și-i) 50: 1; 51: 1; 52: 1; 53: 1; 54: 1; 55: 1; 56: 1; 58: 1; 59: [1]; 60: 1; 61: 1; 62: 1; 64: 1; 65: 1; 66: [1]; 67: 1; 68: 1; 69: 1; 71: 1; 72: 1; 73: 1; 74: 1; 75: [1]; 76: 1; 77: 1; 80: [1]; 81: 1; 82: 1; 83: 1; 84: 1; 86: 1; 87: 1; 88: 1; 91: 「11; 95: [1]; 102: [1];104: 「11; 105: 1; 106: 1; 107: 1; 108: 1; 109: 1; 110: 1; 111: [1]; 112: 1; 113: [1]; 114: [1]; 116: 1; 118: 「17; 119: [1]; 122: [1]; 123: 1; 124: 1; 125: <sup>[1]</sup>, rev. 5'; 126: [1]; 127: 1; 128: [1]; 129: 1; 130: 1; 144: [1]; 145: [1]; 146: [1]; 159: 1; 167: 14; 290: [1]; 291: [17]; 292: [1]; 353: 15.

dullu laispari 196: 1.
dullu peşû šá-hu-ú 79: 1.
dullu takiltu 645: 1–2.
dullu peşû u tabarri or dullu tabarri u
peşî 165: 1; 166: 1; 167: 1.
dullu ša nēbehu 377: 4'; 531: 3.
dullu ša pān muṣê 554: 3.
dullu ša pišannu 471: 2.
dullu ša šiddu 414: 7'.
dullu tabarri 393: 3–4; 430: 5, 11; 441: 8; 542: 2.

INDEXES 565

```
dullu tabarri u takilti or dullu takilti u
                                                     kītu 13: 7; 14: 6.
  tabarri 163, rev. II 4'-5'; 170: 1, 22-
                                                     kītu ša dulla (GADA šá dul-lu/a): 176:
  23; 171: 1; 172: 1'; 173: 1; 174: 1;
                                                       11; 180: 8; 182: 9; 359: 1; cf. šá dul-
  414: 2 (wool); 488: 1.
                                                       lu₄ in 277: 4.
etēqu 45: 5; 46: 6; 66: 6-7, 10, 12, 14;
                                                     maššartu 629: 4.
  67: 18, 23-24; 74: 13; 86: 14; 91: 18;
                                                     māţu (LAL. LAL-ţi) 61: 10; 74: 5; 81:
  116: 19; 117: 18; 30; 168: 9, 11a, 12a;
                                                       6a, 8, 13; 82: 6; 87: [16]; 117: 7, 9, 11;
  169: 5, 11; 292: 13; BM 62637: 4, 9,
                                                       128: 13; 148: 10'; 167: 14.
  14<sup>19</sup>
                                                     miḥṣu 6: 1; 7: 1; 48: 1; 63: 1; 70: [1]; 181:
<sup>na</sup>4gabû; 377: 3'; 453: 3; 461: 5; 477: 6;
                                                       1; 182: 1; 227: 1; 235: [7]; 436: 3.
  517: 1; 526: 2; 528: 1; 529: 1; 530: 1;
                                                     miḥșu dullu 81: 9.
  531: 1; 532: 1; 535: 7; 536: 2; 537: 2;
                                                     miḥṣu dullu peṣû 78: 1.
  538: 2; 539: 1; 540: 3; 541: 1, 5, 7;
                                                     miḥṣu tenû 184: 1; 185: 1; 186: [1]; 187:
  544: 4, 9; 547: 10; 549: 1, 6, 9; 550: 6;
                                                        1; 189: [1]; 190: 1; 191: [1]; 193: 1;
                                                       194: [1]; 195: 1; 197: [1]; 198: 1; 200:
  554: 2; 608: 3; 609: 2.
kandu 550, rev. 5'.
                                                       1; 201: [1]; 202: 1; 203: [1]; 210: [1];
gidlu 607: 7.
                                                       212: 「17; 217: 1; 219: 1; 220: 「17; 221:
gīdu 572: 3.
                                                       1; 222: [1]; 223: [1]; 224: [1]; 225: [1];
ginû 296 col. II 2'; 381: 3; 382: 10;.
                                                       228: <sup>[1]</sup>; 229: 1; 229a: 1; 232: [1]; 238:
gurrubtu 479: 2, cf. Nbn 637: 5.
                                                       [1]; 239: 1; 240: [1]; 241: 1; 242: [1];
                                                       244: 1; 245: 「1」; 250: 1; 259: 「1」; 271:
halluru 595: 2.
halsu 462: 2: 546: 3.
                                                       [1]; 273: 「1<sup>1</sup>; 275: 「1<sup>1</sup>; 281: 1; 290:
hāṭu 16: 18; 24: 17; 64: 18; 171: 11, 15,
                                                       [14]; 291: [17]; 292: [14].
  18; 178: [31]; 293, rev. I 2', rev. II 7';
                                                     mi-hi-iş tenû 243: 1.
  294: [12']; 29, rev. 3'; 295: 9'; 297: 7',
                                                     mi-ih-hi-iş tenû 188: 1.
  rev. II 7'; 298: 11'; 299: 8'; 300: 3 ';
                                                     mihşu šá-hu-ú 168: 1; 117: 1.
  301: 16; 302: 4'; 308, rev. 17; 309, rev.
                                                     mihtu 50: 14 (?); 57: 1.
                                                     mušanatu 620: 4.
  6'; 348: 18; 380: 2; 383: 1; 384: 1;
  387: 1; 472, rev.13.
                                                     nakmaru 338: 9; 370: 2-5; 372: 2.
hâțu 348: 7, 15; 382: 2.
                                                     napišu 574: 3.
hillātu 472: 5; 483: 2; Nbn 664: 5.
                                                     nasāḥu 293, rev. II 3'; 294: 8'; 295: 5';
hišihtu 574: 1.
                                                       297 I 3', rev. II 3'; 299: 12'; 304: [3];
hūratu (GIŠ.LAGAB) 533: <sup>[5]</sup>; 534: 3;
                                                       16: 14; 307: [11'].
  589: 2; 609: 1.
                                                     nishu 618: 5.
inzahurītu 458: 2; 461: 8'; 477: 5; 486: 1;
                                                     pappasu 15: 7, 14, 20; 163, obv. I 9; 296,
                                                       col. II 2'; 410: 6; 412: 1; 419: 3; 439:
  504: 2; 519: 2; 520: 3, 5-6; 525: 1, 8;
  526: 1; 527: 3; 528: 2; 529: 5; 533: 5;
                                                       4; 440: 3; 441: 2; 444: 2, 6; 481: 9;
  535: 1, 6; 536: 1; 537: 1; 539: 2; 540: 2;
                                                       482: 1; 555: 2'; 563: 5; 564: 3; 568: 2;
  544: 4, [8]; 545: 4; 547: 9; 549: 1, 5, 8,
                                                       583: 3'; 588: 5; 591: 19; 592: 4; 593:
  13; 550: 2, rev. 7'; 601: 4; 607: 4; 608:
                                                       1; 599: 2; 600: 2; 604: 3; 609: 4; 627:
  2; 610: [2], 4; 611: 2; 620: [1]; 623: 5;
                                                       2; 630: 3; 631: 2; 634: [1]; 635: 2; 641:
  625: 3, 5.
                                                       2; 645: 3.
inšahurītu 554: 1.
                                                     pelû 459: 3.
<in>-za-hu-ár-re-ti 510: 2.
                                                     pišannu 388: 14; 456: 2; 463: 2; 471: 2;
iškāru 342: 1; 343: 1; 344: 1; 346, rev.
                                                       490: 6; 535: 5; 544: 2.
  4'.
                                                     quppu 609: 12; 625: 2.
kibāsu 365: 4
                                                     sammātu 473: 10.
kibsu 12: 12; 332 rev. 4; 359: 8.
                                                     sattukku 392: 2; 399: 7; 413: 2; 414: 4';
kiriku 502: 2, 6, 10.
                                                       419: 2; 436: 1; 444: 1; 518: 2; 607: 1;
kiskiru 577a: 2; 629: 3.
                                                       608: 10; 629: 2.
<sup>gada</sup>kabaru 367: <sup>[1]</sup>, 14.
                                                     suhû 508: 5.
                                                     şalam šarrê 600: 9.
                                                     ṣapû (a-na ṣa-pi-e) 534: 4; 609: 8; 521: 2.
<sup>19</sup> Cf Part I, p. 34.
```

566 INDEXES

*șiditu* 638: 1. sīpu (a-na ṣi-pi /ṣi-i-pu/ ṣi-i-pi) 518: 6; 526: 3; 527: 4; 530: 3; 536: 4; 538: [3]; 539: 3; 544: 2, 10; 545, rev.3; 546: 5; 547: 11; 548: 2; 549: 2, 7; 551: 3'; 595: 3; 604: 3. șibutu 453: 5. *şubātu* 547: 3. *şubītu* 379: 5. šahû (šá-hu-ú) 70: 1; 79: 1; 117: 1; 168: 1; BM 64081: 5. šapû 67: 22; 472: 9. šir'am 603: 2–3. šubtu 181: 9; 314: 16'-17'; 321: 6; 324: 6; 20; 325: 7, 18; 326: 8, 22; 329: 4, 6, 12; 335: 10'; 336, rev. 3'. tabû 314: 5', 19'-21'; 315: 1; 316: 2, 11; 325: 1; 326: 1; 327: 1; 328: 2; 329: [2]; 332: 1; 338: 3; 339: 1.

talukātu 314: 6'; 315: 7, rev. 2'; 316: 12; 319: 「3¹; 321: 5; 325: 6; 326: 7; 327: [8]; 328: 「7¹; 329: 9; 333: 3'; 334: 「2¹¹. tumbu 388: 13.
uzāru 425: 2; 426: 2; 427: 6', 9'; BM 74577: 1, 4; Nbn 514: 2; Nrg 19: 2. CT 56, 425: 2; CT 56, 426: 2; CT 56, 427: 2.
uzāru ša (muḥḥu) andulli of:
Anunītu 426: 1.
GAŠAN-AN.NA Nrg 19: 2.
Šarrat Sippar 425: 3; 427: 6.
Unidentified 427: 9.
Name of god(dess) not mentioned

Nbn 514: 3.

## **Text concordance**

**Fat** digit refers to a text published with a copy.

```
BM 49188 = No 556
                                        BM 51274 = No 288
BM 49268 = No 3
                                        BM 51293 = No 22
BM 49304 = No 45
                                        BM 51296 = No 310
BM 49333 = No 42
                                        BM 51447 = No 294
BM 49356 = No 618
                                        BM 51498 = No 6
BM 49370 = No 30
                                        BM 51563 = No 303
BM 49416 = No 19
                                        BM 51568 = No 29
BM 49471 = No 18
                                        BM 51659 = No 296
BM 49541 = No 46
                                        BM 51732 = No 37
BM 49567 = No 17
                                        BM 52102 = No 26
BM 49570 = No 39
                                        BM 52110+BM 52541 = No 12
BM 49580 = No 13
                                        BM 52272 = No 33
BM 49607 = No 638
                                        BM 52285 = No 20
BM 49621 = No 43
                                        BM 52314 = No 31
BM 49669 = No 381
                                        BM 52330 = No 36
BM 49757 = No 348
                                        BM 52353 = No 139
BM 49883 = No 451
                                        BM 52361 = No 9
BM 49902 = No 2
                                        BM 52475 = No 298
BM 49913 = No 356
                                        BM 52541, see BM 52110
BM 49931 = No 183
                                        BM 52636 = No 311
                                        BM 52699 = No 38
BM 49992 = No 34
BM 50031+BM 50209 = No 171
                                        BM 52731 = No 25
BM 50066 = No 295
                                        BM 53001 = No 368
BM 50179 = No 299
                                        BM 53219 = No 32
BM 50198 = No 24
                                        BM 53364 = No 302
BM 50209, cf. BM 50031
                                        BM 53743 = No 140
BM 50255 = No 27
                                        BM 54227 = No 233
BM 50272 = No 1
                                        BM 54258 = No 232
BM 50282 = No 359
                                        BM 54818+BM 59729 = No 57
BM 50293 = No 380
                                        BM 54909+BM 73078 = No 201
BM 50342 = No 21
                                        BM 54922 = No 539
BM 50426 = No 10
                                        BM 55011 = No 448
BM 50439 = No 28
                                        BM 55775 = No 496
BM 50449, see Plate 167
                                        BM 57613[CT 55, 840]+ BM 59013 = No
BM 50623 = No 38
BM 50626 = No 308
                                        BM 58028+BM 59834 = No 76
                                        BM 58641 = No 148
BM 50745 = No 297
BM 50786 = No 44
                                        BM 58779 = No 286a
BM 50938 = No 300
                                        BM 58810 = No 286b
BM 50963 = No 383
                                        BM 58846 = No 216
BM 51099 = No 293
                                        BM 58874 = No 272
BM 51148 = No 177
                                        BM 58917 = 47a
BM 51262 = No 47
                                        BM 58976 = No 630a
```

BM 59003 = No 548	BM 61150 = BM 583a
BM $59009 = 599a$	BM 61162 = No 127
BM 59013, see BM 57613	BM 61182 = No 196
BM 59048 = No 268	BM $61192 = No 628a$
BM 59067 = No 269	BM $61211 = No 595$
BM $59175 = No 270$	BM $61218 = No 475$
BM 59227 = No 109	BM 61226 = No 611
BM 59264 = No 96	BM $61228 = No 403$
BM 59270 = No 267	BM $61311 = No 439$
BM 59277 = No 250	BM $61317 = No 501$
BM 59328 = No 158	BM $61364 = No 370$
BM 59405 = No 146	BM $61459 = No 373$
BM 59423 = No 480	BM $61498 = No 54$
BM 59488 = No 457	BM 61504 = No 195
BM 59491 = No 205	BM $61517 = No 292$
BM 59621 = No 455	BM $61580 = No 165$
BM 59642 = No 524	BM $61597 = No 450$
BM 59660 = No 387	BM 61598 = No 408
BM 59713 = No 83	BM 61601 = No 213
BM 59723 = No 85	BM 61611 = No 587
BM 59729, see BM 54818	BM 61629+BM 62119 = No 122
BM 59834 [CT 55, 851], see BM 58028	BM 61690 = No 173
BM 59871 = No 223	BM 61726 = No 413
BM 59963 = No 271	BM $61749 = No 592$
BM 59981 = No 155	BM 61762 = No 167
BM 59990 = No 517	BM 61765 = No 253
BM $60135 = No 632$	BM 61783 = No 202
BM 60307 = No 321	BM 61785+BM 66800 = No 237
BM 60320 = No 478	BM 61805 = No 542
BM 60341 = No 504	BM 61828 = No 601
BM 60427 = No 405	BM 61914 = No 185
BM 60445 = No 392	BM 61916 = No 102
BM 60553 = No 417	BM 61920 = No 305
BM 60579 = No 357	BM 61938 = No 168
BM 60719 = No 586	BM 61942 = No 367
BM 60783 = No 613	BM 61953 = No 273
BM 60784 = No 420	BM 61956 = No 236
BM 60803 = No 544	BM 61964 = No 322
BM 60842 = No 563	BM 61968 = No 226
BM 60847 = No 500	BM 61970 = No 498
BM 60866 = No 594	BM 62003 = No 516
BM 60883 = No 92	BM 62059 = No 84
BM 60900 = No 416	BM 62065 = No 75
BM 60933 = No 395	BM 62099= No 637
BM 60937 = No 564a	BM 62100 = No 343
BM 60954 = No 628c	BM 62108 = No 66
BM 60955 = No 585	BM 62119, see BM 61629
BM 60968 = No 349	BM 62149 = No 541
BM 60976 = No 502	BM 62170 = No 409
BM 61011 = No 407	BM 62178 = No 396
BM 61025 = No 346	BM 62213 = No 514
BM 61107 = No 606	BM 62219 = No 135
BM 61114 = No 81	BM $62244 = No 60$
DIVI 01117 - 110 01	DIT 02277 - 110 00

```
BM 62259 = No 466
                                        BM 64600 = No 418
BM 62415 = No 599
                                        BM 64651 = No 221
                                        BM 64657 = No 79
BM 62420 = No 513
BM 62479 = No 597
                                        BM 64673+BM 66633 = 116
BM 62498 = No 621
                                        BM 64798 = No 453
BM 62528 = No 119
                                        BM 64811 = No 476
BM 62543 = No 63
                                        BM 64903 = No 374
BM 62582+BM 65149 = No 112
                                        BM 64919 = No 487
BM 62613 = No 198
                                        BM 64920 = No 600
                                        BM 64937 = No 394
BM 62626 = No 170
BM 62628 = No 316
                                        BM 64991 = No 560
BM 62654 = No 608
                                        BM 64996 = No 456
BM 62667 = No 220
                                        BM 64998 = No 642
BM 62718 = No 443
                                        BM 65007 = No 629
BM 62962 = No 527
                                        BM 65024 = No 641
BM 62980 = No 479
                                        BM 65041 = No 561
BM 63006 = No 401
                                        BM 65047 = No 393
BM 63011 = No 489a
                                        BM 65050 = No 415
BM 63048 = No 530
                                        BM 65057 = No 636
BM 63054 = No 640
                                        BM 65104 = No 607
BM 63250 = No 334
                                        BM 65114 = No 499
BM 63503+BM 64313 = No 314
                                        BM 65127 = No 495
BM 63522 = No 526
                                        BM 65133 = No 619
BM 63590 = No 603
                                        BM 65146 = No 275
BM 63661 = No 204
                                        BM 65149, see BM 62582
BM 63687 = No 276
                                        BM 65159 = No 107
BM 63710 = No 131
                                        BM 65162 = No 87
                                        BM 65259 = No 371
BM 63745 = No 126
BM 63832 = No 616
                                        BM 65263 = No 628b
BM 63866 = No 598
                                        BM 65341 = No 543
BM 63882 = No 635
                                        BM 65377 = No 610
BM 63899 = No 534
                                        BM 65419, see BM 62582
BM 63909 = No 365
                                        BM 65484+BM 68961 = No 210
BM 63912 = No 535
                                        BM 65503 = No 114
BM 63919 = No 431
                                        BM 65504 = No 229a
BM 63922 = No 553
                                        BM 65592 = No 344
BM 63928 = No 473
                                        BM 65708 = No 194
BM 63941 = No 536
                                        BM 65729 = No 347
BM 63962 = No 467
                                        BM 65732 = No 64
BM 63992 = No 425
                                        BM 65741 = No 626
BM 63993 = No 106
                                        BM 65772 = No 555
BM 64013 = No 547
                                        BM 65841 = No 503
BM 64060 = No 581
                                        BM 65913 = No 591
BM 64072 = No 436
                                        BM 65975 = No 289
BM 64093 = No 507
                                        BM 65976 = No 414
                                        BM 65979 = No 179
BM 64099 = No 554
BM 64113 = No 438
                                        BM 66041 = No 510
BM 64313 see BM 63503
                                        BM 66061 = No 551
                                        BM 66095 = No 309
BM 64469 = No 246
BM 64563 = No 497
                                        BM 66096 = No 588a
BM 64564 = No 625
                                        BM 66166 = No 333
BM 64577 = No 402
                                        BM 66196+ BM 67633 = No 231
                                        BM 66202 = No 422
BM 64594 = No 643
```

D3.5	D14 (024F 11 40F
BM 66232 = No 353	BM 68317 = No 207
BM 66247 = No 144	BM 68324 = No 162
BM 66250 = No 128	BM 68348, see BM 68249
BM 66394 = No 284a	BM $68353 = No 143$
BM 66445 = No 372	BM $68361 = \text{No } 277$
BM $66459 = No 378$	BM $68413 = No 59$
BM 66460 = No 518	BM $68670 = \text{No } 244$
BM 66469 = No 94	BM 68788 = No 164
BM $66535 = No 227$	BM $68857 = \text{No } 335$
BM 66582 = No 366	BM $68902 = \text{No } 369$
BM 66633, see BM 64673	BM 68961, see BM 65484
BM $66698 = No 421$	BM $68964 = No 187$
BM 66746 = No 115	BM $68982 = No 113$
BM 66777 = No 424	BM $69003 = No 550$
BM 66800, see BM 61785	BM $69029 = No 323$
BM 66810 = No 399	BM $69077 = No 274$
BM $66817 = No 150$	BM $69122 = No 474$
BM $66823 = No 492$	BM 69144 = No 136
BM 66852 = No 419	BM $69225 = No 494$
BM 66924+BM 73731 = No 82	BM $69226 = No 494a$
BM 66981 = No 623	BM $69250 = No 35$
BM 66988 = No 627	BM $69280 = No 312$
BM 66993 = No 593a	BM 69406 = No 337
BM $67013 = No 588$	BM $69774 = No 230$
BM $67080 = No 406$	BM 69843 = No 247
BM 67093+BM 68298 = No 86	BM 69861 = No 566
BM 67125 = No 444	BM 69973 = No 153
BM 67149+BM 99925 = No 242	BM $70252 = No 217$
BM 67160 = No 68	BM $70279 = No 214$
BM $67252 = No 430$	BM $70309 = No 355$
BM 67311 = No 132	BM 70333 = No 105
BM 67472 = No 590	BM 70544 = No 248
BM 67525 = No 482	BM $70592 = \text{No } 423$
BM 67542 = No 307	BM 70749, see BM 68200
BM 67633, see BM 66196	BM 70834 = No 238
BM 67734 = No 341	BM 70870 = No 318
BM 67814 = No 95	BM $70885 = \text{No } 351$
BM 67854 = No 505	BM 70916 = No 243
BM 67857 = No 92	
	$RM 70999 = N_0 241$
	BM 70999 = No 241 BM 71048 - No 285
BM 67859 = No 280	BM 71048 = No 285
BM 67859 = No 280 BM 67889 = No 317	BM 71048 = No 285 BM 71100 = No 615
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129 BM 68163 = No 53	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258 BM 71878 = No 434
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129 BM 68163 = No 53 BM 68200+ BM 70749 = No 206	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258 BM 71878 = No 434 BM 71903 = No 286
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129 BM 68163 = No 53 BM 68200+ BM 70749 = No 206 BM 68249 +BM 68348+	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258 BM 71878 = No 434 BM 71903 = No 286 BM 71925 = No 239
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129 BM 68163 = No 53 BM 68200+ BM 70749 = No 206 BM 68249 +BM 68348+ BM 101457 = No 291	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258 BM 71878 = No 434 BM 71903 = No 286 BM 71925 = No 239 BM 72305 = No 209
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129 BM 68163 = No 53 BM 68200+ BM 70749 = No 206 BM 68249 +BM 68348+ BM 101457 = No 291 BM 68263 = No 331	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258 BM 71878 = No 434 BM 71903 = No 286 BM 71925 = No 239 BM 72305 = No 209 BM 72330 = No 446
BM 67859 = No 280 BM 67889 = No 317 BM 67934 = No 593 BM 67964 = No 562 BM 67970 = No 99 BM 68109 = No 98 BM 68144 = No 208 BM 68154 = No 129 BM 68163 = No 53 BM 68200+ BM 70749 = No 206 BM 68249 +BM 68348+ BM 101457 = No 291	BM 71048 = No 285 BM 71100 = No 615 BM 71174 = No 584 BM 71237 = No 97 BM 71337 = No 313 BM 71730 = No 88 BM 71732 = No 159 BM 71735 = No 258 BM 71878 = No 434 BM 71903 = No 286 BM 71925 = No 239 BM 72305 = No 209

## TEXT CONCORDANCE

BM 72584 = No 62	BM 75530 = No 437
BM $72810 = No 345$	BM $75552 = No 91$
BM $72840 = No 531$	BM 75676 = No 508
BM 72875 = No 118	BM $75708 = No 625a$
BM 72963 = No 121	BM $75767 = No 472$
BM $72982 = No 212$	BM $75848 = No 327$
BM $72999 = No 427$	BM 75993 = No 138
BM $73018 = No 72$	BM 76129 = No 125
BM 73072 = No 249	BM 76347 = No 411
BM 73073 = No 281	BM $76362 = No 386$
BM 73078 see BM 54909	BM 76468 = No 110
BM $73111 = No 520$	BM 76590+BM 79793+
BM 73113 = No 515	BM 99874 = No 163
BM $73134 = No 203$	BM $76771 = No 103$
BM 73159 = No 263	BM $76963 = No 350$
BM $73185 = No 174$	BM $77920 = No 375$
BM 73244 = No 340	BM $77968 = No 339$
BM 73254 = No 362	BM $78893 = No 200$
BM 73276 = No 70	BM 78914 = No 14
BM 73347 = No 264	BM 78926 = No 134
BM 73408 = No 278	BM 79134 = No 460
BM 73418 = No 262	BM $79222 = No 452$
BM 73474 = No 265	BM $79326 = No 41$
BM $73489 = No 90$	BM 79346 = No 568
BM $73528 = No 80$	BM 79348 = No 537
BM 73661 = No 156	BM $79352 = No 519$
BM 73673 = No 266	BM 79359 = No 559
BM 73703 = No 352	BM 79383 = No 465
BM 73720 = No 199	BM $79386 = No 23$
BM 73723 = No 169	BM $79560 = No 484a$
BM 73731, see BM 66924	BM $79603 = No 577$
BM 73764 = No 142	BM $79604 = No 628$
BM $73825 = No 426$	BM $79669 = No 572$
BM $73909 = No 89$	BM $79695 = No 447$
BM 73981 = No 224	BM 79711= No 376
BM $74002 = No 219$	BM $79745 = No 61$
BM $74304 = No 319$	BM 79793, see BM 76590
BM $74324 = No 120$	BM $82568 = No 624$
BM $74325 = \text{No } 320$	BM $82578 = No 11$
BM 74431= No 432	BM $82581 = No 180$
BM $74440 = No 123$	BM $82586 = No 40$
BM $74459 = No 440$	BM $83162 = No 617$
BM $74479 = No 441$	BM 83271 = No 583
BM $74484 = No 549$	BM 83275 = No 283
BM $74663 = No 633$	BM $83281 = No 429$
BM $74670 = No 609$	BM 83316 = No 385
BM 74963 = No 620	BM 83329 = No 149
BM 75186 = No 604	BM 83377 = No 445
BM 75289 = No 511	BM 83395 = No 235
BM 75322 = No 589	BM 83408 = No 545
BM 75379 = No 506	BM 83436 = No 145
BM 75397 = No 188	BM 83474 = No 622
BM $75529 = No 602$	BM $83479 = No 533$


BM 83511 = No 464	BM $101193 = No 470$
BM 83528 = No 631	BM $101215 = No 612$
BM $83534 = No 218$	BM 101251 = No 245
BM $83650 = No 408a$	BM $101286 = No 358$
BM $83659 = No 332$	BM $101301 = No 484$
BM 83668 = No 540	BM $101312 = No 605$
BM 83699 = No 630	BM $101340 = No 279$
BM $83706 = No 512$	BM $101416 = No 398$
BM $83708 = No 462$	BM 101457, see BM 68249
BM $83801 = No 141$	BM $101467 = No 361$
BM $83803 = No 284$	BM $101488 = No 435$
BM $83877 = No 404$	BM $101489 = No 634$
BM 83904 = No 166	BM $101678 = \text{No } 412$
BM 83918 = No 449	BM $101687 = No 477$
BM $83973 = No 78$	BM $101726 = No 468$
BM $83985 = No 186$	BM $101776 = No 483$
BM $83987 = No 73$	BM $101793 = No 152$
BM 84034 = No 491	BM $101873 = No 336$
BM $84140 = No 364$	BM 114751 = No 644
BM $84149 = No 360$	BM $114790 = No 645$
BM 84214 = No 388	a a
BM 84254 = No 225	Cam 30 = No 578
BM 84300 = No 481	Cam $39 = No 488$
BM 84381 = No 546	Cam 148 = No 315
BM 84391 = No 486	Cam $158 = No 490$
BM 84407 = No 256	Cam 191= No 579
<b>BM 84470 = No 389</b> BM 84490 = No 161	Cam 250 = No 580 Cam 312 = No 117
BM 84500 = No 363	Cam $312 = No 117$ Cam $382 = No 493$
BM 84509 = No 304	Cam $413 = No 69$
BM 91002 (BBSt 36) = No 175	Cam 413 = 110 07
BM 99462 = No 354	CT 4, 38a = No 178
BM 99474 = No 410	CT 44, 73 = No 67
BM 99494 = No 251	CT 55, 348 = No 521
BM 99512 = No 252	CT 55, 353 = No 525
BM 99535 = No 377	CT 55, 356 = No 522
BM 99578 = No 442	CT 55, 357 = No 523
BM $99850 = No 400$	CT 55, 362 = No 528
BM 99925, see BM 67149	CT 55, 363 = No 529
BM 99937 = No 390	CT 55, 367 = No 532
BM 99951 = No 240	CT 55, 798 = No 576
<b>BM 99874</b> , see <b>BM 76590</b>	CT 55, 801 = No 71
BM 100720 = No 157	CT 55, 802 = No 55
BM $100733 = No 254$	CT 55, 803 = No 130
BM 100764 = No 191	CT 55, 804 = No 51
BM $100792 = No 257$	CT 55, 805 = No 189
BM $100874 = No 614$	CT 55, 806 = No 108
BM 100893 = No 564	CT 55, 807 = No 65
BM 100954 = No 255	CT 55, 808 = No 181
BM 100960 = No 433	CT 55, 809 = No 184
BM 101060 = No 190	CT 55, 810 = No 48
BM 101063 = No 428	CT 55, 811 = No 182
BM 101169 = No 133	CT 55, 812 = No 259


### TEXT CONCORDANCE

CT 55, 813 = No 330	Nbk 312 = No 324
CT 55, 814 = No 329	Nbn 78 = No 193
CT 55, 817 = No 260	Nbn $217 = No 459$
CT 55, 818 = No 211	Nbn 291 = No 565
CT 55, 819 = No 261	Nbn $320 = No 50$
CT 55, 824 = No 215	Nbn $439 = No 570$
	Nbn $460 = \text{No } 570$
CT 55, 826 = No 234	
CT 55, 828 = No 552	Nbn 694 = No 325
CT 55, 830 = No 8	Nbn 696 = No 326
CT 55, 831 = No 558	Nbn 726 = No 77
CT 55, 834 = No 582	Nbn 785 = No 397
CT 55, 837 = No 306	Nbn $826 = No 52$
CT 55, 838 = No 192	Nbn $848 = No 338$
CT 55, 839 = No 147	Nbn $879 = No 573$
CT 55, 840, See BM 59013+	Nbn $929 = No 574$
CT 55, 841 = No 111	Nbn $1015 = No 124$
CT 55, 842 = No 391	Nbn $1061 = No 538$
CT 55, 844 = No 301	
CT 55, 845 = No 101	VS 6, 8 = No 379
CT 55, 846 = No 154	VS 6, 15 = No 5
CT 55, 847 = No 137	VS 6, $16 = No 15$
CT 55, 850 = No 197	VS 6, $17 = No 7$
CT 55, 851, see BM 58028+	VS 6, 23 = No 452
CT 55, 853 = No 49	VS 6, 24 = No 384
CT 55, 854 = No 160	VS 6, 26 = No 287
CT 55, 855 = No 100	VS 6, 28 = No 16
CT 55, 859 = No 454	VS 6, 71 = No 74
CT 55, 865 = No 461	VS 6, 77 = No 471
· · · · · · · · · · · · · · · · · · ·	,
CT 55, 866 = No 509	VS 6, 107 = No 489
CT 55, 867 = No 463	VS 6, 208 = No 4
CT 55, 868 = No 596	7 A 4 N - 4 N - 17
CT 55, 870 = No 469	ZA 4, No $4 = No 17$
CT 55, 871 = No 569	
CT 56, 3 = No 567	
CT 56, 4 = No 577a	
CT 56, 5 = No 575	
CT 56, 6 = No 557	
Cyr 7 = No 228	
Cyr 109 = No 342	
Cyr 185 = No 328	
Cyr 186 = No 56	
Cyr 191 = No 172	
$Cyr\ 201 = No\ 104$	
Cyr 202 = No 485	
Cyr 232 = No 290	
Cyr 241 = No 229	
Cyr 289 = No 58	
•	

# Plates


PLATE 1 577








1. BM 50272







3. BM 49268



6. BM 51498



9. BM 52361


PLATE 3 579



10. BM 50426





11. BM 82578




12. BM 52110

PLATE 5 581






13. BM 49580









14. BM 78914





17. BM 49567

山西今〈雅 河」 山岛河西山谷 古本华州 河谷河下中 石中山谷(山山河 河谷河下中 石山山谷(山山河 河谷河 河下市 石山山谷 河谷河 河下町 一河公 大谷口 河口 一河公山 大谷口 河口 一河公山







18. BM 49471

PLATE 7 583







19. BM 49416






21. BM 50342

PLATE 9 585






22. BM 51293




23. BM 79386





24. BM 50198



26. BM 52102


PLATE 11 587







27. BM 50255




28. BM 50439





29. BM 51568




30. BM 49570




31. BM 52314


PLATE 13 589




34. BM 49992













37. BM 51732



38. BM 52699




40. BM 82586


PLATE 15 591









41. BM 79326








42. BM 49333



43. BM 49621



45. BM 49304




46. BM 49541

PLATE 17 593






47. BM 51262







54. BM 61498




59. BM 68413

PLATE 19 595





61. BM 79745




63. BM 62543







64. BM 65732



66. BM 62108

PLATE 21 597







68. BM 67160




72. BM 73018







78. BM 83973

PLATE 23 599







79. BM 64657




81. BM 61114

PLATE 25 601






85. BM 59723




86. BM 67093+



88. BM 71730


PLATE 27 603




93. BM 60883



96. BM 59264




97. BM 71237




107. BM 65159


PLATE 29 605



112. BM 62582+




116. BM 64673+




117. BM 60770

PLATE 31 607





120. BM 74324




127. BM 61162

PLATE 33 609



128. BM 66250



143. BM 68535



144. BM 66247



146. BM 59405

PLATE 35 611




148. BM 58641



163. BM 76590+, obv.




163. BM 76590+, rev.




164. BM 68788

PLATE 37 613




165. BM 61580




166. BM 83904


167. BM 61762

PLATE 39 615




168. BM 61938







170. BM 62626

PLATE 41 617




171. BM 50031+






174. BM 73185


PLATE 43 619








177. BM 51148



180. BM 82581





183. BM 49931




185. BM 61914


PLATE 45 621






196. BM 61182





207. BM 68317


PLATE 47 623




208. BM 68144




209. BM 72305







210. BM 65484

PLATE 49 625







214. BM 70279




219. BM 74002






220. BM 62667


PLATE 51 627






221. BM 64651

628




231. BM 66196+, obv.

PLATE 53 629




231. BM 66196+, rev.




237a. BM 61785+

PLATE 55 631




242. BM 67149+





245. BM 101251




254. BM 100733

PLATE 57 633



266. BM 73673




267. BM 59270



270. BM 59175



272. BM 58874




284. BM 83803

PLATE 59 635







284a. BM 66394



286a. BM 58779





286b. BM 58810

PLATE 61 637






288. BM 51274






289. BM 65975


PLATE 63 639





291. BM 68249+









292. BM 61517

PLATE 65 641






293. BM 51099





294. BM 51447


PLATE 67 643



295. BM 50066





297. BM 50745, obv.




297. BM 50745, rev.

PLATE 69 645





298. BM 52475




300. BM 50938



303. BM 51563





311. BM 52636



314. BM 63503+

PLATE 71 647






316. BM 62628






317. BM 67889



323. BM 69029


PLATE 73 649



332. BM 83659



334. BM 63250




339. BM 77968


PLATE 75 651






343. BM 62100







344. BM 65592

PLATE 77 653






345. BM 72810




346. BM 61025

PLATE 79 655




348. BM 49757



353. BM 66232

PLATE 81 657



355. BM 70309




356. BM 49913




358. BM 101286

PLATE 83 659



359. BM 50282



360. BM 84149



362. BM 73254






363. BM 84500


PLATE 85 661



364. BM 84140



367. BM 61942




370. BM 61364




371. BM 65259


PLATE 87 663



373. BM 61459



381. BM 49669




382. BM 50623


PLATE 89 665



383. BM 50963




385. BM 83316






387. BM 59660



388. BM 84214

PLATE 91 667









389. BM 84470




390. BM 99937






393. BM 65047


PLATE 93 669




395. BM 60933



396. BM 62178





398. BM 101416




402. BM 64577

PLATE 95 671






403. BM 61228





405. BM 60427






406. BM 67080







407. BM 61011


PLATE 97 673








408a. BM 83650






409. BM 62170






411. BM 76347





412. BM 101678

PLATE 99 675




416. BM 60900






417. BM 60533




418. BM 64600

PLATE 101 677




419. BM 66852





420. BM 60784




427. BM 72999

PLATE 103 679





429. BM 83281





430. BM 67252



434. BM 71818




435. BM 101488

PLATE 105 681




442. BM 99578



444. BM 67125







445. BM 83377


张文章 於

英祖益好次次 英国国际 答


447. BM 79695


PLATE 107 683






450. BM 61597





451. BM 49883





## 品及風奔型語




455. BM 59621







457. BM 59488

PLATE 109 685








458. BM 79222




## 1世月月 1 日本






460. BM 79134

PLATE 111 687



462. BM 83708






465. BM 79383






468. BM 101726



475. BM 61218


PLATE 113 689



476. BM 64811



480. BM 59423



484. BM 101301

PLATE 115 691




484a. BM 79560






487. BM 64919



489a. BM 63011


PLATE 117 693



## 其四十五日本本




491. BM 84034






492. BM 66823




494. BM 69225



495. BM 65127


PLATE 119 695








498. BM 61970






500. BM 60847




503. BM 65841


PLATE 121 697




504. BM 60341



505. BM 67854



512. BM 83706



514. BM 62213

PLATE 123 699






518. BM 66460





519. BM 79352




520. BM 73111




524. BM 59642

PLATE 125 701













527. BM 62962





530. BM 63048





531. BM 72840





533. BM 83479

PLATE 127 703



537. BM 79348




541. BM 62149





543. BM 65341

PLATE 129 705



550. BM 69003





551. BM 66061




559. BM 79359


PLATE 131 707



560. BM 64991



561. BM 65041



562. BM 67964




563. BM 60842

PLATE 133 709











568. BM 79346




572. BM 79669



577. BM 79603


PLATE 135 711






583. BM 83271







583a. BM 61150






584. BM 71174

PLATE 137 713




585. BM 60955



中叶灰中国

586. BM 60719





587. BM 61611



588. BM 67013


PLATE 139 715



588a. BM 66096




590. BM 67472






591. BM 65913

PLATE 141 717




592. BM 61749




593. BM 67934






593a. BM 66993



594. BM 60866

PLATE 143 719




595. BM 61211



597. BM 62479




599. BM 62415




599a. BM 59009

PLATE 145 721









600. BM 64920

# 区制年在古



601. BM 61828



603. BM 63590

PLATE 147 723



604. BM 75186






606. BM 61107




607. BM 65104

PLATE 149 725






608. BM 62654






609. BM 74670



610a. BM 62896

PLATE 151 727






611. BM 61226



617. BM 83162




618. BM 49356




619. BM 65133

PLATE 153 729






623. BM 66981






624. BM 82568

PLATE 155 731



625. BM 64564




625a. BM 75708



626. BM 65741

PLATE 157 733



627. BM 66988



628a. BM 61192






628b. BM 65263






628c. BM 60954





629. BM 65007


PLATE 159 735



630. BM 83699



630a. BM 58976




630b. BM 78548




632. BM 60135

PLATE 161 737




637. BM 62099, obv.




637. BM 62099, rev.


PLATE 163 739







638. BM 49607



639. BM 66012





640. BM 63054


PLATE 165 741



641. BM 65024









644. BM 114751





645. BM 114790

PLATE 167 743



BM 50449

# ORBIS BIBLICUS ET ORIENTALIS — Lieferbare Bände / volumes disponibles

- Bd. 200 HILDI KEEL-LEU / BEATRICE TEISSIER: Die vorderasiatischen Rollsiegel der Sammlungen «Bibel+Orient» der Universität Freiburg Schweiz / The Ancient Near Eastern Cylinder Seals of the Collections «Bible+Orient» of the University of Fribourg. XXII—412 Seiten, 70 Tafeln. 2004.
- Bd. 201 STEFAN ALKIER / MARKUS WITTE (Hrsg.): Die Griechen und das antike Israel. Interdisziplinäre Studien zur Religions- und Kulturgeschichte des Heiligen Landes. VIII–216 Seiten. 2004.
- Bd. 202 ZEINAB SAYED MOHAMED: Festvorbereitungen. Die administrativen und ökonomischen Grundlagen altägyptischer Feste. XVI–200 Seiten. 2004.
- Bd. 203 VÉRONIQUE DASEN (éd.): *Naissance et petite enfance dans l'Antiquité.* Actes du colloque de Fribourg, 28 novembre 1<sup>et</sup> décembre 2001. 432 pages. 2004.
- Bd. 204 IZAK CORNELIUS: The Many Faces of the Goddess. The Iconography of the Syro-Palestinian Goddesses Anat, Astarte, Qedeshet, and Asherah ca. 1500-1000 BCE. XVI–208 pages, 108 plates. 2004.
- Bd. 205 LUDWIG D. MORENZ: Bild-Buchstaben und symbolische Zeichen. Die Herausbildung der Schrift in der hohen Kultur Altägyptens. XXII–390 Seiten. 2004.
- Bd. 206 WALTER DIETRICH (Hrsg.): David und Saul im Widerstreit Diachronie und Synchronie im Wettstreit. Beiträge zur Auslegung des ersten Samuelbuches. 320 Seiten. 2004.
- Bd. 207 INNOCENT HIMBAZA: Le Décalogue et l'histoire du texte. Etudes des formes textuelles du Décalogue et leurs implications dans l'histoire du texte de l'Ancien Testament. XIV–376 pages. 2004.
- Bd. 208 CORNELIA ISLER-KERÉNYI: Civilizing Violence. Satyrs on 6th Century Greek Vases. XII–132 pages. 2004.
- Bd. 209 BERND U. SCHIPPER: *Die Erzählung des Wenamun.* Ein Literaturwerk im Spannungsfeld von Politik, Geschichte und Religion. Ca. 400 Seiten, 6 Tafeln. 2005.
- Bd. 210 CLAUDIA E. SUTER / CHRISTOPH UEHLINGER (eds.): Crafts and Images in Contact. Studies in Eastern Mediterranean Art of the First Millennium BCE. XL–375 pages, 50 plates. 2005.
- Bd. 211 ALEXIS LÉONAS: Recherches sur le langage de la Septante. 360 pages. 2005.
- Bd. 212 BRENT A. STRAWN: What Is Stronger than a Lion? Leonine Image and Metaphor in the Hebrew Bible and the Ancient Near East. XXX–602 pages, 483 figures. 2005.
- Bd. 213 TALLAY ORNAN: *The Triumph of the Symbol*. Pictorial Representation of Deities in Mesopotamia and the Biblical Image Ban. XXXII—488 pages, 220 figures. 2005.
- Bd. 214 DIETER BÖHLER / INNOCENT HIMBAZA / PHILIPPE HUGO (éds.): L'Ecrit et l'Esprit. Etudes d'histoire du texte et de théologie biblique en hommage à Adrian Schenker. 512 pages. 2005.
- Bd. 215 SÉAMUS O'CONNELL: From Most Ancient Sources. The Nature and Text-Critical Use of Greek Old Testament Text of the Complutensian Polyglot Bible. XII–188 pages. 2006.
- Bd. 216 ERIKA MEYER-DIETRICH: Senebi und Selbst. Personenkonstituenten zur rituellen Wiedergeburt in einem Frauensarg des Mittleren Reiches. XII–412 Seiten, 26 Tafeln. 2006.
- Bd. 218 STEFAN ZAWADZKI: *Garments of the Gods.* Studies on the Textile Industry and the Pantheon of Sippar according to the Texts from the Ebabbar Archive. XXIV–264 pages. 2006.

- Bd. 219 CARSTEN KNIGGE: *Das Lob der Schöpfung*. Die Entwicklung ägyptischer Sonnenund Schöpfungshymnen nach dem Neuen Reich. XII-372 Seiten. 2006.
- Bd. 220 SILVIA SCHROER (ed.): *Images and Gender.* Contributions to the Hermeneutics of Reading Ancient Art. 392 pages, 29 plates. 2006.
- Bd. 221 CHRISTINE STARK: «Kultprostitution» im Alten Testament? Die Qedeschen der Hebräischen Bibel und das Motiv der Hurerei. 262 Seiten. 2006.
- Bd. 222 DAGMAR PRUIN: Geschichten und Geschichte. Isebel als literarische und historische Gestalt. XII–424 Seiten. 2006.
- Bd. 223 PIERRE COULANGE: *Dieu, ami des pauvres.* Etude sur la connivence entre le Très-Haut et les petits. 304 pages. 2007.
- Bd. 224 ANDREAS WAGNER (Hrsg.): Parallelismus membrorum. 320 Seiten. 2007.
- Bd. 225 CHRISTIAN HERRMANN: Formen für ägyptische Fayencen aus Qantir II. Katalog der Sammlung des Franciscan Biblical Museum, Jerusalem, und zweier Privatsammlungen. 176 Seiten. 2007.
- Bd. 226 JENS HEISE: Erinnern und Gedenken. Aspekte der biographischen Inschriften der ägyptischen Spätzeit. IV-396 Seiten. 2007.
   Bd. 227 HENRIKE FREY-ANTHES: Unheilsmächte und Schutzgenien, Antiwesen und Grenz-
- gänger. Vorstellungen von Dämonen im alten Israel. 384 Seiten. 2007. Bd. 228 BOB BECKING: From David to Gedaliah. The Book of Kings as Story and History.
- XII–236 pages. 2007.

  Bd. 229 ULRIKE DUBIEL: Amulette, Siegel und Perlen. Studien zu Typologie und Tragesitte
- im Alten und Mittleren Reich. 250 Seiten. 2007.

  Bd. 230 MARIANA GIOVINO: *The Assyrian Sacred Tree.* A History of Interpretations. VIII—
- Bd. 231 PAUL KÜBEL: Metamorphosen der Paradieserzählung. X–246 Seiten. 2007.

314 pages. 2007.

- Bd. 232 SARIT PAZ: *Drums, Women, and Goddesses.* Drumming and Gender in Iron Age II Israel. XII–156 pages. 2007.
- Bd. 233 INNOCENT HIMBAZA / ADRIAN SCHENKER (éds.): *Un carrefour dans l'histoire de la Bible.* Du texte à la théologie au II<sup>e</sup> siècle avant J.-C. X–158 pages. 2007.
- Bd. 234 RICARDO TAVARES: *Eine königliche Weisheitslehre?* Exegetische Analyse von Sprüche 28–29 und Vergleich mit den ägyptischen Lehren Merikaras und Amenemhats. XIV–314 Seiten. 2007.
- Bd. 235 MARKUS WITTE / JOHANNES F. DIEHL (Hrsg.): *Israeliten und Phönizier.* Ihre Beziehungen im Spiegel der Archäologie und der Literatur des Alten Testaments und seiner Umwelt. VIII–304 Seiten. 2008.
- Bd. 236 MARCUS MÜLLER-ROTH: Das Buch vom Tage. XII–644 Seiten. 2008.
- Bd. 237 KARIN N. SOWADA: Egypt in the Eastern Mediterranean during the Old Kingdom. XXIV-312 pages, 48 figures, 19 plates. 2009.
- Bd. 238 WOLFGANG KRAUS (Hrsg.) / OLIVIER MUNNICH (éd.): La Septante en Allemagne et en France / Septuaginta Deutsch und Bible d'Alexandrie. XII–316 Seiten. 2009.
- Bd. 239 CATHERINE MITTERMAYER: Enmerkara und der Herr von Arata. Ein ungleicher Wettstreit. VI–426 Seiten, XIX Tafeln. 2009.
- Bd. 240 ELIZABETH A. WARAKSA: Female Figurines from the Mut Precinct. Context and Ritual Function. XII–252 pages. 2009.

- Bd. 241 DAVID BEN-SHLOMO: Philistine Iconography. A Wealth of Style and Symbolism. XII–236 pages. 2010.
- Bd. 242 JOEL M. LEMON: *Yahweh's Winged Form in the Psalms*. Exploring Congruent Iconography and Texts. XIV–244 pages. 2010.
- Bd. 243 AMR EL HAWARY: Wortschöpfung. Die Memphitische Theologie und die Siegesstele des Pije zwei Zeugen kultureller Repräsentation in der 25. Dynastie. XIV–532 Seiten. 2010.
- Bd. 244 STEFAN H. WÄLCHLI: Gottes Zorn in den Psalmen. Eine Studie zur Rede vom Zorn Gottes in den Psalmen im Kontext des Alten Testaments. 200 Seiten. 2012.
- Bd. 245 HANS ULRICH STEYMANS (Hrsg.): *Gilgamesch.* Ikonographie eines Helden. Gilgamesh: Epic and Iconography. XII–464 Seiten, davon 102 Seiten Abbildungen. 2010.
- Bd. 246 DONNA LEE PETTER: The Book of Ezekiel and Mesopotamian City Laments. XXVI-208 pages. 2011.
- Bd. 247 ERIKA FISCHER: *Tell el-Far<sup>c</sup>ah (Süd)*. Ägyptisch-levantinische Beziehungen im späten 2. Jahrtausend v. Chr. X–442 Seiten, davon 100 Seiten Abbildungen. 2011.
- Bd. 248 THIERRY PETIT: *Œdipe et le Chérubin*. Les sphinx levantins, cypriotes et grecs comme gardiens d'Immortalité. X–390 pages. 90 pages d'illustrations. 2011.
- Bd. 249 WALTER DIETRICH (Hrsg.): Seitenblicke. Literarische und historische Studien zu Nebenfiguren im zweiten Samuelbuch. 472 Seiten. 2011.
- Bd. 250 JEAN-MARIE DURAND / THOMAS RÖMER / MICHAEL LANGLOIS (éds.): Le jeune béros. Recherches sur la formation et la diffusion d'un thème littéraire au Proche-Orient ancien. 376 pages. 2011.
- Bd. 251 MARGARET JAQUES (Hrsg.): Klagetraditionen. Form und Funktion der Klage in den Kulturen der Antike. 120 Seiten. 2011.
- Bd. 252 MICHAEL LANGLOIS: *Le texte de Josué 10*. Approche philologique, épigraphique et diachronique. 278 pages. 2011.
- Bd. 253 PAUL BÉRÉ: Le second Serviteur de Yhwh. Un portrait exégétique de Josué dans le livre éponyme. XVI–284 pages. 2012.
- Bd. 254 GODEFROID BAMBI KILUNGA: Prééminence de YHWH ou autonomie du prophète. Etude comparative et critique des confessions de Jérémie dans le texte hébreu massorétique et la «Septante». XVI–224 pages. 2012.
- Bd. 255 MAYER GRUBER / SHMUEL AHITUV / GUNNAR LEHMANN / ZIPORA TALSHIR (eds.): *All the Wisdom of the East.* Studies in Near Eastern Archaeology and History in Honor of Eliezer D. Oren. XXVIII–568 pages. 2012.
- Bd. 256 CATHERINE MITTERMAYER / SABINE ECKLIN (Hrsg.): Altorientalische Studien zu Ehren von Pascal Attinger. mu-ni u<sub>4</sub> ul-li<sub>2</sub>-a-aš ĝa<sub>2</sub>- ĝa<sub>2</sub>-de<sub>3</sub>. XVIII–458 Seiten. 2012.
- Bd. 257 JEAN-MARIE DURAND / THOMAS RÖMER / JÜRG HUTZLI (éds.): Les vivants et leurs morts. X–294 pages. 2012.
- Bd. 258 RICHARD JUDE THOMPSON: *Terror of the Radiance*. Aššur Covenant to YHWH Covenant. X–296 pages. 2013.
- Bd. 259 JULIA M. ASHER-GREVE / JOAN GOODNICK WESTENHOLZ: Goddesses in Context. On Divine Powers, Roles, Relationships and Gender in Mesopotamian Textual and Visual Sources. XII-460 pages, including 155 figures. 2013.

## ACADEMIC PRESS FRIBOURG VANDENHOECK & RUPRECHT GÖTTINGEN

#### SONDERBÄNDE / VOLUMES HORS SÉRIE

CATHERINE MITTERMAYER: Althabylonische Zeichenliste der sumerisch-literarischen Texte. XII–292 Seiten. 2006.

SUSANNE BICKEL / RENÉ SCHURTE / SILVIA SCHROER / CHRISTOPH UEHLINGER (eds.): *Bilder als Quellen / Images as Sources.* Studies on ancient Near Eastern artefacts and the Bible inspired by the work of Othmar Keel. XLVI–560 pages. 2007.

Weitere Informationen zur Reihe OBO: www.unifr.ch/dbs/publication\_obo.html

#### ORBIS BIBLICUS ET ORIENTALIS, SERIES ARCHAEOLOGICA

- Bd. 9 CLAUDE DOUMET: Sceaux et cylindres orientaux: la collection Chiha. Préface de Pierre Amiet. 220 pages, 24 pages d'illustrations. 1992.
- Bd. 10 OTHMAR KEEL: Corpus der Stempelsiegel-Amulette aus Palästina/Israel. Von den Anfängen bis zur Perserzeit. Einleitung. 376 Seiten mit 603 Abbildungen im Text. 1995.
- Bd. 11 BEATRICE TEISSIER: Egyptian Iconography on Syro-Palestinian Cylinder Seals of the Middle Bronze Age. XII–224 pages with numerous illustrations, 5 plates. 1996.
- Bd. 12 ANDRÉ B. WIESE: *Die Anfänge der ägyptischen Stempelsiegel-Amulette.* Eine typologische und religionsgeschichtliche Untersuchung zu den «Knopfsiegeln» und verwandten Objekten der 6. bis frühen 12. Dynastie. XXII–366 Seiten mit 1426 Abbildungen. 1996.
- Bd. 13 OTHMAR KEEL: Corpus der Stempelsiegel-Amulette aus Palästina/Israel. Von den Anfängen bis zur Perserzeit. Katalog Band I. Von Tell Abu Farağ bis 'Atlit. VIII–808 Seiten mit 375 Phototafeln. 1997.
- Bd. 14 PIERRE AMIET / JACQUES BRIEND / LILIANE COURTOIS / JEAN-BERNARD DUMORTIER: *Tell el Far<sup>c</sup> ab.* Histoire, glyptique et céramologie. 100 pages. 1996.
- Bd. 15 DONALD M. MATTHEWS: The Early Glyptic of Tell Brak. Cylinder Seals of Third Millennium Syria. XIV–312 pages, 59 plates. 1997.
- Bd. 17 OLEG BERLEV / SVETLANA HODJASH: Catalogue of the Monuments of Ancient Egypt. From the Museums of the Russian Federation, Ukraine, Bielorussia, Caucasus, Middle Asia and the Baltic States. XIV–336 pages, 208 plates. 1998.
- Bd. 18 ASTRID NUNN: Der figürliche Motivschatz Phöniziens, Syriens und Transjordaniens vom 6. bis zum 4. Jahrhundert v. Chr. 280 Seiten und 92 Seiten Illustrationen. 2000.
- Bd. 19 ANDREA M. BIGNASCA: I kernoi circolari in Oriente e in Occidente. Strumenti di culto e immagini cosmiche. XII–328 Seiten, Tafeln und Karten inbegriffen. 2000.
- Bd. 20 DOMINIQUE BEYER: Emar IV. Les sceaux. Mission archéologique de Meskéné–Emar. Recherches au pays d'Aštata. XXII–496 pages, 66 planches. 2001.
- Bd. 21 MARKUS WÄFLER: *Tall al-Ḥamīdīya 3*. Zur historischen Geographie von Idamaras zur Zeit der Archive von Mari② und Šubat-enlil/Šeḥnā. Mit Beiträgen von Jimmy Brignoni und Henning Paul. 304 Seiten. 14 Karten. 2001.
- Bd. 22 CHRISTIAN HERRMANN: Die ägyptischen Amulette der Sammlungen BIBEL+ORIENT der Universität Freiburg Schweiz. X–294 Seiten, davon 126 Bildtafeln inbegriffen. 2003.

- Bd. 23 MARKUS WÄFLER: *Tall al-Ḥamīdīya 4.* Vorbericht 1988–2001. 272 Seiten. 20 Pläne. 2004.
- Bd. 24 CHRISTIAN HERRMANN: Ägyptische Amulette aus Palästina/Israel. Band III. XII–364 Seiten, davon 107 Seiten Bildtafeln. 2006.
- Bd. 25 JÜRG EGGLER / OTHMAR KEEL: Corpus der Siegel-Amulette aus Jordanien. Vom Neolithikum bis zur Perserzeit. XVIII–518 Seiten. 2006.
- Bd. 26 OSKAR KAELIN: «Modell Ägypten». Adoption von Innovationen im Mesopotamien des 3. Jahrtausends v. Chr. 208 Seiten. 2006.
- Bd. 27 DAPHNA BEN-TOR: Scarabs, Chronology, and Interconnections. Egypt and Palestine in the Second Intermediate Period. XII–212 text pages, 228 plates. 2007.
- Bd. 28 JAN-WAALKE MEYER: *Die eisenzeitlichen Stempelsiegel aus dem <sup>c</sup>Amuq-Gebiet.* Ein Beitrag zur Ikonographie altorientalischer Siegelbilder. X–662 Seiten. 2008.
- Bd. 29 OTHMAR KEEL: Corpus der Stempelsiegel-Amulette aus Palästina/Israel. Von den Anfängen bis zur Perserzeit. Katalog Band II: Von Bahan bis Tel Eton. XIV–642 Seiten, davon 305 mit Fotos und Zeichnungen. 2010.
- Bd. 30 RAZ KLETTER / IRIT ZIFFER / WOLFGANG ZWICKEL: Yavneh I. The Excavation of the «Temple Hill» Repository Pit and the Cult Stands. XII-298 pages, 29 colour and 147 black and white plates. 2010.
- Bd. 31 OTHMAR KEEL: Corpus der Stempelsiegel-Amulette aus Palästina/Israel. Von den Anfängen bis zur Perserzeit. Katalog Band III: Von Tell el-Far a Nord bis Tell el-Fir. VIII–460 Seiten, davon 214 mit Fotos und Zeichnungen. 2010.
- Bd. 32 KARIN ROHN: Beschriftete mesopotamische Siegel der Frühdynastischen und der Akkad-Zeit. 476 Seiten, davon 66 Bildtafeln. 2011.
- Bd. 33 OTHMAR KEEL: Corpus der Stempelsiegel-Amulette aus Palästina/Israel. Von den Anfängen bis zur Perserzeit. Katalog Band IV: Von Tel Gamma bis Chirbet Husche. Mit Beiträgen von Baruch Brandl, Daphna Ben-Tor und Leonardo Pajarola. XVI–720 Seiten, mit Fotos und Zeichnungen. 2013.
- Bd. 34 AMIR GOLANI: Jewelry from Iron Age II Levant. VIII-328 pages, including 35 plates with figures. 2013.

## Summary

An integral part of *Garments of the Gods* (OBO 218, 2006), this volume offers the transliteration, translation and selected copies of over 600 administrative documents on the textile industry in the Ebabbar temple at Neo-Babylonian Sippar. The documents are mostly divided in accordance with the former discussion presented in OBO 218. The aim of the new publication is to enlarge the data base for future studies and to create the possibility of checking and discussing the observations made in the first volume. Indices provide the names of garments and fabrics, and the paleography will allow the reader easy comparison when identifying new texts in the future.